







# **GAZETTEER**

**OF THE**

## **BOMBAY PRESIDENCY**

**VOLUME I. PART J.**

### **HISTORY OF GUJARÁT.**

---

***UNDER GOVERNMENT ORDERS.***

---

**BOMBAY**  
**PRINTED AT THE GOVERNMENT CENTRAL PRESS.**  
**1896.**







THE earliest record of an attempt to arrange for the preparation of Statistical Accounts of the different districts of the Bombay Presidency is in 1843. In 1843 Government called on the Revenue Commissioner to obtain from all the Collectors as part of their next Annual Report the fullest available information regarding their districts.<sup>1</sup> The information was specially to include their own and their Assistants' observations on the state of the cross and other roads not under the superintendence of a separate department, on the passes and ferries throughout the country, on the streets in the principal towns, and on the extension and improvement of internal communications. As from Collectors alone could any knowledge of the state of the district be obtained, the Collectors were desired to include in their Annual Reports observations on every point from which a knowledge of the actual condition of the country could be gathered with the exception of matters purely judicial which were to be supplied by the Judicial Branch of the Administration. Government remarked that, as Collectors and their Assistants during a large portion of the year moved about the district in constant and intimate communication with all classes they possessed advantages which no other public officers enjoyed of acquiring a full knowledge of the condition of the country, the causes of progress or retrogradation, the good measures which require to be fostered and extended, the evil measures which call for abandonment, the defects in existing institutions which require to be remedied, and the nature of the remedies to be applied. Collectors also, it was observed, have an opportunity of judging of the effect of British rule on the condition and character of the people, on their caste prejudices, and on their superstitious observances. They can trace any alteration for the better or worse in dwellings clothing and diet, and can observe the use of improved implements of husbandry or other crafts, the habits of locomotion, the state of education particularly among the higher classes whose decaying means and energy under our most levelling system compared with that of preceding governments will attract their attention. Finally they can learn how far existing village institutions are effectual to

<sup>1</sup> Secretary's Letter 4223 to the Revenue Commissioner dated 30th December 1843.  
Revenue Volume 1854 of 1843.

their end, and may be made available for self-government and in the management of local taxation for local purposes.

In obedience to these orders reports were received from the Collectors of Ahmedabad Broach Kaira Tháha and Khándesh. Some of the reports, especially that of Mr. J. D. Inverarity, contained much interesting information. These five northern reports were practically the only result of the Circular Letter of 1843.

The question of preparing District Statistical Manuals was not again raised till 1870. In October 1867 the Secretary of State desired the Bombay Government to take steps for the compilation of a Gazetteer of the Presidency on the model of the Gazetteer prepared during that year for the Central Provinces. The Bombay Government requested the two Revenue Commissioners and the Director of Public Instruction to submit a scheme for carrying into effect the orders of the Secretary of State. In reply the officers consulted remarked that the work to be done for the Bombay Presidency would be of a multifarious character; that the article on the commerce of Bombay would require special qualifications in the writer; that again special qualifications would be required for writing accounts of the sacred cities of Násik and Pálitána, of the caves of Ajarta and Ellora, of the histories of Sindh Gujarát and Ahmednagar, and of the Portuguese connection with Western India. The Committee observed that a third form of special knowledge would be required to write accounts of Pársis Khojás and other castes and tribes; that in short the undertaking would be one of much wider scope and greater difficulty than the preparation of the Gazetteer of the Central Provinces. Much thought would be required before the general plan could be laid down, and after the plan was fixed all sorts of questions as to arrangement and treatment of particular parts would be sure to arise. In the Committee's opinion local revenue officers could not as a rule find time to devote to work of this description without neglecting their ordinary duties; but they could correct and amplify such information as a special officer could compile from the published and unpublished records of Government.

In January 1868 the Bombay Government decided that the general supervision and direction of the work should be placed in the hands of a Committee consisting of the Revenue Commissioners, the Director of Public Instruction, and the Commissioner of Customs, and that an Editor should be appointed with a small copying establishment to act under the directions of the Committee. The Editor was to give his entire time to the work and was expected to

finish it in about a year. He was to collect and arrange in alphabetical order all recorded information regarding the towns and other places of interest in each Collectorate, and to send printed on half margin each draft when completed to the local officers for verification, additions, and alterations. When the drafts were returned and corrected by the Editor, they were to be laid before the Committee. To enable the Editor to meet such expenses as a fair remuneration for articles contributed by qualified persons, and also to pay for the printing of the work with small accompanying maps, an amount not exceeding Rs. 12,000 was sanctioned for the total expense of the Gazetteer including the payment of the Editor. At the outset it was decided to place a portion of the sum sanctioned not exceeding Rs. 2000, at the disposal of the Commissioner in Sindh to secure the preparation of articles referring to Sindh. The Committee were requested to meet at Poona in June 1868 and to report to Government on the best mode of preparing and editing the Gazetteer and supervising its publication. The Collectors and Political Officers were in the meanwhile requested to ascertain what records in their possession were likely to be useful for the preparation of a Gazetteer and what papers in the possession of others and likely to be useful for the purpose were obtainable within their charge. Collectors and Political Officers were requested to send their replies direct to the Director of Public Instruction who would collect them on behalf of the Committee.

In August 1868 the Bombay Gazetteer Committee, composed of Messrs. A. F. Bellasis Revenue Commissioner N. D. Chairman, Mr. W. H. Havelock Revenue Commissioner S. D. and Sir Alexander Grant, Director of Public Instruction, submitted a report recommending the following arrangements :

(1) That Mr. W. H. Crowe C. S, then Acting Professor in the Dakhan College, be appointed Editor of the Gazetteer with a monthly remuneration of Rs. 200 out of the Rs. 12,000 sanctioned for the expense of the Gazetteer and that he should at the same time be attached as an Assistant to the Collector of Poona,

(2) That Mr. Crowe be allowed an establishment not exceeding Rs. 50 a month chargeable to the grant of Rs. 12,000, and such contingent charges as may be passed by the Committee;

(3) That Professor Kero Luxman Chhatie be requested to assist Mr. Crowe on various questions both local and mathematical, and that on the completion of the work a suitable honorarium be granted to Professor Kero;

(4) That agreeably to the suggestions of Major Prescott and Colonel Francis, Mr. Light should be directed to compile for the different districts all information in the possession of the Survey Department in communication

with the Editor of the Gazetteer who was to work under the Committee's orders ;

- (5) That the above appointments be made at present for one year only, at the end of which from the Committee's progress report, it would be possible to state with approximate definiteness the further time required for the completion of the Gazetteer.

These proposals were sanctioned on the 11th September 1868. Towards the close of 1868 Mr. (now Sir) J. B. Peile took the place of Sir A. Grant on the Committee and Colonel Francis was added to the list of the members. Adhering as far as possible to the arrangement followed in the Gazetteer of the Central Provinces, which had met with the approval of the Secretary of State, Mr. Crowe drew out the following list of subjects which was forwarded to all Collectors Sub-Collectors and Survey Superintendents :

<p><b>I.—GENERAL DESCRIPTION</b></p> <ul style="list-style-type: none"> <li>(a) Latitude and Longitude.</li> <li>(b) Locality.</li> <li>(c) Foundation.</li> <li>(d) Aspect.</li> <li>(e) Water-supply.</li> <li>(f) Rivers.</li> <li>(g) Mountains.</li> <li>(h) Area.</li> <li>(i) Altitude.</li> </ul> <p><b>II.—CLIMATE, SEASONS.</b></p> <ul style="list-style-type: none"> <li>(a) Rainfall.</li> <li>(b) Health.</li> <li>(c) Prevailing Diseases.</li> </ul> <p><b>III.—GEOLOGY.</b></p> <ul style="list-style-type: none"> <li>(a) Soils.</li> <li>(b) Minerals.</li> <li>(c) Scientific Details.</li> </ul> <p><b>IV.—HISTORY.</b></p> <p><b>V.—ADMINISTRATION.</b></p> <ul style="list-style-type: none"> <li>(a) Judicial.</li> <li>(b) Revenue.</li> <li>(c) Miscellaneous.</li> </ul> <p><b>VI.—REVENUE.</b></p> <ul style="list-style-type: none"> <li>(a) Imperial.</li> <li>(b) Local.</li> </ul> <p><b>VII.—POPULATION.</b></p> <ul style="list-style-type: none"> <li>(a) Census.</li> <li>(b) Description of Inhabitants.</li> <li>(c) Castes.</li> </ul>	<p><b>VIII.—SUB-DIVISIONS.</b></p> <ul style="list-style-type: none"> <li>(a) Names of Talukas.</li> <li>(b) Names of Towns.</li> </ul> <p><b>IX.—PRODUCTION</b></p> <ul style="list-style-type: none"> <li>(a) Agriculture.</li> <li>(b) Forest.</li> <li>(c) Animals.</li> <li>(d) Minerals.</li> <li>(e) Manufactures.</li> </ul> <p><b>X.—TRADE AND COMMERCE.</b></p> <p><b>XI.—COMMUNICATIONS</b></p> <ul style="list-style-type: none"> <li>(a) Roads.</li> <li>(b) Railways.</li> <li>(c) Telegraphs.</li> <li>(d) Post.</li> </ul> <p><b>XII.—REVENUE SYSTEM AND LAND TENURES.</b></p> <p><b>XIII.—EDUCATION.</b></p> <ul style="list-style-type: none"> <li>Schools.</li> <li>Instruction.</li> </ul> <p><b>XIV.—LANGUAGE.</b></p> <p><b>XV.—ARCHITECTURAL REMAINS AND ANTIQUITIES.</b></p> <p><b>XVI.—PRINCIPAL TOWNS AND VILLAGES.</b></p>
---	---

In 1869 the draft articles prepared by Mr. Crowe were submitted to Mr. (now Sir) W. W. Hunter of the Bengal Civil Service, who expressed his satisfaction at the progress made. The Committee adopted certain suggestions made by Sir W. Hunter for the arrangement of the work and for obtaining fuller district figures from the Marine, Irrigation, Cotton, and Survey Offices. In March 1870 a further extension of one year was accorded. The Bombay Government directed that each Collector should choose one of his Assistants to correspond with the Editor and obtain for him all possible information from local records. All Heads of Offices were also desired to exert themselves zealously in aiding the prosecution of the work. In 1871 Mr. Crowe's draft article on the Dhárwár District was sent to Mr. Hunter for opinion who, in addition to detailed criticism on various points made the following general remarks :

"My own conception of the work is that, in return for a couple of days' reading, the Account should give a new Collector a comprehensive, and, at the same time, a distinct idea of the district which he has been sent to administer. Mere reading can never supersede practical experience in the district administration. But a succinct and well conceived district account is capable of antedating the acquisition of such personal experience by many months and of both facilitating and systematising a Collector's personal enquiries. The Compiler does not seem to have caught the points on which a Collector would naturally consult the Account. In order that the Editor should understand these points it is necessary that he should have had practical acquaintance with district administration and that he should himself have experienced the difficulties which beset an officer on his taking charge of a district or sub-division. The individual points will differ according to the character of the country. For example in deltaic districts the important question is the control of rivers; in dry districts it is the subject of water-supply. But in all cases a District Account besides dealing with the local specialties should furnish an historical narration of its revenue and expenditure since it passed under the British rule, of the sums which we have taken from it in taxes, and of the amount which we have returned to it in the protection of property and person and the other charges of civil government."

Sir William Hunter laid much stress on the necessity of stating the authority on the strength of which any statement is made and of the propriety of avoiding anything like libels on persons or classes. In 1871 Sir W. Hunter was appointed Director General of Statistics to the Government of India. In this capacity he was to be a central guiding authority whose duty it was to see that each of the Provincial Gazetteers contained the materials requisite for the comparative statistics of the Empire. As some of the Bombay District Accounts were incomplete and as it was thought advisable to embody in the District Accounts the results of the general Census of 1872, it was decided, in October 1871, that pending the completion of the census

the Gazetteer work should be suspended and that when the results of the census were compiled and classified a special officer should be appointed for a period of six months to revise and complete the drafts. In October 1871, pending the compilation of the census returns, Mr. Crowe was appointed Assistant Collector at Sholapur and the Gazetteer records were left in a room in the Poona Collector's Office. In September 1872 the whole of the Gazetteer records, including thirty-one articles on British Districts and Native States, were stolen by two youths who had been serving in the Collector's Office as peons. These youths finding the Gazetteer office room unoccupied stole the papers piece by piece for the sake of the trifling amount they fetched as waste paper. Search resulted in the recovery in an imperfect state of seven of the thirty-one drafts. The youths were convicted and sentenced to a year's imprisonment in the Poona Reformatory.

In 1873 Mr. Francis Chapman then Chief Secretary to Government took the preparation of the Gazetteer under his personal control. And in June 1873 Mr. James M. Campbell, C.S., was appointed Compiler. An important change introduced by Mr. Chapman was to separate from the preparation of the series of District Manuals certain general subjects and to arrange for the preparation of accounts of these general subjects by specially qualified contributors. The subjects so set apart and allotted were :

GENERAL CONTRIBUTORS, 1874.		
No.	Subject	Contributor
1	Ethnology . . .	Dr. J. Wilson.
2	Meteorology . .	Mr. C. Chambers, F.R.S.
3	Geology . . .	Mr. W. Blandford.
4	Botany . . .	Dr. W. G. G.
5	Archæology . . .	Dr. J. Burgess.
6	Manufactures and Industry	Mr. G. W. Terry.
7	Trade and Commerce . . .	Mr. J. Gordon.

These arrangements resulted in the preparation of the following papers each of which on receipt was printed in pamphlet form :

I. ETHNOLOGY ; II. METEOROLOGY ; III. GEOLOGY ; and IV. BOTANY.

Of these papers it has not been deemed advisable to reprint Dr. J. Wilson's Paper on Castes as it was incomplete owing to Dr. Wilson's death in 1875. Reprinting was also unnecessary in the case of Mr. Blandford's Geology and of the late Mr. Chambers' Meteorology, as the contents of these pamphlets have been embodied in works

specially devoted to the subject of those contributions. Dr. Burgess never prepared his article on the Archaeology of the Presidency, but the materials supplied by the late Pandit Bhagvānlal Indrajī prevented the evil effect which this failure would otherwise have caused. Dr. Bhagvānlal also ably supplied the deficiency caused by Dr. G. Bühler's failure to contribute an article on the Early History of Gujarāt. The notices of the manufactures in the more important industrial centres to some extent supply the blank caused by the absence of Mr. Terry's contribution. Nothing came of the late Mr. Gordon's Account of the Trade of the Presidency.

On the important subject of Botany besides Dr. W. Gray's original contribution, a valuable paper On Useful Trees and Plants was prepared by Dr. J. C. Lasbon, and a detailed account of Kāra field trees by the late Mr G. H. D. Wilson of the Bombay Civil Service. These three papers together form a separate Botany Volume No. XXV.

The general contributions on History contained in Vol. I. Parts I. and II. are among the most valuable portions of the Gazetteer. Besides the shorter papers by Mr. L. R. Ashburner, C.S.I., on the Gujarāt Murmies of 1857, by Mr J. A. Baines, C.S.I., on the Marāthās in Gujarāt, by Mr. W. W. Loe, I.C.S., on the Musalmān and Marāthā histories of Khāndesh and the Bombay Dakhān, and by the late Colonel E. W. West, I. S. C., on the modern history of the Southern Marāthā districts, there are the Reverend A. K. Nairne's History of the Konkan which is specially rich in the Portuguese period (A.D. 1500-1750), the late Colonel J. W. Watson's Musalmāns of Gujarāt with additions by Khān Sāheb Fazl Latifullah Faridi of Surat, and the important original histories of the Early Dakhān by Professor Rāmkrishna Gopāl Bhambarkar, C.I.E., Ph.D., and of the Southern Marāthā districts by Mr J. F. Fleet, I.C.S., C.I.E., Ph.D. With these the early history of Gujarāt from materials supplied by the late Pandit Bhagvānlal Indrajī, Ph.D., is perhaps not unworthy to rank. The work of completing Dr. Bhagvānlal's history was one of special difficulty. No satisfactory result would have been obtained had it not been for the valuable assistance received from Mr. A. M. T. Jackson, M.A., of the Indian Civil Service.

The importance and the interest of the great subject of Population have added several contributions to the Reverend Doctor J. Wilson's original pamphlet of twenty-three pages. Most of these contributions appear in different District Statistical Accounts especially Dr. John Pollen's, I.C.S., accounts in Khāndesh, Mr. Cumme's, I.C.S. in Bijāpur, Mr. K. Raghunāthji's in Thāna and Poona; Assistant Surgeon Shāntārām

Vináyak's in Sholápur, Mr. P. F. DeSouza's in Kánara; and the late Ráo Bahádur Trimalrao's in Dhárwár. Except the valuable articles contributed in the Statistical Account of Kachh by Major J. W. Wray, Mr. Vináyakrao Náráyanand Ráo Sáheb Dalpatráo Pránjivan Khakhar, in the Account of Káthiawár by the late Colonel L. C. Barton, and in the Account of Rewa Kántha by Ráo Bahádur Nandshankar Tuljáshankar the early date at which the Gujarát Statistical Accounts were published prevented the preparation of detailed articles on population. This omission has now been supplied in a separate volume No. IX. The chief contributions to this volume are Ráo Bahádur Bhimbháí Kirpáram's Hindus, Khán Sáheb Fazl Lutfullah Farídi's Musalmáns, and Messrs. Kharsetji N. Servai and Bamanji B. Patel's Pársis.

Besides to these general contributors the series of Statistical Accounts owes much of their fullness and practical usefulness to District Officers especially to the labours of the District Compilers who in most cases were either Collectors or Assistant Collectors. The most important contributors of this class were for Ahmeda'ba'd Mr. F. S. P. Lely, C. S.; for Kaira Mr. G. F. Sheppard, C. S.; for the Ranch Maha'ls Mr. H. A. Acworth, C. S.; for Tha'na Messrs. W. B. Mulock, C. S., E. J. Elden, C. S., W. W. Loch, C. S., and A. Cumine, C. S.; for Kola'ba Mr. E. H. Moscarli, C. S.; for Ratna'giri Mr. G. W. Vidal, C. S.; for Kha'ndesh Mr. W. Ramsay, C. S., Dr. John Pollen, C. S., and Mr. A. Crawley-Boevey, C. S.; for Na'sik Messrs. W. Ramsay, C. S., J. A. Baines, C. S., and H. R. Cooke, C. S.; for Ahmednagar Mr. T. S. Hamilton, C. S.; for Poona Messrs. J. G. Moore, C. S., John MacLeod Campbell, C. S., G. H. Johns, C. S., and A. Keyser, C. S.; for Sata'ra Mr. J. W. P. Muir-Mackenzie, C. S.; for Shola'pur Mr. C. E. G. Crawford, C. S.; for Belgaum Mr. G. McCorkell, C. S.; for Dha'rwa'r Messrs. F. L. Charles, C. S., and J. F. Muir, C. S.; for Bijapur Messrs. H. F. Silcock, C. S., A. Cumine, C. S., and M. H. Scott, C. S.; and for Ka'nara Mr. J. Monteath, C. S., and Colonel W. Peyton. Of the accounts of Native States, the interesting and complete Gazetteer of Baroda is the work of Mr. F. A. H. Elliott, C. S. The chief contributors to the other Statistical Accounts of Native States were for Kachh Colonel L. C. Barton; for Ka'thia'wa'r Colonel J. W. Watson and Colonel L. C. Barton; for Pa'lanpur Colonel J. W. Watson; for Mahi Ka'ntha Colonels E. W. West and P. H. LeGeyt; for Rewa Ka'ntha Colonel L. C. Barton and Ráo Bahádur Nandshankar Tuljáshankar; for Sa'vantva'di Colonel J. F. Lester; for Ja'nira Mr. G. Larcom; for Kolha'pur Colonels E. W. West and W. F. F. Waller and

Ráo Bahádur Yeshvánt M. Kelkar. The names of numerous other contributors both in and out of Government service who gave help in compiling information connected with their districts have been shewn in the body of each District Statistical Account. Of these the learned and most ungrudging assistance received from Dr. J. Gerson DaCunha of Bombay requires special recognition.

The third main source of preparation was the Compiler's head-quarters office. Through the interest which Mr. Francis Chapman took in the Gazetteer the Compiler was able to secure the services as Assistant of Ráo Bahádur Bhimbháu Karpáram who was Head Accountant in the Kára Treasury when the Statistical Account of Kára was under preparation in 1874. Mr. Bhimbháu's minute knowledge of administrative detail, his power of asking for information in the form least troublesome to district establishments, and of checking the information received, together with his talent for directing the work at head-quarters formed one of the most important elements in the success of the Gazetteer arrangements. Besides to the interest taken by Mr. Francis Chapman the Gazetteer owed much to the advice and to the support of Sir W. W. Hunter, who, in spite of the delay and expense which it involved, secured the full record of the survey and other details in which the Bombay revenue system is specially rich.

In addition to Ráo Bahádur Bhimbháu, the members of the Compiler's office whose work entitles them almost to a place among contributors are: Ráo Sahab Krishnarao Narsingh, who drafted many of the Land Revenue and Survey Histories, the late Mr. Ganesh Bhikáji Gupkar, B. A., who drafted many of the Political Histories; the late Mr. Vankarbháram Mannáthram Mohita, B. A., and Ráo Bahádur Itcháram Bhagyasdas, B. A., who drafted many articles on Description, Production, Agriculture, Capital, and Trade; Mr. K. Raghunáthji who prepared many of the fullest caste accounts; Mr. Ratnam Durgaram, B. A., who drafted many papers on places of interest; Mr. Messrs. Yeshvánt Nilkanth and Mahadev, G. Nádkarni who drafted many of the sections on Population, Agriculture, Capital, and Trade.

Other officers of Government who have had an important share in the satisfactory completion of the Gazetteer are: Mr. J. Kingsmill the former and Mr. Frémroz Rustamji the present Superintendent of the Government Central Press and Mr. T. E. Coleman the Head Examiner, whose unfailing watchfulness has detected many a mistake. Mr. Waite the late Superintendent of the Photozincographic Press and Mr. T. LeMesurier the present Superintendent have supplied a set of most handy, clear, and accurate maps.

A further means adopted for collecting information was the preparation of papers on the different social, economic, and religious subjects which had proved of interest in preparing the earliest District Statistical Accounts. Between 1874 and 1880 forty-nine question papers which are given as an Appendix to the General Index Volume were from time to time printed and circulated. The answers received to these papers added greatly to the fullness and to the local interest of all the later Statistical Accounts.

The Statistical Accounts of the eighteen British districts and eighty-two Native States of the Bombay Presidency, together with the Materials toward a Statistical Account of the Town and Island of Bombay extend over thirty-three Volumes and 17,800 pages. In addition to these Statistical Accounts 475 articles were prepared in 1877-78 for the Imperial Gazetteer.

JAMES MACNABB CAMPBELL.

*Bombay Customs House* 1  
*" do "* 1896.

# HISTORY OF GUJARÁT.



This Volume contains the Articles named below

- I.—EARLY HISTORY OF GUJARAT (B.C. 319 - A.D. 1301) — From materials prepared by the late Pandit Bhagvānlāl Indrajī, Ph.D. completed with the help of A. M. T. Jackson, Esquire, M.A., of the Indian Civil Service.
- II.—HISTORY OF GUJARAT. MUSALMAN PERIOD (A.D. 1297-1760) — Prepared by the late Colonel J. W. Watson Indian Staff Corps former Political Agent of Kathiāvada, with additions by Khan Sāhib Fazlullāh Lutfullāh Parodi of Surat.
- III.—HISTORY OF GUJARAT. MARATHA PERIOD. (A.D. 1760-1819).—By J. A. Barnes, Esquire, C.S.I. Late of Her Majesty's Bombay Civil Service.
- IV.—DISTURBANCES IN GUJARAT (A.D. 1857-1859) —By J. R. Ashburner, Esquire, C.S.I. Late of Her Majesty's Bombay Civil Service.

*Appendix*

- I.—The Death of Sultan Bahādur.
- II.—The Hill Fort of Māndu.
- III.—Bhinnmal or Shrinad.
- IV.—Java and Cambodia.
- V.—Arab References.
- VI.—Greek References.

JAMES M. CAMPBELL

29th May 1896.



# CONTENTS.

## EARLY HISTORY OF GUJARÁT.

	PAGE
<b>Boundaries and Name</b> . . . . .	1-5
<b>Ancient Divisions.</b>	
Anarta; Suráshtra; Lata . . . . .	6-7
<b>Legends:</b>	
Anarta the first Puranic king of Gujarát, and the Yádivas in Dwáraka . . . . .	8-12
<b>Mauryan and Greek Rule (B.C. 319-100):</b>	
The Mauryas (B.C. 319-197); The Greeks (B.C. 180-100) . . . . .	13-19
<b>The Kshatrapas (B.C. 70 - A.D. 398):</b>	
The Name; Northern Kshatrapas; Western Kshatrapas; Nahapána (A.D. 78-120); Ushavadata (A.D. 100-120); Nishapána's Era; Málava Era, Chushtana (A.D. 130); The Mevas or Medas; Jayadaman (A.D. 140-143) . . . . .	20-34
Rudradaman (A.D. 143-158), Sudarśana Lake; The Yaudheyas, Dámájada or Damájadaśrí (A.D. 158-168); Jivadaman (A.D. 178); Rudrasinha I. (A.D. 181-196); Rudrasena (A.D. 203-220), Prithvisena (A.D. 222); Saughadaman (A.D. 222-226); Dámāsena (A.D. 226-236); Damájadaśrí II (A.D. 236) . . . . .	35-45
Víradaman (A.D. 236-238), Yasadaman (A.D. 239); Vijayasena (A.D. 238-249); Dámájadaśrí (A.D. 250-255); Rudrasena II (A.D. 256-272); Vísvasinha (A.D. 272-278); Bhattridaman (A.D. 278-294); Vísvasena (A.D. 294-300), Rudrasinha (A.D. 308-311); Yasadaman (A.D. 320); Dámāsini (A.D. 320); Rudrasena (A.D. 348-376), Samhasena; Skanda; Vísvaradatta (A.D. 230-250), Kshatrapa Family Tree . . . . .	46-54
<b>The Traikutakas (A.D. 250-450):</b>	
Initial Date; Their Race . . . . .	55-59
<b>The Guptas (c. 90-149; A.D. 410-470):</b>	
Dynasty; The founder Gupta (A.D. 319-322 [?]); Ghatotkacha (A.D. 322-349 [?]); Chandragupta I. (A.D. 349-369 [?]); Samudragupta (A.D. 370-395); Chandragupta II. (A.D. 396-415); Kumáragupta (A.D. 416-453); Skandagupta (A.D. 454-470) . . . . .	60-70
Budhagupta (A.D. 485); Bhánugupta (A.D. 511); The Pushyamitras (A.D. 455); White Huns (A.D. 450-520); Mihirakula (A.D. 512); Yasodharman of Málwa (A.D. 533-34) . . . . .	71-77

**The Valabhis (A.D. 509 - 766) :**

Valah Town (1893); Valabhi in A.D. 630; Valabhi Copper-plates; Valabhi Administration (A.D. 500-700); Territorial Divisions; Land Assessment; Religion; Origin of the Valabhis; History ... ..	PAGE 78-86
--	---------------

First Valabhi Grant, (A.D. 526); Senāpati Bhatārka (A.D. 509-520?); the Matrakas (A.D. 470-509); Senāpati's Sons; Dhruvasena I (A.D. 526-535); Gūhasena (A.D. 539-569); Dhruvasena II (A.D. 569-589); Śīlāditya I. (A.D. 594-609); Kharagraha (A.D. 610-615), Dhruvasena III. (A.D. 615-620); Dhruvasena II (Bāladitya) (A.D. 620-640), Dhruvasena IV. (A.D. 640-649); Dhruvasena III. (A.D. 650-656); Kharagraha (A.D. 656-665); Śīlāditya II. (A.D. 666-675); Śīlāditya IV. (A.D. 691); Śīlāditya V. (A.D. 722); Śīlāditya VI. (A.D. 766); Śīlāditya VII. (A.D. 766); Valabhi Family Tree; The fall of Valabhi (A.D. 750-770); The importance of Valabhi ... ..	87-96
---	-------

Valabhi and the Gehlots; The Vālas of Kāthiāvāda; The Vālas and Kāthi; Descent from Kanaksen (A.D. 150); Mewād and the Persians; Valas ... ..	97-106
---	--------

**The Chalukyas (A.D. 634-740)**

Jayasimhavarman (A.D. 666-693); Śrīyātraya Śīlāditya (her apparent) (A.D. 669-691), Mangalarāja (A.D. 698-731), Pulakesi Janāśraya (A.D. 732), Buddhavarman (A.D. 713-), Nagavardhana, Chalukya Tree ... ..	107-112
---	---------

**The Gurjjaras (A.D. 580-808).**

Copperplates, Gurjara Tree, Dadda I. (c. 580-605 A.D.), Jayabhata I. Vānapaga (c. 605-620 A.D.), Dadda II. Prasāntaraga (c. 620-650 A.D.), Jayabhata II. (c. 650-675 A.D.), Dadda III. Bahusahaya (c. 675-700), Jayabhata III. (c. 704-731 A.D.) ... ..	113-118
---	---------

**The Ra'shtrakutas (A.D. 713-974).**

Origin, Name; Early Dynasty (A.D. 450-500); The main Dynasty (A.D. 630-972), Rāshtrakuta Family Tree (A.D. 630-972); Copperplates, Karka II. (A.D. 747), Krishna and Govinda II. (A.D. 765-795), Dhruva I. (A.D. 795), Govinda III. (A.D. 800-808), Indra (A.D. 808-842), Karka I. (A.D. 812-821); Dantivarman (Her Apparent); Govinda (A.D. 827-833), Dhruva I. (A.D. 835-867), Akālavarsha (A.D. 867); Dhruva II. (A.D. 867), Akālavarsha Krishna (A.D. 888); Main Line restored (A.D. 888-974); Krishna Akālavarsha (A.D. 888-914); Indra Nityavarsha (A.D. 914) ... ..	119-134
--	---------

**The Mihiras or Mers (A.D. 470-900) :**

History; The Chūlāsamās (A.D. 900-940); The Jethvās; The Mers; White Hūnas; Jhālās ... ..	135-147
---	---------

# THE KINGDOM OF ANAHILAVĀḌA (A.D. 720 - 1300).

## The Chāvada's (A.D. 720 - 956) :

PAGE

Pañchāsar (A.D. 788); Jaysēkhara (A.D. 696); Vanarāja (A.D. 720 - 780 ?); Founding of Anahilavāḍa (A.D. 716 - 765); Vanarāja's Installation; His Image; Vanarāja's Successors (A.D. 780 - 961); Yogarāja (A.D. 806 - 841); Kshemarāja (A.D. 841 - 880); Chāmuṇḍa (A.D. 880 - 908); Ghāghada (A.D. 908 - 937); Chāvada Genealogy .. ...	149-155
--	---------

## The Chaulukyas or Solankis (A.D. 961 - 1242) :

Authorities; The name Chaulukya; Mularāja (A.D. 961 - 996); Chāmuṇḍa (A.D. 997 - 1010); Durgabha (A.D. 1010 - 1022); Bhīma I. (A.D. 1022 - 1064); Mahmūd's Invasion (A.D. 1024); Somapātha (A.D. 1024) .. ...	156-169
Karna (A.D. 1064 - 1094); Siddharāja Jayasīgha (A.D. 1094 - 1143) .. ...	170-181
Kumārapāla (A.D. 1143 - 1174); Ajayapāla (1174 - 1177); Mularāja II. (A.D. 1177 - 1179); Bhīma II. (A.D. 1179 - 1242) ..	182-197

## The Vāghela's (A.D. 1219 - 1304) . . . . .

Arnorāja (A.D. 1170 - 1200); Jayasīgha (A.D. 1200 - 1233); Virāddeva (A.D. 1233 - 1238); Visaldeva (A.D. 1243 - 1261); Arjunadeva (A.D. 1262 - 1274); Sāraṅgadeva (A.D. 1275 - 1296); Karna (A.D. 1296 - 1304); Vāghela Genealogy .. ...	198-206
--	---------

# MUSALMAN PERIOD (A.D. 1297 - 1760).

## Introduction .

Territorial Limits; Sorath, Kāthiavāḍa; Under the Kings (A.D. 1403 - 1573); Under the Mughals (A.D. 1573 - 1760); Condition of Gajarat (A.D. 1297 - 1802) .. ...	207-228
--	---------

## Early Musalman Governors (A.D. 1297 - 1403) :

Alā-ud-din Khulji Emperor (A.D. 1295 - 1315); Ulugh Khān (A.D. 1297 - 1317); Ain-ul-Mulk Governor (A.D. 1318); Order established (A.D. 1318); Muhammad Tughlak Emperor (A.D. 1325 - 1351); 'Uj-ul-Mulk Governor (A.D. 1320); Suppression of insurrection (A.D. 1347); Surrender of Girnār and Kachh (A.D. 1350); Firuz Tughlak Emperor (A.D. 1351 - 1388); Zafar Khān Governor (A.D. 1371); Farbat-ul-Mulk Governor (A.D. 1376 - 1391); Muhammad Tughlak II. Emperor (A.D. 1391 - 1393); Zafar Khān Governor (A.D. 1391 - 1403) .. ...	229-233
--	---------

## Ahmedā'ba'd Kings (A.D. 1403 - 1573) :

Muhammad I. (A.D. 1403 - 1404); Muzaffar (A.D. 1407 - 1419); Ahmed I. (A.D. 1411 - 1441); Ahmedābād built (A.D. 1413); Defeat of the L'dar Chief (A.D. 1414); Spread of Islām (A.D. 1414); Expedition against Mālwa (A.D. 1417); Chāmpāner attacked (A.D. 1418); War with Mālwa (A.D. 1422); Defeat of	
--	--

the I'dar Chief (A.D. 1425); Recovery of Máhim (A.D. 1429) and	PAGE
Báglán (A.D. 1431); Muhammad II. (A.D. 1441-1452); Kutb-	
ud-din (A.D. 1451-1459); War with Málwa (A.D. 1451) Battle	
of Kapadvanj (A.D. 1454); War with Nágor (A.D. 1454-1459);	
War with Chitor (A.D. 1455-1459) ... ..	234-242
Mahmúd I. Begada (A.D. 1459-1513); Defeat of a conspiracy	
(A.D. 1459); Improvement of the soldiery (A.D. 1459-1461);	
Help given to the king of the Dakhan (A.D. 1461); Expedition	
against Junágadh (A.D. 1467); Capture of Girnár (A.D. 1472);	
Disturbances in Chámpáner (A.D. 1472); Conquest of Kachh;	
Jagat destroyed; Conspiracy (A.D. 1480); War against Chám-	
páner (A.D. 1482-1484); Capture of Pávágad (A.D. 1484); The	
Khándesh succession (A.D. 1508); Muzaffar II. (A.D. 1513-1526);	
Expedition against Kdar (A.D. 1514); Disturbances in Málwa	
(A.D. 1517); Capture of Mánér (A.D. 1518); War with Chitor	
(A.D. 1519); Submission of the Rána of Chitor (A.D. 1521);	
Death of Muzaffar II. (A.D. 1526) ... ..	243-252
Sikandar (A.D. 1526); Mahmúd II. (A.D. 1526); Bahádur	
(A.D. 1527-1536); Portuguese intrigues (A.D. 1526); Khándesh	
affairs (A.D. 1528); Turks at Diu (A.D. 1526-1530); Capture	
of Mánér (A.D. 1530); Quarrel with Humáyun (A.D. 1532);	
Fall of Chitor (A.D. 1535); Mughal conquest of Gujarát (A.D.	
1535); The Mughals driven out (A.D. 1536); The Portuguese at	
Diu (A.D. 1536); Death of Bahádur (A.D. 1536); Muhammad II.	
Asrín (A.D. 1536-1554); His escape from control; Choosing	
of evil favourites; Quarrels among the nobles; Disturbances	
(A.D. 1545); Death of Mahmúd (A.D. 1551); Ahmed II. (A.D.	
1554-1561); 'Itimád Khán Regent; Partition of the province;	
Dissensions; Sultánpur and Nandurbár handed to Khándesh	
(A.D. 1560); Defeat and death of Sayyid Mubárak; Death of	
Imád-ul-Mulk Rámi; Daman district ceded to the Portuguese	
(A.D. 1550); Assassination of Ahmed II. (A.D. 1560); Muzaffar	
III. (A.D. 1561-1572), a minor; 'Itimád Khán and the	
Fauládis; The Mírzáis (A.D. 1571); Defeat of 'Itimád Khán;	
Death of Changíz Khán; 'Itimád Khán and the Emperor	
Akbar (A.D. 1572) ... ..	252-264

### ● MUGHAL VICEROYS (A.D. 1573-1758).

#### Emperor Akbar (A.D. 1573-1605):

Capture of Broach and Surat and advance to Ahmedábád	
(A.D. 1573); Mirza Azíz first Viceroy (A.D. 1573-1575);	
Insurrection quelled by Akbar (A.D. 1573); Mirza Khán second	
Viceroy (A.D. 1575-1577); Survey by Rája Todar Mal; Shaháb-	
ud-din third Viceroy (A.D. 1577-1583); Expedition against	
Junágadh; 'Itimád Khán Gujaráti fourth Viceroy (A.D. 1583-	
1584); Ahmedábád captured by Muzaffar (A.D. 1583); Mirza	
Abdur Rahím Khán (Khán Khánán) fifth Viceroy (A.D. 1583-	
1587); Defeat of Muzaffar (A.D. 1584); Ismáil Kulí Khán sixth	
Viceroy (A.D. 1587); Mirza Azíz Kokaltásh seventh Viceroy	
(A.D. 1588-1592); Refuge sought by Muzaffar in Káthiaváda;	
Muzaffar attacked by the imperial army; Muzaffar's flight	
to Kachh and suicide (A.D. 1591-92); Sultán Murád Baksh	
eighth Viceroy (A.D. 1592-1600); Mirza Azíz Kokaltásh ninth	
Viceroy (A.D. 1601-1606) ... ..	265-273

**Jahā'ngir Emperor (A.D. 1605 - 1627):**

PAGE

Kalij Khān tenth Viceroy (A.D. 1606); Sayad Murtaza eleventh Viceroy (A.D. 1606-1609); Mirza Aziz Kokaltash twelfth Viceroy (A.D. 1609-1611); Sack of Surat by Malik Ambar (A.D. 1609); Abdullāh Khān Firūz Jang thirteenth Viceroy (A.D. 1611-1616); Mukarrab Khān fourteenth Viceroy (A.D. 1616); Elephant-hunting in the Panch Mahāls (A.D. 1616); Prince Shāh Jehān fifteenth Viceroy (A.D. 1618-1622); Rebellion of Shāh Jehān (A.D. 1622-23); Shāhi Bāgh, built at Ahmedābād; Sultān Dāwar Baksh sixteenth Viceroy (A.D. 1622-1624); Saif Khān seventeenth Viceroy (A.D. 1624-1627). 273-277

**Shāh Jehān Emperor (A.D. 1627 - 1658):**

Sher Khān Tūar eighteenth Viceroy (A.D. 1627-1632); Famine (A.D. 1631-1632); Islām Khān nineteenth Viceroy (A.D. 1632); Disorders (A.D. 1632); Būkar Khān twentieth Viceroy (A.D. 1632); Sipāhdār Khān twenty-first Viceroy (A.D. 1633); Saif Khān twenty-second Viceroy (A.D. 1633-1635); A'zam Khān twenty-third Viceroy (A.D. 1635-1642); The Kolis punished; The Kāthīs subdued; Revolt of the Jām of Navānagar (A.D. 1640); I'sa Tarkhān twenty-fourth Viceroy (A.D. 1642-1644); Prince Muhammad Aurangzib twenty-fifth Viceroy (A.D. 1644-1646); Shāistah Khān twenty-sixth Viceroy (A.D. 1646-1648); Prince Muhammad Dārā Shikoh twenty-seventh Viceroy (A.D. 1648-1652); Shāistah Khān twenty-eighth Viceroy (A.D. 1652-1654); Prince Murād Baksh twenty-ninth Viceroy (A.D. 1654-1657); Murād Baksh proclaimed emperor (A.D. 1657); Kāsam Khān thirtieth Viceroy (A.D. 1657-1659); Victory of Murād and Aurangzib; Murād confined by Aurangzib (A.D. 1658) ... 277-282

**Aurangzib Emperor (A.D. 1658 - 1707):**

Shāh Nawāz Khān Safāvi thirty-first Viceroy (A.D. 1659); Rebellion of Prince Dārā (A.D. 1659); Prince Dārā defeated (A.D. 1659); Jasavantsingh thirty-second Viceroy (A.D. 1659-1662); Jasavantsingh sent against Shivāji (A.D. 1662); Mahābat Khān thirty-third Viceroy (A.D. 1662-1666); Capture of Navānagar-Islāmānagar (A.D. 1664); Surat plundered by Shivāji (A.D. 1664); Copper coinage introduced (A.D. 1668); Khān Jehān thirty-fourth Viceroy (A.D. 1668-1671); Sidi Yākūt the Mughal Admiral (A.D. 1670); Mahārāja Jasavantsingh thirty-fifth Viceroy (A.D. 1671-1674); Muhammad Amīn Khān Umदा-ul-Mulk thirty-sixth Viceroy (A.D. 1674-1683); Increased power of the Bābi family; Revolt of Idar (A.D. 1679); Mukhtār Khān thirty-seventh Viceroy (A.D. 1683-1684); Famine (A.D. 1684); Shujāāt Khān (Kārtalab Khān) thirty-eighth Viceroy (A.D. 1684-1703); Mutiny quelled by Shujāāt Khān (A.D. 1689); Revolt of Matīās and Momnās (A.D. 1691); Disturbances in Kāthiāvāda (A.D. 1692) and Mārwar; Durgādās Rāthod reconciled to the Emperor (A.D. 1697); Scarcity (A.D. 1698); Prince Muhammad Azam thirty-ninth Viceroy (A.D. 1703-1705); Intrigue against and escape of Durgādās Rāthod; Surat (A.D. 1700-1703); Ibrāhīm Khān fortieth Viceroy (A.D. 1705); Marāthās enter Gujarāt; Battle

of Ratanpūr and defeat of the Musalmāns (A.D. 1705); Battle of the Bába Pīráh Ford and second defeat of the Musalmāns (A.D. 1705); Kolī disturbances; Prince Muhammad Bīdār Bakht forty-first Viceroy (A.D. 1705-1706); Durgādās Ráthod again in rebellion; Ibráhīm Khán forty-second Viceroy (A.D. 1706) ... 283-295

### Fifty Years of Disorder (A.D. 1707-1757):

The Maráthas advance to Ahmedábád and levy of tribute (A.D. 1707); Bahádur Sháh I. Emperor (A.D. 1707-1712); Gház-ul-dīn forty-third Viceroy (A.D. 1708-1710); Jahándár Sháh Emperor (A.D. 1712-13); Ásif-ud-daulah forty-fourth Viceroy (A.D. 1712-13); Farrukhsiyar Emperor (A.D. 1713-1719); Sháhámát Khán forty-fifth Viceroy (A.D. 1713); Dáúd Khán Panní forty-sixth Viceroy (A.D. 1714-15); Religious riots in Ahmedábád (A.D. 1714); Further riots in Ahmedábád (A.D. 1715); Mahárája Ajítsingh forty-seventh Viceroy (A.D. 1715-1716); Disagreement between the Viceroy and Haidar Kúli Khán (A.D. 1715); Khán Daurán Nasrat Jang Bahádur forty-eighth Viceroy (A.D. 1716-1719); Fámáo (A.D. 1719); Muhammad Sháh Emperor (A.D. 1721-1748); Mahárája Ajítsingh forty-ninth Viceroy (A.D. 1719-1721); Piláji Gáikwár at Songad (A.D. 1719); Decay of imperial power (A.D. 1720); Nizám-ul-Mulk Prime Minister of the Empire (A.D. 1721); Haidar Kúli Khán fiftieth Viceroy (A.D. 1721-1722); Disorder in Ahmedábád (A.D. 1721); His arrival in Gujarát (A.D. 1722); Signs of independence shown by him and his recall (A.D. 1722); Nizám-ul-Mulk fifty-first Viceroy (A.D. 1722); Hámid Khán Deputy Viceroy; Momin Khán Governor of Surat (A.D. 1722); Increase of Maráthas power (A.D. 1723)... 295-301

Sarbuland Khán fifty-second Viceroy (A.D. 1723-1730); Shujaát Khán appointed Deputy; Nizám-ul-Mulk and Sarbuland Khán; Sarbuland Khán's Deputy defeated (A.D. 1724); the Maráthas engaged as Allies; Battle of Arás; Hámid Khán defeated by Rustam Ali (A.D. 1723); Hámid Khán joined by Maráthas against Rustam Ali; Mubáriz-ul-Mulk sent against the Maráthas (A.D. 1725); Retreat of Hámid Khán and the Maráthas; Ahmedábád entered by Mubáriz-ul-Mulk (A.D. 1725); Defeat of the Maráthas at Sejitra and Kapadvanj (A.D. 1725); Maráthas expedition against Vadnagar (A.D. 1725); Tribute paid to the Maráthas (A.D. 1726); Alliance with the Peshwa (A.D. 1727); Baroda and Dabhoi obtained by Piláji Gáikwár (A.D. 1727); Capture of Chámpáner by the Maráthas (A.D. 1728); Grant of tribute to the Peshwa (A.D. 1729); Disturbance raised by Mulla Muhammad Ali at Surat (A.D. 1729); Petlád given in farm (A.D. 1729); Athva fort (A.D. 1730); The Viceroy in Káthiáváda and Kachh (1730); Riots at Ahmedábád; Mahárája Abheysingh fifty-third Viceroy (A.D. 1730-1733); The new Viceroy resisted by Mubáriz-ul-Mulk; Battle of Adúlaj; The Mahárája defeated by Mubáriz-ul-Mulk (A.D. 1730); Retreat of Mubáriz-ul-Mulk; Government of Abheysingh; Momin Khán, ruler of Cambay (A.D. 1730); The Peshwa and Viceroy against Piláji Gáikwár (A.D. 1731); The withdrawal of the Peshwa; His opponents defeated;

Abdúlláh Beg appointed Nizám's Deputy at Broach; The death of Piláji Gáikwár procured by the Viceroy (A.D. 1732); Baroda taken; Famino (A.D. 1732); Affairs at Surat (A.D. 1732); Toghbeq Khán Governor of Surat ... 305 - 313

Ratansingh Bhandári Deputy Viceroy (A.D. 1733-1737); Return of the Maráthás; Contest for the government of Gogha; Disturbance at Viramgám (A.D. 1734); Baroda recovered by the Maráthás (A.D. 1734); Change of governor at Viramgám; Failure of Jawán Mard Khán in an attempt on I'dar; Rivalry of Ratansingh Bhandári and Sohráb Khán (A.D. 1735); Battle of Dholi; Defeat and death of Sohráb Khán (A.D. 1735); Rivalry between Ratansingh Bhandári and Momín Khán (A.D. 1735); Marátha affairs; Dámáji Gáikwár and Kántáji (A.D. 1735); Battle of Anand-Mogri; Defeat of Kántáji; The Maráthás helping Bhávsingh to expel the Viramgám Kasbátis; The country plundered by the Gáikwár and Peshwa; Momín Khán fifty-fourth Viceroy (A.D. 1737); Siege of Ahmedábád; Maharája Abheysingh fifty-fifth Viceroy (A.D. 1737); The siege of Ahmedábád continued by Momín Khán; Defence of the city by Ratansingh Bhandári; Ahmedábád captured by Momín Khán (A.D. 1738); Momín Khán fifty-sixth Viceroy (A.D. 1738-1743); Prosperity of Ahmedábád (A.D. 1738); Tribute collected by the Viceroy (A.D. 1738); Sher Khán Bábi Deputy Governor of Sorath (A.D. 1738); Tribute collected by the Deputy Viceroy (A.D. 1739); Capture of Bassein by the Maráthás (A.D. 1739); Tribute expedition (A.D. 1740); The Viceroy at Cambay (A.D. 1741); Viramgám surrendered and Pátdi received by Bhávsingh; Siege of Broach by the Maráthás (A.D. 1741); Battle of Dholka; Defeat of the Maráthás (A.D. 1741); Contests between the Musalmáns and Maráthás; Disturbance at Ahmedábád (A.D. 1742); Collection of tribute in Káthiáváda by the Viceroy; Death of Momín Khán (A.D. 1743) ... 314 - 326

Fidá-ud-dín acting as Viceroy (A.D. 1743); The Maráthás defeated by Muftakhr Khán; Dámáji Gáikwár's return to Gujarát; Abdul Azíz Khán of Junnar Viceroy (by a forged order); Mutiny of the troops; Petlúd captured by the Maráthás; Muftakhir Khán fifty-seventh Viceroy (A.D. 1743-1744); Jawán Mard Khán appointed Deputy, The Maráthás in Ahmedábád; Battle of Kim Kathodra; Defeat and death of Abdul Azíz Khán (A.D. 1744); Fakhr-ud-daulah fifty-eighth Viceroy (A.D. 1744-1748); Jawán Mard Khán Bábi Deputy Viceroy; Khanderao Gáikwár called to Sátára; Defeat and capture of the Viceroy by Jawán Mard Khán Bábi; Rangoji disgraced by Khanderao Gáikwár; Rangoji and Jawán Mard Khán opposed by Punáji Vithal and Fakhr-ud-daulah; Siege of Kapadvanj by Fakhr-ud-daulah (A.D. 1746); The siege raised at the approach of Holkar; Momín Khán II. governor of Cambay (A.D. 1748); Increased strength of Fakhr-ud-daulah's party; Dissensions among the Maráthás; Surat affairs (A.D. 1748); Escape of Mulla Fakhr-ud-dín to Bombay; Cession of Surat revenue to the Gáikwár (A.D. 1747); Famine (A.D. 1747); Marátha dissensions; Fall of Borsad ... 326 - 332

<b>Mahārāja Vakhatsingh</b> fifty-ninth Viceroy (A.D. 1748);	PAGE
<b>Ahmed Shāh Emperor</b> (A.D. 1748-1754); Spread of disorder;	
<b>Surāt affairs</b> (A.D. 1750); <b>Sayad Achchan</b> unpopular; <b>Safdar Muhammad</b> brought back by the Dutch; Retreat of Sayad Achchan; <b>Jawān Mard Khān</b> and the Peshwa (A.D. 1750); The Peshwa and <b>Gāikwār</b> (A.D. 1751); <b>Broach</b> independent (A.D. 1752); <b>Pāndurang Pandit</b> repulsed at Ahmedābād (A.D. 1752); <b>Marāthā</b> invasion; Return of <b>Jawān Mard Khān</b> ; Gallant defence of Ahmedābād; Surrender of <b>Jawān Mard Khān</b> ; Ahmedābād taken by the <b>Marāthās</b> (A.D. 1753); Collection of tribute; <b>Mughal</b> coinage discontinued; Failure of an attempt on <b>Cambay</b> (A.D. 1753); The <b>Kolis</b> ; <b>Cambay</b> attacked by the <b>Marāthās</b> (A.D. 1754); <b>Alamgīr II.</b> (A.D. 1754-1759); Contest with <b>Momīn Khān</b> renewed (A.D. 1754); <b>Gogha</b> taken by <b>Momīn Khān</b> (A.D. 1755); Ahmedābād recovered by <b>Momīn Khān</b> (17th October 1756); <b>Jawān Mard Khān</b> allying himself with the <b>Marāthās</b> ; Ahmedābād invested by the <b>Marāthās</b> (A.D. 1756); <b>Momīn Khān</b> helped by <b>Rāo of Idar</b> (A.D. 1757); Successful sally under <b>Shamshurām</b> . Negotiations for peace; <b>Marāthā</b> arrangements in Ahmedābād; New coins; <b>Momīn Khān</b> at <b>Cambay</b> ; Expedition from <b>Kachh</b> against <b>Sindh</b> (A.D. 1758); Tribute levied by the <b>Marāthās</b> ; <b>Surat</b> affairs (A.D. 1758); The command of <b>Surat</b> taken by the English (A.D. 1759); <b>Momīn Khān's</b> visit to <b>Poona</b> (A.D. 1759); <b>Sadāshiv Rāmchandra Peshwa's</b> Viceroy (A.D. 1760); The <b>Marāthās</b> in <b>Kāthiavād</b> (A.D. 1759); <b>Apā Ganesh</b> Viceroy (A.D. 1761); Battle of <b>Pānipat</b> (A.D. 1761)	... 332-345

#### Appendix I.—Death of Sultān **Bahādar** (A.D. 1526-1536). 347-351

<b>Appendix II.</b> —The Hill Fort of <b>Māndu</b> ; Description; History; The <b>Mālwa Sultāns</b> (A.D. 1400-1570); The <b>Mughals</b> (A.D. 1570-1720); The <b>Marāthās</b> (A.D. 1720-1820); Notices (1820-1895)	... 352-384
--	-------------

### MARĀTHĀ PERIOD (A.D. 1760-1819).

History; **Śivāji's** first inroad (A.D. 1664); **Śivāji's** second attack (A.D. 1670); **Sāler** taken (A.D. 1672); The **Narbada** crossed (A.D. 1675); Raids by **Dābhāde** (A.D. 1699-1713); **Dābhāde** (A.D. 1716); **Dābhāde Senāpati**; the Peshwa's negotiations (A.D. 1717); **Dāmāji Gāikwār** (A.D. 1720); **Marāthā** tribute (A.D. 1723); **Kārtāji Kadam**; **Marāthā** dissensions (A.D. 1725); The Peshwa (A.D. 1726); Cession of tribute (A.D. 1728); Coalition against the Peshwa (A.D. 1730); Defeat of the allies (A.D. 1731); Assassination of **Pilāji Gāikwār** (A.D. 1732); **Baroda** secured by the **Gāikwār** (A.D. 1734); The **Marāthā** Deputy Governor (A.D. 1736); Ahmedābād riots (A.D. 1738-1741); Siege of **Broach** (A.D. 1741); **Rangoji** prisoner at **Borsad** (A.D. 1742); Quarrels regarding the Viceroyalty between **Dāmāji** and **Rāghoji Bhonsle** (A.D. 1743-44); **Rangoji**

confined in Borsad (A.D. 1745); the Gaikwár in Surat (A.D. 1747) ... PAGE 385-395

Haribá attacked by Rangoji; Death of Umábai (A.D. 1748); Dámáji deputy in Gujarát; Dámáji against Peshwa; Dámáji Gaikwár arrested (A.D. 1751); The Peshwa and Surat; Release of Dámáji (A.D. 1752); Capture of Ahmedábád (A.D. 1753); Raghunáthráv at Cambay; The Peshwa's deputy at Ahmedábád; Ahmedábád captured by the Nawáb of Cambay; Dámáji and Khanderáv Gaikwár at Ahmedábád; Surrender of the Nawáb; Sayájíráv in Ahmedábád; Peshwa's agent Sadáshiv at Surat; The Maráthas demand of tribute from the Nawáb of Cambay; The Nawáb at Poona; Lunávada plundered by Khanderáv; Expedition against Bálásinor; The estates of Jawán Mard Khán retaken by Dámáji; The Peshwa and the English (A.D. 1761); One of the Jádhav family Senápati; Ghorpade family again Senápati; Intrigues of Rághobá (A.D. 1768); Death of Dámáji Gaikwár (A.D. 1768); Disputed succession; Rághobá Peshwa (A.D. 1774); Rághobá in Gujarát (A.D. 1775); Rághobá defeated; His arrival at Surat; Treaty of Surat (A.D. 1775); Colonel Keating in Gujarát; Rághobá accompanied by Colonel Keating; Rághobá in Cambay (A.D. 1775); Govindráv Gaikwár's army; Advance of the combined forces; Defeat of Fatesingh (A.D. 1775); Retreat of the ministerial general; Colonel Keating at Dabhoi (A.D. 1775); Rághobá and the Gaikwárs; Withdrawal of the British contingent; Negotiations at Poona; Rághobá at Surat (A.D. 1776); Negotiations at Poona (A.D. 1777); Fresh alliance with Rághobá (A.D. 1778) ... 396-407

The convention of Bhadráon (A.D. 1779); Negotiation with the Gaikwár; Escape of Rághobá from Sindia (A.D. 1779); League against the English (A.D. 1780); Treaty with Fatesingh Gaikwár; Ahmedábád taken by General Goddard (A.D. 1780); Operations against Sindia and Holkar; Treaty of Sálbái (A.D. 1782); Death of Fatesingh (A.D. 1789); Govindráv detained at Poona (A.D. 1793); Office of Regent at Baroda taken by Govindráv; Aba Shelukar Deputy Governor of Gujarát (A.D. 1796); Disputes between Aba and Govindráv Gaikwár; Gujarát farmed to the Gaikwár (A.D. 1799); Anandráv Gaikwár (A.D. 1800); British aid to Govindráv's party; The British and the Gaikwár (A.D. 1800); The Gaikwár's minister Rávji; Treaty of Bassein (21st December 1802); Arabs disbanded; Malbárráv in revolt (A.D. 1803); Contingent strengthened (A.D. 1803); Death of Rávji (A.D. 1803); War with Sindia; The revenue collecting force; Renewal of (Gujarát) farm (A.D. 1804); The British and the Gaikwár (A.D. 1805); Káthiávada tribute; State of Káthiávada (A.D. 1807); The revenue raid system ... 407-418

The Maráthás in Sorath; Securities; Bháts and Chárans (A.D. 1807); British intervention; Financial and political settlements (A.D. 1807); Peshwa's share in Káthiávada; Later arrangements; The Mahi Kántha; Supplementary treaty (A.D. 1808); Okhámandal (A.D. 1809); Disturbances in Káthiávada (A.D. 1811); The Gaikwár's payment of the pecuniary loan to the British Government (A.D. 1812); Discussions with

Poona government about the old claims on the Gáikwár's estate (A.D. 1813-14); Peshwa intrigue in Baroda (A.D. 1814); Okhámandal ceded to the Gáikwár; British aid at Junágadh; Treaty of Poona (A.D. 1817); Treaty with the Gáikwár (A.D. 1817-18); Close of Marátha supremacy (A.D. 1819); General Review	... ..	418-432
--	--------	---------

### GUJARÁT DISTURBANCES (A.D. 1857-1859).

The Red Salt Scare (A.D. 1857); The passing of the Pariah dog; Gold hoarding; Seizure of native press; Maulvi Saráj-ud-din; Apparent weakness of British rule; Administrative defects; The Courts disliked; The Inám Commission; The army disloyal; Báiza Báí of Gwálior; Pársi riot in Broach (June 1857); Mutiny at Mhow (July 1857); Mutiny at Ahmedábád (July 1857); Mr. Ashburner's force; General Roberts; Rising at Amjera and in the Panch Maháls (July 1857); Mutinies at Abu and Erinpur (A.D. 1857); Disturbance at Ahmedábád (14th September 1857); Rádhanpur disloyal; Arab outbreak at Sunth; Disturbance in Lunāváda; Conspiracy at Dísá; Conspiracy at Baroda; Want of combination; Marátha conspiracy; Gathering at Partábpur and at Lodra; Partial disarming; Náikda revolt (October 1858); Tátiá Topi (A.D. 1858); Tátiá Topi's defeat at Chhota Udepur (December 1858); Náikda disturbance (A.D. 1858); Wágher outbreak (A.D. 1859); Expedition against Bet (A.D. 1859); Bet Fort taken; Dwárka fort taken; Rising in Nagar Párkár	... ..	433-448
--	--------	---------

### APPENDICES.

<b>Bhinmál or Shrimál</b> —Description, People, Objects of Interest, History, Inscriptions	... ..	449-488
<b>Javá and Cambodia</b>	... ..	489-504
<b>Arab References</b>	... ..	505-531
<b>Greek References</b>	... ..	532-547
<b>Index</b>	... ..	549-594





## ERRATA.

Page 3 note 5 :

*For* about thirty miles north-east of Ábu

*Read* about fifty miles west of Ábu.

Page 140 note 5 and page 145 top line of notes :

*For* Aldjayhání *read* Aljanharí. .



# EARLY HISTORY OF GUJARÁT.

## CHAPTER I.

### BOUNDARIES AND NAME.

THE portion of the Bombay Presidency known as Gujarát fills the north-east corner of the coast of Western India.

Chapter I.  
BOUNDARIES.

On the west is the Arabian Sea; on the north-west is the Gulf of Cutch. To the north lie the Little Ran and the Meyád désert; to the north-east Abu and other outliers of the Arávali range. The east is guarded and limited by rough forest-land rugged in the north with side spurs of the Vindhya, more open towards the central natural highway from Baroda to Ratlám, and southwards again rising and roughening into the northern offshoots from the main range of the Sátpradá. The southern limit is uncertain. History somewhat doubtfully places it at the Tápti. Language carries Gujarát about a hundred miles further to Balsár and Párdi where wild forest-covered hills from the north end of the Sahyádrí range stretch west almost to the sea.

The province includes two parts, Mainland Gujarát or Gurjjara-ráshtra and Peninsular Gujarát the Sauráshtra of ancient, the Káthiá-váda of modern history. To a total area of about 72,000 square miles Mainland Gujarát with a length from north to south of about 280 miles and a breadth from east to west varying from fifty to 150 miles contributes 45,000 square miles; and Peninsular Gujarát with a greatest length from north to south of 155 miles and from east to west of 200 miles contributes about 27,000 square miles. To a population of about 9,250,000 Mainland Gujarát contributes 6,900,000 and the Peninsula about 2,350,000.

The richness of Mainland Gujarát the gift of the Sábarmati Mahi Nerbada and Tápti and the goodliness of much of Sauráshtra the Goodly Land have from before the beginning of history continued to draw strangers to Gujarát both as conquerors and as refugees.

By sea probably came some of the half-mythic Yádavas (B.C. 1500 - 500); contingents of Yavanas (B.C. 300 - A.D. 100) including Greeks Baktrians Parthians and Skythians; the pursued Pársis and the pursuing Arabs (A.D. 600 - 800); hordes of Sanganian pirates (A.D. 900 - 1200); Pársi and Naváyut Musalmán refugees from Khulagu Khán's devastation of Persia (A.D. 1250 - 1300); Portuguese and rival Turks (A.D. 1500 - 1600); Arab and Persian Gulf pirates (A.D. 1600 - 1700); African Arab Persian and Makran soldiers of fortune (A.D. 1500 - 1800); Armenian Dutch and French traders (A.D. 1600 - 1750); and the British (A.D. 1750 - 1812). By land from the north

## EARLY GUJARÁT.

**Chapter I.** have come the Skythians and Huns (B.C. 200 - A.D. 500), the Gurjjaras (A.D. 400 - 600), the early Jádejás and Káthis (A.D. 750 - 900), wave on wave of Afghan Turk Moghul and other northern Musalmáns. (A.D. 1000 - 1500), and the later Jádejás and Káthis (A.D. 1300 - 1500) : From the north-east the prehistoric Aryans till almost modern times (A.D. 1100 - 1200) continued to send settlements of Northern Bráhmans ; and since the thirteenth century have come Turk Afghan and Moghul Musalmáns. From the east have come the Mauryans (B.C. 300), the half-Skythian Kshatrapas (B.C. 100 - A.D. 300), the Guptas (A.D. 380), the Gurjjars (A.D. 400 - 600), the Moghals (A.D. 1530), and the Maráthás (A.D. 1750) : And from the south the Sátakurnis (A.D. 100), the Chulukyas and Rásatrakutas (A.D. 650 - 950), occasional Musalmán raiders (A.D. 1100 - 1600), the Portuguese (A.D. 1500), the Maráthás (A.D. 1660 - 1760), and the British (A.D. 1780 - 1820).

**Gujars.** The name Gujarát is from the Prákrit Gujjara-ratta, the Sanskrit of which is Gurjjara-rishtra that is the country of the Gujjaras or Gurjjaras. In Sanskrit books and inscriptions the name of the province is written Gurjjara-mandala and Gurjjara-desa the land of the Gurjjaras or Gurjjaras. The Gurjjaras are a foreign tribe who passing into India from the north-west gradually spread as far south as Khándesh and Bombay Gujarát. The present Gujars of the Panjab and North-West Provinces preserve more of their foreign traits than the Gujar settlers further to the south and east. Though better-looking, the Panjab Gujars in language dress and calling so closely resemble their associates the Játs or Jats as to suggest that the two tribes entered India about the same time. Their present distribution shows that the Gujars spread further east and south than the Játs. The earliest Gujar settlements seem to have been in the Panjab and North-West Provinces from the Indus to Mathurá where they still differ greatly in dress and language from most other inhabitants. From Mathurá the Gujars seem to have passed to East Rajputána and from there by way of Kotah and Mandasor to Málwa, where, though their original character is considerably altered, the Gujars of Málwa still remember that their ancestors came from the Doab between the Ganges and the Jamna. In Málwa they spread as far east as Bhilsa and Saharanpur. From Málwa they passed south to Khándesh and west probably by the Ratlam-Bohad route to the province of Gujarát.

Like the modern Ahirs of Káthiáváda the Gujars seem to have been a tribe of cattle-rearers husbandmen and soldiers who accompanied some conqueror and subsequently were pushed or spread forwards as occasion arose or necessity compelled. In the absence of better authority the order and locality of their settlements suggest that their introduction into India took place during the rule of the Skythian or Kushán emperor Kanerkes or Kanishka (A.D. 78 - 106) in whose time they seem to have settled as far east as Mathurá to which the territory of Kanishka is known to have extended. Subsequently along with the Guptas, who rose to power about two hundred years later (A.D. 300), the Gujars settled in East Rajputána, Málwa, and Gujarát, provinces all of which were apparently

subjugated by the Guptas. It seems probable that in regard for their share in the Gupta conquests the leading Gujars were allotted fiefs and territories which in the declining power of their Gupta overlords they afterwards (A.D. 450 - 550) turned into independent kingdoms.

The earliest definite reference to a kingdom of North Indian Gujars is about A.D. 890 when the Kashmir king Sankaravarmā sent an expedition against the Gurjjara king Alakhāna and defeated him. As the price of peace Alakhāna offered the country called Takkades'a. This Takkades'a appears to be the same as the Tschkia of Hiuen Tsiang (A.D. 630-640) who puts it between the Biyās on the east and the Indus on the west thus including nearly the whole Punjab. The tract surrendered by Alakhāna was probably the small territory to the east of the Chināb as the main possessions of Alakhāna must have lain further west between the Chināb and the Jehlum, where lie the town of Gujurāt and the country still called Gujur-des'a the land of the Gujars.

\* As early as the sixth and seventh centuries records prove the existence of two independent Gurjjara kingdoms in Bombay Gujarat one in the north the other in the south of the province. The Northern kingdom is mentioned by Hiuen Tsing in the seventh century under the name Kiu-che-lo. He writes: 'Going north from the country of Valabhi 1800 li (300 miles) we come to the kingdom of Kiu-che-lo. This country is about 5000 li in circuit, the capital, which is called Pi-lo-mo-lo, is 30 li or so round. The produce of the soil and the manners of the people resemble those of Saurashtra. The king is of the Kshatriya caste. He is just twenty years old.' Hiuen Tsaung's Kiu-che-lo is apparently Gurjjara, the capital of which Pi-lo-mo-lo is probably Bhulmal or Bhinnmal, better known as Srimal. Though Hiuen Tsaung calls the king a Kshatriya he was probably a Gujar who like the later Southern Gujars claimed to be of the Kshatriya race.

## Chapter I.

### THE NAME.

Northern  
Gujjara  
Kingdom.  
*Huen Tsiang's*  
*Kiu-che-lo,*  
*A.D. 620.*

<sup>1</sup> *Rāja Tarāngini* (Calc. Edition), V, 150, 155, Cunningham's *Archaeological Survey*, II, 8. An earlier but vaguer reference occurs about the end of the sixth century in *Bhāṣa's Sūtrshākhya*, p. 27<sup>1</sup> quoted in *Ep. Ind.* I, 67ff, where *Prabhākara-vardhana* of *Thīnesar* the father of the great *Sūtra* *Huṣha* is said to have waged war with several kings of whom the *Gujarats* are one.

<sup>2</sup> Beal's *Buddhist Records of the Western World*, I, 165 note 1.

<sup>3</sup> Cunningham's *Archaeological Survey*, II, 71.

<sup>1</sup> Beal's *Buddhist Records* II. 270.

" This identification was first made by the late Col. J. W. Watson, I.S.C., Ind. Ant. VI. 31. Bhūmad or Bhūmal also called Sivad, is an old town about thirty miles north east of Alor, north latitude 25° 4' east longitude 71° 14'. General Cunningham (Ancient Geography of India, 313) and P'ofe or Beal (Buddhist Records, II. 270) identify Pi-lo-mo-lo with Balmor or Badameta (north latitude 71° 10' east longitude 26° 0') in the Jodhpur State of West Rajputana. This identification is unsatisfactory. Balmor is a small town on the slope of a hill in an arid tract with no vestige of antiquity. Huen Tsang notes that the produce of the soil and the manners of the people of Pi-lo-mo-lo resemble those of Surāshtra. This description is unsuited to so arid a tract as surrounds Balmor; it would apply well to the fertile neighbourhood of Bhūmal or Bhūmal. Since it is closely associated with Juvr that is Gurjjara the Al Bāilāman of the Arabs (A.D. 750, Elliot's History, I. 442) may be Bhūmal. A Jain writer (Ind. Ant. XIX. 233) mentions Bhūmal as the seat of king Bhūmasena and as connected with the origin of the Gadhia coinage. The date Bhūmal in a M.S. of A.D. 906 (Ditto, page 35) suggests it was then a seat of learning under the Gurjjaras. The prince of S'rimāl is mentioned (Rās Mālā, I. 58)

## Chapter I.

THE NAME.  
Southern  
Gurjjara  
Kingdom,  
A.D. 589 - 735.

The Southern Gurjjara kingdom in Gujarát, whose capital was at Nándipuri, perhaps the modern Nándod the capital of the Rájpipla State, flourished from A.D. 589 to A.D. 735.<sup>1</sup> The earlier inscriptions describe the Southern Gurjjaras as of the Gurjjara Vans'a. Later they ceased to call themselves Gurjjaras and traced their genealogy to the Puránic king Karna.

From the fourth to the eighth century the extensive tract of Central Gujarát between the North and South Gurjjara kingdoms was ruled by the Valabhis. The following reasons seem to show that the Valabhi dynasty were originally Gujars. Though it is usual for inscriptions to give this information none of the many Valabhi copper-plates makes any reference to the Valabhi lineage. Nor does any inscription state to what family Senápati Bhatárka the founder of the dynasty belonged. Hinen Tsiang describes the Valabhi king as a Kshatriya and as marrying with the kings of Málwa and Kanauj. The Valabhi king described by Hinen Tsiang is a late member of the dynasty who ruled when the kingdom had been greatly extended and when the old obscure tribal descent may have been forgotten and a Kshatriya lineage invented instead. Intermarriage with Málwa and Kanauj can be easily explained. Rajputs have never been slow to connect themselves by marriage with powerful rulers.

The establishment of these three Gujar kingdoms implies that the Gurjjara tribe from Northern and Central India settled in large numbers in Gujarát. Several Gujar castes survive in Gujarát. Among them are Gujar Vániás or traders, Gujar Sútárs or carpenters, Gujar Sonis or goldsmiths, Gujar Kumblárs or potters, and Gujar Saláts or masons. All of these are Gujars who taking to different callings have formed separate castes. The main Gujar underlayer are the Lewás and Kadwás the two leading divisions of the important class of Gujarát Kunbis. The word Kunbi is from the Sanskrit Kuṭumbin, that is one possessing a family or a house. From ancient times the title Kuṭumbin has been prefixed to the names of cultivators.<sup>2</sup> This practice still obtains in parts of the North-West Provinces where the peasant proprietors are addressed as Gṛihasthus or householders. As cattle-breeding not cultivation was the original as it still is the characteristic calling of many North Indian Gujars, those of the tribe who settled to cultivation came to be specially known as Kuṭumbin or householders. Similarly Deccan surnames show that many tribes of wandering cattle-owners settled as householders and are now known as Kunbis.<sup>3</sup> During the last

an accompanying Mula Rája Solankhi (A.D. 942 - 997) in an expedition against Sorath. Al Biruni (A.D. 1030, Sachau's Edn., I. 153, 267) refers to Bhillamála between Multán and Anhilaváda. As late as A.D. 1611 Nicholas Uffet, an English traveller from Agra to Ahmadábad (Kerr's Voyages, VIII. 301) notices "Boelmahl as having an ancient wall 24 kos (36 miles) round with many fine tanks going to ruin." The important sub-divisions of upper class Gujarát Hindus who take their name from it show S'rinál to have been a great centre of population.

<sup>1</sup> Indian Antiquary, XIII. 70-81. Buhler (Ind. Ant. VII. 62) identifies Nandipuri with a suburb of Broach.

<sup>2</sup> Bombay Gazetteer, Násik, page 604. Bombay Arch. Survey Sep. Number X. 38.

<sup>3</sup> Among Deccan Kunbi surnames are Jádhav, Chuhán, Nikumbha, Parmár, Selár, Solké. Cf. Bombay Gazetteer, XXIV. 65 note 2, 414.

twenty years the settlement as Kunbis in Khándesh of tribes of wandering Wanjára herdsmen and grain-carriers is an example of the change through which the Gujarát Kanbis and the Deccan Kunbis passed in early historic times.

Besides resembling them in appearance and in their skill both as husbandmen and as cattle-breeders the division of Gujarát Kanbis into Lewa and Kadwa seems to correspond with the division of Málwa Gujars into Dáha and Karad, with the Lewa origin of the East Khándesh Gujars, and with the Lawi tribe of Panjáb Gujars. The fact that the head-quarters of the Lewa Kanbis of Gujarát is in the central section of the province known as the Chayotar and formerly under Valabhi supports the view that the founder of Valabhi power was the chief leader of the Gujar tribe. That nearly a fourth of the whole Hindu population of Gujarát are Lewa and Kadwa Kanbis and that during the sixth seventh and eighth centuries three Gujar chiefs divided among them the sway of the entire province explain how the province of Gujarát came to take its name from the tribe of Gujars.<sup>1</sup>

## Chapter I.

## THE NAME.

Gujars.

<sup>1</sup> Though the identification of the Valabhis as Gurjjaras may not be certain, in inscriptions noted below both the Chivadis and the Solankis are called Gurjjara kings. The Gurjjara origin of either or of both these dynasties may be questioned. The name Gurjjara kings may imply no more than that they ruled the Gurjjara country. At the same time it was under the Chavadas that Gujarát got its name. Though to Al Biruni (A.D. 1020) Gujarát still meant part of Rájpútana, between A.D. 750 and 950 the name Gurjjaras' land passed as far south as the territory connected with Anhilvada and Vadnagara that is probably as far as the Mahi. As a Rástriakuta copperplate of A.D. 898 (S. 810) (Ind. Ant. XIII. 69) brings the Konkan as far north as Varán on the Tapti the extension of the name Gujarát to Lata south of the Mahi seems to have taken place under Muslim rule. This southern application is still somewhat incomplete. Even now the people of Smt both Hindus and Muslims when they visit Pattan (Anhilvada) and Ahm alahad speak of going to Gujarát, and the Ahmadabad section of the Nagai Brahmins still call their Surat caste-brethren by the name of Kunkanis that is of the Konk.

## CHAPTER II. ANCIENT DIVISIONS.

### Chapter II.

#### ANCIENT

#### A'narṭta.

FROM ancient times the present province of Gujarāt consisted of three divisions Anarṭta, Surāshṭra, and Lāṭa. Anarṭta seems to have been Northern Gujarāt, as its capital was Anandapura or Anandnagara or Chief City, which is also called Anarttapura.<sup>1</sup> Both these names were in use even in the times of the Valabhi kings (A.D. 500-770).<sup>2</sup> According to the popular story, in each of the four cycles or *yugas* Anandapura or Vadanagara had a different name, Chamatkārapura in the first or Satya-yuga, Anarttapura in the second or Tretā-yuga, Anandapura in the third or Dvāpara-yuga; and Vriddha-nagara or Vadanagar in the fourth or Kālī-yuga. The first name is fabulous. The city does not seem to have ever been known by so strange a title. Of the two Anarttapura and Anandapura the former is the older name, while the latter may be its proper name or perhaps an adaptation of the older name to give the meaning City of Joy. The fourth Vriddha-nagara meaning the old city is a Sanskritized form of the still current Vadanagar, the Old or Great City. In the Gīrnār inscription of Kshatrapa Rudradāman (A.D. 150) the mention of Anarṭta and Surāshṭra as separate provinces subject to the Pahlava viceroy of Junāgaḍh agrees with the view that Anarṭta was part of Gujarāt close to Kāthiāvāḍ. In some Purānas Anarṭta appears as the name of the whole province including Surāshṭra, with its capital at the well known shrine of Dwārikā. In other passages Dwārikā and Prabhās are both mentioned as in Surāshṭra which would seem to show that Surāshṭra was then part of Anarṭta as Kāthiāvāḍ is now part of Gujarāt.

#### Surāshṭra.

Surāshṭra the land of the Sus, afterwards Sanskritized into Saurāshṭra the Goodly Land, preserves its name in Sorath the southern part of Kāthiāvāḍ. The name appears as Surāshṭra in the Mahābhārata and Pāṇini's *Ganapāṭha*, in Rudradāman's (A.D. 150) and Skandagupta's (A.D. 456) Gīrnār inscriptions, and in several Valabhi copper-plates. Its Prākṛit form appears as Suratha in the Nāsik inscription of Gotamiputra (A.D. 150) and in later Prākṛit as Suraththa in the *Tirthakalpa* of Jinaprabhāsuri of the thirteenth or fourteenth century.<sup>3</sup> Its earliest foreign mention is perhaps Strābo's (B.C. 50 - A.D. 20) *Suraostus* and Pliny's (A.D. 70) *Orutura*.<sup>4</sup> Ptolemy

<sup>1</sup> See *Nagarakhanda* (Junagadh Edition), 13, 32, 35, 185, 289, 332, 542.

<sup>2</sup> The Alma grants (Indian Antiquary, VII. 73, 77) dated Valabhi 330 and 337 (A.D. 649-656) are both to the same donee who in the A.D. 649 grant is described as originally of Anarttapura and in the A.D. 656 grant as originally of Anandapura.

<sup>3</sup> *Gīrnāra Kalpa*, *Atthi Suraththa vasa Ujjinto ulma pavva rammo*. In the Suraththa district is a lovely mountain named Ujjinto (Gīrnār).

<sup>4</sup> Hamilton and Falconer's *Strabo*, II. 252-253; Pliny's *Natural History*, VI. 20.

the great Egyptian geographer (A.D. 150) and the Greek author of the *Periplus* (A.D. 210) both call it *Surastrene*.<sup>1</sup> The Chinese pilgrim Hsiao Tsiang (A.D. 600-610) mentions *Valabhi* then large and famous and *Surishtra* as separate kingdoms.<sup>2</sup>

## Chapter II.

ANCIENT  
DIVISIONS.

Lāṭa.

Lāṭa is South Gujarāt from the Mahi to the Tāpti. The name Lāṭa does not appear to be Sanskrit. It has not been found in the *Mahābhārata* or other old Sanskrit works, or in the cave or other inscriptions before the third century A.D., probably because the *Parāṇas* include in *Aparānta* the whole western seaboard south of the *Narbada* as far as *Goa*. Still the name Lāṭa is old. Ptolemy (A.D. 150) uses the form *Larike*<sup>3</sup>, apparently from the Sanskrit *Lāṭaka*. *Vātsyāyana* in his *Kāma-Sūtra* of the third century A.D. calls it Lāṭa, describes it as situated to the west of *Mālwa*; and gives an account of several of the customs of its people.<sup>4</sup> In Sanskrit writings and inscriptions later than the third century the name is frequently found. In the sixth century the great astronomer *Varāhamihira* mentions the country of Lāṭa, and the name also appears as Lāṭa in an *Ajanta* and in a *Mandasor* inscription of the fifth century.<sup>5</sup> It is common in the later inscriptions (A.D. 700-1200) of the *Chālukya* *Gurjara* and *Rāshtrakūṭa* kings<sup>6</sup> as well as in the writings of Arab travellers and historians between the eighth and twelfth centuries.<sup>7</sup>

The name Lāṭa appears to be derived from some local tribe, perhaps the *Lattas*, who, as *r* and *l* are commonly used for each other, may possibly be the well known *Rāshtrakūṭas* since their great king *Amoghavarsha* (A.D. 851-874) calls the name of the dynasty *Ratta*. *Lattalura* the original city of the *Rattas* of *Samudatti* and *Belgaum* may have been in Lāṭa and may have given its name to the country and to the dynasty.<sup>8</sup> In this connection it is interesting to note that the country between *Breach* and *Dhār* in *Mālwa* in which are the towns of *Bāgh* and *Tānda* is still called *Rāṭha*.

<sup>1</sup> Bernius' Ptolemy, VII. 1. McCrindle's *Periplus*, 113. The *Periplus* details regarding *Indo-Skythia*, *Smastrene*, and *Ujjain* are in agreement with the late date (A.D. 247) which *Remond* (*Indian Antiquary* of Dec. 1879 pp. 330-338) and *Barnell* (*S. Ind. Pal.* 47 note 3) assign to its author.

<sup>2</sup> Hsiao Tsiang's *Valabhi* kingdom was probably the same as the modern *Gohil-vāṭa*, which *Jnaprabhasa*. This *stranajaya-kalpa* calls the *Vallika-Vāṭa*.

<sup>3</sup> *Strabo* Ptolemy, VII. 1.

<sup>4</sup> *Vātsyāyana Sūtra*, Chap. II.

<sup>5</sup> *Arch. Sur. of Western India*, IV. 127. The *Mandasor* inscription (A.D. 437-38) mentions silk weavers from *Latvishaya*. Fleet's *Corpus Ins. Ind.* III. 80. The writer (*Ibid.*, 81) describes Lāṭa as green-hilled, pleasing with choice flower-burdened trees, with temples *exhaus* and assembly halls of the gods.

<sup>6</sup> *Ind. Ant.* XIII. 157, 158, 163, 180, 188, 196, 199, 204.

<sup>7</sup> Elliot's *History*, I. 378.

<sup>8</sup> Compare Lassen in *Ind. Ant.* XIV. 325.

## CHAPTER III.

## LEGENDS.

Chapter III.  
LEGENDS.  
Anartta the First  
Purāṇic King of  
Gujarat.

THE oldest Purāṇic legend regarding Gujarat appears to be that of the holy king Anartta son of Śaryāti and grandson of Manu. Anartta had a son named Revata, who from his capital at Kuśāsthali or Dwārikā governed the country called Anartta. Revata had a hundred sons of whom the eldest was named Raivata or Kakudmi. Raivata had a daughter named Revati who was married to Baladeva of Kuśāsthali or Dwārikā, the elder brother of Kṛṣṇa. Regarding Revati's marriage with Baladeva, the Purāṇic legends tell that Raivata went with his daughter to Brahmā in Brahma-loka to take his advice to whom he should give the girl in marriage. When Raivata arrived Brahmā was listening to music. As soon as the music was over Raivata asked Brahmā to find the girl a proper bridegroom. Brahmā told Raivata that during the time he had been waiting his kingdom had passed away, and that he had better marry his daughter to Baladeva, born of Vishnu, who was now ruler of Dwārikā.<sup>1</sup> This story suggests that Raivata son of Anartta lost his kingdom and fled perhaps by sea. That after some time during which the Yādavas established themselves in the country, Raivata, called a son of Revata but probably a descendant as his proper name is Kakudmi, returned to his old territory and gave his daughter in marriage to one of the reigning Yādava dynasty, the Yādavas taking the girl as representing the dynasty that had preceded them. The story about Brahmā and the passing of ages seems invented to explain the long period that elapsed between the flight and the return.

The Yādavas  
in Dwārikā.

The next Purāṇic legends relate to the establishment of the Yādava kingdom at Dwārikā. The founder and namegiver of the Yādava dynasty was Yadu of whose family the Purāṇas give very detailed information. The family seems to have split into several branches each taking its name from some prominent member, the chief of them being Vṛṣṇi, Kukkura, Bhoja, Śātvata, Audhaka, Madhu, Śurasena, and Daśārha. Śātvata was thirty-seventh from Yadu and in his branch were born Devaki and Vasudeva, the parents of the great Yādava hero and god Kṛṣṇa. It was in Kṛṣṇa's time that the Yādavas had to leave their capital Mathurā and come to Dwārikā. This was the result of a joint invasion of Mathurā on one side by a

<sup>1</sup> The Vishnu Purāṇa (Anū. iv. Chap. i. Verse 19 to Chap. ii. Verse 2) gives the longest account of the legend. The Bhāgavata Purāṇa (Skanda ix. Chap. iii. Verse 16-36) gives almost the same account. The Matsya Purāṇa (Chap. xii. Verse 22-24) dismisses the story in two verses. See also Harivamśa, X.

legendary Deccan hero Kálavyana and on the other by Jarásandha the powerful king of Magadha or Behar, who, to avenge the death of his brother-in-law<sup>1</sup> Kansa killed by Krishna in fulfilment of a prophecy, is said to have invaded the Yádava territory eighteen times.

According to the story Kálavyana followed the fugitive Krishna and his companions as far as Suráshtra where in a mountain cave he was burnt by fire from the eye of the sleeping sage Muchakunda whom he had roused believing him to be his enemy Krishna. According to the Harivansa the fugitive Yádavas quitting Mathurá went to the Sindhu country and there established the city of Dwáriká on a convenient site on the sea shore making it their residence.<sup>2</sup> Local tradition says that the Yádavas conquered this part of the country by defeating the demons who held it.

The leading Yádava chief in Dwáriká was Ugrasena, and Ugrasena's three chief supporters were the families of Yádu, Bhoja, and Andhaka. As the entire peninsula of Káthiáwáda was subject to them the Yádavas used often to make pleasure excursions and pilgrimages to Prabhás and Gírnár. Krishna and Baladeva though not yet rulers held high positions and took part in almost all important matters. They were in specially close alliance with their paternal aunt's sons the Pándava brothers, kings of Hastinápura or Delhi. Of the two sets of cousins Krishna and Arjuna were on terms of the closest intimacy. Of one of Arjuna's visits to Káthiáwáda the Mahábháratagives the following details: 'Arjuna after having visited other holy places arrived in Aparánta (the western seaboard) whence he went to Prabhás. Hearing of his arrival Krishna marched to Prabhás and gave Arjuna a hearty welcome. From Prabhás they came together to the Raivataka hill which Krishna had decorated and where he entertained his guest with music and dancing. From Gírnár they went to Dwáriká driving in a golden car. The city was adorned in honour of Arjuna; the streets were thronged with multitudes; and the members of the Vrishni, Bhoja, and Andhaka families met to honour Krishna's guest.'<sup>3</sup>

Some time after, against his elder brother Baladeva's desire, Krishna helped Arjuna to carry off Krishna's sister Subhadrá, with whom Arjuna had fallen in love at a fair in Gírnár of which the Mahábháratagives the following description: 'A gathering of the Yádavas chiefly the Vrishnis and Andhakas took place near Raivataka. The hill and the country round were rich with fine rows of fruit trees and large mansions. There was much dancing singing and music. The princes of the Vrishni family were in handsome carriages glistening with gold. Hundreds and thousands of the people of Junágadh with their families attended on foot and in vehicles of various kinds. Baladeva with his wife Revati moved about attended by many Gandharvās. Ugrasena was there with his thousand queens and musicians. Sámha and Pradyumna attended

<sup>1</sup> Compare Mahábh. II. 13,594ff. Jarásandha's sisters Asti and Prápti were married to Kansa.

<sup>2</sup> Hari-vansa, XXXV. - OXII.    <sup>3</sup> Mahábháratá Ádiparva, chapa, 218-221.

Chapter III.  
LEGENDS.  
The Yādavas.

in holiday attire and looked like gods. Many Yādavas and others were also present with their wives and musicians.'

Some time after this, gathering Subhadrá came to Gīrnār to worship and Arjuna carried her off. Eventually Vasudeva and Baladeva consented and the runaways were married with due ceremony. The large fair still held in Māgh (February-March) in the west Gīrnār valley near the modern temple of Bhavanāth is perhaps a relic of this great Yādava fair.

The Yādava occupation of Dwáriká was not free from trouble. When Krishna was at Hastinápura on the occasion of the Rájasúya sacrifice performed by Yudhishthira, Sálva king of Mrittikávati in the country of Saubha led an army against Dwáriká. He slew many of the Dwáriká garrison, plundered the city and withdrew unmolested. On his return Krishna learning of Sálva's invasion led an army against Sálva. The chiefs met near the sea shore and in a pitched battle Sálva was defeated and killed.<sup>1</sup> Family feuds brought Yádava supremacy in Dwáriká to a disastrous end. The final family struggle is said to have happened in the thirty-sixth year after the war of the Mahábhárata, somewhere on the south coast of Káthiáwáda near Prabhás or Somnāth Pátan the great place of Bráhmanical pilgrimage. On the occasion of an eclipse, in obedience to a proclamation issued by Krishna, the Yādavas and their families went from Dwáriká to Prabhás in state well furnished with dainties, animal food, and strong drink. One day on the sea shore the leading Yádava chiefs heated with wine began to dispute. They passed from words to blows. Krishna armed with an iron rod<sup>2</sup> struck every one he met, not even sparing his own sons. Many of the chiefs were killed. Baladeva fled to die in the forests and Krishna was slain by a hunter who mistook him for a deer. When he saw trouble was brewing Krishna had sent for Arjuna. Arjuna arrived to find Dwáriká desolate. Soon after Arjuna's arrival Vasudeva died and Arjuna performed the funeral ceremonies of Vasudeva Baladeva and Krishna whose bodies he succeeded in recovering. When the funeral rites were completed Arjuna started for Indraprastha in Upper India with the few that were left of the Yádava families,

<sup>1</sup> Mahábhárata Vanaparva, Chap. xiv. - xxii. Skanda x. Mrittikávati the capital of Sálva cannot be identified. The name of the country sounds like S'vabhra in Rudradáman's Gīrnār inscription, which is apparently part of Charotar or South Ahmadabad. A trace of the old word perhaps remains in the river Sábhrmati the modern Sábarmati. The fact that Sálva passed from Mrittikávati along the sea shore would seem to show that part of the seaboard south of the Mahi was included in Sálva's territory. Dr. Buhler (Ind. Ant. VII 263) described Pandit Bhagvanlál's reading of S'vabhra as a bold conjecture. A further examination of the original convinced the Pandit that S'vabhra was the right reading.

<sup>2</sup> The following is the legend of Krishna's iron flail. Certain Yádava youths hoping to raise a laugh at the expense of Viśvámitra and other sages who had come to Dwáriká presented to their Sámbar Krishna's son dressed as a woman big with child. The lads asked the sages to foretell to what the woman would give birth. The sages replied: 'The woman will give birth to an iron rod which will destroy the Yádava race.' Obedient to the sage's prophecy Sámbar produced an iron rod. To avoid the ill effects of the prophecy king Ugrasena had the rod ground to powder and cast the powder into the sea. The powder grew into the grass called *eraka* *Typha elephantina*. It was this grass which Krishna plucked in his rage and which in his hands turned into an iron flail. This *eraka* grass grows freely near the mouth of the Hiranya river of Prabhás.

chiefly women. On the way in his passage through the Panchanada<sup>1</sup> or Panjab a body of Abhīras attacked Arjuna with sticks and took several of Krishna's wives and the widows of the Andhaka Yādava chiefs. After Arjuna left it the deserted Dwārikā was swallowed by the sea.<sup>2</sup>

Chapter III.  
LEGENDS.  
The Yādavas.

<sup>1</sup> This suggests that as in early times the Great Ran was hard to cross the way from Kathiāvāda to Indraprastha or Delhi was by Kachch and Sindh and from Sindh by Multān and the Lower Panjab. According to the Bhāgavata Purāna Krishna took the same route when he first came from Indraprastha to Dwārikā. On the other hand these details may support the view that the head quarters of the historic Krishna were in the Panjab.

<sup>2</sup> So far as is known neither Gujarāt nor Kathiāvāda contains any record older than the Gīrnār rock inscription of about B.C. 240: The great Kshatrapa Rudra Dāman's (A. N. 139) inscription on the same rock has a reference to the Maurya Rāja Chandragupta about B.C. 300. No local sign of Krishna or of his Yādavas remains.

In the Journal of the Royal Asiatic Society, XX, XXI, and XXII, Mr. Hewitt has recently attempted to trace the history of Western India back to B.C. 3000 perhaps to as early as B.C. 6000. The evidence which makes so far-reaching a past probable is the discovery of Indian indigo and muslin in Egyptian tombs of about B.C. 1700 (J. R. A. S. XX, 206), and the proof that a trade in teak and in Sindh or Indian muslins existed between Western India and the Euphrates mouth as far back as B.C. 3000 or even B.C. 4000 (J. R. A. S. XV, 335, 337 and XXI, 204). According to Mr. Hewitt the evidence of the Hindu calendar carries the historical past of India to still remoter ages. The moon mansions and certain other details of the Hindu calendar seem to point to the Euphrates valley as the home of Hindu lunar astronomy. As in the Euphrates valley inscriptions of the Semitic kingargon of Sippara prove that in B.C. 3750 moon-worship was already antiquated (J. R. A. S. XXI, 325), and as the precession of the equinoxes points to about B.C. 4700 as the date of the introduction of the sun zodiac (Sayce's Hibbert Lectures, 398) the system of lunar mansions and months, if it came from the Euphrates valley, must have reached India before B.C. 4700. The trade records of the black-headed perhaps Dravidian-speaking Sumris of the Euphrates mouth prove so close relations with the peninsula of Sinai and Egypt as to make a similar connection with Western India probable as far back as B.C. 6000. (Compare Sayce's Hibbert Lectures, 33 J. R. A. S. XXI, 325.) Of the races of whose presence in Gujarāt and the neighbourhood Mr. Hewitt finds traces the earliest is the same black-headed moon-worshipping Sumri (Ditto). Next from Susiana in south-east Persia, the possessors of a lunar-solar calendar and therefore not later than B.C. 4700 (J. R. A. S. XXI, 325, 327, 330), the trading Sus or Saus, in Hindu books known as Suvarnas, entered India by way of Baluchistan and settled at Pātala in South Sindh. (J. R. A. S. XXI, 209.) With or soon after the Sus came from the north the cattle-herding sun-worshipping Sakas (J. R. A. S. XXII, 332). The Sus and Sakas passed south and together settled in Surashtra and West Gujarāt. At a date which partly from evidence connected with the early Vedic hymns (J. R. A. S. XXII, 466) partly from the early Babylonian use of the Sanskrit Sindhū for India (J. R. A. S. XXI, 309), Mr. Hewitt holds cannot be later than B.C. 3940 northern Aryas entered Gujarāt and mixing with the Sus and Sakas as merchant traders and soldiers carried the use of Sanskrit southward (J. R. A. S. XX, 343). Of other races who held sway in Gujarāt the earliest, perhaps about B.C. 2000 since their power was shattered by Parasurama long before Mahābhārata times (J. R. A. S. XXI, 209-265), were the snake-worshipping perhaps Accadian (Ditto, 265) Huhayas now represented by the Gond and the Hahayas' vassals the Vaidarbhas (Ditto, 209) a connection which is supported by trustworthy Central Indian Uraon or Gond tradition that they once held Gujarāt (Elliott's Races, N. V. P., I. 154). Next to the Hahayas and like them earlier than the Mahābhārata (say B.C. 1500-2000) Mr. Hewitt would place the widespread un-Aryan Bhārata or Bhārgava (J. R. A. S. XXI, 279-282, 286) the conquerors of the Hahayas (Ditto, 288). In early Mahābhārata times (say between B.C. 1000 and 800, Ditto 197 and 200) the Bhārata were overcome by the very mixed race of the Bhojas and of Krishna's followers the Vrishnis (Ditto, 270). Perhaps about the same time the chariot-driving Gandharvas of Cutch (Ditto, 273) joined the Sus and Sakas, together passed east to Kosala beyond Benares, and were there established in strength at the time of Gautama Buddha (B.C. 530) (Ditto). To the later Mahābhārata times, perhaps about B.C. 400 (Ditto, 197-271), Mr. Hewitt would assign the entrance into Gujarāt of the Abhīras or Ahirs whom he identifies with the northern or

## Chapter III.

LEGENDS.  
The Yádivas.

Skythian Abars. Mr. Hewitt finds the following places in Gujarát associated with those early races. Pátála in South Sindh he (J. R. A. S. XXI. 209) considers the head-quarters of the Sus and Sakas. Another Su capital Prágjyotisha which is generally allotted to Bengal he would (XXI, 206) identify with Broach. With the Vandalabhas the vassals of the Haihayas he associates Surparika, that is Sopara near Bassem, which he identifies (Ditto, 206) with the modern Surat on the Tapti. He connects (Ditto, 266) the Baroda river Visvámitra and Vaidurga the hill Pávágad with the same tribe. He finds a trace of the Bhárats in Baroda and in Bharati an old name of the river Mahi (Ditto, 286) and of the same race under their name Bhárgav in Broach (Ditto, 289). The traditional connection of the Bhojas with Dwárka is well established. Finally Kárpásika a Mahábhárata name for the shore of the Gulf of Cambay (Ditto, 209) may be connected with Kárván on the Narbada, about twenty miles above Broach one of the holiest Shav places in India. Though objection may be taken to certain of Mr. Hewitt's identifications of Gujarát places, and also to the extreme antiquity he would assign to the trade between India and the west and to the introduction of the system of lunar mansions, his comparison of sacred Hindu books with the calendar and ritual of early Babylonia is of much interest.

## CHAPTER IV.

## MAURYAN AND GREEK RULE

(B.C. 319-100.)

AFTER the destruction of the Yādavas a long blank occurs in the traditional history of Gujarāt. It is probable that from its seaboard position, for trade and other purposes, many foreigners settled in Kāthiāvāda and South Gujarāt; and that it is because of the foreign element that the Hindu Dharmaśāstras consider Gujarāt a Mlechchha country and forbid visits to it except on pilgrimage.<sup>1</sup> The fact also that Aśoka (B.C. 230) the great Mauryan king and propagator of Buddhism chose, among the Buddhist Theras sent to various parts of his kingdom, a Yavana Thera named Dhamma-rakkhita as evangelist for the western seaboard,<sup>2</sup> possibly indicates a preponderating foreign element in these parts. It is further possible that these foreign settlers may have been rulers. In spite of these possibilities we have no traditions between the fall of the Yādavas and the rise of the Mauryas in B.C. 319.

## Chapter IV.

THE MAURYAS,  
B.C. 319-100.

Gujarāt history dates from the rule of the Mauryan dynasty, the only early Indian dynasty the record of whose rule has been preserved in the writings of the Brāhmins, the Buddhists, and the Jains. This fulness of reference to the Mauryas admits of easy explanation. The Mauryas were a very powerful dynasty whose territory extended over the greater part of India. Again under Mauryan rule Buddhism was so actively propagated that the rulers made it their state religion, waging bloody wars, even revolutionizing many parts of the empire to secure its spread. Further the Mauryas were beneficent rulers and had also honourable alliances with foreign, especially with Greek and Egyptian, kings. These causes combined to make the Mauryans a most powerful and well remembered dynasty.

Inscriptions give reason to believe that the supremacy of Chandragupta, the founder of the Mauryan dynasty (B.C. 319), extended over Gujarāt. According to Rudradāman's inscription (A.D. 150) on the great edict rock at Gīrnār in Kāthiāvāda, a lake called Sudarśana<sup>3</sup> near the edict rock was originally made by Pushyagupta of the Vaiśya caste, who is described as a brother-in-law of the Mauryan king Chandragupta.<sup>4</sup> The language of this inscription leaves no doubt that Chandragupta's sway extended over

<sup>1</sup> Mahābhārata Anuśāsanaparvan 2158-9 mentions Līṭas among Kshatriya tribes who have become outcastes from seeing no Brāhmins. Again, Chap. VII. 72. ib. couples (J. Bl. As. Soc. VI. (1) 387) thievish Bāhika; and robber Surāshtras. Compare Vishnu Purāna, II. 37, where the Yavanas are placed to the west of Bhāratavarsha and also J. R. A. S. (N. S.) IV. 468; and Brockhaus' Prabodha Chandrodaya, 87. The *śloka* referred to in the text runs: He who goes to Anga, Vanga, Kahnga, Saurāshtra, or Magadha unless it be for a pilgrimage deserves to go through a fresh purification.

<sup>2</sup> Turnour's Mahāwanso, 71.

<sup>3</sup> Bombay Branch Royal Asiatic Society Journal, 1891, page 47.

<sup>4</sup> It is interesting to note that Chandragupta married a Vaiśya lady. Similarly while at Sānchi on his way to Ujjain Aśoka married Devī, the daughter of a Setthi. Turnour's Mahāwanso, 76; Cunningham's Bhilsa Topes, 95.

**Chapter IV.**  
**THE MAURYAS**  
**B.C. 319-197.**

Girnár as Pushyagupta is simply called a Vaiśya and a brother-in-law of king Chandragupta and has no royal attribute, particulars which tend to show that he was a local governor subordinate to king Chandragupta. The same inscription<sup>1</sup> states that in the time of Aśoka (B.C. 250) his officer Yavanarāja-Tusháspa adorned the same Sudarśana lake with conduits. This would seem to prove the continuance of Mauryan rule in Girnár for three generations from Chandragupta to Aśoka. Tusháspa is called Yavanarāja. The use of the term *rāja* would seem to show that, unlike Chandragupta's Vaiśya governor Pushyagupta, Tusháspa was a dignitary of high rank and noble family. That he is called Yavanarāja does not prove Tusháspa was a Greek, though for Greeks alone Yavana is the proper term. The name Tusháspa rather suggests a Persian origin from its close likeness in formation to Kershásp, a name still current among Bombay Pársis. Evidence from other sources proves that Aśoka held complete sway over Málwa, Gujarát, and the Konkan coast. All the rock edicts of Aśoka hitherto traced have been found on the confines of his great empire. On the north-west at Kapurdighi and at Shahbazgarhi in the Baktro-Páli character; in the north north-west at Kālsi, in the east at Dhauli and Junágadh; in the west at Girnár and Sopára, and in the south in Maisur all in Maurya characters. The Girnár and Sopára edicts leave no doubt that the Gujarát, Káthiáváda, and North Konkan seaboard was in Aśoka's possession. The fact that an inland ruler holds the coast implies his supremacy over the intervening country. Further it is known that Aśoka was viceroy of Málwa in the time of his father and that after his father's death he was sovereign of Málwa. The easy route from Mandasor (better known as Dasapur) to Dohad has always secured a close connection between Málwa and Gujarát. South Gujarát lies at the mercy of any invader entering by Dohad and the conquest of Káthiáváda on one side and of Upper Gujarát on the other might follow in detail. As we know that Káthiáváda and South Gujarát as far as Sopára were held by Aśoka it is not improbable that Upper Gujarát also owed his sway. The Maurya capital of Gujarát seems to have been Girinagara or Junágadh in Central Káthiáváda, whose strong hill fort dominating the rich province of Sorath and whose lofty hills a centre of worship and a defence and retreat from invaders combined to secure for Junágadh its continuance as capital under the Kshatrapas (A.D. 100-380) and their successors the Guptas (A.D. 380-460). The southern capital of the Mauryas seems to have been Sopára near Bassein in a rich country with a good and safe harbour for small vessels, probably in those times the chief centre of the Konkan and South Gujarát trade.

Buddhist and Jain records agree that Aśoka was succeeded, not by his son Kunála who was blind, but by his grandsons Daśaratha and Samprati. The Barábar hill near Gayá has caves made by Aśoka and bearing his inscriptions; and close to Barábar is the

<sup>1</sup> Probably from some mistake of the graver's the text of the inscription अशोकस्य ते यवनराजेन yields no meaning. Some word for governor or officer is apparently meant.

Nāgarjuna hill with caves made by Daśaratha also bearing his inscriptions. In one of these inscriptions the remark occurs that one of the Barābar caves was made by Daśaratha 'installed immediately after.' As the caves in the neighbouring hill must have been well known to have been made by Aśoka this 'after' may mean after Aśoka, or the 'after' may refer solely to the sequence between Daśaratha's installation and his excavation of the cave. In any case it is probable that Daśaratha was Aśoka's successor. Jaina records pass over Daśaratha and say that Aśoka was succeeded by his grandson Samprati the son of Kunāla. In the matter of the propagation of the Jain faith, Jain records speak as highly of Samprati as Buddhist records speak of Aśoka.<sup>1</sup> Almost all old Jain temples or monuments, whose builders are unknown, are ascribed to Samprati, who is said to have built thousands of temples as Aśoka is said to have raised thousands of stupas. In his Pātaliputra-kalpa Jānaprabhāsuri the well known Jaina Āchārya and writer gives a number of legendary and other stories of Pātaliputra. Comparing Samprati with Aśoka in respect of the propagation of the faith in non-Aryan countries the Āchārya writes: 'In Pātaliputra flourished the great king Samprati son of Kunāla lord of Bharata with its three continents, the great Arhanta who established viharas for Śramanas even in non-Aryan countries.'<sup>2</sup> It would appear from this that after Aśoka the Mauryan empire may have been divided into two, Daśaratha ruling Eastern India, and Samprati, whom Jaina records specially mention as king of Ujjain, ruling Western India, where the Jain sect is specially strong. Though we have no specific information on the point, it is probable, especially as he held Mālwa, that during the reign of Samprati Gujārāt remained under Mauryan sway. With Samprati Mauryan rule in Gujārāt seems to end. In later times (A.D. 500) traces of Mauryan chiefs appear in Mālwa and in the North Konkan. The available details will be given in another chapter.

After Samprati, whose reign ended about B.C. 197, a blank of seventeen years occurs in Gujārāt history. The next available information shows traces of Baktrian-Greek sway over parts of Gujārāt. In his description of Surastrene or Surashtra the author of the Periplus (A.D. 210) says: 'In this part there are preserved even to this day memorials of the expedition of Alexander, old temples, foundations of camps, and large wells.'<sup>3</sup> As Alexander did not

Chapter IV.  
THE MAURYAS  
B.C. 319-197.

<sup>1</sup> Hemachandra's Parisiṣṭa Parva Merutunga's Viśākhāśreni.

<sup>2</sup> The text is 'Kundlasānuṣṭrikhaṇḍabharatāthupāh Paramarhanto Andryasēśeshvapi Pravaritāramāṇa-vihārah Samprati Mahārāja Sahābhavāt' meaning 'He was the great king Samprati son of Kunāla, sovereign of India of three continents, the great saint who had started monasteries for Jain priests even in non-Aryan countries.'

<sup>3</sup> McCrindle's Periplus, 115. The author of the Periplus calls the capital of Surastrene Minnagara. Pandit Bhagvanlāl believed Minnagara to be a miswriting of Girinagara the form used for Girnār both in Rudradāman's (A.D. 150) rock inscription at Girnār (Fleet's Corpus Ins. Ind. III. 57) and by Varāha-Mihira (A.D. 570) (Bṛhat-Saṃhitā, XIV. 11). The mention of a Minagara in Ptolemy inland from Sorath and Monoglossum or Mangrū suggests that either Girnār or Junagaḍh was also known as Minnagara either after the Mins or after Mēn, that is Menander. At the same time it is possible that Ptolemy's Agrinagara though much out of place may be Girinagara and that Ptolemy's Minagara in the direction of Ujjain may be Mandasor.

Chapter IV.  
THE GREEKS.  
B.C. 180-100.

come so far south as Káthiáváda and as after Alexander's departure the Mauryas held Káthiáváda till about B.C. 197, it may be suggested that the temples, camps and wells referred to by the author of the *Periplus* were not memorials of the expedition of Alexander but remains of later Baktrian-Greek supremacy.

Demetrius, whom Justin calls the king of the Indians, is believed to have reigned from B.C. 190 to B.C. 165.<sup>1</sup> On the authority of Apollodorus of Astamita Strabo (B.C. 50 - A.D. 20) names two Baktrian-Greek rulers who seem to have advanced far into inland India. He says: 'The Greeks who occasioned the revolt of Baktria (from Syria B.C. 256) were so powerful by the fertility and advantages of the country that they became masters of Ariana and India. . . . The chiefs, particularly Menander, conquered more nations than Alexander. These conquests were achieved partly by Menander and partly by Demetrius son of Euthydemus king of the Baktrians. They got possession not only of Pattalene but of the kingdoms of Saraostus and Sigerdis, which constitute the remainder of the coast.'<sup>2</sup> Pattalene is generally believed to be the old city of Pátál in Sindh (the modern Haidarábád), while the subsequent mention of Saraostus and Sigerdis as kingdoms which constitute the remainder of the coast, leaves almost no doubt that Saraostus is Suráshtra and Sigerdis is Sagaradvípa or Cutch. The joint mention of Menander (B.C. 126) and Demetrius (B.C. 190) may mean that Demetrius advanced into inland India to a certain point and that Menander passed further and took Sindh, Cutch, and Káthiáváda. The discovery in Cutch and Káthiáváda of coins of Baktrian kings supports the statements of Justin and Strabo. Dr. Bhagvanlal's collecting of coins in Káthiáváda and Gujarát during nearly twenty-five years brought to light among Baktrian-Greek coins an obolus of Eucratides (B.C. 180-155), a few drachmæ of Menander (B.C. 126-110), many drachmæ and copper coins of Apollodotus (B.C. 110-100), but none of Demetrius. Eucratides was a contemporary of Demetrius. Still, as Eucratides became king of Baktria after Demetrius, his conquests, according to Strabo of a thousand cities to the east of the Indus, must be later than those of Demetrius.

As his coins are found in Káthiáváda Eucratides may either have advanced into Káthiáváda or the province may have come under his sway as lord of the neighbouring country of Sindh. Whether or not Eucratides conquered the province, he is the earliest Baktrian-Greek king whose coins have been found in Káthiáváda and Gujarát. The fact that the coins of Eucratides have been found in different parts of Káthiáváda and at different times seems to show that they were the currency of the province and were not merely imported either for trade or for ornament. It is to be noticed that these coins are all of the smallest value of the numerous coins issued by Eucratides. This may be explained by the fact that these small

<sup>1</sup> Justin's date is probably about A.D. 250. His work is a summary of the History of Trogus Pompeius about A.D. 1. Watson's Justin, 277; Wilson's Ariana Antiqua, 231.

<sup>2</sup> Hamilton and Falconer's Strabo, II. 252-253.

coins were introduced by Eucratides into Káthiáváda to be in keeping with the existing local coinage. The local silver coins in use before the time of Eucratides are very small, weighing five to seven grains, and bear the Buddhist symbols of the Svastika, the Trident, and the Wheel. Another variety has been found weighing about four grains with a misshapen elephant on the obverse and something like a circle on the reverse.<sup>1</sup> It was probably to replace this poor currency that Eucratides introduced his smallest obolus of less weight but better workmanship.

The end of the reign of Eucratides is not fixed with certainty: it is believed to be about B.C. 155.<sup>2</sup> For the two Baktrian-Greek kings Menander and Apollodotus who ruled in Káthiáváda after Eucratides, better sources of information are available. As already noticed Strabo (A.D. 20) mentions that Menander's conquests (B.C. 120) included Cutch and Suráshtra.<sup>3</sup> And the author of the Periplus (A.D. 240) writes: 'Up to the present day old drachmæ bearing the Greek inscriptions of Apollodotus and Menander are current in Barugaza (Broach).'<sup>4</sup> Menander's silver drachmæ have been found in Káthiáváda and Southern Gujarát.<sup>5</sup> Though their number is small Menander's coins are comparatively less scarce than those of the earliest Kshatrapás Nahapána and Chashtana (A.D. 100-140). The distribution of Menander's coins suggests he was the first Baktrian-Greek king who resided in these parts and that the monuments of Alexander's times, camps, temples and wells, mentioned by the author of the Periplus<sup>6</sup> were camps of Menander in Suráshtra. Wilson and Rochette have supposed Apollodotus to be the son and successor of Menander,<sup>7</sup> while General Cunningham believes Apollodotus to be the predecessor of Menander.<sup>8</sup> Inferences from the coins of these two kings found in Gujarát and Káthiáváda support the view that Apollodotus was the successor of Menander. The coins of Apollodotus are found in much larger numbers than those of Menander and the workmanship of Apollodotus' coins appears to be of a gradually declining style. In the later coins the legend is at times undecipherable. It appears from this that for some time after Apollodotus until Nahapána's (A.D. 100) coins came into use, the chief local currency was debased coins struck after the type of the coins of Apollodotus. Their use as the type of coinage generally happens to the coins of the last king of a dynasty. The statement by the author of the Periplus that in his time (A.D. 240) the old drachmæ of Apollodotus and Menander were

<sup>1</sup> These small local coins which were found in Hálár Gondal were presented to the Bombay Asiatic Society by the Political Agent of Káthiáwár and are in the Society's cabinet. Dr. Bhagvanlál found the two elephant coins in Junágadh.

<sup>2</sup> Wilson's *Ariana Antiqua*, 266. Gardner's *British Museum Catalogue*, 26, brings Eucratides to after B.C. 162.

<sup>3</sup> See above page 15.

<sup>4</sup> McCrindle's *Periplus*, 121.

<sup>5</sup> The Bombay Asiatic Society possesses some specimens of these coins of bad workmanship found near Broach with the legend incorrect, probably struck by some local governor of Menander. Two were also found in Junágadh.

<sup>6</sup> McCrindle's *Periplus*, 115.

<sup>7</sup> *Numismatic Chronicle* (New Series), X. 80; Wilson's *Ariana Antiqua*, 268.

<sup>8</sup> *Numismatic Chronicle* (New Series), XI. 60.

**Chapter IV.**  
**THE GREEKS.**  
B.C. 180-100.

current in Barugaza, seems to show that these drachmæ continued to circulate in Gujarāt along with the coins of the Western Kshatrapas. The mention of Apollodotus before Menander by the author of the Periplus may either be accidental, or it may be due to the fact that when the author wrote fewer coins of Menander than of Apollodotus were in circulation.

The silver coins both of Menander and Apollodotus found in Gujarāt and Kāthiāvāda are of only one variety, round drachmæ. The reason that of their numerous large coins, tetradrachmæ didrachmæ and others, drachmæ alone have been found in Gujarāt is probably the reason suggested for the introduction of the obolus of Eucratides, namely that the existing local currency was so poor that coins of small value could alone circulate. Still the fact that drachmæ came into use implies some improvement in the currency, chiefly in size. The drachmæ of both the kings are alike. The obverse of Menander's coins has in the middle a helmeted bust of the king and round it the Greek legend ΒΑΣΙΛΕΩΣ ΣΩΤΗΡΟΣ ΜΕΝΑΝΔΡΟΥ Of the king the Saviour Menander. On the reverse is the figure of Athens Promachos surrounded by the Baktro-Pāli legend Mahārājasa Trādātasa Menandrasa that is Of the Great king the Saviour Menander, and a monogram.<sup>1</sup> The drachmæ of Apollodotus have on the obverse a bust with bare filleted head surrounded by the legend ΒΑΣΙΛΕΩΣ ΣΩΤΗΡΟΣ ΑΠΟΛΛΟΔΟΤΟΥ Of the king the Saviour Apollodotus. Except in the legend the reverse with two varieties of monogram<sup>2</sup> is the same as the reverse of the drachmæ of Menander. The legend in Baktro-Pāli character is Mahārājasa Rājātirājasa Apaladatasa that is Of the Great king the over-king of kings Apaladata. During his twenty-five years of coin-collecting Dr. Bhagvānlāl failed to secure a single copper coin of Menander either in Gujarāt or in Kāthiāvāda. Of the copper coins of Apollodotus a deposit was found in Junāgadh, many of them well preserved.<sup>3</sup> These coins are of two varieties, one square the other round and large. Of the square coin the obverse has a standing Apollo with an arrow in the right hand and on the top and the two sides the Greek legend ΒΑΣΙΛΕΩΣ ΣΩΤΗΡΟΣ ΚΑΙ ΦΙΛΟΠΑΤΡΟΣ ΑΠΟΛΛΟΔΟΤΟΥ that is Of the King Saviour and Fatherlover Apollodotus. On the reverse is the tripod of Apollo with a monogram<sup>4</sup> and the letter *di* in Baktro-Pāli on the left and the legend in Baktro-Pāli characters Mahārājasa Trādātasa Apaladatasa. The round coin has also, on the obverse, a standing Apollo with an arrow in the right hand; behind is the same monogram as in the square coin and all round runs the Greek legend ΒΑΣΙΛΕΩΣ ΣΩΤΗΡΟΣ ΑΠΟΛΛΟΔΟΤΟΥ. On the reverse is the tripod of Apollo with on its right and left the letters *di* and *u* in Baktro-Pāli and all round the Baktro-Pāli legend Mahārājasa Trādātasa Apaladatasa.

<sup>1</sup> Wilson's *Ariana Antiqua*, Plate XXII. Number 41. Gardner's *British Museum Catalogue*, Plate XI. Number 8.

<sup>2</sup> Wilson's *Ariana Antiqua*, Plate XXII. Number 66, shows one variety of this monogram.

<sup>3</sup> These coins are said to have been found in 1882 by a cultivator in an earthen pot. Two of them were taken for Pandit Bhagvānlāl and one for Mr. Vajeshankar Gaurishankar Naib Divān of Bhāvnagar. The rest disappeared.

<sup>4</sup> *Ariana Antiqua*, Plate XXII. Number 47.

The reason why so few copper coins of Apollodotus have been found in Gujarát perhaps is that these copper coins were current only in the time of Apollodotus and did not, like his silver drachmæ, continue as the currency of the country with the same or an imitated die. The date of the reign of Apollodotus is not fixed. General Cunningham believes it to be B.C. 165-150,<sup>1</sup> Wilson and Gardner take it to be B.C. 110-100.<sup>2</sup> Though no Indian materials enable us to arrive at any final conclusion regarding this date the fact that Apollodotus' coins continued to be issued long after his time shows that Apollodotus was the last Bactrian-Greek ruler of Gujarát and Káthiáváda. After Apollodotus we find no trace of Bactrian-Greek rule, and no other certain information until the establishment of the Kshatrapas about A.D. 100. The only fact that breaks this blank in Gujarát history is the discovery of copper coins of a king whose name is not known, but who calls himself Basileus Basileon Soter Megas that is King of Kings the Great Saviour. These coins are found in Káthiáváda andutch as well as in Rájputána the North-West Provinces and the Kabul valley, a distribution which points to a widespread Indian rule. The suggestion may be offered that this king is one of the leaders of the Yaudheyas whose constitution is said to have been tribal, that is the tribe was ruled by a number of small chiefs who would not be likely to give their names on their coins.<sup>3</sup>

<sup>1</sup> Numismatic Chronicle (New Series), X. 86.

<sup>2</sup> *Ariana Antiqua*, 285, Gardner and Poole's Catalogue of Indian Coins, xxxiii.

<sup>3</sup> Wilson (*Ariana Antiqua*, 332-334) identifies the coins marked Basileus Basileon Soter Megas with a king or dynasty of Indian extraction who reigned between Azes and Kadphises (B.C. 50-25), chiefly in the Panjáb. Gardner (*British Museum Catalogue*, 47) says The Nameless king is probably cotemporary with Abdagases (A.D. 30-50) he may have been a member of the Kadphises dynasty. Cunningham (*Ancient Geography*, 245) places the coins of the tribal Yaudheyas in the first century A.D. The remark of Prinsep (*Jour. Bengal Soc.* VI. 2, 973) that in the Behat group of Buddhist coins some with Baktro-Páli legends have the name Yaudheya in the margin seems to support the suggestion in the text. But the marked difference between the Stag coins of the Yaudheyas (Thomas' Prinsep, I. Plate V) and the Nameless king's coins (Gardner, Plate XIV. 1-6) tells strongly against the proposed identification. Of the Yaudheyas details are given below.

## CHAPTER V.

### THE KSHATRAPAS

(B.C. 70 - A.D. 398.)

#### Chapter V.

THE KSHATRAPAS,  
B.C. 70 - A.D. 398.

#### Two Dynasties.

WITH the Kshatrapas (B.C. 70) begins a period of clearer light, and, at the same time, of increased importance, since, for more than three centuries, the Kshatrapas held sway over the greater part of Western India. Till recently this dynasty was known to orientalists as the Sâh dynasty a mistaken reading of the terminal of their names which in some rulers is Simha Lion and in others, as in Rudra Sena (A.D. 203-220) son of Rudra Simha, Sena Army.<sup>1</sup>

The sway of the rulers who affix the title Kshatrapa to their names extended over two large parts of India, one in the north including the territory from the Kâbul valley to the confluence of the Ganges and the Jamnâ; the other in the west stretching from Ajmir in the north to the North Konkan in the south and from Mâlwa in the east to the Arabian

<sup>1</sup> Journal Bengal Asiatic Society (1835), 681; (1837), 351; (1838), 346; Thomas' Prinsep's Indian Antiquities, I. 425-435, II 84-93; Thomas in Journal Royal Asiatic Society (Old Series), XII. 1-72; Wilson's Ariana Antiqua, 405-413, Journal B. B. R. A. S. VI. 377, VII 392, Burgess' Archaeological Report of Kathiâwar and Kachh, 18-72, Journal B B R. A. S. XII (Proceedings), XXIII.; Indian Antiquary, VI. 43, X 221-227.

The dynasty of the Kshatrapas or Mahâkshatrapas of Saurâshtra was known to Prinsep (J. R. A. S. Bl. VII. - I. (1837), 351) to Thomas (J. R. A. S. F. S. XII. 1-72), and to Newton (Jl B. B. R. A. S. IX 1-19) as the Sâh or Sâh kings. More recently, from the fact that the names of some of them end in Sena or army, the Kshatrapas have been called the Sena kings. The origin of the title Sâh is the ending *sîha*, that is *simha* lion, which belongs to the names of several of the kings. *Sîha* has been read either *sâh* or *sena* because of the practice of omitting from the die vowels which would fall on or above the top line of the legend and also of omitting the short vowel *i* with the following *anusvâra*. Sâh is therefore a true reading of the writing on certain of the coins. That the form Sâh on these coins is not the correct form has been ascertained from stone inscriptions in which freedom from crowding makes possible the complete cutting of the above-line marks. In stone inscriptions the ending is *sîha* lion. See Fleet's Corpus Inscriptionum Indicarum, III. 36 note 1. Mr. Fleet (Ditto) seems to suggest that with the proof of the incorrectness of the reading Sâh the evidence that the Kshatrapas were of Indo-Skythian origin ceases. This does not seem to follow. In addition to the Parthian title Kshatrapa, their northern coinage, and the use of the Śaka (A.D. 78) era, now accepted as the accession of the great Kushân Kanishka, the evidence in the text shows that the line of Kâthiâvâda Kshatrapas starts from the foreigner Chastâna (A.D. 130) whose predecessor Nahâpana (A.D. 120) and his Śaka son-in-law Ushavadatta are noted in Nâsik inscriptions (Nâsik Gazetteer, 538 and 621) as leaders of Śakas, Pâlavas, and Yavanas. Further as the limits of Ptolemy's (A.D. 150) Indo-Skythia (McCrindle, 136) agree very closely with the limits of the dominions of the then ruling Mahâkshatrapa Rudradâman (A.D. 150) it follows that Ptolemy or his informer believed Rudradâman to be an Indo-Skythian. There therefore seems no reasonable doubt that the Kshatrapas were foreigners. According to Cunningham (Num. Chron. VIII. 231) they were Śakas who entered Gujarat from Sindh. The fact that the Kushân era (A.D. 78) was not adopted by the first two of the Western Kshatrapas, Chastâna and Juvâhman, supports the view that they belonged to a wave of northerners earlier than the wave.

in the west. The former may be called the Northern the latter the Western Kshatrapas.

Besides as Kshatrapa, in the Prākṛit legends of coins and in inscriptions the title of these dynasties appears under three forms Chhatrapa,<sup>1</sup> Chhatrava,<sup>2</sup> and Khatapa.<sup>3</sup> All these forms have the same meaning namely Lord or Protector of the warrior-race, the Sanskrit Kshatra-pa.<sup>4</sup> It is to be noted that the title Kshatrapa appears nowhere as a title of any king or royal officer within the whole range of Sanskrit literature, or indeed on any inscription, coin, or other record of any Indian dynasty except the Northern and the Western Kshatrapas. According to Prinsep Kshātrapa is a Sanskritized form of Satrapa, a term familiar to the Grecian history of ancient Persia and used for the prefect of a province under the Persian system of government. As Prinsep further observes Satrapa had probably the same meaning in Ariana that Kshatrapa had in Sanskrit, the ruler feeder or patron of the *kshatra* or warrior class, the chief of a warlike tribe or clan.<sup>5</sup> Prinsep further notes the Persian kings were often in need of such chiefs and as they entrusted the chiefs with the government of parts of their dominions the word came to mean a governor. So during the anarchy which prevailed on the Skythian overthrow of Greek rule in Baktria<sup>6</sup> (B.C. 160) several chiefs of Malaya, Pallava, Abhira, Meda, and other predatory tribes came from Baktria to Upper India, and each established for himself a principality or kingdom. Subsequently these chiefs appear to have assumed independent sovereignty. Still though they often call themselves *rājās* or kings with the title Kshatrapa or Mahākshatrapa, if any Baktrian king advanced towards their territories, they were probably ready to acknowledge him as Overlord. Another reason for believing these Kshatrapa chiefs to have been foreigners is that, while the names of the founders of Kshatrapa sovereignty are foreign, their inscriptions and coins show that soon after the establishment of their rule they became converts to one or other form of the Hindu religion and assumed Indian names.<sup>7</sup>

Chapter V.

THE KSHATRAPAS.  
B.C. 70 - A.D. 300  
The Name.

<sup>1</sup> The Taxila plate in Journal R. A. S. (New Series), IV. 487; the Baktra-Pāli on Nahapāna's coins also gives the form Chhatrapa.

<sup>2</sup> Chhatrava appears in an unpublished Kshatrapa inscription from Mathurā formerly (1888) in Pandit Bhagvānlāl's possession.

<sup>3</sup> Khatapa appears in the inscription of Nahapāna's minister at Junnar (Bombay Gazetteer, XVIII. Pt. I. 167) and in some coins of the Northern Kshatrapa kings Parauasha, Rājavala, and Sudasa found near Mathurā. Prinsep's Indian Antiquities, II. Pl. XLIV. Figs. 12, 20, 21.

<sup>4</sup> Kshatrapāpātīti Kshatrapah.

<sup>5</sup> Thomas' Prinsep, II. 63 and 64.

<sup>6</sup> Malaya or Malava, Pallava, Abhira, Meva or Meda, and Mihira or Mehr appear to be the leading warlike tribes who came to India under these chiefs. These tribes formed the Kshatras whose lords or Kshatrapas these chiefs were.

<sup>7</sup> The explanation of the word Kshatrapa started by Prinsep and accepted by Pandit Bhagvānlāl is of doubtful accuracy. The title is well known in Greek literature in the form *σατραπης*, and in the form Kshatrapāvan occurs in the great Behistan inscription of Darius (Rawlinson's Herodotus, I. 329; Spiegel's *Altperische Keilinschriften*, 24-26). The meaning of Kshatrapāvan in old Persian is not "protector of the Kshatra race" but "protector of the kingdom," for the word *sa* occurs in the inscriptions of the Achæmenides with the meaning of "kingship" or "kingdom" (Spiegel, *Altperische Keilinschriften*, 215). As is well known Satrap was the official title of the ruler of a Persian province. That the name continued in use with the same meaning under the Greek kings of Baktria

**Chapter V.**  
**NORTHERN**  
**KSHATRAPAS,**  
**70 - A.D. 78.**

According to inscriptions and coins Northern Kshatrapa rule begins with king Maues about B.C. 70 and ends with the accession of the Kushán king Kanishka about A.D. 78. Maues probably belonged to the Śaka tribe of Skythians. If the Maues of the coins may be identified with the Moga of the Taxila plate the date of king Patika in the Taxila plate shows that for about seventy-five years after the death of Maues the date of his accession continued to be the initial year of the dynasty. From their connexion with the Sakas, arriving in India during the reign of the Saka Maues and for nearly three quarters of a century accepting the Śaka overlordship, the Kshatrapas, though as noted above their followers were chiefly Malayas, Pallavas, Abhīras, and Medas, appear to have themselves come to be called Sakas and the mention of Saka kings in Purāṇik and other records seems to refer to them. After lasting for about 150 years the rule of the Northern Kshatrapas seems to have merged in the empire of the great Kushán Kanishka (A.D. 78).

Though recently found inscriptions and coins show that the Kshatrapas ruled over important parts of India including even a share of the western seaboard, nothing is known regarding them from either Indian or foreign literary sources. What little information can be gleaned is from their own inscriptions and coins. Of the Northern Kshatrapas this information is imperfect and disconnected. It shows that they had probably three or four ruling branches, one in the Kábul valley, a second at Taxila near Attak on the North-West Panjab frontier, a third at Behāt near Sahāranpur or Delhi, and a fourth at Mathurá. The last two were perhaps subdivisions of one kingdom; but probably those at Kábul and at Taxila were distinct dynasties. An inscription found

(B.C. 250-100) is known from Strabo, who says (XI 11) "the Greeks who held Bactria divided it into satrapies (*σατραπείας*) of which Aspionus and Touriva were taken from Eukratides (B.C. 180) by the Parthians." It is to be presumed that the Baktro-Greeks introduced the same arrangement into the provinces which they conquered in India. The earliest occurrence of the title in its Indian form is on the coins of a Rajabula or Banjabola (Gardner, B. M. Cat. 67), who in his Greek legend makes use of the title "King of kings," and in his Indian legend calls himself "The unconquered (Kshatrapa)." His adoption for the reverse of his coins of the Athene Promachos type of Menander and Apollodotus Philopator connects Rajabula in time with those kings (B.C. 126-100) and we know from an inscription (Cunningham Arch. Rep. XX, 48) that he reigned at Mathurá. He was probably a provincial governor who became independent about B.C. 100 when the Greek kingdom broke up. The above facts go to show that Kshatrapa was originally a Persian title which was adopted by the Greeks and continued in use among their successors: that it originally denoted a provincial governor; but that, when the Greek kingdom broke up and their provincial chiefs became independent, it continued in use as a royal title. That after the Christian era, even in Parthia, the title Satrapes does not necessarily imply subjection to a suzerain is proved by the use of the phrase *σατραπὴς τῶν σατραπῶν* Satrap of Satraps, with the sense of King of Kings in Gotarzes' Behistan inscription of A.D. 50. See Rawlinson's Sixth Monarchy, 88 n. 2 and 260 n. 1.—(A. M. T. J.)

The Pandit's identification of the Malayas or Malavas with a northern or Skythian tribe is in agreement with Alberuni (A.D. 1015), who, on the authority of the Bāṇ Purāṇa (Sachau's Text, chap. 29 page 150-155) groups as northern tribes the Pallavas, Sakas, Mallas, and Gurjars. In spite of this authority it seems better to identify the Mallas, Malavas, or Malayas with Alexander the Great's (B.C. 325) Mallol of Multan (compare McCrindle's Alexander's Invasion of India, Note P). At the same time (Rockhill's Life of Buddha, 132, 133, 137) the importance of the Mallas in Vaishali (between Patnā and Tirhut) during the lifetime of Śākya Muni (B.C. 580) favours the view that several distinct tribes have borne the same or nearly the same name.

in Mathurá shows a connection either by marriage or by neighbourhood between the Behát and Mathurá branches. This is a Baktro-Páli inscription recording the gift of a stúpa by Nandasiriká daughter of Kshatrapa Rájavula and mother of Kharaosti Yuvarája. Kharaosti is the dynastic name of the prince, his personal name appears later in the inscription as Talama (Ptolemy?). From his dynastic name, whose crude form Kharaosta<sup>2</sup> or Kharaottha may be the origin of the Prakrit. Chhaharáta and the Sanskritised Kshaharáta, this Talama appears to be a descendant of the Kshatrapa Kharaosti whose coins found at Taxila call him Artaputa that is the son of Arta apparently the Parthian, Ortus. •

The same Baktro-Páli Mathurá inscription also mentions with special respect a Kshatrapa named Patika,<sup>1</sup> who, with the title of Kusulaka or Kozolon, ruled the Kábul valley with his capital first at Nagaraka and later at Taxila.

The same inscription further mentions that the stúpa was given while the Kshatrapa Sudása son of the Mahákshatrapa Rájavula was ruling at Mathurá. The inference from the difference in the titles of the father and the son seems to be that Sudása was ruling in Mathurá as governor under his father who perhaps ruled in the neighbourhood of Delhi where many of his coins have been found. While the coins of Sudása have the legend in Nágari only, Rájavula's coins are of two varieties, one with the legend in Baktro-Páli and the other with the legend in Nágari, a fact tending to show that the father's territories stretched to the far north.

Though Kharaosti is mentioned as a Yuvarája or prince heir-apparent in the time of his maternal uncle Sudása, the inscription shows he had four children. It is curious that while the inscription mentions Nandasiriká as the mother of Kharaosti Yuvarája, nothing is said about her husband. Perhaps he was dead or something had happened to make Nandasiriká live at her father's home.

Another inscription of Sudása found by General Cunningham at Mathurá is in old Nágari character. Except that they have the distinctive and long continued Kshatrapa peculiarity of joining *ya* with other letters the characters of this inscription are of the same period as those of the inscriptions of the great Indo-Skythian or Kushán king Kanishka. This would seem to show that the conquest of Mathurá by Kanishka took place soon after the time of Kshatrapa Sudása. It therefore appears probable that Nahapána, the first Kshatrapa ruler of Gujarát and Káthiaváda, the letters of whose inscriptions are of exactly the same Kshatrapa type as those of Sudása, was a scion of the Kharaosti family, who, in this overthrow of kingdoms, went westwards conquering either on his own account or as a general sent by Kanishka. Nahapána's advance seems to have lain through East Rajputána by Mandasor<sup>3</sup>

# Chapter V.

NORTHERN  
KSHATRAPAS,  
B.C. 70 : A.D. 700

WESTERN  
KSHATRAPAS,  
A.D. 70 - 398.

<sup>1</sup> Patika was apparently the son of the Liako Kujulako of the Taxila plate. Dowson in Jour. B. A. S. New Series. IV. 497 mis-translates the inscription and fails to make out the name Patika.

<sup>2</sup> Compare Specht. Jour. Asiatique, 1883. t. II. 325. According to Chinese writers about A.D. 20 Yen-kao-tchin-tai or Kadphises II. conquered India (Thientchou) and there established generals who governed in the name of the Yuechl.

<sup>3</sup> Pandit Bhagvánlal found two of his copper coins at Mandasor in 1884.

Chapter V.  
WESTERN  
KSHATRAPAS,  
A.D. 70-398.

in West Málwa along the easy route to Dohad as far as South Gujarát. From South Gujarát his power spread in two directions, by sea to Káthiáváda and from near Balsár by the Dáng passes to Násik and the Deccan, over almost the whole of which, judging from coins and inscriptions, he supplanted as overlord the great Andhra kings of the Deccan. No evidence is available to show either that East Málwa with its capital at Ujjain or that North Gujarát formed part of his dominions. All the information we have regarding Nahapána is from his own silver coins and from the inscriptions of his son-in-law Ushavadáta at Násik and Kárlé and of his minister Ayama (Sk. Aryaman) at Junnar. Nahapána's coins are comparatively rare. The only published specimen<sup>1</sup> is one obtained by Mr. Justice Newton.<sup>2</sup> Four others were also obtained by Dr. Bhagvánlal from Káthiáváda and Násik.

Kshatrpa I.  
Nahapána,  
A.D. 78-120.

The coins of Nahapána are the earliest specimens of Kshatrpa coins. Though the type seems to have been adopted from the Baktrian-Greek, the design is original and is not an imitation of any previous coinage. The type seems adopted in idea from the drachma of Apollodotus (B.C. 110-100). On the obverse is a bust with a Greek legend round it and on the reverse a thunderbolt and an arrow probably as on the reverse of the coins of Apollodotus<sup>3</sup> representing the distinctive weapons of Athene Promachos and of Apollo. In addition to the Baktrian-Páli legend on the Apollodotus drachma, the reverse of Nahapána's coin has the same legend in Nágari, since Nágari was the character of the country for which the coin was struck. The dress of the bust is in the style of the over-dress of Nahapána's time. The bust, facing the right, wears a flat grooved cap and has the hair combed in ringlets falling half down the ear. The neck shows the collar of the coat. The workmanship of the coins is good. The die seems to have been renewed from time to time as the face altered with age. Of Dr. Bhagvánlal's four coins one belongs to Nahapána's youth, another to his old age, and the remaining two to his intervening years. In all four specimens the Greek legend is imperfect and unreadable. The letters of the Greek legend are of the later period that is like the letters on the coins of the great Skythian king Kadphises I. (B.C. 26). One of the coins shows in the legend the six letters LLODO-S. These may be the remains of the name Apollodotus (B.C. 110-100). Still it is beyond doubt that the letters are later Greek than those on the coins of Apollodotus. Until the legend is found clear on some fresher specimen, it is not possible to say anything further. In three of the coins the Baktrian-Páli legend on the reverse runs :

रजो च्छरातस नहपानस.

Rājō Chhaharātasa Nahapānasa.

Of king Chhaharāta Nahapāna.

The fourth has simply

रजो च्छरातस

Rājō Chhaharātasa.

Of king Chhaharāta.

<sup>1</sup> This is a bad specimen with the legend dim and worn.

<sup>2</sup> Some coins of Apollodotus have on the reverse Apollo with his arrow; others have Athene Promachos with the thunderbolt.

The old Nāgarī legend is the same in all :

राज्ञो क्शहारातस नहपानस .

Raño Kshaharātasa Nahapānasa.

Of king Kshaharāta Nahapāna.

The Chhaharāta of the former and the Kshaharāta of the latter are the same, the difference in the initial letter being merely dialectical. As mentioned above Kshaharāta is the family name of Nahapāna's dynasty. It is worthy of note that though Nahapāna is not styled Kshatrpa in any of his coins the inscriptions of Ushavadāta at Nāsik repeatedly style him the Kshaharāta Kshatrpa Nahapāna.<sup>1</sup>

Ushavadāta was the son-in-law of Nahapāna being married to his daughter Dakṣamitā or Dakṣamitrā. Ushavadāta bears no royal title. He simply calls himself son of Dīnīka and son-in-law of Nahapāna, which shows that he owed his power and rank to his father-in-law, a position regarded as derogatory in India, where no scion of any royal dynasty would accept or take pride in greatness or influence obtained from a father-in-law.<sup>2</sup> Nāsik Inscription XIV. shows that Ushavadāta was a Śaka. His name, as was first suggested by Dr. Bhan Dāji, is Prakrit for Rishabhādatta. From the many charitable and publicly useful works mentioned in various Nāsik and Karle inscriptions, as made by him in places which apparently formed part of Nahapāna's dominions, Ushavadāta appears to have been a high officer under Nahapāna. As Nahapāna seems to have had no son Ushavadāta's position as son-in-law would be one of special power and influence. Ushavadāta's charitable acts and works of public utility are detailed in Nāsik Inscriptions X, XII. and XIV. The charitable acts are the gift of three hundred thousand cows; of gold and of river-side steps at the Bārnasa or Banās river near Abu in North Gujarāt; of sixteen villages to gods and Brāhmins; the feeding of hundreds of thousands of Brāhmins every year; the giving in marriage of eight wives to Brāhmins at Prabhās in South Kāthiavada; the bestowing of thirty-two thousand coconut trees in Nanangola or Nārgol village on the Thāna seaboard on the Charaka priesthoods of Pinditakāvada, Govardhana near Nāsik, Suvarnamukha, and Rāmatīrtha in Sorpāraga or Sopāra on the Thāna coast; the giving of three hundred thousand cows and a village at Pushkara or Pokhar near Ajmir in East Rajputāna; making gifts to Brāhmins at Chechina or Chichan near Kalyāṇ-Māhim on the Thāna coast; and the gift of trees and 70,000 *kārshāpanas* or 2000 *suvarṇas* to gods and Brāhmins at Dāhānu in Thāna. The public works executed by Ushavadāta include rest-houses and alms-houses at Bharu Kachha or Broach, at Daśapura or Mandasor in North Mālwa, and gardens and wells at Govardhana and Sopāra; free ferries across the Ibā or Amlīkā, the Pārāda or Pār, the Damanā or Damanganga, the Tāpi or Tāpti, the Karabenā or Kāveri, and the Dāhānukā or Dāhānu river. Waiting-places and steps were also built on both banks of each of these rivers. These charitable and public works of Ushavadāta savour much of the Brāhmanic religion. The only

Chapter V.

WESTERN  
KSHATRAPAS,  
A.D. 70-300

Ushavadāta,  
A.D. 100-120.

<sup>1</sup> Bom. Gaz. XVI. 571ff.

<sup>2</sup> A well known Sanskrit saying is शत्रुहयातोषमायमः : A man known through his father-in-law is the vilest of the vile.

## Chapter V.

WESTERN  
KSHATRAPAS,  
A.D. 70 - 303.  
Ushavadāta,  
A.D. 100 - 120.

Buddhist charities are the gift of a cave at Nāsik ; of 3000 *kārshāpanas* and eight thousand coconut trees for feeding and clothing monks living in the cave ; and of a village near Kārle in Poona for the support of the monks of the main Kārle cave. Ushavadāta himself thus seems to have been a follower of the Brāhmanical faith. The Buddhist charities were probably made to meet the wishes of his wife whose father's religion the Buddhist wheel and the Bodhi tree on his copper coins prove to have been Buddhism. The large territory over which these charitable and public works of Ushavadata spread gives an idea of the extent of Nahapāna's rule. The gift of a village as far north as Pokhara near Ajmir would have been proof of dominion in those parts were it not for the fact that in the same inscription Ushavadāta mentions his success in assisting some local Kshatriyas. It is doubtful if the northern limits of Nahapāna's dominions extended as far as Pokhar. The village may have been given during a brief conquest, since according to Hindu ideas no village given to Brāhmanas can be resumed. The eastern boundary would seem to have been part of Mālwa and the plain lands of Khandesh Nāsik and Poona ; the southern boundary was somewhere about Bombay ; and the western Kāthiāvāda and the Arabian sea.

Nahapāna's  
Era.

Nahapāna's exact date is hard to fix. Ushavadāta's Nāsik cave Inscriptions X. and XII. give the years 41 and 42 ; and an inscription of Nahapāna's minister Ayāma at Junnar gives the year 46. The era is not mentioned. They are simply dated *vase Sk. varsha* that is in the year. Ushavadāta's Nāsik Inscription XII. records in the year 42 the gift of charities and the construction of public works which must have taken years to complete. If at that time Ushavadāta's age was 40 to 45, Nahapāna who, as Inscription X. shows, was living at that time, must have been some twenty years older than his son-in-law or say about 65. The Junnar inscription of his minister Ayāma which bears date 16 proves that Nahapāna lived several years after the making of Ushavadāta's cave. The bust on one of his coins also shows that Nahapāna attained a ripe old age.

Nahapāna cannot have lived long after the year 46. His death may be fixed about the year 50 of the era to which the three years 41, 42, and 46 belong. He was probably about 75 years old when he died. Deducting 50 from 75 we get about 25 as Nahapāna's age at the beginning of the era to which the years 41, 42, and 46 belong, a suitable age for an able prince with good resources and good advisers to have established a kingdom. It is therefore probable that the era marks Nahapāna's conquest of Gujarāt. As said above, Nahapāna was probably considered to belong to the Śaka tribe, and his son-in-law clearly calls himself a Śaka. It may therefore be supposed that the era started by Nahapāna on his conquest of Gujarāt was at first simply called Varsha ; that it afterwards came to be called Śakavarsha or Sakasamvatsara ; and that finally, after various changes, to suit false current ideas, about the eleventh or twelfth century the people of the Deccan styled it Śālivahana Śaka mixing it with current traditions regarding the great Śātavahana or Śālivahana king of Pāṭiṇā. If, as mentioned above, Nahapāna's conquest of Gujarāt and the establishment of his era be taken to come close after the conquest of Mathurā by

Kanishka, the Gujarāt conquest and the era must come very shortly after the beginning of Kanishka's reign, since Kanishka conquered Mathurā early in his reign. As his Mathurā inscriptions<sup>1</sup> give 5 as Kanishka's earliest date, he must have conquered Mathurā in the year 3 or 4 of his reign. Nahapāna's expedition to and conquest of Gujarāt was probably contemporary with or very closely subsequent to Kanishka's conquest of Mathurā. So two important eras seem to begin about four years apart, the one with Kanishka's reign in Upper India, the other with Nahapāna's reign in Western India. The difference being so small and both being eras of foreign conquerors, a Kushān and a Śaka respectively, the two eras seem to have been subsequently confounded. Thus, according to Dr. Burnell, the Javanese Śaka era is A.D. 74, that is Kanishka's era was introduced into Java, probably because Java has from early times been connected with the eastern parts of India where Kanishka's era was current. On the other hand the astrological works called Karana use the era beginning with A.D. 78 which we have taken to be the Western era started by Nahapāna. The use of the Śaka era in Karana works dates from the time of the great Indian astronomer Varāha Mihira (A.D. 587). As Varāha Mihira lived and wrote his great work in Avanti or Mālwa he naturally made use of the Śaka era of Nahapāna, which was current in Mālwa. Subsequent astronomers adopted the era used by the master Varāha Mihira. Under their influence Nahapāna's A.D. 78 era passed into use over the whole of Northern and Central India eclipsing Kanishka's A.D. 74 era. On these grounds it may be accepted that the dates in the Nāsik inscriptions of Ushavadāta and in Ayāma's inscription at Junnar are in the era founded by Nahapāna on his conquest of Gujarāt and the West Deccan. This era was adopted by the Western Kshatrapa successors of Nahapāna and continued on their coins for nearly three centuries.<sup>2</sup>

<sup>1</sup> Cunningham's Arch. Sur. III. Plate 13. Inscriptions 2 and 3.

<sup>2</sup> The author's only reason for supposing that two eras began between A.D. 70 and 80 seems to be the fact that the Javanese Śaka era begins A.D. 74, while the Indian Śaka era begins A.D. 78. It appears, however, from Lassen's Ind. Alt. II. 1040 note 1, that the Javanese Śaka era begins either in A.D. 74 or in A.D. 78. The author's own authority, Dr. Burnell (S. Ind. Pal. 72) while saying that the Javanese Śaka era dates from A.D. 74, gives A.D. 80 as the epoch of the Śaka era of the neighbouring island of Bali, thus supporting Baffle's explanation (Java, II. 68) that the difference is due to the introduction into Java of the Muhammadan mode of reckoning during the past 300 years. The Javanese epoch of A.D. 74 cannot therefore be treated as an authority for assuming a genuine Indian era with this initial date. The era of Kanishka was used continuously down to its year 281 (Fergusson Hist. of Ind. Architecture, 740) and after that date we have numerous instances of the use of the Śakāmpakāla or Śakakāla down to the familiar Śaka of the present day. It seems much more likely that the parent of the modern Śaka era was that of Kanishka, which remained in use for nearly three centuries, than that of Nahapāna, who so far as we know left no son, and whose era (if he founded one) probably expired when the Kshaharāta power was destroyed by the Andhrabhūtiyas in the first half of the second century A.D. We must therefore assume A.D. 78 to be the epoch of Kanishka's era. There remains the question whether Nahapāna dates by Kanishka's era, or uses his own regnal years. There is nothing improbable in the latter supposition, and we are not forced to suppose that Nahapāna was a feudatory of the Kushan kings. It has been shown above that the use of the title Kshatrapa does not necessarily imply a relation of inferiority. On the other hand (*pace* Oldenburg in Ind. Ant. X. 213) the later Kshatrapas certainly seem to have used Kanishka's era; and Nahapāna and the Kushan dynasty seem to have been of the same race; for Hetaus, who was certainly a Kushan, apparently calls himself Śaka on his coins (Gardner B. M. Cat. xlvii.); and it is highly probable that Nahapāna, like his son-in-law Ushavadāta, was a Śaka. Further, the fact that Nahapāna does not call himself Mahārāja but Rāja goes to show that he was not a paramount sovereign. —(A. M. T. J.)

## Chapter V.

WESTERN  
KSHATRAPAS,  
A.D. 70-300—  
Nahapāna's  
Era.

**Chapter V.**

WESTERN  
KSHATRAPAS,  
A.D. 70-398.  
[The Malava Era,  
I.C. 56.]

The question arises why should not the dates on the Western Kshatrapa coins belong to the era which under the incorrect title of the Vikrama era is now current in Gujarāt and Mālwa. Several recently found Mālwa inscriptions almost prove that what is called the Vikrama era beginning with B.C. 56 was not started by any Vikrama,<sup>1</sup> but marks the institution of the tribal constitution of the Mālavas.<sup>2</sup> Later the era came to be called either the era of the Mālava lords<sup>3</sup> or Mālava Kāla that is the era of the Mālavas. About the ninth century just as the Śaka era became connected with the Śahavāhana of Purāṇa, this old Malava era became connected with the name of Vikramaditya, the great legendary king of Ujjain.

It might be supposed that the Mālavas who gave its name to the Malava era were the kings of the country now called Mālwa. But it is to be noted that no reference to the present Malwa under the name of Malayadesa occurs in any Sanskrit work or record earlier than the second century A.D. (Ch. I). The original Sanskrit name of the country was Avanti. It came to be called Malava from the time the Malava tribe conquered it and settled in it, just as Kāthiavāda and Mevāda came to be called after their Kāthi and Meva or Meda conquerors. The Mālavas, also called Malāvas,<sup>4</sup> seem like the Medas to be a foreign tribe, which, passing through Upper India conquered and settled in Central India during the first century before Christ. The mention in the *Andhraksha* of a Malava king among five Upper Indian kings shows that in the time of the Mauryas (B.C. 300) a Mālava kingdom existed in Upper India which after the decline of Maurya supremacy spread to Central India. By Nahapāna's time the Mālavas seem to have moved eastwards towards Jaipur, as Ushayadāta defeated them in the neighbourhood of the Pushkar lake; but the fact that the country round Ujjain was still known to Rudradaman as Avanti, shows that the Mālavas had not yet (A.D. 150) entered the district now known as Mālwa. This settlement and the change of name from Avanti to Malava probably took place in the weakness of the Kshatrapas towards the end of the third century A.D. When they established their sway in Central India these Malavas or Malavas like the ancient Yaudheyas (B.C. 100) and the Kathis till recent times (A.D. 1818) seem to have had a democratic constitution.<sup>5</sup> Their political system seems to have proved unsuited to the conditions of a settled community. To put an end to dissensions the Malava tribe appears to have framed what the Mamlasor inscription terms a *sthati* or constitution in honour of which they began a new era.<sup>6</sup> It may be asked, Why may not Nahapāna have been the head of the Mālavas who under the new constitution became the first Mālava sovereign and his reign-dates be those of

<sup>1</sup> Journ. B. B. R. A. S. XVI. 378. Ind. Ant. XV. 198, 201, XIII. 126; Arch. Sur. X. 33.

<sup>2</sup> Cunningham's Arch. Sur. XIII. 162. Cf. Kielhorn in Ind. Ant. XIX. 200f.

<sup>3</sup> Cunningham's Arch. Sur. X. 33-34. Numerous Western India inscriptions prove that *ga* and *ka* are often intermixed in Prakrit.

<sup>4</sup> Vide T. Telang's *Madh. Prakasha*, 201. Mr. Telang gives several readings the best of which is *ga* rather the king of the Mālava country or the king of the Malva tribe.

<sup>5</sup> Macauland (1818) notices the democratic constitution of the Kathis. Trans. Bom. Lit. Soc. I. 274.

<sup>6</sup> Compare *Malet's Corpus Ins. Ind.* III. 87, 152, 158 from the (supremacy of) the tribal constitution of the Mālavas. Prof. Kielhorn has however shown that the words of the inscription do not necessarily mean this. Ind. Ant. XIX. 56.

the new Málava era? Against this we know from a Násik inscription of Ushavadáta<sup>1</sup> that Nahapána was not a Málava himself but an opponent of the Málavas as he sent Ushavadáta to help a tribe of Kshatriyas called Uttamabhadras whom the Málavas had attacked. Further a chronological examination of the early ruling dynasties of Gujarat does not favour the identification of the Kshatrapa era with the Málava era. The available information regarding the three dynasties the Kshatrapas the Guptas and the Valabhis, is universally admitted to prove that they followed one another in chronological succession. The latest known Kshatrapa date is 320. Even after this we find the name of a later Kshatrapa king whose date is unknown but may be estimated at about 320. If we take this Kshatrapa 320 to be in the Vikrama Samvat, its equivalent is A.D. 261. In consequence of several new discoveries the epoch of the Gupta era has been finally settled to be A.D. 319. It is further settled that the first Gupta conqueror of Malwa and Gujarat was Chandragupta II.<sup>2</sup> the date of his conquest of Malwa being Gupta 80 (A.D. 399). Counting the Kshatrapa dates in the Samvat era this gives a blank of  $(399 - 261 =)$  138 years between the latest Kshatrapa date and the date of Chandragupta's conquest of Gujarat to fill which we have absolutely no historical information. On the other hand in support of the view that the Kshatrapa era is the Saka era the Káthavada coins of the Gupta king Kumaragupta son of Chandragupta dated 100 Gupta closely resemble the coins of the latest Kshatrapa kings, the workmanship proving that the two styles of coin are close in point of time. Thus taking the Kshatrapa era to be the Saka era the latest Kshatrapa date is  $320 + 78 =$  A.D. 398, which is just the date (A.D. 399) of Chandragupta's conquest of Málwa and Gujarát. For these reasons, and in the absence of reasons to the contrary, it seems proper to take the dates in Ushavadata's and Ayóma's inscriptions as in the era which began with Nahapána's conquest of Gujarát, namely the Saka era whose initial date is A.D. 78.

After Nahapána's the earliest coins found in Gujarát are those of Chashtana. Chashtana's coins are an adaptation of Nahapána's coins. At the same time Chashtana's bust differs from the bust in Nahapána's coins. He wears a moustache the cap is not grooved but plain, and the hair which reaches to the neck is longer than Nahapána's hair. In one of Chashtana's coins found by Mr. Justice Newton, the hair seems dressed in ringlets as in the coins of the Parthian king Phraates II. (B.C. 136 - 129).<sup>3</sup> On the reverse instead of the thunderbolt and arrow as in Nahapána's coins, Chashtana's coins have symbols of the sun and moon in style much like the sun and moon symbols on the Parthian coins of Phraates II., the moon being a crescent and the sun represented by eleven rays shooting from a central beam. To the two on the reverse a third symbol seems to have been added consisting of two arches resting on a straight line, with a third arch over and between

## Chapter V.

WESTERN  
KSHATRAPAS,  
A.D. 70 - 398.

The Málava Era,  
B.C. 56.

Kshatrapa II.  
Chashtana,  
A.D. 130.

<sup>1</sup> Inscription 10 lines 3-4. Bom. Gaz. XVI. 572.

<sup>2</sup> Details are given below under the Guptas.

<sup>3</sup> Burgess' Archaeological Report of Kathiáwar and Cutch, 55, Numismata Orientalia, I. Pl. II. Fig. 8.

## Chapter V.

WESTERN  
KSHATRAPAS,  
A.D. 70-393.  
Chashtana's  
Coins,  
A.D. 130.

the two arches, and over the third arch an inverted semicircle. Below these symbols stretches a waving or serpentine line.<sup>1</sup>

The same symbol appears on the obverse of several very old medium-sized square copper coins found in Upper India. These coins Dr. Bhagvanlāl took to be coins of Aśoka. They have no legend on either side, and have a standing elephant on the obverse and a rampant lion on the reverse. As these are the symbols of Aśoka, the elephant being found in his rock inscriptions and the lion in his pillar inscriptions, Dr. Bhagvanlāl held them to be coins of Aśoka. The arch symbol appears in these coins over the elephant on the obverse and near the lion on the reverse but in neither case with the underlying zigzag line.<sup>2</sup> So also a contemporary coin bearing in the Aśoka character the clear legend वटस्र्वक Vatasvaka shows the same symbol, with in addition a robed male figure of good design standing near the symbol saluting it with folded hands. The position of the figure (Ariana Antiqua, Plate XV. Fig. 30) proves that the symbol was an object of worship. In Chashtana's coins we find this symbol between the sun and the moon, a position which suggests that the symbol represents the mythical mountain Meru, the three semicircular superimposed arches representing the peaks of the mountain and the crescent a *Siddha-sithi* or Siddhas' seat, which Jaina works describe as crescent-shaped and situated over Meru. The collective idea of this symbol in the middle and the sun and moon on either side recalls the following śloka :

यावद्वीचीनरङ्गान्वहति सुरजदी जान्दवी पूर्णतोया ।

यावच्चाकाशमार्गे तपनि दिनकरो भास्करो लोकपाल :

यावद्वज्रेन्दुनीलस्फटिकमणिशिला वर्तते मेरुशृङ्गे ।

तावत्त्वं पुत्रपौत्रैः स्वजनपरिवृतो जीव शम्भो : प्रसादात् ॥

Mayest thou by the favour of Śambhu live surrounded by sons grandsons and relations so long as the heavenly Ganges full of water flows with its waves, so long as the brilliant sun the protector of the universe shines in the sky, and so long as the shih of diamond moonstone lapis lazuli and sapphire remains on the top of Meru.

Dr. Bird's Kanheri copperplate has a verse with a similar meaning regarding the continuance of the glory of the relic shrine of one Pushya, so long as Meru remains and rivers and the sea flow.<sup>3</sup> The meaning of showing Meru and the sun and moon is thus clear. The underlying serpentine line apparently stands for the Jāhnavī river or it may perhaps be a representation of the sea.<sup>4</sup> The object of repre-

<sup>1</sup> The meaning of this symbol has not yet been made out. It is very old. We first find it on the punched coins of Mālwa and Gujarāt (regarded as the old coinage in India) without the serpentine line below, which seems to show that this line does not form part of the original symbol and has a distinct meaning.

<sup>2</sup> Compare Wilson's Ariana Antiqua, Plate XV Fig. 26-27.

<sup>3</sup> Cave Temple Inscriptions, Bombay Archaeological Survey, Extra Number (1881), 58.

<sup>4</sup> Ariana Antiqua, Plate XV. Fig. 29. Some imaginary animals are shown under the serpentine line.

sending these symbols on coins may be that the coins may last as long as the sun, the moon, mount Meru, and the Ganges or ocean. Against this view it may be urged that the coins of the Buddhist kings of Kuninda (A.D. 100), largely found near Saharanpur in the North-West Provinces, show the arch symbol with the Buddhist trident over it, the Bodhi tree with the railing by its side, and the serpentine line under both the tree and the symbol, the apparent meaning being that the symbol is a Buddhist shrine with the Bodhi tree and the river Niranjana of Buddha Gaya near it. The same symbol appears as a Buddhist shrine in Andhra coins<sup>1</sup> which make it larger with four rows of arches, a tree by its side, and instead of the zigzag base line a railing. This seems a different representation perhaps of the shrine of Mahabodhi at Buddha Gaya. These details seem to show that popular notions regarding the meaning of this symbol varied at different times.<sup>2</sup>

Such of the coins of Chashtana as have on the reverse only the sun and the moon bear on the obverse in Baktro-Pali characters a legend of which the four letters रजो जिमो Raño jimo can alone be made out. An illegible Greek legend continues the Baktro-Pali legend. The legend on the reverse is in old Nagari character :

राज्ञो क्षत्रपस यमोतिकपुत्र [सच] टनस.<sup>3</sup>

Rājño Kshatrapasa Ysamotikaputra(sa Cha)-ṣṭanasa.

Of the king Kshatrapa Chashtana son of Ysamotika.

The variety of Chashtana's coins which has the arch symbol on the reverse, bears on the obverse only the Greek legend almost illegible and on the reverse the Baktro-Pali legend चटनस Chaṭanasa meaning Of Chashtana and in continuation the Nagari legend :

राज्ञोमहाक्षत्रपस यमोतिकपुत्रस चटनस

Rājño Mahākshatrapasa Ysamotikaputrasa Chashtanasa.

Of the king the great Kshatrapa Chashtana son of Ysamotika.

The name Zamotika is certainly not Indian but foreign apparently a corruption of some such form as Psamotika or Xamotika. Further the fact that Zamotika is not called Kshatrapa or by any other title, would seem to show that he was an untitled man whose son somehow came to authority and obtained victory over these parts where (as his earlier coins with the sun and the moon show) he was at first called a Kshatrapa and afterwards (as his later coins with the third symbol show) a Mahākshatrapa or great Kshatrapa. We know nothing of any connection between Nahapána and Chashtana. Still it is clear that Chashtana obtained a great part of the territory over which

### Chapter V.

WESTERN  
KSHATRAPAS,  
A.D. 70-390.  
Chashtana's  
Coins,  
A.D. 130.

Chashtana's  
Father.

<sup>1</sup> Jour. B. B. A. Soc. XIII. 303.

<sup>2</sup> The variations noted in the text seem examples of the law that the later religion reads its own new meaning into early luck signs.

<sup>3</sup> This letter टस in both is curiously formed and never used in Sanskrit. But it is clear and can be read without any doubt as टस. Paulit Bhagvanlal thought that it was probably meant to stand as a new-coined letter to represent the Greek Z which has nothing corresponding to it in Sanskrit. The same curiously formed letter appears in the third syllable in the coin of the fourth Kshatrapa king Damajadastri.

## Chapter V.

WESTERN  
KSHATRAPAS,  
c. 70-398.  
Chashtana,  
A.D. 130.

Nahapána previously held sway. Though Chashtana's coins and even the coins of his son and grandson bear no date, we have reason to believe they used a nameless era, of which the year 72 is given in the Junágad inscription of Chashtana's grandson Rudradáman.<sup>1</sup> Though we have no means of ascertaining how many years Rudradáman had reigned before this 72 it seems probable that the beginning of the reign was at least several years earlier. Taking the previous period at seven years Rudráman's succession may be tentatively fixed at 65. Allowing twenty-five years for his father Jayadáman and his grandfather Chashtana (as they were father and son and the son it is supposed reigned for some years with his father<sup>2</sup>) Chashtana's conquest of Gujarať comes to about the year 40 which makes Chashtana contemporary with the latter part of Nahapána's life. Now the Turanæ whom Ptolemy mentions as having Ozene for his capital<sup>3</sup> is on all hands admitted to be Chashtana and from what Ptolemy says it appears certain that his capital was Ujjain. Two of Chashtana's coins occur as far north as Ajmir. As the Chashtana coins in Dr. Gerson DuCunha's collection were found in Káthiáwáda he must have ruled a large stretch of country. The fact that in his earlier coins Chashtana is simply called a Kshatrapa and in his latter coins a Mahikshatrapa leads to the inference that his power was originally small. Chashtana was probably not subordinate to Nahapána but a contemporary of Nahapána originally when a simple Kshatrapa governing perhaps North Gujarať and Malwa. Nor was Chashtana a member of Nahapána's family as he is nowhere called Kshaharata which is the name of Nahapána's family. During the lifetime of Nahapána Chashtana's power would seem to have been established first over Ajmir and Mewar. Perhaps Chashtana may have been the chief of the Uttamabhadra Kshatriyas, whom, in the year 42, Ushavadata went to assist when they were besieged by the Malavas or Málavyas<sup>4</sup>; and it is possible that the Malavas being thus driven away Chashtana may have consolidated his power, taken possession of Malwa, and established his capital at Ujjain.

Deccan Recovered  
by the Andhras,  
A.D. 138.

On Nahapána's death his territory, which in the absence of a son had probably passed to his son-in-law Ushavadata, seems to have been wrested from him by his Andhra neighbours, as one of the attributes of Gautamiputra Satakarni is exterminator of the dynasty of Kshaharata (or Kshaharata). That North Konkan, South Gujarať, and Káthiáwáda were taken and incorporated with Andhra territory appears from Gautamiputra's Nasik inscription (No. 26) where Suráshtra and Aparanta are mentioned as parts of his dominions. These Andhra

<sup>1</sup> The text of the inscription is रुद्रदाम्नो वर्षे that is in the year of Rudradaman. That this phrase means 'in the reign of' is shown by the Gunda inscription of Rudradaman's son Rudrasimha, which has रुद्रसिंहस्य वर्षे त्र्युत्तरशते that is in the hundred and third year of Rudrasimha. Clearly a regnal year cannot be meant as no reign could last over 103 years. So with the year 72 in Rudradaman's inscription. The same style of writing appears in the inscriptions at Mathura of Huvishka and Vasudeva which say 'year — of Huvishka' and 'year — of Vasudeva' though it is known that the era is of Kanishka. In all these cases what is meant is 'the dynastic or era year — in the reign of —'.

<sup>2</sup> See below page 34.

<sup>3</sup> McCrindle's Ptolemy, 155.

<sup>4</sup> See above page 29.

conquests seem to have been shortlived. Chashtana appears to have eventually taken Káthiávāda and as much of South Gujarāt as belonged to Nahapána probably as far south as the Nimbada. Mevād, Malwa, North and South Gujarāt and Káthiavāda would then be subject to him and justify the title Mahākshatrapa on his later coins.

The bulk of Chashtana's army seems to have consisted of the Mevas or Medas from whose early conquests and settlements in Central Rajputāna the province seems to have received its present name Mevāda. If this supposition be correct an inference may be drawn regarding the origin of Chashtana. The Mathura inscription of Nandasirikā, daughter of Kshatrapa Rajavula and mother of Kharanosti Yuvarāja, mentions with respect a Mahakshatrapi Kuzulko Patika who is called in the inscription Mevaki that is of the Meva tribe. The inscription shows a relation between the Kharanostis (to which tribe we have taken Kshaharāta Nahapána to belong) and Mevaki Patika perhaps in the nature of subordinate and overlord. It proves at least that the Kharanostis held Patika in great honour and respect.

The Taxila plate shows that Patika was governor of Taxila during his father's lifetime. After his father's death when he became Mahakshatrapa, Patika's capital was Nagaraka in the Jallalābād or Kabul valley. The conquest of those parts by the great Kushān or Indo-Skythian king Kanishka (A.D. 78) seems to have driven Patika's immediate successors southwards to Sindh where they may have established a kingdom. The Skythian kingdom mentioned by the author of the Periplus as stretching in his time as far south as the mouth of the Indus may be a relic of this kingdom. Some time after their establishment in Sindh Patika's successors may have sent Chashtana, either a younger member of the reigning house or a military officer, with an army of Mevas through Umarkot and the Great Ran to Central Rajputāna, an expedition which ended in the settlement of the Mevas and the change of the country's name to Mevāda. Probably it was on account of their previous ancestral connection that Nahapána sent Ushavadata to help Chashtana in Mevāda when besieged by his Málava neighbours. That Ushavadata went to bathe and make gifts<sup>1</sup> at Pushkara proves that the scene of the Uttanabhadras' siege by the Málavas was in Mevāda not far from Pushkara.

Chashtana is followed by an unbroken chain of successors all of the dynasty of which Chashtana was the founder. As the coins of Chashtana's successors bear dates and as each coin gives the name of the king and of his father they supply a complete chronological list of the Kshatrapa dynasty.

Of Chashtana's son and successor Jayadāman the coins are rare. Of three specimens found in Káthiávāda two are of silver and one of copper. Both the silver coins were found in Jnnāgradh<sup>2</sup> but they are doubtful specimens as the legend is not complete. Like Chashtana's

### Chapter V.

WESTERN  
KSHATRAPAS,  
A.D. 70-300.

The Mevas or  
Medas.

Kshatrapa III  
Jayadaman,  
A.D. 140-143.

<sup>1</sup> See above page 25.

<sup>2</sup> Of these coins Dr. Bhagvānlāl kept one in his own collection. He sent the other to General Cunningham. The Pandit found the copper coin in Amreli in 1863 and gave it to Dr. Bhaui Diji.

**Chapter V.**

WESTERN  
KSHATRAPAS,  
A.D. 70-398.

Kshatrapa III.  
Jayadaman,  
A.D. 140-143.

coins they have a bust on the obverse and round the bust an incomplete and indecipherable Greek legend. The reverse has the sun and the moon and between them the arched symbol with the zigzag under-line. All round the symbols on the margin within a dotted line is the legend in Baktro-Pali and Devanagari. Only three letters रञ्जो छ ञ of the Baktro-Pali legend can be made out. Of the Nagari legend seven letters राज्ञा क्षत्रपस ज्ञ Jayān Kshatrapasa Ja can be made out. The remaining four letters Dr. Bhagvanlal read यदासस Yādāmasa.<sup>1</sup> The copper coin which is very small and square has on the obverse in a circle a standing limped bull looking to the right and fronting an erect trident with an axe. In style the bull is much like the bull on the square hemichalcus of Apollodotus (no. 110-100). Round the bull within a dotted circle is the legend in Greek. It is unfortunate the legend is incomplete as the remaining letters which are in the Skythian-Greek style are clearer than the letters on any Kshatrapa coin hitherto found. The letters that are preserved are στρυξ. The reverse has the usual moon and sun and between them the arched symbol without the zigzag under-line. All round within a dotted circle is the Nagari legend:

राज्ञो क्षत्रपस] जयदामस.

Rājño Kshatrapasa Jayadamas.

On the king Kshatrapa Jayadaman.

Though the name is not given in any of these coins, the fact that Chashtana was Jayadaman's father has been determined from the genealogy in the Girda inscription of Rudrasinha I the seventh Kshatrapa, in the Jashdan inscription of Rudrasena I, the eighth Kshatrapa,<sup>2</sup> and in the Junágadh cave inscription<sup>3</sup> of Rudradaman's son Rudrasinha. All these inscriptions and the coins of his son Rudradaman call Jayadaman Kshatrapa not Mahakshatrapa. This would seem to show either that he was a Kshatrapa or governor of Kathiavada under his father or that his father's territory and his rank as Mahakshatrapa suffered some reduction.<sup>4</sup> The extreme rarity of his coins suggests that Jayadaman's reign was very short. It is worthy of note that while Zamotila and Chashtana are foreign names, the names of Jayadaman and all his successors with one exception<sup>5</sup> are purely Indian.

Kshatrapa IV.  
Rudradaman,  
A.D. 143-150.

Jayadaman was succeeded by his son Rudradaman who was probably the greatest of the Western Kshatrapas. His beautiful silver coins, in style much like those of Chashtana, are frequently found in Kathiavada. On the obverse is his bust in the same style of dress as Chashtana's and

<sup>1</sup> Except that the ञ is much like the Nagari legend in the silver coin obtained for General Cunningham is equally bad, and the Baktro-Pali legend is wanting.

<sup>2</sup> Ind. Ant. X. 157.

<sup>3</sup> Journ. B. B. R. A. Soc. VIII. 231-5 and Ind. Ant. XII. 320.

<sup>4</sup> Dr. Burgess' Archaeological Report of Kathiawar and Cutch, 140.

<sup>5</sup> The explanation of the reduction of Jayadaman's rank is probably to be found in the Nasik Inscription (No. 26) of Guttamuputra Satkarni who claims to have conquered Surashtra, Kikura (or Rappurra), Anupa, Vidarbha (Berar), Akara, and Avantī (Ujain). (A. M. T. J.)

<sup>6</sup> See below page 39.

round the bust is the Greek legend incomplete and un decipherable. The reverse has the usual sun and moon and the archer symbol with the zigzag under-line. The old Nagari legend fills the whole outer circle. None of Rudradaman's coins shows a trace of the Bakto-Pali legend. The Nagari legend reads :

राज्ञा क्षत्रपस जयदामपुत्रस राज्ञा महाक्षत्रपस रुद्रदामस.

Rājña Kshatripa a Jayadamaṇḍitaśa  
Rājña Mahakshatripaśa Rudradamaśa.

Of the king the great Kshatripa Rudradaman son of the  
king the Kshatripa Jayadaman

None of Rudradaman's copper coins have been found. Except Jayadaman none of the Kshatrapas seem to have stamped their names on any but silver coins.

An inscription on the Gurnār rock gives us more information regarding Rudradaman than is available for any of the other Kshatrapas. The inscription records the construction of a new dam on the SudarSana lake close to the inscription rock in place of a dam built up the time of the Maurya king Chaṇḍragupta (B.C. 300) and added to in the time of his grandson the great Aśoka (B.C. 240) which had suddenly burst in a storm. The new dam is recorded to have been made under the orders of Svayashkha son of Kulapa a Pahlava by tribe, who was 'appointed by the king to protect the whole of Anarta and Surashtre.' Pahlava seems to be the name of the ancient Persians and Parthians and the name Svayashkha as Dr. Bhau Daji suggests may be a Sanskritised form of Soyaxa. One of the Kharle inscriptions gives a similar name Soyaxa apparently a corrupt Indian form of the original Persian from which the Sanskritised Svayashkha must have been formed. Soyaxa it will be noted is mentioned in the Kharle inscription as an subordinate of Abulanti, apparently the old trade mart of Ohollah at the head of the Persian Gulf. This trade connection between the Persian Gulf and the Western Indian seaboard must have led to the settlement from very early times of the Pahlavas who gradually became converted to Buddhism, and, like the Parsis their modern enterprising representatives, seem to have advanced in trade and political influence. Subsequently the Pahlavas attained such a pre-eminence that about the fifth century a dynasty of Pahlava kings reigned in the Dekhan, Hindu in religion and name, even tracing their origin to the great ancient sage Bhṛagyaṇi.<sup>1</sup>

The statement in Rudradaman's SudarSana lake inscription, that Anarta and Surashtre were under his Pahlava governor, seems to show

## Chapter V.

WESTERN  
KSHATRAPAS,  
A.D. 70-300,  
Kshatripa IV.  
Rudradaman,  
A.D. 143-158.

SudarSana Lake,  
A.D. 150.

<sup>1</sup> Several small mixed metal coins weighing from 3 to 10 grains with on the obverse an elephant in some and a bull in others and on the reverse the usual archer Kshatripa symbol have been found in Malwa and Kathiavada. The symbols show them to be of the lowest Kshatripa currency. Several of them bear dates from which it is possible as in the case of Rudrasinha's and Rudrasana's coins to infer to what Kshatripa they belonged. Lead coins have also been found at Anur in Kathiavada. They are square and have a bull on the obverse and on the reverse the usual archer Kshatripa symbol with underneath it the date 182.

<sup>2</sup> Compare however Weber, Hist. of Indian Lit. 187-8.

<sup>3</sup> Jour. B. B. R. A. S. VII, 114.

<sup>4</sup> Ind. Ant. II. 156, V. 50, 154 &c.

## Chapter V.

WESTERN  
KSHATRAPAS,  
A.D. 70-398.

Kshatrapa IV.  
Rudradaman,  
A.D. 143-158.

that Rudradaman's capital was not in Gujara't or Kāthiāvāda. Probably like his grandfather Chastana Rudradaman held his capital at Ujjain. The poetic eulogies of Rudradaman appear to contain a certain share of fact. One of the epithets 'he who himself has earned the title Mahakshatrapa' indicates that Rudradaman had regained the title of Mahakshatrapa which belonged to his grandfather Chastana but not to his father Javadaman. Another portion of the inscription claims for him the overlordship of Akarāvanti,<sup>1</sup> Anūpa,<sup>2</sup> Amrta, Surashtra, Svahra,<sup>3</sup> Mava,<sup>4</sup> Kachchha,<sup>5</sup> Sindhu-Sauvira,<sup>6</sup> Kukura,<sup>7</sup> Aparanta,<sup>8</sup> and Nishada;<sup>9</sup> that is roughly the country from Bhilsa in the east to Sindh in the west and from about Abu in the north to the North Konkan in the south including the peninsulas of Cutch and Kāthiāvada. The inscription also mentions two wars waged by Rudradaman, one with the Yaudheyas the other with Satakarni lord of Dakshinapatha. Of the Yaudheyas the inscription says that they had become arrogant and untractable in consequence of their having proclaimed their assumption of the title of Heroes among all Kshatriyas. Rudradaman is described as having exterminated them. These Yaudheyas were known as a warlike race from the earliest times and are mentioned as warriors by Panini.<sup>10</sup>

The Yaudheyas.

Like the Malavas these Yaudheyas appear to have had a democratic constitution. Several round copper coins of the Yaudheyas of about the third century A.D. have been found in various parts of the North-West Provinces from Mathura to Sahāranpur. These coins

<sup>1</sup> Akarāvanti that is Akara and Avanti are two names which are always found together. Cf. Gāndhāriya N. S. inscription (No. 26). Avanti is well known as being the name of the part of Malva which contains Ujjain. Akara is probably the modern province of Bilāsa whose capital was Vidisa the modern deserted city of Besnagar. Instead of Akarāvanti Bhāti-samhita mentions Akaravavantaka of which the third name Vena Pāda Bhāgyavāda took to be the country about the Sagarā zila containing the old town of Lāva, near which still flows a river called Vena. The adjectives east and west are used respectively as referring to Akara which is East Malva and Avanti which is West Malva. Compare Indian Antiquary, VII. 259; Bombay Gazetteer, XVI. 631.

<sup>2</sup> Anūpa is a common noun literally meaning well-watered. The absence of the term *ulad* or 'country' which is in general superadded to it shows that Anūpa is here used as a proper noun, meaning the Anūpa country. Dr. Bhāgyavāda was unable to identify Anūpa. He took it to be the name of some well-watered tract near Gujara't.

<sup>3</sup> See above page 10 note 1. The greater part of North Gujara't was probably included in Svahra.

<sup>4</sup> Mava is the well known name of Marwar.

<sup>5</sup> Kachchha is the flourishing state still known by the name of Cutch.

<sup>6</sup> Sindhu Sauvira like Akarāvanti, are two names usually found together. Sindhu is the modern Sindh and Sauvira may have been part of Upper Sind, the capital of which is mentioned as Dattamitra. Alberuni (I. 300) defines Sauvira as including Multan and Jhārawar.

<sup>7</sup> Nothing is known about Kukura and it cannot be identified. It was probably part of East Rajputana.

<sup>8</sup> Aparanta meaning the Western End is the western seaboard from the Mahi in the north to Goa in the south. Ind. Ant. VII. 259. The portion of Aparanta actually subject to Rudradaman must have been the country between the Mahi and the Damanganga as at this time the North Konkan was subject to the Andhras.

<sup>9</sup> Nishada cannot be identified. As the term Nishada is generally used to mean Bhils and other wild tribes, its mention with Aparanta suggests the wild country that includes Bilāsa, Sahāranpur, and north-east Thāna.

<sup>10</sup> Grammar, V. iii. 117.

which are adapted from the type of Kanishka's coins<sup>1</sup> have on the obverse a standing robed male figure extending the protecting right hand of mercy. On the reverse is the figure of a standing Kārtika-svami and round the figure the legend in Gupta characters of about the third century :

योधेय गणस्य

Yāudheya Gaṇasya.

Of the Yaudheya tribe.<sup>2</sup>

That the Gīrnār inscription describes Rudradāman as the exterminator of 'the Yaudheyas' and not of any king of the Yaudheyas confirms the view that their constitution was tribal or democratic.<sup>3</sup>

The style of the Yaudheya coins being an adaptation of the Kanishka type and their being found from Mathura to Sahasrāpur where Kanishka ruled is a proof that the Yaudheyas wrested from the successors of Kanishka the greater part of the North-West Provinces. This is not to be understood to be the Yaudheyas' first conquest in India. They are known to be a very old tribe who after a temporary suppression by Kanishka must have again risen to power with the decline of Kushan rule under Kanishka's successors Huviska (A.D. 100-123) or Vasudeva (A.D. 123-150), the latter of whom was a contemporary of Rudradāman.<sup>4</sup> It is probably to this increase of Yaudheya power that Rudradāman's inscription refers as making them arrogant and intractable. Their forcible extermination is not to be understood literally but in the Indian hyperbolic fashion.

The remark regarding the conquest of Sātakarni lord of Dakṣiṇā-patha is as follows: 'He who has obtained glory because he did not destroy Satakarni, the lord of the Dekhan, on account of there being no distance in relationship, though he twice really conquered him.'<sup>5</sup> As Sātakarni is a dynastic name applied to several of the Andhra kings, the question arises Which of the Satakarnis did Rudradāman twice defeat? Of the two Western India kings mentioned by Ptolemy one Triastanes with his capital at Ozene or Ujjain<sup>6</sup> has been identified with Chashtana; the other Siri Ptolemaios or Polemaios, with his royal seat at Baithana or Paithan,<sup>7</sup> has been identified with the Pulmāyi Vāsishṭhiputra of the Nāsi cave inscriptions. These statements of

<sup>1</sup> Compare Gardner and Poole's Catalogue, Pl. XXVI, Fig. 2 &c.

<sup>2</sup> Another variety of their brass coins was found at Belat near Sahasrāpur. Compare Thomas' Prinsep's Indian Antiquities, I. Pl. IV, Figs. 11a, 12a and Pl. XIX, Figs. 5, 6, 9. General Cunningham, in his recent work on The Coins of Ancient India, 75ff., describes three chief types, the Belat coins being the earliest and belonging to the first century B.C., the second type which is that described above is assigned to about A.D. 300, and the third type, with a six-headed figure on the obverse, is placed a little later. General Cunningham's identification of the Yaudheyas with the Jōhiya Rājputs of the lower Satlej, seems certain, Rudradāman would then have "uprooted" them when he acquired the province of Sauvira.

<sup>3</sup> Mr Fleet notices a later inscription of a *Mahādāja Mahāsandpati* "who has been set over" the 'Yaudheya gṇa or tribe' in the fort of Byasa in Bharatpur. Ind. Ant. XIV. 8, Corp. Insc. Ind. III. 251ff. The Yaudheyas are also named among the tribes which submitted to Samudraguṇḍa. See Corp. Insc. Ind. III. 8.

<sup>4</sup> Huviska's latest inscription bears date 45 that is A.D. 123 (Cunningham's Arch. Sur. III. Pl. XV. Number 8).

<sup>5</sup> Ind. Ant. VII. 262.

<sup>6</sup> McCrindle's Ptolemy, 152.

<sup>7</sup> McCrindle's Ptolemy, 175.

**Chapter V.**

WESTERN  
KSHATRAPAS,  
A.D. 70-398.  
Kshatrapa IV.  
Rudradaman,  
A.D. 143-158.

Ptolemy seem to imply that Chashtana and Puhmāyi were contemporary kings reigning at Ujjain and Paithan. The evidence of their coins also shows that if not contemporaries Chashtana and Puhmāyi were not separated by any long interval. We know from the Nasik inscriptions and the Puranas that Puhmāyi was the successor of Gautamīputra Satakarni and as Gautamīputra Satakarni is mentioned as the exterminator of the Kshaharata race (and the period of this extermination has already been shown to be almost immediately after Nahapana's death), there is no objection to the view that Chashtana, who was the next Kshatrapa after Nahapana, and Puhmāyi, who was the successor of Gautamīputra, were contemporaries. We have no positive evidence to determine who was the immediate successor of Puhmāyi, but the only king whose inscriptions are found in any number after Puhmāyi is Gautamīputra Yajña Sri Satakarni. His Kanheri inscription recording gifts made in his reign and his coin found among the relics of the Sopara stūpa built also in his reign prove that he held the North Konkan. The Sopara coin gives the name of the father of Yajñasri. Unfortunately the coin is much worn. Still the remains of the letters constituting the name are sufficient to show they must be read चतुरपान<sup>1</sup> Chaturapana. A king named Chaturapana is mentioned in one of the Nanaghat inscriptions where like Puhmāyi he is called Vasishthīputra and where the year 13 of his reign is referred to. The letters of this inscription are almost coeval with those in Puhmāyi's inscriptions. The facts that he was called Vasishthīputra and that he reigned at least thirteen years make it probable that Chaturapana was the brother and successor of Puhmāyi. Yajñasri would thus be the nephew and second in succession to Puhmāyi and the contemporary of Rudradaman the grandson of Chashtana, whom we have taken to be a contemporary of Puhmāyi. A further proof of this is afforded by Yajñasri's silver coin found in the Sopara stūpa. All other Andhra coins hitherto found are adapted from contemporary coins of Ujjain and the Central Provinces, the latter probably of the Sungas. But Gautamīputra Yajñasri Satakarni's Sopara coin is the first silver coin struck on the type of Kshatrapa coins; it is in fact a clean adaptation of the type of the coins of Rudradaman himself which proves that the two kings were contemporaries and rivals. An idea of the 'not distant relationship' between Rudradaman and Yajñasri Satakarni mentioned in Rudradaman's Gumar inscription, may be formed from a Kanheri inscription recording a gift by a minister named Sateraka which mentions that the queen of Vasishthīputra Satakarni was born in the Kārdamaka dynasty and was connected apparently on the maternal side with a Mahākshatrapa whose name is lost. If the proper name of the lost Vasishthīputra be Chaturapana, his son Yajñasri Satakarni would, through his mother being a Mahākshatrapa's granddaughter, be a relative of Rudradaman.

Rudradaman's other epithets seem to belong to the usual stock of

<sup>1</sup> Jour B B R A Soc. XV 306.

<sup>2</sup> Jour B B R A Soc. XV 313, 314. See also Ind Ant XII 272, where Bühler suggests that the queen was a daughter of Rudradaman, and traces the syllables Rudradā in the Kanheri inscription.

Indian court epithets. He is said 'to have gained great fame by studying to the end, by remembering understanding and applying the great sciences such as grammar, polity, music, and logic.' Another epithet describes him as having 'obtained numerous garlands at the Svayamvaras of kings' daughters,' apparently meaning that he was chosen as husband by princesses at several *svayamvaras* or choice-marrriages a practice which seems to have been still in vogue in Rudradāman's time. As a test of the civilized character of his rule it may be noted that he is described as 'he who took, and kept to the end of his life, the vow to stop killing men except in battle.' Another epithet tells us that the embankment was built and the lake reconstructed by 'expending a great amount of money from his own treasury, without oppressing the people of the town and of the pargana by (extracting) taxes, forced labour, acts of affection (beneficence) and the like.'

As the Kshatriya year 30 (A.D. 143) has been taken to be the date of close of Chastana's reign, and as five years may be allowed for the short reign<sup>1</sup> of Jivadaman, the beginning of the reign of Rudradāman may be supposed to have been about the year 63 (A.D. 143). This Gumar inscription gives 72 as the year in which Rudradāman was then reigning and it is fair to suppose that he reigned probably up to 80. The conclusion is that Rudradāman ruled from A.D. 143 to 158.

Rudradāman was succeeded by his son Dāmāzāda or Dāmājadaśrī regarding whom all the information available is obtained from six coins obtained by Dr. Bhagvanlal. The workmanship of all six coins is good, after the type of Rudradāman's coins. On the obverse is a bust in the same style as Rudradāman's and round the bust is an illegible Greek legend. Like Rudradāman's coins these have recuttes, a proof of their antiquity, as all later Kshatriya coins have dates in Nagari numerals. The reverse has the usual sun and moon and between them the arched symbol with the zigzag under-line. Around them in three specimens is the following legend in old Nagari:

राज्ञी महाक्षत्रपस रुद्रदामपुत्रस रज्ञः क्षत्रपस दामाजडास

Rājñi Mahākṣatrapasa Rudradāmaputrasa Rājñah  
Kshatriyasa Dāmāyadaśa.

Of the king the Kshatriya Dāmāzāda's son of the king the  
Rājñi Rudradāman.

<sup>1</sup> See above page 34.

<sup>2</sup> It seems doubtful whether the Pandit's estimate of fifteen years might not with advantage be increased. As his father's reign was so short Rudradāman probably succeeded when still young. The abundance of his coins points to a long reign and the scarcity of the coins both of his son Dāmāzāda and of his grandson Jivadaman imply that neither of his successors reigned more than a few years. Jivadaman's earliest date is A.D. 178 (S. 100). If five years are allowed to Jivadaman's father the end of Rudradāman's reign would be A.D. 173 (S. 95) that is a reign of thirty years, no excessive term for a king who began to rule at a comparatively early age. (A. M. T. J.)

<sup>3</sup> Two specimens of his coins were obtained by Mr. Vajeshankar Gavrishankar Naib Diwan of Bhavnagar, from Kāthiavāda, one of which he presented to the Pandit and lent the other for the purpose of description. The legend in both was legible but doubtful. A recent find in Kāthiavāda supplied four new specimens, two of them very good.

<sup>4</sup> Apparently a mistake for रुद्रदाम्न पुत्रस.

<sup>5</sup> As in the case of Zamotika the father of Chastana, the variation दस for ञ proves that at first दस and afterwards ञ was used to represent the Greek Z.

## Chapter V.

WESTERN  
KSHATRAPAS,  
A.D. 70-328.

Kshatriya IV.  
Rudradāman,  
A.D. 143-158.

Kshatriya V.  
Dāmāzāda or  
Dāmājadaśrī,  
A.D. 158-168.

## Chapter - ૨.

WESTERN  
KSHATRAPAS,  
A.D. 70-398.  
Kshatrapa V.  
Damazada or  
Dāmājadaśrī,  
A.D. 158-168.

The legend on the other three is :

રાજો મહાક્ષત્રપસ રુદ્રદામ્નઃ પુત્રસ રાજોઃ ક્ષત્રપસ દામાજડશ્રિયઃ

Rājño Mahākshatrapasa Rudradāmanahputrasa Rājñah  
Kshatrapasa Dāmājadaśrīyah.

Of the king the Kshatrapa Dāmājadaśrī son of the king  
the great Kshatrapa Rudradāma.

Dāmīzāda and Dāmājadaśrī seem to be two forms of the same name, Dāmīzāda with ઝ્સ for ઝ being the name first struck, and Dāmājadaśrī, with the ordinary જ for ઝ, and with Śrī added to adorn the name and make it more euphonic, being the later form. It will be noted that, except by his son Jivadāman, Dāmīzāda or Dāmājadaśrī is not called a Mahākshatrapa but simply a Kshatrapa. His coins are very rare. The six mentioned are the only specimens known and are all from one find. He may therefore be supposed to have reigned as heir-apparent during the life-time of Rudradāman, or it is possible that he may have suffered loss of territory and power. His reign seems to have been short and may have terminated about 90 that is A.D. 168 or a little later.

Kshatrapa VI.  
Jivadāman,  
A.D. 178.

Dāmīzāda or Dāmājadaśrī was succeeded by his son Jivadāman. All available information regarding Jivadāman is from four rare coins obtained by Pandit Bhagvānāl, which for purposes of description, he has named A, B, C, and D<sup>1</sup>. Coin A bears date 100 in Nāgarī numerals, the earliest date found on Kshatrapa coins. On the obverse is a bust in the usual Kshatrapa style with a plump young face of good workmanship. Round the bust is first the date 100 in Nāgarī numerals and after the date the Greek legend in letters which though clear cannot be made out. In these and in all later Kshatrapa coins merely the form of the Greek legend remains; the letters are imitations of Greek by men who could not read the original. On the reverse is the usual archaic symbol between the sun and the moon, the sun being twelve-rayed as in the older Kshatrapa coins. Within the dotted circle in the margin is the following legend in old Nāgarī :

રાજો મહાક્ષત્રપસ દામશ્રિયઃ પુત્રસ રાજો મહાક્ષત્રપસ જીવદામ્ન[.]

Rājño Mahākshatrapasa Dāmasrīyahputrasa Rājño  
Mahākshatrapasa Jivadāmanah.

Of the king the great Kshatrapa Jivadāman son of the king  
the great Kshatrapa Dāmāśrī.

Coin B has the bust on the obverse with a face apparently older than the face in A. Unfortunately the die has slipped and the date has not been struck. Most of the Greek legend is very clear but as in coin A the result is meaningless. The letters are K I U I U Z K N S Y L perhaps meant for Kuzulka. On the reverse are the usual three symbols, except

<sup>1</sup> The oldest of the four was found by the Pandit for Dr. Bhan Dāji in Amreli. A fair copy of it is given in a plate which accompanied Mr. Justice Newton's paper in Jour. B. B. R. A. S. IX, page 141, Plate I, Fig. 6. Mr. Newton read the father's name in the legend Dāmāśrī, but it is Dāmājadaśrī, the die having missed the letters જ and ડ though space is left for them. This is coin A of the description. Of the remaining three, B was lent to the Pandit from his collection by Mr. Vajeshankar Gavrishankar. C and D were in the Pandit's collection.

that the sun has seven instead of twelve rays. The legend is :

राज्ञो महाक्षत्रपस दामजडस पुत्रस राज्ञो महाक्षत्रपस जीवदामस

Rājño Mahākshatrapasa Dāmajulasaputrasa Rājño  
Mahākshatrapasa Jivadāmasa.

Of the king the great Kshatrapa Jivadāman son of the  
king the great Kshatrapa Dāmajada.

Coin C though struck from a different die is closely like B both on the obverse and the reverse. Neither the Greek legend nor the date is clear, though enough remains of the lower parts of the numerals to suggest the date 118. Coin D is in obverse closely like C. The date 118 is clear. On the reverse the legend and the symbols have been twice struck. The same legend occurs twice, the second striking having obliterated the last letters of the legend which contained the name of the king whose coin it is.

राज्ञो महाक्षत्रपस दामजडस पुत्रस

Rājño Mahākshatrapasa Dāmajulasaputrasa.

Of the son of the king the great Kshatrapa Dāmajada.

In these four specimens Dāmāsri or Dāmajada is styled Mahākshatrapa, while in his own coins he is simply called Kshatrapa. The explanation perhaps is that the known coins of Dāmāsri or Dāmajada belong to the early part of his reign when he was subordinate to his father, and that he afterwards gained the title of Mahākshatrapa. Some such explanation is necessary as the distinction between the title Kshatrapa and Mahākshatrapa is always carefully preserved in the earlier Kshatrapa coins. Except towards the close of the dynasty no ruler called Kshatrapa on his own coins is ever styled Mahākshatrapa on the coins of his son unless the father gained the more important title during his lifetime.

The dates and the difference in the style of the used in coining A and in coining B, C, and D are worth noting as the earliest coin has the date 100 and C and D the third and fourth coins have 118. If Jivadāman's reign lasted eighteen years his coins would be common instead of very rare. But we find between 102 and 118 numerous coins of Rudrasimha son of Pāladāman and paternal uncle of Jivadāman. These facts and the difference between the style of A and the style of B, C, and D which are apparently imitated from the coins of Rudrasimha and have a face much older than the face in A, tend to show that soon after his accession Jivadāman was deposed by his uncle Rudrasimha, on whose death or defeat in 118, Jivadāman again rose to power.

Rudrasimha the seventh Kshatrapa was the brother of Dāmajadaśri. Large numbers of his coins have been found. Of thirty obtained by Dr. Bhagvānlāl twenty have the following clearly cut dates : 103, 106, 108, 109, 110, 112, 113, 114, 115, 116, and 118. As the earliest year is 103 and the latest 118 it is probable that Rudrasimha deposed his nephew Jivadāman shortly after Jivadāman's accession. Rudrasimha appears to have ruled fifteen years when power again passed to his nephew Jivadāman.

### Chapter V.

WESTERN  
KSHATRAPAS,  
A.D. 70-398.  
Kshatrapa VI.  
Jivadāman,  
A.D. 178.

Kshatrapa VII.  
Rudrasimha I.  
A.D. 181-196.

## Chapter V.

WESTERN  
KSHATRAPAS.Kshatrapa VII.  
Rudrasimha I.  
A.D. 181-196

The coins of Rudrasimha are of a beautiful type of good workmanship and with clear legends. The legend in old Nāgarī character reads :

राज्ञो महाक्षत्रपस रुद्रदामपुत्रस राज्ञो महाक्षत्रपस रुद्रसिंहस

Rājño Mahākshatrapasa Rudradāmaputrasa Rājño  
Mahākshatrapasa Rudrasimhasa.

Of the king the great Kshatrapa Rudrasimha son of the  
king the great Kshatrapa Rudradāma.

Rudrasimha had also a copper coinage of which specimens are recorded from Mālwa but not from Kāthiavāda. Pandit Bhagvānlāl had one specimen from Ujjain which has a bull on the obverse with the Greek legend round it and the date 117. The reverse seems to have held the entire legend of which only five letters रुद्रसिंहस (Rudrasimhasa) remain. This coin has been spoilt in cleaning.

To Rudrasimha's reign belongs the Gunda inscription carved on a stone found at the bottom of an unused well in the village of Gunda in Halīr in North Kāthiavāda.<sup>1</sup> It is in six well preserved lines of old Nāgarī letters of the Kshatrapa type. The writing records the digging and building of a well for public use on the borders of a village named Rasopadra by the commander-in-chief Rudrahūti an Abhira son of Senāpati Bāpaka. The date is given both in words and in numerals as 103, 'in the year' of the king the Kshatrapa Svāmi Rudrasimha, apparently meaning in the year 103 during the reign of Rudrasimha. The genealogy given in the inscription is : 1 Chashtana ; 2 Jayadāman ; 3 Rudradāman ; 4 Rudrasimha, the order of succession being clearly defined by the text, which says that the fourth was the great grandson of the first, the grandson of the second, and the son of the third. It will be noted that Dāmajadaśrī and Jivadāman the fifth and sixth Kshatrapas have been passed over in this genealogy probably because the inscription did not intend to give a complete genealogy but only to show the descent of Rudrasimha in the direct line.

Kshatrapa VIII  
Rudrasena,  
A.D. 203-220

The eighth Kshatrapa was Rudrasena, son of Rudrasimha, as is clearly mentioned in the legends on his coins. His coins like his father's are found in large numbers. Of forty in Dr. Bhagvānlāl's collection twenty-seven bear the following eleven<sup>2</sup> dates, 125, 130, 131, 132, 133, 134, 135, 136, 138, 140, 142. The coins are of the usual Kshatrapa type closely like Rudrasimha's coins. The Nāgarī legend reads :

राज्ञो महाक्षत्रपस रुद्रसिंहस पुत्रस राज्ञो महाक्षत्रपस रुद्रसेनस

Rājño Mahākshatrapasa Rudrasimhasa putrasa Rājño  
Mahākshatrapasa Rudrasenasa.

Of the king the great Kshatrapa Rudrasena son of the king  
the great Kshatrapa Rudrasimha.

Two copper coins square and smaller than the copper coins of

<sup>1</sup> This inscription which has now been placed for safe custody in the temple of Dvarkamūth at Jamnagar, has been published by Dr. Bühler in Ind. Ant. X. 157-158, from a transcript by Āchārya Vallabji Haridatta. Dr. Bhagvānlāl held that the date is 103 *trayuttarasate* not 102 *devuttarasate* as read by Dr. Bühler ; that the name of the father of the donor is Bāpaka and not Bahaka ; and that the name of the *nakshatra* or constellation is Rohini not Śruvana.

<sup>2</sup> Several coins have the same date.

Rudrasimha have been found in Ujjain<sup>1</sup> though none are recorded from Kāthiāvāḍa. On their obverse these copper coins have a facing bull and on the back the usual symbols and below them the year 140, but no legend. Their date and their Kshatrapa style show that they are coins of Rudrasena.\*

Besides coins two inscriptions one at Muliyaśar the other at Jasdan give information regarding Rudrasena. The Muliyaśar inscription, now in the library at Dwārka ten miles south-west of Muliyaśar, records the erection of an upright slab by the sons of one Vānījaka. This inscription bears date 122, the fifth of the dark half of Vaiśākha in the year 122 during the reign of Rudrasimha.<sup>2</sup> The Jasdan inscription, on a stone about five miles from Jasdan, belongs to the reign of this Kshatrapa. It is in six lines of old Kshatrapa Nāgarī characters shallow and dim with occasional engraver's mistakes, but on the whole well-preserved. The writing records the building of a pond by several brothers (names not given) of the Mamasa gotra sons of Pramāthaka and grandsons of Khara. The date is the 5th of the dark half of Bhādrapada 'in the year' 126.<sup>3</sup> The genealogy is in the following order :

Mahākshatrapa Chashtana.  
Kshatrapa Jayadāman.  
Mahākshatrapa Rudradāman.  
Mahākshatrapa Rudrasimha.  
Mahākshatrapa Rudrasena.

Each of them is called Svāpi Lord and Bhādrāmukha Luckyfaced.<sup>4</sup> As Rudrasena's reign began at least as early as 122, the second reign of Jivadāman is narrowed to four years or even less. As the latest date is 142 Rudrasena's reign must have lasted about twenty years.

After Rudrasena the next evidence on record is a coin of his son Prithivīśena found near Anreli. Its workmanship is the same as that of Rudrasena's coins. It is dated 144 that is two years later than the last date on Rudrasena's coins. The legend runs :

राज्ञो महाक्षत्रपस रुद्रसेनस पुत्रस राज्ञः क्षत्रपस पृथिवीसेनस

Rājño Mahākshatrapasa Rudrasenasa putrasa Rājñah  
Kshatrapasa Prithivīśenasa.

Of the king the Kshatrapa Prithivīśena son of the king  
the Kshatrapa Rudrasena.

As this is the only known specimen of Prithivīśena's coinage ; as the earliest coin of Prithivīśena's uncle the tenth Kshatrapa Saṅghadāman is dated 144 ; and also as Prithivīśena is called only Kshatrapa he seems to have reigned for a short time perhaps as Kshatrapa of Surāshtra or Kāthiāvāḍa and to have been ousted by his uncle Saṅghadāman.

Rudrasena was succeeded by his brother the Mahākshatrapa Saṅghadāman. His coins are very rare. Only two specimens have been

### Chapter V.

WESTERN  
KSHATRAPAS,  
A.D. 70-308.  
Kshatrapa VIII.  
Rudrasena,  
A.D. 203-220.

Kshatrapa IX.  
Prithivīśena,  
A.D. 222.

Kshatrapa X  
Saṅghadāman,  
A.D. 222-226.

<sup>1</sup> One is in the collection of the B. G. B. A. Society, the other belonged to the Pundit.

<sup>2</sup> An unpublished inscription found in 1865 by Mr. Bhagvānlal Sampatram.

<sup>3</sup> The top of the third numeral is broken. It may be 7 but is more likely to be 6.

<sup>4</sup> The Jasdan inscription has been published by Dr. Bhāu Dāji, J. B. R. A. S. VIII. 234ff, and by Dr. Hoernle, Ind. Ant. XII. 32ff.

## Chapter V.

WESTERN  
KSHATRAPAS,  
A.D. 70-398.  
Kshatrapa N  
Sanghadaman,  
A.D. 222-228.

obtained, of which one was in the Pandit's collection the other in the collection of Mr. Vajeshankar Gavrishankar.<sup>1</sup> They are dated 145 and 144. The legend in both reads :

राज्ञो महाक्षत्रपस रुद्रसिंहस पुत्रस राज्ञो महाक्षत्रपस संघदान्न [ : ]

Rajaso Mahakshatrapasa Rudrasinhasa putrasa Rājño  
Mahakshatrapasa Sanghadānna.

Of the king the great Kshatrapa Sanghadaman son of the king  
the great Kshatrapa Rudrasinha.

These two coins seem to belong to the beginning of Sanghadānna's reign. As the earliest coins of his successor Dāmasena are dated 148 Sanghadānna's reign seems not to have lasted over four years.<sup>2</sup>

<sup>1</sup> Five have recently been identified in the collection of Dr. Gerson dat'min.  
- His name, the fact that he regarded the title Mahakshatrapa, and his date about A.D. 225 suggest that Sanghadaman (A.D. 222-228) may be the Sandanes whom the Periplus (McCrindle, 128) describes as taking the regular mail Kalyan near Bombay from Samanes, that is the Dakhan Satavahans and, to prevent it again becoming a place of trade, forbidding all Greek ships to visit Kalyan, and sailing under a guard to Branch any Greek ships that even by accident entered its port. The following reasons seem conclusive against identifying Sanghadaman with Sandanes: (1) The abbreviation from Sanghadaman to Sandanes seems excessive in the case of the name of a well known ruler who lived within thirty years of the probable time (A.D. 217) when the writer of the Periplus visited Gujarat and the Konkan. (2) The date of Sanghadaman (A.D. 222-228) is twenty to thirty years too early for the probable collection of the Periplus details: (3) Apart from the date of the Periplus the apparent distinction in the writer's mind between Sandanes' capture of Kalyan and his own time implies a longer lapse than suits a reign of only four years.

In favour of the Sandanes of the Periplus being a dynasty, not a personal name is its close correspondence both in form and in geographical position with Ptolemy's (A.D. 150) Sandanes, who gave their name, Ariake Sadmon or the Sadms' Aria, to the North Konkan, and, according to McCrindle (Ptolemy, 33) in the time of Ptolemy ruled the prosperous trading communities that occupied the sea coast to about Semulla (Chaul). The details in the present text show that some few years before Ptolemy wrote the conquests of Sanghadaman had brought the North Konkan under the Gujarat Kshatrapas. Similarly shortly before the probable date of the Periplus (A.D. 217) the fact that Sanghadaman and his successors Dāmasena (A.D. 226-236) and Vijayasena (A.D. 238-249) all used the title Mahakshatrapa makes their possession of the North Konkan probable. The available details of the Kathiawadi Kshatrapas therefore confirm the view that the Sadms of Ptolemy and the Sandanes of the Periplus are the Gujarat Kshatrapas. The question remains how did the Greeks come to know the Kshatrapas by the name of Sadan or Sandan. The answer seems to be the word Sadan or Sadmon is the Sanskrit *Sādhanā* which according to Lassen (McCrindle's Ptolemy, 40) and Williams Sanskrit Dictionary may mean agent or representative and may therefore be an approximate rendering of Kshatrapa in the sense of Viceroy. Wilford (As. Res. IX 76, 198) notices that Sanskrit writers gave the early English in India the title Sadman English. This Wilford would translate Lord but it seems rather meant for a rendering of the word Factor. Prof. Bhāmlarkar (Bon. Gaz. XIII, 418 note 1) notices a tribe mentioned by the geographer Varāhamihira (A.D. 580) as Sātūkas and associated with the Aparāntakas or people of the west coast. He shows how according to the rules of letter changes the Sanskrit Sātūka would in Prakrit be Sandino. In his opinion it was this form Sandino which was familiar to Greek merchants and sailors. Prof. Bhāmlarkar holds that when (A.D. 100-110) the Kshatrapa Nahapāna displaced the Satavāhanas or Āmīrādhityas the Sātūkas or Sandino became independent in the North Konkan and took Kalyan. To make their independence secure against the Kshatrapas they forbade intercourse between their own territory and the Dakhan and sent foreign ships to Barygaza. Against this explanation it is to be urged; (1) That Nātsik and Jānāni inscriptions show Nahapāna supreme in the North Konkan at least up to A.D. 120, (2) That according to the Periplus the action taken by the Samlana or Sadams was not against the Kshatrapas but against the Sātakarnis; (3) That the action was not taken in the time of Nahapāna but at a later time, later not only than the first Gautamiputra the conqueror of Nahapāna or his son-in-law Ushavādāta (A.D. 138), but later than the second Gautamiputra, who was defeated by the Kathiawadi Kshatrapa Rudhadaman some time before A.D. 150. (4) That if the Sātūkas were solely a North

Saṅghadāman was succeeded by his brother Dāmasena, whose coins are fairly common, of good workmanship, and clear lettering. Of twenty-three specimens eleven have the following dates: 148, 150, 153, 155, 156, 157, 158. The legend runs:

राज्ञो महाक्षत्रपस रुद्रसिंहस पुत्रस राज्ञो महाक्षत्रपस दामसेनस

Rājño Mahakṣatrapasa Rudrasinhasa putrasa Rājño  
Mahakṣatrapasa Dāmasenasasa.

Of the king the great Kshatrapa Dāmasena son of the king  
the great Kshatrapa Rudrasinha

Dāmasena seems to have reigned ten years (148-158) as coins of his son Viradaman are found dated 158.

Damājadaśrī the twelfth Kshatrapa is styled son of Rudrasena probably the eighth Kshatrapa. Dāmājadaśrī's coins are rare.<sup>1</sup> The legend runs:

राज्ञो महाक्षत्रपस रुद्रसेनपुत्रस राज्ञश्चत्रपस दामाजडश्रियः

Rājño Mahakṣatrapasa Rudrasenaputrasa Rājñashchtrapas  
Dāmajadashriyah.

Of the king the Kshatrapa Dāmajadāśrī (son of the king  
the great Kshatrapa Rudrasena).

Five specimens, the only specimens on record are dated 154. As 154 falls in the reign of Dāmasena it seems probable that Dāmājadaśrī was either a minor or a viceroy or perhaps a ruler claiming independence, as about this time the authority of the main dynasty seems to have been much disputed.

Konkan tribe they would neither wish nor be able to send foreign ships to Broach. The action described in the Periplus of refusing to let Greek ships enter Kalyan and of sending all such ships to Broach was the action of a Gujarati conqueror of Kalyan determined to make foreign trade centre in his own chief emporium Broach. The only possible lord of Gujarat either in the second or third century who can have adopted such a policy was the Kshatrapa of Ujjain or Malwa and of Munagara or Junagadh in Kathiavada, the same ruler, who, to encourage foreign vessels to visit Broach had (McGindley's Periplus, 118, 119) stationed native fishermen with well-manned long boats off the south Kathiavada coast to meet ships and pilot them through the tidal and other dangers up the Nerbudda to Broach. It follows that the Sandanes of the Periplus and Ptolemy's North Konkani Sailas are the Gujarati Mahakshatrapas. The correctness of this identification of Sadan with the Saka Erit Sadhan and the explanation of Sadhan as a translation of Kshatrapa or viceroy is a reserve confirmation from the fact that the necrologist Kṛṣṇacharya in the Bhojeshwara Vritti (J. B. B. R. A. S. IX, 111-112), late in date (A.D. 1000-1100) but with notable details of the Saka or Sati invaders, calls the Saka king Sadhana-Sinha. If on this evidence it may be held that the Kshatrapas were known as Sadhanas, it seems to follow that Sautika the form used by Varahamihira (A.D. 505-527) is a conscious and intentional Sanskritizing of Sadan whose correct form and origin had passed out of knowledge, a result which would suggest conscious or artificial Sanskritizing as the explanation of the forms of many Purāṇic tribal and place names. A further important result of this inquiry is to show that the received date of A.D. 70 for the Periplus cannot stand. Now that the Kanishka era A.D. 78 is admitted to be the era used by the Kshatrapas both in the Dakhn and in Gujarāt it follows that a writer who knows the elder and the younger Satakarnis cannot be earlier than A.D. 150 and from the manner in which he refers to them must almost certainly be considerably later. This conclusion supports the date A.D. 247 which on other weighty grounds the French scholar Reinaud (Ind. Ant. Dec., 1879, pp. 330, 338) has assigned to the Periplus.

<sup>1</sup> The Pandit's coin was obtained by him in 1863 from Amroli in Kāthiāvādīja. A copy of it is given by Mr. Justice Newton who calls Saṅghadāman son of Rudrasinha (J. B. B. R. A. S. IX, Pl. I, Fig. 7). The other specimen is better preserved.

<sup>2</sup> One of these coins was lent to the Pandit by Mr. Vajeshankar Gavvishankar.

## Chapter V.

WESTERN  
KSHATRAPAS,  
A.D. 70-398.

Kshatrapa XI.  
Dāmasena,  
A.D. 226-236.

Kshatrapa XII  
Dāmajadaśrī II  
A.D. 236.

## Chapter V.

WESTERN  
KSHATRAPAS,  
A.D. 70-398.

After Dāmasena we find coins of three of his sons Vīradāman Yaśadāman and Vijayasena. Vīradāman's coins are dated 158 and 160, Yaśadāman's 160 and 161, and Vijayasena's earliest 160. Of the three brothers Vīradāman who is styled simply Kshatrapa probably held only a part of his father's dominions. The second brother Yaśadāman, who at first was a simple Kshatrapa, in 161 claims to be Mahākshatrapa. The third brother Vijayasena, who as early as 160, is styled Mahākshatrapa, probably defeated Yaśadāman and secured the supreme rule.

Kshatrapa XIII  
Vīradāman,  
A.D. 236-238

Vīradāman's coins are fairly common. Of twenty-six in Pandit Bhagvānlāl's collection, nineteen were found with a large number of his brother Vijayasena's coins. The legend reads :

राज्ञो महाक्षत्रपस दामसेनस पुत्रस राज्ञो क्षत्रपस वीरदाम्नः

Rājño Mahākshatrapasa Dāmasenasa putrasa Rājñah  
Kshatrapasa Vīradāmanah.

Of the king the Kshatrapa Vīradāman son of the king  
the great Kshatrapa Dāmasena.

Of the twenty-six ten are clearly dated, six with 158 and four with 160.

Kshatrapa XIV  
Yaśadāman,  
A.D. 239.

Yaśadāman's coins are rare. Pandit Bhagvānlāl's collection contained seven.<sup>1</sup> The bust on the obverse is a good imitation of the bust on his father's coins. Still it is of inferior workmanship, and starts the practice which later Kshatrapas continued of copying their predecessor's image. On only two of the seven specimens are the dates clear, 160 and 161. The legend on the coin dated 160 is :

राज्ञो महाक्षत्रपस दामसेनस पुत्रस राज्ञः क्षत्रपस यशदाम्नः

Rājño Mahākshatrapasa Dāmasenasa putrasa Rājñah  
Kshatrapasa Yaśadāmanah.

Of the king the great Kshatrapa Yaśadāman son of the  
king the great Kshatrapa Dāmasena.

On the coin dated 161 the legend runs :

राज्ञो महाक्षत्रपस दामसेनस पुत्रस राज्ञो महाक्षत्रपस यशदाम्नः

Rājño Mahākshatrapasa Dāmasenasa putrasa Rājñah  
Mahākshatrapasa Yaśadāmanah.

Of the king the great Kshatrapa Yaśadāman son of the  
king the great Kshatrapa Dāmasena.

Kshatrapa XV.  
Vijayasena,  
A.D. 238-249.

Vijayasena's coins are common. As many as 167 were in the Pandit's collection. Almost all are of good workmanship, well preserved, and clearly lettered. On fifty-four of them the following dates can be clearly read, 160, 161, 162, 163, 164, 165, 166, 167, 168, 170, and 171. This would give Vijayasena a reign of at least eleven years from 160 to 171 (A.D. 238-249). The legend reads :

राज्ञो महाक्षत्रपस दामसेनपुत्रस राज्ञो महाक्षत्रपस विजयसेनस

Rājño Mahākshatrapasa Dāmasenaputrasa Rājñah  
Mahākshatrapasa Vijayasenasa.

Of the king the great Kshatrapa Vijayaseana son of the  
king the great Kshatrapa Dāmasena.

<sup>1</sup> One specimen in the collection of Mr. Vajeshankar bears date 158.

In two good specimens of Vijayasena's coins with traces of the date 166 he is styled Kshatrapa. This the Pandit could not explain.<sup>1</sup>

Vijayasena was succeeded by his brother Dāmājadāsri III. called Mahākshatrapa on his coins. His coins which are comparatively uncommon are inferior in workmanship to the coins of Vijayasena. Of seven in the Pandit's collection three are dated 174, 175, and 176.

After Dāmājadāsri come coins of Rudrasena II son of Virādāman, the earliest of them bearing date 178. As the latest coins of Vijayasena are dated 171, 173 may be taken as the year of Dāmājadāsri's succession. The end of his reign falls between 176 and 178, its probable length is about five years. The legend on his coins reads :

राज्ञो महाक्षत्रपस दामसेनपुत्रस राज्ञो महाक्षत्रपस दामाजडश्रियः

Rājño Mahākshatrapasa Dāmasenapūtrasa Rājño Mahākshatrapasa  
Dāmajadashriyah

Of the king the great Kshatrapa Dāmājadāsri son of the king  
the great Kshatrapa Dāmasena.

Dāmājadāsri III. was succeeded by Rudrasena II. son of Dāmājadāsri's brother Virādāman the thirteenth Kshatrapa. Rudrasena II.'s coins like Vijayasena's are found in great abundance. They are of inferior workmanship and inferior silver. Of eighty-four in Dr. Bhagavānlāl's collection eleven bore the following clear dates : 178, 180, 183, 185, 186, 188, and 190. The earliest of 178 probably belongs to the beginning of Rudrasena's reign as the date 176 occurs on the latest coins of his predecessor. The earliest coins of his son and successor Visvasimha are dated 198. As Visvasimha's coins are of bad workmanship with doubtful legend and date we may take the end of Rudrasena II.'s reign to be somewhere between 190 and 198 or about 191. This date would give Rudrasena a reign of about sixteen years, a length of rule supported by the large number of his coins. The legend reads :

राज्ञो क्षत्रपस वीरदामपुत्रस राज्ञो महाक्षत्रपस रुद्रसेनस

Rājño Kshatrapasa Vīradāmapūtrasa Rājño Mahākshatrapasa Rudrasenasa.

Of the king the great Kshatrapa Rudrasena son of the king the Kshatrapa Virādāman.

Rudrasena was succeeded by his son Visvasimha. In style and abundance Visvasimha's coins are on a par with his father's. They are carelessly struck with a bad die and in most the legend is faulty often omitting the date. Of fifty-six in the Pandit's collection only four bear legible dates, one with 198, two with 200, and one with 201. The date 201 must be of the end of Visvasimha's reign as a coin of his brother Bhartridāman is dated 200. It may therefore be held that Visvasimha reigned for the six years ending 200 (A.D. 272-278). The legend reads :

राज्ञो महाक्षत्रपस रुद्रसेनपुत्रस राज्ञः क्षत्रपस विश्वसिंहस.

Rājño Mahākshatrapasa Rudrasenapūtrasa Rājñah  
Kshatrapasa Visvasimhasa

Of the king the Kshatrapa Visvasimha son of the king  
the great Kshatrapa Rudrasena.

One of them was lent by Mr. Vajeshankar Gavrishankar.

### Chapter V.

WESTERN  
KSHATRAPAS,  
A.D. 70-398.

Kshatrapa XVI.  
Dāmājadāsri,  
A.D. 250-255.

Kshatrapa XVII.  
Rudrasena II.  
A.D. 256-272.

Kshatrapa XVIII.  
Visvasimha,  
A.D. 272-278.

## Chapter V.

WESTERN  
KSHATRAPAS,  
A.D. 70-398.

Kshatrapa XIX.  
Bharttridāman,  
A.D. 278-291.

It is not known whether Viśvasimha's loss of title was due to his being subordinate to some overlord, or whether during his reign the Kshatrapas suffered defeat and loss of territory. The probable explanation seems to be that he began his reign in a subordinate position and afterwards rose to supreme rule.

Viśvasimha was succeeded by his brother Bharttridāman.<sup>1</sup> His coins which are found in large numbers are in style and workmanship inferior even to Viśvasimha's coins. Of forty-five in the Pandit's collection seven bear the dates 202, 207, 210, 211, and 214. As the earliest coin of his successor is dated 218, Bharttridāman's reign seems to have lasted about fourteen years from 202 to 216 (A.D. 278-291). Most of the coin legends style Bharttridāman Mahākshatrapa though in a few he is simply styled Kshatrapa. This would seem to show that like his brother Viśvasimha he began as a Kshatrapa and afterwards gained the rank and power of Mahākshatrapa.

In Bharttridāman's earlier coins the legend reads :

राज्ञो महाक्षत्रपस रुद्रसेनपुत्रस राज्ञः क्षत्रपस भर्तृदाग्नः

Rājño Mahākshatrapasa Rudrasenaputrasa Rājñah  
Kshatrapasa Bharttridāmanah.

Of the king the Kshatrapa Bharttridāman son of the king  
the great Kshatrapa Rudrasena.

In the later coins the legend is the same except that महाक्षत्रपस the great Kshatrapa takes the place of क्षत्रपस the Kshatrapa.

Kshatrapa XX.  
Viśvasena,  
A.D. 291-300.

Bharttridāman was succeeded by his son Viśvasena the twentieth Kshatrapa. His coins are fairly common, and of bad workmanship, the legend imperfect and carelessly struck, the obverse rarely dated. Of twenty-five in Dr. Bhagvānlāl's collection, only three bear doubtful dates one 218 and two 222. The legend reads :

राज्ञो महाक्षत्रपस भर्तृदामपुत्रस राज्ञः क्षत्रपस विश्वसेनस,

Rājño Mahākshatrapasa Bharttridāmanaputrasa Rājñah  
Kshatrapasa Viśvasenasa.

Of the king the Kshatrapa Viśvasena son of the king the  
Mahākshatrapa Bharttridāman.

It would seem from the lower title of Kshatrapa which we find given to Viśvasena and to most of the later Kshatrapas that from about 220 (A.D. 298) the Kshatrapa dominion lost its importance.

A hoard of coins found in 1861 near Karād on the Krishna, thirty-one miles south of Sātara, suggests<sup>2</sup> that the Kshatrapas retained the North Konkan and held a considerable share of the West Dakhan down to the time of Viśvasena (A.D. 300). The hoard includes coins of the six following rulers: Vijayasena (A.D. 238-249), his brother Dāmājadaśrī III. (A.D. 251-255), Rudrasena II. (A.D. 256-272) son of Viśvalāman, Viśvasimha (A.D. 272-278) son of Rudrasena, Bharttridāman (A.D. 278-291) son of Rudrasena II., and Viśvasena (A.D. 296-300) son of Bharttridāman. It may be argued that this Karād hoard is of no historical value being the chance importation of some Gujarāt pilgrim to the Krishna. The following considerations favour the

<sup>1</sup> This name has generally been read Atridāman.

<sup>2</sup> Jour. B. B. R. A. S. VII. 16.

view that the contents of the hoard furnish evidence of the local rule of the kings whose coins have been found at Karād. The date (A.D. 238-249) of Vijayasena, the earliest king of the hoard, agrees well with the spread of Gujarāt power in the Dakhan as it follows the overthrow both of the west (A.D. 180-200) and of the east (A.D. 220) Śātakarnis, while it precedes the establishment of any later west Dakhan dynasty: (2) All the kings whose coins occur in the hoard were Mahākshatrapas and from the details in the Periplus (A.D. 247), the earliest, Vijayasena, must have been a ruler of special wealth and power: (3) That the coins cease with Viśvasena (A.D. 296-300) is in accord with the fact that Viśvasena was the last of the direct line of Chashtana, and that with or before the close of Viśvasena's reign the power of the Gujarāt Kshatrapas declined. The presumption that Kshatrapa power was at its height during the reigns of the kings whose coins have been found at Karād is strengthened by the discovery at Amravati in the Berars of a hoard of coins of the Mahākshatrapa Rudrasimha (II. 2) (A.D. 256-272) son of the Mahākshatrapa Damaajadasri.<sup>1</sup>

Whether the end of Chashtana's direct line was due to their conquest by some other dynasty or to the failure of heirs is doubtful. Whatever may have been the cause, after an interval of about seven years (A.D. 300-308) an entirely new king appears, Rudrasimha son of Jivadāman. As Rudrasimha's father Jivadāman is simply called Svami he may have been some high officer under the Kshatrapa dynasty. That Rudrasimha is called a Kshatrapa may show that part of the Kshatrapa dominion which had been lost during the reign of Viśvasena was given to some distant member or scion of the Kshatrapa dynasty of the name of Rudrasimha. The occurrence of political changes is further shown by the fact that the coins of Rudrasimha are of a better type than those of the preceding Kshatrapas. Rudrasimha's coins are fairly common. Of twelve in Dr. Bhagvānlāl's collection five are clearly dated, three 230, one 231, and one 240. This leaves a blank of seven years between the last date of Viśvasena and the earliest date of Rudrasimha. The legend reads:

स्वामिर्जावदामपुत्रस राज्ञः क्षत्रपस रुद्रसिंहस

Svami Jivadāman, son of Raja Rajñah Kshatrapasa Rudrasimhasa  
Of the king the Kshatrapa Rudrasimha son of Svami Jivadāman.

Rudrasimha was succeeded by his son Yaśadāman whose coins are rather rare. Of three in Dr. Bhagvānlāl's collection two are dated 289, apparently the first year of Yaśadāman's reign as his father's latest coins are dated 240. Like his father Yaśadāman is simply called Kshatrapa. The legend reads:

राज्ञः क्षत्रपस रुद्रसिंहपुत्रस राज्ञः क्षत्रपस यशदाम्नः

Rajñah Kshatrapasa Rudrasimhaputrasa Rajñah  
Kshatrapasa Yaśadāmannah.

Of the king the Kshatrapa Yaśadāman son of the  
king the Kshatrapa Rudrasimha,

### Chapter V.

WESTERN  
KSHATRAPAS,  
A.D. 70-398.  
Kshatrapa XX.  
Viśvasena,  
A.D. 294-300.

Kshatrapa XXI.  
Rudrasimha,  
A.D. 300-311

Kshatrapa XXII.  
Yaśadāman,  
A.D. 320.

## Chapter V.

WESTERN  
KSHATRAPAS,  
A.D. 70-398.

Kshatrapa  
XXIII.  
Damasiri,  
A.D. 320

The coins found next after Yaśadāman's are those of Dāmasiri who was probably the brother of Yaśadāman as he is mentioned as the son of Rudrasimha. The date though not very clear is apparently 242. Only one coin of Dāmasiri's is recorded. In the style of face and in the form of letters it differs from the coins of Yaśadāman, with which except for the date and the identity of the father's name any close connection would seem doubtful. The legend on the coin of Dāmasiri reads:

राज्ञो महाक्षत्रपस रुद्रसिंहस पुत्रस राज्ञो महाक्षत्रपस दामसिरिस.

Rājño Mahākshatrapasa Rudrasindhasaputrasa Rājño  
Mahākshatrapasa Damasirisa.

Of the king the great Kshatrapa Damsira son of the king the  
great Kshatrapa Rudrasimha.

It will be noted that in this coin both Rudrasimha and Dāmasiri are called great Kshatrapas, while in his own coin and in the coins of his son Yaśadāman, Rudrasimha is simply styled Kshatrapa. It is possible that Dāmasiri may have been more powerful than Yaśadāman and consequently taken to himself the title of Mahākshatrapa. The application of the more important title to a father who in life had not enjoyed the title is not an uncommon practice among the later Kshatrapas. The rarity of Dāmasiri's coins shows that his reign was short.

After Dāmasiri comes a blank of about thirty years. The next coin is dated 270. The fact that, contrary to what might have been expected, the coins of the later Kshatrapas are less common than those of the earlier Kshatrapas, seems to point to some great political change during the twenty-seven years ending 270 (A.D. 321-348).

Kshatrapa  
XXIV.  
Rudrasena,  
A.D. 348-370

The coin dated 270 belongs to Svāmī Rudrasena son of Svāmī Rudradāman both of whom the legend styles Mahākshatrapas. The type of the coin dated 270 is clearly adapted from the type of the coins of Yaśadāman. Only two of Rudrasena's coins dated 270 are recorded. But later coins of the same Kshatrapa of a different style are found in large numbers. Of fifty-four in the Paudit's collection, twelve have the following dates 288, 290, 292, 293, 294, 296, and 298. The difference in the style of the two sets of coins and the blank between 270 and 288 leave no doubt that during those years some political change took place. Probably Rudrasena was for a time overthrown but again came to power in 288 and maintained his position till 298. Besides calling both himself and his father Mahākshatrapas Rudrasena adds to both the attribute Svāmī. As no coin of Rudrasena's father is recorded it seems probable the father was not an independent ruler and that the legend on Rudrasena's coins is a further instance of a son ennobling his father. The legend is the same both in the earlier coins of 270 and in the later coins ranging from 288 to 298. It reads:

राज्ञो महाक्षत्रपस स्वामिरुद्रदामपुत्रस राज्ञो महाक्षत्रपस स्वामिरुद्रसेनस.

Rājño Mahākshatrapasa Svāmī Rudradāmaputrasa Rājño  
Mahākshatrapasa Svāmī Rudrasenasa.

Of the king the great Kshatrapa Svāmī Rudrasena son of the king  
the great Kshatrapa Svāmī Rudradāman.

After Rudrasena come coins of Kshatrapa Rudrasena son of Satyasena. These coins are fairly common. Of five in the Pandit's collection through faulty minting none are dated. General Cunningham mentions coins of Kshatrapa Rudrasena dated 300, 301, and 310.<sup>1</sup> This would seem to show that he was the successor of Rudrasena son of Rudradaman and that his reign extended to over 310. The legend on these coins runs:

राज्ञो महाक्षत्रपस स्वामिसव्यमेनपुत्रस राज्ञो महाक्षत्रपस स्वामिरुद्रसेनस.

Rājño Mahakshatrapasa Svāmī Savyasenaputrasa Rājño

• Mahakshatrapasa Svāmī Rudrasenasa

Of the king the great Kshatrapa Svāmī Rudrasena son  
of the king the great Kshatrapa Svāmī Satyasena

Of Rudrasena's father Satyasena no coin is recorded and as this Rudrasena immediately succeeds Rudrasena IV, son of Rudradaman, there is little doubt that Satyasena was not an actual ruler with the great title Mahakshatrapa, but that this was an honorific title given to the father when his son attained to sovereignty. General Cunningham records that a coin of this Rudrasena IV. was found along with a coin of Chakragupta II. in a *stupa* at Sultanganj on the Ganges, about fifteen miles south-east of Mongir.<sup>2</sup>

With Rudrasena IV. the evidence from coins comes almost to a close. Only one coin in Dr. Bhagvānlāl's collection is clearly later than Rudrasena IV. In the form of the bust and the style of the legend on the reverse this specimen closely resembles the coins of Rudrasena IV. Unfortunately owing to imperfect stamping it bears no date. The legend reads:

राज्ञो महाक्षत्रपस स्वामि रुद्रसेनस राज्ञो महाक्षत्रपस स्वामिरिद्रसेनस,

Rājño Mahakshatrapasa Svāmī Rudrasenasa Rājño Mahakshatrapasa  
Svāmī Simhasenasa

Of the king the great Kshatrapa Svāmī Simhasena, sister's son of  
the king the great Kshatrapa Svāmī Rudrasena

This legend would seem to show that Rudrasena IV. left no issue and was succeeded by his nephew Simhasena. The extreme rarity of Simhasena's coins proves that his reign was very short.

The bust and the characters on one other coin show it to be of later date than Simhasena. Unfortunately the legend is not clear. Something like the letters राज्ञो क्षत्रपस Rājño Kshatrapasa may be traced in one place and something like पुत्रस स्कन्द Putrasa Skanda in another place. Dr. Bhagvānlāl took this to be a Gujarāt Kshatrapa of unknown lineage from whom the Kshatrapa dominion passed to the Guptas.

Along with the coins of the regular Kshatrapas coins of a Kshatrapa of unknown lineage named Íśvaradatta have been found in Kāthiāvāḍa. In general style, in the bust and the corrupt Greek legend on the obverse, and in the form of the old Nāgarī legend

### Chapter V.

WESTERN  
KSHATRAPAS,  
A.D. 70-398  
Kshatrapa XX<sup>1</sup>  
Rudrasena,  
A.D. 374-384.

Kshatrapa  
XXVI  
Simhasena

Kshatrapa  
XXVII  
Skanda.

Íśvaradatta,  
A.D. 230-250

<sup>1</sup> Cunningham's Arch. Sur. X. 127; XV. 29-30.

<sup>2</sup> This coin of Rudrasena may have been taken so far from Gujarāt by the Gujarāt monk in whose honour the *stupa* was built.

**Chapter V.**

WESTERN  
KSHATRAPS,  
A.D. 70-398.

Kshatraps  
XXVIII.  
Ísvara latta,  
A.D. 230-250

on the reverse, Ísvaradatta's coins closely resemble those of the fifteenth Kshatraps Vijayasena (A.D. 238-249). At the same time the text of the Nágari legend differs from that on the reverse of the Kshatraps coins by omitting the name of the ruler's father and by showing in words Ísvaradatta's date in the year of his own reign. The legend is:

राज्ञो महाक्षत्रपम ईश्वरदत्तम वर्षे प्रथमे,

Rājño Mahākshatrapasa Ísvaradattasa varshe prathamē.

In the first year of the king the great Kshatraps Ísvaradatta.

Most of the recorded coins of Ísvaradatta have this legend. In one specimen the legend is

वर्षे द्वितीये.

Varshē dvitīyē.

In the second year.

It is clear from this that Ísvaradatta's reign did not last long. His peculiar name and his separate date leave little doubt that he belonged to some distinct family of Kshatrapas. The general style of his coins shows that he cannot have been a late Kshatraps while the fact that he is called Mahākshatraps seems to show he was an independent ruler. No good evidence is available for fixing his date. As already mentioned the workmanship of his coins brings him near to Vijayasena (A.D. 238-249). Nāsik Cave X. the letters of Inscription XV. closely correspond with the letters of the legends on Kshatraps coins, and probably belong to almost the same date as the inscription of Rudradaman on the Gīrnār rock that is to about A.D. 150. The absence of any record of the Andhras except the name of the king Madharīputa Sirisena or Sakasena (A.D. 180), makes it probable that after Yājñasrī Gantamīputra (A.D. 150) Andhra power waned along the Konkan and South Gujarat seaboard. According to the Purānas the Abhīras succeeded to the dominion of the Andhras. It is therefore possible that the Abhīra king Ísvarasena of Nāsik Inscription XV. was one of the Abhīra conquerors of the Andhras who took from them the West Dakhan. A migration of Abhīras from Ptolemy's Abiria in Upper Sindh through Sindh by sea to the Konkan and thence to Nāsik is within the range of possibility. About fifty years later king Ísvaradatta<sup>1</sup> who was perhaps of the same family as the Abhīra king of the Nāsik inscription seems to have conquered the kingdom of Kshatraps Vijayasena, adding Gujarāt, Kāthiāwāḍa, and part of the Dakhan to his other territory. In honour of this great conquest he may have taken the title Mahākshatraps and struck coins in the Gujarāt Kshatraps style but in an era reckoned from the date of his own conquest. Ísvaradatta's success was shortlived. Only two years later (that is about A.D. 252) the Mahākshatraps Dīmājadāsī won back the lost Kshatraps territory. The fact that Ísvaradatta's recorded coins belong to only two years and that the break between the regular

<sup>1</sup> Ísvaradatta's name ends in *datta* as does also that of Sivadatta the father of king Ísvarasena of the Nāsik inscription.

Kshatrapas Vijayasena and Dāmājadāsī did not last more than two or three years gives support to this explanation.<sup>1</sup>

The following table gives the genealogy of the Western Kshatrapas :


### Chapter V.

WESTERN  
KSHATRAPAS,  
A.D. 70-398.

<sup>1</sup> Dr. Bhagvānīl's suggestion that Vijayasena (A.D. 238-249) was defeated by the Abhir or Alor king Śvaradatta who entered Gujārat from the North Konkan seems open to question. First as regards the suggestion that Vijayasena was the Kshatrapa whose power Śvaradatta overthrew it is to be noticed that though the two coinless years (A.D. 249-251) between the last coin of Vijayasena and the earliest coin of Dāmājadāsī agree with the recorded length of Śvaradatta's supremacy the absence of coins is not in itself proof of a reverse or loss of Kshatrapa power between the reigns of Vijayasena and Dāmājadāsī. It is true the Pandit considers that Śvaradatta's coins closely resemble those of Vijayasena. At the same time he also (Nasik Stat. Acct. 624) thought them very similar to Viradaman's (A.D. 236-238) coins. Viradaman's date so immediately precedes Vijayasena's that in many respects their coins must be closely alike. It is to be noted that A.D. 230-235 the time of rival Kshatrapas among whom Viradaman was one (especially the time between A.D. 236 and 238 during which none of the rivals assumed the title Mahākshatrapa) was suitable to (perhaps was the result of) a successful invasion by Śvaradatta, and that this same invasion may have been the cause of the transfer of the capital, noted in the Periplus (A.D. 247) as having taken place some years before, from Ozene or Ujjain to Munnagura or Junagadh (McCrindle, 114, 122). On the other hand the fact that Vijayasena regarded the title of Mahākshatrapa and handed it to his successor Dāmājadāsī III. would seem to shew that no reverse or humiliation occurred during the coinless years (A.D. 249-251) between their reigns; a supposition which is supported by the flourishing state of the kingdom at the time of the Periplus (A.D. 247) and also by the evidence that both the above Kshatrapas ruled near Karid in Sātra. At the same time if the difference between Viradaman's and Vijayasena's coins is sufficient to make it unlikely that Śvaradatta's can be copies of Viradaman's it seems possible that the year of Śvaradatta's overlordship may be the year A.D. 244 (K. 166) in which Vijayasena's coins bear the title Kshatrapa, and that the assumption of this lower title in the middle of a reign, which with this exception throughout claims the title Mahākshatrapa, may be due to the temporary necessity of acknowledging the supremacy of Śvaradatta. With reference to the Pandit's suggestion that Śvaradatta was an Abhira the fact noted above of a trace of Kshatrapa rule at Karid thirty-one miles south of Sātra together with the fact that they held Aparānta or the Konkan makes it probable that they reached Karid by Chiplūn and the Kunbhārli pass. That the Kshatrapas entered the Dakhan by so southerly a route instead of by some one of the more central Thāna passes, seems to imply the presence of some hostile power in Nasik and Khandesh. This after the close of the second century A.D. could hardly have been the Andhras or Satakarnis. It may therefore be presumed to have been the Andhras' successors the Abhiras. As regards the third suggestion that Kshatrapa Gujārat was overrun from the North Konkan it is to be noted that the evidence of connection between Śvarasena of the Nasik inscription (Cave X. No. 15) and Śvaradatta of the coins is limited to a probable nearness in time and a somewhat slight similarity in name. On the other hand no inscription or other record points to Abhira ascendancy in the North Konkan or South Gujārat. The presence of an Abhira power in the North Konkan seems inconsistent with Kshatrapa rule at Kalyan and Karid in the second half of the third century. The position allotted to Abhira in the Periplus (McCrindle, 113) inland from Surastrene, apparently in the neighbourhood of Thar and Pārkar; the finding of Śvaradatta's coins in Kāthiāvāda (Nasik Gazetteer, XIII. 624); and (perhaps between A.D. 230 and 240) the transfer westwards of the headquarters of the Kshatrapa kingdom seem all to point to the east rather than to the south, as the side from which Śvaradatta invaded Gujārat. At the same time the reference during the reign of Rudrasinha I. (A.D. 181) to the Abhira Rudrabhūti who like his father was Senapati or Commander-in-Chief suggests that Śvaradatta may have been not a foreigner but a revolted general. This supposition, his assumption of the title Mahākshatrapa, and the finding of his coins only in Kāthiāvāda to a certain extent confirm.

**Chapter V.**  
**The Kshatrapa**  
**Family Tree.**

**THE WESTERN KSHATRAPAS.**



## CHAPTER VI.

### THE TRAIKÚTAKAS

(A.D. 250-450.)

THE materials regarding the Traikútakas, though meagre, serve to show that they were a powerful dynasty who rose to consequence about the time of the middle Kshatrapas (v.d. 250). All the recorded information is in two copperplates, one the Kanheri copperplate found by Dr. Bird in 1839,<sup>1</sup> the other a copperplate found at Párdi near Balsár in 1885.<sup>2</sup> Both plates are dated, the Kanheri plate 'in the year two hundred and forty-five of the increasing rule of the Traikútakas'; the Párdi plate in Samvat 207 clearly figured. The Kanheri plate contains nothing of historical importance; the Párdi plate gives the name of the donor as Dahrasena or Dhurasena 'the illustrious great king of the Traikútakas.' Though it does not give any royal name the Kanheri plate expressly mentions the date as the year 245 of the increasing rule of the Traikútakas. The Párdi plate gives the name of the king as 'of the Traikútakas' but merely mentions the date as Sam. 207. This date though not stated to be in the era of the Traikútakas must be taken to be dated in the same era as the Kanheri plate seeing that the style of the letters of both plates is very similar.

The initial date must therefore have been started by the founder of the dynasty and the Kanheri plate proves the dynasty must have lasted at least 215 years. The Párdi plate is one of the earliest copper-plate grants in India. Neither the genealogy nor even the usual three generations including the father and grandfather are given, nor like later plates does it contain a wealth of attributes. The king is called 'the great king of the Traikútakas,' the performer of the *āśvamedha* or horse-sacrifice, a distinction bespeaking a powerful sovereign. It may therefore be supposed that Dahrasena held South Gujarāt to the Narbáda together with part of the North Konkan and of the Ghát and Dakhan plateau.

What then was the initial date of the Traikútakas? Ten Gujarāt copper-plates of the Gurjjaras and Chalukyas are dated in an unknown era with Sam. followed by the date figures as in the Párdi plate and as in Gupta inscriptions. The earliest is the fragment from Sāukhedá in the Baroda State dated Sam 316, which would fall in the reign of Dadda I. of Broach.<sup>3</sup> Next come the two Kaira grants of the Gurjjara king Dadda Prasāntarāga dated Sam. 380 and Sam. 385<sup>4</sup>; and the Sāukhedá grant of Ranagraha dated Sam. 391<sup>5</sup>; then the Kaira grant of the Chalukya king Vijayarāja or Vijayavarman dated Samvatsara 394<sup>6</sup>; then the Bagumrá grant of the Sendraka chief Nikumbhalla-

**Chapter VI.**  
**TRAIKÚTAKAS,**  
A.D. 250-450.  
Two Plates.

Initial Date.

<sup>1</sup> Cave Temple Inscriptions, Bom. Arch. Sur. Sep. Number XI. page 57ff.

<sup>2</sup> J. B. B. R. A. S. XVI. 346. <sup>3</sup> Epigraphia Indica, II. 19. <sup>4</sup> Ind. Ant. XIII. 81ff.

<sup>5</sup> Ep. Ind. II. 20.

<sup>6</sup> Ind. Ant. VII. 248ff. Dr. Bhandárkar (Early Hist. of the Deccan, 42 note 7) has given reasons for believing this grant to be a forgery.

**Chapter VI.**  
**TRAIKUTAKAS,**  
**A.D. 250-450.**  
**Initial Date.**

śakti<sup>1</sup>; two grants from Navsāri and Surat of the Chalukya king Śilāditya Śrīśraya dated 421 and 443<sup>2</sup>; two the Navsāri and Kāvi grants of the Gurjjara king Jayabhata dated respectively Sam. 456 and Sam. 486<sup>3</sup>; and a grant of Pulakesi dated Samvat 490.<sup>4</sup>

Of these the grant dated 421 speaks of Śilāditya Śrīśraya as Yuvarāja or heir-apparent and as the son of Jayasimhavarmman. The plate further shows that Jayasimhavarmman was brother of Vikramāditya and son of Pulakesi Vallabha 'the conqueror of the northern king Harshavardhana.' The name Jayasimhavarmman does not occur in any copperplate of the main line of the Western Chalukyas of the Dakhan. That he is called Mahārāja or great king and that his son Śilāditya is called Yuvarāja or heir-apparent suggest that Jayasimhavarmman was the founder of the Gujarāt branch of the Western Chalukyas and that his great Dakhan brother Vikramāditya was his overlord, a relation which would explain the mention of Vikramāditya in the genealogy of the copper-plate. Vikramāditya's reign ended in A.D. 680 (Saka 602).<sup>5</sup> Supposing our grant to be dated in this last year of Vikramāditya, Samvat 421 should correspond to Saka 602, which gives Saka 181 or A.D. 259 as the initial date of the era in which the plate is dated. Probably the plate was dated earlier in the reign of Vikramāditya giving A.D. 250. In any case the era used cannot be the Gupta era whose initial year is now finally settled to be A.D. 319.

The second grant of the same Śilāditya is dated Samvat 443. In it, both in an eulogistic verse at the beginning and in the text of the genealogy, Vinayāditya Satyāśraya Vallabha is mentioned as the paramount sovereign which proves that by Samvat 443 Vikramāditya had been succeeded by Vinayāditya. The reign of Vinayāditya has been fixed as lasting from Saka 602 to Saka 618 that is from A.D. 680 to A.D. 696-97.<sup>6</sup> Taking Saka 615 or A.D. 693 to correspond with Samvat 443, the initial year of the era is A.D. 250.

The grant of Pulakesivallabha Janāśraya dated Samvat 490, mentions Mangalarasārāja as the donor's elder brother and as the son of Jayasimhavarmman. And a Balsār grant whose donor is mentioned as Mangalarāja son of Jayasimhavarmman, apparently the same as the Mangalarasārāja of the plate just mentioned, is dated Saka 653.<sup>7</sup> Placing the elder brother about ten years before the younger we get Samvat 480 as the date of Mangalarāja, which, corresponding with Saka 653 or A.D. 730-31, gives A.D. 730 minus 480 that is A.D. 250-51 as the initial year of the era in which Pulakesi's grant is dated. In the Navsāri plates, which record a gift by the Gurjjara king Jayabhata in Samvat 456, Dadda II. the donor of the Kaira grants which bear date 380 and 385, is mentioned in the genealogical part at the beginning as 'protecting the lord of Valabhi who had been defeated by the great lord the illustrious Harshadeva.' Now the great Harshadeva or Harsha Vardhana of Kanauj whose court was visited by the Chinese pilgrim Hiuen

<sup>1</sup> Ind. Ant. XVIII. 265ff.

<sup>2</sup> J. B. B. R. A. S. XVI. 1ff. ; Trans. Vienna Or. Congress, 210ff.

<sup>3</sup> Ind. Ant. XIII. 70ff. and V. 109ff.

<sup>4</sup> Trans. Vienna Or. Congress, 210ff.

<sup>5</sup> Fleet's Kānarese Dynasties, 27.

<sup>6</sup> Fleet's Kānarese Dynasties, 27.

<sup>7</sup> Ind. Ant. XIV. 75 and Jour. B. B. R. A. S. XVI. 1ff.

Tsiang between A.D. 629 and 645, reigned according to Reinaud from A.D. 607 to about A.D. 648. Taking A.D. 250 as the initial year of the era of the Kaira plates, Dadda II.'s dates 380 and 385, corresponding to A.D. 630 and 635, fall in the reign of Harshavardhana.

These considerations seem to show that the initial date of the Traikúta era was at or about A.D. 250 which at once suggests its identity with the Chedi or Kalachuri era.<sup>1</sup> The next question is, Who were these Traikútakas. The meaning of the title seems to be kings of Trikúta. Several references seem to point to the existence of a city named Trikúta on the western seaboard. In describing Ragh's triumphant progress the Rámáyana and the Raghuvamśa mention him as having established the city of Trikúta in Aparánta on the western seaboard.<sup>2</sup> Trikútakam or Trikútam, a Sanskrit name for sea salt seems a reminiscence of the time when Trikúta was the emporium from which Konkan salt was distributed over the Dakhan. The scanty information regarding the territory ruled by the Traikútakas is in agreement with the suggestion that Junnar in North Poona was the probable site of their capital and that in the three ranges that encircle Junnar we have the origin of the term Trikúta or Three-Peaked.

Of the race or tribe of the Traikútakas nothing is known. The conjecture may be offered that they are a branch of the Abhíra kings of the Puráṇas, one of whom is mentioned in Inscription XV. of Násik Cave X. which from the style of the letters belongs to about A.D. 150 to 200. The easy connection between Násik and Balsár by way of Peth (Peint) and the nearness in time between the Násik inscription and the initial date of the Traikútakas support this conjecture. The further suggestion may be offered that the founder of the line of Traikútakas was the Íśvaradatta, who, as noted in the Kshatrapa chapter, held the overlordship of Káthiáváḍa as Mahákshatrapa, perhaps during the two years A.D. 248 and 249, a result in close agreement with the conclusions drawn from the examination of the above quoted Traikúta and Chalukya copperplates. As noted in the Kshatrapa chapter after two years' supremacy Íśvaradatta seems to have been defeated and regular Kshatrapa rule restored about A.D. 252 (K. 174) by Dímájadaśrí son of Vijayasena. The unbroken use of the title Mahákshatrapa, the moderate and uniform lengths of the reigns, and the apparently unquestioned successions suggest, what the discovery of Kshatrapa coins at Karád near Sátára in the Dakhan and at Amrávati in the Berárs seems to imply, that during the second half of the third century Kshatrapa rule was widespread and firmly established.<sup>3</sup> The conjecture may be offered that Rudrasena (A.D. 256-272) whose coins have been found in Amrávati in the Berárs spread his power at the expense of the Traikútakas driving them towards the Central Provinces where they established themselves at Tripura and Kálanjara.<sup>4</sup> Further that under Bráhma

**Chapter VI.**

TRAIKUTAKAS,  
A.D. 250-450.

Initial Date.

Their Race  
or Tribe.

<sup>1</sup> Mr. Fleet (Corp. Ins. Ind. III. 9) and Sir A. Cunningham (Arch. Sur. IX. 77) agree in fixing A.D. 250 as the initial date of the Chedi era. Prof. Kielhorn has worked out the available dates and finds that the first year of the era corresponds to A.D. 249-50. Ind. Ant. XVII. 215.

<sup>2</sup> Válmiki's Rámáyana, Ganpat Krishnaji's Edition; Raghuvamśa, IV. 59.

<sup>3</sup> For details see above page 48.

<sup>4</sup> Tripura four miles west of Jabalpur; Kálanjara 140 miles north of Jabalpur.

**Chapter VI.****TRAIKUTAKAS,  
A.D. 250-450.****Their Race  
or Tribe.**

influence, just as the Gurjjaras called themselves descendants of Karna the hero of the Mahābhārata, and the Pallavas claimed to be of the Bhāradvāja stock, the Traikūtakas forgot their Abhira origin and claimed descent from the Hahayas. Again as the Valabhis (A.D. 480-767) adopted the Gupta era but gave it their own name so the rulers of Tripura seem to have continued the original Traikūtaka era of A.D. 248-9 under the name of the Chedi era. The decline of the Kshatrapas dates from about A.D. 300 the rule of Viśvasena the twentieth Kshatrapa son of Bhartṛidāman. The subsequent disruption of the Kshatrapa empire was probably the work of their old neighbours and foes the Traikūtakas, who, under the name of Hahayas, about the middle of the fifth century (A.D. 455-6) rose to supremacy and established a branch at their old city of Trikūṭa ruling the greater part of the Bombay Dakhan and South Gujarāt and probably filling the blank between A.D. 410 the fall of the Kshatrapas and A.D. 500 the rise of the Chālukyas.

About 1887 Pandit Bhagvānlāl secured nine of a hoard of 500 silver coins found at Daman in South Gujarāt. All are of one king a close imitation of the coins of the latest Kshatrapas. On the obverse is a bust of bad workmanship and on the reverse are the usual Kshatrapa symbols encircled with the legend:

महाराजेंद्रवर्मपुत्रपरमवैष्णवश्रीमहाराजरुद्रगणः

Mahārājendrayanaputra Parama Vaiṣṇava  
Śrī Mahārāja Rudragana.

The devoted Vaiṣṇava the illustrious king Rudragana  
son of the great king Indrayama

At Karād, thirty-one miles south of Sātara, Mr. Justice Newton obtained a coin of this Rudragana, with the coins of many Kshatrapas including Viśvasinha son of Bhartṛidāman who ruled up to A.D. 300. This would favour the view that Rudragana was the successful rival who wrested the Dakhan and North Konkan from Viśvasinha. The fact that during the twenty years after Viśvasinha (A.D. 300-320) none of the Kshatrapas has the title Mahākshatrapa seems to show they ruled in Kāthiāvāda as tributaries of this Rudragana and his descendants of the Traikūtaka family. The Dahrasena of the Pardi plate whose inscription date is 207, that is A.D. 157, may be a descendant of Rudragana. The Traikūtaka kingdom would thus seem to have flourished at least till the middle of the fifth century. Somewhat later, or at any rate after the date of the Kauheri plate (215 = A.D. 195), it was overthrown by either the Mauryas or the Guptas.<sup>1</sup>

<sup>1</sup> That the era used by the Gurjjaras and Chālukyas of Gujarāt was the Chedi era may be regarded as certain since the discovery of the Sāṅkheḍā grant of Nīrinhiḷaka (Ep. Ind. II 21), who speaks of a certain Saṅkarana as his overlord. Palaeographically this grant belongs to the sixth century, and Dr. Bühler has suggested that Saṅkarana is the Chedi Saṅkaragana whose son Buddhārāja was defeated by Mangalīśa some time before A.D. 602 (Ind. Ant. XIX 16). If this is accepted, the grant shows that the Chedis or Kalachuris were in power in the Nerbāda valley during the sixth century, which explains the prevalence of their era in South Gujarāt. Chedi rule in the Nerbāda valley must have come to an end about A.D. 580 when Dadda I. established himself at Broach. It being established that the Kalachuris once ruled in South Gujarāt, there is no great difficulty in the way of identifying the Traikūtakas with them. The two known Traikūtaka grants are dated in the third century of their era, and belong palaeographically to the fifth century A.D. Their era, therefore, like that of the Kalachuris, begins in the third century A.D.: and it is simpler to suppose that the two eras were the same than

## Chapter VI.

TRAIKŪṬAKAS,  
A.D. 250-450.

that two different eras, whose initial points were only a few years apart, were in use in the same district. Now that the Saka and the Vikrama eras are known to have had different names at different times, the change in the name of the era offers no special difficulty. This identification would carry back Kalachuri rule in South Gujurāt to at least A.D. 455-6, the date of the Pārdi grant and it is worth noting that Varahamihira (Br. Samh. XIV. 20) places the Hauhays or Kalachuris in the west along with the Aparāntakas or Konkanis.

Though the name Traikūṭaka means of Triakūta, the authorities quoted by Dr Bhagvān-lāl do not establish the existence of a city called Triakuta. They only vouch for a mountain of that name somewhere in the Western Ghāts, and there is no evidence of any special connection with Junnar. Further, the word Triakūṭakam seems to mean rock-salt, not sea-salt, so that there is here no special connection with the Western coast. Wherever Triakūṭa may have been, there seems no need to reject the tradition that connects the rise of the Kalachuris with their capture of Kalanjara (Cunningham's Arch. Surv. IX 77ff), as it is more likely that they advanced from the East down the Nerbuddā than that their original seats were on the West Coast, as the Western Indian inscriptions of the third and fourth centuries contain no reference either to Traikūṭakas or to Junnar or other western city as Triakuta.

With reference to the third suggestion that the Traikūṭakas twice overthrew the Kshatrapas, under Śvarādatta in A.D. 248 and under Rudragana in A.D. 310-320, it is to be noted that there is no evidence to show that Śvarādatta was either an Abhira or a Traikūṭaka and that the identification of his date with A.D. 248-250 seems less probable than with either A.D. 244 or A.D. 236 (Compare above Footnote page 53). Even if Śvarādatta's supremacy coincided with A.D. 250 the actual date of the Traikūṭaka era, it seems improbable that a king who reigned only two years and left no successor should have had any connection with the establishment of an era which is not found in use till two centuries later. As regards Rudragana it may be admitted that he belonged to the race or family who weakened Kshatrapa power early in the fourth century A.D. At the same time there seems no reason to suppose that Rudragana was a Traikūṭaka or a Kalachuri except the fact that his name, like that of Śaṅkaragana, is a compound of the word *gana* and a name of Śiva, while the irregular posthumous use of the title Mahīkshatrapa among the latest (23rd to 26th) Kshatrapas favours the view that they remained independent till their overthrow by the Guptas about A.D. 410. The conclusion seems to be that the Traikūṭaka and the Kalachuri eras are the same namely A.D. 248-9; that this era was introduced into Gujurāt by the Traikūṭakas who were connected with the Hauhays; and that the introduction of the era into Gujurāt did not take place before the middle of the fifth century A.D. — (A. M. T. J.)


## CHAPTER VII.

## THE GUPTAS

(G. 90-149; A.D. 410-470)

Chapter VII.  
THE GUPTAS,  
A.D. 410-470

AFTER the Kshatrapas (A.D. 120-410) the powerful dynasty of the Guptas established themselves in Gujarát. So far as the dynasty is connected with Gujarát the Gupta tree is :



According to the Puráṇas<sup>1</sup> the original seat of the Guptas was between the Ganges and the Jamna. Their first capital is not determined. English writers usually style them the Guptas of Kanauj. And though this title is simply due to the chance that Gupta coins were first found at Kanauj, further discoveries show that the chief remains of Gupta records and coins are in the territory to the east and south-east of Kanauj. Of the race of the Guptas nothing is known. According to the ordinances of the Smṛitis or Sacred Books,<sup>2</sup> the terminal *gupta* belongs only to Vaiśyas a class including shepherds

<sup>1</sup> Vayu Purāṇa, Wilson's Works, IX. 210n.

<sup>2</sup> Vishnu Purāṇa, III Chapter 10 Verse 9; Burnell's Manu, 20. Mr. Fleet (Corp. Ins. Ind. III. Ins. 11 note 1) quotes an instance of a Brāhman named Brāhmagupta.

cultivators and traders. Of the first three kings, Gupta Ghatotkacha and Chandragupta I., beyond the fact that Chandragupta I. bore the title of Mahārājādhirāja, neither descriptive titles nor details are recorded. As the fourth king Samudragupta performed the long-neglected horse-sacrifice he must have been Brahmanical in religion. And as inscriptions style Samudragupta's three successors, Chandragupta II. Kumāragupta and Skandagupta, Parama Bhāgavata, they must have been Smārta Vaiṣṇavas, that is devotees of Vishnu and observers of Vedic ceremonies.

The founder of the dynasty is styled Gupta. In inscriptions this name always appears as Sri-gupta which is taken to mean protected by Śrī or Lakshmi. Against this explanation it is to be noted that in their inscriptions all Gupta's successors have *π* Śrī before their names. The question therefore arises; If Śrī forms part of the name why should the name Śrigupta have had no second Śrī prefixed in the usual way. Further in the inscriptions the lineage appears as Gupta-vamśa that is the lineage of the Guptas never Śriguptavamśa<sup>1</sup>; and when never dates in the era of this dynasty are given they are conjoined with the name Gupta never with Śrigupta.<sup>2</sup> It may therefore be taken that Gupta not Śrigupta is the correct form of the founder's name.<sup>3</sup>

Gupta the founder seems never to have risen to be more than a petty chief. No known inscription gives him the title *Mahārājādhirāja* Supreme Ruler of Great Kings, which all Gupta rulers after the founder's grandson Chandragupta assume. Again that no coins of the founder and many coins of his successors have been discovered makes it probable that Gupta was not a ruler of enough importance to have a currency of his own. According to the inscriptions Gupta was succeeded by his son Ghatotkacha a petty chief like his father with the title of Mahārāja and without coins.

Chandragupta I (A.D. 349-369 [?]), the son and successor of Ghatotkacha, is styled Mahārājādhirāja either because he himself became powerful, or, more probably, because he was the father of his very powerful successor Samudragupta. Though he may not have gained the dignity of "supreme ruler of great kings" by his own successes Chandragupta I. rose to a higher position than his predecessors. He was connected by marriage with the Lichchhavi dynasty of Tirhut an alliance which must have been considered of importance since his son Samudragupta puts the name of his mother Kumāradevi on his coins, and always styles himself daughter's son of Lichchhavi.<sup>4</sup>

## Chapter VII.

THE GUPTAS,  
A. D. 410-470.

The Founder  
Gupta,  
A. D. 319-322 (?).

Ghatotkacha,  
A. D. 322-349 (?).

Chandragupta I.  
A. D. 349-369 (?).

<sup>1</sup> Fleet's Corp. Ins. Ind. III Ins. 53 line 7.

<sup>2</sup> Compare Skandagupta's Junāgaḥ Inscription line 15, Ind. Ant. XIV.; Cunningham's Arch. Sur. X. 113; Fleet's Corp. Ins. Ind. III. Ins. 59.

<sup>3</sup> Compare Mr. Fleet's note in Corp. Ins. Ind. III Ins. 8.

<sup>4</sup> Fleet's Corp. Ins. Ind. III. 135. Mr. Fleet believes that the Lichchhavi family concerned was that of Nepāl, and that they were the real founders of the era used by the Guptas. Dr. Bühler (Vienna Or. Journal, V. Pt. 3) holds that Chandragupta married into the Lichchhavi family of Pataliputra and became king of that country in right of his wife. The coins which bear the name of Kumāradevi are by Mr. Smith (J. R. A. S. (N. S.) XXI. 63) and others assigned to Chandragupta I., reading the reverse legend *Lichchhavayak* The Lichchhavis in place of Dr. Bhagvānlal's *Lichchhavayak* Daughter's son of Lichchhavi. On the Kacha coins see below page 62 note 2.

The Lichchhavis claim to be sprung from the solar dynasty. Manu (Burnell's Manu,

**Chapter VII.**

THE GUPTAS,  
A.D. 410-470.

Samudragupta,  
A.D. 370-395.

Samudragupta was the first of his family to strike coins. His numerous gold coins are, with a certain additional Indian element, adopted from those of his Indo-Skythian predecessor. The details of the royal figure on the obverse are Indian in the ornaments, large earrings, and headdress; they are Indo-Skythian in the tailed coat, long boots, and straddle. The goddess on the reverse of some coins with a fillet and cornucopia is an adaptation of an Indo-Skythian figure, while the lotus-holding Ganges on an alligator and the standing Glory holding a fly-kipper on the reverse of other coins are purely Indian.<sup>1</sup>

*His Coins*

A noteworthy feature of Samudragupta's coins is that one or other of almost all his epithets appears on each of his coins with a figure of the king illustrating the epithet. Coins with the epithet *Sarvarājachchhetra* De-royer-of-all-kings have on the obverse a standing king stretching out a banner topped by the wheel or disc of universal supremacy.<sup>2</sup>

Coins with the epithet *Apratiratha* Peerless have on the obverse a standing king whose left hand rests on a bow and whose right hand holds a horse-lying unaimed arrow and in front an eagle or Garuda standard symbolizing the unrivalled supremacy of the king, his arrow no longer wanted, his standard waving unchallenged. On the obverse is the legend :

308) describes them as descended from a degraded Kshatriya. Beal (R. A. S. N. S. XIV. 339) would identify them with an early wave of the Yuchi or Kushans; Smith (J. R. A. S. XX. 55 n. 2) and Howitt (J. R. A. S. XX. 355-366) take them to be a Kolarian or local tribe. The fame of the Lichchhavis of Vaisali or Passalia between Patna and Tirhut goes back to the time of Gautama Buddha (B.C. 480) in whose funeral rites the Lichchhavis and their neighbours and associates the Mallas took a prominent share (Rockhill's Life of Buddha, 62-63, 115, 203. Compare Legge's Fa Hien, 71-76; Beal's Buddhist Records, II. 67, 70, 73, 77 and 81 note). According to Buddhist writings the first king of Thibet (A.D. 50) who was elected by the chiefs of the South Thibet tribes was a Lichchhavi the son of Prasenajit of Kosala (Rockhill's Life of Buddha, 208). Between the seventh and ninth centuries (A.D. 635-854) a family of Lichchhavis was ruling in Nepal (Fleet's Corp. Ins. Ind. III. 131). The earliest historical member of the Nepal family is Jayadeva I whose date is supposed to be about A.D. 330 to 355. Mr. Fleet (Ibid., 135) suggests that Jayadeva's reign began earlier and may be the epoch from which the Gupta era of A.D. 318-319 is taken. He holds (Ibid., 136) that in all probability the so-called Gupta era is a Lichchhavi era.

<sup>1</sup> The figure of the Ganges standing on an alligator with a stalked lotus in her left hand on the reverse of the gold coins of Samudragupta the fourth king of the dynasty may be taken to be the Sri or Luck of the Guptas. Compare Smith's Gupta Coinage, J. Beng. A. S. LIII. Plate I. Fig. 10. J. R. A. S. (N. S.) XXI. Pl. I. 2.

<sup>2</sup> The presence of the two letters क च that is *ka cha* on the obverse under the arm of the royal figure, has led the late Mr. Thomas, General Cunningham, and Mr. Smith to suppose that the coins belonged to Ghatotkacha, the last two letters of the name being the same. This identification seems improbable. Ghatotkacha was never powerful enough to have a currency of his own. *Sarvarājachchhetra* the attribute on the reverse is one of Samudragupta's epithets, while the figure of the king on the obverse grasping the standard with the disc, illustrating the attribute of universal sovereignty, can refer to none other than Samudragupta the first very powerful king of the dynasty. Perhaps the *Kacha* or *Kacha* on these coins is a pet or child name of Samudragupta. Mr. Rapson (Numismatic Chron. 3rd Ser. XI. 48ff) has recently suggested that the *Kacha* coins belong to an elder brother and predecessor of Samudragupta. But it seems unlikely that a ruler who could justly claim the title Destroyer-of-all-kings should be passed over in silence in the genealogy. Further, as is remarked above, the title *Sarvarājachchhetra* belongs in the inscriptions to Samudragupta alone: and the fact that in his lifetime Samudragupta's father chose him as successor is against his exclusion from the throne even for a time.

<sup>3</sup> Smith's Gupta Coinage in J. R. A. S. (N. S.) XXI. Pl. I. 10.

अप्रतिरथराजन्यकीर्ति (र) मम विजयते.

Apratiratharājanyakīrti(r)mama vijayate.<sup>1</sup>

Triumphant is the glory of me the unvalled sovereign.

Coins with the attribute *Kṛitānta paraśu* the Death-like-battle-axe have on the obverse a royal figure grasping a battle-axe.<sup>2</sup> In front of the royal figure a boy, perhaps Samudragupta's son Chandragupta, holds a standard. Coins with the attribute *Aśvamedhapardakramah* Able-to-hold-a-horse-sacrifice have on the obverse a horse standing near a sacrificial post *yūpa* and on the reverse a female figure with a fly-flap.<sup>3</sup> The legend on the obverse is imperfect and hard to read. The late Mr. Thomas restores it :

नवजमधः राजाधिराज पृथिवीं जियत्य-

Navajamadhah rājādhirāja pṛthivīm jiyaty-

Horse sacrifice, after conquering the earth, the great king (performs).

Coins with the legend *Lichchhaveyah*, a coin abbreviation for *Lichchhavidandhutra* Daughter's son of Lichchhavi (?), have on the obverse a standing king grasping a javelin.<sup>4</sup> Under the javelin hand are the letters *Chandraguptah*. Facing the king a female figure with trace of the letters *Kumāradevi* seems to speak to him. These figures of his mother and father are given to explain the attribute Lichchhaveya or seion of Lichchhavi. This coin has been supposed to belong to Chandragupta I. but the attribute *Lichchhaveyah* can apply only to Samudragupta.

A fuller source of information regarding Samudragupta remains in his inscription on the Allahabad Pillar.<sup>5</sup> Nearly eight verses of the first part are lost. The first three verses probably described his learning as what remains of the third verse mentions his poetic accomplishments, and line 27 says he was skilled in poetry and music, a trait further illustrated by what are known as his Lyrist coins where he is shown playing a lute.<sup>6</sup> The fourth verse says that during his lifetime his father chose Samudragupta to rule the earth from among others of equal birth. His father is mentioned as pleased with him and this is followed by the description of a victory during which several opponents are said to have submitted. The seventh verse records the sudden destruction of the army of Achyuta Nāgasena and the punishment inflicted on a descendant of the Kota family.

Lines 19 and 20 record the conquest, or submission, of the following South Indian monarchs, Mahendra of Kosala, Vyāghrarāja of Mahā Kāntīra,<sup>7</sup> Mularāja of Kanrāṭṭa,<sup>8</sup> Svamidatta of Paishatapura Mahendra-Giri and Auttūra<sup>9</sup>, Danana of Airāṇḍapallaka, Vishnu of Kāñchī, Nilarāja Śāpāvamukta,<sup>10</sup> Hastivarman of Veṅgī, Ugrasena of Pālaka,<sup>11</sup>

## Chapter VII.

THE GUPTAS,  
A.D. 410-470.

Samudragupta,  
A.D. 370-395.

His Allahabad  
Inscription.

<sup>1</sup> Compare Wilson's *Ariana Antiqua*, Pl. XVIII. Fig. 8, which has the same legend with me for mama. <sup>2</sup> Smith J. R. A. S. (N. S.) XXI. Pl. I. 11, 12.

<sup>3</sup> Smith J. R. A. S. (N. S.) XXI. Pl. I. 4.

<sup>4</sup> Smith J. R. A. S. (N. S.) XXI. Pl. I. Mr. Smith reads *Lichchhavayah* (the Lichchhavis) and assigns this type to Chandragupta I.

<sup>5</sup> *Corpus Ins. Ind.* III. 1.

<sup>6</sup> Smith J. R. A. S. (N. S.) XXI. Pl. I. 5, 6.

<sup>7</sup> Apparently South Kosala, the country about Raipur and Chhattisgarh.

<sup>8</sup> Fleet reads Mantarāja of Kerala.

<sup>9</sup> Fleet divides the words differently and translates "Mahendra of Pishatapura, Svamidatta of Kottūra on the hill."

<sup>10</sup> Fleet reads "Nilarāja of Avamukta."

<sup>11</sup> Fleet reads Palakka or Pālakka.

## Chapter VII.

THE GUPTAS,  
A.D. 410-470.Samudragupta,  
A.D. 370-395.

Kubera of Daivarāshīra, and Dhananjaya of Kausthalapura. Line 21 gives a further list of nine kings of Aryāvarta exterminated by Samudragupta :

Rudradeva.	Chandravarman.	Achyuta.
Matila.	Ganapatināga.	Nandin.
Nāgalatta.	Nāgasena.	Balavarman.

As no reference is made to the territories of these kings they may be supposed to be well known neighbouring rulers. General Cunningham's coins and others obtained at Mathurā show that the fifth ruler Ganapatināga was one of the Nāga kings of Gwālor and Narwār.<sup>1</sup> The inscription next mentions that Samudragupta took into his employ the chiefs of the forest countries. Then in lines 22 and 23 follows a list of countries whose kings gave him tribute, who obeyed his orders, and who came to pay homage. The list includes the names of many frontier countries and the territories of powerful contemporary kings. The frontier kingdoms are :<sup>2</sup>

Samatata. Davāka. Kāmarūpa. Nepāla. Karttika.

The Indian kingdoms are :<sup>3</sup>

Malava.	Mādraka.	Sanakānika.
Arjunayana.	Abhira.	Kāka.
Yaudheya.	Prājnya.	Kharaparika.

Mention is next made of kings who submitted, gave their daughters in marriage, paid tribute, and requested the issue of the Garuḍa or Eagle charter to secure them in the enjoyment of their territory.<sup>4</sup> The tribal names of these kings are :<sup>5</sup>

Devaputra.	Saka.
Shāhi.	Mamda.
Shāhānushāhi.	Samhalaka.

Island Kings.

<sup>1</sup> Arch. Surv. II. 310; J. B. A. S. 1865 115-121.

<sup>2</sup> Samatata is the Ganges delta. Davāka may, as Mr. Fleet suggests, be Dacca for Karttika. Mr. Fleet reads Kantipura, otherwise Cuttack might be intended.

<sup>3</sup> For the Malavas see above page 21. The Arjunayanas can hardly be the Kalachuris as Mr. Fleet (C. I. I. III. 10) has suggested, as Varaha Mihira (Br. S. XIV. 25) places the Arjunayanas in the north near Trigarta, and General Cunningham's coin (Coins of Ancient India, 90) points to the same region. The Yaudheyas lived on the lower Sutlej see above page 36. The Mādrakas lived north-east of the Yaudheyas between the Chenab and the Sutlej (Cunningham Anc. Geog. 185). The Abhiras must be those on the south-east border of Sindh. The Prājnyas do not appear to be identifiable. A Sanakānika Mahārāja is mentioned (C. I. I. III. 3) as dedicating an offering at Udayagiri near Bhilsa, but we have no clue to the situation of his government. The name of his grandfather, Chhagalaga, has a Turki look. Kāka may be Kakapur near Bithūr (Cunningham Anc. Geog. 380). Kharaparika has not been identified—(A. M. T. J.)

<sup>4</sup> Mr. Fleet translates "(giving) Garuḍa-tokens, (surrendering) the enjoyment of their own territories."

<sup>5</sup> The first three names Devaputra, Shāhi, and Shāhānushāhi, belong to the Kushān dynasty of Kanishka (A.D. 78). Shāhānushāhi is the oldest, as it appears on the coins from Kanishka downwards in the form Shahanushah (Stein in Babylonian and Oriental Record, I. 163). It represents the old Persian title Shahanshah or king of kings. Shāhi, answering to the simple Shah, appears to be first used alone by Vasudeva (A.D. 128-176). The title of Devaputra occurs first in the inscriptions of Kanishka. In the present inscription all three titles seem to denote divisions of the Kushān empire in

The inscribed pillar is said to have been set up by the great Captain or Dandanāyaka named Tilabhattachāyaka.

This important inscription shows that Samudragupta's dominions included Mathurā, Oudh, Gorakhpur, Allahābād, Benares, Behār, Tirhut, Bengal, and part of East Rājputāna. The list of Dakhan and South Indian kingdoms does not necessarily imply that they formed part of Samudragupta's territory. Samudragupta may have made a victorious campaign to the far south and had the countries recorded in the order of his line of march. The order suggests that he went from Behār, by way of Gayā, to Kosala the country about the modern Raipur in the Central Provinces, and from Kosala, by Ganjam and other places in the Northern Circars, as far as Kāñchī or Conjeveram forty-six miles south-west of Madras. Malwa is shown in the second list as a powerful allied kingdom. It does not appear to have formed part of Samudragupta's territory nor, unless the Sakas are the Kshatrapas, does any mention of Gujarāt occur even as an allied state.

Samudragupta was succeeded by his son Chandragupta II. whose mother was the queen Dattadevī. He was the greatest and most powerful king of the Gupta dynasty and added largely to the territory left by Samudragupta. His second name Vikramāditya or the Sun of Prowess appears on his coins. Like his father Chandragupta II. struck gold coins of various types. He was the first Gupta ruler who spread his power over Mālwa and Gujarāt which he apparently took from the Kshatrapas as he was the first Gupta to strike silver coins and as his silver coins of both varieties the eastern and the western are modifications of the Kshatrapa type. The expedition which conquered Mālwa seems to have passed from Allahābād by Bundelkhand to Bhilsā and thence to Mālwa. An undated inscription in the Udayagiri caves at Vidishā (the modern Besnagar) near Bhilsā records the making of a cave of Mahādeva by one Śaka of the Kautsa gotra and the family name of Vīrasena, a poet and native of Pataliputra who held the hereditary office of minister of peace and war *sandhivigrahika*, and who is recorded to have arrived with the king who was intent upon conquering the whole earth.<sup>1</sup> A neighbouring cave bears an inscription of a feudatory of Chandragupta who was chief of Sanakīmika.<sup>2</sup> The chief's name is lost, but the names of his father Vishnudasa and of his grandfather Chhugulaya remain. The date is the eleventh of the bright half of

## Chapter VII.

THE GUPTAS,  
A.D. 410-470.

Samudragupta,  
A.D. 370-395.

Chandragupta II.  
A.D. 395-415.

India. The title of Shah was continued by the Turks (A.D. 600?-900) and Brahmins (A.D. 900-1000) of Kabul (Alberuni, II. 10) and by the Shahis (Elliot, I. 138) of Alor in Sindh (A.D. 490?-631). Unless it refers to the last remnants of the Gujarāt Mahāksatrapas the word Saka seems to be used in a vague sense in reference to the non-Indian tribes of the North-West frontier. The Murundas may be identified with the Murundas of the Native dictionaries, and hence with the people of Lampāka or Langhān twenty miles north-west of Jalalabad. It is notable that in the fifth century A.D. Jayanātha, Mahārāja of Uchchakalpa (not identified) married a Murundadevī (Corp. Ins. Ind. III. 128, 131, 136).

The mention of the king of Simhala and the Island Kings rounds off the geographical picture. Possibly after the Chinese fashion presents from these countries may have been magnified into tribute. Or Simhala may here stand, not for Ceylon, but for one of the many Simhapuras known to Indian geography. Sihor in Kāthiavāda, an old capital, may possibly be the place referred to. The Island Kings would then be the chiefs of Cutch and Kāthiavāda.—(A. M. T. J.)

<sup>1</sup> Corp. Ins. Ind. III. Ins. 6.

<sup>2</sup> Corp. Ins. Ind. III. Ins. 3.

Chaj	Chapter VII.
THE	THE GUPTAS,
A.D.	A.D. 410-470.
Samf	Chandragupta II.
A.D.	A.D. 395-415.

Ashvādhya Samvatsara 82 (A.D. 401). From this Chandragupta's conquest of Vidiśā may be dated about Samvatsara 80 (A.D. 399) or a little earlier.

A third inscription is on the railing of the great Sāñchi stūpa.<sup>1</sup> It is dated the 14th day of Bhādrapada Samvat 93 (A.D. 412) and records the gift of 25 *dīnāras* and something called *Īśvaravāsaka* (perhaps a village or a field) to the monks of the great monastery of Kakanādabojasrī for the daily maintenance of five *bhikshus* and the burning of a lamp in the *ratnagriha* or shrine of the Buddhist *triratna*, for the merit of the supreme king of great kings Chandragupta who bears the popular name of Devarāja or god-like.<sup>2</sup> The donor a feudatory of Chandragupta named Āmrakārdava is described as having the object of his life gratified by the 'favours of the feet of the supreme ruler of great kings the illustrious Chandragupta, and as showing to the world the hearty loyalty of a good feudatory. Āmrakārdava seems to have been a chief of consequence as he is described as winning the flag of glory in numerous battles. The name of his kingdom is also recorded. Though it cannot now be made out the mention of his kingdom makes it probable that he was a stranger come to pay homage to Chandragupta. The reference to Chandragupta seems to imply he was the ruler of the land while the two other inscriptions show that his rule lasted from about 80 (A.D. 399) to at least 93 (A.D. 412). During these years Chandragupta seems to have spread his sway to Ujjain the capital of west Mālwa, of which he is traditionally called the ruler. From Ujjain by way of Bāgh and Tōṇḍa in the province of Rāṭh he seems to have entered South Gujarāt and to have passed from the Branch coast to Kāthiavāḍa. He seems to have wrested Kāthiavāḍa from its Kshatrapa rulers as he is the first Gupta who struck silver coins and as his silver coins are of the then current Kshatrapa type. On the obverse is the royal bust with features copied from the Kshatrapa face and on the reverse is the figure of a peacock, probably chosen as the bearer of Kūrtikasvāmi the god of war. Round the peacock is a Sanskrit legend. This legend is of two varieties. In Central Indian coins it runs:

श्री गुप्तकुलस्य महाराजाधिराज श्री चंद्रगुप्तविक्रमादिकस्य

Srī Guptakulasya Mahārājādhirāja Śrī Chandraguptavikramādikasya,  
(Coin) of the king of kings the illustrious Chandragupta Vikramādika,  
of the family of the illustrious Gupta.<sup>3</sup>

In the very rare Kāthiavāḍa coins, though they are similar to the above in style, the legend runs:

परमभागवत महाराजाधिराज श्री चन्द्रगुप्त विक्रमादित्य

Paramabhāgavata Mahārājādhirāja Śrī Chandragupta Vikramāditya.

The great devotee of Vishnu the supreme ruler of great kings,  
the illustrious Chandragupta Vikramāditya.<sup>4</sup>

Several gold coins of Chandragupta show a young male figure behind the king with his right hand laid on the king's shoulder. This youthful figure is apparently Chandragupta's son Kumāragupta who may have acted as Yuvarāja during the conquest of Mālwa.

<sup>1</sup> Corp. Ins. Ind. III. Ins. 5.

<sup>2</sup> Mr. Fleet (Corp. Ins. Ind. III. Ins. 33) prefers to take Devarāja to be the name of Chandragupta's minister.

<sup>3</sup> J. R. A. S. (N. S.) XXI. 120.

<sup>4</sup> J. R. A. S. (N. S.) XXI. 121.

The rareness of Chandragupta's and the commonness of Kumāragupta's coins in Kāthiāváḍa, together with the date 90 (A.D. 409) on some of Kumāragupta's coins make it probable that on their conquest his father appointed Kumāragupta viceroy of Gujarāt and Kāthiāváḍa. .

As the first Gupta was a chief of no great power or influence it is probable that though it is calculated from him the Gupta era was established not by him but by his grandson the great Chandragupta II.<sup>1</sup> This view is confirmed by the absence of dates on all existing coins of Chandragupta's father Samudragupta. It further seems probable that like the Málavas in B.C. 57 and the Kshatrapas in A.D. 78 the occasion on which Chandragupta established the Gupta era was his conquest of Málwa. The Gupta era did not remain long in use. After the fall of Gupta power (A.D. 470) the old Málava era of B.C. 57 was revived. The conjecture may be offered that, in spite of the passing away of Gupta power, under his title of Vikramāditya, the fame of the great Gupta conqueror Chandragupta II. lived on in Málwa and that, drawing to itself tales of earlier local champions, the name Vikramāditya came to be considered the name of the founder of the Málava era.<sup>2</sup>

Working back from Gupta Samvat 80 (A.D. 400) the date of Chandragupta's conquest of Málwa we may allot 1 to 12 (A.D. 319-332) to the founder Gupta; 12 to 29 (A.D. 332-349) to Gupta's son Ghatotkacha; 29 to 49 (A.D. 349-369) to Ghatotkacha's son Chandragupta I.; and 50 to 75 (A.D. 370-395) to Chandragupta's powerful son Samudragupta who probably had a long reign. As the latest known date of Chandragupta II. is 93 (A.D. 413) and as a Bilsal inscription<sup>3</sup> of his successor Kumāragupta is dated 96 (A.D. 416) the reign of Chandragupta II. may be calculated to have lasted during the twenty years ending 95 (A.D. 415).

<sup>1</sup> Mr. Fleet (Corp. Ins. Ind. III. Introd. 13 off) argues that the era was borrowed from Nepal after Chandragupta I. married his Lichchhavi queen. Dr. Bühler thinks there is no evidence of this, and that the era was started by the Guptas themselves (Vienna Or. JI. V. Pt. 3).

<sup>2</sup> The further suggestion may be offered that if as seems probable Dr. Bhagavānśukla is correct in considering Chandragupta I. to be the founder of the Gupta era this high honour was due not to his conquest of Málwa but to some success against the Indo-Skythians or Sakas of the Panjab. The little more than nominal suzerainty claimed over the Devaputras, Shilas, and Shahanushilas in Chandragupta's father's inscription shows that when he came to the throne Chandragupta found the Saka power practically unbroken. The absence of reference to conquests is no more complete in the case of the Panjab than it is in the case of Gujarāt or of Kāthiāváḍa which Chandragupta is known to have added to his dominions. In Kāthiāváḍa, though not in Gujarāt, the evidence from coins is stronger than in the Panjab. Still the discovery of Chandragupta's coins (J.B. A. S. XXI. 5 note 1) raises the presumption of conquests as far north and west as Panipat and as Ludhiana (in the heart of the Panjab). Chandragupta's name Devavāḷja may, as Pandit Bhagavānśukla suggests, be taken from the Saka title Devaputra. Further, the use of the name Vikramāditya and of the honorific Śrī is in striking agreement with Heron's statement (Sachau, II. 6) that the conqueror of the Sakas was named Vikramāditya and that to the conqueror's name was added the title Śrī. Mr. Fleet (Corp. Ins. Ind. III. 37 note 2) holds it not improbable that either Chandragupta I. or II. defeated the Indo-Skythians. The fact that Chandragupta I. was not a ruler of sufficient importance to issue coins and that even after his son Samudragupta's victories the Sakas remained practically independent make it almost certain that if any subjection of the Sakas to the Guptas took place it happened during the reign of Chandragupta II.

<sup>3</sup> Corp. Ins. Ind. III. Ins. 10.

## Chapter VII.

THE GUPTAS,  
A.D. 410-470.

Chandragupta II.  
A.D. 396-415.

## Chapter VII.

Cha  
The  
A.D.  
Sam  
A.D.

THE GUPTAS,  
A.D. 410-470.  
Kumārāgupta,  
A.D. 416-453.

Chandragupta I. was succeeded by his son Kumārāgupta whose mother was the queen Dhruva-Devī. On Kumārāgupta's coins three titles occur: Mahendra, Mahendra-Vikrama, and Mahendraditya. As already noticed the circulation of Kumārāgupta's coins in Kāthiāvāda during his father's reign makes it probable that on their conquest his father appointed him viceroy of Kāthiāvāda and Gujarāt. Kumārāgupta appears to have succeeded his father about 96 (A.D. 416). An inscription at Mankuwar near Prayāga shows he was ruling as late as 129 (A.D. 459) and a coin of his dated 130 (A.D. 450) adds at least one year to his reign. On the other hand the inscription on the Girnār rock shows that in 137 (A.D. 457) his son Skandagupta was king. It follows that Kumārāgupta's reign ended between 130 and 137 (A.D. 450-457) or about 133 (A.D. 453).

None of Kumārāgupta's four inscriptions gives any historical or other details regarding him.<sup>1</sup> But the number and the wide distribution of his coins make it probable that during his long reign he maintained his father's dominions intact.

Large numbers of Kumārāgupta's coins of gold silver and copper have been found. The gold which are of various types are inferior in workmanship to his father's coins. The silver and copper coins are of two varieties, eastern and western. Both varieties have on the obverse the royal bust in the Kshatrapa style of dress. In the western pieces the bust is a copy of the moustached Kshatrapa face with a corrupted version of the corrupt Greek legend used by the Kshatrapas. The only difference between the obverses of the Western Gupta and the Kshatrapa coins is that the date is in the Gupta instead of in the Kshatrapa era. On the reverse is an ill formed peacock facing front as in Chandragupta II.'s coins. The legend runs:

परम भागवत महाराजाधिराज श्री कुमारगुप्त महेंद्रादित्य.

Paramabhāgavata Maharājādhirāja Śrī Kumārāgupta  
Mahendraditya.

The great Vishnava the supreme ruler of great kings,  
the illustrious Kumārāgupta Mahendraditya.<sup>2</sup>

In Kumārāgupta's eastern silver and copper coins the bust on the obverse has no moustache nor is there any trace of the corrupt Greek legend. The date is in front of the face in perpendicular numerals one below the other instead of behind the head as in the Kshatrapa and Western Kumārāgupta coins. On the reverse is a well-carved peacock facing front with tail feathers at full stretch. Round the peacock runs the clear cut legend:

विजितावनिरवनिपति कुमारगुप्तो देवं जयति.

Vijitāvaniravaniṇipati Kumārāgupto devaṃ jayati.

This legend is hard to translate. It seems to mean:

Kumārāgupta, lord of the earth, who had conquered the  
kings of the earth, conquers the Deva.

<sup>1</sup> Corp. Ins. Ind. III. Ins. 8, 9, 10 and 11.

<sup>2</sup> J. R. A. S. (N. S.) XXI. 123.

Probably the Dova whose name suggested the antithesis between the kings of the earth and the gods was one of the Devaputra family of Indo-Skythian rulers.<sup>1</sup>

Kumārāgupta was succeeded by his son Skandagupta. An inscription of his on a pillar at Bhitari near Saidpur in Ghazipur bearing no date shows that on his father's death Skandagupta had a hard struggle to establish his power.<sup>2</sup> The text runs: "By whom when he rose to fix fast again the shaken fortune of his house, three months<sup>3</sup> were spent on the earth as on a bed," an apparent reference to flight and wanderings. A doubtful passage in the same inscription seems to show that he was opposed by a powerful king named Pushyamitra on whose back he is said to have set his left foot.<sup>4</sup> The inscription makes a further reference to the troubles of the family stating that on re-establishing the shaken fortune of his house Skandagupta felt satisfied and went to see his weeping afflicted mother. Among the enemies with whom Skandagupta had to contend the inscription mentions a close conflict with the Hūnas that is the Ephthalites, Thetals, or White Huns.<sup>5</sup> Verse 3 of Skandagupta's Girnār inscription confirms the reference to struggles stating that on the death of his father by his own might he humbled his enemies to the earth and established himself. As the Girnār inscription is dated 136 (A.D. 456) and as Kumārāgupta's reign ended about 134, these troubles and difficulties did not last for more than two years. The Girnār inscription further states that on establishing his power he conquered the earth, destroyed the arrogance of his enemies, and appointed governors in all provinces. For Surāshtra he selected a governor named Parṇadatta and to Parṇadatta's son Chakrapāṇi he gave a share of the management placing him in charge of Junāgadh city. During the governorship of Parṇadatta the Sudarsāna lake close to Junāgadh, which had been strongly rebuilt in the time of the Kshatrapa Rudrakāman (A.D. 159), again gave way during the dark sixth of Bhādrapada of the year 136 (A.D. 456). The streams Palāśinī Sīkatā and Vilāśinī<sup>6</sup> burst through the dam and flowed unchecked. Repairs were begun on the first of bright *Grīshma* 137 (A.D. 457) and finished in two months. The new dam is said to have been 100 cubits

## Chapter VII.

THE GUPTAS,  
A.D. 410-470.

Skandagupta,  
A.D. 454-470.

<sup>1</sup> J. R. A. S. (N. S.) XXI, 120. But Kumārāgupta's two successors, Skandagupta and Puṣyagupta, use the same phrase *decam jagati* makes the explanation in the text doubtful. As Mr. Smith (Ditto) suggests *decam* is probably a mistake for *deco*, meaning His Majesty. The legend would then run, Kumārāgupta a lord of the earth . . . . . is triumphant. Dr. Bhagvanlal would have preferred *deco* (see page 70 note 2) but could not neglect the *anuvāsa* - (A. M. T. J.) <sup>2</sup> Corp. Ins. Ind. III. Ins. 13.

<sup>3</sup> Mr. Fleet (Corp. Ins. Ind. III. 53, 55) reads "*anta trīmasā*" and translates "a (whole) night was spent." Dr. Bhagvanlal read "*anta trīmasak*"

<sup>4</sup> Mr. Fleet finds that Pushyamitra is the name of a tribe not of a king. No VI. of Dr. Bühler's Jain inscriptions from Mathura (Ep. Ind. I. 378ff) mentions a Pushyamitriya kula of the Vārānagana, which is also referred to in Bhadrabāhu's Kalpa-sūtra (Jacobi's Edition, 80), but is there referred to the Charana-gana, no doubt a misreading for the Vārāna of the inscription. Dr. Bühler points out that Vārāna is the old name of Bulandshahr in the North-West Provinces, so that it is there that we must look for the power that first weakened the Guptas - (A. M. T. J.)

<sup>5</sup> See V. de St. Martin's Essay, Les Huns Blancs: seecht in Journal Asiatique Oct. - Dec. 1883 and below page 71.

<sup>6</sup> In Rudrakāman's inscription the Palāśinī is mentioned, and also the Suvarna-sīkatā "and the other rivers." In Skandagupta's inscription Mr. Fleet translates Sīkatāvilāśinī as an adjective agreeing with Palāśinī.

## Chapter VII.

THE GUPTAS,  
A.D. 410-470.Skandagupta,  
A.D. 454-470.

long by 68 cubits broad and 7 men or about 38 feet high. The probable site of the lake is in the west valley of the Girnār hill near what is called Bhavarātha's pass.<sup>1</sup> The inscription also records the making of a temple of Vishṇu in the neighbourhood by Chakrapālita, which was probably on the site of the modern Dāmodar's Mandir in the Bhavanātha pass, whose image is of granite and is probably as old as the Guptas. A new temple was built in the fifteenth century during the rule of Mandālīka the last Chudāsami ruler of Junāgaḍh. At the time of the Musalmān conquest (A.D. 1484) as violence was feared the images were removed and buried. Mandālīka's temple was repaired by Amarji Divān of Junāgaḍh (1759-1794). It was proposed to make and consecrate new images. But certain old images of Vishṇu were found in digging foundations for the enclosure wall and were consecrated. Two of these images were taken by Girnāra Brāhmans and consecrated in the names of Baladevji and Revatī in a neighbouring temple specially built for them. Of the original temple the only trace is a pilaster built into the wall to the right as one enters. The style and carving are of the Gupta period.

As almost all the Gupta coins found in Cutch are Skandagupta's and very few are Kumāragupta's, Skandagupta seems to have added Cutch to the provinces of Gujarāt and Kāthiāvāda inherited from his father. In Kāthiāvāda Skandagupta's coins are rare, apparently because of the abundant currency left by his father which was so popular in Kāthiāvāda that fresh Kumāragupta coins of a degraded type were issued as late as Valabhi times.

Like his father, Skandagupta issued a gold coinage in his eastern dominions but no trace of a gold currency appears in the west. Like Kumāragupta's his silver coins were of two varieties, eastern and western. The eastern coins have on the obverse a bust as in Kumāragupta's coins and the date near the face. On the reverse is a peacock similar to Kumāragupta's and round the peacock the legend :

विजितावनिरवनिपति जयति देवं स्कन्दगुप्तो यं

Vijitāvaniravanipati jayati devaṃ Skandagupto'yam.

This king Skandagupta who having conquered the earth conquers the Deva.<sup>2</sup>

Skandagupta's western coins are of three varieties, one the same as the western coins of Kumāragupta, a second with a bull instead of a peacock on the reverse, and a third with on the reverse an altar with one upright and two side jets of water. Coins of the first two varieties are found both in Gujarāt and in Kāthiāvāda. The third water-jet variety is peculiar to Cutch and is an entirely new feature in the western Gupta coinage. On the reverse of all is the legend :

परमभागवत महाराजाधिराज स्कन्दगुप्त क्रमादित्य

Paramabhāgavata Mahārājādhirāja Skandagupta Kramāditya.

The great Vaishnava the supreme ruler of great kings,  
Skandagupta the Sun of Prowess.<sup>3</sup>

<sup>1</sup> Remains of the dam were discovered in 1890 by Khān Bahādūr Ardesir Jamsetji Special Divān of Junāgaḍh. The site is somewhat nearer Junāgaḍh than Dr. Bhagvānlāl supposed. Details are given in Jour. B. B. R. A. S. XVIII. Number 48 page 47.

<sup>2</sup> The reading *deva* is to be preferred but the *anuvāra* is clear both on these coins and on the coins of his father. For these coins see J. R. A. S. (N. S.) XXI. Pl. IV, 4.

<sup>3</sup> J. R. A. S. (N. S.) XXI. Pl. IV, 627.

The beginning of Skandagupta's reign has been placed about Gupta 133 or A.D. 453 : his latest known date on a coin in General Cunningham's collection is Gupta 149 or A.D. 469.<sup>1</sup>

With Skandagupta the regular Gupta succession ceases.<sup>2</sup> The next Gupta is Budhagupta who has a pillar inscription<sup>3</sup> in a temple at Eran in the Saugor district dated 165 (A.D. 485) and silver coins dated Samvat 174 and 180 odd (A.D. 494 - 500 odd). Of Budhagupta's relation or connection with Skandagupta nothing is known. That he belonged to the Gupta dynasty appears from his name as well as from his silver coins which are dated in the Gupta era and are the same in style as the eastern coins of Skandagupta. On the obverse is the usual bust as in Skandagupta's coins with the date (174, 180 odd) near the face. On the reverse is the usual peacock and the legend is the same as Skandagupta's :

• देवं जयति विजितावनिरवनिपति श्री बुधगुप्तो

Devam jayati vijitavaniravanipati Śrī Budhagupto.

The king the illustrious Budhagupta who has conquered the earth  
conquers the Deva.<sup>4</sup>

Since the coins are dated Samvat 174 and 180 odd (A.D. 494 and 500 odd) and the inscription's date is 165 (A.D. 485) the inscription may be taken to belong to the early part of Budhagupta's reign the beginning of which may be allotted to about 160-162 (A.D. 480-482). As this is more than ten years later than the latest known date of Skandagupta (G. 149 A.D. 469) either a Gupta of whom no trace remains must have intervened or the twelve blank years must have been a time of political change and disturbance. The absence of any trace of a gold currency suggests that Budhagupta had less power than his predecessors. The correctness of this argument is placed beyond doubt by the pillar inscription opposite the shrine in the Eran temple where instead of his predecessor's title of monarch of the whole earth Budhagupta is styled protector of the land between the Jamna (Kālindī) and the Narbādā implying the loss of the whole territory to the east of the Jamna.<sup>5</sup> In the west the failure of Gupta power seems still more complete. Neither in Gujarāt nor in Kāthiāvāda has an inscription or even a coin been found with a reference to Budhagupta or to any other Gupta ruler later than Skandagupta (G. 149 A.D. 469). The pillar inscription noted above which is of the year 165 (A.D. 485) and under the rule of Budhagupta states that the pillar was a gift to the temple by Dhanya Viṣṇu and his brother Mātri Viṣṇu who at the time of the gift seem to have been local Brāhman governors. A second inscription on the lower part of the neck of a huge Boar or Varāha image in a corner shrine of the same temple records that the image was completed on the tenth day of Phālguna in the first year of the reign of

<sup>1</sup> The known dates of Skandagupta are 136 and 137 on his Girmār inscription, 141 in his pillar inscription at Kalaon in Gorakhpur, and 146 in his Indor-Khera copperplate. The coin dates given by General Cunningham are 144, 145, and 149.

<sup>2</sup> But see below page 73.

<sup>3</sup> Dr. Bhagvānlāl examined and copied the original of this inscription. It has since been published as Number 19 in Mr. Fleet's Corp. Ins. Ind. III.

<sup>4</sup> J. R. A. S. (N. S.) XX1, 134.

<sup>5</sup> It is now known that the main Gupta line continued to rule in Magadha. See page 73 below.

## Chapter VII.

THE GUPTAS,  
A.D. 410-470.

Bhudagupta,  
A.D. 485.

## Chapter VII.

THE GUPTAS,  
A.D. 410-470.Budhagupta,  
A.D. 485.

Toramāna the supreme ruler of great kings and was the gift of the same Dhanya Vishṇu whose brother Mātri Vishṇu is described as gone to heaven.<sup>1</sup> Since Mātri was alive in the Budhagupta and was dead in the Toramāna inscription it follows that Toramāna was later than Budhagupta. His name and his new era show that Toramāna was not a Gupta. A further proof that Toramāna wrested the kingdom from Budhagupta is that except the change of era and that the bust turns to the left instead of to the right, Toramāna's silver coins are directly adapted from Gupta coins of the eastern type.

Certain coin dates seem at variance with the view that Toramāna flourished after Budhagupta. On several coins the date 52 is clear. As Toramāna's coins are copies of the coins of Kumāragupta and Skandagupta and as most of these coins have a numeral for one hundred the suggestion may be offered that a one dropped out in striking Toramāna's die and that this date should read 152 not 52. Accepting this view Toramāna's date would be 152 (A.D. 472) that is immediately after the death of Skandagupta.

The Gwālior inscription<sup>2</sup> mentions prince Mihirakula as the son of Toramāna and a second inscription from a well in Mandasor<sup>3</sup> dated Mūlava Samvat 589 (A.D. 533) mentions a king named Yaśodharman who was ruler of Malwa when the well was built and who in a second Mandasor inscription<sup>4</sup> is mentioned as having conquered Mihirakula. This would separate Mihirakula from his father Toramāna (A.D. 471) by more than sixty years. In explanation of this gap it may be suggested that the [1]52 (A.D. 472) coins were struck early in Toramāna's reign in honour of his conquest of the eastern Gupta territory. A reign of twenty years would bring Toramāna to 177 (A.D. 497). The Gwālior inscription of Mihirakula is in the fifteenth year of his reign that is on the basis of a succession date of 177 (A.D. 497) in Gupta 192 (A.D. 512). An interval of five years would bring Yaśodharman's conquest of Mihirakula to 197 (A.D. 517). This would place the making of the well in the twenty-first year of Mihirakula's reign.

Bhānugupta,  
A.D. 511.

After Budhagupta neither inscription nor coin shows any trace of Gupta supremacy in Mālwa. An Eran inscription<sup>5</sup> found in 1869 on a *līṅga*-shaped stone, with the representation of a woman performing *sutī*, records the death in battle of a king Goparājā who is mentioned as the daughter's son of Sarabharājā and appears to have been the son of king Madhava. Much of the inscription is lost. What remains records the passing to heaven of the deceased king in the very destructive fight with the great warrior (*pravīra*) Bhānugupta brave as Pārtha. The inscription is dated the seventh of dark Bhādrapada Gupta 191 in words as well as in numerals that is in A.D. 511. This Bhānugupta would be the successor of Budhagupta ruling over a petty Mālwa principality which lasted till nearly the time of the great Harshavardhana the beginning of the seventh century (A.D. 607-650), as a Devagupta of Mālwa is one of Rājyavardhana's rivals in the *Sriharshacharita*. While Gupta power failed in Mālwa

<sup>1</sup> Published by Mr Fleet Corp. Ins. Ind. III. Ins. 36.<sup>2</sup> Fleet Corp. Ins. Ind. III. Ins. 37.<sup>3</sup> Fleet Corp. Ins. Ind. III. Ins. 35.<sup>4</sup> Fleet Corp. Ins. Ind. III. Ins. 33.<sup>5</sup> Fleet Corp. Ins. Ind. III. Ins. 20.

and disappeared from Western India a fresh branch of the Guptas rose in Magadha or Behar and under Naragupta Baladitya, perhaps the founder of the eastern branch of the later Gupta dynasty, attained the dignity of a gold coinage.<sup>1</sup>

[Though the history of their last years is known only in fragments, chiefly from inscriptions and coins, little doubt remains regarding the power which first seriously weakened the early Guptas. The Bhitari stone pillar of Skandagupta<sup>2</sup> speaks of his restoring the fortunes of his family and conquering the Pushyamitras and also of his joining in close conflict with the Hūnas.<sup>3</sup> Unfortunately the Bhitari inscription is not dated. The Junágadh inscription, which bears three dates covering the period between A.D. 455 and 458,<sup>4</sup> mentions pride-broken enemies in the country of the Mlechchhas admitting Skandagupta's victory. That the Mlechchhas of this passage refers to the Huns is made probable by the fact that it does not appear that the Pushyamitras were Mlechchhas while they and the Huns are the only enemies whom Skandagupta boasts either of defeating or of meeting in close conflict. It may therefore be assumed that the Huns became known to Skandagupta before A.D. 455. As according to the Chinese historians<sup>5</sup> the White Huns did not cross the Oxus into Bactria before A.D. 452, the founding of the Hun capital of Badeghis<sup>6</sup> may be fixed between A.D. 452 and 455. As the above quoted inscriptions indicate that the Huns were repulsed in their first attempt to take part in Indian politics the disturbances during the last years of Kumaragupta's reign were probably due to some tribe other than the Huns. This tribe seems to have been the Pushyamitras whose head-quarters would seem to have been in Northern India. Some other enemy must have arisen in Malwa

## Chapter VII.

THE GUPTAS,  
A.D. 410-470.

The  
Pushyamitras,  
A.D. 455.

<sup>1</sup> On Naragupta see below page 77, and for his coins J. R. A. S. (N. S.) XXI. note PL III. 11. <sup>2</sup> Fleet's Corp. Ins. Ind. III. Ins. 13 lines 10 and 15.

<sup>3</sup> The Pushyamitras seem to have been a long established tribe like the Yaudheyas (above page 37). During the reign of Kanishka (A.D. 78-93) Pushyamitras were settled in the neighbourhood of Bulandshahr and at that time had already given their name to a Jain sect.

The sense of the inscription is somewhat doubtful. Mr Fleet (Corp. Ins. Ind. III. page 62) translates: 'Whose fame, moreover, even (his) enemies in the countries of the Mlechchhas . . . having their pride broken down to the very root announce with the words: 'Verily the victory has been achieved by him.' Prof. Peterson understands the meaning to be that Skandagupta's Indian enemies were forced to retire beyond the borders of India among friends Mlechchhas and in a foreign land admit that the renewal of their conflict with Skandagupta was beyond hope. The retreat of Skandagupta's Indian enemies to the Mlechchhas suggests the Mlechchhas are the Hūnas that is the White Huns who were already in power on the Indian border, whom the enemies had previously in vain brought as allies into India to help them against Skandagupta. This gives exactness to the expression used in Skandagupta's Bhitari inscription (Corp. Ins. Ind. III. Number 13 page 56) that he joined in close conflict with the Hūnas . . . among enemies, as if in this conflict the Hūnas were the allies of enemies rather than the enemies themselves. For the introduction into India of foreign allies, compare in B.C. 327 (McCrindle's Alexander in India, 112) the king of Taxila, 36 miles north-west of Rawalpindi, sending an embassy to Bactria to secure Alexander as an ally against Puras of the Gujarat country. And (Ditto, 109) a few years later (B.C. 310) the North Indian Malayaketu allying himself with Yavanas in his attack on Pataliputra or Patna.

<sup>4</sup> Fleet's Corp. Ins. Ind. III. Ins. 14 line 4.

<sup>5</sup> T'oungtien quoted by Specht in Journal Asiatique for Oct. - Dec. 1883.

<sup>6</sup> Badeghis is the modern Badkhyr the upper plateau between the Merv and the Herat rivers. The probable site of the capital of the White Huns is a little north of Herat. See Marco Polo's Itineraries No. I.; Yule's Marco Polo, I. xxxii.

## Chapter VII.

THE GUPTAS,  
A.D. 410-470.The  
Pushyamitras,  
A.D. 455.White Huns,  
A.D. 460-520.

since the terms of Purnadatta's appointment to Surāshtra in A.D. 455-6 suggest that country had been lost to the Gupta empire and re-conquered by Skandagupta which would naturally be the case if a rival state had arisen in Málwa and been overthrown by that king. So far as is known the Huns made no successful attack on the Gupta empire during the lifetime of Skandagupta whose latest date is A.D. 468-9. It is not certain who succeeded Skandagupta. His brother Purn(or Sthira-)gupta ruled in or near Magadha. But it is not certain whether he was the successor or the rival of Skandagupta.<sup>1</sup> That Skandagupta's inscriptions are found in the Patna district in the east<sup>2</sup> and in Káthiaváda in the west<sup>3</sup> suggests that during his life the empire was not divided nor does any one of his inscriptions hint at a partition. The probability is that Skandagupta was succeeded by his brother, Puragupta, who again was followed by his son Narasimhagupta and his grandson Kumāragupta II.<sup>4</sup>

Among the northerners who with or shortly after the Pushyamitras shared in the overthrow of Gupta power two names, a father and a son, Toramāna and Mihirakula are prominent. It is not certain that these kings were Huns by race. Their tribe were almost certainly his rivals' allies whom Skandagupta's Bhitari and Junágadh inscriptions style the one Hūnas the other Mlechchhas.<sup>5</sup> On one of Toramāna's coins Mr. Fleet reads<sup>6</sup> the date 52 which he interprets as a regnal date. This though not impossible is somewhat unlikely. The date of Mihirakula's accession to his father is fixed somewhere about A.D. 515.<sup>7</sup> In the neighbourhood of Gwálior he reigned at least fifteen years.<sup>8</sup> The story of Mihirakula's interview with Bilāditya's mother and his long subsequent history<sup>9</sup> indicate that when he came to the throne he was a young man probably not more than 25. If his father reigned fifty-two years he must have been at least 70 when he died and not less than 45 when Mihirakula was born. As Mihirakula is known to have had at least one younger brother,<sup>10</sup> it seems probable that Toramāna came to the throne a good deal later than A.D. 460 the date suggested by Mr. Fleet.<sup>11</sup> The date 52 on Toramāna's coins must therefore refer to some event other than his own accession. The suggestion may be offered that that event was the establishment of the White Huns in Baktria and the founding of their capital Badeghis,<sup>12</sup> which, as fixed above between A.D. 452 and 455, gives the very suitable date of A.D. 504 to 507 for the 52 of Toramāna's coin. If this suggestion is correct a further identification follows. The Chinese ambassador Sungyun (A.D. 520)<sup>13</sup>

<sup>1</sup> See the Ghazipur Seal. Smith & Hoernle, J. A. S. Ben. LVIII. 81ff and Fleet Ind. Ant. XIX. 224ff. <sup>2</sup> Bihar Ins. Fleet's Corp. Ins. Ind. III. Ins. 12.

<sup>3</sup> Junágadh Inscript. Fleet's Corp. Ins. Ind. III. Ins. 14. <sup>4</sup> See note 1 above.

<sup>5</sup> See above notes 1 and 2. <sup>6</sup> Ind. Ant. XVIII. 225.

<sup>7</sup> Fleet's Corp. Ins. Ind. III. Introdn. 12. <sup>8</sup> Fleet's Corp. Ins. Ind. Ins. 37 line 4.

<sup>9</sup> Beal's Buddhist Records, I. 169-172 and Rājataranginī, I. 289-326 quoted by Fleet in Ind. Ant. XV. 217-249.

<sup>10</sup> Beal's Hsuen Tsang, I. 169-171. As Mr. Fleet suggests the younger brother is possibly the Chandra referred to in Corp. Ins. Ind. III. Ins. 32 line 5 and Introdn. 12 and 140 note 1. <sup>11</sup> Ind. Ant. XIII. 230 and Corp. Ins. Ind. III. Introdn. 12.

<sup>12</sup> Specht in Journal Asiatique for Oct. - Dec. 1883. Histoire des Wei.

<sup>13</sup> Beal's Buddhist Records, I. c. - cii.

describes an interview with the king of Gandhāra whose family Sangyun notices was established in power by the *Ye-tha*, that is the Ephthalites or White Huns, two generations before his time.<sup>1</sup> Mihirakula is known to have ruled in Gandhāra<sup>2</sup> and Sangyun's description of the king's pride and activity agrees well with other records of Mihirakula's character. It seems therefore reasonable to suppose that the warlike sovereign who treated Sangyun and the name of his Imperial mistress with such scant courtesy was no other than the meteor Mihirakula. If Sangyun is correct in stating that Mihirakula was the third of his line the dynasty must have been established about A.D. 430. Beal is in doubt whether the name Lac-lh given by Sangyun<sup>3</sup> is the family name or the name of the founder. As a recently deciphered inscription shows Toramāna's family name to have been Janvka<sup>4</sup> it seems to follow that Lac-lh, or whatever is the correct transliteration of the Chinese characters, is the name of the father of Toramāna. Sangyun's reference to the establishment of this dynasty suggests they were not White Huns but leaders of some subject tribe.<sup>5</sup> That this tribe was settled in Bactria perhaps as far south as Kabul before the arrival of the White Huns seems probable. The Hindu or Persian influence notable in the tribal name *Matraka* and in the personal name *Mihirakula* seems unsuited to Huns newly come from the northern frontiers of China and proud of their recent successes.<sup>6</sup> Chinese records show that the tribe who preceded the White Huns in Bactria and north-east Persia, and who about A.D. 350-400 destroyed the power of Kitolo the last of the Kushāns, were the Yuan-Yuan or Jumen-Jumen whom Sir H. Howorth identifies with the Avar. To this tribe it seems on the whole probable that

## Chapter VII.

THE GUPTAS,  
A.D. 410-470.White Huns,  
A.D. 450-620.

<sup>1</sup> Beal's Buddhist Records, I, xcix.

<sup>2</sup> Beal's Buddhist Records, I, 171. Hsien Tsiang's statement (Ibid.) that Mihirakula conquered Gandhāra after his capture by Baladitya may refer to a reconquest from his brother, perhaps the Chandra referred to in note 10 on page 74.

<sup>3</sup> Beal's Buddhist Records, I, c, suggests that Lac-lh is the founder's name in his note 50 he seems to regard Lac-lh as the only name.

<sup>4</sup> Bühler Ep. Ind. I, 238. Dr. Bühler hesitates to identify the Toramāna of this inscription with Mihirakula's father.

<sup>5</sup> Beal's Buddhist Records, I, xcix. c. This is the kingdom which the Ye-tha destroyed and afterwards set up Lac-lh to be king over the country.

<sup>6</sup> *Matraka* is a Sanskritised form of *Mihra* and this again is perhaps an adaptation of the widespread and well known Western Indian tribal name *Mer* or *Med*. Compare Fleet's Corp. Ins. Ind. III, 326-327. It is to be remembered that the name of the emperor then (A.D. 450-500) ruling the White Huns was Khushnawiz, a Persian name, the Happy Cherisher. . . . The emperor's Persian name *Mihirakula* reported (Darrosterer, *Jl. Asiatique*, X, 70 n. 3) introduction of Magi into Kashmir, and the maptness of *Mihirakula* as a personal name give weight to Mr. Fleet's suggestion (Ind. Ant. XV, 245-252) that *Mihirakula* is pure Persian. The true form may then be *Mihiragula*, that is *Sm Rose*, a name which the personal beauty of the prince may have gained him. 'I have heard of my son's wisdom and beauty and wish once to see his face' said the late-reviving mother of king Baladitya (Beal's Buddhist Records, I, 169) when the captive *Mihirakula* was led before her his young head for very shame shrouded in his cloak.

<sup>7</sup> Specht in *Jour. Asiatique* 1883 II, 335 and 348.

<sup>8</sup> J. R. A. S. XXI, 721. According to other accounts (Ency. Brit. IX, Ed. Art. Turk. page 658) a portion of the Jumen-Jumen remained in Eastern Asia, where, till A.D. 552, they were the masters of the Tukkiu or Turks, who then overthrew their masters and about ten years later (A.D. 560) crushed the power of the White Huns.

## Chapter VII.

THE GUPTAS,  
A.D. 460-470.White Huns,  
A.D. 450-520.

Lao-lih the father of Toramāna belonged.<sup>1</sup> At the same time, though perhaps not themselves White Huns, the details regarding Toramāna and Mihirakula so nearly cover the fifty years (A.D. 470-530) of Ilūna ascendancy in North India that, as was in keeping with their position in charge of his Indian outpost, the White Hun emperor Khushnāwaz, while himself engaged in Central Asia and in Persia (A.D. 460-500),<sup>2</sup> seems to have entrusted the conquest of India to Toramāna and his son Mihirakula. Of the progress of the mixed Ymau-Yuan and White Hun invaders in India few details are available. Their ascendancy in the north seems to have been too complete to allow of opposition, and Hūnas were probably closely associated with the Maitraka or Mebara conquest of Kathāváda (A.D. 480-520). The southern fringe of the White Hun dominions, the present Sangor district of the Central Provinces, seems to have been the chief theatre of war, a debatable ground between the Guptas, Toramāna, and the Malwa chiefs. To the east of Sangor the Guptas succeeded in maintaining their power until at least A.D. 528-9.<sup>3</sup> To the west of Sangor the Guptas held Eran in A.D. 484-5.<sup>4</sup> About twenty years later (A.D. 505)<sup>5</sup> Eran was in the hands of Toramāna, and in A.D. 510-11 Bhaungupta<sup>6</sup> fought and apparently won a battle at Eran.

Mihirakula,  
A.D. 512.

Mihirakula's accession to the throne may perhaps be fixed at A.D. 512. An inscription of Yaśodharman, the date of which cannot be many years on either side of A.D. 532-3, claims to have enforced the submission of the finians Mihirakula whose power had established itself on the thrones of kings and who had hitherto bowed his neck to no one but Śiva.<sup>7</sup> In spite of this defeat Mihirakula held Gwāhor and the inaccessible fortress of the Himālayas.<sup>8</sup> These dates give about A.D. 520 as the time of Mihirakula's greatest power, a result which suggests that the Gollas, whom, about A.D. 520, the Greek merchant Cosmas Indicopleustes heard of in the ports of Western India as the supreme ruler of Northern India was Kula or Mihirakula.<sup>9</sup>

Yaśodharman  
of Málwa,  
A.D. 533-4.

Regarding the history of the third destroyers of Gupta power in Málwa, inscriptions show that in A.D. 437-8, under Kumāragupta, Bandhuvāman son of Vishnuvarman ruled as a local king.<sup>10</sup>

<sup>1</sup> The name Jonen Jonen seems to agree with Toramāna's surname Jāyila and with the Juvia whom Cosmas Indicopleustes (A.D. 520-535) places to the north-east of Persia. Prianlx's Indian Travels, 220.

<sup>2</sup> Rawlinson's Seventh Monarchy, 311-349.

<sup>3</sup> Fleet's Corp. Ins. Ind. III. Ins. 25 line 1.

<sup>4</sup> Fleet's Corp. Ins. Ind. III. Ins. 19 line 2.

<sup>5</sup> Fleet's Corp. Ins. Ind. III. Ins. 36.

<sup>6</sup> Fleet's Corp. Ins. Ind. III. Ins. 20.

<sup>7</sup> Fleet's Corp. Ins. Ind. III. Ins. 33.

<sup>8</sup> Fleet's Corp. Ins. Ind. III. and Ind. Ant. XVIII. 219.

<sup>9</sup> Prianlx's Indian Travels, 222. Compare Yule's Cathay, I. clxx.; Mignes' Patr. (tr. 88 page 450. For the use of Kula for Mihirakula, the second half for the whole, compare Fleet's Corp. Ins. Ind. III. 8 note. As regards the change from Kula to Gollas it is to be noted that certain of Mihirakula's own coins (Ind. Ant. XV 249) have the form Gola not Kula, and that this agrees with the suggestion (page 75 note 6) that the true form of the name is the Persian Mihiragula Rose of the Sun. Of this Gollas, who, like Mihirakula, was the type of conqueror round whom legends gather, Cosmas says (Prianlx, 223). Besides a great force of cavalry Gollas could bring into the field 2000 elephants. So large were his armies that once when besieging an inland town defended by a water-fosse his men horses and elephants drank the water and marched in dry-shod.

<sup>10</sup> Fleet's Corp. Ins. Ind. III. Ins. 18.

Possibly Bandhuvarman afterwards threw off his allegiance to the Guptas and thereby caused the temporary loss of Suráshtra towards the end of Kumáragupta's reign. Nothing further is recorded of the rulers of Málwa until the reign of Yaśodharman in A.D. 533-4.<sup>1</sup> It has been supposed that one of Yaśodharman's inscriptions mentioned a king Vishnuvardhana but there can be little doubt that both names refer to the same person.<sup>2</sup> The name of Yaśodharman's tribe is unknown and his crest the *āulikara* has not been satisfactorily explained.<sup>3</sup> Mandasor<sup>4</sup> in Western Malwa, where all his inscriptions have been found, must have been a centre of Yaśodharman's power. Yaśodharman boasts<sup>5</sup> of conquering from the Brahmaputra to mount Mahendra and from the Himálayas to the Western Ocean. In the sixth century only one dynasty could claim such widespread power. That dynasty is the famous family of Ujjain to which belonged the well known Vikramāditya of the Nine Gems. It may be conjectured not only that Yaśodharman belonged to this family but that Yaśodharman was the great Vikramāditya himself.<sup>6</sup>

The difficult question remains by whom was the power of Mihirakula overthrown. Yaśodharman claims to have subdued Mihirakula, who, he distinctly says, had never before been defeated.<sup>7</sup> On the other hand, Huen Tsiang ascribes Mihirakula's overthrow to a Báláditya of Magadha.<sup>8</sup> Coins prove that Báláditya<sup>9</sup> was one of the titles of Narasimhagupta grandson of Kumáragupta I. (A.D. 417-455) who probably ruled Magadha as his son's seal was found in the Gházipur district.<sup>10</sup> If Huen Tsiang's story is accepted a slight chronological difficulty arises in the way of this identification. It is clear that Mihirakula's first defeat was at the hands of Yaśodharman about A.D. 530. His defeat and capture by Báláditya must have been later. As Skandagupta's reign ended about A.D. 470 a blank of sixty years has to be filled by the two reigns of his brother and his nephew.<sup>11</sup> This, though not impossible, suggests caution in identifying Báláditya. According to Huen Tsiang Báláditya was a feudatory of Mihirakula who rebelled against him when he began to persecute the Buddhists. Huen Tsiang notices that, at the intercession of his own mother, Báláditya spared Mihirakula's life and allowed him to retire to Kashmir. He further notices that Mihirakula and his brother were rivals and his statement suggests that from Kashmir Mihirakula defeated his brother and recovered Gandhára. The ascendancy of the White Huns cannot have lasted long after Mihirakula. About A.D. 560 the power of the White Huns was crushed between the combined attacks of the Persians and Turks.<sup>12</sup>—(A. M. T. J.)

## Chapter VII.

THE GUPTAS,  
A.D. 460-470.

Yaśodharman  
of Málwa,  
A.D. 533-4.

<sup>1</sup> Fleet's Corp. Ins. Ind. III. Ins. 33-35.

<sup>2</sup> Fleet's Corp. Ins. Ind. III. Ins. 35 line 5. <sup>3</sup> Fleet's Corp. Ins. Ind. III. Ins. 33 line 4.

<sup>4</sup> N. Lat. 24° 3'; E. Long. 75° 8'

<sup>5</sup> Fleet's Corp. Ins. Ind. III. Ins. 33 line 5.

<sup>6</sup> This has already been suggested by Genl. Cunningham, *Nam. Chron.* (3rd Ser.), VIII. 41. Dr. Hearnle (J. B. A. S. LVIII. 100ff) has identified Yaśodharman with Vikramāditya's son Śilāditya Pratyapala.

<sup>7</sup> Fleet's Corp. Ins. Ind. III. Ins. 33 line 6.

<sup>8</sup> Beal's Buddhist Records, I. 169.

<sup>9</sup> Hearnle in J. B. A. S. LVIII. 97.

<sup>10</sup> See Smith and Hearnle J. B. A. S. LVIII. 84; and Fleet Ind. Ant. XIX. 224.

<sup>11</sup> Hearnle makes light of this difficulty J. B. A. S. LVIII. 97.

<sup>12</sup> Rawlinson's Seventh Monarchy. 420, 422.

## CHAPTER VIII.

## THE VALABHIS

(A.D. 509-766)

## Chapter VIII.

THE VALABHIS,  
A.D. 509-766.Valch Town,  
1893.

THE Valabhi dynasty, which succeeded the Guptas in Gujarāt and Kāthiavāda, take their name from their capital in the east of Kāthiavāda about twenty miles west of Bhavnagar and about twenty-five miles north of the holy Jain hill of Śatruñjaya. The modern name of Valabhi is Valch. It is impossible to say whether the modern Valch is a corruption of Valabhi the Prakrit form of the Sanskrit Valabhi or whether Valabhi is Sanskritised from a local original Valch. The form Valabhi occurs in the writings of Jīva-prabhasuri a learned Jain of the thirteenth century who describes Śatruñjaya as in the Valabhaka province. A town in the chiefship of Valch now occupies the site of old Valabhi,<sup>1</sup> whose ruins lie buried below thick layers of black earth and silt under the modern town and its neighbourhood. The only remains of old buildings are the large foundation bricks of which, except a few new houses, the whole of Valch is built. The absence of stone supports the theory that the buildings of old Valabhi were of brick and wood. In 1872 when the site was examined the only stone remains were a few scattered Lingas and a well-polished life-size granite Nandi or bull lying near a modern Mahādeva temple. Diggers for old bricks have found copper pots and copper plates and small Buddhist relic shrines with earthen pots and clay seals of the seventh century.

The ruins of Valabhi show few signs of representing a large or important city. The want of sweet water apparently unfits the site for the capital of so large a kingdom as Valabhi. Its choice as capital was probably due to its being a harbour on the Bhūvānagar creek. Since

---

<sup>1</sup> Mr. Vapshanka Gavrisanka, Sub-Divān of Bhavnagar, has made a collection of articles found in Valabhi. The collection includes clay seals of four varieties and of about the seventh century with the Buddhist formula *Ye Dharma heta Prabhava*; a small earthen tube with the same formula imprinted on its base with a seed, beads and ring stones *etc.* of several varieties of *akik* or carnelian and *sphatik* or coral some finished others half finished showing that as in modern Cambay the polishing of carnelians was a leading industry in early Valabhi. One circular figure of the size of a half rupee carved in black stone has engraved upon it the letters *ma ra* in characters of about the second century \*. A royal seal found by Colonel Watson in Valch bears on it an imperfect inscription of four lines in characters as old as Dharmasena I. (A.D. 526). This seal contains the names of three generations of kings, two of which the grandfather and grandson read Abhaya and Pushyana all three being called *Maharaja* or great king. The dynastic name is lost. The names on these moveable objects need not belong to Valabhi history. Still that seals of the second and fifth centuries have been discovered in Valabhi shows the place was in existence before the founding of the historical Valabhi kingdom. A further proof of the age of the city is the mention of it in the Kathasarit-sagara a comparatively modern work but of very old materials. To this evidence of age, with much hesitation, may be added Balai Ptolemy's name for Gopāth point which suggests that as early as the second century Valch or Balch (compare Alberici's era of Balat) was known by its present name. Baily minted coins of the Gupta ruler Kumāragupta (A.D. 417-453) are so common as to suggest that they were the currency of Valabhi.

The *ma* and *ra* are of the old style and the side and upper strokes, that is the *kina* and *mūla* of *ra* are horizontal.

the days of Valabhi's prime the silt which thickly covers the ruins has also filled and choked the channel which once united it with the Bhāvnagar creek when the small Ghelo was probably a fair sized river.

In spite of the disappearance of every sign of greatness Hsien Tsiang's (A.D. 610) details show how rich and populous Valabhi was in the early part of the seventh century. The country was about 1000 miles (6000 *li*) and the capital about five miles (30 *li*) in circumference. The soil the climate and the manners of the people were like those of Malava. The population was dense; the religious establishments rich. Over a hundred merchants owned a hundred *lákhs*. The rare and valuable products of distant regions were stored in great quantities. In the country were several hundred monasteries or *sanghārāmas* with about 6000 monks. Most of them studied the Little Vehicle according to the Sāṃmatīya school. There were several hundred temples of Devas and sectaries of many sorts. When Tathāgata or Gautama Buddha (B.C. 560 - 180) lived he often travelled through this country. King Aśoka (B.C. 240) had raised monuments or *stupas* in all places where Buddha had rested. Among these were spots where the three past Buddhas sat or walked or preached. At the time of Hsien Tsiang's account (A.D. 610) the king was of the Kṣhātrīya caste, as all Indian rulers were. He was the nephew of Śīlāditya of Malava and the son-in-law of the son of Śīlāditya the reigning king of Kanyakubja. His name was Dharmapala (Tu-hu-h'o-po-tu). He was of a lively and hasty disposition, shallow in wisdom and statecraft. He had only recently attached himself sincerely to the faith in the three precious ones. He yearly summoned a great assembly and during seven days gave away valuable gems and choice meats. On the monks he bestowed in charity the three garments and medicaments, or their equivalents in value, and precious articles made of the seven rare and costly gems. These he gave in charity and redeemed at twice their price. He esteemed the virtuous, honoured the good, and revered the wise. Learned priests from distant regions were specially honoured. Not far from the city was a great monastery built by the Arhat Achāra ('O-che-lo), where, during their travels the Bodhisattvas Guṇamati and Sthiramati (Kien-hwu) settled and composed renowned treatises.<sup>1</sup>

The only historical materials regarding the Valabhi dynasty are their copperplates of which a large number have been found. That such powerful rulers as the Valabhis should leave no records on stones and no remains of religious or other buildings is probably because, with one possible exception at Gopudh,<sup>2</sup> up to the ninth century all temples and religious buildings in Kāthiavāḍa and Gujarāt were of brick and wood.<sup>3</sup>

## Chapter VIII.

THE VALABHIS,  
A.D. 509 - 766.

Valabhi in  
A.D. 620.

Valabhi  
Copperplates.

<sup>1</sup> As suggested by Dr. Bühler (Ind. Ant., VI, 10), this is probably the Vihāra called Śrī Bappapāḍiyavihāra which is described as having been constructed by Achārya Bhādanta Sthiramati who is mentioned as the grantee in a copperplate of Dharaśena II. bearing date Gupta 269 (A.D. 588). The Sthiramati mentioned with titles of religious veneration in the copperplate is probably the same as that referred to by Hsien Tsiang. (Ditto).

<sup>2</sup> Burgess' Kuthiwar and Kuteb, 187.

<sup>3</sup> Stories on record about two temples one at Sātrūjaya the other at Somanātha support this view. As regards the Sātrūjaya temple the tradition is that while the minister of Kumarapāla (A.D. 1113 - 1174) of Anahilavāḍa was on a visit to Sātrūjaya to worship and meditate in the temple of Adinātha, the wick of the lamp in the shrine was removed

**Chapter VIII.**THE VALABHIS,  
A.D. 509-766.Valabhi  
Copperplates.

The Valabhi copperplates chiefly record grants to Brahmanical temples and Buddhist monasteries and sometimes to individuals. All are in one style two plates inscribed breadthwise on the inner side, the earliest plates being the smallest. The plates are held together by two rings passed through two holes in their horizontal upper margin. One of the rings bears on one side a seal with, as a badge of the religion of the dynasty, a well-proportioned seated Nandi or bull. Under the bull is the word Bhatārka the name of the founder of the dynasty. Except such differences as may be traced to the lapse of time, the characters are the same in all, and at the same time differ from the character then in use in the Valabhi territory which must have been that from which Devanāgarī is derived. The Valabhi plate character is adopted from that previously in use in South Gujarāt plates which was taken from the South Indian character. The use of this character suggests that either Bhatārka or the clerks and writers of the plates came from South Gujarāt.<sup>1</sup> The language of all the grants is Sanskrit prose. Each records the year of the grant, the name of the king making the grant, the name of the grantee the name of the village or field granted, the name of the writer of the charter either the minister of peace and war *śānti-śānti-dhikṛta* or the military head *balā-dhikṛta*, and sometimes the name of the *dātaka* or gift-giver generally some officer of influence or a prince and in one case a princess. The grants begin by recording they were made either 'from Valabhi' the capital, or 'from the royal camp' '*Vijaya-skandhārā*.' Then follows the genealogy of the dynasty from Bhatārka the founder to the grantor king. Each king has in every grant a series of attributes which appear to have been fixed for him once for all. Except in rare instances the grants contain nothing historical. They are filled with verbose description and figures of speech in high flown Sanskrit. As enjoined in law-books or *dharmaśāstras* after the genealogy of the grantor comes the name of the composer usually the minister of peace and war and after him the boundaries of the land granted. The plates conclude with the date of the grant, expressed in numerals following the letter *śam* or the letters *śamra* for *śamratśara* that is year. After the numerals are given the lunar month and day and the day of the week, with, at the extreme end, the sign manual *svahasto mama* followed by the name of the king in the genitive case that is Own hand of me so and so. The name of the era in which the date is reckoned is nowhere given.

Period  
Covered.

So far as is known the dates extend for 240 years from 207 to 447. That the earliest known date is so late as 207 makes it pro-

---

by mice and set on fire and almost destroyed the temple which was wholly of wood. The minister seeing the danger of wooden buildings determined to erect a stone edifice (*Kumārāpāla Charita*). The story about Somanātha is given in an inscription of the time of Kumārāpāla in the temple of Bhadrakālī which shows that before the stone temple was built by Bhīmaadeva I. (A.D. 1022-1072) the structure was of wood which was traditionally believed to be as old as the time of Kṛishṇa. Compare the Bhadrakālī inscription at Somanātha.

<sup>1</sup> The correctness of this inference seems open to question. The descent of the Valabhi plate character seems traceable from its natural local source the Skandagupta (A.D. 450) and the Rudradāman (A.D. 150) Gīrnār inscriptions.—(A. M. T. J.)

hable that the Valabhis adopted an era already in use in Káthiáváda. No other era seems to have been in use in Valabhi. Three inscriptions have their years dated expressly in the Valabhi Samvat. The earliest of these in Bhadrakáli's temple in Sonnáthi Pátanis of the time of Kumárapála (A.D. 1113-1171) the Solanki ruler of Anahilaváda. It bears date Valabhi Samvat 850. The second and third are in the temple of Harsata Devi at Verával. The second which was first mentioned by Colonel Tod, is dated Hijra 682, Vikrama Samvat 1320, Valabhi Samvat 915, and Simha Samvat 151. The third inscription, in the same temple on the face of the pedestal of an image of Krishna represented as upholding the Govardhana hill, bears date Valabhi S 927. These facts prove that an era known as the Valabhi era, which the inscriptions show begun in A.D. 319, was in use for about a hundred years in the twelfth and thirteenth centuries. This may be accepted as the era of the Valabhi plates which extended over two centuries. Further the great authority (A.D. 1030) Alberuni gives Saka 241 that is A.D. 319 as the starting point both of the 'era of Balah' and of what he calls the Gupta-kala or the Gupta era. Beruni's accuracy is established by a comparison of the Mandasor inscription and the Nepal inscription of Amínvarman which together prove the Gupta era started from A.D. 319. Though its use by the powerful Valabhi dynasty caused the era to be generally known by their name in Gujarat in certain localities the Gupta era continued in use under its original name as in the Morá copperplate of Jálkadeva which bears date 588 "of the era of the Guptas."<sup>1</sup>

The Valabhi grants supply information regarding the leading office bearers and the revenue police and village administrators whose names generally occur in the following order :

- (1) *Aguktaka*, } meaning appointed, apparently any superior
- (2) *Viníyuktaka* } official.
- (3) *Dráṅgaka*, apparently an officer in charge of a town, as *dravaka* means a town.
- (4) *Mahattara* or Senior has the derivative meaning of high in rank. *Mhátara* the Maráthi for an old man is the same word. In the Valabhi plates *mahattara* seems to be generally used to mean the accredited headman of a village, recognised as headman both by the people of the village and by the Government.
- (5) *Chátabhata* that is *bhata*s or sepoy's for *chitas* or rogues, police mounted and on foot, represent the modern police *jamádárs* *haváldárs* and constables. The Kumárapála Charita mentions that Chátabhata were sent by Siddharaja to apprehend the fugitive Kumárapála. One plate records the grant of a village 'unenterable by *chátabhata*s.'<sup>2</sup>
- (6) *Dhruva* fixed or permanent is the hereditary officer in charge of the records and accounts of a village, the Taláti and Kulkarni

## Chapter VIII.

THE VALABHIS,  
A.D. 500-766.

Period  
Covered.

Valabhi  
Administration,  
A.D. 500-700.

<sup>1</sup> The era has been exhaustively discussed by Mr. Fleet in Corp. Ins. Ind. III. Introduction.

<sup>2</sup> Nepal Inscriptions. The phrase *acháta-bhata* is not uncommon. Mr. Fleet (Corp. Ins. Ind. III. page 98 note 2) explains *acháta-bhata-praveśya* as "not to be entered either by regular (*bhata*) or by irregular (*chata*) troops."

## Chapter VIII.

THE VALABHIS,  
A.D. 500-700.Valabhi  
Administration,  
A.D. 500-700.

of modern times. One of the chief duties of the Dhruva was to see that revenue farmers did not take more than the royal share.<sup>1</sup> The name is still in use in Cutch where village accountants are called *Dhru* and *Dhrava*. *Dhru* is also a common surname among Nāgar Brāhmins and Modh and other Vānīs in Cutch Gujarat and Kāthiāvāda.

(7) *Adhikarāyika* means the chief judicial magistrate or judge of a place.

(8) *Dandapāśaka* literally 'holding the fetters or noose of punishment,' is used both of the head police officer and of the hangman or executioner.

(9) *Chandodharāyika* the thief-catcher. Of the two Indian ways of catching thieves, one of setting a thief to catch a thief the other the *Pagi* or tracking system, the second answers well in sandy Gujarat and Kāthiāvāda where the Tracker or *Pagi* is one of the *Bīrābalute* or regular village servants.

(10) *Rājasthānīya*, the foreign secretary, the officer who had to do with other states and kingdoms *rājasthānas*. Some authorities take *rājasthānīya* to mean viceroy.

(11) *Amātya* minister and sometimes councillor is generally coupled with *kumāra* or prince.

(12) *Anutpannādāsaśamudgrāhaka* the arrears-gatherer.

(13) *Saulkika* the superintendent of tolls or customs.

(14) *Bhoga* or *Bhogadharāyika* the collector of the *Bhoga* that is the state share of the land produce taken in kind, as a rule one-sixth. The term *bhoga* is still in use in Kāthiāvāda for the share, usually one-sixth, which landholders receive from their cultivating tenants.

(15) *Varuapāla* the roadwatch were often mounted and stationed in *thānās* or small roadside sheds.<sup>2</sup>

(16) *Pratīsaraka* patrols night-guards or watchmen of fields and villages.<sup>3</sup>

(17) *Vishayapati* division-lord probably corresponded to the present subāh.

(18) *Rāshṭrapati* the head of a district.

(19) *Grāmakūṭa* the village headman.

Territorial  
Divisions.

The plates show traces of four territorial divisions: (1) *Vishaya* the largest corresponding to the modern administrative Division: (2) *Āhāra* or *Āharanī* that is collectorate (from *āhāra* a collection) corresponding to the modern district or zillah: (3) *Pathaka*, of the road, a sub-division, the place named and its surroundings: (4) *Sthalī* a petty division the place without surroundings.<sup>4</sup>

Land  
Assessment.

The district of Kaira and the province of Kāthiāvāda to which the Valabhi grants chiefly refer appear to have had separate systems

<sup>1</sup> Buhler in Ind. Ant. V, 205.<sup>2</sup> Ind. Ant. VII, 68.<sup>3</sup> Ind. Ant. VII, 68.

<sup>4</sup> Of the different territorial divisions the following examples occur: Of *Vishaya* or main division Svabhṭgapuravishaye and Sūryapuravishaye; of *Āhāra* or collectorate Khetaka-ghāra the Kaira district and Hastavapra-āhara or Hastavapraharanī the Hāthab district near Bhavnagar; of *Pathaka* or sub-division Nagur-panthaka Porbandar panthaka (Parris still talk of Navsāri panthaka); of *Sthalī* or petty division Vajasthali, Lonapadrakasthali, and others.

of land assessment Kaira by yield Kāthiāvāda by area. Under the Kāthiāvāda system the measurement was by *pālāvarta* literally the space between one foot and the other that is the modern *kulam* or pace. The pace used in measuring land seems to have differed from the ordinary pace as most of the Kāthiāvāda grants mention the *bhūpālāvarta* or land pace. The Kaira system of assessment was by yield the unit being the *paṭaka* or basketful, the grants describing fields as capable of growing so many baskets of rice or barley (or as requiring so many baskets of seed). As the grants always specify the Kaira basket a similar system with a different sized basket seems to have been in use in other parts of the country. Another detail which the plates preserve is that each field had its name called after a guardian or from some tree or plant. Among field names are Kotilaka, Atimāna-kedāra, Khanda-kedāra, Gargara-kshetra, Bhīma-kshetra, Khagah-kedāra, Sami-kedāra.

The state religion of the Valabhi kings was Śaivism. Every Valabhi copperplate hitherto found bears on its seal the figure of a bull with under it the name of Bhatāka the founder of the dynasty who was a Śaiva. Except Dhruvasena I (A D. 526) who is called *Paramabhīṣarata* or the great Vaiṣṇava and his brother and successor Pharapatta who is styled *Paramādityabhakta* or the great devotee of the sun, and Guhasena, who in his grant of Sam. 218 calls himself *Paramopāsaka* or the great devotee of Buddha, all the Valabhi kings are called *Parama-māheśvara* the great Śaiva.

The grants to Buddhist *vihāras* or monasteries of which there are several seem special gifts to institutions founded by female relatives the granting kings. Most of the grants are to Brāhmins who though performing Vaidik ceremonies probably as at present honoured Śaivism. This Śaivism seems to have been of the old Pāśupata school of Nakulīśa or Lakulīśa as the chief shrine of Lakulīśa was at Kārvāna the modern Kārvan in the Gāikwār's territory fifteen miles south of Baroda and eight miles north-east of Miyagān railway station a most holy place till the time of the Vāghela king Arjunadeva in the thirteenth century.<sup>1</sup> The special

## Chapter VIII.

THE VALABHIS,  
A D. 509-706.Land  
Assessment.

Religion.

<sup>1</sup> Kārvān seems to have suffered great desecration at the hands of the Muslims. All round the village church and pipal trees, images and pieces of sculpture and large *lamps* are scattered. To the north and east of the village on the banks of a large built pond called Kīśikundā are numerous sculptures and *lamps*. Partly embedded in the ground a pillar in style of about the eleventh century has a writing over it of latter times. The inscription contains the name of the place Sanskritised as Kīśa-varohana, and mentions an ascetic named Vnabalaśraraśi who remained male for twelve years. Near the pillar, at the steps leading to the water, is a carved doorway of about the tenth or eleventh century with some well proportioned figures. The left doorpost has at the top a figure of Śiva, below the Śiva a figure of Śūrya, below the Śūrya a male and female, and under them attendants or *ganis* of Śiva. The right doorpost has at the top a figure of Viṣṇu seated on Garuḍa, below the seated Viṣṇu a standing Viṣṇu with four hands, and below that two sitting male and female figures, the male with hands folded in worship the female holding a purse. These figures probably represent a married pair who paid for this gateway. Further below are figures of *ganis* of Śiva. In 1881 in repairing the south bank of the pond a number of carved stones were brought from the north of the town. About half a mile north-west of the town on the bank of a dry brook, is a temple of Chāmunda Devi of about the tenth century. It contains a mutilated life size image of Chāmunda. Facing the temple lie mutilated figures of the seven Matrikās and of Bhairava, probably the remains of a separate altar.

## Chapter VIII.

THE VALABHIS,  
A.D. 500-750.

Religion.

holiness attached to the Nārādā in Śaivism and to its pebbles as *lingas* is probably due to the neighborhood of this shrine of Kāvān. The followers of the Nakulisa-Pāśupata school were strict devotees of Śaivism, Nakulisa the founder being regarded as an incarnation of Śiva. The date of the formation of this school is not yet determined. It appears to have been between the second and the fifth century A.D. Nakulisa had four disciples Kuśika, Gargya, Kārṣṇa, and Mātreyā founders of four branches which spread through the length and breadth of India. Though no special representatives of this school remain, in spite of their nominal allegiance to Śaṅkarācharya the Dasanamis or Atits are in fact Nakulisas in their discipline doctrines and habits—applying ashes over the whole body, planting a *linga* over the grave of a buried Atit, and possessing proprietary rights over Śiva temples. The Pāśupatas were ever ready to fight for their school and often helped and served in the armies of kings who became their disciples. Till a century ago these unpaid followers recruited the armies of India with celibates firm and strong in fighting. It was apparently to gain these recruits that so many of the old rulers of India became followers of the Pāśupata school. To secure their services the rulers had to pay them special respect. The leaders of these fighting monks were regarded as pontiffs like the Bappa-pala or Pontiff of the later Valabhi and other kings. Thus among the later Valabhis Śīladitya IV. is called *Bappapādānūthyata* and all subsequent Śīladityas *Bappapādānūthyata* both titles meaning Worshipping at the feet of Bava or Bappa.

This Bava is the popular Prakrit form of the older Prakrit or *devi* Bappa meaning Father or worshipful. Bappa is the original of the Hindustāni and Gujarati Bava father or elder, it is also a special term for a head Gosavi or Atit or indeed for any recluse. The epithet *Bappa-pādānūthyata* Bowing at the feet of Bappa, occurs in the attributes of several Nepal kings, and in the case of king Vasantasena appears the full phrase

*Parama-devadeva-bappa-bhothānūthyat, a-S'ce-jābhānūthyata.*

Bowing at the illustrious feet of the great Mahārāja Lord Bappa.

These Nepal kings were Śaivas as they are called *parama-māhasava* in the text of the inscription and like the Valabhi seals their seals bear a bull. It follows that the term *Bappa* was applied both by the Valabhis and the Nepal kings to some one, who can hardly be the same individual, unless he was their

---

facing the temple with the *matrī-mardala* or Mother-Meeting upon it. The village has a large modern temple of Śiva called Nukleśvara, on the site of some old temple and mostly built of old carved temple stones. In the temple close by are a number of old images of the sun and the boar incarnation of Viṣṇu all of about the tenth or eleventh century. The name Nukleśvara would seem to have been derived from Nukulesa the founder of the Pāśupata sect and the temple may originally have had an image of Nukulisa himself or a *linga* representing Nukulisa. Close to the west of the village near a small dry reservoir called the Kunda of Rājārājēśvara lies a well-preserved black stone seated figure of Chanda one of the most respected of Śiva's attendants, without whose worship all worship of Śiva is imperfect, and to whom all that remains after making oblations to Śiva is offered. A number of other sculptures lie on the bank of the pond. About a mile to the south of Kāvān is a village called Langthak the place of *lingas*.

common overlord, which the distance between the two countries and still more the fact that his titles are the same as the titles of the Valabhi kings make almost impossible. In these circumstances the most probable explanation of the Bappa or Bava of these inscriptions is that it was applied to Shaivite pontiffs or ecclesiastical dignitaries. The attribute *Parama-dattata* The Great Divine prefixed to Bappa in the inscription of Vasantasena confirms this view. That such royal titles as *Mahārāja*, *Parama-bhāṭṭāraka*, and *Paramasvara* are ascribed to Bappa is in agreement with the present use of *Mahārāja* for all priestly Brāhmanas and recluses and of *Bhāṭṭāraka* for Digambara Jain priests. Though specially associated with Saivites the title *bappa* is applied also to Vaishnavā dignitaries. That the term *bappa* was in similar use among the Buddhists appears from the title of a Valabhi *vihāra* Bappapāḍīyavihāra The monastery of the worshipful Bappa that is of the great teacher Sthiramati by whom it was built.<sup>1</sup>

The tribe or race of Bhatārka the founder of the Valabhi dynasty is doubtful. None of the numerous Valabhi copperplates mentions the race of the founder. The Chālukya and Rāshtrakūṭa copperplates are silent regarding the Valabhi dynasty. And it is worthy of note that the Gohils and Gohils, who are descended from the Valabhis, take their name not from their race but from king Guha or Guhasena (A.D. 559-567) the fourth ruler and apparently the first great sovereign among the Valabhis. These considerations make it probable that Bhatārka belonged to some low or stranger tribe. Though the evidence falls short of proof the probability seems strong that Bhatārka belonged to the Gujjara tribe, and that it was the supremacy of him and his descendants which gave rise to the name Gujjara nāṭra the country of the Gujjaras a name used at first by outsiders and afterwards adopted by the people of Gujārāt. Except Bhatārka and his powerful dynasty no kings occur of sufficient importance to have given their name to the great province of Gujarat. Against their Gujjara origin it may be urged that the Chinese traveller Hsien Tsiang (A.D. 610) calls the king of Valabhi a Kshatriya. Still Hsien Tsiang's remark was made more than a century after the establishment of the dynasty when their rise to power and influence had made it possible for them to ennoble themselves by calling themselves Kshatriyas and tracing their lineage to Puranic heroes. That such ennobling was not only possible but common is beyond question. Many so-called Rājput families in Gujarat and Kāthiavāda can be traced to low or stranger tribes. The early kings of Nāndipurī or Nāndod (A.D. 450) call themselves Gurjjaras and the later members of the same dynasty trace their lineage to the Mahābhārata hero Karna. Again two of the Nāndod Gurjjaras Dadā II. and Jayabhata II. helped the Valabhis under circumstances which suggest that the bond of sympathy

## Chapter VIII.

THE VALABHIS,  
A.D. 509-766.

Religion.

Origin of  
the Valabhis.

<sup>1</sup> Compare Beal Buddhist Records, II. 268 note 76 and Ind. Ant. VI. 9. The meaning and reference of the title *Bappa* have been much discussed. The question is treated at length by Mr. Fleet (Corp. Ins. Ind. III. 186 note 1) with the result that the title is applied not to a religious teacher but to the father and predecessor of the king who makes the grant. According to Mr. Fleet *bappa* would be used in reference to a father, *bāra* in reference to an uncle.

## Chapter VIII.

THE VALABHIS,  
A.D. 509-766.Origin of  
the Valabhis.

may have been their common origin. The present chiefs of Nándod derive their lineage from Karna and call themselves Gohils of the same stock as the Bhāvnagar Gohils who admittedly belong to the Valabhi stock. This supports the theory that the Gurjjaras and the Valabhis had a common origin, and that the Gurjjaras were a branch of and tributary to the Valabhis. This would explain how the Valabhis came to make grants in Broach at the time when the Gurjjaras ruled there. It would further explain that the Gurjjaras were called *sāmāntas* or feudatories because they were under the overlordship of the Valabhis.<sup>1</sup>

## History.

The preceding chapter shows that except Chandragupta (A.D. 410) Kumāragupta (A.D. 416) and Skandagupta (A.D. 456) none of the Guptas have left any trace of supremacy in Gujarat and Kāthiāvāda. Of what happened in Gujarāt during the forty years after Gupta 150 (A.D. 469), when the reign of Skandagupta came to an end nothing is known or is likely to be discovered from Indian sources. The blank of forty years to the founder Bhatārka (A.D. 509) or more correctly of sixty years to Dhruvasena (A.D. 526) the first Valabhi king probably corresponds with the ascendancy of some foreign dynasty or tribe. All trace of this tribe has according to custom been blotted out of the Sm-skt and other Hindu records. At the same time it is remarkable that the fifty years ending about A.D. 525 correspond closely with the ascendancy in north and north-west India of the great tribe of Ephthalites or White Huns. As has been shown in the Gupta Chapter, by A.D. 470 or 480, the White Huns seem to have been powerful if not supreme in Upper India. In the beginning of the sixth century, perhaps about A.D. 520, Cosmas Indicopleustes describes the north of India and the west coast as far south as Kāthiāva that is Kalyān near Bombay as under the Huns whose king was Gollas.<sup>2</sup> Not many years later (A.D. 530) the Hun power in Central India suffered defeat and about the same time a new dynasty arose in south-east Kāthiāvāda.

First Valabhi  
Grant,  
A.D. 526.

The first trace of the new power, the earliest Valabhi grant, is that of Dhruvasena in the Valabhi or Gupta year 207 (A.D. 526). In this grant Dhruvasena is described as the third son of the Senāpati or general Bhatārka. Of Senāpati Bhatārka neither copperplate nor inscription has been found. Certain coins which General Cunningham Arch. Surv. Rept. IX. Pl. V. has ascribed to Bhatārka have on the obverse a bust, as on the western coins of

<sup>1</sup> Whether the Valabhis were or were not Gurjjaras the following facts favour the view that they entered Gujarat from Malwa. It has been shown (Fl. & Ind. Ant. XX. 376) that while the Guptas used the so-called Northern year beginning with Chaitra, the Valabhi year began with Kārtika (see Ind. Ant. XX. 376). And further Kielhorn in his examination of questions connected with the Vikrama era (Ind. Ant. XIX and XX) has given reasons for believing that the original Vikrama year began with Kārtika and took its rise in Malwa. It seems therefore that when they settled in Gujarāt, while they adopted the Gupta era the Valabhis still adhered to the old arrangement of the year to which they had been accustomed in their home in Malwa. The arrangement of the year entered into every detail of their lives, and was therefore much more difficult to change than the starting point of their era, which was important only for official acts. —(A. M. T. J.)

<sup>2</sup> Montfaucon's Edition in Priault's Indian Travels, 222-223. It seems doubtful if Cosmas meant that Gollas' overlordship spread as far south as Kalyān. Compare Migne's Patrologiæ Cursus, lxxxviii. 466; Yule's Cathay, I. cliz.

## THE VALABHIS.

Kumāragupta, and on the reverse the Śaiva trident, and round the trident the somewhat doubtful legend in Gupta characters :

Rājño Mahākṣatri Paramādityabhakta Śrī Śarvva-bhaṭṭarakasa.

Of the king the great Kṣatri, great devotee of the son, the illustrious Śarvva-bhaṭṭaraka.

This Śarvva seems to have been a Rāshtrakūṭa or Gurjjara king. His coins were continued so long in use and were so often copied that in the end upright strokes took the place of letters. That these coins did not belong to the founder of the Valabhi dynasty appears not only from the difference of name between Bhaṭṭaraka and Bhaṭarka but because the coiner was a king and the founder of the Valabhis a general.

Of the kingdom which Senāpati Bhaṭarka overthrew the following details are given in one of his epithets in Valabhi copperplates : ' Who obtained glory by dealing hundreds of blows on the large and very mighty armies of the Maṭṭakas, who by force had subdued their enemies.' As regards these Maṭṭakas it is to be noted that the name Maṭṭaraka means Solar. The second of the compound epithet *Maṭṭaka-amitra* that is Maṭṭaka-enemy used in the inscription makes it probable that the usual form Mihira, or solar was rejected in favour of Maṭṭaraka which also means solar, to secure the necessary assuance with *amitra* or enemy. The form Mihira solar seems a Hinduzing or meaning-making of the northern tribal name Moḥh or Mehr, the Mehirs being a tribe which at one time seem to have held sway over the whole of Kāthiāváḍa and which are still found in strength near the Barda hills in the south-west of Kāthiāváḍa.<sup>1</sup> The Jethvā chiefs of Porbandar who were formerly powerful rulers are almost certainly of the Mehirs tribe. They are still called Mehr kings and the Mehirs of Kāthiāváḍa regard them as their lords and at the call of their Head are ready to fight for him. The chief of Mehr traditions describes the fights of their founder Makaradvaja with one Mayúradhvaja. This tradition seems to embody the memory of an historical struggle. The *makara* or fish is the tribal badge of the Mehirs and is marked on a Morbi copperplate dated A.D. 901 (G. 585) and on the forged Dhíniki grant of the Mehr king Jāikādva. On the other hand Mayúradhvaja or peacock bannered would be the name of the Guptas beginning with Chandragupta who ruled in Gujarāt (A.D. 335-416) and whose coins have a peacock on the reverse. The tradition would thus be a recollection of the struggle between the Mehirs and Guptas in which about A.D. 470 the Guptas were defeated. The Mehirs seem to have been a northern tribe, who, the evidence of place names seems to show, passed south through Western Rājputāna, Jaslo, Ajo, Bad, and Kōml leaders of this tribe giving their names to the settlements of Jesalmir, Ajmir, Badner, and Kōmalner. The resemblance of name and the nearness of dates suggest a connection between the Mehirs and the great Panjāb conqueror of the Guptas Mihirakula (A.D. 512-540?). If not them-

## Chapter VIII.

THE VALABHIS,  
A.D. 509-766.

Senāpati Bhaṭarka,  
A.D. 509-520?

The Maṭṭakas,  
A.D. 470-509.

<sup>1</sup> The Mehirs seem to have remained in power also in north-east Kāthiāváḍa till the thirteenth century. Mokherāji Gohil the famous chief of Piram was the son of a daughter of Dhan Mehr or Mair of Dhanduka, Rās Māla, I. 316.

## Chapter VIII.

THE VALABHIS,  
A.D. 509-766.The Maitrakas,  
A.D. 470-509.

selves Hūnas the Mehars may have joined the conquering armies of the Hūnas and passing south with the Hūnas may have won a settlement in Kāthiavāda as the Kāthis and Jhādejās settled about 300 years later. After Senāpati Bhaṭārka's conquests in the south of the Peninsula the Mehars seem to have retired to the north of Kāthiavāda.

The above account of the founder of the Valabhis accepts the received opinion that he was the Senāpati or General of the Guptas. The two chief points in support of this view are that the Valabhis adopted both the Gupta era and the Gupta currency. Still it is to be noted that this adoption of a previous era and currency by no means implies any connection with the former rulers.<sup>1</sup> Both the Guṇjjaras (A.D. 580) and the Chālukyas (A.D. 642) adopted the existing era of the Traikutakas (A.D. 218-9) while as regards currency the practice of continuing the existing type is by no means uncommon.<sup>2</sup> In these circumstances, and seeing that certain of the earlier Valabhi inscriptions refer to an overlord who can hardly have been a Gupta, the identification of the king to whom the original Senāpati owed allegiance must be admitted to be doubtful.

All known copperplates down to those of Dharaṣena (A.D. 579 the great grandson of Bhaṭārka) give a complete genealogy from Bhaṭārka to Dharaṣena. Later copperplates omit all mention of any descendants but those in the main line.

Senāpati's  
Sons.

Senāpati Bhaṭārka had four sons, (1) Dharaṣena (2) Dronasimha (3) Dhruvasena and (4) Dharaṣatta. Of Dharaṣena the first son no record has been traced. His name first appears in the copperplates of his brother Dhruvasena where like his father he is called Senāpati. Similarly of the second son Dronasimha no record exists except in the copperplates of his brother Dhruvasena. In these copperplates unlike his father and elder brother Dhruvasena is called *Mahārāja* and is mentioned as 'invested with royal authority in person by the great lord, the lord of the wide extent of the whole world.' This great lord or *paramasūmi* could not have been his father Bhaṭārka. Probably he was the king to whom Bhaṭārka owed allegiance. It is not clear where Dronasimha was installed king probably it was in Kāthiavāda from the south-east of which his father and elder brother had driven back the Mehars or Maitrakas.<sup>3</sup>

<sup>1</sup> All the silver and copper coins found in Valabhi and in the neighbouring town of Sihor are poor imitations of Kumāragupta's (A.D. 417-453) and of Skandagupta's (A.D. 454-470) coins, smaller lighter and of bad almost rude workmanship. The only traces of an independent currency are two copper coins of Dharaṣena, apparently Dharaṣena IV., the most powerful of the dynasty who was called *Chakravartin* or Emperor. The question of the Gupta-Valabhi coins is discussed in Jour. Royal As. Socy. for Jan. 1893 pages 133-143. Dr. Balder (page 138) holds the view put forward in this note of Dr. Blegvad's namely that the coins are Valabhi copies of Gupta currency. Mr. Smith (Ditto, 142-143) thinks they should be considered the coins of the kings whose names they bear.

<sup>2</sup> The three types of coins still current at Ujjain, Bhilsa, and Gwālior in the territories of His Highness Sindbia are imitations of the previous local Muhammadan coinage.

<sup>3</sup> As the date of Dronasimha's investiture is about A.D. 520 it is necessary to consider what kings at this period claimed the title of supreme lord and could boast of ruling the whole earth. The rulers of this period whom we know of are Mihirakula,

The third son Dhruvasena is the first of several Valabhis of that name. Three copperplates of his remain: The Kukad grant dated Gupta 207 (A.D. 526),<sup>1</sup> an unpublished grant found in Junágadh dated Gupta 210 (A.D. 529), and the Valch grant dated Gupta 216 (A.D. 535).<sup>2</sup> One of Dhruvasena's attributes *Parama-bhattāraka-pādānudhyāta*, Bowing at the feet of the great lord, apparently applies to the same paramount sovereign who installed his brother Dronasimha. The paramount lord can hardly be Dhruvasena's father as his father is either called *Bhattārka* without the *parama* or more commonly *Senapati* that is general. Dhruvasena's other political attributes are *Mahārāja* Great King or *Mahāsīmanta* Great Chief, the usual titles of a petty feudatory king. In the A.D. 535 plates he has the further attributes of *Mahāpratihāra* the great doorkeeper or chamberlain, *Mahādandanāyaka* the great magistrate, and *Mahākīrtakritika* (?) or great general, titles which seem to show he still served some overlord. It is not clear whether Dhruvasena succeeded his brother Dronasimha or was a separate contemporary ruler. The absence of 'falling at the feet of' or other successional phrase and the use of the epithet 'serving at the feet of' the great lord seem to show that his power was distinct from his brothers. In any case Dhruvasena is the first of the family who has a clear connection with Valabhi from which the grants of A.D. 526 and 529 are dated.

In these grants Dhruvasena's father Bhattārka and his elder brothers are described as 'great Māheśvaras' that is followers of Śiva, while Dhruvasena himself is called *Paramabhagavata* the great Vaishnava. It is worthy of note, as stated in the A.D. 535 grant, that his niece Duddā (or Lailā?) was a Buddhist and had dedicated a Buddhist monastery at Valabhi. The latest known date of Dhruvasena is A.D. 535 (G. 216). Whether Dharapatta or Dharapatta's son Gulasena succeeded is doubtful. That Dharapatta is styled *Mahārāja* and that a twenty-four years' gap occurs between the latest grant of Dhruvasena and A.D. 559 the earliest grant of

## Chapter VIII.

THE VALABHIS,  
A.D. 509-766.Dhruvasena I. \*  
A.D. 526-535.

Yasodharman Vishnuvardhana, the descendants of Kumāragupta's son Paragupta, and the Gupta chiefs of Eastern Mīlwa. Neither Toramāpa nor Mihirakula appears to have borne the paramount title. *Paramēśvara* though the former is called *Maharājādhirāja* in the Eran inscription and *Samapati* or Lord of the Earth (— simply king) on his coins in the Gwalior inscription Mihirakula is simply called Lord of the Earth. He was a powerful prince but he could hardly claim to be ruler of "the whole circumference of the earth." He therefore cannot be the installer of Dronasimha. Turning next the Guptas of Magadha we find on the Bhutari seal the title of *Maharājādhirāja* given to each of them, but there is considerable reason to believe that their power had long since shrunk to Magadha and Eastern Mīlwa, and if Hsuen Tsang's Baladitya is Narasimhagupta, he must have been about A.D. 520 a feudatory of Mihirakula, and could not be spoken of as supreme lord, nor as ruler of the whole earth. The Guptas of Mīlwa have even less claim to these titles, as Bhūmiguṇa was a mere *Mahārāja*, and all that is known of him is that he won a battle at Eran in Eastern Mīlwa in A.D. 510-11. Last of all comes Vishnuvardhana or Yasodharman of Mandasor. In one of the Mandasor inscriptions he has the titles of *Rājadhirāja* and *Paramēśvara* (A.D. 532-33); in another he boasts of having carried his conquests from the Lauhitya (Brahmaputra) to the western ocean and from the Himālaya to mount Mahendra. It seems obvious that Yasodharman is the Paramasvami of the Valabhi plate, and that the reference to the western ocean relates to Bhattārka's successes against the Maitrakas.—(A.M.T.J.)

<sup>1</sup> Ind. Ant. V. 204.<sup>2</sup> Ind. Ant. IV 104.<sup>3</sup> In a commentary on the Kalpasūtra *Dandanāyaka* is described as meaning *Tantrapāla* that is head of a district

## Chapter VIII.

THE VALABHIS,  
A.D. 509-766Gulhasena,  
A.D. 539-569

Gulhasena favour the succession of Dharapatta. On the other hand in the A.D. 559 grant all Gulhasena's sins are said to be cleansed by falling at the feet of, that is, by succeeding, Dhruvasena. It is possible that Dharapatta may have ruled for some years and Dhruvasena again risen to power.

Of Gulhasena (A.D. 539<sup>2</sup>-569) three plates and a fragment of an inscription remain. Two of the grants are from Valabhi dated A.D. 559 and 565 (G. 240 and 245)<sup>1</sup>; the third is from Bhavnagar dated A.D. 567 (G. 248).<sup>2</sup> The inscription is on an earthen pot found at Valabhi and dated A.D. 566 (G. 247).<sup>3</sup> In all the later Valabhi plates the genealogy begins with Gulhasena who seems to have been the first great ruler of his dynasty. Gulhasena is a Sanskrit name meaning Whose army is like that of Kārttika-svāmi: his popular name was probably Gūhila. It appears probable that the Gohil and Gehlot Rajput chiefs of Kāthiāvada and Rājputāna, who are believed to be descendants of the Valabhis, take their name from Gulhasena or Gūha, the form Gehloti or Gehlot, *Gūhila-utta*, being a corruption of Gūhilaputra or descendants of Gūhila, a name which occurs in old Rājput records.<sup>4</sup> This lends support to the view that Gulhasena was believed to be the first king of the dynasty. Like his predecessors he is called Mahārāja or great king. In one grant he is called the great Śaiva and in another the great Buddhist devotee (*paramopāsaka*), while he grants villages to the Buddhist monastery of his paternal aunt's daughter Dudda. Though a Śaivite Gulhasena, like most of his predecessors, tolerated and even encouraged Buddhism. His minister of peace and war is named Skandabhata.

The beginning of Gulhasena's reign is uncertain. Probably it was not earlier than A.D. 539 (G. 220). His latest known date is A.D. 567 (G. 248) but he may have reigned two years longer.

Dharasena II  
A.D. 569-589

About A.D. 569 (G. 250) Gulhasena was succeeded by his son Dharasena II. Five of his grants remain, three dated A.D. 571 (G. 252),<sup>5</sup> the fourth dated A.D. 588 (G. 269),<sup>6</sup> and the fifth dated A.D. 589 (G. 270).<sup>7</sup> In the first three grants Dharasena is called Mahārāja or great king, in the two later grants is added the title Mahāsāmānta Great Feudatory, seeming to show that in the latter part of his reign Dharasena had to acknowledge as overlord some one whose power had greatly increased.<sup>8</sup> All his copperplates style Dharasena II. *Parama-māheśvara* Great Śaiva. A gap of eighteen years occurs between A.D. 589 Dharasena's latest grant and A.D. 607 the earliest grant of his son Śīlāditya.

Śīlāditya I.  
A.D. 594-609.

Dharasena II. was succeeded by his son Śīlāditya I. who is also called Dharmāditya or the sun of religion.

The Śātrunājaya Mahātmya has a prophetic account of one Śīlāditya who will be a propagator of religion in Vikrama Samvat

<sup>1</sup> Ind. Ant. VII. 66; IV. 174<sup>2</sup> Ind. Ant. V. 206.<sup>3</sup> Ind. Ant. XIV. 75<sup>4</sup> Kumārapāla-Charita, Abu Inscriptions.<sup>5</sup> Ind. Ant. VIII. 302, VII. 68, XIII. 160<sup>6</sup> Ind. Ant. VI. 9<sup>7</sup> Ind. Ant. VII. 90.<sup>8</sup> This change of title was probably connected with the increase of Gurjara power, which resulted in the founding of the Gurjara kingdom of Broach about A.D. 580. See Chapter X, below.

477 (A.D. 420). This *Māhātmya* is comparatively modern and is not worthy of much trust. Vikrama Samvat 477 would be A.D. 420 when no Valabhi kingdom was established and no Śīlāditya can have flourished. If the date 477 has been rightly preserved, and it be taken in the Śaka era it would correspond with Gupta 237 or A.D. 556, that is thirty to forty years before Śīlāditya's reign. Although no reliance can be placed on the date still his second name Dharmāditya gives support to his identification with the Śīlāditya of the *Māhātmya*.

His grants like many of his predecessors style Śīlāditya a great devotee of Śiva. Still that two of his three known grants were made to Buddhist monks shows that he tolerated and respected Buddhism. The writer of one of the grants is mentioned as the minister of peace and war Chandrabhātī; the Dātaka or donor of the gift in two of the Buddhist grants is Bhātta Adityaśaśa apparently some military officer. The third grant, to a temple of Śiva, has for its Dātaka the illustrious Kharagraha apparently the brother and successor of the king.

Śīlāditya's reign probably began about A.D. 594 (G. 275). His latest grant is dated A.D. 609 (G. 290).<sup>1</sup>

Śīlāditya was succeeded by his brother Kharagraha, of whom no record has been traced. Kharagraha seems to have been invested with sovereignty by his brother Śīlāditya who probably retired from the world. Kharagraha is mentioned as a great devotee of Śiva.

Kharagraha was succeeded by his son Dharasena III of whom no record remains.

Dharasena III. was succeeded by his younger brother Dhruvasena II. also called Bālāditya or the rising sun. A grant of his is dated A.D. 629 (G. 310).<sup>2</sup> As observed before, Dhruvasena is probably a Sanskritised form of the popular but meaningless Dhruvapaṭṭa which is probably the original of Hiuen Tsiang's 'Tu-lu-h'o-po-tu, as A.D. 629 the date of his grant is about eleven years before the time when (640) Hiuen Tsiang is calculated to have been in Mālwa if not actually at Valabhi. If one of Dhruvasena's poetic attributes is not mere hyperbole, he made conquests and spread the power of Valabhi. On the other hand the Navsāri grant of Jayabhāta III (A.D. 706-731) the Gurjjara king of Broach states that Dadda II. of Broach (A.D. 620-650) protected the king of Valabhi who had been defeated by the great Śrī Harshadeva (A.D. 607-648) of Kanauj.

Dhruvasena II. was succeeded by his son Dharasena IV. perhaps the most powerful and independent of the Valabhis. A copper-plate dated A.D. 649 (G. 330) styles him *Parama-bhaṭṭāraka, Mahārājādhirāja, Paramēśvara, Chakravartin* Great Lord, King of Kings, Great Ruler, Universal Sovereign. Dharasena IV.'s successors continue the title of *Mahārājādhirāja* or great ruler, but none is called *Chakravartin* or universal sovereign a title which implies numerous conquests and widespread power.

## Chapter VIII.

THE VALABHIS,  
A.D. 509-766.

Śīlāditya I.  
A.D. 590-609.

Kharagraha,  
A.D. 610-615.

Dharasena III.  
A.D. 615-620.

Dhruvasena II.  
(Bālāditya)  
A.D. 620-640.

Dharasena IV.  
A.D. 640-649.

<sup>1</sup> Ind. Ant. XI. 306.

<sup>2</sup> Ind. Ant. VI. 13

## Chapter VIII.

THE VALABHIS,  
A.D. 509-766.Dharasena IV.  
A.D. 640-649.

Two of Dharasena IV.'s grants remain, one dated A.D. 645 (G. 326) the other A.D. 649 (G. 330). A grant of his father Dhruvasena dated A.D. 631 (G. 315) and an unpublished copperplate in the possession of the chief of Morbi belonging to his successor Dhruvasena III. dated A.D. 651 (G. 332) prove that Dharasena's reign did not last more than seventeen years. The well known Sanskrit poem *Bhaṭṭikāvya* seems to have been composed in the reign of this king as at the end of his work the author says it was written at Valabhi protected (governed) by the king the illustrious Dharasena.<sup>1</sup> The author's application to Dharasena of the title *Narendra* Lord of Men is a further proof of his great power.

Dhruvasena III.  
A.D. 650-656.

Dharasena IV. was not succeeded by his son but by Dhruvasena the son of Derabhata the son of Dharasena IV.'s paternal grand-mother. Derabhata appears not to have been ruler of Valabhi itself but of some district in the south of the Valabhi territory. His epithets describe him as like the royal sage Agastya spreading to the south, and as the lord of the earth which has for its two breasts the Sahya and Vindhya hills. This description may apply to part of the province south of Kaira where the Sahyādrī and Vindhya mountains may be said to unite. In the absence of a male heir in the direct line, Derabhata's son Dhruvasena appears to have succeeded to the throne of Valabhi. The only known copperplate of Dhruvasena III.'s, dated A.D. 651 (G. 332), records the grant of the village of Pedhapadra in Vantali, the modern Vantali in the Navanagar State of North Kathiāwāḍa. A copperplate of his elder brother and successor Kharagraha dated A.D. 656 (G. 337) shows that Dhruvasena's reign cannot have lasted over six years.

Kharagraha  
A.D. 656-66.

The less than usually complimentary and respectful reference to Dhruvasena III. in the attributes of Kharagraha suggests that Kharagraha took the kingdom by force from his younger brother as the rightful successor of his father. At all events the succession of Kharagraha to Dhruvasena was not in the usual peaceful manner. Kharagraha's grant dated A.D. 656 (G. 337) is written by the Divinapati or Chief Secretary and minister of peace and war Anahilla son of Skandabhata.<sup>2</sup> The *Dūtaka* or causer of the gift was the *Pramātri* or survey officer Śrīnā.

Śilāditya III.  
A.D. 666-675.

Kharagraha was succeeded by Śilāditya III. son of Kharagraha's elder brother Śilāditya II. Śilāditya II. seems not to have ruled at Valabhi but like Derabhata to have been governor of Southern Valabhi, as he is mentioned out of the order of succession and with the title Lord of the Earth containing the Vindhya mountain. Three grants of Śilāditya III. remain, two dated A.D. 666 (G. 346)<sup>3</sup> and the third dated A.D. 671 (G. 352)<sup>4</sup>. He is called *Parama-bhaṭṭāraka* Great Lord, *Mahārājādhirāja* Chief King among Great Kings, and *Paramēśvara* Great Ruler. These titles continue to be applied to all

<sup>1</sup> *Kavyamulam rachitam mayā Valubhyām, S'ri Dharasena-narendra pādīdyam.*<sup>2</sup> *Ind. Ant.* VII. 70.<sup>3</sup> *Journ. Beng. A. S.* IV. and an unpublished grant in the museum of the B. B. R. A. Soc.<sup>4</sup> *Ind. Ant.* XI. 305.

subsequent Valabhi kings. Even the name Śīlāditya is repeated though each king must have had some personal name.


Śīlāditya III. was succeeded by Śīlāditya IV. of whom one grant dated A.D. 691 (G. 379) remains. The writer prepared the grant in the name of the king. The grant is in the name of Śīlāditya III. Haragana the son of Bappa the son of the king. The grant is in the name of the prince Kharagana, which may perhaps be the personal name of the next king Śīlāditya V.

Of Śīlāditya V the son and successor of Śīlāditya IV. two grants dated A.D. 722 (G. 403) both from Gondal remain. Both record grants to the same person. The writer of both was general Gillaka son of Buddhahatta, and the gift-causer of both prince Śīlāditya.

Of Śīlāditya VI. the son and successor of the last, one grant dated A.D. 760 (G. 441) remains. The grantee is an Atharvavedi Brahman. The writer is Sasyagupta son of Emapatha and the gift-causer is Gānjasāti Śrī Jajjar (or Jajjir).

Of Śīlāditya VII the son and successor of the last, who is also called Dhruvabhata (Sk. Dhruvabhata), one grant dated A.D. 766 (G. 447) remains.

The following is the genealogy of the Valabhi Dynasty:



### Chapter VIII.

THE VALABHIS,  
A.D. 509 - 766.

Śīlāditya IV.  
A.D. 691.

Śīlāditya V.  
A.D. 722.

Śīlāditya VI.  
A.D. 760.

Śīlāditya VII.  
A.D. 766.

Valabhi  
Family Tree.

## Chapter VIII.

THE VALABHIS,  
A.D. 509-766.The Fall of  
Valabhi,  
A.D. 750-770.

Of the overthrow of Valabhi many explanations have been offered.<sup>1</sup> The only explanation in agreement with the copperplate evidence that a Śilāditya was ruling at Valabhi as late as A.D. 766 (Val. Sam. 447)<sup>2</sup> is the Hindu account preserved by Alberuni (A.D. 1030)<sup>3</sup> that soon after the Sindh capital Mansūra was founded, say A.D. 750-770, Ranka a disaffected subject of the era-making Valabhi, with presents of money persuaded the Arab lord of Mansūra to send a naval expedition against the king of Valabhi. In a night attack king Valabha was killed and his people and town were destroyed. Alberuni adds: Men say that still in our time such traces are left in

<sup>1</sup> Since his authorities mention the destroyers of Valabhi under the vague term *mlechchhas* or barbarians and since the era in which they date the overthrow may be either the Vikrama B.C. 57, the Sakā A.D. 78, or the Valabhi A.D. 319, Tod is forced to offer many suggestions. His proposed dates are A.D. 244 Vik. Sam. 300 (Western India, 269), A.D. 424 Val. Sam. 105 (Ditto, 51 and 214), A.D. 524 Val. Sam. 205 (Annals of Rajasthan, I. 83 and 217-220), and A.D. 619 Val. Sam. 300 (Western India, 352). Tod identifies the barbarian destroyers of Valabhi either with the descendants of the second century Parthians, or with the White Huns (Göcs or Kathis, or with a mixture of these whom the beginning of the sixth century supplanted the Parthians (An. of Rāj. I. 83 and 217-220, Western India, 214, 352). Elliot (History, I. 408) accepting Tod's date A.D. 524 refers the overthrow to Skythian barbarians from Sindh. Elphinstone, also accepting A.D. 524 as an approximate date, suggested (History, 3rd Edition, 212) as the destroyer the Sassanian Naushirvān or Chosroes the Great (A.D. 531-579) citing in support of a Sassanian invasion Malcolm's Persia, I. 141 and Pottinger's Travels, 386. Forbes (Rās Mālā, I. 22) notes that the Jain accounts give the date of the overthrow Vik. Sam. 375 that is A.D. 319 apparently in confusion with the epoch of the Gupta era which the Valabhi kings adopted \* Forbes says (Ditto, 21) If the destroyers had not been called *mlechchhas* I might have supposed them to be the Hakkha Chalukyas. Genl. Cunningham (Anc. Geog. 318) holds that the date of the destruction was A.D. 658 and the destroyer the Rashtrakūṭa Raja Govind who restored the ancient family of Samashṭīa. Thomas (Prinsep's Useful Tables, 158) fixes the destruction of Valabhi at A.D. 715 (S. 802). In the Kāthiāwar Gazetteer (Col. Watson in one passage (page 671) says the destroyers may have been the early Muhammadans who retired as quickly as they came. In another passage (page 274), accepting Mr. Burgess (Arch. Sur. Rep. IV. 75) Gupta era of A.D. 195 and an overthrow date of A.D. 642, and citing a Wadhvān couplet telling how Elhal Valabhi withstood the huns, Col. Watson suggests the destroyers may have been Iranians. If the Persians came in A.D. 642 they must have come not as raiders but as refugees. If they could they would not have destroyed Valabhi. If the Persians destroyed Valabhi where next did they flee to.

\* Similarly S. 205 the date given by some of Col. Tod's authorities (An. of Rāj. I. 82 and 217-220) represents A.D. 524 the practical establishment of the Valabhi dynasty. The mistake of ascribing an era to the overthrow not to the founding of a state occurs (compare Sachau's Alberuni, II. C) in the case both of the Vikrama era B.C. 57 and of the Shalivahana era A.D. 78. In both these cases the error was intentional. It was devised with the aim of hiding the supremacy of foreigners in early Hindu history. So also, according to Alberuni's information (Sachau, II. 7) the Gupta-kāla A.D. 319 marks the ceasing not the beginning of the wicked and powerful Guptas. This device is not confined to India. His Mede informant told Herodotus (H. 150 Rawlinson's Herodotus, I. 107) that B.C. 705 was the founding of the Median monarchy. The date really marked the overthrow of the Medes by the Assyrian Sargon.

<sup>2</sup> Tod (An. of Rāj. I. 231) notices what is perhaps a reminiscence of this date (A.D. 766). It is the story that Bappa, who according to Mewād tradition is the founder of Gehlot power at Chitor, abandoned his country for Irān in A.D. 764 (S. 820). It seems probable that this Bappa or Saila is not the founder of Gehlot power at Chitor, but, according to the Valabhi use of Bappa, is the founder's father and that this retreat to Irān refers to his being carried captive to Mansūra on the fall either of Valabhi or of Gandhār.

<sup>3</sup> Reinaud's Fragments, 143 note 1; Mémoire Sur l'Inde, 105; Sachau's Alberuni, I. 193. The treachery of the magician Ranka is the same cause as that assigned by Forbes (Rās Mālā, I. 12-18) from Jain sources. The local legend (Ditto, 18) points the inevitable Tower of Siloam moral, a moral which (compare Rās Mālā, I. 18) is probably at the root of the antique tale of Lot and the Cities of the Plain, that men whose city was so completely destroyed must have been sinners beyond others. Dr. Nicholson (J. R. A. S. Ser. I Vol. XIII. page 153) in 1851 thought the site of Valabhi bore many traces of destruction by water.

that country as are found in places wasted by an unexpected attack.<sup>1</sup> For this expedition against Valabhi Alberuni gives no date. But as Mansūra was not founded till A.D. 750<sup>2</sup> and as the latest Valabhi copperplate is A.D. 766 the expedition must have taken place between A.D. 750 and 770. In support of the Hindu tradition of an expedition from Mansūra against Valabhi between A.D. 750 and 770 it is to be noted that the Arab historians of Sindh record that in A.D. 758 (H. 140) the Khalif Mansūr sent Amru bin Jamal with a fleet of barks to the coast of Barada.<sup>3</sup> Twenty years later A.D. 776 (H. 160) a second expedition succeeded in taking the town, but, as sickness broke out, they had to return. The question remains should the word, which in these extracts Elliot reads Barada, be read Balaba. The lax rules of Arab cursive writing would cause little difficulty in adopting the reading Balaba.<sup>4</sup> Further it is hard to believe that Valabhi, though to some extent sheltered by its distance from the coast and probably a place of less importance than its chroniclers describe, should be unknown to the Arab raiders of the seventh and eighth centuries and after its fall be known to Alberuni in the eleventh century. At the same time, as during the eighth century there was, or at least as there may have been,<sup>5</sup> a town Barada on the south-west coast of Kāthiāváda the iden-

## Chapter VIII.

THE VALABHIS,  
A.D. 509-766.The Fall of  
Valabhi,  
A.D. 750-770.

<sup>1</sup> Lassen (Ind. Alt. III 533) puts aside Alberuni's Arab expedition from Mansūra as without historical support and inadmissible. Lassen held that Valabhi flourished long after its alleged destruction from Mansūra. Lassen's statement (see Ind. Alt. III 533) is based on the mistaken idea that as the Valabhis were the Balharas the Balharas' capital Mankir must be Valabhi. So far as is known, except Alberuni himself (see below) none of the Arab geographers of the ninth tenth or eleventh centuries mentions Valabhi. It is true that according to Lassen (Ind. Alt. 536) Masudi A.D. 915, Istakhri A.D. 951, and Ibn Hikal A.D. 976 all attest the existence of Valabhi up to their own time. This remark is due either to the mistake regarding Malkhet or to the identification of Balwi or Balzi in Sindh (Elliot's History, I. 27-34) with Valabhi. The only known Muslim reference to Valabhi later than A.D. 750 is Alberuni's statement (Sachau, II. 7) that the Valabhi of the era is 30 *parasangs* or 200 miles south of Amulavada. That after its overthrow Valabhi remained, as it still continues, a local town has been shown in the text. Such an after-life is in no way inconsistent with its destruction as a leading capital in A.D. 767.

<sup>2</sup> According to Alberuni (Sachau, I. 21) Al Mansūra, which was close to Brāhmanabād about 47 miles north east of Hindarābad (Elliot's Muslim History, I. 372-374) was built by the great Muhammad Kasim about A.D. 713. Apparently Alberuni wrote Muhammad Kasim by mistake for his grandson Amru Muhammad (Elliot, I. 372 note 1 and 442-3), who built the city a little before A.D. 750. Renaud (Fragments, 210) makes Amru the son of Muhammad Kasim. Masudi (A.D. 915) gives the same date (A.D. 750), but (Elliot, I. 441) makes the builder the Umayyad governor Mansūr bin Ja'far Idrisi (A.D. 11). Elliot, I. 78 says Mansura was built and named in honour of the Khalif Abū Jāfar al-Mansur. If so its building would be later than A.D. 751. On such a point Idrisi's authority carries little weight. Elliot, I. 244.

<sup>4</sup> That the word read Barada by Elliot is in the lax pointless *shikasta* writing is shown by the different proposed readings (Elliot, I. 444 note 1) Nārand, Barand, and Barid. So far as the original goes Balaba is probably as likely a rendering as Barada. Renaud (Fragments, 212) says he cannot restore the name.

Though, except as applied to the Porbandar range of hills, the name Barada is almost unknown, and though Ghumh not Barada was the early (eighth-twelfth century) capital of Porbandar some place named Barada seems to have existed on the Porbandar coast. As early as the second century A.D., Ptolemy (McCrindle, 37) has a town Bara-xema on the coast west of the village *Kome* (probably the road or *kom*) of Saurashtra; and St. Martin (Géographie Grecque et Latine de l'Inde, 203) identifies Pliny's (A.D. 77) Varetatue next the Odombeni or people of Kachh with the Varadas according to Hemachandra (A.D. 1150) a class of foreigners or *mlechchhas*. A somewhat tempting identification of Barada is with Beruni's Bārwi (Sachau, I. 208) or Baraoua (Reinaud's Fragments, 121) 84 miles (14 *parasangs*) west of Somanātha. But an examination of Beruni's text shows that Bārwi is not the name of a place but of a product of Kachh the *bāra* or bezoar stone.

**Chapter VIII.**

THE VALABHIS,  
A.D. 509-766.

The Fall of  
Valabhi,  
A.D. 750-770.

The Importance  
of Valabhi.

tification of the raids against Barada with the traditional expedition against Balaba though perhaps probable cannot be considered certain. Further the statement of the Sindh historians<sup>1</sup> that at this time the Sindh Arabs also made a naval expedition against Kandahar seems in agreement with the traditional account in Tod that after the destruction of Valabhi the rulers retired to a fort near Cambay from which after a few years they were driven<sup>2</sup>. If this fort is the Kandahar of the Sindh writers and Gundahar on the Broach coast about twenty miles south of Cambay, identifications which are in agreement with other passages, the Arab and Rājput accounts would fairly agree.<sup>3</sup>

The discovery of its lost site, the natural but mistaken identification of its rulers with the famous eighth and ninth century (A.D. 753-972) Balharas of Mulkhet in the East Dakhan,<sup>4</sup> the tracing to Valabhi of the Rina of Udepur in Mewād the head of the Sesolia or Gohils the most exalted of Hindu families<sup>5</sup>; and in later times the wealth of Valabhi copperplates have combined to make the Valabhis one of the best known of Gujarāt dynasties. Except the complete genealogy, covering the 250 years from the beginning of the sixth to the middle of the eighth century, little is known of Valabhi or its chiefs. The

<sup>1</sup> Elliot, I. 115.

<sup>2</sup> Compare Tod Annals, I. 83 and 217. Gajm or Gayni another capital whence the last prince Shihab was expelled by Pathan invaders in the sixth century.

<sup>3</sup> Compare Richard Fremonts 212 note 1, who identifies it with the Ain-i-Akbari Kandahar that is Gundahar in Broach. The identification is doubtful. Tod (Annals, I. 217) names the fort Hupa or Gayni and there was a fort Gajm close to Cambay. Elliot (I. 115) would identify the Arab Kandahar with Khandahar in north-west Kathiavād.

Even after A.D. 770 Valabhi seems to have been attacked by the Arabs. Dr Bhagvanlal notices that two Jain dates for the destruction of the city 826 and 846 are in the Vira era and that this means not the Mahavira era of B.C. 526 but the Vikram era of B.C. 57. The corresponding dates are therefore A.D. 769 and 829. Evidence in support of the A.D. 759 and 770 date is given in the text. On behalf of Dr Bhagvanlal's second date A.D. 829 it is remarkable that in or about A.D. 830 (Elliot, I. 117) Mūsa the Arab governor of Sindh captured Bala the ruler of As Sharqi. As there seems no reason to identify this As Sharqi with the Sindh lake of As Sharqi mentioned in a raid in A.D. 750 (Elliot, I. 141; J. R. A. S. (1893) page 76) the phrase would mean Bala king of the east. The Arab record of the defeat of Bala would thus be in close agreement with the Jain date for the latest foreign attack on Valabhi.

<sup>4</sup> The identification of the Balharas of the Arab writers with the Chālukyas (A.D. 500-753) and Rashtrakūṭas (A.D. 753-972) of Mulkhet in the East Dakhan has been accepted. The vagueness of the early (A.D. 850-900) Arab geographers still more the inaccuracy of Idrisi (A.D. 1137) in placing the Balharas capital in Gujarat (Elliot, I. 87) suggested a connection between Balharas and Valabhi. The suitability of this identification was increased by the use among Rājput writers of the title Balakaraī for the Valabhi chief (Tod An. of Rāj. I. 83) and the absence among either the Chālukyas (A.D. 500-753) or the Rashtrakūṭas (A.D. 753-972) of Mulkhet of any title resembling Balhara. Prof. Bhandarkar's (Decan History, 56-57) discovery that several of the early Chālukyas and Rashtrakūṭas had the personal name Vallabha Beloved settled the question and established the accuracy of all Masudi's (A.D. 915) statements (Elliot, I. 19-21) regarding the Balhara who ruled the Kanakara; that is Kanakura or Karnātak (Sachau's Kermui I. 202; II. 318) and had their Kanarese (Kuriya) capital at Mankir (Mulkhet) 640 miles from the coast.

<sup>5</sup> After their withdrawal from Valabhi to Mewād the Vālas took the name of Gehlot (see below page 98), then of Aharya from a temporary capital near Udepur (Tod's An. of Rāj. I. 215), next of Sesolia in the west of Mewād (Tod's An. of Rāj. I. 216; Western India, 57). Since 1508 the Rina's head-quarters have been at Udepur. Rāj. Gaz. III. 18. After the establishment of their power in Chitor (A.D. 780), a branch of the Gehlot or Gohil family withdrew to Kheir in south-west Mārwar. These driven south by the Rathods in the end of the twelfth century are the Gohils of Pīram, Bhāvnagar, and Rājpipla in Kāthiavād and Gujarāt. Tod's Annals of Rāj. I. 114, 228.

origin of the city and of its rulers, the extent of their sway, and the cause and date of their overthrow are all uncertain. The unsuitness of the site, the want of reservoirs or other stone remains, the uncertainty when its rulers gained an independent position, the fact that only one of them claimed the title *Chakravarti* or All Ruler are hardly consistent with any far-reaching authority. Add to this the continuance of Maitraka or Mer<sup>1</sup> power in North Káthiáváda, the separateness though perhaps dependence of Sauráshtra even in the time of Valabhi's greatest power,<sup>2</sup> the rare mention of Valabhi in contemporary Guj'rat grants,<sup>3</sup> and the absence of trustworthy reference in the accounts of the Arab raids of the seventh or eighth centuries tend to raise a doubt whether, except perhaps during the ten years ending 650, Valabhi was ever of more than local importance.

In connection with the pride of the Sesodias or Gohils of Mewád in their Valabhi origin<sup>4</sup> the question who were the Valabhis has a special interest. The text shows that Pandit Bhagvínal was of opinion the Valabhis were Gurjjaras. The text also notes that the Pandit believed they reached south-east Káthiáváda by sea from near Broach and that if they did not come to Broach from Málwa at least the early rulers obtained (A.D. 520 and 526) investiture from the Málwa kings. Apart from the doubtful evidence of an early second to fifth century Bála or Valabhi three considerations weigh against the theory that the Valabhis entered Gujarat from Málwa in the sixth century. First their acceptance of the Gupta era and of the Gupta currency raises the presumption that the Valabhis were in Káthiáváda during Gupta ascendancy (A.D. 410 - 480): Second that the Sesodias trace their pedigree through Valabhi to an earlier settlement at Dhánk in south-west Káthiáváda and that the Válas of Dhánk still hold the place of heads of the Válas of Káthiáváda: And Third that both Sesodias and Válas trace their origin to Kanaksen a second century North Indian immigrant into Káthiáváda combine to raise the presumption that the Válas were in Káthiáváda before the historical founding of Valabhi in A.D. 526<sup>4</sup> and that the city took its name from its founders the Válas or Bálás.

Whether or not the ancestors of the Gohils and Válas were settled in Káthiáváda before the establishment of Valabhi about A.D. 526

## Chapter VIII.

THE VALABHIS,  
A.D. 509 - 766.

The Importance  
of Valabhi,  
A.D. 750 - 770.

Valabhi and  
the Gohils.

<sup>1</sup> The somewhat doubtful Jakkadeva plates (above page 87 and Kathiavada Gazetteer, 275) seem to show the continuance of Maitraka power in North Káthiáváda. This is supported by the expedition of the Arab chief of Sindham to Kachch (A.D. 840) against the Medhs of Hind which ended in the capture of Mallá in North Káthiáváda. Elliot, I. 450. Hsien Tsiang (A.D. 630) (Beal's Buddhist Records, II 159) describes Sauráshtra as a separate state but at the same time notes its dependence on Valabhi. Its rulers seem to have been Mehars. In A.D. 713 (Elliot, p. 123) Muhammad Kasim made peace with the men of Saurast, Medhs, seafarers, and pirates.

<sup>2</sup> The only contemporary rulers in whose grants a reference to Valabhi has been traced are the Gurjjaras of Broach (A.D. 580-808) one of whom, Dadda II (A.D. 633), is said (Ind. Ant. XIII. 79) to have gained renown by protecting the lord of Valabhi who had been defeated by the illustrious Sri Harshadeva (A.D. 608 - 649), and another Jayakhaṭa in A.D. 706 (Ind. Ant. V. 115) claims to have quieted with the sword the impetuosity of the lord of Valabhi.

<sup>3</sup> Tod An. of Raj. I. 217: Western India, 269.

<sup>4</sup> Tod An. of Raj. I. 112 and Western India, 148. Rás Málá, I. 21. It is not clear whether these passages prove that the Sesodias or only the Válas claim an early settlement at Dhánk. In any case (see below page 101) both clans trace their origin to Kanaksen.

## Chapter VIII.

THE VALABHIS,  
A.D. 509-766.Valabhi and  
the Gehlots.

several considerations bear out the correctness of the Rājput traditions and the Jain records that the Gohils or Sesodias of Mewād came from Bala or Valabhi in Kathiavāḍa. Such a withdrawal from the coast, the result of the terror of Arab raids, is in agreement with the fact that from about the middle of the eighth century the rulers of Gujarāt established an inland capital at Anahilavāḍa (A.D. 746).<sup>1</sup> It is further in agreement with the establishment by the Gohil refugees of a town Balh in Mewād; with the continuance as late as A.D. 968 (S. 1024) by the Sesodia chief of the Valabhi title Śīlāditya or Sail<sup>2</sup>; and with the peculiar Valabhi blend of Sun and Śiva worship still to be found in Udepur.<sup>3</sup> The question remains how far can the half-poetic accounts of the Sesodias be reconciled with a date for the fall of Valabhi so late as A.D. 766. The mythical wanderings, the caveborn Guha, and his rule at Idar can be easily spared. The name Gehlot which the Sesodias trace to the caveborn Guha may as the Bhāvnagar Gehlots hold have its origin in Guhasena (A.D. 559-567) perhaps the first Valabhi chief of more than local distinction.<sup>4</sup> Tod<sup>5</sup> fixes the first historical date in the Sesodia family history at A.D. 720 or 728 the ousting of the Mori or Maurya of Chitor by Bappa or Sail. An inscription near Chitor shows the Mori in power in Chitor as late as A.D. 714 (S. 770).<sup>6</sup> By counting back nine generations from Sakti Kumāra the tenth from Bappa whose date is A.D. 1068 Tod fixes A.D. 720-728 as the date when the Gohils succeeded the Moris. But

<sup>1</sup> Tod's Western India, 51.<sup>2</sup> Tod's An. of Raj. I. 230.

<sup>3</sup> The cherished title of the later Valabhis, Śīlāditya Sun of Virtue, confirms the special sun worship at Valabhi, which the mention of Dharapatta (A.D. 530) as a devotee of the supreme sun supports, and which the legends of Valabhi's sun-horse and sun-fountain keep fresh (Rās Mala, I. 14-18). So the great one-stone lingas, the most notable trace of Valabhi city (J. R. A. S. Ser. I. Vol. XIII. 119 and XVII. 271), bear out the Valabhi copperplate claim that its rulers were great worshippers of Śiva. Similarly the Ikma of Udepur, while enjoying the title of Sun of the Hindus, prospering under the sun banner, and specially worshipping the sun (Tod's Annals, I. 565) is at the same time the Minister of Śiva the One Ling *Eklingāditya* (Ditto 222, Raj. Gaz. III. 53). The blend is natural. The fierce moon-tide sun is Mahakālā the Destroyer. Like Śiva the Sun is lord of the Moon. And unshrilled by Somnatha the great Soul Home the souls of the dead pass heavenwards along the rays of the setting sun. [Compare Sachau's Alberuni, II. 168.] It is the common sun element in Śaivism and in Vaiṣṇavism that gives their holiness to the sunset shrines of Somnatha and Dwarka. For (Ditto, 169) the setting sun is the door whence men march forth into the world of existence Westwards, heavenwards.

<sup>4</sup> This explanation is hardly satisfactory. The name Gehlot seems to be Guhila-putra from Gohila-putra an ancient Brāhman gotra, one of the not uncommon cases of Rājputs with a Brāhman gotra. The Rājput use of a Brāhman gotra is generally considered a technical affiliation, a mark of respect for some Brāhman teacher. It seems doubtful whether the practice is not a reminiscence of an ancestral Brāhman strain. This view finds confirmation in the Aitpur inscription (Tod's Annals, I. 802) which states that Guhadit the founder of the Gohil tribe was of Brāhman race *Vipre kula*. Compare the legend (Rās Mala, I. 13) that makes the first Śīlāditya of Valabhi (A.D. 590-609) the son of a Brāhman woman. Compare (Elliot, I. 411) the Brāhman Chāch (A.D. 630-670) marrying the widow of the Shāhi king of Aḥor in Sindh who is written of as a Rājput though like the later (A.D. 850-1040) Shāhiyas of Kabul (Alberuni, Sachau II. 48) the dynasty may possibly have been Brāhmans\*. The following passage from Hodgson's Essays (J. A. Soc. B. II. 218) throws light on the subject. Among the Khās or Rājputs of Nepal the sons of Brāhmans by Khās women take their fathers' gotras. Compare Ibbetson's Punjab Census 1931 page 236.

\* In support of a Brāhman origin is Prinsep's conjecture (J. A. S. B. LXXIV. (Feb. 1838) page 94) that Divaj the name of the first recorded king may be Divja or Twice-born. But Divaj for Devāditya, like Silaj for Śīlāditya, seems simpler and the ease with which the writer speaks of Chāch as the Brāhman almost implies that his predecessors were not Brāhmans. According to Elliot (II. 426) the Pāls of Kabul were Rājputs, perhaps Khattias.

<sup>5</sup> Tod's Annals, I. 229-231.<sup>6</sup> Annals, I. 229.

the sufficient average allowance of twenty years for each reign would bring Bappa to A.D. 770 or 780 a date in agreement with a fall of Valabhi between A.D. 760 and 770, as well as with the statement of Abul Fazl, who, writing in A.D. 1590, says the Rāna's family had been in Mewād for about 800 years.<sup>1</sup>

The Arab accounts of the surprise-attack and of the failure of the invaders to make a settlement agree with the local and Rājputana traditions that a branch of the Valabhi family continued to rule at Valab until its conquest by Mūla Rāja Solankhi in A.D. 950.<sup>2</sup> Though their bards favour the explanation of Vala from the Gujarati *vala* 'return' or the Persian *vāla*<sup>3</sup> 'noble' the family claim to be of the old Valabhi stock. They still have the tradition they were driven out by the Muslims, they still keep up the family name of Selat or Siladitya.<sup>4</sup>

The local tradition regarding the settlement of the Valas in the Balakshetra south of Valabhi is that it took place after the capture of Valabhi by Mūla Rāja Solankhi (A.D. 950).<sup>5</sup> If, as may perhaps be accepted, the present Valas represent the rulers of Valabhi it seems to follow the Valas were the overlords of Balakshetra at least from the time of the historical prosperity of Valabhi (A.D. 526-680). The traditions of the Bahmās who held the east of Sorath show that when they arrived (A.D. 1200-1250) the Vala Rājputs were in possession and suggest that the lands of the Vālas originally stretched as far west as Dm.<sup>6</sup> That the Vālas held central Kathiavāda is shown by their possession of the old capital Vauthali nine miles south-west of Junāgadh and by (about A.D. 850) their transfer of that town to the Chudāsamās.<sup>7</sup> Dhānk, about twenty-five miles north-west of Junāgadh, was apparently held by the Vālas under the Jetwas when (A.D. 800-1200?) Ghumli or Bhumli was the capital of south-west Kāthiavāda. According to Jetwa accounts the Vālas were newcomers whom the Jetwas allowed to settle at Dhānk.<sup>8</sup> But as the Jetwas are not among the earliest settlers in Kāthiavāda it seems more probable that, like the Chudāsamās at Vauthali, the Jetwas found the Vālas in possession. The close connection of the Vālas with the earlier waves of Kāthis is admitted.<sup>9</sup> Considering that the present

## Chapter VIII.

THE VALABHIS,  
A.D. 509-766.

The Vālas of  
Kāthiavāda.

<sup>1</sup> Gladwin's *Ain-i-Akbari*, II. 81. Tod's *Annals*, I. 235 and note\*. Tod's dates are confused. The *Aitpur inscription* (Ditto, page 230) gives Sakti Kumara's date A.D. 968 (81024) while the authorities which Tod accepts (Ditto, 231) give A.D. 1068 (81125). That the Moris were not driven out of Chitor as early as A.D. 728 is proved by the *Nasāri inscription* which mentions the Arabs defeating the Mauryas as late as A.D. 738-9 (Sam. 490). See above page 56.

<sup>2</sup> Tod *Western India* 268 says Siddha Rāja (A.D. 1091-1143) Mūla Rāja (A.D. 942-997) seems correct. See *Ras Mali*, I. 65. <sup>3</sup> *Kathiawar Gazetteer*, 672.

<sup>4</sup> The chronicles of Bhadro, fifty-one miles south-west of Bhavnagar, have (Kāth. Gaz. 380) a Selat Vala as late as A.D. 1574.

<sup>5</sup> *Kathiawar Gazetteer*, 672. Another account places the movement south after the arrival of the Gohils A.D. 1250. According to local traditions the Vālas did not pass to Bhadro near Mahuva till A.D. 1554 (Kāth. Gaz. 380) and from Bhadro (Kāth. Gaz. 660) retired to Dholavra.

<sup>6</sup> Kāth. Gaz. 111 and 132. According to the *Ain-i-Akbari* (Gladwin, II. 61) the inhabitants of the ports of Mahua and Tulaja were of the Vala tribe.

<sup>7</sup> Kāth. Gaz. 680.

<sup>8</sup> Kāth. Gaz. 114.

<sup>9</sup> The Vāla connection with the Kāthis complicates their history. Col. Watson (Kāth. Gaz. 130) seems to favour the view that the Vālas were the earliest wave of Kāthis who came into Kāthiavāda from Mālwa apparently with the Guptas (A.D. 450) (Ditto, 671). Col. Watson seems to have been led to this conclusion in consequence of the existence

## Chapter VIII.

THE VALABHIS,  
A.D. 509 - 766.The Válas and  
Káthis.

(1881) total of Káthiávāḍa Vāla Rājputs is about 900 against about 9000 Vāla Káthis, the Válas,<sup>1</sup> since their loss of power, seem either to have passed into unnoticeable subdivisions of other Rājput tribes or to have fallen to the position of Káthis.

If from the first and not solely since the fall of Valabhi the Válas have been associated with the Káthis it seems best to suppose they held to the Káthis a position like that of the Jetwas to their followers the Mers. According to Tod<sup>2</sup> both Válas and Káthis claim the title *Tata Multánka Rai* Lords of Tata and Multán. The accounts of the different sackings of Valabhi are too confused and the traces of an earlier settlement too scanty and doubtful to justify any attempt to carry back Valabhi and the Válas beyond the Maṭraka overthrow of Gupta power in Káthiávāḍa (A.D. 470 - 480). The boast that Bhatárka, the reputed founder of the house of Valabhi (A.D. 509), had obtained glory by dealing hundreds of blows on the large and very mighty armies of the Maṭrakas who by force had subdued their enemies, together with the fact that the Valabhis did and the Maṭrakas did not adopt the Gupta era and currency seem to show the Válas were settled in Káthiávāḍa at an earlier date than the Mers and Jetwas. That is, if the identification is correct, the Válas and Káthis were in Káthiávāḍa before the first wave of the White Huns approached. It has been noticed above under Skandagupta that the enemies, or some of the enemies, with whom, in the early years of his reign A.D. 452-454, Skandagupta had so fierce a struggle were still in A.D. 456 a source of anxiety and required the control of a specially able viceroy at Junágadh. Since no trace of the Káthis appears in Káthiávāḍa legends or traditions before the fifth century the suggestion may be offered that under Vāla or Bāla leadership the Káthis were among the enemies who on the death of Kumāragupta (A.D. 454) seized the Gupta possessions in Káthiávāḍa. Both Válas and Káthis would then be northerners driven south from Multán and South

---

of the petty state of Katti in west Khándesh. But the people of the Káthi state in west Khándesh are Blus or Kolis. Neither the people nor the position of the country seems to show connection with the Káthis of Káthiávāḍa. Col. Watson (Kath. Gaz. 130) inclines to hold that the Válas are an example of the rising of a lower class to be Rājputs. That both Válas and Káthis are northerners admitted into Hindúsm may be accepted. Still it seems probable that on arrival in Káthiávāḍa the Válas were the leaders of the Káthis and that it is mainly since the fall of Valabhi that a large branch of the Válas have sunk to be Káthis. The Káthi traditions admit the superiority of the Válas. According to Tod (Western India, 270 Annals, I. 112-113) the Káthis claim to be a branch or descendants of the Válas. In Káthiávāḍa the Válas, the highest division of Káthis (Ras Malá, I. 296; Kath. Gaz. 122, 123, 131, 139), admit that their founder was a Vāla Rājput who lost caste by marrying a Kathi woman. Another tradition (Ras Malá, I. 296; Kath. Gaz. 122 note 1) records that the Káthis flying from Sindh took refuge with the Válas and became their followers. Col. Watson (Kath. Gaz. 130) considers the practice in Porbandar and Navanagar of styling any lady of the Dhānk Vāla family who marries into their house Káthiāmbī the Káthi lady proves that the Válas are Káthis. But as this name must be used with respect it may be a trace that the Válas claim to be lords of the Káthis as the Jetwas claim to be lords of the Mers. That the position of the Válas and Káthis as Rājputs is doubtful in Káthiávāḍa and is assured (Tod's Annals, I. 111) in Rājputāna is strange. The explanation may perhaps be that aloofness from Muhamínadans is the practical test of honour among Rājputāna Hindús, and that in the troubled times between the thirteenth and the seventeenth centuries, like the Jhálás, the Válas and Káthis may have refused Moghal alliances, and so won the approval of the Rājputs of Mewád.

<sup>1</sup> Kath. Gaz. 110-120.

<sup>2</sup> Western India, 207; Annals, I. 112-113.

Sindh by the movements of tribes displaced by the advance of the Ephthalites or White Huns (A.D. 440-450) upon the earlier North Indian and border settlements of the Yuan-Yuan or Avars.<sup>1</sup>

The Sesodia or Gohil tradition is that the founder of the Válas was Kanaksen, who, in the second century after Christ, from North India established his power at Virát or Dholka in North Gujarát and at Dhánk in Káthiáváda.<sup>2</sup> This tradition, which according to Tod<sup>3</sup> is supported by at least ten genealogical lists derived from distinct sources, seems a reminiscence of some connection between the early Válas and the Kshatrapas of Junágadh with the family of the great Kushán emperor Kanishka (A.D. 78-98). Whether this high ancestry belongs of right to the Válas and Gohils or whether it has been won for them by their bards nothing in the records of Káthiáváda is likely to be able to prove. Besides by the Válas Kanaksen is claimed as an ancestor by the Chávas of Okhámandal as the founder of Kanakapurí and as reigning in Krishna's throne in Dwárá.<sup>4</sup> In support of the form Kanaka for Kanishka is the doubtful Kanaka-Sakas or Kamshka-Sakas of Varáhámihira (A.D. 580).<sup>5</sup> The form Kanak is also used by Alberuni<sup>6</sup> for the famous Vihára or monastery at Pesháwar of whose founder Kanak Alberuni retails many widespread legends. Tod<sup>7</sup> says; 'If the traditional date (A.D. 144) of Kanaksen's arrival in Káthiáváda had been only a little earlier it would have fitted well with Wilson's Kanishka of the Raja Tarangini.' Information brought to light since Tod's time shows that hardly any date could fit better than A.D. 144 for some member of the Kushán family, possibly a grandson of the great Kanishka, to make a settlement in Gujarat and Káthiáváda. The date agrees closely with the revolt against Vasudeva (A.D. 123-150), the second in succession from Kanishka, raised by the Panjab Yandheyas, whom the great Gujarat Kshatrapa Rudrahánan (A.D. 113-158), the introducer of Kanishka's (A.D. 78) era into Gujarát, humbled. The tradition calls Kanaksen Kosalaputra and brings him from Lohkot in North India.<sup>8</sup> Ko-sala has been explained as Ondh and Lohkot as Lahore, but as Kanak came from the north not from the north-east an original Kushána-putra or Son of the Kushán may be the true form. Similarly Lohkot cannot be Lahore. It may be Alberuni's Lauhavar or Lahir in the Káshmir uplands one of the main centres of Kushan power.<sup>9</sup>

# Chapter VIII.

THE VALABHIS,  
A.D. 509-766.

Descent from  
Kanaksen,  
A.D. 150.

<sup>1</sup> It is worthy of note that Balas and Kathias are returned from neighbouring Panjab districts. Balas from Delira Ismail Khán (Panjab Census Report 1891 Part III. 310), Káthiá Rájputs from Montgomery (Ibid., 318), and Káthiá Jits from Jhang and Dera Ismail Khán (Ibid., 143). Compare Jbbetson's (1881) Panjab Census, I. 259, where the Káthias are identified with the Kathaon who fought Alexander the Great (B.C. 325) and also with the Káthiá of Káthiáváda. According to this report (page 210) the Válas are said to have come from Malwa and are returned in East Panjab.

<sup>2</sup> Tod's Annals, I. 83 and 215; Elliot, II. 410, Jour. B. Br. A. S. XXIII.

<sup>3</sup> Annals, I. 215.

<sup>4</sup> Kath Gaz 589.

<sup>5</sup> Brihat-Samhitá, XIV. 21. The usual explanation (compare Fleet Ind. Ant. XXII. 180) Gold-Sakas seems meaningless.

<sup>6</sup> Sachau, II. 11. Among the legends are the much-applied tales of the foot-stamped cloth and the self-sacrificing minister.

<sup>7</sup> Western India, 213.

<sup>8</sup> Tod's Annals, I. 83, 215; Western India, 270-352.

<sup>9</sup> Sachau, I. 208, II. 341. For the alleged descent of the Sesodias and Válas from Ráma of the Sun race the explanation may be offered that the greatness of Kanishka, whose power was spread from the Ganges to the Oxus, in accordance with the Hindu

## Chapter VIII.

THE VALABHIS,  
A.D. 509 - 706.Mewad and  
the Persians.

One further point requires notice, the traditional connection between Valabhi and the Rānās of Mewad with the Sassanian kings of Persia (A.D. 250 - 650). In support of the tradition Abul Fazl (A.D. 1590) says the Rānās of Mewad consider themselves descendants of the Sassanian Naushirvān (A.D. 531 - 579) and Tod quotes fuller details from the Persian history Maaser-al-Umra.<sup>1</sup> No evidence seems to support a direct connection with Naushirvān.<sup>2</sup> At the same time marriage between the Valabhi chief and Maha Bann the fugitive daughter of Yazdigerd the last Sassanian (A.D. 651) is not impossible.<sup>3</sup> And the remaining suggestion that the link may be Naushirvān's son Naushirzad who fled from his father in A.D. 570 receives support in the statement of Procopius<sup>4</sup> that Naushirzad found shelter at Belapadan in Klonzistān perhaps Balapatan in Gurjaristān. As these suggestions are unsupported by direct evidence, it seems best to look for the source of the legend in the fire symbols in use on Kāthiāváda and Mewad coins. These fire symbols, though in the main Indo-Skythian, betray from about the sixth century a more direct Sassanian influence. The use of similar coins coupled with their common sun worship seems sufficient to explain how the Agnikulas and other Kāthiāváda and Mewad Rajputs came to believe in some family connection between their chiefs and the fireworshipping kings of Persia.<sup>5</sup>

Válas.

Can the Vala traditions of previous northern settlements be supported either by early Hindu inscriptions or from living traces in the present population of Northern India? The convenient and elaborate tribe and surname lists in the Census Report of the Panjāb, and vaguer information from Rajputāna, show traces of Bālas and Valas among the Musalmān as well as among the Hindu population of Northern India.<sup>6</sup> Among the tribes mentioned in Varāha-Mihira's sixth century (A.D. 580)<sup>7</sup> lists the Vādhikas appear along with the dwellers on Sindhu's banks. An inscription of a king Chandra, probably Chandragupta and if so about A.D. 350-400,<sup>8</sup> boasts of crossing the seven mouths of the Indus to attack the Vādhikas. These references suggest that the Bālas or Vālas are the Vādhikas and that the Bādhikas of the Harivamśa (A.D. 350-500?) are not as Langlois supposed people then ruling

---

doctrine (compare Beal's Buddhist Records, I. 99 & 152, Ris Malā, I. 320, Fryer's New Account, 190) that a conqueror's success is the fruit of transcendental merit in a former birth, led to Kanishka being considered an incarnation of Rama. A connection between Kanishka and the race of the sun would be made easy by the intentional confusing of the names Kshatriya and Kshatriya and by the fact that during part at least of his life he and the sun were Kanishka's favourite deities.

<sup>1</sup> Gladwin's Am-i Akhbari, II. 81; Tod's Annals, I. 235.

<sup>2</sup> The invasion of Sindh formerly (Reinard's Fragments, 29) supposed to be by Naushirvān in person according to fuller accounts seems to have been a raid by the ruler of Sestān (Elliot, I. 107). Still Reinard (Mémoire Sur l'Inde, 127) holds that in sign of vassalage the Sindh king added a Persian type to his coins.

<sup>3</sup> Compare Tod's Annals, I. 235-239 and Rawlinson's Seventh Monarchy, 576.

<sup>4</sup> Rawlinson's Seventh Monarchy, 452 note 3.

<sup>5</sup> Compare Tod's Annals, I. 63, Thomas' Prinsep, I. 413; Cunningham's Arch. Survey, VI. 201. According to their own accounts (Ris Malā, I. 296) the Kathis learned sun-worship from the Vāla of Dhānk by whom the famous temple of the sun at Thān in Kāthiāváda was built.

<sup>6</sup> Vālas Musalmān Jāts in Lahor and Gurdaspur; Vāls in Gujarāt and Gujranwālā; Vāls in Mozafarnagar and Dhera Ismael Khan. Also Vāls Hindus in Kāngra. Panjāb Census of 1891, III. 162.

<sup>7</sup> Brihat Samhitā, V. 80.

<sup>8</sup> Corp. Ins. Ind. III. 140-141.

in Balkh but people then established in India.<sup>1</sup> Does it follow that the Vāhikas of the inscriptions and the Bāhikas of the Harivamśa are the Panjāb tribe referred to in the Mahābhārata as the Bāhikas or Bāhikas, a people held to scorn as keeping no Brāhman rites, their Brāhman degraded, their women abandoned?<sup>2</sup> Of the two Mahābhārata forms Bahuka and Bahika recent scholars have preferred Bāhika with the sense of people of Balkh or Baktria.<sup>3</sup> The name Bahika might belong to more than one of the Central Asian invaders of Northern India during the centuries before and after Christ, whose manner of life might be expected to strike an Aryāvarta Brāhman with horror. The date of the settlement of these northern tribes (B.C. 150 - A.D. 300) does not conflict with the comparatively modern date (A.D. 150-250) now generally received for the final revision of the Mahābhārata.<sup>4</sup> This explanation does not remove the difficulty caused by references to Bahikas and Bahikas, in Pāṇini and other writers earlier than the first of the after-Alexander Skythian invasions. At the same time as shown in the footnote there seems reason to hold that the change from the Bakhtri of Darius (B.C. 510) and Alexander the Great (B.C. 330) to the modern Balkh did not take place before the first century after Christ. If this view is correct it follows that

## Chapter VIII

THE VALABHIS,  
A.D. 509-766.

Valas.

<sup>1</sup> The references are, Langlois' Harivamśa, I. 388-420, II. 178. That in A.D. 247 Balkh or Baktria was free from Indian overlordship (McCrindle's Periplus, 121), and that no more distant tribe than the Gandharis finds a place in the Harivamśa lists combine to make it almost certain that, at the time the Harivamśa was written, whatever their origin may have been, the Bāhikas were settled not in Baktria but in India.

<sup>2</sup> The passage from the Kurma Parva or Eighth Book of the Mahābhārata is quoted in Mun's Sanskrit Texts, II. 482, and in greater fullness in St. Martin's Geog. Grecque et Latine de l'Inde, 402-410. The Bāhikas - Bahikas are classed with the Madhas, Gandharas, Arattas, and other Panjāb tribe. In their Brāhman features it is said the eldest son alone is a Brāhman. The younger brothers are without restraint Kshatriyas, Vaidyas, Sudras, even Barbers. A Brāhman may sink to be a Barber and a barber may rise to be a Brāhman. The Bāhikas eat flesh even the flesh of the cow and drink liquor. Their women know no restraint. They dance in public places, unclothed save with garlands. In the Harivamśa (Langlois, I. 493 and II. 178, 388, 420) the Bāhikas occur in lists of kings and peoples.

<sup>3</sup> Kern in Mun's Sanskrit Texts, II. 116. St. Martin (Geog. Grecque et Latine de l'Inde, 149) takes Bahika to be a contraction of Bāhika. Reasons are given below for considering the Mahābhārata form Bahika a confusion with the earlier tribes of that name rather than a contraction of Bāhika or Bāhika. The term Bahika was also favoured by the writer in the Mahābhārata because it fitted with his punning derivation from the two word ancestors *Bah* and *Hika*. St. Martin, 408.

<sup>4</sup> St. Martin (Geog. Grecque et Latine de l'Inde, 403), puts the probable date at A.C. 380 or about fifty years before Alexander. St. Martin held that the passage belonged to the final revision of the poem. Since St. Martin's time the tendency has been to lower the date of the final revision by at least 500 years. The fact noted by St. Martin (Ibid., page 404) that Jartika which the Mahābhārata writer gives as another name for Bahika is a Sanskritised form of Jat further supports the later date. It is now generally accepted that the Jats are one of the leading tribes who about the beginning of the Christian era passed from Central Asia into India.

<sup>5</sup> The name Valabhi, as we learn from the Jam historians, is a Sanskritised form of Valahi, which can be easily traced back to one of the many forms (Bāhika, Bahika, Bahika, Bahika, Bāhika, Vāhika, Vāhika, Vāhika, Vāhika, Vāhika) of a tribal name which is of common occurrence in the Epics. This name is, no doubt rightly, traced back to the city of Balkh, and originally denoted merely the people of Baktria. There is, however, evidence that the name also denoted a tribe doubtless of Baktrian origin, but settled in India. The Emperor Chandragupta speaks of defeating the Vāhikas after crossing the seven mouths of the Indus: Varaha-Mihira speaks of the Vāhikas along with the people who dwell on Sindhu's banks (Br. Sam. V. 80): and, most decisive of all, the Kāśikā Vṛtti on Pāṇ. VIII. iv. 9 (A.D. 650) gives Bahika as the name of the people of the Sauvāra country, which, as Alberuni tells us, corresponded to the

## Chapter VIII.

THE VALABHIS,  
A.D. 509-766.

Vālas.

if the form Bahlika occurs in Pāṇini or other earlier writers it is a mistaken form due to some copyist's confusion with the later name Bahlika. As used by Pāṇini the name Bāhika applied to certain Panjāb tribes seems a general term meaning Outsider a view which is supported by Brian Hodgson's identification of the Mahābhārata Bāhikas with the Bahings one of the outcaste or broken tribes of Nepāl.<sup>1</sup> The use of Baluka in the Mahābhārata would then be due either to the wish to identify new tribes with old or to the temptation to use a word which had a suitable meaning in Sanskrit. If then there is fair ground for holding that the correct form of the name in the Mahābhārata is Balluka and that Bāhika means men of Balkh the question remains which of the different waves of Central Asian invaders in the centuries before and after Christ are most likely to have adopted or to have received the title of Baktrians. Between the second century before and the third century after Christ two sets of northerners might justly have claimed or have received the title of Baktrians. These northerners are the Baktrian Greeks about B.C. 180 and the Yuechi between B.C. 20 and A.D. 300. Yavana is so favourite a name among Indian writers that it may be accepted that whatever other northern tribes the name Yavana includes no name but Yavana passed into use for the Baktrian Greeks. Their long peaceful and civilised rule (B.C. 180 - A.D. 300 ?) from their capital at Balkh entitles the Yuechi to the name Baktrians or Bāhikas. That the Yuechi were known in India as Baktrians is proved by the writer of the Periplus (A.D. 247), who, when Baktria was still under Yuechi rule, speaks of the Baktranoi as a most warlike race governed by their own sovereign.<sup>2</sup> It is known that in certain cases the Yuechi tribal names were of local origin. Kushān the name of the leading tribe is according to some authorities a place-name.<sup>3</sup>

modern Multan, the very country to which the traditions of the modern Vālas point.

If the usual derivation of the name Balluka be accepted,\* it is possible to go a step further and fix a probable limit before which the tribe did not enter India. The name of Balkh in the sixth century B.C. was, as we learn from Darius inscriptions, Baktri, and the Greeks also knew it as Baktra the Avesta form is Bakhdi, which according to the laws of sound-change established by Prof. Darmstadter for the Achaemenian language as represented by the modern Pushtu, would become Bahh (see *Chants Populaires des Afghans*, Introd. page xxvii). This reduction of the hard aspirate to spirants seems to have taken place about the first century A.D.; parallel cases are the change from Parthava to Palhava, and Mihra to Mihra. It would seem therefore that the Bāhikas did not enter India before the first century A.D. and if we may identify their subduer Chandra with Chandragupta I., we should have the fourth century A.D. as a lower limit for dating their invasion.

Unfortunately, however, these limits cannot at present be regarded as more than plausible for the name Balluka or Valhika appears to occur in works that can hardly be as modern as the first century A.D. The Atharvaveda-pariśiṣṭas might be put aside, as they show strong traces of Greek influence and are therefore of late date and the supposed occurrences in Pāṇini belong to the commentators and to the Gauapāṭha only and are of more or less uncertain age. But the name occurs, in the form Balluka, in one hymn of the Atharvaveda itself (Book V. 22) which there is no reason to suppose is of late date.

The lower limit is also uncertain as the identification of Chandra of the inscription with the Gupta king is purely conjectural — (A. M. T. J.)

\* There is a very close parallel in the modern Panjāb, where (see Census Report of 1881)

the national name Baluch has become a tribal name in the same way as Bāhika.

<sup>1</sup> Hodgson's Essays on Indian Subjects, I. 405 Note.

<sup>2</sup> McCrindle's Periplus, 121. Compare Rawlinson's Seventh Monarchy, 79. The absence of Indian reference to the Yuechi supports the view that in India the Yuechi were known by some other name.

<sup>3</sup> According to Reinaud (Mémoire Sur l'Inde, 82 note 3) probably the modern

And it is established that the names of more than one of the tribes who about B.C. 50 joined under the head of the Kusháns were taken from the lands where they had settled. It is therefore in agreement both with the movements and with the practice of the Yuechi, that, on reaching India, a portion of them should be known as Báhlíkas or Báhlikas. Though the evidence falls short of proof there seems fair reason to suggest that the present Rajput and Káthi Válas or Bálas of Gujarát and Rajputána, through a Sanskritised Váhlhka, may be traced to some section of the Yuechi, who, as they passed south from Baktria, between the first century before and the fourth century after Christ, assumed or received the title of men of Balkh.

One collateral point seems to deserve notice. St. Martin<sup>1</sup> says: 'The Greek historians do not show the least trace of the name Báhlhka.' Accepting Báhika, with the general sense of Outsider, as the form used by Indian writers before the Christian era and remembering<sup>2</sup> Pálini's description of the Málavas and Kshudrakas as two Báhika tribes of the North-West the fact that Pálini lived very shortly before or after the time of Alexander and was specially acquainted with the Panjáb leaves little doubt that when (A.D. 326) Alexander conquered their country the Malloi and Oxydrakai, that is the Málavas and Kshudrakas, were known as Báhikas. Seeing that Alexander's writers were specially interested in and acquainted with the Malloi and Oxydrakai it is strange if St. Martin is correct in stating that Greek writings show no trace of the name Báhika. In explanation of this difficulty the following suggestion may be offered.<sup>3</sup> As the Greeks sounded their *h* (*h*) as a spirant, the Indian Báhika would strike them as almost the exact equivalent of their own word *Βακχικός*. More than one of Alexander's writers has curious references to a Bacchic element in the Panjáb tribes. Arrian<sup>4</sup> notices that, as Alexander's fleet passed down the Jhelum, the people lined the banks chanting songs taught them by Dionysus and the Bacchantes. According to Quintus Curtius<sup>5</sup> the name of Father Bacchus was famous among the people to the south of the Malloi. These references are vague. But Strabo is definite.<sup>6</sup> The Malloi and Oxydrakai are reported to be the descendants of Bacchus. This passage is the more important since Strabo's use of the writings of Aristobolus Alexander's historian and of Onesikritos Alexander's pilot and Bráhman-interviewer gives his details a special value.<sup>7</sup> It may be said Strabo explains why the Malloi and Oxydrakai were called Bacchic and Strabo's explanation is not in agreement with the proposed Báhika origin. The answer is that Strabo's explanation can be proved to be in part, if not altogether, fictitious. Strabo<sup>8</sup> gives two reasons why the Oxydrakai

## Chapter VIII.

THE VALABHIS,  
A.D. 509-766.

Válas.

Kochanya or Kashania sixty or seventy miles west of Samarkand. This is Hsien Tsiang's (A.D. 620) Ki'uh-shwangi-ni-kia or Kushanika. See Beal's Buddhist Records, I. 31.

<sup>1</sup> Etude sur la Géographie (Grecque et Latine de l'Inde, 147.

<sup>2</sup> McCrindle's Alexander in India, 350.

<sup>3</sup> The suggestion is made by Mr. A. M. T. Jackson.

<sup>4</sup> McCrindle's Alexander, 136.

<sup>5</sup> McCrindle's Alexander, 252.

<sup>6</sup> Compare Strabo, XV. I. 8. The Oxydrakai are the descendants of Dionysus. Again, XV. I. 24: The Malloi and the Oxydrakai who as we have already said are fabled to be related to Dionysus.

<sup>7</sup> See McCrindle's Alexander, 157, 369, 378, 398. Compare St. Martin Geog. Grecque et Latine de l'Inde, 102.

<sup>8</sup> Strabo, XV. I. 8 and 24, Hamilton's Translation, III. 76, 95.

## Chapter VIII.

THE VALABHIS,  
A.D. 509-766.

Válas.

were called Bacchic. First because the vine grew among them and second because their kings marched forth *Bakkhikós* that is after the Bacchic manner. It is difficult to prove that in the time of Alexander the vine did not grow in the Panjáb. Still the fact that the vines of Nysa near Jalálábád and of the hill Meros are mentioned by several writers and that no vines are referred to in the Greek accounts of the Panjáb suggests that the vine theory is an after-thought.<sup>1</sup> Strabo's second explanation, the Bacchic pomp of their kings, can be more completely disproved. The evidence that neither the Malloi nor the Oxydrakai had a king is abundant.<sup>2</sup> That the Greeks knew the Malloi and Oxydrakai were called Bakkhikoi and that they did not know why they had received that name favours the view that the explanation lies in the Indian name Báhika. One point remains. Does any trace of the original Báhikas or Outsiders survive? In Cutch Káthiáváda and North Gujarát are two tribes of half settled cattle-breeders and shepherds whose names Rahbáris as if Rahábaher and Bharváds as if Baherváda seem like Báhika to mean Outsider. Though in other respects both classes appear to have adopted ordinary Hindu practices the conduct of the Bharvád women of Káthiáváda during their special marriage seasons bears a curiously close resemblance to certain of the details in the Mahábhárata account of the Báhika women. Colonel Barton writes:<sup>3</sup> 'The great marriage festival of the Káthiáváda Bharváds which is held once in ten or twelve years is called the Milkdrinking, *Dudhpiño*, from the lavish use of milk or clarified butter. Under the exciting influence of the butter the women become frantic singing obscene songs breaking down hedges and spoiling the surrounding crops.' Though the Bharváds are so long settled in Káthiáváda as to be considered aboriginals their own tradition preserves the memory of a former settlement in Márwár.<sup>4</sup> This tradition is supported by the fact that the shrine of the family goddess of the Cutch Rahbáris is in Jodhpur,<sup>5</sup> and by the claim of the Cutch Bharváds that their home is in the North-West Provinces.<sup>6</sup>

<sup>1</sup> References to the vines of Nysa and Meros occur in Strabo, Pliny, Quintus Curtius, Philostratus, and Justin. McCrindle's *Alexander in India*, 193 note 1, 321, and 339. Strabo (Hamilton's Translation, III. 86) refers to a vine in the country of Muskanus or Upper Sindh. At the same time (Ditto, 108) Strabo accepts Megasthenes' statement that in India the wild vine grows only in the hills.

The Kathaori Malloi and Oxydrakai are (Arrian in McCrindle's *Alexander*, 115, 137, 140, 149) called independent in the sense of kingless. they (Ditto, 154) sent leading men not ambassadors: (compare also Diodorus Siculus and Plutarch, Ditto 287, 311): the Malloi had to chose a leader (Q. Curtius, Ditto 236).

<sup>2</sup> Káthiáwár Gazetteer, 138. <sup>4</sup> Káthiáwár Gazetteer, 137. <sup>5</sup> Cutch Gazetteer, 80.

<sup>6</sup> Cutch Gazetteer, 81.

## CHAPTER IX.

## THE CHÁLUKYAS

(A.D. 634-740.)

THE Chálukyas conquered their Gujarát provinces from the south after subduing the Konkan Mauryas of Purí either Rájápurí that is Janjira or Elephanta in Bombay harbour. The fifth century Váda inscription of king Suketuvarman proves that this Maurya dynasty<sup>1</sup> ruled in the Konkan for at least a century before they came into collision with the Chálukyas under Kirtivarman.<sup>2</sup> They were finally defeated and their capital Purí taken by Chandakanda an officer of Pulakesi II. (A.D. 610-640).<sup>3</sup> The Chálukyas then pressed northwards, and an inscription at Aihole in South Bijápur records that as early as A.D. 634 the kings of Láta, Málava, and Gurjjara submitted to the prowess of Pulakesi II. (A.D. 610-640).

Chapter IX.  
THE CHÁLUKYAS  
A.D. 634-740.

The regular establishment of Chálukya power in South Gujarát seems to have been the work of Dhírá-raya Jayasimhavarman son of Pulakesi II. and younger brother of Vikramáditya Satyasraya (A.D. 670-680). A grant of Jayasimhavarman's son Siláditya found in Navsári describes Jayasimhavarman as receiving the kingdom from his brother Vikramáditya. As Jayasimhavarman is called *Paramabháttaraka* Great Lord, he probably was practically independent. He had five sons and enjoyed a long life, ruling apparently from Navsári. Of the five Gujarát Chálukya copperplates noted below, three are in an era marked Sam. which is clearly different from the Saka era (A.D. 78) used in the grants of the main Chálukyas. From the nature of the case the new era of the Gujarát Chálukyas may be accepted as of Gujarát origin. Grants remain of Jayasimhavarman's sons dated S. 421, 443, and 490.<sup>4</sup> This checked by Vikramáditya's known date (A.D. 670-680) gives an initial between A.D. 249 and 259. Of the two Gujarát eras, the Gupta-Valabhi (A.D. 319) and the Traikútaka (A.D. 248-9), the Gupta-Valabhi is clearly unsuitable. On the other hand the result is so closely in accord with A.D. 248-9, the Traikútaka epoch, as to place the correctness of the identification almost beyond question.

Jayasimhavarman,  
A.D. 666-693.

Jayasimhavarman must have established his power in South Gujarát before A.D. 669-70 (T. 421), as in that year his son Sryá-raya made a grant as heir apparent. Another plate of Sryá-raya found in Surat shows that in A.D. 691-2 (T. 443) Jayasimhavarman was still ruling with Sryá-raya as heir apparent. In view of these facts the establishment of Jayasimhavarman's power in Gujarát must be taken at about A.D. 666. The copperplates of his sons and grandson do not say whom Jayasimhavarman overthrew. Probably the defeated rulers were Gurjjaras, as about this time a Gurjjara dynasty held the Broach district with its capital at Nándipurí the modern Nándod in the Rájpipla State about thirty-five miles east of Broach. So far

<sup>1</sup> Bom. Gaz. XIV. 372.<sup>2</sup> Ind. Ant. VIII. 243.<sup>3</sup> Ind. Ant. VIII. 244.<sup>4</sup> J. B. B. R. A. S. XVI. 1ff. . Proceedings VIIth Oriental Congress, 210ff.

**Chapter IX.**

THE CHÁLUKYAS,  
A.D. 634-710.

Jayasinhavarman,  
A.D. 666-693.

as is known the earliest of the Nándod Gurjjaras was Dadda who is estimated to have flourished about A.D. 580 (T. 331).<sup>1</sup> The latest is Jayabhata whose Navsári copperplate bears date A.D. 734-5 (T. 486)<sup>2</sup> so that the Gurjjara and Chálukya kingdoms flourished almost at the same time. It is possible that the power of the earlier Gurjjara kings spread as far south as Balsár and even up to Konkan limits. It was apparently from them that, during the reign of his brother Vikramáditya, Jayasinhavarman took South Gujarát, driving the Gurjjaras north of the Tápti and eventually confining them to the Broach district, the Gurjjaras either acknowledging Chálukya sovereignty or withstanding the Chálukyas and retaining their small territory in the Broach district by the help of the Valabhis with whom they were in alliance.<sup>3</sup> In either case the Chálukya power seems to have hemmed in the Broach Gurjjaras, as Jayasinhavarman had a son Buddhavarman ruling in Kaira. A copperplate of Buddhavarman's son Vijayarāja found in Kaira is granted from Vijavapura identified with Bijapur near Párantij, but probably some place further south, as the grant is made to Bráhmans of Jambusar. Five copperplates remain of this branch of the Chálukyas, the Navsári grant of S'ryásraya Siláditya Yuvarāja dated A.D. 669-70 (T. 421); the Surat grant of the same Siláditya dated A.D. 691-2 (T. 443); the Balsár grant of Vinayáditya Mangalarāja dated A.D. 731 (S'aka 653), the Navsári grant of Pulakesi Janá'sraya dated A.D. 738-9 (T. 490); the Kaira grant of Vijayarāja dated Samvatsara 394; and the undated Nirpan grant of Nágavarddhana Tribhuvaná'sraya.

S'ryásraya  
Siláditya  
(Heir Apparent)  
A.D. 669-691.

The first four grants mention Jayasinhavarman as the younger brother of Vikramáditya Satyá'sraya the son of Pulakesi Satyá'sraya the conqueror of Harshavarddhana the lord of the North. Jayasinhavarman's eldest son was S'ryásraya Siláditya who made his Navsári grant in A.D. 669-70 (T. 421), the village granted being said to be in the Navasáriká Vishaya. S'ryásraya's other plate dated A.D. 691-2 (T. 443) grants a field in the village of Osunbhalá in the Kármameya Khúra that is the district of Kámlej on the Tápti fifteen miles north-east of Surat. In both grants Siláditya is called Yuvarāja, which shows that his father ruled with him from A.D. 669 to A.D. 691. Both copperplates show that these kings treated as their overlords the main dynasty of the southern Chálukyas as respectful mention is made in the first plate of Vikramáditya Satyá'sraya and in the second of his son Vinayáditya Satyá'sraya. Apparently S'ryásraya died before his father as the two late grants of Balsár and Khedá give him no place in the list of rulers.

Mangalarāja,  
A.D. 698-731.

Jayasinhavarman was succeeded by his second son Mangalarāja. A plate of his found at Balsár dated A.D. 731 (S'aka 653) records a grant made from Mangalapuri, probably the same as Purí the doubtful Konkan capital of the Siláháras.<sup>4</sup> As his elder brother was heir-apparent in A.D. 691-2 (T. 443), Mangalarāja must have succeeded some years later, say about A.D. 698-9 (T. 450). From this it may be inferred that the copperplate of A.D. 731 was issued towards the end of his reign.

<sup>1</sup> See Chap. X. below.

<sup>2</sup> Ind. Ant. XIII. 73.  
<sup>4</sup> B. B. R. A. 8, XVI. 5.

<sup>3</sup> Ind. Ant. XIII. 70.

Mangalarāja was succeeded by his younger brother Pulakeśi Janāśraya. This is the time of Khalif Hashām (H. 105-125, A.D. 721-743) whose Sindh governor Junaid is recorded to have sent expeditions against Marmād, Mandal, Dalmaj (Kāmlaj?), Bārus, Uzain, Mālība, Baharimad (Mevad?), Al Bailāimān (Bhinmāl?), and Juzr. Though several of these names seem to have been misread and perhaps misspelt on account of the confusion in the original Arabic, still Marmād, Mandal, Barus, Uzain, Mālība, and Juzr can easily be identified with Mārvād, Mandal near Viramgām, Bharuch, Ujjain, Mālwa, and Gurjjara. The defeat of one of these raids is described at length in Pulakeśi's grant of A.D. 738-9 (T. 490) which states that the Arab army had afflicted the kingdoms of Sindhu, Kacchella, Saurāshtra, Chāvotaka, Maurya, and Gurjjara that is Sindh, Kacch, the Chāvadās, the Mauryas of Chitor,<sup>1</sup> and the Gurjjaras of Bhīmāl.<sup>2</sup>

## Chapter IX.

THE CHALUKYAS,  
A.D. 634-740.Pulakeśi  
Janāśraya,  
A.D. 738.

<sup>1</sup> For the Moris or Mauryas, described as a branch of Pramātras, who held Chitor during the eighth century compare Tod. Jr. R. A. S. 211; Wilson's Works, XII. 132.

<sup>2</sup> The text of the copperplate runs

शरशसीरमुद्ररोद्धारिणि तरलतरतारतरवारिदा

- [24] रितोदितसैन्धवकच्छेलुसौराष्ट्र चावोटक मौर्यगुर्जरादिरा [अये] निःशेष-  
दाक्षिणान्यक्षितिपतिजि  
[25] गीपया दक्षिणापथप्रवेश.....प्रथममेवनवसारिकाविषयप्र-  
साधनभ्यागत त्वरित

PLATE II.

- [1] तुरगवरमुखरमुखरोखातवरिणिधूलिधूसरिदिगन्तरे कुन्तप्रान्तनितान्तावि-  
मयमानरभसाभिधाविता  
[2] द्रुतस्थलेदरविवरविनिर्गतांत्रप्रथुनरुधिरवाररंजितकवचभीषणवपुषि स्वा-  
मिमहा  
[3] सन्मानदानग्रहण कयीकृतस्वशिरोभिरभिमुखमापतितैप्रदंयदशनाग्रदष्टोष्ट-  
पुटकैरने  
[4] कसमराजिरविवरवरिकरिकटितटहयविघटनविशालितघनरुधिरपटलपाट-  
लितपटुक्रपाणपट्टैरपि महा  
[5] योवैरलब्धपरभागै विपक्षक्षपणाक्षेपक्षिप्रक्षिप्रतीक्षणक्षुरप्रप्रहारविलूनवैरि-  
शिर कमलमलनालैरा  
[6] हवरसरभसरोमांचकंचुकाच्छादिततनूभिरनेकैरपि नरेन्द्रब्रंद्रदारकैरजित-  
पुर्वैः व्यपगतमस्माक  
[7] अणमनेन स्वामिनः स्वशिरःप्रदानेनाद्यतावदेकजन्मीयमित्येवमिपोपजातप-  
रितोषानन्तरप्रहतपटुप  
[8] टहरवप्रवृत्तकबन्धद्वारासमण्डलीके समराशिरासी विजितेताजिकानिके शो-  
य्यानुरागिणा श्रीवदत्रमनरै  
[9] द्रेण प्रसादीकृतापरनामचतुष्टयस्तद्यथा दक्षिणापथसाधारणचलुकिकुलालं-  
कारपृथ्वीवदत्रमानिवर्त्तकनिव  
[10] र्त्तयित्रवनिजनाश्रयश्रीपुलकेशिराजस्सर्वानंवात्मीयान्

**Chapter IX.**  
**THE CHÁLUKYAS,**  
A.D. 634-740.

Buddhavarman,  
A.D. 713 (?)

Pulakesi was at this time ruling at Navsári. It is uncertain how much longer this Chálukya kingdom of Navsári continued. It was probably overthrown about A.D. 750 by the Gujarát branch of the Ráshtrakútas who were in possession in A.D. 757-8.<sup>1</sup>


The Kaira grant dated 394 gives in hereditary succession the names Jayasinha, Buddhavarman, and Vijayarāja.<sup>2</sup> The grant is made from Vijayapura, which, as the late Colonel West suggested, may be Bijápur near Paráñij though this is far to the north of the otherwise known Chálukya limits. The village granted is Pariyaya in the Kásákula division. If taken as Trakútaka the date 394 corresponds to A.D. 612-3. This is out of the question, since Vijayarāja's grand-nucle Vikramāditya flourished between A.D. 670 and 680. Professor Bhandarkar considers the plate a forgery, but there seems no sufficient reason for doubting its genuineness. No fault can be found with the character. It is written in the usual style of Western Chálukya grants, and contains the names of a number of Bráhman grantees with minute details of the fields granted a feature most unusual in a forged grant. In the Gupta era, which equally with the Trakútaka era may be denoted by the word *Sam.* and which is more likely to be in use in North Gujarát the 394 would represent the fairly probable A.D. 713. Jayasinha may have conquered part of North Gujarát and sent his son Buddhavarman to rule over it.

Nagavarddhana.

Jayasinha appears to have had a third son Nágavarddhana ruling in West Násik which was connected with South Gujarát through Balsár, Párdi, and Penth. The Nirpan grant of Nágavarddhana is undated,<sup>3</sup> and, though it gives a wrong genealogy, its seal, the form of composition, the *biruda* or title of the king, and the alphabet all so closely agree with the style of the Gujarát Chálukya plates that it cannot be considered a forgery.

Not long after A.D. 710 the Chálukyas seem to have been supplanted in South Gujarát by the Ráshtrakútas.

Chalukya  
Tree.



<sup>1</sup> Journal B. B. R. A. S. XVI.105.    <sup>2</sup> Ind. Ant. VII. 241.    <sup>3</sup> Ind. Ant. IX. 123.

Vijayarāja's grant of the year 394 (A.D. 642-3) is the earliest trace of Chálukya rule in Gujarāt. Dr. Bhagvánlál, who believed in its genuineness, supposes it to be dated in the Gupta era (c. 394 = A.D. 714) and infers from it the existence of Chálukya rule far to the north of Broach. But the most cursory comparison of it with the Khedá grants of Dadda II. (see Ind. Ant. XIII. 81ff) which are dated (admittedly in the [so-called] Traikúṭaka era) 380 and 385 respectively, shows that a large number of Dadda's grantees reappear in the Chálukya grant. The date of the Chálukya plate must therefore be interpreted as a Traikúṭaka or Chedi date.

This being so, it is clearly impossible to suppose that Vijayarāja's grandfather Jayasimha is that younger son of Pulakesi II. (A.D. 610-640) who founded the Gujarāt branch family. It has been usually supposed that the Jayasimha of our grant was a younger brother of Pulakesi II. : But this also is chronologically impossible for Jayasimha can hardly have been more than ten years of age in A.D. 597-98, when his elder brother was set aside as too young to rule. His son Buddhavarman could hardly have been born before A.D. 610, so that Buddhavarman's son Vijayarāja must have made his grant at the age of twelve at latest. The true solution of the question seems to be that given by Dr. Bhandárkar in his Early History of the Deccan (page 42 note 7), namely that the grant is a forgery. To the reasons advanced by him may be added the fact pointed out by Mr. Fleet (Ind. Ant. VII. 251) that the grant is a palm-leaf, the engraver having originally commenced it "Svasti Vijayavikshepán Na." It can hardly be doubted that Na is the first syllable of Nandipurī the palace of the Gurjjara kings. Many of the grantees were Bráhmans of Jambusar and subjects of Dadda II. of Broach, whose grants to them are extant. It seems obvious that Vijayarāja's grant was forged in the interest of these persons by some one who had Gurjjara grants before him as models, but knew very little of the forms used in the chancery of the Chálukyas.

Setting aside this grant, the first genuine trace of Chálukya rule in Gujarāt is to be found in the grant of the Sindraka chief Nikumbhallaśakti, which bears date Samv. 406 (A.D. 654-5) and relates to the gift to a Bráhman of the village of Bahsa (Wanesa) in the Trepayana (Ten) district. Dr. Bühler has shown (Ind. Ant. XVIII. page 265ff) that the Sindrakas were a Kanarese family, and that Nikumbhallaśakti must have come to Gujrat as a Chálukya feudatory, though he names no overlord. He was doubtless subordinate to the Chálukya governor of Nasik.

The next grant that requires notice is that of Nagavarddhana, who describes himself distinctly as the son of Pulakesi's brother Jayasimha, though Dr. Bhagvánlál believed this Jayasimha to be Pulakesi's son. Mr. Fleet points out other difficulties connected with this grant, but on the whole decides in favour of its genuineness (see Ind. Ant. IX. 123). The description of Pulakesi II. in this grant refers to his victory over Harshavarddhana, but also describes him as having conquered the three kingdoms of Chera, Chola, and Pándya by means of his horse of the Chitrakanṭha breed, and as meditating on the feet of Sri Nagavarddhana. Now all of these epithets, except the reference to Harshavarddhana, belong properly, not to Pulakesi II. but to his son Vikramáditya I. The conquest of the confederacy of Cholas, Cheras (or Keralas), and Pándyas is ascribed to Vikramáditya in the inscriptions of his son Vimaláditya (Fleet in Ind. Ant. X. 134) : the Chitrakanṭha horse is named in Vikramáditya's own grants (Ind. Ant. VI. 75 &c.) while his meditation upon the feet of Nagavarddhana recurs in the T. 421 grant of Sryāstraya Śiláditya (B. B. R. A. S. XVI. 1ff). This confusion of epithets between Pulakesi II. and Vikramáditya makes it difficult to doubt that Nagavarddhana's grant was composed either during or after Vikramáditya's reign, and under the influence of that king's grants. It may be argued that even in that case the grant may be genuine, its inconsistencies being due merely to carelessness. This supposition the following considerations seem to negative. Pulakesi II. was alive at the time of Hiuen Tsiang's visit (A.D. 640), but is not likely to have reigned very much longer. And, as Vikramáditya's reign is supposed to have begun about A.D. 669-70, a gap remains of nearly thirty years. That part of this period was occupied by the war with the three kings

## Chapter IX.

THE CHÁLUKYAS,  
A.D. 634-740.

A.D. 610-640.

**Chapter IX.**  
**THE CHĀLUKYAS,**  
**A.D. 631-740.**

of the south we know from Vikramāditya's own grants: but the grant of Sryāśraya Śilāditya referred to above seems to show that Vikramāditya was the successor, not of his father, but of Nagavarddhana upon whose feet he is described as meditating. It follows that Nagavarddhana succeeded Pulakesi and preceded Vikramāditya on the imperial throne of the Chālukyas whereas his grant could not have been composed until the reign of Vikramāditya.

Although the grant is not genuine, we have no reason to doubt that it gives a correct genealogy, and that Nagavarddhana was the son of Pulakesi's brother Jayasinha and therefore the first cousin of Vikramāditya. The grant is in the regular Chālukya style, and the writer, living near the Northern Chālukya capital, Nāsik, had better models than the composer of Vīṇayiraja's grant. Both grants may have been composed about the time when the Chālukya power succumbed to the attacks of the Rāshtrakūṭas (A.D. 743).—(A. M. T. J.)

## CHAPTER X.

## THE GURJJARAS

• (A.D. 580-808.)

In the Valabhi and Chihlukya ascendancy a small Gurjjara kingdom flourished in and about Broach. As has been noticed in the Valabhi chapter the Gurjjaras were a foreign tribe who came to Gujrat from Northern India. All the available information regarding the Broach Gurjjaras comes from nine copperplates,<sup>1</sup> three of them found and obtained from South Gujarat. These plates limit the regular Gurjjara territory to the Broach district between the Mahi and the Narmada, though at times their power extended north to Khedi and south to the Tapti. Like the grants of the contemporary Gujarat Chahukyas, all the genuine copperplates are dated in the Trankata era which begins in A.D. 580.<sup>2</sup> The Gurjjara capital seems to have been Nandpur or Nandol, the modern Nandol the capital of Rajpura in Rewa Kantha about thirty-four miles east of Broach. Two of their grants issue *Varahpuradatta*<sup>3</sup> that is 'from Nandpur' like the *Panchadatta* or 'from Valabhi' of the Valabhi copperplates, a phrase which in both cases seems to show the place named was the capital since in other Gurjjara grants the word *rastra* or empire occurs.

Though the Gurjjaras held a considerable territory in South Gujarat their plates seem to show they were not independent rulers. The general titles are either *Samadhigata-panchamaharajata* 'He who has attained the five great title,' or *Samanta* 'Feudatory.' In one instance Jayabhata<sup>4</sup> who was probably a powerful ruler is called *Samavardhana* 'Chief of Feudatories.' It is hard to say how far the Broach Gurjjaras acknowledged fealty. Latterly they seem to have accepted the Chahukyas on the south as their overlords. But during the greater part of their existence they may have been feudatories of the Valabhi dynasty, who, as

## Chapter X.

THE GURJJARAS  
A.D. 580-808.

Copperplates.

<sup>1</sup> Ind. Ant. V. 149ff. Ind. Ant. VII. 11ff. & Jour. R. A. Soc. N. S. 1. 271ff. Ind. Ant. XIII. 81, 91, Jour. B. R. R. A. Soc. N. 190. Ind. Ant. XIII. 115-119. Ind. Ant. XVII. and Ep. Ind. II. 190. <sup>2</sup> See above page 107.

<sup>3</sup> That Nandol or Nandol was an old and important city is proved by the fact that Brahmins and Vaisias called Nandol is that is of Nandol are found throughout Gu. Mongrol and Chorvad on the South Kathiawar coast have settlements of Vaisias vine cultivators who call themselves Nandol Vaisias and apparently brought the vine from Nandol. Dr. Buhler, however, identifies the Nandol part of the grants with old fort of the same name about two miles north of the east gate of Broach. See L. 19. at VII. 62. <sup>4</sup> Ind. Ant. XIII. 81, 88. <sup>5</sup> Ind. Ant. XIII. 70.

<sup>6</sup> The fact that the Ind. and Iluc plates give their grantor Badila II. the title *Maharajadhiraja* 'Supreme Lord of Great Kings,' is one of the grounds for holding them forgeries.

**Chapter X.**  
**THE GURJJARAS,**  
 A.D. 580-808.  
 Copperplates.

mentioned above were probably Gurjjaras who passed from Mûlwa to South Gujarât and thence by sea to Valabhi leaving a branch in South Gujarât.

The facts that in A.D. 649 (Valabhi 330) a Valabhi king had a 'camp of victory' at Broach where Runagrala's plate<sup>1</sup> shows the Gurjjaras were then ruling and that the Gurjjara king Dadda II. gave shelter to a Valabhi king establish a close connection between Valabhi and the Nândod Gurjjaras.

Their copperplates and seals closely resemble the plates and seals of the Gujarât Châlukya's. The characters of all but the forged grants are like those of Gujarât Châlukya grants and belong to the Gujarât variety of the Southern India style. At the same time it is to be noted that the royal signature at the end of the plates is of the northern type, proving that the Gurjjaras were originally northerners. The language of most of the grants is Sanskrit prose as in Valabhi plates in a style curiously like the style of the contemporary author Bana in his great works the Kâdambarî and Harshacharita. From this it may be inferred that Bana's style was not peculiar to himself but was the style in general use in India at that time.

**Gurjjara**  
**Tree.**

The following is the Gurjjara family tree

```

Dadda I. A.D. 580.
|
Jayabhata I. A.D. 605
|
Dadda II. A.D. 633
|
Jayabhata II. A.D. 655
|
Dadda III. A.D. 680
|
Jayabhata III. A.D. 706-734

```

A recently published grant<sup>2</sup> made by Nandhullaka, the chieftain of a jungle tribe in the lower valley of the Narbada, shows that towards the end of the sixth century A.D. that region was occupied by wild tribes who acknowledged the supremacy of the Chedi or Kalachuri kings: a fact which accounts for the use of the Chedi or Trakûṭaka era in South Gujarât. Nandhullaka names with respect a king Sankaragana, whom Dr. Bühler would identify with Sankaragana the father of the Kalachuri Buddhavarman who was defeated by Mangalîsa the Châlukya about A.D. 500.<sup>3</sup> Sankaragana himself must have flourished about A.D. 580, and the Gurjjara conquest must be subsequent to this date. Another new grant,<sup>4</sup> which is only a fragment and contains no king's name, but which on the ground of date (Sam. 346 A.D. 594-5) and style may be safely attributed to the Gurjjara dynasty, shows that the jaras were established in the country within a few years of aragana's probable date.

-till nearer approximation to the date of the Gurjjara conquest is -sted by the change in the titles of Dharasena I. of Valabhi, who

in his grants of Samvat 252<sup>1</sup> (A.D. 571) calls himself Mahārāja, while in his grants of 269 and 270<sup>2</sup> (A.D. 588 and 589), he adds the title of Mahāsāmānta, which points to subjection by some foreign power between A.D. 571 and A.D. 588. It seems highly probable that this power was that of the Gurjjaras of Bhīnmāl; and that their successes therefore took place between A.D. 580 and 585 or about A.D. 585.

The above mentioned anonymous grant of the year 316 (A.D. 591-95) is ascribed with great probability to Dadda I. who is known from the two Khedā grants of his grandson Dadda II. (c. 620-650 A.D.)<sup>3</sup> to have "uprooted the Nāga" who must be the same as the jungle tribes ruled by Nūhulūka and are now represented by the Nūkdās of the Panch Mahals and the Talabdas or Locals of Broach. The northern limit of Dadda's kingdom seems to have been the Vindhya, as the grant of 380 (A.D. 628-29) says that the lands lying around the feet of the Vindhya were for his pleasure. At the same time it appears that part at least of Northern Gujrat was ruled by the Mahāsāmānta Dharasena of Valabhi, who in Val 270 (A.D. 589-90) granted a village in the *akhira* of Khetaka (Khedā).<sup>4</sup> Dadda is always spoken of as the *Sāmānta*, which shows that while he lived his territory remained a part of the Gurjjara kingdom of Bhīnmāl. Subsequently North Gujrat fell into the hands of the Malava kings, to whom it belonged in Huen Tsiang's time (c. 640 A.D.).<sup>5</sup> Dadda I. is mentioned in the two Khedā grants of his grandson as a worshipper of the sun: the fragmentary grant of 316 (A.D. 591-95) which is attributed to him gives no historical details.

Dadda I. was succeeded by his son Jayabhata I. who is mentioned in the Khedā grants as a victorious and virtuous ruler, and appears from his title of Vitarāga the Passionless to have been a religious prince.

Jayabhata I. was succeeded by his son Dadda II. who bore the title of Pra-santarāga the Passion-calmed. Dadda was the donor of the two Khedā grants of 380 (A.D. 628-29) and 385 (A.D. 633-34), and a part of a grant made by his brother Ranagrāha in the year 391 (A.D. 639-40) has lately been published.<sup>6</sup> Three forged grants purporting to have been issued by him are dated respectively Saka 400 (A.D. 478), Saka 415 (A.D. 493), and Saka 417 (A.D. 495).<sup>7</sup> Both of the Khedā grants relate to the gift of the village of Sīr'ar'akaka (Sisodra) in the Akrośvara (Ankleshvara) to certain Brahmanas of Jambusar and Broach. In Ranagrāha's grant the name of the village is lost.

Dadda II.'s own grants describe him as having attained the five great titles, and praise him in general terms: and both he and his brother Ranagrāha sign their grants as devout worshippers of the sun. Dadda II. heads the genealogy in the later grant of 456 (A.D. 704-5),<sup>8</sup> which states that he protected "the lord of Valabhi who had been defeated by the great lord the illustrious Harshadeva." The event referred to must have been some expedition of the great Harshavardhana of Kanauj

## Chapter X.

THE GURJJARAS,  
A.D. 580-808.

Dadda I.  
c. 585-605 A.D.

Jayabhata I.  
Vitarāga,  
c. 605-620 A.D.

Dadda II.  
Pra-santarāga,  
c. 620-650 A.D.

<sup>1</sup> Ind. Ant. VII. 68, VIII. 302, XIII. 160, and XV. 187.

<sup>2</sup> Ind. Ant. VI. 9, VII. 70.

<sup>3</sup> Ind. Ant. XIII. 81-88.

<sup>4</sup> Ind. Ant. VII. 70.

<sup>5</sup> Beal's Buddhist Records, II. 266, 268.

<sup>6</sup> Ind. Ant. XIII. 81-88, Ep. Ind. II. 19.

On these forged grants see below page 117.

<sup>7</sup> Ind. Ant. XIII. 70.

**Chapter X.**  
**THE GUJJARAS,**  
 A.D. 580-803.  
**Dadda II**  
*Prasadamagn,*  
 c. 620-630 A.D.

(A.D. 607-648), perhaps the campaign in which Harsha was defeated on the Narbada by Pulakesi II. (which took place before A.D. 631). The protection given to the Valabhi king is perhaps referred to in the Kheda grants in the mention of "strangers and suppliants and people in distress." If this is the case the defeat of Valabhi took place before A.D. 628-29, the date of the earliest of the Kheda grants. On the other hand, the phrase quoted is by no means decisive, and the fact that in Huen Tsiang's time Dharmasena of Valabhi was son-in-law of Harsha's son, makes it unlikely that Harsha should have been at war with him. It follows that the expedition referred to may have taken place in the reign of Dharmasena IV who may have been the son of Dharmasena by another wife than Harsha's granddaughter.

To Dadda II's reign belongs Huen Tsiang's notice of the kingdom of Broach (c. 640 A.D.).<sup>1</sup> He says "all their profit is from the sea" and describes the country as salt and barren, which is still true of large tracts in the west and twelve hundred years ago was probably the condition of a much larger area than at present. Huen Tsiang does not say that Broach was subject to any other kingdom but it is clear from the fact that Dadda bore the five great titles that he was a mere feudatory. At this period the valuable port of Broach, from which all their profit was made, was a prize fought for by all the neighbouring powers. With the surrounding country of Lata, Broach submitted to Pulakesi II. (A.D. 610-649) — it may afterwards have fallen to the Málava kings, to whom in Huen Tsiang's time (A.D. 640) both Kheda (K'ie-ch'ia) and Anandapura (Vadnapur) belonged; later it was subject to Valabhi, as Dharmasena IV. made a grant at Broach in A.S. 330 (A.D. 641-50).<sup>2</sup>

Knowledge of the later Gujjaras is derived exclusively from two grants of Jayabhata III. dated respectively 456 (A.D. 701-2) and 486 (A.D. 731-2).<sup>3</sup> The later of these two grants is imperfect, only the last plate having been preserved. The earlier grant of 456 (A.D. 701-2) shows that during the half century following the reign of Dadda II the dynasty had ceased to call themselves Gujjara, and had adopted a Puranic pedigree traced from king Kurma, a hero of the Bharata yuga. It also shows that from Dadda III. onward the family were Śaivas instead of sun-worshippers.

**Jayabhata II**  
 c. 650-675 A.D.

The successor of Dadda II. was his son Jayabhata II who is described as a warlike prince, but of whom no historical details are recorded.

**Dadda III**  
**Bāhusahāya,**  
 c. 675-700.

Jayabhata's son, Dadda III. Bāhusahāya, is described as waging wars with the great kings of the east and of the west (probably Malava and Valabhi). He was the first Śaiva of the family, studied Manu's works, and strictly enforced "the duties of the *śarnas* or castes and of the *asramas* or Brāhman stages." It was probably to him that the Gujjaras owed their Purānic pedigree and their recognition as true Kshatriyas. Like his predecessors Dadda III.

<sup>1</sup> Beal's *Buddhist Records*, II. 259.

<sup>2</sup> *Ind. Ant.* VIII. 237.

<sup>3</sup> *Ind. Ant.* XV. 335.

<sup>4</sup> *Ind. Ant.* V. 109, XIII. 70.

## THE GURJJARAS.

was not an independent ruler. He could claim only the five great titles, though no hint is given who was his suzerain. His immediate superior may have been Jayasimha the Chālukya, who received the province of Lata from his brother Vikramaditya (c. 660-680 A.D.)<sup>1</sup>

The son and successor of Dadda III was Jayabhatta III, whose two grants of 156 (A.D. 704-5) and 486 (A.D. 731-5),<sup>2</sup> and 6 belong respectively to the beginning and the end of his reign. He attained the five great titles, and was therefore a feudatory, probably of the Chālukyas, but his title of Mahasamantadhipati implies that he was a chief of importance. He is praised in vague terms, but the only historical event mentioned in his grants is a defeat of a lord of Valabhi, noted in the grant of 486 (A.D. 731-5). The Valabhi king referred to must be either Śiladitya IV. (A.D. 691) or Śiladitya V. (A.D. 722). During the reign of Jayabhatta III took place the great Arab invasion which was repulsed by Pulakesi Janāsiya at Naysar. Like the kingdoms named in the grant of Pulakesi, Broach must have suffered from this raid. It is not specially mentioned probably because it formed part of Pulakesi's territory.

After A.D. 734-5 no further mention occurs of the Gujjaras of Broach. Whether the dynasty was destroyed by the Arabs or by the Gujjarat Rashtrakutas (A.D. 750) is not known. Later references to Gujjaras in Rashtrakuta times refer to the Gujjaras of Bhimad not to the Gujjaras of Broach, who, about the time of Dadda III (c. 675-700 A.D.), ceased to call themselves Gujjaras.

A few words more to be said regarding the three grants from Hlo, Uneta and Begmura (Ind. Ant. XIII. 116, VII. 16, and XVII. 18) as their genuineness has been assumed by Dr. Bühler in his recent paper on the Mahabharata in spite of Mr. Fleet's proof (Ind. Ant. XVIII. 19) that their dates do not work out correctly.

Dr. Bhattacharya (Ind. Ant. XIII. 70) chief grounds for holding that the Uneta and Hlo grants (the Begmura grant was unknown to him) were forgeries were

(1) Their close resemblance in palaeography to one another and to the forged grant of Dharmasena II. of Valabhi dated S. 400.

(2) That though they purport to belong to the fifth century they bear the same writer's name as the Kheda grants of the seventh century.

But Mr. Fleet (Ind. Ant. XVII. 19) pointed out

(3) That the description of Dadda I. on the Hlo and Uneta grants agrees almost literally with that of Dadda II. in the Kheda grants and that where it differs the Kheda grants have the better readings.

To these arguments Dr. Bühler has replied (Ind. Ant. XVII. 183)

(1) That though there is a resemblance between these grants and that of Dharmasena II., still it does not prove more than that the forger of Dharmasena's grant had one of the other grants before him.

(2) That, as the father's name of the writer is not given in the Kheda grants, it cannot be assumed that he was the same person as the writer of the Hlo and Uneta grants, and

## Chapter X.

THE GURJJARAS.  
A.D. 780-808.

Jayabhatta III.  
c. 704-731 A.D.

<sup>1</sup> B. B. R. A. S. JI. XVI. 10.

<sup>2</sup> Ind. Ant. V. 109, XIII. 70. The earlier grant was made from Kāyāvatara (Kurvan) the later one is mutilated. \* Before A.D. 738-9. See Chap. IX. above.

**Chapter X.**  
**THE GURJJARAS,**  
**A.D. 580-808.**

(3) That genuine grants sometimes show that a description written for one king is afterwards applied to another, and that good or bad readings are no test of the age of a grant.

It may be admitted that Dr Bühler has made it probable that the suspected grants and the grant of Dharaśena were not all written by the same hand, and also that the coincidence in the writer's name is not of much importance in itself. But the paleographical resemblance between Dharaśena's grant on the one hand and the doubtful Gurjara grants on the other is so close that they must have been written at about the same time. As to the third point, the verbal agreement between the doubtful grants on the one hand and the Kheda grants on the other implies the existence of a continuous tradition in the record office of the dynasty from the end of the fifth till near the middle of the seventh century. But the Samhela grant of Nushikaka (Ep. Ind. II, 21) shows that towards the end of the sixth century the lower Narmada valley was occupied by jungle tribes who acknowledged the supremacy of the Kalachuris. Is it reasonable to suppose that after the last Gurjara line was thus displaced, the restorers of the dynasty should have had any memory of the forms in which the first line drew up their grants? At any rate if they had, they would also have retained their original seal, which, as the analogy of the Valabhi plates teaches us, would bear the founder's name. But we find that the seal of the Kheda plates bears the name 'Samanta Dadda' who can be no other than the "Samanta Dadda" who ruled from c. 585-605 A.D. It follows that the Gurjaras of the seventh century themselves traced back their history in Bhoj to no further than A.D. 585. Again, it has been pointed out in the text that a passage in the description of Dadda II, A.D. 620-650 in the Kheda grants seems to refer to his protection of the Valabhi king, so that the description must have been written for *him* and not for the fifth century Dadda as Dr. Bühler's theory requires.

These points coupled with Mr. Fleet's opinion (Ind. Ant. XVII, 91) that the Saka dates do not work out correctly, may perhaps be enough to show that none of these three grants can be relied upon as genuine. —(A. M. T. J.)

## CHAPTER XI.

## THE RĀSHṬRAKŪṬAS

(A.D. 743-974.)

THE Rāshṭrakūṭa connection with Gujarāt lasted from Śaka 365 to 891 (A.D. 743-974) that is for 231 years. The connection includes three periods: A first of sixty-five years from Śaka 365 to 730 (A.D. 743-808) when the Gujarāt ruler was dependent on the main Dakhan Rāshṭrakūṭa; a second of eighty years between Śaka 730 and 810 (A.D. 808-888) when the Gujarāt family was on the whole independent; and a third of eighty-six years Śaka 810 to 896 (A.D. 888-974) when the Dakhan Rāshṭrakūṭas again exercised direct sway over Gujarāt.

Information regarding the origin of the Rāshṭrakūṭas is imperfect. That the Gujarāt Rāshṭrakūṭas came from the Dakhan in Śaka 365 (A.D. 743) is known. It is not known who the Dakhan Rāshṭrakūṭas originally were or where or when they rose to prominence. Rāthod the dynastic name of certain Kanauj and Marwar Rājputs represents a later form of the word Rāshṭrakūṭa. Again certain of the later inscriptions call the Rāshṭrakūṭas Rattas a word which, so far as form goes, is hardly a correct Prakrit contraction of Rāshṭrakūṭa. The Sanskrit contraction of tribal names is not exact. If the word Rattā was a tribe it might be pronounced Ratta, Rattha, or Roldi. This last form almost comports with the modern Kānarese caste name Reddi, which, so far as information goes, would place the Rāshṭrakūṭas among the tribes of pre-Sanskrit southern origin.

If Rattā is the name of the dynasty *kūṭa* or *kūda* may be an attribute meaning prominent. The combination Rāshṭrakūṭa would then mean the chiefs or leaders as opposed to the rank and file of the Rattas. The bardic accounts of the origin of the Rāthods of Kanauj and Marwar vary greatly. According to a Jam account the Rāthods, whose name is fancifully derived from the *rahit* or spine of Indra, are connected with the Yavon through an ancestor Yavanaśva prince of Pārlipur. The Rāthod genealogies trace their origin to Kuśa son of Rāma of the Solar Race. The bards of the

## Chapter XI.

THE  
RĀSHṬRAKŪṬAS  
A.D. 743-974.

Their Origin.

Their Name.

**Chapter XI.**

THE  
RĀSHTRAKŪTAS,  
A.D. 743-972.  
Their Name

Solar Race hold them to be descendants of Hiranya Kaśipa by a demon or *daitya* mother. Like the other great Rājput families the Rāsthods' accounts contain no date earlier than the fifth century A.D. when (A.D. 470, S. 529) Nāga Pāla is said to have conquered Kanauj slaying its monarch Appala.<sup>1</sup> The Dakṣiṇa Rāshtrakūtas (whose earliest known date is also about A.D. 450) call themselves of the Lunar Race and of the Yādava dynasty. Such contradictions leave only one of two origins to the tribe. They were either foreigners or southerners Brahmanised and included under the all-embracing term Rājput.

Early Dynasty,  
A.D. 450-500.

Of the rise of the Rāshtrakūtas no trace remains. The earliest known Rāshtrakūta copperplate is of a king Abhimanyu. This plate is not dated. Still its letters, its style of writing, and its lion seal, older than the Girdi mark which the Rāshtrakūtas assumed along with the claim of Yādava descent, leave no doubt that this is the earliest of known Rāshtrakūta plates. Its probable date is about A.D. 450. The plate traces the descent of Abhimanyu through two generations from Mananka. The details are

Mananka,

Devanaga

Abhimanyu

The grant is dated from Manapana, perhaps Mananka's city, probably an older form of Manvakheta the modern Malkhed the capital of the later Rāshtrakūtas about sixty miles south-east of Sholapur. These details give fair ground for holding the Manankas to be a family of Rāshtrakūta rulers earlier than that which appears in the usual genealogy of the later Rāshtrakūta dynasty (A.D. 740-972).

The  
Mam Dynasty,  
A.D. 630-972.

The earliest information regarding the later Rāshtrakūtas is from a comparatively modern and therefore not quite trustworthy, Chalukya copperplate of the eleventh century found by Mr. Wathen. This plate states that Jayasimha I. the earliest Chalukya defeated the Rāshtrakūta Indrasena son of Krishna the lord of 800 elephants. The date of this battle would be about A.D. 500. If historic the reference implies that the Rāshtrakūtas were then a well established dynasty. In most of their own plates the genealogy of the Rāshtrakūtas begins with Geymda about A.D. 680. But that Geymda was not the founder of the family is shown by Dantidurga's Elura Daśāvatara inscription (about A.D. 750) which gives two earlier names Dantivarman and Indra. The founding of Rāshtrakūta power is therefore of doubtful date. Of the date of its overthrow there is no question. The overthrow came from the hand of the Western Chalukya Taleppa in Śaka 894 (A.D. 972) during the reign of the last Rāshtrakūta Kakka III, or Kakkala.

<sup>1</sup> Tod's *Annals of Rajasthan*, I. 88; II. 2.



## Chapter XI.

THE  
RĀSHTRAKŪṬAS,  
A.D. 743-974

Kakka II.  
A.D. 747.

The plate notices that Kakka the grantor was the son of Govinda by his wife the daughter of the illustrious Nāgavarman. Kakka is further described by the laudatory title '*Samadhigatapanch-mahasabdhah*' Holder of the five great names. At the same time he is also called *Paramabhattacharya-Maharāja* Great Lord Great King, attributes which seem to imply a claim to independent power. The grant is dated the eighth seventh of Āsvayuja, Śaka 669 (A.D. 747). The date is almost contemporary with the year of Dantidurga in the Samangad plate (A.D. 753). As Dantidurga was a very powerful monarch we may identify the first Kakka of this plate with Kakka I, the grandfather of Dantidurga and thus trace from Dhruva Kakka's son a branch of feudatory Rashtrakutas ruling in Malwa in Gujarat, whose leaders were Dhruva, his son Govinda, and Govinda's son Kakka II. Further Dantidurga's grant shows that he conquered Central Gujarat between the Mahi and the Narmadā<sup>1</sup> while his Khma Dasavatara inscription (A.D. 750) shows that he held Lāṭa and Malava.<sup>2</sup> Dantidurga's conquest of Central Gujarat seems to have been signified by grants of land made by his mother in every village of the Matar division which is apparently the Matar taluka of the Kaira district.<sup>3</sup> It is possible that Dantidurga gave conquered Gujarat to his paternal cousin's son and contemporary Kakka, the grantor of the Antoh plate (A.D. 747), as the representative of a family ruling somewhere under the overlordship of the main Dakṣiṇ Rashtrakutas. Kakka's Baroda grant<sup>4</sup> (A.D. 812) supports this theory. Dantidurga died childless and was succeeded by his uncle Krishna. Of this Krishna the Baroda grant says that he assumed the government for the good of the family after having rooted out a member of the family who had taken to mischief-making. It seems probable that Kakka II the grantor of the Antoh plate is the mischief-maker and that his mischief was, on the death of Dantidurga, the attempt to secure the succession to himself. Krishna frustrated Kakka's attempt and rooted him out so effectively that no trace of Kakka's family again appears.

Krishna and  
Govinda II.  
A.D. 765-795.

From this it follows that so far as is known, the Rashtrakuta conquest of Gujarat begins with Dantidurga's conquest of Lāṭa, that is South Gujarat between the Mahi and the Narmada, from the Gujjara king Jayabhatta whose latest known date is A.D. 736 or seventeen years before the known date of Dantidurga. The Gujjaras probably retired to the Rappipla hills and further east on the confines of Malwa where they may have held a lingering sway.<sup>5</sup> No Gujarat event of importance is recorded during the reign of Krishna (A.D. 765) or of his son Govinda II. (A.D. 780) who about

<sup>1</sup> Ind. Ant. XI, 112.

<sup>2</sup> Bombay Arch. Sur. Separate Number, 10, 94.

<sup>3</sup> This verse which immediately follows the mention of Govinda's conquests on the banks of the Mahi and the Narmadā obviously explains the name of the Matar taluka as meaning the Mother's taluka.

<sup>4</sup> Ind. Ant. XII, 156.

<sup>5</sup> The Khandesh Revue and Dore Gujars of Chopdā and Baver in the east, and also over most of the west, may be a remnant of these Gujjars of Broach who at this time (A.D. 710), and perhaps again about sixty years later, may have been forced up the Narmada and Tapti into South Malwa and West Khandesh. This is doubtful as their migration is said to have taken place in the eleventh century and may have been due to pressure from the north the effect of Mahmūd Ghaznavi's invasions (A.D. 1000-1025).

A.D. 795 was superseded by his powerful younger brother Dhruva.<sup>1</sup>

Dhruva was a mighty monarch whose conquests spread from South India as far north as Allahabád. During Dhruva's lifetime his son Govinda probably ruled at Mayúrakhambh or Morkhambh in the Násik district and held the Ghát country and the Gujarat coast from Balsár northwards. Though according to a Kapadvanj grant Govinda had several brothers the Radhanpur (A.D. 808) and Van-Dudori (A.D. 808) grants of ~~his son~~ Govinda III state that his father, seeing Govinda's supernatural Krishna-like powers, offered him the sovereignty of the whole world. Govinda declined, saying, 'The Kanthaka or coast tract already given to me is enough.' Seeing that Mayúrakhambh or Morkhambh in Nasik was Govinda's capital, this Kanthaka appears to be the coast from Balsar northwards.

According to Gujrat Govinda's (A.D. 827-834) Kavi grant (A.D. 827), finding his power threatened by Shambha and other kings, Dhruva made the great Govinda independent during his own lifetime. This suggests that while Dhruva continued to hold the main Rashtrakuta sovereignty in the Deccan he probably invested Govinda with the sovereignty of Gujrat. This fact the Kavi grant (A.D. 827) being a Gujrat grant would rightly mention while it would not find a place in the Radhanpur (A.D. 808) and Van-Dudori (A.D. 808) grants of the main Rashtrakutas. Of the kings who opposed Govinda the chief was Shambha who may have some connection with Canbaya a ruler during the time of the Anandavada kings. Canbaya came to be called Shambha-tritha instead of by its old name of Canbhira. According to the grant the allied chiefs were no match for Govinda. The Gujjara fled through fear, not returning even in dreams, and the Malwa king submitted. When the Gujjara were it is hard to say. He may have belonged to some Gujjara dynasty that rose to importance after Dantidurga's conquest or the name may mean a ruler of the Gujjara country. In either case some North Gujrat ruler is meant whose conquest opened the route from Broach to Malwa. From Malwa Govinda marched to the Vindhya where the king apparently of East Malwa named Mara Sarva submitted to Govinda paying tribute. From the Vindhya Govinda returned to Gujrat passing the rains at S'citavaya,<sup>2</sup> apparently Subhon in the Amel Taluka of Broach, a favourite locality which he had ruled during his father's lifetime. After the rains Govinda went south as far as the Tungabhadra. On starting for the south Govinda handed Gujrat to his brother Indra with whom begins the Gujrat branch of the Rashtrakutas. Several plates distinctly mention that Indra was given the kingdom of the Lord of Lata by (his brother) Govinda. Other Gujrat grants, apparently with intent to show that Indra won Gujrat and did not receive it in gift, after mentioning Sarva Amoghavarsha as the successor of Govinda (A.D. 818), state that the king (apparently of Gujrat) was Sarva's uncle Indra.

## Chapter XI.

THE  
RASHTRAKÚTAS,  
A.D. 743-974.

Dhruva I.  
A.D. 795.

Govinda III.  
A.D. 800-808.

<sup>1</sup> Ind. Ant. VI, 65, Journ. R. A. Soc., V. 350.

<sup>2</sup> Ind. Ant. VI, 65.

## Chapter XI.

THE  
RĀSHTRAKŪṬAS,  
A.D. 743-974.

Indra,  
A.D. 808-812.

As Govinda III. handed Gujarāt to his brother Indra about Śāka 730 (A.D. 808) and as the grant of Indra's son Karka is dated Śāka 734 (A.D. 812) Indra's reign must have been short. Indra is styled the ruler of the entire kingdom of Latesvara,<sup>1</sup> the protector of the *mandala* of Līṭa given to him by his lord. An important verse in an unpublished Baroda grant states that Indra chased the lord of Gurjara who had prepared to fight, and that he honourably protected the multitude of Dakhan (Dakshināpatha) feudatories (*mahāsāmantas*) whose glory was shattered by Śrīvallabha (that is Śarva or Amoghavarsha) then hereditary of Govinda. That is, in attempting to establish himself in independent power, Indra aided certain of the Rāshtrakūṭa feudatories in an effort to shake off the overlordship of Amoghavarsha.

Indra was succeeded by his son Karka I. who is also called Suvarnavarsha and Patalamalla. Karka reversed his father's policy and loyally accepted the overlordship of the main Rāshtrakūṭas. Three grants of Karka's remain, the Baroda grant dated Śāka 734 (A.D. 812) and two unpublished grants from Navsār and Sīrat dated respectively Śāka 738 (A.D. 816) and Śāka 743 (A.D. 821). Among Doctor Bhagvānlāl's collection of inscriptions bequeathed to the British Museum the Baroda grant says that Karka's *śrīman* or lord, apparently Govinda III, made use of Karka's arm to protect the king of Malava against invasion by the king of Gurjara who had become pulled up by conquering the lords of Gauda and Vanga that is modern Bengal. This powerful Gurjara king who conquered countries so distant as Bengal has not been identified. He must have been ruling north of the Mahī and threatened an invasion of Malwa by way of Dohad. He may have been either a Valabhi king or one of the Bhīmāli Gurjaras, who, during the decline of the Valabhis, and with the help of their allies the Chāyadās of Amulavada whose leader at this time was Yog Rāja (A.D. 806-811), may have extended their dominion as far south as the Mahī. As the Baroda plate (A.D. 812) makes no mention of Amoghavarsha-Śarva while the Navsār plate (A.D. 816) mentions him as the next king after Govinda III, it follows that Govinda III died and Amoghavarsha succeeded between A.D. 812 and 816 (S. 734 and 738). This supports Mr. Fleet's conclusion, on the authority of Amoghavarsha's Sirur inscription, that he came to the throne in Śāka 736 (A.D. 814). At first Amoghavarsha was unable to make head against the opposition of some of his relations and feudatories, supported, as noted above, by Karka's father Indra. He seems to have owed his

<sup>1</sup> The kingdom is not called Lāṭa in the copperplate but Lāṭesvarī *mandala*. An unpublished Baroda grant has इास्तु प्रतापप्रदितः पृथिव्या सर्वस्य लाटेश्वरमण्डलस्य. The ruler boasts by glory, of the whole kingdom of the king of Lāṭa. Other published grants record Govinda's gift of Gujarāt to Indra as तद्वत्तद्विश्वमण्डलस्य त्रिभुज (Triputa) to whom the kingdom of the lord of Lāṭa had been given by him (Govinda). Ind. Ant. XII, 162.

<sup>2</sup> Ind. Ant. XII, 160, unpublished Baroda grant. Śrīvallabha appears to mean Amoghavarsha who is also called Lakshmovallabha in an inscription at Sirur in Dhārwar (Ind. Ant. XII, 215).

subsequent success to his cousin Karka whom an unpublished Surat grant and two later grants (S' 757 and S' 789, A.D. 835 and 867) describe as establishing Anoghavarsha in his own place after conquering by the strength of his arm arrogant tributary Rāshtrakūṭas who becoming firmly allied to each other had occupied provinces according to their own will.

Karka's Baroda plates (S' 731, A.D. 812) record the grant of Baroda itself called Vadapadaka in the text. Baroda is easily identified by the mention of the surrounding villages of Jambavāṭ-vikā the modern Jambhvada on the east, of Ankottaka the modern Akotā on the west, and of Vaggbachchha perhaps the modern Vaghodia on the north. The writer of the grant is mentioned as the great minister of peace and war Nemaḍitya son of Durgabhatta, and the Dūtaka or grantor is said to be Kapaṇṭha that is prince Dantivarman apparently a son of Karka. The grantee is a Brahmin originally of Valabhi.

Karka's Navsari grant (S' 738, A.D. 816) is made from Kheda and records the gift of the village of Samāpadaka in the country lying between the Mahi and the Nerbada. The grantee is a South Indian Brāhmin from Badami in Bijapur, a man of learning popularly known as Pandita Vallabhanaga because he was proficient in the fourteen Vidyas. The Dūtaka of this grant is a South Indian *bhāṭa* or military officer named the illustrious Divacamma.

Karka's Surat grant (S' 743, A.D. 821) is made from the royal camp on the bank of the Vankika apparently the Vanki creek near Balsār. It records the grant of a field in Ambopadaka village near Nāgasarika (Navsari) to a Jain temple at Nagarika (Navsari). The writer of the grant is the minister of war and peace Narayana son of Durgabhatta. As this is the first grant by a Gujarat Rāshtrakūṭa of lands south of the Tapti it may be inferred that in return for his support Anoghavarsha added to Karka's territory the portion of the North Konkan which now forms Gujarat south of the Tapti.

According to Karka's Baroda plate (S' 731, A.D. 812) Karka had a son named Dantivarman who is mentioned as the princely Dūtaka of the plate. The fact of his being a Dūtaka implies that Dantivarman was then of age, i.e. that Dantivarman was a son of Karka is supported by Akalavarsha's Bagmura plate (S' 810, A.D. 888), where, though the plate is badly composed and the grammar is faulty, certain useful details are given regarding Dantivarman who is clearly mentioned as the son of Karka. Karka had another son named Dhruva, who, according to three copperplates, succeeded to the throne. But as Dantivarman's son's grant is dated Śaka 810 or seventy-six years later than the Baroda plate some error seems to have crept into the genealogy of the plate. Neither Dantivarman nor Dhruva seems to have succeeded their father as according to Govinda's Kāvī grant (A.D. 827) their uncle Govinda succeeded his brother Karka. The explanation may be that Dantivarman died during his father's lifetime, and that some years later, after a great yearning for a son,<sup>1</sup> probably in Karka's old age, a second

## Chapter XI.

THE  
RĀSHTRAKŪṬAS,  
A.D. 743-974.  
Karka I.  
A.D. 812-821.

Dantivarman,  
His Appoint.

<sup>1</sup> Several copperplates give Karka the epithet *Pratijātastasya* 'son yearning

**Chapter XI.**

THE

RASHTRAKÚTAS,  
A.D. 743-974Govinda,  
A.D. 827-833.

son Dhruva was born, during whose minority, after Karka's death, Govinda appears to have temporarily occupied the throne.

This Govinda, the brother and successor of Karka, was also called Prabhūtavarsha. One plate of Govinda's Kāvī grant is dated Śaka 749 (A.D. 827). It gives no details regarding Govinda. The grant is made from Broach and records the gift of a village<sup>1</sup> to a temple of the Sun called Javaditya in Kōmpur near Kāpikā that is Kāvī thirty miles north of Broach. The writer of the grant is Yogesvara son of Avalokita and the Dātaka or grantor was one Bhatta Kimmuda. As it contains no reference to Govinda's succession the plate favours the view that Govinda remained in power only during the minority of his nephew Dhruva.

Dhruva I,  
A.D. 835-867.

This Dhruva who is also called Nrupama and Dhāruvarsha, is mentioned as ruler in a Baroda grant dated Śaka 757 (A.D. 835).<sup>2</sup> He therefore probably came to the throne either on attaining his majority in the lifetime of his uncle and predecessor Govinda or after Govinda's death. Dhruva's Baroda grant (S. 757, A.D. 835) is made from a place called Savyamangala near Khedi and records the gift of a village to a Brahman named Yogi of Badarasidhi apparently Dorad. The writer of the grant is mentioned as the minister of peace and war Narayana son of Dingabhatta, and the Dātaka or grantor is the illustrious Devaraja. Dhruva seems to have assumed his father's position of loyal feudatory to the main Rashtrakūtas. According to a copperplate dated Śaka 832 (A.D. 910, Vallabha that is Amoghavarsha, also called the illustrious great Skanda, sent an army and besieged and burned the Kanthuka that is the coast tract between Bombay and Cambay. In the course of this campaign, according to Dhruva II's Bagumra grant (S. 789, A.D. 867),<sup>3</sup> Dhruva died on the field of battle covered with wounds while routing the army of Vallabha or Amoghavarsha. This statement is supported by a Kenheri cave inscription which shows that Amoghavarsha was still alive in Śaka 799 (A.D. 877).

Akalavarsha,  
A.D. 867.

Dhruva was succeeded by his son Akalavarsha also called Śubhatunga. A verse in Dhruva II's Bagumra grant (S. 789, A.D. 867) says that Akalavarsha established himself in the territory of his father, which after Dhruva's death in battle, had been overrun by the army of Vallabha and had been distracted by evil-minded followers and dependants.<sup>4</sup>

Dhruva II,  
A.D. 867.

Akalavarsha was succeeded by his son Dhruva II also called Dhāruvarsha and Nrupama. Of Dhruva II two copperplates remain the published Bagumra grant dated Śaka 789<sup>5</sup> (A.D. 867) and an

<sup>1</sup> All village and boundary details have been identified by Dr. Bühler. Ind. Ant. V. 148.

<sup>2</sup> Ind. Ant. XIV. 199.

<sup>3</sup> This done is said to have been given the name of Jyotishuka by the illustrious Govindanaka apparently the uncle and predecessor of the granting king.

<sup>4</sup> Ind. Ant. XII. 179.

<sup>5</sup> Ind. Ant. XII. 181. The verse may be translated 'By whom before long was occupied the province handed down from his father which had been overrun by the forces of Vallabha and distracted by numbers of evil-minded followers.'

<sup>6</sup> Ind. Ant. XII. 179.

unpublished Baroda grant dated Śaka 793 (A.D. 871)<sup>1</sup>. Both plates record that Dhruva crushed certain intrigues among his relatives or *bandhucarya*, and established himself firmly on the throne. Regarding the troubles at the beginning of his reign the Bagumra plate states that, on one side Vallabha the head of the Dakhan Rāshtrakūtas was still against him, on another side Dhruva had to face an army of Gujjaras instigated by a member of his own family<sup>2</sup>, thirdly he was opposed by certain of his relatives or *bāndhava*; and lastly he had to contend against the intrigues of a younger brother or *anapa*. It further appears from Dhruva II's Bagumra plate that he checked an incursion by a Mihna king with a powerful army. This Mihna king was probably a chief of the Kathavada Mehrs who on the downfall of the Valabhis spread their power across Gujjarāt. In all these troubles the Bagumra grant notes that Dhruva was aided by a younger brother named Govindarāja. This Govindarāja is mentioned as appointed by Dhruva the Dūtaka of the grant.

Dhruva II's Bagumra (A.D. 897) grant was made at Bhregh-Kachhliha or Broach after bathing in the Narbada. It records the gift to a Brahman of the village of Parahamaka probably the village of Palsana<sup>3</sup> twelve miles south-east of Bagumra in the Balesar subdivision of the Garkwā's territory of Surat and Navsari. Dhruva's Baroda grant (A.D. 871) was also made at Broach. It is a grant to the god Kapalesvara Mahadeva of the village Konyalli and Naktabhaga both mentioned as close to the south bank of the Mahi. The facts that the Bagumra grant (A.D. 897) transfers a village so far south as Balesar near Navsari and that four years later the Baroda grant (A.D. 871) mentions that Dhruva's territory lay between Broach and the Mahi seem to prove that between A.D. 897 and 871 the portion of Dhruva's kingdom south of Broach passed back into the hands of the main Rashtrakutas.

The next and last known Gujjarāt Rashtrakūta king is Akalayursha-Krishna son of Dantivarmman. A grant of this king has been found in Bagumra dated Śaka 810 (A.D. 887)<sup>4</sup>. The composition of the grant is so bad and the genealogical verses after Karka are so confused that it seems unsafe to accept any of

## Chapter XI.

THE  
RASHTRAKÚTAS  
A.D. 743-974.

Dhruva II.  
A.D. 867.

Akalayursha-  
Krishna,  
A.D. 888.

<sup>1</sup> This plate was in Dr. Blegny's possession. It is among the plates deposited to the British Museum. Dr. Bhabalal Chatterjee (A.S. III XVIII 255) mentions another unpublished grant of Ś. 789 (A.D. 867) made by Dhruva's brother Dantivarmman.

<sup>2</sup> These may be either the Gujjaras between Malwa and Gujjarāt, or the Bhutnadi Gujjaras north of the Mahi. It is also possible that they may be Chavadas as in this passage the term Gujjara does not refer to the tribe but to the country. [There seems little reason to doubt the reference as to the Gujjaras of Bhutnadi or Satal, probably noting through their underlords the Chavadas of Anandavada whose king in A.D. 865 was the warlike Kshema Raja (A.D. 841-866). Census and other recent information establish almost with certainty that the Chavadas or Chavolakas are of the Gujjaras race.]

<sup>3</sup> The identification is not satisfactory. Except the Brahman settlement of Mottaka, apparently the well known Motāla Brahman settlement of Motā, which is mentioned as situated on the west though it is on the north-east, none of the boundary villages can be identified in the neighbourhood of Palsana. In spite of this the name Palsana and its close vicinity to Bagumra where the grant was found make this identification probable.

<sup>4</sup> Ind. Ant. XIII. 65.

**Chapter XI.**

THE  
RĀSHTRAKŪṬAS,  
A.D. 743-974.  
Akālavarsha-  
Krishna,  
A.D. 888.

Main Line  
Restored,  
A.D. 858-974.

Krishna  
Akālavarsha,  
A.D. 888-911.

its details except its date which is clearly Śaka 810 (A.D. 888). It seems also improbable that the son of Dantivarman who flourished in Śaka 734 (A.D. 812) could be reigning in Śaka 810 (A.D. 888) seventy-six years later. Still the sixty-three years' reign of the contemporary Mānyakheṭa Rāshtrakūṭa Amoghavarsha (Ś. 736-799, A.D. 814-877) shows that this is not impossible.

The grant which is made from Anklesvar near Broach records the gift to two Brāhmins of the village of Kavithasādhi the modern Kosād four miles north-east of Surat, described as situated in the Varāvi (the modern Varay two miles north of Surat) sub-division of 116 villages in the province of Konkani. The grant is said to have been written by the peace and war minister the illustrious Jajjaka son of Kuluka, the Dutaka being the head officer (*mahattama-saradhikari*) the Brahman Ollavaka.<sup>1</sup> This grant seems to imply the recovery by the local dynasty of some portion of the disputed area to the south of the Tapti. This recovery must have been a passing success. After Śaka 810 (A.D. 888) nothing is known of the Gujarat Rāshtrakūṭas. And the re-establishment of the power of the Rāshtrakūṭas of Mānyakheṭa of the main line in south Gujarāt in Śaka 836 (A.D. 914) is proved by two copperplates found in Navsārī which record the grant of villages near Navsārī, in what the text calls the Lata country, by king Indra Nityanvarsha son of Jagattinga and grandson of Krishna Akālavarsha.<sup>2</sup>

That Amoghavarsha's long reign lasted till Śaka 799 (A.D. 877) is clear from the Kaveri cave inscription already referred to. His reign can hardly have lasted much longer; about Śaka 800 (A.D. 878) may be taken to be its end.

Amoghavarsha was succeeded by his son Krishna also called Akālavarsha, both his names being the same as those of the Gujarāt Rāshtrakūṭa king of the same time (A.D. 888).<sup>3</sup> It has been noted above that, in consequence of the attempt of Karka's son Dhruva I. (A.D. 835-837) to establish his independence, Amoghavarsha's relations with the Gujarat Rāshtrakūṭas became extremely hostile and probably continued hostile till his death (A.D. 877). That Amoghavarsha's son Krishna kept up the hostilities is shown by Indra's two Navsārī plates of Śaka 836 (A.D. 914) which mention his grandfather Krishna fighting with the roaring Gurjjara.<sup>4</sup> Regarding this fight the late Rāshtrakūṭa Karka plate (Ś. 891, A.D. 973) further says that Krishna's enemies frightened by his exploits abandoned Khetika, that is Khedā, with its Mandala and its forepart that is the surrounding country. Probably this roaring Gurjjara or king of Gujarāt, was a northern ally called in by some Rāshtrakūṭa of the

<sup>1</sup> Ind. Ant. XIII. 65-69.

<sup>2</sup> These were among Dr. Bhagvanlal's copperplates, and seem to be the same as the two grants published by Dr. Bhandarkar in B. B. R. A. S. JI. XVIII. 253.

<sup>3</sup> See above page 127.

<sup>4</sup> The text is: उद्यद्दीधितिरत्नजालजटिलव्याकृष्टर्षादग्धनुः। कुद्वेनोपरि वैरिवीरशिर-  
साभेय विमुक्ताः शराः। धारासारिणी मेन्द्रचापवलये यस्येत्य मन्दागमे गर्ज्जरङ्ग-  
सगर्व्यतिकर्षं जीर्णजनः शंसति.

Gujarāt branch, perhaps by Kṛishna's namesake the donor of the A.D. 888 Bagumrā grant. The Dakhan Kṛishna seems to have triumphed over his Gujarāt namesake as henceforward South Gujarāt or Lāṭa was permanently included in the territory of the Dakhan Rāshtrakūṭas.<sup>1</sup>

At this time (A.D. 910) a grant from Kapadvanj dated S. 832 (A.D. 910) and published in Ep. Ind. I 52ff. states that a *mahā-sāmanta* or noble of Krishna Akālavarsha's named Prachanda, with his *daṇḍanāyaka* Chandragupta, was in charge of a sub-division of 750 villages in the Kheda district at Harshapura apparently Harsol near Parāntij. The grant gives the name of Prachanda's family as Brāhma-vaka (?) and states that the family gained its fortune or Lakshinī by the prowess of the feet of Akālavarsha, showing that the members of the family drew their authority from Akālavarsha. The grant mentions four of Prachanda's ancestors, all of whom have non-Gujarāt Kānarese-looking names. Though not independent rulers Prachanda's ancestors seem to have been high Rāshtrakūṭa officers. The first is called Sudha-kkumbadi, the second his son Degadi, the third Degadi's son Rājahansa, the fourth Rājahansa's son Dhavalappa the father of Prachanda and Akkuka. The plate describes Rājahansa as bringing back to his house its flying fortune as if he had regained lost authority. The plate describes Dhavalappa as killing the enemy in a moment and then giving to his lord the Maṇḍala or kingdom which the combined enemy, desirous of glory, had taken. This apparently refers to Akālavarsha's enemies abandoning Khetaka with its Maṇḍala as mentioned in the late Rāshtrakūṭa Karda plate (A.D. 973). Dhavalappa is probably Akālavarsha's general who fought and defeated the roaring Gurjjara, a success which may have led to Dhavalappa being placed in military charge of Gujarāt.<sup>2</sup> The Kapadvanj (A.D. 910) grant describes Dhavalappa's son Prachanda with the feudatory title 'Who has obtained the five great words.' Dr. Bhagvānlāl believed Prachanda to be a mere epithet of Akkuka, and took Chandragupta to be another name of the same person, but the published text gives the facts as above stated. The grantee is a Brāhman and the grant is of the village of Vyāghrāsa, perhaps Vagrā in Broach.<sup>3</sup> The plate describes Akkuka as gaining glory fighting in the battle field. A rather unintelligible verse follows implying that at this time the Sella-Vidyādhara, apparently the North Konkan Silāhāras (who traced their lineage from the Vidyādhara) also helped Akālavarsha against his enemies,<sup>4</sup> probably by driving them from South Gujarāt. The Silāhāra king at this time would be Jhanjha (A.D. 916).

<sup>1</sup> It will be noted that in S'aka 836 (A.D. 914) Kṛishna's grandson Indra re-grants 400 ~~permanently~~ villages many of which were perhaps resumed at this time by Kṛishna.

<sup>2</sup> It follows that none of Dhavalappa's three ancestors had any connection with Gujarāt.

<sup>3</sup> Dr. Hultsch (Ep. Ind. I. 52) identifies Vyāghrāsa with Vaghās, north-east of Kapadvanj. Dr. Bhagvānlāl's account of the grant was based on an impression sent to him by the Māmlatdar of Kapadvanj.

<sup>4</sup> The text is: सेलु विद्याधरेणापि सेलु [हेल्ने] क्खलित तपानि पाणिना निहत्वा शत्रून् समये [रे] यशमाकलमलंकृतं. Dr. Hultsch takes the Sella-Vidyādhara here named to be another brother of Prachanda and Akkuka. The verse is corrupt.

## Chapter XI.

THE  
RĀSHTRAKŪTAS,  
A.D. 743-974.  
Krishna  
Akālavarsha,  
A.D. 888-914. •

## Chapter XI.

THE  
RĀSHTRAKŪṬAS,  
A.D. 743-974.

Indra  
Nityamvarsha,  
A.D. 914.

Kṛishṇa or Akālarvarsha had a son named Jagattuṅga who does not appear to have come to the throne. Other plates show that he went to Chedi the modern Bundelkhand and remained there during his father's lifetime. By Lakshmi the daughter of the king of Chedi, Jagattuṅga had a son named Indra also called Nityamvarsha Raṭṭikandarpa. In both of Indra's Navsārī copperplates (A.D. 914) Indra is mentioned as *Pādīnādhyata*, Falling at the feet of, that is successor of, not his father but his grandfather Akālarvarsha.<sup>1</sup> One historical attribute of Indra in both the plates is that "he uprooted in a moment the Mehr,"<sup>2</sup> apparently referring to some contemporary Mehr king of North Kathiāwār. Both the Navsārī plates of Śaka 836 (A.D. 914) note that the grants were made under peculiar conditions. The plates say that the donor Indra Nityamvarsha, with his capital at Manyakheta, had come to a place named Kurundaka for the *puṭṭabandha* or investiture festival. It is curious that though Manyakheta is mentioned as the capital the king is described as having come to Kurundaka for the investiture. Kurundaka was apparently not a large town as the plates mention that it was given in grant.<sup>3</sup> At his investiture Indra made great gifts. He weighed himself against gold or silver, and before leaving the scales he gave away Kurundaka and other places, twenty and a half lākhs of dramma coins, and 400 villages previously granted but taken back by intervening kings. These details have an air of exaggeration. At the same time gifts of coins by lākhs are not improbable by so mighty a king as Indra and as to the villages the bulk of them had already been alienated. The fact of lavish grants is supported by the finding of these two plates of the same date recording grants of two different villages made on the same occasion, the language being the same, and also by a verse in the late Rāshtrakūṭa Kardā plate (S. 894, A.D. 972) where Indra is described as making numerous grants on copperplates and building many temples of Śiva.<sup>4</sup> The date of Indra's grants (S. 836, A.D. 914) is the date of his investiture and accession. This is probable as the latest known date of his grandfather Kṛishṇa is Śaka 833<sup>5</sup> (A.D. 911) and we know that Indra's father Jagattuṅga did not reign.<sup>6</sup> Umvarā and Tenna, the villages granted in the two investiture plates, are described as situated near Kammapijja the modern Kāmlej in the Lāṭa province. They are probably the modern villages of Umra near Sāyan four miles west of Kāmlej, and of Tenna immediately to the west of Bārdoli, which last is mentioned under the form Vāradapallikā as the eastern boundary village. Dhruva II.'s Bagumra plate (S. 789, A.D. 867) mentions Tenna as granted

<sup>1</sup> The Khārepātan grant makes this clear by passing over Indra's father Jagattuṅga in the genealogy and entering Indra as the grandson and successor of Akālarvarsha. Jour. B. B. R. A. Soc. I. 217.

<sup>2</sup> The text has *Helomūlituneruṇā* to chime with the poetical allusion and figure about Indra. By Meru no doubt Meis or Mehr is meant.

<sup>3</sup> Kurundaka may be the village of Kurund in the Thāna zilla seven miles north-east of Bhiwadi. It was a village given away in grant and cannot therefore be any large town. [Kurundāvid at the holy meeting of the Kṛishṇa and Pañchganga in the Southern Maratha Country close to Narsol's Vadi seems a more likely place for an investiture.]

<sup>4</sup> J. R. A. S. III. 94.

<sup>5</sup> Ind. Ant. XI. 109.

<sup>6</sup> See above.

by Dhruva I. to a Bráhmaṇa named Dhoddi the father of the Nennapa who is the grantee of Dhruva II.'s A.D. 837 Bagumrá grant, whose son Siddhabhatta is the grantee of Indra's A.D. 914 grant.<sup>1</sup> The re-granting of so many villages points to the re-establishment of the main Ráshtrakúta power and the disappearance of the Gujarát branch of the Ráshtrakútas.<sup>2</sup>

Though no materials remain for fixing how long after A.D. 914 Gujarát belonged to the Mányakheṭa Ráshtrakútas, they probably continued to hold it till their destruction in Śaka 894 (A.D. 972) by the Western Chálukya king Tailappa. This is the more likely as inscriptions show that till then the neighbours of Gujarát, the North Konkan Śilaháras, acknowledged Ráshtrakúta supremacy.

It is therefore probable that Gujarát passed to the conquering Tailappa as part of the Ráshtrakúta kingdom. Further, as noted below in Part II. Chapter II., it seems reasonable to suppose that about Śaka 900 (A.D. 978) Tailappa entrusted Gujarát to his general Bírappa or Dvárappa, who fought with the Solanki Múlarāja of Anahilavada (A.D. 961-997).

[The text does not carry the question of the origin of the Ráshtrakútas beyond the point that, about the middle of the fifth century A.D., two tribes bearing the closely associated names Rathod and Raṭṭa, the leaders of both of which are known in Sanskrit as Ráshtrakutas, appeared the first in Upper India the second in the Bombay Kanáṭak, and that the traditions of both tribes seem to show they were either southerners or foreigners Bráhmaṇised and included under the all embracing term Rápput. The Sanskrit form Ráshtrakuta may mean either leaders of the Ráshtra tribe or heads of the territorial division named *rashtra*. The closely related forms Ráshtrapati and Gramakuta occur above page 82 in Valabhi inscriptions. And Mr. Fleet (Kamarose Dynasties, 32) notices that Ráshtrakuta is used in the inscriptions of many dynasties as a title equivalent to Ráshtrapati. Such a title might readily become a family name like that of the Sádhuṭs of the Panjab or the Muḍḍi surnames Patel, Nalkarni, and Desai. It may be noted that one of the Marwar traditions (Rápputana Gazetteer, III. 246) connects the word Rathod with Ráshtra country making the original form Ráshtravara or Word-blessing and referring to an early tribal guardian Ráshtra-yena or the Word-Falcon. It is therefore possible that the origin of both forms of the name, of Rathod as well as of Ráshtrakúta, is the title ruler of a district. At the same time in the case of the southern Ráshtrakútas the balance of evidence is in support of a tribal origin of the name. The Raṭṭas of Saundatti in Belgann, apparently with justice, claim descent from the former Ráshtrakúta rulers (Belgann Gazetteer, 355). Further that the Ráshtrakútas considered themselves to belong to the Raṭṭa tribe is shown by Indra Nityanavarsha (A.D. 914)

<sup>1</sup> Though the name of the *gotra* *Lakshmanavasa* and *Lakshyagavasa* differs slightly in the two grants, the identity of the name Nennapa the son of Dhoddi and the father of Siddhabhatta the A.D. 914 grantee, suggests that the original grant of the village of Tenna by Dhruva I. (A.D. 795) had been cancelled in the interval and in A.D. 914 was renewed by king Indra Nityanavarsha. [Dr. Bhandárkar reads the name in Indra's Navsári grant (A.D. 914) as Vennapa.]

<sup>2</sup> That in A.D. 915 the Dakhan Ráshtrakútas held Gujarát as far north as Cambay is supported by the Arab traveller Al Masúdi who (P. 101 s. d'Or, I. 253-254) speaks of Cambay, when he visited it, as a flourishing town ruled by Bania the deputy of the Baharí lord of Mankir. The country along the gulf of Cambay was a succession of gardens villages fields and woods with date-palm and other groves alive with peacocks and parrots.

## Chapter XI.

THE  
RÁSHTRAKÚTAS,  
A.D. 743-974.

Indra  
Nityanavarsha,  
A.D. 914.

## Chapter XI.

THE  
RĀSHTRAKŪṬAS,  
A.D. 743-974.

calling himself Rāṭtakandarpa the Love of the Rāṭṭas. The result is thus in agreement with the view accepted in the text that Rāshtrakūṭa means leaders of the Rāṭṭa tribe, the form Rāshṭrā being perhaps chosen because the leaders held the position of Rāshtrakūṭas or District Headmen. According to Dr. Bhandarkar (*Deccan History*, 9) the tribal name Rāṭṭa or Rāshṭra enters into the still more famous Dakhan tribal name Maharāṭha or Mahratta. So far as present information goes both the Rāṭṭas and the Great Rāṭṭas are to be traced to the Rāstikas mentioned in number five of Asoka's (B.C. 245) Gūnar edicts among the Apāntas or westerners along with the Pētēnikas or people of Paithan about forty miles north east of Ahimainagar (Kolhapur Gazetteer, 82). Whether the Rāstika of the edicts is like Pētēnika a purely local name and if so why a portion of the north Dakhan should be especially known as the country or Rāshṭra are points that must remain open.<sup>1</sup>

The explanation that Kūṭa the second half of Rāshtrakūṭa, means chief, has been accepted in the text. This is probably correct. At the same time the rival theory deserves notice that the name Rāshtrakūṭa is formed from two tribal names Kūṭa representing the early widespread tribe allied to the Gonds known as Koṭṭas and Koḍs in the Central Provinces North Konkan and Delhi (*Thana Gazetteer*, XII. Part II. 414). In support of this view it may be noticed that Abhimanyu's fifth century Rāshtrakūṭa inscription (*J. Bo. Br. R. As.*, XVI. 92) refers to the Koṭṭas though as enemies not allies of the Rāshtrakūṭas. At the same time certain details in Abhimanyu's grant favour an early Rāshtrakūṭa settlement in the Central Provinces, the probable head-quarters of the Koṭṭas. The grant is dated from Mānapura and is made to Dakshina Siva of Pethapaingaraka which may be the Great Siva shrine in the Mahādev hills in Hoshangabad, as this shrine is under the management of a petty chief of a place called Pagara, and as Mānapur in the Vinḍhya hills is not far off. Against the tribal origin of the word Kūṭa is to be set the fact that the northern Rāṭṭas are also called Rāshtrakūṭas though any connection between them and the Koṭṭa tribe seems unlikely.

The question remains were the southern Rāṭṭas or Rāshtrakūṭas connected with the northern Rāthōḷas or Rāshtrakūṭas. If so what was the nature of the connection and to what date does it belong. The fact that, while the later southern Rāshtrakūṭas

<sup>1</sup> It seems doubtful whether the Kānarese Rāṭṭas the Belgaum Rāṭṭas and the Telugu Reddis could have been Rāstikas or heads in the north Dakhan. The widespread Reddis trace their origin (Balfour's *Encyclopædia of India*, III. 360) to Rājamandri about thirty miles from the mouth of the Godāvari. A tradition of a northern origin remains among some of the Reddis. The Tinnivelly Reddis (*Madras J. Lit. and Science*, 187-88, page 136 note 96) call themselves Audh Reddis and assert that Ondh is the native country of their tribe. The late Sir George Campbell (*J. R. As.*, Soc. XXXV. Part II. 124) has revealed the notable fact that the fine handsome Reddis of the north of the Kānara country are like the Jāts. With this personal resemblance may be compared the Reddis' curious form of polyandry (*Balfour's Encyclopædia*, III. 340) in accordance with which the wife of the child-husband bears children to the adult males of the family, a practice which received theories (compare Mr. Kirkpatrick in *Indian Ant.* VII. 86 and Dr. Muir in *Ditto* VI. 315) would associate with the northern or Skythian conquerors of Upper India during the early centuries of the Christian era. In support of a northern Rāṭa element later than Asoka's Rāstikas the following points may be noted. That the Khaharāṭa or Khabarāṭa tribe to which the great northern conqueror Nahāpāna (A.D. 180) belonged should disappear from the Dakhan seems unlikely. Karahāṭaka the Mahābhārata name (*As. Res.* XV. 47, quoted in Wilson's *Works* VI. 178) for Karād on the Krishna suggests that Nahāpāna's conquest included Sātara and that the name of the holy place on the Krishna was altered to give it a resemblance to the name of the conqueror's tribe. That, perhaps after their overthrow by Gautamiputra Śātakarni (A.D. 149), the Khaharāṭas may have established a local centre at Kurandwād at the meeting of the Krishna and the Panchganga may be the explanation why in A.D. 616, centuries after Mānyakheta or Mālket had become their capital, the Rāshtrakūṭa Indra should proceed for investiture to Kurandaka, which, though this is doubtful, may be Kurandwād. The parallel case of the Khaharāṭas' associates the Palhavas, who passed across the southern Dakhan and by intermarriage have in the Pāḷas assumed the characteristics of a southern tribe, give a probability to the existence of a northern Khabarāṭa or Rāṭa element in the southern Rāshtrakūṭas and Rāṭṭas which the facts at present available would not otherwise justify.

## Chapter XL

THE  
RĀSHTRAKŪṬAS  
A.D. 743-974.

call themselves Yādavas of the Lunar-race, the northerners claim descent either from Kuṣa the son of Rāma or from Hinanyakaśipu would seem to prove no connection did not Abhinanyu's fifth century grant show that in his time the southern Rāshtrakūṭas had not begun to claim Yādava descent. That the Mārwar Rāthods trace their name to the *raṭh* or spine of India (Tod's Annals, II. 2), and in a closely similar fashion the Rāth or Rattu Jāts of the Sutlej (Ibbetson's 1981 Census, page 236) explain their name as stronghanded, and the Rāṭas of Bijapur (Bijapur Stat. Account, 145) trace their name to the Kāmarose *raṭṭa* right arm, may imply no closer connection than the common attempt to find a meaning for the name Rāṭa in a suitable word of similar sound. A legend preserved in the Rajputana Gazetteer (III. 246), but not noted by Tod, tells how Sevji, after (A.D. 1139) the Muslims drove his father Jaichand out of Kanauj (Tod's Annals, I. 88) took Khergal from the Gehlots and went to the Kumaṭak where the Rāthods had ruled before they came to Kanauj. From the Kumaṭak Sevji brought the image of the Rāthod Rāshtraśyena which is now in the temple of Nāgāna in Meval. The account quoted in the text from Tod (Annals, I. 88) that the Rāthods who rose to power in Mārwar in the thirteenth century belonged to a royal family who had held Kanauj since the fifth century has not stood the test of recent inquiry. It is now known that about A.D. 470 Kanauj was in the hands of the Guptas. That about A.D. 600, according to the contemporary Śrīharṣa-*charita* it was ruled by the Maukhari (Grahavarman who was put to death by a *Mahā* chief and was succeeded by Harsha. About A.D. 750, according to the Rajatanagani, Kanauj was held by Yaśovarman, and, in the next century, as inscriptions prove by the family of Dhona. It was not till about A.D. 1050 that Kanauj was occupied by the Gāhādavāla or Gāhurwāla family from whom the Rāthods of Mārwar claim descent.<sup>1</sup> If the legendary connection of the Mārwar Rāthods with Kanauj must be dismissed can the Mārwar Rāthods be a branch of the southern Rāshtrakūṭas who like the Marathās some 800 years later spread conquering northwards? Such a northern settlement of the southern Rāshtrakūṭas might be a consequence of the victories of the great Rāshtrakūṭa Dhruva who according to received opinions about A.D. 790 conquered as far north as Allahabad. It is beyond question that southerners or Karpāṭas were settled in North India between the seventh and the eleventh centuries. Still the latest information makes it improbable that Dhruva's conquests extended further north than Gujarāt. Nor has any special connection been traced between the southern Rāshtrakūṭas and the middle-age settlements of southerners or Karpāṭas in North India.<sup>2</sup> Must therefore the North Indian tribe of Rāthods be admitted to have its origin

<sup>1</sup> The eleventh century Kanauj Gāhādavālas are now represented by the Bundelas who about A.D. 1200 overthrew the Gāhādavālas in Bundelkhand. These Gāhādavālas or Bundelas trace their origin to Benares or Kāsi and may, as Harsha's *Charita* has been related to the Palas of that city who several centuries earlier carried with the Dakhan Rāshtrakūṭas. The Gāhādavālas seem to have nothing to do with the district of Garhwal (Gāhādavāla) in the Hindukhyas — (A. M. T. J.)

<sup>2</sup> The Vatsarāja defeated by Dhruva who has hitherto been identified with the Vatsa king of Kosambi is more likely to prove to be a Bachāṭa of the Gurjaras of Bhīnmal or Sindh in north Gujarāt. Among references to southern settlements in North India between A.D. 600 and 1000 may be noted the tradition (Wilson's Indian Castes, II. 143) of a Dravidian strain in the Kashmir Brahmins and in the eleventh century also in Kashmir (Rajatanagani, VI. 337) the presence of a Śātaśāhana dynasty bearing the same name as the early Śātaśāhanas of Paithan near Ahmadnagar. Other instances which might seem more directly associated with the southern Rāshtrakūṭas (A.D. 600-970) are the Karnāṭaka rulers of Nepāl beginning with A.D. 443 (Ind. Ant. VII. 91) and the natives of Karnāṭaka in Mahmūd Ghaznavi's army (A.D. 1000-1025) who (Sachau's Alberuni, I. 173 II. 167) used the Karnāṭa alphabet. The presence of Karnāṭa rulers in Nepāl in the ninth and tenth centuries remains a puzzle. But the use of the term Karnāṭa for Chalukyas of Kalyāṇ in A.D. 1000 (Ep. Ind. I. 230) suggests that the Nepāl chiefs were Chalukyas rather than Rāshtrakūṭas while Mahmūd Ghaznavi's Karnāṭas may naturally be traced to the mercenary remains of Trappa's army of Kalyāṇ Chalukyas whose general Bārappa was slain (Ras. Malis, I. 51) and his followers dispersed in north Gujarāt by Māla Rāja Solanki at the close of the tenth century. The only recorded connection of the southern Rāshtrakūṭas with Northern India during the middle ages (A.D. 750-1150) are their intermarriages

सिंहवर्मा - सुद्धि  
सोमवर्मा - सुद्धि

Citankya

**Chapter XI.**  
**THE**  
**RĀSHTRAKŪṬAS,**  
**A.D. 743-974.**

as late as the twelfth century, and further is the North Indian name Rāthod not tribal but derived from the title head of a district. Several considerations make both of these solutions unlikely if not impossible. First there is the remarkably widespread existence of the name Rāthor, Ratha, or Ratti, and endless variations of these names, in almost all parts of the Panjāb, among all castes from the Brāhman to the Baluch, among all religions Musalmān, Sikh, Jain, and Brāhmanic.<sup>1</sup> No doubt the practice of a waning tribe adopting the name of a waxing tribe has always been common. No doubt also the fame of the name during the last 600 years must have tempted other classes to style themselves Rāthod. Still it is to be noted first that (Ibbetson, page 240) the Rāthods of the Panjāb though widespread are not numerous; and second that the list of sub-caste names has this merit that with a few exceptions the holders of the sub-name are not known by it but by some general or craft name. The evidence of these 'sub-caste' or tribal names seems therefore to support the view that some very large section of the Panjāb population represent an important tribe or nation of whom the least mixed remnant are perhaps the Rāthas or lower class Rājputs of Kangra and Chamba (Ibbetson, pages 219 and 251) and from some connection with whom the Marwār Rāthods of the thirteenth century may have taken their name. Among other traces of northern Rāshtrakūṭas in the middle ages may be mentioned the twelfth and thirteenth century Rāshtrakūṭas of Bajaur in the North-West Provinces (Kielhorn in *Epigraphia Indica*, I 61 and 63) and (A.D. 1150) in the Kumarapala-Charitra (Tod's *Western India*, 182) the mention of Rāshtrakūṭa near the Sawālik hills. Among earlier and more doubtful references are the Aratrii whom probably correctly (since at that time A.D. 247 one main Roman trade route to Central Asia passed up the Indus) the author of the *Periplus* (McCrindle, 120) places between Abdura or lower Sindh and Arachosia or south-east Afghanistan that is in north Sindh or south Panjāb. Another earlier and still more doubtful reference is Ptolemy (A.D. 77) Orature (*Hist. Nat.* VI 23) whom Vivien de St. Martin (*Geog. Grecque et Latine de l'Inde*, 203) identifies with the Rāthods. The fact that while claiming descent from Rāma the Marwār Rāthods (Tod's *Annals*, II, 2 and 5) preserve the legend that their founder was Yavanaśwa from the northern city of Parahpur supports the view that the tribe to which they belonged was of non-Indian or Central Asian origin, and that this is the tribe of whom traces remain in the Rāth Rājputs of the Kangra hill country and less purely in the widely spread Rāts, Rāttas, and Rātis of the Panjāb plains. The examples among Panjāb caste names Rora for Arora (Ibbetson's 1851 Census, page 297), Her for Ahir (Ditto, 230-275), and Her for Ahir (Ditto, 310) suggest that the Panjāb Rāthods or Rāttas may be the ancient Aratrii whom the *Mahābhārata* (Chap. VII Verse 11. J. Bl. Soc. VI. Pt. I 357 and Vivien de St. Martin *Geog. Grecque et Latine de l'Inde*, 149) ranks with Prasthalis, Madras, and Gandharas, Panjāb and frontier tribes, whose identification with the Babakas (Karnajevan, 2063ff.) raises the probability of a common Central Asian origin. Remembering that the evidence (*Kshatrapa* Chapter, pages 22 and 33) favours the view that the Kshatrapa family who ruled the Panjāb between B.C. 70 and A.D. 78 were of the same tribe as Nahapana, and also that Shahn is so favourite a prefix in Samudra Gupta's (A.D. 380) list of Kushān tribes, the suggestion may be offered that Kshaharata is the earlier form of Shāharatta and is the tribe of foreigners afterwards known in the Panjāb as Arattas and of which traces survive in the present widespread tribal names Rāta, Ratta, Ratha, and Rāthor.]

with the Pādās of Benares (A.D. 850-1000) mentioned above (Page 132 Note 1), and, between A.D. 880 and 950, with the Kalachuris of Tūpura near Jabalpur (Cunningham's *Arch. Survey Report* for 1891, IX. 40)

<sup>1</sup> The details compiled from the excellent index and tables in the Panjāb Census yield the following leading groups: 37 sub-castes named Rāthor, Rator, and other close variants; 53 Rāth and Rāthis and 2 Rāttas, 50 Rātas, Rātin, or other close variants. Compare Rāthi the name of the people of Moum Abu (*Rajputana Gazetteer*, III, 189) and the Rāth tract in the north-west of Ahar (Ditto, 167).

## CHAPTER XII.

## THE MIHIRAS OR MERS.

A.D. 470-900.

THAT the Guptas held sway in Kāthiāvāda till the time of Skandagupta (A.D. 451-470) is proved by the fact that his Sorath Viceroy is mentioned in Skandagupta's inscription on the Gurnār rock. After Skandagupta under the next known Gupta king Budhagupta (Gupta 165-180, A.D. 451-470) no trace remains of Gupta sovereignty in Sorath. It is known that Budhagupta was a weak king and that the Gupta kingdom had already entered on its decline and lost its outlying provinces. Who held Surāshtra and Gujarāt during the period of Gupta decline until the arrival and settlement of Bhātākāka in A.D. 514 (Gupta 195) is not determined. Still there is reason to believe that during or shortly after the time of Budhagupta some other race or dynasty overthrew the Gupta Viceroy of these provinces and took them from the Guptas. These powerful conquerors seem to be the tribe of Maṭrakas mentioned in Valabhi copperplates as people who had settled in Kāthiāvāda and established a *mandala* or kingdom. Though these Maṭrakas are mentioned in no other records from Surāshtra there seems reason to identify the Maṭrakas with the Mihiras the well-known tribe of Mhers or Mers. In Sanskrit both *mītra* and *mihira* are names of the sun, and it would be quite in agreement with the practise of Sanskrit writers to use derivatives of the one for those of the other. These Mhers or Mers are still found in Kāthiāvāda settled round the Barda hills while the Porbandar chiefs who are known as Jethvās are recognized as the head of the tribe. The name Jethvā is not a tribal but a family name, being taken from the proper or personal name of the ancestor of the modern chiefs. As the Porbandar chiefs are called the kings of the Mhers they probably belong to the same tribe, though, being chiefs, they try, like other ruling families, to rank higher than their tribe tracing their origin from Hanumān. Though the Jethvās appear to have been long ashamed to acknowledge themselves to belong to the Mher tribe the founders of minor Mher kingdoms called themselves Mher kings. The Porbandar chiefs have a tradition tracing their dynasty to Makaradhvaja son of Hanumān, and there are some Purāṇik legends attached to the tradition. The historical kernel of the tradition appears to be that the Mhers or Jethvās had a *makara* or fish as their flag or symbol. One of the mythical stories of Makaradhvaja is that he fought with Mayūradhvaja. Whatever coating of fable may have overlaid the story, it contains a grain of history. Mayūradhvaja stands for the Guptas whose chief symbol was a peacock *mayūra*, and with them Makaradhvaja that is the people with the fish-symbol that is

## Chapter XII.

THE MHERS,  
A.D. 470-900.

## Chapter XII.

THE MHERS,  
A.D. 470-900.

the Mhers had a fight. This fight is probably the historical contest in which the Mhers fought with and overthrew the Gupta Viceroy of Káthiávāda.

The Káthiávāda Mhers are a peculiar tribe whose language dress and appearance mark them as foreign settlers from Upper India. Like the Málavas, Játs, Gurjaras, and Pahlavas, the Mhers seem to have passed through the Punjáb Sindh and North Gujarát into Káthiávāda leaving settlements at Ajmír, Bádner, Jesalmír, Kokalmír, and Mhervāda. How and when the Mhers made these settlements and entered Káthiávāda is not known. It may be surmised that they came with Toramāṇa (A.D. 470-512) who overthrew the Guptas, and advanced far to the south and west in the train of some general of Toramāṇa's who may perhaps have entered Suráshtra. This is probable as the date of Toramāṇa who overthrew Budhagupta is almost the same as that of the Maitrakas mentioned as the opponents and enemies of Bhatárka. In the time of Bhatárka (A.D. 509-520?) the Mhers were firmly established in the peninsula, otherwise they would not be mentioned in the Valabhi grants as enemies of Bhatárka, a tribe or *maṇḍala* wielding incomparable power. As stated above in Chapter VIII, some time after the Mher settlement and consolidation of power, Bhatárka seems to have come as general of the fallen Guptas through Málwa and Broach by sea to East Káthiávāda. He established himself at Valabhi and then gradually dislodged the Mhers from Sorath until they retired slightly to the north settling eventually at Morbi, which the Jethvās still recognize as the earliest seat of their ancestors. At Morbi they appear to have ruled contemporarily with the Valabhis. In support of this it is to be noted that no known Valabhi plate records any grant of lands or villages in Hálár, Machbukántha, or Okhánandal in North Káthiávāda. As the north-most place mentioned in Valabhi plates is Venuthali known as Wania's Vantali in Hálár it may be inferred that not the Valabhis but the Mhers ruled the north coast of Káthiávāda, probably as feudatories or subordinates of the Valabhis. On the overthrow of Valabhi about A.D. 770 the Mhers appear to have seized the kingdom and ruled the whole of Káthiávāda dividing it into separate chiefships grouped under the two main divisions of Bardái and Gohelvāda. About A.D. 860 the Mhers made incursions into Central Gujarát. A copperplate dated Śaka 789 (A.D. 847) of the Gujarát Ráshtrakúta king Dhruva describes him as attacked by a powerful Mihira king whom he defeated.<sup>1</sup> At the height of their power the Mhers seem to have established their capital at the fort of Bhumli or Ghumli in the Bardái hills in the centre of Káthiávāda. The traditions about Ghumli rest mainly on modern Jethvā legends of no historical interest. The only known epigraphical record is a copperplate of a king named Jāchikadeva found in the Morbi district.<sup>2</sup> Unfortunately only the second plate remains. Still the fish mark on the plate, the locality where it was found, and its date

<sup>1</sup> Ind. Ant. XII, 179.

<sup>2</sup> Ind. Ant, II, 257.

leave little doubt that the plate belongs to the Makaradhvaja or Jethvá kings. The date of the grant is 585 Gupta era the 5th Phálguna Sudi that is A.D. 901, about 130 years after the destruction of Valabhi, a date with which the form of the letters agrees.

A similar copperplate in which the king's name appears in the slightly different form Jáikadeva has been found at Dhiniki in the same neighbourhood as the first and like it bearing the fish mark.<sup>1</sup> This copperplate describes the king as ruling at Bhūmlika or Bhūmli in Sorath and gives him the high titles of Paramabhāṭṭāraka-Mahārājādhirāja-Paramesvara, that is Great Lord Great King of Kings Great King, titles which imply wide extent and independence of rule. This grant purports to be made on the occasion of a solar eclipse on Sunday Vikrama Samvat 794 Jyeshtha constellation, the no-moon of the second half of Kartika. This would be A.D. 738 or 166 years before the Jáchuka of the Morbi plate. Against this it is to be noted that the letters of this plate, instead of appearing as old as eighth century letters, look later than the letters of the tenth century Morbi plate. As neither the day of the week, the constellation, nor the eclipse work out correctly Dr. Bhagvanlál believed the plate to be a forgery of the eleventh century, executed by some one who had seen a fish-marked copperplate of Jáchuka dated in the *Saka* era. It should however be noted that the names of ministers and officers which the plate contains give it an air of genuineness. Whether the plate is or is not genuine, it is probably true that Jáikadev was a great independent sovereign ruling at Bhūmli. Though the names of the other kings of the dynasty, the duration of the Bhūmli kingdom, and the details of its history are unknown it may be noted that the dynasty is still represented by the Porbandar chiefs. Though at present Bhūmli is deserted several ruined temples of about the eleventh century stand on its site. It is true no old inscriptions have been found; it is not less true that no careful search has been made about Bhūmli.

Early in the tenth century a wave of invasion from Sindh seems to have spread over Kacch and Káthiaváda. Among the invading tribes were the Jádejás of Kacch and the Chúdásamás of Sorath, who like the Bhattis of Jesalmír call themselves of the Yaduvamśa stock. Doctor Bhagvanlál held that the Chúdásamás were originally of the Abhíra tribe, as their traditions attest connexion with the Abhíras and as the description of Graharipu one of their kings by Hemachandra in his *Dvyáraya* points to his being of some local tribe and not of any ancient Rájput lineage. Further in their bardic traditions as well as in popular stories the Chúdásamás are still commonly called Abera-ráuás. The position of Aberia in Ptolemy (A.D. 150) seems to show that in the second century the Ahíras were settled between Sindh and the Panjáb. Similarly it may be suggested that Jádejá is a corruption of Jandhejá which

## Chapter XII.

THE MERS,  
A.D. 170-900.

<sup>1</sup> Ind. Ant. XII. 151.

**Chapter XII.**

THE MERS,  
A.D. 470-800.

in turn comes from Yandheya (the change of *y* to *j* being very common) who in Kshatrapa Inscriptions appear as close neighbours of the Ahirs. After the fall of the Valabhis (A.D. 775) the Yandheyas seem to have established themselves in Kacch and the Ahirs settled and made conquests in Káthiávāda. On the decline of local rule brought about by these incursions and by the establishment of an Ahir or Chúdásamā kingdom at Junágadh, the Jethváś seem to have abandoned Bhūmli which is close to Junágadh and gone to Srinagar or Kāntelun near Porbandar which is considered to have been the seat of Jethvá power before Porbandar.

A copperplate found at Haddálá on the road from Dholka to Dhandhuka dated A.D. 917 (Śaka 839) shows that there reigned at Vadhvān a king named Dharañivarāha of the Chápa dynasty,<sup>1</sup> who granted a village to one Mahesvarácharya, an apostle of the Amardáka Śákhá of Saivism. Dharañivarāha and his ancestors are described as feudatory kings, ruling by the grace of the feet of the great king of kings the great lord the illustrious Mahípádeva. This Mahípála would seem to be some great king of Káthiávāda reigning in A.D. 917 over the greater part of the province. Dr. Bhagvánlál had two coins of this king of about that time, one a copper coin the other a silver coin. The coins were found near Junágadh. The copper coin, about ten grains in weight, has one side obliterated but the other side shows clearly the words Ráná Śrī Mahípála Deva. The silver coin, about fourteen grains in weight, has on the obverse a well-executed elephant and on the reverse the legend Ráná Śrī Mahípála Deva. From the locality where the name Mahípála appears both in coins and inscriptions, and from the fact that the more reliable Chúdásamā lists contain similar names, it may be assumed as probable that Mahípála was a powerful Chúdásamā ruler of Káthiávāda in the early part of the tenth century.

After the fall of Valabhi no other reliable record remains of any dynasty ruling over the greater part of Gujarat. The most trustworthy and historical information is in connection with the Chávadās of Ayahulpura. Even for the Chávadās nothing is available but scant references recorded by Jain authors in their histories of the Solankis and Vághelās.

The Chúdásamās,  
A.D. 900-940.

[The modern traditions of the Chúdásamā clan trace their origin to the Yádava race and more immediately to the Samma tribe of Nagar Thattha in Sindh.<sup>2</sup> The name of the family is said to have been derived from Chúdáchandra the first ruler of Vanthalí

<sup>1</sup> The inscription calls Chápa the founder of the dynasty. The name is old. A king Vyághrarāja of the Chápa Vamśa is mentioned by the astronomer Brahmagupta as reigning in Śaka 550 (A.D. 628) when he wrote his book called *Brahma-Gupta Siddhanta*. The entry runs "In the reign of Śrī Vyághramukha of the Śrī Chápa dynasty, five hundred and fifty years after the Śaka king having elapsed." *Jour. B. B. R. A. Soc.* VIII. 27. For Dharañivara's grant see *Ind. Ant.* XII. 190ff.

<sup>2</sup> Elliot's History, I. 266.

(Káthiáwár Gazetteer, 489). Traces of a different tradition are to be found in the Tuhfat-ul-Kirám (Elliot, I. 837) which gives a list of Chúdásammá's ancestors from Nuh (Noah), including not only Krishna the Yáduva but also Ráma of the solar line. In this pedigree the Musalmán element is later than the others: but the attempt to combine the solar and lunar lines is a sure sign that the Samma clan was not of Hindu origin, and that it came under Hindu influence fairly late though before Sindh became a Musalmán province. This being admitted it follows that the Sammas were one of the numerous tribes that entered India during the existence of the Turkish empire in Transoxiana (A.D. 560 - c. 750). In this connection it is noteworthy that some of the Jáms bore such Turkish names as Tardíchi, Tughhk, and Sanjár.

The migration of the Sammas to Kacch is ascribed by the Tarikh-i-Tahiri (A.D. 1621) to the tyranny of the Súmra chiefs. The Sammas found Kacch in the possession of the Cháwaras, who treated them kindly, and whom they repented by seizing the fort of Gúntri by a stratagem similar to that which brought about the fall of Gurná.

The date of the Chúdásamá settlement at Vanthalí is usually fixed on traditional evidence, at about A.D. 875, but there is reason to think that this date is rather too early. In the first place it is worthy of notice that Chúdáchandra, the traditional eponym of the family, is in the Tuhfat-ul-Kirám made a son of Jádan (Yádava) and only a great-grandson of Krishna himself, a fact which suggests that, if not entirely mythical, he was at all events a very distant ancestor of Mularája's opponent Grahári, and was not an actual ruler of Vanthalí. As regards Grahári's father Visvavaraha and his grandfather Mularája, there is no reason to doubt that they were real persons, although it is very questionable whether the Chúdásamás were settled in Káthiáváda in their time. In the first place, the Morbi grant of Jákadéva shows that the Jethvás had not been driven southwards before A.D. 907. Secondly Dharanivaráha's Vadhvái grant proves that the Chápa family of Bhímál were still supreme in Káthiáváda in A.D. 914: whereas the Tarikh-i-Tahiri's account of the Chúdásamá conquest of Kacch implies that the Cháwaras, who must be identified with the Chápas of Bhímál, were losing their power when the Chúdásamás captured Gúntri, an event which must have preceded the settlement at Vanthalí in Káthiáváda. Beyond the fact that Mularája Solanki transferred the capital to Anahilaváda in A.D. 942, we know nothing of the events which led to the break-up of the Bhímál empire. But it is reasonable to suppose that between A.D. 920 and 940 the Chávas gradually lost ground and the Chúdásamás were able first to conquer Sindh and then to settle in Káthiáváda. — A. M. T. J.]

[Káthiáváda contains three peculiar and associated classes of Hindus, the Mers, the Jethvás, and the Jhálás. The Mers and the Jethvás stand to each other in the relation of vassal and lord. The Jhálás are connected with the Jethvás by origin history and alliance. The bond

## Chapter XII.

THE MERS,  
A.D. 470 - 900.

The Chúdásamás,  
A.D. 900 - 940.

## Chapter XII.

THE MERS,  
A.D. 470-900.  
The Jethvās

of union between the three classes is not only that they seem to be of foreign that is of non-Hindu origin, but whether or not they belong to the same swarm of northern invaders, that they all apparently entered Kāthiāvāda either by land or sea through Sindh and Kacch. So far as record or tradition remains the Mers and Jethvās, reached Kāthiāvāda in the latter half of the fifth century after Christ, and the Jhālās, and perhaps a second detachment of Mers and Jethvās, some three hundred years later.<sup>1</sup> The three tribes differ widely in numbers and in distribution. The ruling Jethvās are a small group found solely in south-west Kāthiāvāda.<sup>2</sup> The Jhālās, who are also known as Makvanas, are a much larger clan. They not only fill north-east Kāthiāvāda, but from Kāthiāvāda, about A.D. 1500, spread to Rajputāna and have there established a second Jhālāvāda,<sup>3</sup> where, in reward for their devotion to the Sesodia Rāja of Mewāl in his struggles with the Emperor Akbar (A.D. 1580-1606), the chief was given a daughter of the Udepur family and raised to a high position among Rajputs.<sup>4</sup> The Mers are a numerous and widespread race. They seem to be the sixth to tenth century Medhs, Meds, Mamls or Mins of Baluchistan, South-Sindh, Kacch, and Kāthiāvāda.<sup>5</sup> Further they seem to be the Mers of Mevāda or Medajetha in Rajputāna<sup>6</sup> and of Mairvāda in Mālava,<sup>7</sup> and also to be the Musalmān Meos and Minas of Northern India.<sup>8</sup> In Gujarāt

<sup>1</sup> According to the Kathiawan Gazetteer pages 110 and 278, the first wave reached about A.D. 650 and the second about 250 years later. Dr. Bhagvanlal's identification of the Mers with the Matrakas would take back their arrival in Kathiavada from about A.D. 650 to about A.D. 400. The Mers were again formidable in Gujarat in the late ninth and early tenth centuries. In A.D. 867 (see above Pages 127 and 130) the Rashtrakūta Dhruva II. checked an invasion of a Mihra king with a powerful army. Again in A.D. 911 the Rashtrakūta Indra III. in a moment uprooted the Mehr (Ditto).

<sup>2</sup> The Amra-Akbari (Gladwin, II. 69) notices that the sixth division of Saurashtra, which was almost impervious by reason of mountain rivers and woods, was (A.D. 1580) inhabited by the tribe Chetore that is Jethwa.

<sup>3</sup> Of the Jhālās or Chhalās the Amra-Akbari (Gladwin, II. 61) has, Chhalawarch (in north-east Kathiavada) formerly independent and inhabited by the tribe of Chhalah.

<sup>4</sup> Tod's Annals of Rajasthan, II. 113.

<sup>5</sup> Elliot and Dowson, I. 114 and 519-531. It is noted in the text that to the Arab invaders of the eighth and ninth centuries the Medhs of Hind were the chief people of Kathiavada both in South in the south and in Māhā in the north. They were as famous by sea as by land. According to Beloduri (A.D. 950) Reinand's Memoire sur l'Inde, 234-235) the Medys of Saurashtra and Kacch were sailors who lived on the sea and sent fleets to a distance. Ibbekhruladha (A.D. 912) and Idrisi (A.D. 1120), probably from the excellent Ahljevhasi (Reinand's Abulfeda, lxiii, and Elliot, I. 79), have the form Mand. Elliot, I. 11. The form Mand survives in a musical mode popular in Rajputāna, which is also called Rajewār. The Mand is like the Central Asian Mus-tazad (K. S. Fazullah Lutfallah.)

<sup>6</sup> Indian Antiquary, VI. 191.

<sup>7</sup> Rajputāna Gazetteer, I. 11.

<sup>8</sup> Rajputāna Gazetteer, I. 66; North-West Province Gazetteer, III. 265; Ibbetson's Punjab Census page 261. Some of these identifications are doubtful. Dr. Bhagvanlal in the text (21 Note 6 and 33) distinguishes between the Mevas or Medas whom he identifies as northern immigrants of about the first century B.C. and the Mers. This view is in agreement with the remark in the Rajputāna Gazetteer, I. 66 that the Mers have been suspected to be a relic of the Indo-Skythian Meds. Again Tod (Annals of Rajasthan, I. 9) derives Mevāda from *mudhya* (Sk.) middle, and the Mer of Merwāda from *meru* a hill. In support of Tod's view it is to be noted that the forts Balmer Jesalmer Komalmer and Ajmer, which Pandit Bhagvanlal would derive from the personal names of Mer leaders, are all either hill forts or rocks (Annals, I. 11, and Note 4). It is, on the other hand, to be noted that no hill forts out of this particular tract of country are called Mers, and that the similar names Koh and Malava, which with equal probability as Medh might be derived from Koh and Mala hill, seem to be tribal not geographical names.

their strength is much greater than the 30,000 or 40,000 returned as Mers. One branch of the tribe is hidden under the name Koli; another has disappeared below the covering of Islām.<sup>1</sup>

Formerly except the vague contention that the Melhās, Jhetvās, and Jhāla-Makvánās were northerners of somewhat recent arrival little evidence was available either to fix the date of their appearance in Káthiávāda or to determine to which of the many swarms of non-Hindu Northerners they belonged.<sup>2</sup> This point Dr. Bhagvánlāl's remarks in the text go far to clear. The chief step is the identification of the Mers with the Matrakas, the ruling power in Káthiávāda between the decline of the Guptas about A.D. 470 and the establishment of Valabhi rule about sixty years later. And further that they fought at the same time against the same Hindu rulers and that both are described as foreigners and northerners favours the identification of the

## Chapter XII.

THE MERS,  
A.D. 470-900.

The Mers.

<sup>1</sup> The tales cited in the Ras Mela (I. 103) prove that most of the Kohs between Gujarat and Kathiavada are Mems. That till the middle of the tenth century the south-east of Káthiávāda was held by Medhs (Kath. Gazetteer, 672) supports the view that the Kohs, whom about A.D. 1190 (Tod's Western India, I. 265) the Gohls drove out of the island of Prām, were Medhs, and this is in agreement with Idnisi (A.D. 1130 Elia, I. 83) who calls both Prām and the Medhs by the name Mand. Similarly some of the Koh clans of Kacch (Gazetteer, 70) seem to be descended from the Medhs. And according to Mr. Dalpatram Khakim three subdivisions of Brahmacakshatis, of which the best known are the Mansura Mers and the Pipra Mers, maintain the surname Mar or Mer. (Cutch Gazetteer, 52 note 2.) Mera or Meria is a common surname among Sindhi Baluchis. Many of the best Musalman captains and pilots from Kathiavada, Kacch, and the Makran coast still have Mer as a surname. Mer is also a favourite name among both Khojās and Memans, the two special classes of Kathiavada converts to Islam. The Khojās explain the name as meaning Merh Ah the friend of Ah, the Memans also explain Mer as Merh or friend. But as among Memans Mer is a common name for women as well as for men the word can hardly mean friend. The phrase Merbat or Lady Mer applied to Meman mothers seems to have its origin in the Rajput practice of calling the wife by the name of her caste or tribe as Kathiwalai, Merambai. In the case both of the Khojās and the Memans the name Mer seems to be the old tribal name continued because it yielded itself to the uss of Islam. Merh, Mihr, and Mahar are also used as titles of respect. The Khant Kohs of Gumar, apparently a mixture of the Matrakas of the text and of a local hill tribe, still (Kathiawar Gazetteer, 142) honour their leaders with the name Mer explaining the title by the Gujarati *mar* the man bead in a rosary. Similarly in Malwa a Gurjara title is Mihr (Rajputana Gazetteer, I. 80) and in the Punjab Mahar (Gazetteer of Punjab, Gujrat, 51). And in Kacch the headman among the Bhairwāds, who according to some accounts are Gujjaras, is called Mir (Cutch Gazetteer, 81). Similarly among the Rabaris of Kacch the name of the holy she-camel is Māta Merl. (Ditto, 80.) All these terms of respect are probably connected with Mihra, Sun.

<sup>2</sup> Compare Tod (Western India, 420). Though enrolled among the thirty-six royal races we may assert the Jethvas have become Hindus only from locality and circumstance. Of the Jhālas Tod says (Rajasthan, I. 113). As the Jhālas are neither Sohar Lunar nor Agnikula they must be strangers. Again (Western India 411) The Jhāla Makvánās are a branch of Hūnas. Of the name Makvāna (Kathiawar Gazetteer, 111, Ras Mela, I. 207) two explanations may be offered, either that the word comes from Mak the dewy tracts in Central Kacch (Cutch Gazetteer, 75 note 2) where (Kathiawar Gazetteer, 420) the Jhālas stopped when the Mers and Jethvas passed south, or that Makvāna represents Mauna a Puranic name for the Hūnas (Wilson's Works, IV. 207). Tod's and Wilford's (Asiatic Researches, IX. 287) suggestion that Makvāna is Mahahuna is perhaps not phonetically possible. At the same time that the Makvānas are a comparatively recent tribe of northerners is supported by the ascendancy in the fourteenth century in the Himālayas of Makvánis (Hodgson's Essay, I. 397; Government of India Secretions XLVII. 54 and 119) who used the Indo-Skythian title Sāh (Ditto). With the Nepal Makvánis may be compared the Makpons or army-men the caste of the chief of Balistan or Little Tibet. Vigne's Kashmir, II. 258, 439.

## Chapter XII.

THE MERS,  
A.D. 470-900.  
White Hunas.

power of the Maitrakas with the North Indian empire of the Epthalites, Yethas, or White Hunas.<sup>1</sup>

Though the sameness in name between the Mihiras and Mihirakula (A.D. 508-530), the great Indian champion of the White Hunas, may not imply sameness of tribe it points to a common sun-worship.<sup>2</sup>

That the Multán sun-worship was introduced under Sassanian influence is supported by the fact (Wilson's *Ariana Antiqua*, 357) that the figure of the sun on the fifth century Hindu sun coins is in the dress of a Persian king: that the priests who performed the Multán sun-worship were called Magas; and by the details of the dress and ritual in the account of the introduction of sun-worship given in the Bhavishya Purāṇa.<sup>3</sup> That the Meyds or Mandas had some share in its introduction is supported by the fact that the Purāṇa names the third or Sudra class of the sun-worshippers Mandagas.<sup>4</sup> That the Meyds were associated with the Magas is shown by the mention of the Magas as Mihiragas.<sup>5</sup> The third class whom the Bhavishya Purāṇa associates with the introduction of sun-worship are the Mānas who

<sup>1</sup> The evidence in support of the statement that the Maitrakas and Hunas fought at the same time against the same Hindu rulers is given in the text. One of the most important passages is in the grant of Dhruvasena III. (Epig. Ind. I. 89 [A.D. 653-4]) the reference to Bhatarika the founder of Valabhi (A.D. 509-520) meeting in battle the matchless armies of the Maitrakas.

<sup>2</sup> Mr. Fleet (Epigraphia Indica, III. 327 and note 12) would identify Mihirakula's tribe with the Muktakas. More recent evidence shows that his and his father Toramana's tribe was the Juvlas. That the White Hunas or other associated tribes were sun-worshippers appears from a reference in one of Mihirakula's inscriptions (Corpus Inscriptionum Indicarum, III. 161) to the building of a specially fine temple of the sun, and from the fact that in Kushāṇi Mihirakula founded a city Mihirapūra and a temple to Mihreshwar. (Darmstadter in Journal Asiatique, X. 70. Fleet in Indian Antiquary, XV. 212-252.) Mihirakula's (A.D. 508-530) sun-worship may have been the continuance of the Kushāṇi (A.D. 50-150) worship of Mithra or Helios (Wilson's *Ariana Antiqua*, 357). At the same time the fact that Mihirakula uses the more modern form Mihir makes it probable (Compare Rawlinson's *Seventh Monarchy*, 284) that Mihirakula's sun-worship was more directly the result of the spread of sun-worship in Central Asia under the fiercely propagandist Sassanians Varāṇ V. or Behrām Gur (A.D. 420-440), and his successors Izdigerd II. (A.D. 440-457), and Perozes (A.D. 457-483). The extent to which Zoroastrian influence pervaded the White Hunas is shown by the Persian name not only of Mihirakula but of Kushnawaz (A.D. 470-490) the great emperor of the White Hunas the overthrower of Perozes. That this Indian sun-worship, which, at latest, from the seventh to the tenth century made Multán so famous was not of local origin is shown by the absence of reference to sun-worship in Multán in the accounts of Alexander the Great. Its foreign origin is further shown by the fact that in the time of Berni (A.D. 1020 Sachau's Edition, I. 119) the priests were called Maghas and the image of the sun was clad in a northern dress falling to the ankles. It is remarkable as illustrating the Hindu readiness to adopt priests of conquering tribes into the ranks of Brāhmanas that the surname Magha survives (Cutch Gazetteer, 62 note 2) among Shrināth Brāhmanas. These Maghas are said to have married Bhaga or Rajput girls and to have become the Brāhman Bhojaks of Dwarka. Even the Mandas who had Saka wives, whose descendants were named Mandagas, obtained a share in the temple ceremonies. (Reinaud's *Mémoire Sur l'Inde*, 393.

<sup>3</sup> Wilson's *Vishnu Purāṇa* Preface xxxix. in Reinaud's *Mémoire Sur l'Inde*, 391. Details are given in Wilson's Works, X. 381-385.

<sup>4</sup> Reinaud's *Mémoire Sur l'Inde*, 393; Wilson's Works, X. 382.

<sup>5</sup> The name Mihiraga is explained in the Bhavishya Purāṇa as derived from their ancestress a daughter of the sage Rigu or Rijvahva of the race named Mihira (Reinaud's *Mémoire Sur l'Inde*, 393; Wilson's Works, X. 382). The name Mihiraga suggests that the spread of sun-worship in the Panjāb and Sindh, of which the sun-worship in Multán, Sindh, Kāthiāwāḍa and Mewāḍ and the fire-worshipping Rajput and Sindh coins of the fifth and sixth centuries are evidence, was helped by the spread of Sassanian influence.

are given a place between the Magas and the Mands. The association of the Mānas with the Mihiras or Maitrakas suggests that Māna is Mauna a Purānik name for the White Hūyas.<sup>1</sup> That the Multān sun idol of the sixth and seventh centuries was a Hūya idol and Multān the capital of a Hūya dynasty seems in agreement with the paramount position of the Kais of Alor or Rori in the sixth century. Though their defeat by Yeshodharman of Mālwā about A.D. 540 at the battle of Karur, sixty miles east of Multān, may have ended Hūya supremacy in north and north-west India it does not follow that authority at once forsook the Hūyas. Their widespread and unchallenged dominion in North India, the absence of record of any reverse later than the Karur defeat, the hopelessness of any attempt to pass out of India in the face of the combined Turk and Sassanian forces make it probable that the Hūyas and their associated tribes, adopting Hinduism and abandoning their claim to supremacy, settled in west and north-west India. This view finds support in the leading place which the Hūyas and Hāra-Hūyas, the Maitrakas or Mers, and the Gurjaras hold in the centuries that follow the overthrow of the White Hūya empire. According to one rendering of Cosmas<sup>2</sup> (A.D. 525) the chief of Orrhotha or Sorath in common with several other coast rulers owed allegiance to Gollas, apparently, as is suggested at page 75 of the text, to Gulla or Mihirgulla the Indian Emperor of the White Hūyas. These details support the view that the Maitrakas, Mihiras, or Mers who in Cosmas' time were in power in Kāthiāwāda, and to whose ascendancy during the seventh and eighth centuries both the Chinese pilgrim Hsuen Tsiang (A.D. 612-610) and the Arab historians of Sindh bear witness, were a portion of the great White Hūya invasion (A.D. 480-530).<sup>3</sup> In the many recorded swarmings south from

## Chapter XII.

THE MERS,  
A.D. 470-900.  
White Hūyas.

into Baluchistan Kacch-Gandevi and other parts of western Sindh, through Sakastene the modern western Seistan near the lake Helmand. This Sakastene or land of the Sakas received its name from the settlement in it of one of the earlier waves of the Yuechi in the second or first century before Christ. The name explains the statement in the Bhavishya Purāna that sun-worship was introduced by Magas into Multān from Sakadvipa the land of the Sakas. In this connection it is interesting to note that Darmsteter (Zend Avesta, xxxiv.) holds that the Zend Avesta was probably completed during the reign of Shāhpur II (A.D. 309-379); that (lxxxix) Zend was a language of eastern Persia and early form of Pahlavi, and that (lxxxiv) western Seistan and the Helmand river valley the holy land of the Avesta the birth-place of Zoroastrianism and the scene of king Vishtasp's triumphs. A memory of the spread of this western or Sassanian influence remains in the reference in the Maṇuśrī-T-Tawārīkh in Elliot, I, 107-109, to the fire temples established in Kaudahil (Gandevi) and Buddha (Mansura) by Mahra a general of Bahman that is of Varahran V (A.D. 420-440). It seems probable that Mahra is Mehr the family name or the title (Rawlinson's Sassanian Monarchy, 224 note 4 and 312) of the great Mihran family of Persian nobles. The general in question may be the Mehr-Nases the minister of Varahran's son and successor Izdigerd II. (A.D. 440-457), who enforced Zoroastrianism in Armenia (Rawlinson, Ditto 305-308). Mehr's success may be the origin of the Indian stories of Varahran's visit to Mālwā. It may further be the explanation of the traces of fire temples and towers of silence noted by Pottinger (1810) in Baluchistan (Travels, 126-127) about sixty miles west of Khetat.

<sup>1</sup> Wilson's Works, IX, 207.

<sup>2</sup> Compare Priault's Embassies, 222.

<sup>3</sup> The White Hūyas overran Bakhtria and the country of the Yuechi between A.D. 450 and 460. About a hundred years later they were crushed between the advancing Turks and the Sassanian Chosroes I. or Naushirvān (A.D. 537-590). Rawlinson's Sassanian Monarchy, 420; Speer in Journal Asiatique (1883) Tom II, 349-350. The Hūyas supremacy in North India did not last beyond A.D. 530 or 540. The overthrow of their

## Chapter XII.

THE MEHS,  
A.D. 470-900.  
White Hūnas.

Central Asia into Persia and India no feature is commoner than the leading of the conquered by certain families of the conquering tribe. Chinese authorities place it beyond doubt that when, towards the middle of the fifth century A.D., the White Hūnas crossed the Oxus they found in power a cognate tribe of northerners whose date of settlement on the Indian frontier was less than a century old. This preceding swarm was the Yuán-Yuan, Var-Var, or Avār, who, about the close of the fourth century (A.D. 380), had driven from Balkh southwards into the Kabul valley Kitolo the last ruler of the long established Yuetchi (B.C. 50-A.D. 380).<sup>1</sup> It is known that in retreating before the Yuán-Yuán a division of the Baktrian Yuetchi, under the leadership of Kitolo's son, under the name of the Kidāras or Little Yuetchi, established their power in Gandhāra and Peshāwar.<sup>2</sup> This Kidāra invasion must have driven a certain share of the people of the Kabul valley to the east of the Indus. The invasion of the White Hūnas a century later, who were welcomed as allies by some of the Panjāb chiefs,<sup>3</sup> would cause fresh movements among the frontier tribes. The welcome given to the Hūnas, and the show and dash which marked their century of ascendancy in India and Persia, make it probable that as leaders they conducted south as far as Kāthiāwāda and Mālava large bodies of the earlier northern settlers. To which of the waves of earlier northerners the Medhs belonged is doubtful.<sup>4</sup> The view held by Pandit Bhagvānlāl that one branch of the Medhs entered India in the first century before Christ among the tribes of which the great Yuetchi were the chief is on the whole in agreement with General Cunningham's argument that Medus Hydaspes, Virgil's phrase for the Jhelum, proves that the Medhs were then (B.C. 40) already settled on its banks.<sup>5</sup>

supremacy perhaps dates from A.D. 540 the battle of Karur about sixty miles east of Multān, their conqueror being Yasodharman of Malwa the second of the three great Vikramādityas of Malwa. Of the Hūnas' position among Hindu castes Colonel Tod says: "The Hūnas are one of the Skyths who have got a place among the thirty-six races of India. They probably came along with the Kāthi, Bāla, and Makvāna of Samāshtra." Tod's Annals of Rajasthan, I. 110.

<sup>1</sup> Specht in Journal Asiatique (1883), II. 348.

<sup>2</sup> Specht in Journal Asiatique (1883), II. 349.

<sup>3</sup> Compare above Chapter VI, page 73 note 3.

<sup>4</sup> Dr. Bhagvānlāl (Text, 33) traces our set of Medhs to the Mevas the tribe of Ysamotika the father of the Kshatrapa Chastana (A.D. 130). He holds these Mevas entered India (21) with the Malayas, Pillayas, and Abhiras about B.C. 150 (?). At the same time he seems to have considered those early Mevas different from the fifth and sixth century Mihiras and from the seventh and eighth century Medhs.

<sup>5</sup> Arch. Report for 1863-64, II. 52. In support of this Cunningham cites Ptolemy's (A.D. 150) Enthymedia (that is Sagala, sixty miles north-west of Lahore, and the Media of Ptolemy's Tālish (A.D. 400). This Enthymedia is a corruption of the original Enthymedia the name given to Sagala by Demetrios (B.C. 190) the great Græco-Baktrian in honour of his father Enthymedon (Compare Text page 16 and McCrindle's Ptolemy, 124). Of the cause of this change of name, which may be only a clerical error, two different explanations have been offered. Tod (An. of Raju. I. 233) would make the new form Enthymedia the Middle Yuchi. Cunningham (Arch. Surv. Rep. II. 53) would attribute it to the southward migration towards Sindh about B.C. 50 of the Kshān-pressed horde which under Moas or Mogha came from Little Tibet and entered the Panjāb either by way of Kashmir or down the Swāt valley. According to General Cunningham (Ditto, 53) the followers of this Moas were Mandrueni called after the Mandrus river south of the Oxus. The two forms Medh and Mand are due to the cerebral which explains the Minnagaras of Ptolemy and the Periplus; Masudi's (A.D. 915) Mind and Ibn Khurdad-

Dr. Bhagvánlál's view that the Jethvās are Medhs ennobled by long overlordship is somewhat doubtfully shared by Colonel Watson<sup>1</sup> and is not inconsistent with Tod's opinions.<sup>2</sup> Still though the Hindu ruler-worship, which, as in the case of the Marátha Siváji, explains the raising to the twice-born of leaders of successful early and foreign tribes makes it possible that the Jethvās were originally Mers, it seems on the whole probable that the Jethvās' claim to an origin distinct from the Mers is well founded. The evidence recorded by Colonel Tod and the name Jethva led the late Dr. John Wilson to trace the Jethvās to the Játs or Jits.<sup>3</sup> According to the bards the name of the Káthiáwáda tribe Jethva is derived from Jetha No. 85 or No 95 of the Porbandar list, who was probably so called because he was born under the Jyeshtha constellation.<sup>4</sup> The common practice of explaining a tribal name by inventing some name-giving chief deprives this derivation of most of its probability.<sup>5</sup> In the present case it may further be noticed that the name Jethi is borne by two of the chiefs earlier than the Jetha referred to.<sup>6</sup> In the absence of any satisfactory explanation the name Jethva suggests an origin in Yetha, the shortened Chinese form of Ye-ta-i-li-to or Ephthalte the name of the ruling class of the White Húnas.<sup>7</sup> It is true that so good an authority as Specht holds that the shortened form Yetha is peculiar to the Chinese and was never in use. But the form Tetel or Haital, adopted by

## Chapter XII.

THE MERS,  
A.D. 470-900.  
White Húnas.

Wah's (ibid A.D. 912) and Idrisi's (perhaps from Adjayhání) Mand (Elliot, I. 14 and 79, Reinand's Abulfeda, I. 11); the present associated Mers and Muns in Rajputána (Ditto, 53), and perhaps the Musalmán Meos and Munas of the Pmjab (Ibbetson's Census, 261).

<sup>1</sup> The Jethvās are closely allied to the Medhs (Káth. Gaz. 138); they entered Káthiáwada along with the Medhs (Ditto, 278).

<sup>2</sup> The passages are somewhat contradictory. Tod (Western India, 113) says: Jethvas marry with Káthis, Ahirs, and Mers. In the Káthiáwár Gazetteer (page 110) Colonel Barton seems to admit the Jethvās' claim to be of distinct origin from the Mers. In another passage he says (page 188): The Mers claim to be Jethvas: thus the Jethvās deny. So also Colonel Watson in one passage (page 621) seems to favour a distinct origin while in another (page 279) he says: It seems probable the Jethvās are merely the ruling family Rájputa of the Mers and that they are all of one tribe. Two points seem clear. The Jethvās are admitted to rank among Káthiáwáda Rájputs and they formerly married with the Mers. The further question whether the Jethvas were originally of a distinct and higher tribe remains undetermined.

<sup>3</sup> Bombay Administration Report for 1873. Colonel Tod made the same suggestion: Western India, 256. Compare Le Strange's (Travels in Baluchistán, 61) identification of the Jeths of Kacch-Gandevi north of Khelat with Játs or Jits.

<sup>4</sup> Tod's Western India, 413.

<sup>5</sup> Compare Bühler in Epigraphia Indica, I. 291. Like the Chálukyas and other tribes the Jethvas trace the name Jethva to a name-giving chief. Of the Jethvās Tod says (Annals of Rajasthan, I. 111): The Jethvās have all the appearance of Skythian descent. As they make no pretension to belong to any of the old Indian races they may be a branch of Skythians. In his Western India (page 412), though confused by his identification of Káukha-ilwára with Sakotra instead of with Bet Dwarka (compare Káth. Gaz. 619), Tod still holds to a northern origin of the Jethvās.

<sup>6</sup> Nos. 6 and 82 of Colonel Watson's List, Káthiáwár Gazetteer, 621. The Pandit's evidence in the text ascribes to the somewhat doubtful Jaikadeva a date of A.D. 738 (Vikram 794); to Jáchikadeva a date of about A.D. 901 (Gupta 585); and to the Gúmli ruins a probable eleventh century. Tod (Western India, 417) traces the Jethvās further back putting the founding of Ghúmli or Bhúmli at about A.D. 692 (S 749) the date of a settlement between the Thars of Delhi and the Jethvās (Ditto, 411). Col. Watson (Káth. Gaz. 278) gives either A.D. 650 or A.D. 900.

<sup>7</sup> The form Yetha is used by the Chinese pilgrim Sung-ynn A.D. 519. Beal's Buddhist Records, I. xc.

<sup>8</sup> Journal Asiatique (1883), II. 319.

## Chapter XII.

THE MERS,  
A.D. 470-900.  
White Hūnas.

Jhālās.

Armenian Musalmān and Byzantine historians,<sup>1</sup> makes probable an Indian Yethāl or Jethāl if not a Yetha or Jetha. Nor does there seem any reason why Yetha the Chinese form of the word should not be more likely to be adopted in India than the western and otherwise less correct form Tetāl or Haithal. In any case the irregular change from a correct Yethāl to an incorrect Yetha cannot be considered of much importance, if, as seems likely, the change was made in order to give the word an Indian meaning.<sup>2</sup> The *r* in Jethva would come to be added when the origin from a chief named Jetha was accepted.

Another name for the White Hūnas, or for a section of the White Hūna swarm, is preserved by Cosmas<sup>3</sup> in the form *Jāvla*. This form, if it is not a mis-reading for *Omnia* or *Hūna*, suggests *Jāuvla* the recently identified name of the tribe ennobled in India by the great Toramāya (A.D. 450-500) and his son Māhurakula (A.D. 500-510), and of which a trace seems to remain in the *Jāwla* and *Jhāwla* divisions of Panjāb Gujjats.<sup>4</sup> This *Jāuvla*, under such a fire baptism as would admit the holders of the name among Hindus, might be turned into *Jvāla* flaming and *Jvāla* be shortened to *Jhāla*. That *Jhāla* was formerly punningly connected with flame is shewn by a line from the bard Chand, 'The lord of the Ramas the powerful *Jhāla* like a flaming fire.'<sup>5</sup> That the Kāthiāvada bands were either puzzled by the name *Jhāla* or were unwilling to admit its foreign origin is shewn by the story preserved in the *Ras Mālā*,<sup>6</sup> that the tribe got the name because the children of Hirpāl Makvana, about to be crushed by an elephant, were snatched away *jhāla* by their witch-mother. It has been noticed in the text that the break in Gujarāt History between A.D. 480 and 520, agreeing with the term of Hūna supremacy in North India, seems to imply a similar supremacy in Gujarāt. The facts that up to the twelfth century Hūnas held a leading place in Gujarāt chronicles,<sup>7</sup> and that while in Rājputāna and other parts of Northern India the traces of Huns are fairly widespread in Gujarāt they have almost if not altogether disappeared, support the view that the Hūna strain in Kāthiāvada is hid under the names Mera, Jethva, and *Jhāla*.<sup>8</sup>

<sup>1</sup> Journal Asiatique (1883), II. 311.

<sup>2</sup> Compare for the chief's name Jetha, Colonel Watson Kāth. Gaz. 622 in the Jyeshtha Nakshatra.

<sup>3</sup> Prank's Embassies, 220; Migne's Patrologie Cursus Vol. 88 page 98.

<sup>4</sup> Census of 1891 III. 116. A reference to the *Jhāuvlas* is given above page 75 note 4. General Cunningham (Ninth Oriental Congress, I. 228-244) traces the tribe of *Jhāuvla* ruling in Smthi, Zabulistan or Ghazni, and Makran from the sixth to the eighth and ninth centuries.

<sup>5</sup> Tod's Western India, 194 Note †. Tod adds: Chand abounds in such jeu-de-mot on the names of tribes.

<sup>6</sup> Ras Mālā, I. 302; Kāthiāwār Gazetteer, 111. <sup>7</sup> Tod's Annals of Rajasthan, I. 111.

<sup>8</sup> Among references to Hūnas may be noted: In the Vāyu Purāna (Suchau's Albefuni, I. 300) in the west between Kārnapravarma and Darva; in the Vishnu Purāna Hūnas between the Śaindhavas and the Salvās (Wilson's Works, VII. 183 and 184 Note †); in the eighth century Ungutsi lord of the Hūnas who helped Chitor (Tod's Annals, II. 457); in the Khichi bard Mogji, traditions of many powerful Hūna kings in India (Tod's Annals, I. 111 Note †) among them the Hūna chief of Barolli (Ditto, II. 705); and Raja Hūna of the Pramāra race who was lord of the Pathār or plateau of Central India (Ditto, II. 457).

In the Middle Ages the Húnas were considered Kshatriyas and Kshatriyas married Húna wives (Wilson's Works, VII. 134 Note †) Of existing traces in the Panjab may be noted Hon and Hona Rájputs and Gujjars, Hona Jats, Hon Labánas, Hon Lohars, Honi Malis, Hon Mochis, Húna Barbers, and Haun Rabáris (Panjab Census 1891. III. pages 116, 139, 227, 233, 246, 265, 276, 305, 315). The only traces Colonel Tod succeeded in finding in Gujarát were a few Húna huts at a village opposite Umetha on the gulf of Cambay, a second small colony near Somanatha, and a few houses at Trisanli five miles from Baroda. (Western India, 217, 323) Since 1825 these traces have disappeared.

Chapte

THE ————  
A.D. 490 - 900.



## PART II.

# THE KINGDOM OF ANAHILAVADA.

A.D. 720-1360

## CHAPTER. I.

### THE CHÁVADAS

(A.D. 720-956)

THE history embodied in the preceding chapters is more or less fragmentary, pieced together from coins, stone and copperplate inscriptions, local traditions, and other similar sources. A history based on such materials alone must of necessity be imperfect, leaving blanks which it may be hoped fresh details will gradually fill.

The rise of the Anahilaváda kingdom (A.D. 720) marks a new period of Gujarát history regarding which materials are available from formal historical writings.<sup>1</sup> Though this section of Gujarát history begins with the establishment of Anahilaváda by the Cháavadas (A.D. 720-956) the details for the earlier portions are very imperfect being written during the time of the Chálukya or Solanki (A.D. 957-1212) successors of the Cháavadas. The chief sources of information regarding the earlier period of Cháavadá rule are the opening chapters of the Prabandhachintámāni, Vichárasreni, Sukritasankirtana, and Ratnamálá.<sup>2</sup>

Before the establishment of Anahilaváda a small Cháavadá chiefship centred at Pañchásar, now a fair-sized village in Vadhiár between Gujarát and Kacch.<sup>3</sup> The existence of a Cháavadá chiefship at Pañchásar is proved by the Navamant dated Samvat 490 (A.D. 788-89) of the Gujarát Chálukya king Pulikeśi Janástraya. This grant in recording the triumphant progress of an army of Tájikas or Arabs

### Chapter I.

THE CHÁVADA  
A.D. 720-956.

Pañchásar,  
A.D. 788.

<sup>1</sup> The following manuscript histories have been used in preparing Part II. Hemachandra's Dvyasrayakavya, Merutunga's Prabandhachintámāni, Merutunga's Vichárasreni, Jhaprabhasúri's Tirthakalpā, Jnananandunopadhyaya's Kumarapala-prabandha, Kṛṣṇa-rishi's Kṛṣṇapala-charita, Kṛṣṇabhaṭṭa's Ratnamálá, Somasvara's Kirtikaumudí, Arisinha's Sukritasankirtana, Rájasekhara's Chaturvimsatiprabandha, Vasupálacharita, and published and unpublished inscriptions from Gujarát and Káthiaváda.

<sup>2</sup> The Prabandhachintámāni is a short historical compilation; the Vichárasreni, though a mere list of kings, is more reliable; the Ratnamálá is a poetic history with good descriptions and many fables taken from the Prabandhachintámāni, the Sukritasankirtana is a short work largely borrowed from the Vichárasreni.

<sup>3</sup> This is apparently Vriddhi Ahára or the Vriddhi Collectorate, probably called after one village or town of that name.

**Chapter I.**

THE CHÁVADÁS,  
A.D. 720-956.

PAÑCHÁSAR,  
A.D. 788.

from Sindh to Navsári and mentioning the kingdoms "afflicted" by the Arabs, names the Chávotakas next after the kings of Kacch and Sauráshtra. These Chávotakas can be no other than the Chávadáś of Pañchásar on the borders of Kacch. The Chávadáś of Pañchásar do not appear to have been important rulers. At the most they seem to have held Vadhiár and part of the north coast of Káthiaváda. Whatever be the origin of the name Chávadá, which was afterwards Sanskritised into the high-sounding Chápoṭkata or Strongbow, it does not seem to be the name of any great dynasty. The name very closely resembles the Gujaráti Chor (Prakrit Chautá or Choraṭá) meaning thieves or robbers; and Jávadá, which is a further corruption of Chávadá, is the word now in use in those parts for a thief or robber. Except the mention of the Chávotakas in the Navsári copperplate we do not find the Chávadáś noticed in any known contemporary Gujarát copperplates. For this reason it seems fair to regard them as unimportant rulers over a territory extending from Pañchásar to Anahilaváda.

Jaya'sekhara,  
A.D. 696.

The author of the Ratnamálá (c. 1230 A.D.) says that in A.D. 696 (S. 752) Jaya'sekhara the Chávadá king of Pañchásar was attacked by the Chalukya king Bhuvada of Kalyánakataka in Kanyákubja or Kanoj and slain by Bhuvada in battle. Before his death Jaya'sekhara, finding his affairs hopeless, sent his pregnant wife Rupasundarí to the forest in charge of her brother Sorapáda, one of his chief warriors. After Jaya'sekhara's death Rupasundarí gave birth to a son named Vanarāja who became the illustrious founder of Anahilaváda. It is hard to say how much truth underlies this tradition. In the seventh century not Chalukya but Pála kings flourished in Kanoj. No place of importance called Kalyánakataka is recorded in the Kanoj territory. And though there was a southern Chalukya kingdom with its capital at Kalyán, its establishment at Kalyán was about the middle of the eleventh not in the seventh century. Further the known Dakhan Chalukya lists contain no king named Bhuvada, unless he be the great Chalukya king Vijayádhitya (A.D. 696-733) also called Bhuvanásraya, who warred in the north and was there imprisoned but made his escape. The inference is that the author of the Ratnamálá, knowing the Solankis originally belonged to a city called Kalyán, and knowing that a Chalukya king named Bhuvada had defeated the Chávadáś may have called Bhuvada king of Kalyánakataka and identified Kalyánakataka with a country so well known to Puránik fame as Kanyákubja. This view is supported by the absence in the Prabandha-chintámáni and other old records of any mention of an invasion from Kanoj. It is possible that in A.D. 696 some king Bhuvada of the Gujarát Chálukyás, of whom at this time branches were ruling as far north as Kaira,<sup>1</sup> invaded the Chávadáś under Jaya'sekhara. Since traces of a Chávotaka kingdom remain, at least as late as A.D. 720; it seems probable that the destruction of Pañchásar was caused not by Bhuvada in A.D. 696, but in the Arab raid mentioned above whose date falls about A.D. 720.<sup>2</sup> About A.D. 720 may therefore be taken as the date

<sup>1</sup> See above page 103.

<sup>2</sup> See above page 109.

of the birth of Vanarāja. Merutunga the author of the *Prabandhachintāmaṇi* tells how Rupasundarī was living in the forest swinging her son in a hammock, when a Jain priest named Śīlaguṇasūri noticing as he passed royal marks on the boy bought him from his mother. The story adds that a nun named Vīramatī brought up the boy whom the *sādhu* called Vānarāja or the forest king. When eight years old, the priest employed Vanarāja to protect his place of worship from rats. The boy's skill in shooting rats convinced the priest he was not fit to be a *sādhu* but was worthy of a kingdom. He therefore returned the boy to his mother. These details seem invented by the Jains in their own honour. No mention of any such story occurs in the *Ratnamālā*.<sup>1</sup>

In the forests where Vanarāja passed his youth lived his maternal uncle Surapāla, one of Jayasēkhara's generals, who, after his sovereign's defeat and death, had become an outlaw. Vanarāja grew up under Surapala's charge. The *Prabandhachintāmaṇi* records the following story of the origin of Vanarāja's wealth. A Kanyakubja king married Mahīnakā the daughter of a Gujjarat king. To receive the proceeds of the marriage cess which the Gujjarat king had levied from his subjects, a deputation or *punchkūla* came from Kanyakubja to Gujjarat. The deputation made Vanarāja their leader or *śaṭṭhat* to realize the proceeds of the cess. In six months Vanarāja collected 24 lakhs of *Pārutthu drammas*<sup>2</sup> and 1000 horses, which the deputation took and started for Kanyakubja. Vanarāja waylaid and killed them, secured the money and horses, and remained in hiding for a year. With the wealth thus acquired Vanarāja enrolled an army and established his power assuming the title of king. He fixed the site of a capital which afterwards rose to be the great city of Anahilavāpa. The story of the choice of the site is the usual story of a hunted hare turning on the hounds showing the place to be the special nurse of strength and courage. Vanarāja is said to have asked a Bhārvaḍ or Shepherd named Anahila son of Śākhakī to show him the best site. Anahila agreed on condition that the city should be called by his name. Anahila accordingly showed Vanarāja the place where a hare had attacked and chased a dog. Though much in this tradition is fabulous the city may have been called after some local chief since it was popularly known as Anahilavāḍa (Sk. Anahilavāṭa) that is the place of Anahila. In the *Prabandhachintāmaṇi* Merutunga gives A.D. 716 (S. 802) as the date of the installation of Vanarāja, while in his *Vichārasreni* the same author gives A.D. 765 (S. 821 *Vasakha Śukla 2*) as the date of the foundation of the city. The discrepancy may be explained by taking A.D. 746 (S. 802) to refer to the date of Vanarāja's getting money enough to fix the site of his capital, and A.D. 765 (S. 821) to refer to the date of his installation in the completed Anahilavāḍa. Local tradition connects the date A.D. 716 (S. 802) with an image of Ganpati which is said to be as old as the establishment of the city and

## Chapter I.

THE CHAVADAS,  
A.D. 720-956.

Vanarāja,  
A.D. 720-780 (?).

Founding of  
Anahilavāpa,  
A.D. 746-765.

<sup>1</sup> In the *Satyapurakalpa* of his *Tirthakalpa*, Jinaprabhasūri tells an almost identical story of another king.

<sup>2</sup> This name often recurs in Jain works. These would seem to be Kshatrapa coins as Gadhoiva coins are simply called *drammas*.

**Chapter I.**

THE CUĀVADĀS,  
A.D. 720 - 956.  
Founding of  
Anahilavāda,  
A.D. 746 - 766.

to bear the date 802. But as the letters of the inscription on the image can be made out by ordinary readers they cannot have been inscribed at nearly so early a date as 802. A.D. 765 (S. 821), the year given in the Vichāraśreni, seems the more probable date for the installation as the Prabandhachintāmaṇi says that Vanarāja got himself installed at Anahilapura when he was about fifty. This accords with the date fixed on other grounds. 'Placing Vanarāja's birth at about A.D. 720 would make him 44 in A.D. 765 (S. 821) the date at which according to the Vichāraśreni he was formally installed as sovereign of Anahilavāda. Merutunga in both his works gives the length of Vanarāja's life at 109 and of his reign at sixty years. The figure 60 seems to mark the length of his life and not of his reign. So long a reign as sixty years is barely possible for a sovereign who succeeded late in life, and the 109 years of his life can hardly be correct. Taking Vanarāja's age at 45 when he was installed in A.D. 765 (S. 821) and allowing fifteen years more to complete the sixty years A.D. 780 (S. 836) would be the closing year of his reign.

Vanarāja's  
Installation.

The Prabandhachintāmaṇi narrates how generously Vanarāja rewarded those who had helped him in his adversity. His installation was performed by a woman named Śrī Devī of Kākara village whom in fulfilment of an early promise Vanarāja had taken to be his sister.<sup>2</sup> The story regarding the promise is that once when Vanarāja had gone with his uncle on a thieving expedition to Kākara village and had broken into the house of a merchant he by mistake dipped his hand into a pot of curds. As to touch curds is the same as to dine at a house as a guest, Vanarāja left the house without taking anything from it.<sup>3</sup> Hearing what had happened the merchant's sister invited Vanarāja as a brother to dinner and gave him clothes. In return Vanarāja promised if he ever regained his father's kingdom he should receive his installation as king at her hands.<sup>4</sup> Vanarāja chose as minister a Bania named Jāmā. The story is that while Vanarāja was looting with two others he came across a merchant Jāmā who had five arrows. Seeing only three enemies, Jāmā broke and threw away two of the arrows, shouting 'One for each of you.' Vanarāja admiring his coolness persuaded Jāmā to join his band and found him so useful that he promised to make him minister. From the absence of any reference to him in these and similar tales it is probable that his uncle Surapāla died before the installing of Vanarāja. Vanarāja is said to have built at Anahilavāda a Jain temple of Pañchāsarā Pārasnāth so called because the image was brought from the old settlement of Pañchāsar. Mention of this temple continues during the Solanki and Vaghela times.

His Image.

Vanarāja is said to have placed a bowing image of himself facing the image of Pārasnāth. The figure of Vanarāja is still shown at Sidhpur

<sup>1</sup> The text is 'Pañchāsaratavarashadesyah.'

<sup>2</sup> Probably Kākrej famous for its bullocks.

<sup>3</sup> Stories of thieves refraining from plundering houses where they have accidentally laid their hands on salt or millet are common.

<sup>4</sup> The making of the installation mark on the forehead is the privilege of the king's sister who gives a blessing and receives a present of villages.

and a woodcut of it is given by the late Mr. Forbes in his *Rās Málá*. It is clearly the figure of a king with the umbrella of state and a nimbus round the head and in the ears the long ornaments called *kundalas* noticed by Arab travellers as characteristic of the Balhara or Rāshtrakūṭa kings who were cotemporary with Vanarāja.<sup>1</sup> The king wears a long beard, a short waistcloth or *dhōṭi*, a waistband or *kummarband*, and a shoulder garment or *uparīṭa* whose ends hang down the back. Besides the earrings he is adorned with bracelets armlets and anklets and a large ornament hangs across the chest from the left shoulder to the right hip. The right hand is held near the chest in the act of granting protection and the left hand holds something which cannot be made out. By his side is the umbrella-bearer and five other attendants. The statue closely resembles the lifesize figure of a king of the Solanki period lying in the yard of a temple at Māhā about twenty-four miles north of Somanātha Patan. At Somanātha Patan are similar but less rich cotemporary figures of local officers of the Solankis. Another similar figure of which only the torso remains is the statue of Anrāja the father of Vastupāla in a niche in Vastupāla's temple at Ginnar. The details of this figure belong to the Solanki period.

The lists of Vanarāja's successors vary so greatly in the names, in the order of succession, and in the lengths of reigns, that little trust can be placed in them. The first three agree in giving a duration of 196 years to the Chavadá dynasty after the accession of Vanarāja. The accession of the Solanki founder Mularāja is given in the *Vichāras'repi* at Samvat 1017 and in the *Prabandhachintāmaṇi* at Samvat 998 corresponding with the original difference of nineteen years (S. 802 and 821) in the founding of the city. This shows that though the total duration of the dynasty was traditionally known to be 196 years the order of succession was not known and guesses were made as to the duration of the different reigns. Certain dates fixed by inscriptions or otherwise known to some compilers and not known to others caused many discrepancies in the various accounts.

According to the calculations given above Vanarāja's reign lasted to about A.D. 780. Authorities agree that Vanarāja was succeeded by his son Yogarāja. The length of Yogarāja's reign is given as thirty-five years by the *Prabandhachintāmaṇi* and the *Ratnamālā* and as twenty-one by the *Vichāras'repi*. That is according to the *Prabandhachintāmaṇi* and *Ratnamālā* his reign closes in A.D. 841 (S. 897) and according to the *Vichāras'repi* in A.D. 836 (S. 891). On the whole the *Prabandhachintāmaṇi* date A.D. 841 (S. 897) seems the more probable. The author of the *Vichāras'repi* may have mistaken the 7 of the manuscripts for a 1, the two figures in the manuscripts of that date being closely alike. If A.D. 780 is taken as the close of Vanarāja's reign and A.D. 806 as the beginning of Yogarāja's reign an interval of twenty-six years is left. This blank, which perhaps accounts for the improbably long reign and life assigned to Vanarāja, may have been filled by the forgotten reign of a childless elder brother of Yogarāja.

## Chapter I

THE  
CHAVADAS  
A.D. 720-956  
Image of  
Vanarāja

Vanarāja's  
Successors,  
A.D. 780-961

Yogarāja,  
A.D. 806-841

<sup>1</sup> Elliot and Dowson, I. 11.

**Chapter I.**

THE CHĪVADĀS  
A.D. 720 - 956.

Yogarāja,  
A.D. 806 - 814.

Of Yogarāja the Prabandhachintāmaṇi tells the following tale. Kshemarāja one of Yogarāja's three sons reported that several ships were storm-stayed at Prabhāsa or Somanātha. The ships had 10,000 horses, many elephants, and millions of money and treasure. Kshemarāja prayed that he might seize the treasure. Yogarāja forbid him. In spite of their father's orders the sons seized the treasure and brought it to the king. Yogarāja said nothing. And when the people asked him why he was silent he answered: To say I approve would be a sin; to say I do not approve would annoy you. Hitherto on account of an ancestor's misdeeds we have been laughed at as a nation of thieves. Our name was improving and we were rising to the rank of true kings. This act of my sons has renewed the old stain. Yogarāja would not be comforted and mounted the funeral pyre.

Kshemarāja,  
A.D. 841 - 880.

According to the Prabandhachintāmaṇi in A.D. 841 (S. 898) Yogarāja was succeeded by his son Kshemarāja. The Vichāras'reṇi says that Yogarāja was succeeded by Ratnāditya who reigned three years, and he by Vairisimha who reigned eleven years. Then came Kshemarāja who is mentioned as the son of Yogarāja and as coming to the throne in A.D. 849 (S. 905). The relationship of Yogarāja to Ratnāditya and Vairisimha is not given. Probably both were sons of Yogarāja as the Prabandhachintāmaṇi mentions that Yogarāja had three sons. The duration of Kshemarāja's reign is given as thirty-nine years. It is probable that the reigns of the three brothers lasted altogether for thirty-nine years, fourteen years for the two elder brothers and twenty-five years for Kshemarāja the period mentioned by the Prabandhachintāmaṇi. Accepting this chronology A.D. 880 (S. 936) will be the date of the close of Kshemarāja's reign.

Chāmunda,  
A.D. 880-908.

According to the Vichāras'reṇi and the Sukritasankīrtana Kshemarāja was succeeded by his son Chāmunda. Instead of Chāmunda the Prabandhachintāmaṇi mentions Bhūyada perhaps another name of Chāmunda, as in the Prabandhachintāmaṇi the name Chāmunda does not occur. The Prabandhachintāmaṇi notes that Bhūyada reigned twenty-nine years and built in Anahilavāda Patan the temple of Bhūyadeshyar. The Vichāras'reṇi gives twenty-seven years as the length of Chāmunda's reign an insignificant difference of two years. This gives A.D. 908 (S. 964) as the close of Chāmunda's reign according to the Vichāras'reṇi.


Ghaghada,  
A.D. 908-937.

After Bhūyada the Prabandhachintāmaṇi places Vairisimha and Ratnāditya assigning twenty-five and fifteen years as the reigns of each. The Vichāras'reṇi mentions as the successor of Chāmunda his son Ghaghada who is called Rāhada in the Sukritasankīrtana. Instead of Ghaghada the Prabandhachintāmaṇi gives Sāmantasimha or Lion Chieftain perhaps a title of Ghaghada's. The Vichāras'reṇi gives Ghaghada a reign of twenty-seven years and mentions as his successor an unnamed son who reigned nineteen years. The Sukritasankīrtana gives the name of this son as Bhūbhata. According to these calculations the close of Ghaghada's reign would be A.D. 936 (Samvat 965 + 27 = 992). Adding nineteen years for Bhūbhata's reign brings the date of the end of the dynasty to A.D. 956 (Samvat

993 + 19 = 1012) that is five years earlier than S. 1017 the date given by the Vicharas'reni. Until some evidence to the contrary is shown Merutunga's date A.D. 961 (S. 821 + 196 = 1017) may be taken as correct.

Chapter I.  
THE CHAVADÁS,  
A.D. 720-956.

According to the above the Chávadá genealogy stands as follows:



[The period of Chávadá rule at Anahilavāda is likely to remain obscure until the discovery of contemporary inscriptions throws more light upon it than can be gathered from the confused and contradictory legends collected by the Solanki historians, none of whom are older than the twelfth century. For the present a few points only can be regarded as established:

- (i) The Chávadás, Chávotakas, or Chápotkaṣas, are connected with the Chápas of Bhímál and of Vadhvón and are therefore of Gurjjara race (Compare Ind. Ant. XVII. 192.)
- (ii) They probably were never more than feudatories of the Bhímál kings.
- (iii) Though the legend places the fall of Pañchásar in A.D. 696 and the foundation of Anahilavāda in A.D. 746, the grant of Pulakeśi Janásraya shows that a Chávadá (Chávotaka) kingdom existed in A.D. 728.

As regards the chronology of the dynasty, the explanation of the long life of 110 years ascribed to Vanaraja may be that a grandson of the same name succeeded the founder of the family. The name of Chamunda has, as Dr Bühler long ago pointed out, crept in through some error from the Solanki list. But when the same author in two different works gives such contradictory lists and dates as Merutunga does in his Prabandhachintāmañi and his Vicharas'reni, it is clearly useless to attempt to extract a consistent story from the chroniclers.—  
A.M. T. J.]

## CHAPTER II:

## THE CHAULUKYAS OR SOLANKIS

(A.D. 961-1242.)

## Chapter II.

THE  
CHAULUKYAS,  
A.D. 961-1242.  
Authorities

THE next rulers are the Chaulukyas or Solankis (A.D. 961-1242) whose conversion to Jainism has secured them careful record by Jain chroniclers. The earliest writer on the Solankis, the learned Jain priest Hemachandra (A.D. 1089-1173), in his work called the *Dvyāśraya*, has given a fairly full and correct account of the dynasty up to Siddharāja (A.D. 1143). The work is said to have been begun by Hemachandra about A.D. 1160, and to have been finished and revised by another Jain monk named Abhayatilakagani in A.D. 1255.<sup>1</sup> The last chapter which is in Prakrit deals solely with king Kumārapāla. This work is a grammar rather than a chronicle, still, though it has little reference to dates, it is a good collection of tales and descriptions. For chronology the best guide is the *Vichārasreṇi* which its author has taken pains to make the chief authority in dates. The *Vichārasreṇi* was written by Merutunga about A.D. 1314, some time after he wrote the *Prabandhachintamani*.

The Name  
Chaulukya

According to the *Vichārasreṇi* after the Chāvaḍās, in A.D. 961 (Vaishakh Suddha 1017), began the reign of Mūlarāja the son of a daughter of the last Chāvaḍā ruler. The name Chaulukya is a Sanskritised form, through an earlier form Chālukya, of the old names Chalkya, Chahkya, Chirikya, Chālukya of the great Dakhan dynasty (A.D. 552-973), made to harmonise with the Purāṇik-looking story that the founder of the dynasty sprang from the palm or *chuluka* of Brahma. The form Chaulukya seems to have been confined to authors and writers. It was used by the great Dakhan poet Bilhana (c. 1050 A.D.) and by the Anahilavāḍa chroniclers. In Gujarāt the popular form of the word seems to have been Solaki or Solanki (a dialectic variant of Chālukya), a name till lately used by Gujarāt bards. The sameness of name seems to show the Dakhan and Gujarāt dynasties to be branches of one stock. No materials are available to trace the original seat of the family or to show when and whence they came to Gujarāt. The balance of probability is, as Dr. Buhler holds, that Mūlarāja's ancestors came from the north.<sup>2</sup>

Mūlarāja,  
A.D. 961-996.

The *Sukritasankīrtana* says that the last Chāvaḍā king Bhūbhata was succeeded by his sister's son Mūlarāja. Of the family or country of Mūlarāja's father no details are given. The *Prabandhachintamani* calls Mūlarāja the sister's son of Sāmantasinha and gives the following details. In A.D. 930 of the family of Bhūvāḍa (who destroyed Jayaśekhara) were three brothers Rāji, Bija, and Daṇḍaka, who stopped at Anahilavāḍa on their way back from a pilgrimage to Somanātha in the guise of Kārpāṭika or Kāpdi beggars. The three brothers attended a cavalry

<sup>1</sup> Ind. Ant. IV. 71-72 and VI. 180.

<sup>2</sup> Ind. Ant. VI. 180ff. The suggestion may be offered that the Kanyākubja which is mentioned as the seat of Mūlarāja's ancestors, is Kanyakubja, an old name of Juna-gaḥ, compare Burgess' Kathiāwar and Kutch, 166.

parade held by king Sámantasimha. An objection taken by Ráji to some of the cavalry movements pleased Sámantasimha, who, taking him to be the scion of some noble family, gave him his sister Líládeví in marriage. Líládeví died pregnant and the child, which was taken alive from its dead mother's womb was called Múlarája, because the operation was performed when the Múla constellation was in power. Múlarája grew into an able and popular prince and helped to extend the kingdom of his maternal uncle. In a fit of intoxication Sámantasimha ordered Múlarája to be placed on the throne. He afterwards cancelled the grant. But Múlarája contended that a king once installed could not be degraded. He collected troops defeated and slew his uncle and succeeded to the throne in A.D. 942 (S. 998). The main facts of this tale, that Múlarája's father was one Ráji of the Chálukya family, that his mother was a Chávadá princess, and that he came to the Chávadá throne by killing his maternal uncle, appear to be true. That Múlarája's father's name was Ráji is proved by Dr. Bühler's copperplate of Múlarája.<sup>1</sup> Merutnóga's details that Ráji came in disguise to Anahilaváda, took the fancy of Sámantasimha, and received his sister in marriage seem fictions in the style common in the bardic praises of Rájput princes. Dr. Bühler's copperplate further disproves the story as it calls Múlarája the son of the illustrious Ráji, the great king of kings *Maharajadhiraja*, a title which would not be given to a wandering prince. Ráji appears to have been of almost equal rank with the Chávadás. The Ratnamálá calls Ráji fifth in descent from Bhuváda, his four predecessors being Karnáditya, Chandráditya, Somáditya, and Bhuvanáditya. But the Ratnamálá list is on the face of it wrong, as it gives five instead of seven or eight kings to fill the space of over 200 years between Jayasekhara and Múlarája.

Most Jain chroniclers begin the history of Anahilaváda with Múlarája who with the Jains is the glory of the dynasty. After taking the small Chávadá kingdom Múlarája spread his power in all directions, overrunning Káthiaváda and Kacch on the west, and fighting Bārappa of Lāta or South Gujarāt on the south, and Vighnarāja king of Ajmir on the north. The Ajmir kings were called Sapádalaksha. Why they were so called is not known. This much is certain that Sapádalaksha is the Sanskrit form of the modern Sewálík. It would seem that the Choháns, whom the Gujarāt Jain chroniclers call Sapádalakshíya, must have come to Gujarāt from the Sewahk hills. After leaving the Sewálík hills the capital was at Ajmir, which is usually said to have been first fortified by the Chohán king Ajayapála (A.D. 1174-1177).<sup>2</sup> This story seems invented by the Choháns. The name Ajmir appears to be derived from the Mehars who were in power in these parts between the fifth and the eighth centuries. The Hammíramahákavya begins the Chohán genealogy with Vásudeva (A.D. 780) and states that Vásudeva's fourth successor Ajayapála established the hill fort of Ajmir. About this time (A.D. 840) the Choháns seem to have made settlements in the Ajmir country and to have harassed Gujarāt. Vighnarāja the tenth in suc<sup>ce</sup>.

## Chapter II.

THE  
CHAULUKYAS,  
A.D. 961-1242.  
Mularaja,  
A.D. 961-996.

<sup>1</sup> Ind. Ant. VI. 191ff.<sup>2</sup> Kirtane's Hammíramahákavya, I.

## Chapter II.

THE  
CHAULUKYAS,  
A.D. 961 - 1242.  
Mularaja,  
A.D. 961 - 996.

cession from Vāsudeva is described as killing Mularāja and weakening the Gurjjara country.<sup>1</sup> The author of the Prabandhachintāmaṇi gives the following details. The Sapādalakṣha or Ajmir king entered Gujarāt to attack Mularāja and at the same time from the south Mularāja's territory was invaded by Bārappa a general of king Tailapa of Telingāna.<sup>2</sup> Unable to face both enemies Mularāja at his minister's advice retired to Kanthādurga apparently Kanthkot in Cutch.<sup>3</sup> He remained there till the Navarātra or Nine-Night festival at the close of the rains when he expected the Sapādalakṣha king would have to return to Ajmir to worship the goddess Sākambhari when Bārappa would be left alone. At the close of the rains the Sapādalakṣha king fixed his camp near a place called Sākambhari and bringing the goddess Sākambhari there held the Nine-Night festival. This device disappointed Mularāja. He sent for his *sāmantas* or nobles and gave them presents. He told them his plans and called on them to support him in attacking the Sapādalakṣha king. Mularāja then mounted a female elephant with no attendant but the driver and in the evening came suddenly to the Ajmir camp. He dismounted and holding a drawn sword in his hand said to the doorkeeper 'What is your king doing. Go and tell your lord that Mularāja waits at his door.' While the attendant was on his way to give the message, Mularāja pushed him on one side and himself went into the presence. The doorkeeper called 'Here comes Mularāja.' Before he could be stopped Mularāja forced his way in and took his seat on the throne. The Ajmir king in consternation asked 'Are you Mularāja?' Mularāja answered 'I would regard him as a brave king who would meet me face to face in battle. While I was thinking no such brave enemy exists, you have arrived. I ask no better fortune than to fight with you. But as soon as you are come, like a bee falling in at dinner time, Bārappa the general of king Tailapa of Telingana has arrived to attack me. While I am punishing him you should keep quiet and not give me a side blow.' The Ajmir king said, 'Though you are a king, you have come here alone like a foot soldier, not caring for your safety. I will be your ally for life.' Mularāja replied 'Say not so.' He refused the Rāja's invitation to dine, and leaving sword in hand mounted his elephant and with his nobles attacked the camp of Bārappa. Bārappa was killed and eighteen of his elephants and 10,000 of his horses fell into Mularāja's hands. While returning with the spoil Mularāja received news that the Sapādalakṣha king had fled.

<sup>1</sup> The Chohans of Ajmir were also known as the rulers of Sākambhari, the Sāmlihar lake in Rajputāna on the borders of Jampur and Jodhpur. The corrected edition of the Harsha inscription published by Prof. Kriehorn in *Epigraphia Indica* II. 116ff. shows that their first historical king was Guvaka, who reigned some time in the first half of the ninth century (c. 820 A.D.) The Chohans are still very numerous in the neighbourhood of the Sewālik hills, especially in the districts of Ambālā and Karnāl. Compare Ibbetson's *Panjab Census* for 1881.

<sup>2</sup> It appears from the grant of Saka 972 published by Mr. Dhruva in *Ind. Ant.* XII. 196 and from the Surat grant of Kirttirāja dated Saka 940, that this Bārappa was the founder of a dynasty who ruled Lāṭa or South Gujarāt as under-kings of the Dakhan Chalukyas until at least A.D. 1050. Bārappa was, as his name shows, a Southerner from the Kānarese country, but his descendants spell the family name Chaulukya in the same way as the dynasty of Anahilavāḍa.

<sup>3</sup> Dr. Bühler (*Ind. Ant.* XII. 123) sees a reference to this retirement in Mularāja's grant of Samvat 1043.

This story of the author of the *Prabandhachintāmaṇi* differs from that given by the author of the *Hammīrakāvya* who describes Mūlarāja as defeated and slain. The truth seems to be that the Ajmīr king defeated Mūlarāja and on Mūlarāja's submission did not press his advantage. In these circumstances Mularaja's victory over Bārappa seems improbable. The *Dvyāstraya* devotes seventy-five verses (27-101) of its sixth chapter to the contest between Bārappa and Mūlarāja. The details may be thus summarised. Once when Mūlarāja received presents from various Indian kings Dvārappa<sup>1</sup> king of Lātadesa sent an ill-omened elephant. The marks being examined by royal officers and by prince Chāmunda, they decided the elephant would bring destruction on the king who kept him. The elephant was sent back in disgrace and Mūlarāja and his son started with an army to attack Lātadesa and avenge the insult. In his march Mūlarāja first came to the Svabhṛavati or Subarmati which formed the boundary of his kingdom, frightening the people. From the Sābarmati he advanced to the ancient Puri<sup>2</sup> where also the people became confused. The Lāta king prepared for fight, and was slain by Chāmunda in single combat. Mūlarāja advanced to Broach where Bārappa who was assisted by the island kings opposed him. Chāmunda overcame them and slew Bārappa. After this success Mūlarāja and Chāmunda returned to Anahilapura.<sup>3</sup>

The *Dvyāstraya* styles Bārappa king of Lātadesa; the *Prabandhachintāmaṇi* calls him a general of Tailapa king of Telingāna; the *Sukritasankīrtana*, a general of the Kanyākubja king; and the *Kīrtikaumudī*<sup>4</sup> a general of the Lord of Lāta.

Other evidence proves that at the time of Mūlarāja a Chaulukya king named Bārappa did reign in Lātadesa. The Surat grant of Kīrtirāja grandson of Bārappa is dated A.D. 1018 (Saka 940). This, taking twenty years to a king, brings Bārappa's date to A.D. 978 (Saka 900), a year which falls in the reign of Mūlarāja (A.D. 961-996; S. 1027-1053). The statement in the *Prabandhachintāmaṇi* that Bārappa was a general of Tailapa seems correct. The southern form of the name Bārappa supports the statement. And as Tailapa overthrew the Rāshtrakūṭas in A.D. 972 (Saka 894) he might well place a general in military charge of Lāta, and allow him practical independence. This would explain why the *Dvyāstraya* calls Bārappa king of Lātadesa and why the *Kīrtikaumudī* calls him general of the Lord of Lāta.

One of Mūlarāja's earliest wars was with Graharipu the Abhīra or Chudāsamā ruler of Sorath.<sup>5</sup> According to Mūlarāja's bards, the cause

## Chapter II.

THE  
CHAULUKYAS,  
A.D. 961-1242.  
Mūlarāja,  
A.D. 961-996.

<sup>1</sup> Apparently a Sanskrit form of Bārappa. <sup>2</sup> Broach according to the commentator.

<sup>3</sup> The *Sukritasankīrtana* mentions this defeat of Bārappa who is said to be a general of the Kanyākubja or Kanoj king. The *Prabandhachintāmaṇi* (Mūlarāja-prabandha) also mentions the invasion and slaughter of Bārappa; but there is no reference to it in the grant of Bārappa's descendant Trilochanapāla (Ind. Ant. Xii, 196ff.)

<sup>4</sup> Canto II. Verso 3.

<sup>5</sup> As Mr. Forbes rightly observed Graharipu the Planet-seizer is a made-up title based on the resemblance of the planet-seizer's name kīthu to Rā the title of the Chudāsamās of Junāgaḍh. The personal name of the chief is not given and the list of the Junāgaḍh Chudāsamās is too incomplete to allow of identification.

## Chapter II.

THE  
CHAULUKYAS,  
A.D. 961-1242.  
Múlarāja,  
A.D. 961-996.

of war was Grahariṇ's oppression of pilgrims to Prabhāsa. Grahariṇ's capital was Vāmanasthali, the modern Vantali nine miles west of Junāgaḍh, and the fort of Durgapalli which Grahariṇ is said to have established must be Junāgaḍh itself which was not then a capital. Grahariṇ is described as a cow-eating Mlechha and a grievous tyrant. He is said to have had much influence over Lākha, son of king Phula of Kacch and to have been helped by Turks and other Mlechhas. When Múlarāja reached the Jambumali river, he was met by Grahariṇ and his army. With Grahariṇ was Lākha of Kacch, the king of Sindhi probably a Sumra, Mewās Bhilas, and the sons of Grahariṇ's wife Nili who had been summoned from near the Bhadar river by a message in the Yavana language.<sup>1</sup> With Múlarāja were the kings of Silāprastha,<sup>2</sup> of Mārwar, of Kāśī, of Arbuda or Abu, and of Śrīmūla or Bhīmāl. Múlarāja had also his own younger brother Gangāmā, his friend king Revatimitra, and Bhils. It is specially mentioned that in this expedition Múlarāja received no help from the sons of his paternal uncles Bija and Dandaka. The fight ended in Grahariṇ being made prisoner by Múlarāja, and in Lākha being slain with a spear. After the victory Múlarāja went to Prabhāsa, worshipped the *Uṅgā*, and returned to Anahilavāḍa with his army and 108 elephants.

According to the author of the *Prabandhachintāmaṇi* Lākhi met his death in a different contest with Múlarāja. Lākha who is described as the son of Phulaki and Kāmalatā daughter of Kīrttirāja a Parmār king, is said to have been invincible because he was under the protection of king Yaśovarman of Malwa. He defeated Múlarāja's army eleven times. In a twelfth encounter Múlarāja besieged Lākha in Kapilakot, slew him in single combat, and trod on his flowing beard. Enraged at this insult to her dead son Lākha's mother called down on Múlarāja's descendants the curse of the spider poison that is of leprosy.<sup>3</sup>

Mr. Forbes, apparently from bardic sources, states that on his wife's death Rāji the father of Múlarāja went to the temple of Vishnu at Dwārka. On his return he visited the court of Lākha Phulāni and espoused Lākha's sister Rāyāji by whom he had a son named Rākhaich. This marriage proved the ruin of Rāji. In a dispute about precedence Lākha slew Rāji and many of his Rājput followers, his wife Rāyāji becoming a Sati. Bija the uncle of Múlarāja urged his nephew to avenge his father's death and Múlarāja was further incited against Lākha because Lākha harboured Rākhaich the younger son of Rāji at his court as a rival to Múlarāja.

According to the *Dvyāśraya*, either from the rising power of his son or from repentance for his own rough acts, after Chāmunḍa's victory over Bārappa Múlarāja installed him as ruler and devoted himself to religion and charity. According to the *Prabandhachintāmaṇi* Múlarāja built in Anahilavāḍa a Jain temple named Múlavasatikā. But as the Nandi

<sup>1</sup> The mention of her name and of the language in which she wrote suggest something remarkable in the race and position of queen Nili.

<sup>2</sup> Perhaps Siṭha in Jhālavād.

<sup>3</sup> The same account appears in the *Kumārāpālacharita*.

symbol on his copperplate shows that Mularāja was a devoted Śaivite, it is possible that this temple was built by some Jain guild or community and named after the reigning chief.<sup>1</sup> Mularāja built a Mahādeva temple called Mūlasvāmi in Anahilavāda, and, in honour of Somanātha, he built the temple of Mūlesvara at Maṇḍali-nagara where he went at the bidding of the god.<sup>2</sup> He also built at Anahilavāda a temple of Mahādevā called Tripurnashaprasāda on a site to which the tradition attaches that seeing Mularāja daily visiting the temple of Mūlanāthadeva at Maṇḍali, Somanātha Mahādeva being greatly pleased promised to bring the ocean to Anahilavāda. Somanātha came, and the ocean accompanying the god certain ponds became brackish. In honour of these salt pools Mularāja built the Tripurnashaprasāda. Looking for some one to place in charge of this temple, Mularāja heard of an ascetic named Kauthaki at Siddhapura on the banks of the Sarasvatī who used to fast every other day and on the intervening day lived on five morsels of food. Mularāja offered this sage the charge of the temple. The sage declined saying 'Authority is the surest path to hell.' Eventually Vayajāladeva a disciple of the sage undertook the management on certain conditions. Mularāja passed most of his days at the holy shrine of Siddhapura, the modern Sidhpur on the Sarasvatī about fifteen miles north-east of Anahilavāda. At Sidhpur Mularāja made many grants to Brāhmanas. Several branches of Gujarāt Brāhmanas, Audichyas, Śrīgaudas and Kanojias, trace their origin in Gujarāt to an invitation from Mularāja to Siddhapura and the local Puranas and Mahātmyas confirm the story. As the term Audichya means Northerner Mularāja may have invited Brāhmanas from some such holy place as Kurukshetra which the Audichyas claim as their home. From Kanyākubja in the Madhyadesa between the Ganges and the Yamunā another equally holy place the Kanojias may have been invited. The Śrī Gaudas appear to have come from Bengal and Tihlut. Gauda and Tihlut Brāhmanas are noted Tāntriks and Mantrasāstiris a branch of learning for which both the people and the rulers of Gujarāt have a great fondness. Grants of villages were made to these Brāhmanas. Sidhpur was given to the Audichyas, Simhapura or Sihor in Kathiāwāda to some other colony, and Stambhatīrtha or Cambay to the Śrī Gaudas. At Siddhapura Mularāja built the famous temple called the Rudramahālaya or the great shrine of Rudra. According to tradition Mularāja did not complete the Rudramahālaya and Siddharāja finished it. In spite of this tradition it does not appear that Mularāja died leaving the great temple unfinished as a copperplate of A.D. 987 (S. 1043) records that

## Chapter II.

THE  
CHAULUKYAS;  
A.D. 901 - 1242.  
Mularāja,  
A.D. 901 - 996

<sup>1</sup> Compare the Lakshmi-Vihāra Jain temple in Jesalmir built by the Jain Saṅgha and called after the reigning king Lakshmana.

<sup>2</sup> Dr. Bühler's copperplate of Mularāja records a grant to this temple, said to be of Mūlanāthadeva in Maṇḍali in the Vardhi zilla, apparently the modern Māndal near Pafichasar in the Vadhiār province near Jhinjhuvāda. The grant is in Samvat 1043 and is dated from Anahilapura though the actual gift was made at Śrīsthala or Sidhpur after bathing in the Sarasvatī and worshipping the god of the Rudramahālaya. The grant is of the village of Kamboika, the modern Kanboi near Modhera. Ind. Ant. VI. 192-193. The grant is said to have been written by a Kāyastha named Kaśchapa and ends with the words "of the illustrious Mularāja."

## Chapter II.

THE  
CHATLUKYN,  
A.D. 961-1242  
Mularaja,  
A.D. 961-996.

Mularaja made the grant after worshipping the god of the Rudramahalaya on the occasion of a solar eclipse on the fifteenth of the dark half of Magha. It would seem therefore that Mularaja built one large Rudramahalaya which Siddharaja may have repaired or enlarged. Mularaja is said while still in health to have mounted the funeral pile, an act which some writers trace to remorse and others to unknown political reasons. The Vicharasreni gives the length of Mularaja's reign at thirty-five years A.D. 961-996 (S. 1017-1052); the Prabandhachintamani begins the reign at A.D. 942 (S. 998) and ends it at A.D. 997 (S. 1053) that is a length of fifty-five years.<sup>1</sup> Of the two, thirty-five years seems the more probable, as, if the traditional accounts are correct, Mularaja can scarcely have been a young man when he overthrew his uncle's power.

Chamunda,  
A.D. 997-1010.

Of Mularaja's son and successor Chamunda no historical information is available. The author of the Prabandhachintamani assigns him a reign of thirteen years. The author of the Dvyasraya says that he had three sons Vallabha Raja, Durlabha Raja, and Naga Raja. According to his account Chamunda installed Vallabha in A.D. 1010 (S. 1066) and went on pilgrimage to Benares. On his passage through Malwa Munja the Malwa king carried off Chamunda's umbrella and other marks of royalty.<sup>2</sup> Chamunda went on to Benares in the guise of a hermit. On his return he prayed his son to avenge the insult offered by the king of Malwa. Vallabha started with an army but died of small-pox. The author of the Prabandhachintamani gives Chamunda a reign of six months, while the author of the Vicharasreni entirely drops his name and gives a reign of fourteen years to Vallabha made up of the thirteen years of Chamunda and the six months of Vallabha. This seems to be a mistake. It would seem more correct, as is done in several copperplate lists, to omit Vallabha, since he must have reigned jointly with his father and his name is not wanted for purposes of succession. The Vicharasreni and the Prabandhachintamani agree in ending Vallabha's reign in A.D. 1010 (S. 1066). The author of the Dvyasraya states that Chamunda greatly lamenting the death of Vallabha installed Vallabha's younger brother Durlabha, and himself retired to die at Suklatirtha on the Narmada.

Durlabha,  
A.D. 1010-1022

Durlabha whom the Sukritasankirtana also calls Jagatjampaka or World Guardian came to the throne in A.D. 1010 (S. 1066). The Prabandhachintamani gives the length of his reign at eleven years and six months while the Vicharasreni makes it twelve years closing it in A.D. 1022 (S. 1078). The author of the Dvyasraya says that along with his brother Naga Raja, Durlabha attended the Svayamvara or bridegroom-choosing of Durlabha Devi the sister of Mahendra the

<sup>1</sup> The difference between 1052 and 1053 is probably only a few months.

<sup>2</sup> The fight with Munja must have taken place about A.D. 1011 (S. 1067). As Chamunda started just after installing Vallabha the beginning of the reign must be before A.D. 997 as Tailapa who fought with Munja died in that year. This is proved by a manuscript dated A.D. 994 (S. 1060) which gives the reigning king as Munja. That Bhaja Munja's successor was ruling in A.D. 1014 (S. 1070) makes it probable that Munja's reign extended to A.D. 1011 (S. 1067).

Rāja of Nadol in Márwār. The kings of Aṅga, Kási, Avantí, Chedí, Kuru, Húna, Mathurá, Vindhya, and Andhra were also present.<sup>1</sup> The princess chose Durlabha and Mahendra gave his younger sister Lakshmi to Durlabha's brother Nága Rāja. The princess' choice of Durlabha drew on him the enmity of certain of the other kings all of whom he defeated. The brothers then returned to Anahilaváda where Durlabha built a lake called Durlabhasarovara. The author of the Prabandhachintāmaṇi says that Durlabha gave up the kingdom to his son (?) Bhíma.<sup>2</sup> He also states that Durlabha went on pilgrimage and was insulted on the way by Muñja king of Málwa. This seems the same tale which the Dvyás'raya tells of Chámunda. Since Muñja cannot have been a cotemporary of Durlabha the Dvyás'raya's account seems correct.

Durlabha was succeeded by his nephew Bhíma the son of Durlabha's younger brother Nága Rāja. The author of the Dvyás'raya says that Durlabha wishing to retire from the world offered the kingdom to his nephew Bhíma; that Bhíma declined in favour of his father Nága Rāja; that Nága Rāja refused; that Durlabha and Nága Rāja persuaded Bhíma to take the government; and that after installing Bhíma the two brothers died together. Such a voluntary double death sounds unlikely unless the result was due to the machinations of Bhíma. The Prabandhachintāmaṇi gives Bhíma a reign of fifty-two years from A.D. 1022 to 1074 (S. 1078-1130), while the Vicharās'repi reduces his reign to forty-two years placing its close in A.D. 1064 (S. 1120). Forty-two years would seem to be correct as another copy of the Prabandhachintāmaṇi has 42.

Two copperplates of Bhíma are available one dated A.D. 1030 (S. 1086) eight or nine years after he came to the throne the other from Kacch in A.D. 1037 (S. 1093).

Bhíma seems to have been more powerful than either of his predecessors. According to the Dvyás'raya his two chief enemies were the kings of Sindh and of Chedí or Bundelkhand. He led a victorious expedition against Hammuka the king of Sindh, who had conquered the king of Sivasána and another against Karna king of Chedí who paid tribute and submitted. The Prabandhachintāmaṇi has a verse, apparently an old verse interpolated which says that on the Málwa king Bhoja's death, while sacking Dhárápuri, Karna took Bhíma as his coadjutor, and that afterwards Bhíma's general Dánura took Karna captive and won from him a gold *maṇḍapiká* or canopy and images of Ganesa and Nilakanthes'vara Mahádeva. Bhíma is said to have presented the canopy to Šomanátha.

When Bhíma was engaged against the king of Sindh, Kulachandra the general of the Málwa king Bhoja with all the Málwa feudatories, invaded Anahilaváda, sacked the city, and sowed shell-money at the gate where the time-marking gong was sounded. So great was the

## Chapter II.

THE  
CHAULUKYAS,  
A.D. 961-1242.  
Durlabha,  
A.D. 1010-1022.

Bhíma I.  
A.D. 1022-1064.

<sup>1</sup> This Svayamvara and the list of attendant and rival kings seem imaginary. The Nadol chiefship was not important enough to draw kings from the countries named.

<sup>2</sup> The text has son but Bhíma was Durlabha's nephew not his son.

## Chapter II.

THE  
CHAUUKYAS,  
A.D. 961-1242.  
Bhīma I.  
A.D. 1022-1064.

loss that the 'sacking of Kulachandra' has passed into a proverb. Kulachandra also took from Anahilavāḍa an acknowledgment of victory or *jayapatra*. On his return Bhoja received Kulachandra with honour but blamed him for not sowing salt instead of shell-money.<sup>1</sup> He said the shell-money is an omen that the wealth of Mālwa will flow to Gujarāt. An unpublished inscription of Bhoja's successor Udayāditya in a temple at Udepur near Blusā confirms the above stating that Bhīma was conquered by Bhoja's officers.<sup>2</sup>

The Solanki kings of Anahilapura being Śaivites held the god Somanātha of Prabhāsa in great veneration. The very ancient and holy shrine of Prabhāsa has long been a place of special pilgrimage. As early as the Yadavas of Dwarkā,<sup>3</sup> pilgrimages to Prabhāsa are recorded but the Mahābhārata makes no mention either of Somanātha or of any other Śaivite shrine. The shrine of Somanātha was probably not established before the time of the Valabhis (A.D. 480-767). As the Valabhi kings were most open-handed in religious gifts, it was probably through their grants that the Somanātha temple rose to importance. The Solankis were not behind the Valabhis in devotion to Somanātha. To save pilgrims from oppression Mularāja fought Grharipu the Abhīra king of Sorath.<sup>4</sup> Mularāja afterwards went to Prabhāsa and also built temples in Gujarāt in honour of the god Somanātha. As Mularāja's successors Chāmuṇḍa and Durlabha continued firm devotees of Somanātha during their reigns (A.D. 997-1022) the wealth of the temple must have greatly increased.

No Gujarāt Hindu writer refers to the destruction of the great temple soon after Bhīma's accession.<sup>5</sup> But the Muslim historians place beyond doubt that in A.D. 1024 the famous tenth raid of

Mahmūd's  
Invasion,  
A.D. 1024.

<sup>1</sup> By sowing cowries Kulachandra may have meant to show the cheapness of Anahilavāḍa. Bhoja's meaning was that as shells are money, to sow shells was to sow Mālwa wealth in Gujarāt. If Kulachandra had sown salt all would have melted, and no trace been left. [This seems a symbolical later stage explanation. The sense seems to be shell-sowing keeps the Anahilavāḍa gnomes in place since gnomes can live in shells. Salt-sowing scares the guardian spirits and makes the site of the city a haunt of demons. Bhoja saw that thanks to his general the Luck of Anahilavāḍa would remain safe in the shells.]

<sup>2</sup> The Prabandhaśekharam tells other stories of the relations between Bhīma and Bhoja. Once when Gujarat was suffering from famine Bhīma heard that Bhoja was coming with a force against Gujarat. Alarmed at the news Bhīma asked Dāmara his minister of peace and war to prevent Bhoja coming. Dāmara went to Mālwa, amused the king by witty stories, and while a play was being acted in court degrading and joining other kings, something was said regarding Tailapa of Telingana. On this Dāmara reminded the king that the head of his grandfather Mūḍja was fixed at Tailapa's door. Bhoja grew excited and started with an army against Telingana. Hearing that Bhīma had come against him as far as Bhūmapura (?) Bhoja asked Dāmara to prevent Bhīma advancing further. Dāmara stopped Bhīma by taking him an elephant as a present from Bhoja. The Prabandhaśekharam gives numerous other stories showing that at times the relations between Bhoja and Bhīma were friendly.

<sup>3</sup> See above page 9.

<sup>4</sup> See above page 160.

<sup>5</sup> With this silence compare the absence (Reinard's *Mémoire Sur l'Inde*, 67) of any reference either in Sanskrit or in Buddhist books to the victories, even to the name, of Alexander the Great. Also in modern times the ignoring of British rule in the many inscriptions of Jain repairers of temples on Satruñjaya hill who belong to British territory. The only foreign reference is by one merchant of Daman who acknowledges the protection of the Phirangī jāti Puratākāli Pātasali the king of the Phirangis of Por. (e.g. Buhler in *Epigraphia Indica*, II, 36.)

Mahmūd of Ghazni, ended in the destruction and plunder of Somanātha.<sup>1</sup>

Of the destruction of Somanātha the earliest Musalmān account, that of Ibn Asīr (A.D. 1160 - 1229), supplies the following details: In the year A.D. 1024 (H. 414) Mahmūd captured several forts and cities in Hind and he also took the idol called Somanātha. This idol was the greatest of all the idols of Hind. At every eclipse<sup>2</sup> the Hindus went on pilgrimage to the temple, and there congregated to the number of a hundred thousand persons. According to their doctrine of transmigration the Hindus believe that after separation from the body the souls of men meet at Somanātha; and that the ebb and flow of the tide is the worship paid to the best of its power by the sea to the idol.<sup>3</sup> All that is most precious in India was brought to Somanātha. The temple attendants received the most valuable presents, and the temple was endowed with more than 10,000 villages.<sup>4</sup> In the temple were amassed jewels of the most exquisite quality and of incalculable value. The people of India have a great river called Ganga to which they pay the highest honour and into which they cast the bones of their great men, in the belief that the deceased will thus secure an entrance to heaven. Though between this river and Somanātha is a distance of about 1200 miles (200 *parasangs*) water was daily brought from it to wash the idol.<sup>5</sup> Every day a thousand Brahmins performed the worship and introduced visitors.<sup>6</sup> The shaving of the heads and beards of pilgrims employed three hundred barbers.<sup>7</sup> Three hundred and fifty persons sang and danced at the gate of the temple,<sup>8</sup> every one receiving a settled daily allowance. When Mahmūd was gaining victories and demolishing idols in North India, the Hindus said Somanātha is displeased with these idols. If Somanātha had been satisfied with them no one could have destroyed or injured them. When Mahmūd heard this he resolved on making a campaign to destroy Somanātha, believing that when the Hindus saw their prayers and imprecations to be false and futile they would embrace the Faith.

So he prayed to the Almighty for aid, and with 30,000 horse besides volunteers left Ghazni on the 10th Sha'bān (H. 414, A.D. 1024).

## Chapter II.

THE  
CHAULUKYAS,  
A.D. 961-1242.  
Somanātha,  
A.D. 1024.

<sup>1</sup> Elliot and Dowson, II. 468ff. For H. M. Elliot gives extracts for this expedition from the *Tārīkh-i-Alfi*, *Tārīkh-i-Akbarī*, *Tārīkh-i-Nāfirī*, and *Ramzāt-i-Safā*.

<sup>2</sup> Since the earliest times Hindus have held eclipse days sacred. According to the *Mahabharata* the Yadavas of Dwarka came to Somanātha for an eclipse fair. Great fairs are still held at Somanātha on the Kartika and Chaitra (December and April) fullmoons.

<sup>3</sup> This old Indian idea is expressed in a verse in an inscription in Somanātha Patan itself.

<sup>4</sup> Ten thousand must be taken vaguely.

<sup>5</sup> Compare Sachau's Alberuni, II. 104. Every day they brought Somanātha a jug of Ganges water and a basket of Kashmir flowers. Somanātha they believed cured every inveterate sickness and healed every desperate and incurable disease. The reason why Somanātha became so famous was that it was a harbour for those who went to and from Sofala in Zanzibar to China. It is still the practice to carry Ganges water to bathe distant gods.

<sup>6</sup> These must be the local Sompura Brahmins who still number more than five hundred souls in Somanātha Patan.

<sup>7</sup> Shaving is the first rite performed by pilgrims.

<sup>8</sup> Dancers are now chiefly found in the temples of Southern India.

Chapter II.  
 THE  
 CHAULUKYAS,  
 A.D. 961-1242.  
 Somanátha,  
 A.D. 1021.

He took the road to Multán and reached it in the middle of Ramzán. The road from Multán to India lay through a barren desert without inhabitants or food. Mahmúd collected provisions for the passage and loading 30,000 camels with water and corn started for Anahilaváda. After he had crossed the desert he perceived on one side a fort full of people in which place there were wells.<sup>1</sup> The leaders came to conciliate him, but he invested the place, and God gave him victory over it, for the hearts of the people failed them through fear. He brought the place under the sway of Islám, killed the inhabitants; and broke in pieces their images. His men carrying water with them marched for Anahilaváda, where they arrived at the beginning of Zilkáda.

The Chief of Anahilaváda, called Bhím, fled hastily, and abandoning his city went to a certain fort for safety and to prepare for war. Mahmúd pushed on for Somanátha. On his march he came to several forts in which were many images serving as chamberlains or heralds of Somanátha. These Mahmúd called Shaitán or devils. He killed the people, destroyed the fortifications, broke the idols in pieces, and through a waterless desert marched to Somanátha. In the desert land he met 20,000 fighting men whose chiefs would not submit. He sent troops against them, defeated them, put them to flight, and plundered their possessions. From the desert he marched to Dabálwárah,<sup>2</sup> two days' journey from Somanátha. The people of Dabálwárah stayed in the city believing that the word of Somanátha would drive back the invaders. Mahmúd took the place, slew the men, plundered their property, and marched to Somanátha.

Reaching Somanátha on a Thursday in the middle of Zilkáda Mahmúd beheld a strong fortress built on the sea-shore, so that its walls were washed by the waves.<sup>3</sup> From the walls the people jeered at the Musalmáns. Our deity, they said, will cut off the last man of you and destroy you all. On the morrow which was Friday the assailants advanced to the assault. When the Hindus saw how the Muhammadaus fought they abandoned their posts and left the walls. The Musalmáns planted their ladders and scaled the walls. From the top they raised their war-cry, and showed the might of Islám. Still their loss was so heavy that the issue seemed doubtful. A body of Hindus hurried to Somanátha, cast themselves on the ground before him, and besought him to grant them victory. Night came on and the fight was stayed.

Early next morning Mahmúd renewed the battle. His men made greater havoc among the Hindus till they drove them from the town to the house of their idol Somanátha. At the gate of the temple the slaughter was dreadful. Band after band of the defenders entered the temple and standing before Somanátha with their hands clasped round their necks wept and passionately entreated him. Then they issued forth to fight and fought till they were slain. The few left alive took

<sup>1</sup> Mahmúd seems to have crossed the desert from Multán and Baháwalpur to Bikanér and thence to Ajmir.

<sup>2</sup> Apparently Delvada near Uná. Mahmúd's route seems to have been from Anahilaváda to Nodhera and Mándal, thence by the Little Ran near Pátri and Bajána, and thence by Jhalvād Gohelvād and Bábriavād to Delvada.

<sup>3</sup> The waves still beat against the walls of the ruined fort of Somanátha.

to the sea in boats but the Musalmáns overtook them and some were killed and some were drowned.

The temple of Somanátha rested on fifty-six pillars of teakwood covered with lead.<sup>1</sup> The idol was in a dark chamber. The height of the idol was five cubits and its girth three cubits. This was what appeared to the eye; two cubits were hidden in the basement. It had no appearance of being sculptured. Mahmúd seized it, part of it he burnt, and part he carried with him to Ghazni, where he made it a step at the entrance of the Great Mosque.<sup>2</sup> The dark shrine was lighted by exquisitely jewelled chandeliers. Near the idol was a chain of gold 200 *mans* in weight. To the chain bells were fastened. And when each watch of the night was over the chain was shaken and the ringing of the bells roused a fresh party of Bráhmans to carry on the worship. In the treasury which was near the shrine were many idols of gold and silver. Among the treasures were veils set with jewels, every jewel of immense value. What was found in the temple was worth more than two millions of *diráms*. Over fifty thousand Hindus were slain.<sup>3</sup>

After the capture of Somanátha, Mahmúd received intelligence that Bhím the chief of Apahlaváda had gone to the fort of Khandahat,<sup>4</sup> about 240 miles (40 *parasangs*) from Somanátha between that place and the desert. Mahmúd marched to Khandahat. When he came before it he questioned some men who were hunting as to the tide. He learned that the ford was practicable, but that if the wind blew a little the crossing was dangerous. Mahmúd prayed to the Almighty and entered the water. He and his forces passed safely and drove out the enemy. From Khandahat he returned intending to proceed against Mansúra in central Sindh, whose ruler was an apostate Muhamádan. At the news of Mahmúd's approach the chief fled into the date forests. Mahmúd followed, and surrounding him and his adherents, many of them were slain, many drowned, and few escaped. Mahmúd then went

## Chapter II.

THE  
CHAULUKYAS,  
A.D. 961-1242.  
Somanátha,  
A.D. 1024.

<sup>1</sup> This shows that the temple was a building of brick and wood. According to Alberuni (Sachau, II. 105) the temple was built about a hundred years before Mahmúd's invasion. An inscription at Patan states that Bhímaleyn I (A.D. 1022-1072) rebuilt the Somanátha temple of stone. In Dr. Bhatiyá's opinion the first dynasty in Gujarat to make stone buildings were the Solankis. Before them buildings and temples were of wood and brick.

<sup>2</sup> Of the fate of the great Liúga Alberuni (Sachau, II. 103) writes: Prince Mahmúd ordered the upper part to be broken. The rest with all its coverings and trappings of gold jewels and embroidered garments he transported to Ghazni. Part of it together with the brass Chakravartí or Vishnu of Thaneshvar has been thrown into the hippodrome of the town. Part lies before the mosque for people to rub their feet on.

<sup>3</sup> The next paragraph relating to Mahmúd's return will be found on page 219 of the same volume of Sir H. Elliott's work.

<sup>4</sup> Khandahat which must have been on the coast has not been identified. The description suggests some coast island in the gulf of Kacch. By the Gímar route forty *parasangs* that is 240 miles would reach the Kacch coast. Kanthkot in Vagad in east Kacch suits well in sound and is known to have been a favourite resort of the Solankis. But the ebb and flow of the tide close to it are difficult to explain. The identification with Kanthkot is favoured by Dr. Bühler. Colonel Watson (Kathiáwár Gazetteer, 80) prefers Gándhvi on the Káthiaváda coast a few miles north-east of Míáni. M. Reinard and Dr. Weil suggest Gandhár in Broach on the left bank of the mouth of the Dhádhar river. Sir H. Elliot (I. 445 and II. 473) prefers Khandadár at the north-west angle of Káthiaváda.

## Chapter II.

## The

CHAULUKYAS,  
A.D. 961-1242.Somanátha,  
A.D. 1024.

to Bhátia, and after reducing the inhabitants to obedience, returned to Ghazni where he arrived on the 10th Safar 417 H. (A.D. 1026).

The Rauzatn-s-safá of Mirkhand supplements these details with the following account of Mahmúd's arrangements for holding Gujarát: 'It is related that when Sultan Mahmúd had achieved the conquest of Somanátha he wished to fix his residence there for some years because the country was very extensive and possessed many advantages among them several mines which produced pure gold. Indian rubies were brought from Sarandíp, one of the dependencies of the kingdom of Gujarát. His ministers represented to Mahmúd that to forsake Khurásán which had been won from his enemies after so many battles and to make Somanátha the seat of government was very improper. At last the king made up his mind to return and ordered some one to be appointed to hold and carry on the administration of the country. The ministers observed that as it was impossible for a stranger to maintain possession he should assign the country to one of the native chiefs. The Sultan accordingly held a council to settle the nomination, in concurrence with such of the inhabitants as were well disposed towards him. Some of them represented to him that amongst the ancient royal families no house was so noble as that of the Dabshilins of whom only one member survived, and he had assumed the habit of a Bráhmaṇ, and was devoted to philosophical pursuits and austerity.'<sup>1</sup>

That Mahmúd should have found it necessary to appoint some local chief to keep order in Gujarát is probable. It is also probable that he would choose some one hostile to the defeated king. It has been suggested above that Bhíma's uncle Durlabha did not retire but was ousted by his nephew and that the story of Vallabha and Durlabha dying together pointed to some usurpation on the part of Bhíma. The phrase the Dabshilins seems to refer either to Durlabhasena or his son. Whoever was chosen must have lost his power soon after Mahmúd's departure.<sup>2</sup>

<sup>1</sup> According to Ferishta (Bombay Persian Ed. I 57, Briggs' Translation, I 74) Mahmúd stayed and meant to make his capital at Anahlavaja not at Somanátha. That Mahmúd did stay at Anahlavaja the Martyr's Mound and the Ghazni Mosque in Patan are evidence. Still the mound was probably raised and the mosque may at least have been begun in honour of the capture of Anahlavaja on the journey south. Traces of a second mosque which is said to have had a tablet recording Mahmúd of Ghazni as the builder have recently (1878) been found at Munjpur about twenty-five miles south east of Rathanpur.

<sup>2</sup> Briggs' Ferishta, I. 75. This account of the Dabshilins reads more like a tradition than an historical record. It is to be noted that the authors both of the 'Ain-i-Akbari (A.D. 1583) and of the Mirat-i-Ahmadi (A.D. 1762) give Chámunḍa as king at the time of Mahmúd's invasion. Their statements cannot weigh against Ibn Asir's account. Compare Dr. Bühler's remarks in Ind. Ant. VI. 184. Of Mahmúd's return to Ghazni (A.D. 1026) the Tabakat-i-Akbari says 'When Mahmúd resolved to return from Somanátha he learned that Parama Dev, one of the greatest Rájás of Hindustán, was preparing to intercept him. The Sultan, not deeming it advisable to contend with this chief, went towards Multán through Sindh. In this journey his men suffered much in some places from scarcity of water in others from want of forage. After enduring great difficulties he arrived at Ghazni in A.D. 1029 (H. 417).' This Parama Dev would seem to be the Parmara king of A'bu who could well block the Ajmir-Gujarát route. The route taken by Mahmúd must have passed by Mansúra near Bráhmaṇábád, Bhátia, and Multán. It

An inscription at Somanátha shows that soon after Mahmúd was gone Bhímadeva began to build a temple of stone in place of the former temple of brick and wood.

A few years later Bhíma was on bad terms with Dhandhuka the Paramára chief of Ábu, and sent his general Vimala to subdue him. Dhandhuka submitted and made over to Vimala the beautiful Chitrakūṭa peak of Ábu, where, in A.D. 1032 (S. 1088), Vimala built the celebrated Jain temples known as Vimalavasahí still one of the glories of Ábu.<sup>1</sup>

Bhíma had three wives Udayámati who built a step-well at Apalilavāda, Bkuládeví, and another. These ladies were the mothers of Karna, Kshemarāja, and Múlarāja. Of the three sons Múlarāja, though his mother's name is unknown, was the eldest and the heir-apparent. Of the kindly Múlarāja the author of the *Prabandhachintámāni* tells the following tale: In a year of scarcity the Kutumbikas or cultivators of Vishopaka and Dandāhi found themselves unable to pay the king his share of the land-produce. Bhímarāja sent a minister to inquire and the minister brought before the king all the well-to-do people of the defaulting villages. One day prince Múlarāja saw these men talking to one another in alarm. Taking pity on them he pleased the king by his skilful riding. The king asked him to name a boon and the prince begged that the demand on the villagers might be remitted. The boon was granted, the ryots went home in glee, but within three days Múlarāja was dead. Next season yielded a bumper harvest, and the people came to present the king with his share for that year as well as with the remitted share for the previous year. Bhímdev declined to receive the arrears. A jury appointed by the king settled that the <sup>royal</sup> share of the produce for both years should be placed in the king's hands for the erection of a temple called the new Tripurushaprásāda for the spiritual welfare of prince Múlarāja.<sup>2</sup>

must have been in the crossing of the great desert that he suffered so severely from scarcity of water and forage. Ferishta (Briggs, I. 75) says that many of Mahmúd's troops died raging mad from the intolerable heat and thirst. The historian Muhammad 'U'n (A.D. 1200) alleges (Elliot, II. 192) that two Hindus disguised as countrymen offered themselves as guides and led the army three days' march out of the right course, where they were saved only by Mahmúd's untimely discovery of a pool of sweet water. [This tale of the self-sacrificing Brahman or priest and the miraculous find of water has gathered round Mahmúd as the latest of myth centres. It is Herodotus' (Book III. 154-158) old Zopyrus tale (Rawlinson's *Seventh Monarchy*, 318) — it is revived in honour of the Great Kushin Kamshika, A.D. 78 (Beroun in Elliot, II. 11), of the Sassanian Firoz A.D. 457-483 (Rawlinson's *Seventh Monarchy*, 318), and of a certain king of Zabulistan of Ghazni of uncertain date (Elliot II. 170). Similarly the puzzling Dabshihim tale seems to be peculiar neither to Gujarat nor to Mahmúd of Ghazni. It seems a repetition of the tale of Dabshihim the man of the royal race, who, according to the *Panchatantra* or *Fables of Pīlpai*, was chosen successor of Porus after Alexander the Great's Viceroy had been driven out. [Compare Remond's *Mémoires Sur l'Inde*, 127-128.] The *Tabakat-i-Nāsiri* (A.D. 1227) adds (Elliot, II. 475) that the guide devoted his life for the sake of Somanátha and this account is adopted by Ferishta. Briggs' Translation, I. 78.

<sup>1</sup> Vasahis Prākṛit for Vasatī that is residence. The word is used to mean a group of temples.

<sup>2</sup> Several later mentions of a *Tripurushaprásāda* show there was only one building of that name. The statement that the great Múlarāja I. built a Tripurushaprásāda seems a mistake, due to a confusion with prince Múlarāja.

## Chapter II.

THE  
CHAULUKYAS,  
A.D. 961-1242.  
Bhíma I.  
A.D. 1022-1064.

## Chapter II.

## THE

CHAULUKYAS,  
A.D. 961-1242.Bhīma I.  
A.D. 1022-1064.

Bhīma reigned forty-two years. Both the Prabandhachintāmaṇi and the Vichāraśreni mention Karna as his successor. According to the Dvyāśraya Bhīma, wishing to retire to a religious life, offered the succession to Kshemarāja. But Kshemarāja also was averse from the labour of ruling and it was settled that Karna should succeed.

Bhīma died soon after and Kshemarāja retired to a holy place on the Sarasvatī named Mundakeśvara not far from Anahilavāda. Karna is said to have granted Dahithālī a neighbouring village to Devaprāsāda the son of Kshemarāja that he might attend on his father in his religious seclusion. But as the Kṣmārapālacharita mentions Kshemarāja being settled at Dahithālī as a ruler not as an ascetic it seems probable that Dahithālī was granted to Kshemarāja for maintenance as villages are still granted to the *bhāyās* or brethren of the ruler.

Karna,  
A.D. 1064-1094.

Karna who came to the throne in A.D. 1064 (S. 1120) had a more peaceful reign than his predecessors. He was able to build charitable public works among them a temple called Karna-meru at Anahilavāda. His only war was an expedition against Aśhā Bhīl, chief of six lākhs<sup>1</sup> of Bhils residing at Aśhāpallī the modern village of Asāval near Ahmadābād.<sup>2</sup> Aśhā was defeated and slain. In consequence of an omen from a local goddess named Kochharva,<sup>3</sup> Karna built her a temple in Asāval and also built temples to Jayantī Devī and Karṇeśvara Mahadeva. He made a lake called Karnasāgara and founded a city called Karnāvati which he made his capital.

Karna had three ministers Munjāla, Sāntu, and Udaya. Udaya was a Śrīmālī Vāṇi of Mīrwar, who had settled in Anahilavāda and who was originally called Udā. Sāntu built a Jain temple called Sāntu-vasahi and Udā built at Karnāvati a large temple called Udaya-varāha, containing seventy-two images of Tirthankars, twenty-four past twenty-four present and twenty-four to come. By different wives Udā had five sons, Ahada or Asthāda, Chābāda, Bāhāda, Ambāda, and Sollā, of whom the last three were half brothers of the first two.<sup>4</sup> Except Sollā, who continued a merchant and became very wealthy, all the sons entered the service of the state and rose to high stations during the reign of Kṣmārapāla.

In late life Karna married Mīyānalladevī daughter of Jayakeśi son of Subhakeśi king of the Karnaṭaka. According to the Dvyāśraya a wandering painter showed Karna the portrait of a princess whom he described as daughter of Jayakeśi the Kadamba king<sup>5</sup> of

<sup>1</sup> Meaning a large number of Bhils of whom Aśhā was the head.

<sup>2</sup> Forbes' *Bas Mali* (New Ed.), 79.

<sup>3</sup> Probably a Bhil goddess. The name does not sound Sanskrit.

<sup>4</sup> In one passage the Prabandhachintāmaṇi calls these princes half-brothers of Udaya. Further details show that they were half-brothers of one another and sons of Udaya.

<sup>5</sup> This Jayakeśi is Jayakeśi I. son of Shashthadeva (S'uchakeśi) the third of the Goa Kādambas. Jayakeśi's recorded date A.D. 1052 (S. 974) fits well with the time of Karna (Fleet's *Kānarasa Dynasties*, 91). The Prabandhachintāmaṇi tells the following story of the death of Jayakeśi. Jayakeśi had a favourite parrot whom he

Chandrapura<sup>1</sup> in the Dakhan, and who he said had taken a vow to marry Karna. In token of her wish to marry Karna the painter said the princess had sent Karna an elephant. Karna went to see the present and found on the elephant a beautiful princess who had come so far in the hope of winning him for a husband. According to the Prabandhachintamani Karna found the princess ugly and refused to marry her. On this the princess with eight attendants determined to burn themselves on a funeral pyre and Udayāmatī Karna's mother also declared that if he did not relent she too would be a sacrifice. Under this compulsion Karna married the princess but refused to treat her as a wife. The minister Muñjāla, learning from a *kañchukī* or palace-servant that the king loved a certain courtesan, contrived that Miyānalladevī should take the woman's place, a device still practised by ministers of native states. Karna fell into the snare and the queen became pregnant by him, having secured from the hand of her husband his signet ring as a token which could not be disclaimed. Thus in Karna's old age Miyānalladevī became the mother of the illustrious Siddharāja Jayasinha, who, according to a local tradition quoted by Mr. Forbes, first saw the light at Palanpur.<sup>2</sup> When three years old the precocious Siddharāja climbed and sat upon the throne. This ominous event being brought to the king's notice he consulted his astrologers who advised that from that day Siddharāja should be installed as heir-apparent.

The Gujarāt chronicles do not record how or when Karna died. It appears from a manuscript that he was reigning in A.D. 1089 (S. 1145).<sup>3</sup> The Hanumīraṇṇahakāvya says 'The illustrious Karna-deva was killed in battle by king Duśśala of Śakambharī,' and the two appear to have been contemporaries.<sup>4</sup> The author of the Dvyāśraya says that Karna died fixing his thoughts on Vishnu, recommending to Siddharāja his cousin Devaprasāda son of Kṣhemarāja. According to the Prabandhachintamani Vichāraśrenī and Sukṛita-sankīrtana Karna died in A.D. 1094 (S. 1150).

As, at the time of his father's death, Siddharāja was a minor<sup>5</sup> the reins of government must have passed into the hands of his mother Miyānalladevī. That the succession should have been attended with struggle and intrigue is strange. According to the Dvyāśraya Devaprasāda, the son of Kṣhemarāja burned himself on the funeral pile shortly after the death of Karna, an action which was probably the result of some intrigue regarding the succession. Another intrigue

## Chapter II.

THE  
CHAULUKYAS,  
A.D. 961 - 1242.  
Karna,  
A.D. 1084 - 1094.

Siddharāja  
Jayasinha,  
A.D. 1094 - 1143.

one day asked to come out of his cage and dine with him. The parrot said: The cat sitting near you will kill me. The king seeing no cat replied: If any cat kills you I too will die. The parrot left his cage, ate with the king, and was killed by the cat. Jayakesī made ready his funeral pyre, and, in spite of his minister's prayers, taking the dead parrot in his hand laid himself on the funeral pyre and was burned.

<sup>1</sup> Chandrapura is probably Chandāvar near Gokarn in North Kānara.

<sup>2</sup> Rās Malā (New Edition), 83.

<sup>3</sup> Kielhorn's Report on Sanskrit Manuscripts for 1881 page 22.

<sup>4</sup> Duśśala was sixth in descent from Vighnarāja the enemy of Mularāja from whom Karna was fifth in descent.

<sup>5</sup> The date of his installation is given by the author of the Vichāraśrenī as Vikrama S. 1160.

## Chapter II.

THE  
CHAULUKYAS,  
A.D. 961-1242.  
Siddharāja  
Jayasingha,  
A.D. 1094-1143.

ended in the death of Madanapāla brother of Karna's mother queen Udayāmatī, at the hands of the minister Śāntu, who along with Mññjāla and Udā, helped the queen-mother Miyānalladevī during the regency. Mññjāla and Śāntu continued in office under Siddharāja. Another minister built a famous Jain temple named Mahārājabhuvana in Sidhpur at the time when Siddharāja built the Rudramālā. An inscription from a temple near Bhadrēsar in Kacch dated A.D. 1139 (S. 1195 Aśvādha Vad 10, Sunday), in recording grants to Audīchya Brahmans to carry on the worship in an old temple of Udalesvara and in a new temple of Kumārāpālesvara built by Kumārāpāla son of the great prince Āsapāla,<sup>1</sup> notes that Dadaka was then minister of Siddharāja. Among his generals the best known was a chief named Jagaddeva (Jag Dev), commonly believed to be a Paramāra, many of whose feats of daring are recorded in bardic and popular romances.<sup>2</sup> Though Jag Dev is generally called a Paramāra nothing of his family is on record. The author of the Prabandhachintāmani describes Jagaddeva as a thrice valiant warrior held in great respect by Siddharāja. After Siddharāja's death Jagaddeva went to serve king Permādi to whose mother's family he was related.<sup>3</sup> Permādi gave him a chiefship and sent him to attack Malava.

When Siddharāja attained manhood his mother prepared to go in great state on pilgrimage to Somanātha. She went with rich offerings as far as Bāmloda apparently the large modern village of Bholāda on the Gujarāt-Kathiavada frontier about twenty-two miles south-west of Dholkā. At this frontier town the Anahilavāda kings levied a tax on all pilgrims to Somanātha. Many of the pilgrims unable to pay the tax had to return home in tears. Miyānalladevī was so saddened by the woes of the pilgrims that she stopped her pilgrimage and returned home. Siddharāja met her on the way and asked her why she had turned back. Miyānalladevī said, I will neither eat nor go to Somanātha until you order the remission of the pilgrim tax. Siddharāja called the Bholāda treasurer and found that the levy yielded 72 lakhs a year.<sup>4</sup> In spite of the serious sacrifice Siddharāja broke the board authorizing the levy of the tax and pouring water from his hand into his mother's declared that the merit of the remission was hers. The queen went to Somanātha and worshipped the god with gold presenting an elephant and other gifts and handing over her own weight in money.

According to the Prabandhachintāmani while Miyānalladevī and Siddharāja were on pilgrimage Yasovarman king of Mālwa continually harassed the Gurjjara-Maṇḍala. Śāntu who was in charge of the kingdom asked Yasovarman on what consideration he would retire.

<sup>1</sup> Āsapāla and Kumārāpāla appear to be local chiefs.

<sup>2</sup> Compare Forbes' *Ras Mal*, I. 114-153.

<sup>3</sup> Goa Kulāmba inscriptions say that Jagaddeva was the cousin of the Goa Kādamba king Vijayarka the nephew of Miyānalladevī and call him by courtesy the younger brother of Vijayarka's son Jayakesī II. He would seem to have been held in esteem by Vijayarka and his son Jayakesī, to have then gone for some time to Siddharāja, and after leaving Siddharāja to have transferred his services to Permādi. His being called Paramāra may be due to his connection with Permādi. Fleet's *Kānarese Dynasties*, 91.

<sup>4</sup> Seventy-two a favourite number with Indian authors.

Yaśovarman said he would retire if Siddharāja gave up to him the merit of the pilgrimage to Somesvara. Santu washed his feet and taking water in his hand surrendered to Yaśovarman the merit of Siddharāja, on which, according to his promise, Yaśovarman retired. On his return Siddharāja asked Santu what he meant by transferring his sovereign's merit to a rival. Santu said, 'If you think my giving Yaśovarman your merit has any importance I restore it to you.' This curious story seems to be a Jain fiction probably invented with the object of casting ridicule on the Brāhmanical doctrine of merit. Yaśovarman was not a cotemporary of Siddharāja. The Malwa king referred to is probably Yaśovarman's predecessor Naravarman, of whom an inscription dated A.D. 1134 (S. 1190) is recorded.

Under the name Sadharo Jesingh, Siddharāja's memory is fresh in Gujarāt as its most powerful, most religious, and most charitable ruler. Almost every old work of architectural or antiquarian interest in Gujarāt is ascribed to Siddharāja. In inscriptions he is styled The great king of kings, The great lord The great Bhāṭṭāraka, The lord of Avantī, The hero of the three worlds, The conqueror of Barbaraka, The universal ruler Siddha, The illustrious Jayasimhadeva. Of these the commonest attributes are Siddhachakravartin the Emperor of Magic and Siddharāja the Lord of Magic, titles which seem to claim for the king divine or supernatural powers.<sup>1</sup> In connection with his assumption of these titles the Kumārapālprabandha, the Dvyāśraya, and the Prabandhachintāmani tell curious tales. According to the Dvyāśraya, the king wandering by night had subdued the Bhūtas, Sākinis, and other spirits. He had also learnt many *mantras* or charms. From what he saw at night he would call people in the day time and say 'You have such a cause of uneasiness' or 'You have such a comfort.' Seeing that he knew their secrets the people thought that the king knew the hearts of all men and must be the *avatāra* of some god. A second story tells how Siddharāja helped a Nāga prince and princess whom he met by night on the Sarasvatī.<sup>2</sup> According to a third story told in the Kumārapālprabandha two Yognis or nymphs came from the Himalayas and asked the king by what mystic powers he justified the use of the title Siddharāja. The king agreed to perform some wonders in open court in the presence of the nymphs. With the help of a former minister, Lūpala, the king had a dagger prepared whose blade was of sugar and its handle of non-set with jewels. When the king appeared in court to perform the promised wonders a deputation of ambassadors from king Permādi of Kalyānakataka<sup>3</sup> was

## Chapter II.

THE  
CHAULUKYAS,  
A.D. 961 - 1242.  
Siddharāja  
Jayasingha,  
A.D. 1094 - 1143.

<sup>1</sup> Prabandhachintāmani and Kumārapālcharita.

<sup>2</sup> Dr. Kielhorn's Report on Sanskrit Manuscripts for 1881 page 22.

<sup>3</sup> The Kumārapālcharita says that the title was assumed on the conquest of Barbaraka. The verse is :

सिद्धो बर्बरकक्षस्य सिद्धराजस्ततोभवत्

that is, by him the demon Barbaraka was vanquished, therefore he became Siddharāja The Lord of Magical Power.

<sup>4</sup> Ind. Ant. IV. 265.

<sup>5</sup> This Permādi may be the Goa Kādamba chief Permādi Sivachitta (A.D. 1147 - 1175), who was heir-apparent in the time of Siddharāja, or the Sinda chief Permādi who was a cotemporary of Siddharāja and flourished in A.D. 1144.

Chapter II.  
THE  
CHAULUKYAS,  
A.D. 961 - 1242.  
Siddharāja  
Jayasīnha,  
A.D. 1094 - 1143.

announced. The deputation entered and presented the prepared dagger as a gift from their lord. The king kept the prepared dagger and in its stead sent all round the court a real dagger which was greatly admired. After the real dagger had been seen and returned the king said : I will use this dagger to show my mystic powers, and in its place taking the false dagger ate its sugar blade. When the blade was eaten the minister stopped the king and said 'Let the Yoginīs eat the handle. The king agreed and as the Yoginīs failed to eat the handle which was iron the superiority of the king's magic was proved.

A fourth story in the Dvyāśraya tells that when the king was planning an invasion of Mālwa a Yoginī came from Ujjain to 'Patan and said 'O Rāja, if you desire great fame, come to Ujjain and humbly entreat Kāhka and other Yoginīs and make friends with Yasovarman the Rāja of Ujjain.' The king contemptuously dismissed her, saying, 'If you do not fly hence like a female crow, I will cut off your nose and ears with this sword.'

So also the king's acts of prowess and courage were believed to be due to magical aid. According to the common belief Siddharāja did his great acts of heroism by the help of a demon named Báraro, whom he is said to have subdued by riding on a corpse in a burying ground. The story in the Prabandhaśmṛtāmāni is similar to that told of the father of Īlarshavardhana who subdued a demon with the help of a Yogī. It is notable that the story had passed into its present form within a hundred years of Siddharāja's death. Somesvara in his Kīrtikanmudī says, 'This moon of kings fettered the prince of goblins Barbaraka in a burial-place, and became known among the crowd of kings as Siddharāja.' Older records show that the origin of the story, at least of the demon's name, is historical being traceable to one of Siddharāja's copperplate attributes Barbaraka-jishṇu that is conqueror of Barbaraka. The Dvyāśrayakosha represents this Barbara as a leader of Rākshasas or Mlechhas, who troubled the Brāhmins at Śrīsthala-Siddhapura. Jayasīnha conquered him and spared his life at the instance of his wife Puṅgalikā. Afterwards Barbara gave valuable presents to Jayasīnha and 'served him as other Rajputs'.<sup>1</sup> Barbaraka

<sup>1</sup> Ind. Ant. IV. 2. Regarding Barbaraka Doctor Buhler remarks in Ind. Ant. VI. 167 : 'The Varvarakas are one of the non Aryan tribes which are settled in great numbers in North Gujarat, Koli, Bhil, or Mer.' Siddharāja's contests with the Barbarakas seem to refer to what Tod (Western India, 173 and 196) describes as the inroads of mountaineers and foresters on the plains of Gujarat during the eleventh and twelfth centuries. To attempt to identify Bhil, Barbar or Varvaris is hazardous. The name Barbar is of great age and is spread from India to Morocco. Wilson (Works, VII. 176) says : 'The analogy between Barbaras and barbarians is not in sound only. In all Sanskrit authorities Barbaras are classed with borderers and foreigners and nations not Hindu. According to Sir Henry Rawlinson (Ferrier's Caravan Journeys, 223 note) tribes of Berbers are found all over the east. Of the age of the word Canon Rawlinson (Herodotus, IV. 252) writes : Barbar seems to be the local name for the early race of Accad. In India Ptolemy (A.D. 150; McCrindle's Edn. 146) has a town Barbarei on the Indus and the Periplus (A.D. 247; McCrindle's Ed. 108) has a trade-centre Barbarikon on the middle mouth of the Indus. Among Indian writings, in the Rāmāyana (Hall in Wilson's Works, VII. 176 Note \*) the Barbaras appear between the Tukharas and the Kambojas in the north; in the Mahābhārata (Muir's Sanskrit Texts, I. 481-2) in one list Var-varas are entered between Savaras and Sakas and in another list (Wilson's Works, VII. 176)

seems to be the name of a tribe of non-Aryans whose modern representatives are the Bābariās settled in South Kāthiāvāḍa in the province still known as Bābariāvāḍa.

A Dohad inscription of the time of Siddharāja dated A.D. 1140 (S. 1196) says of his frontier wars: 'He threw into prison the lords of Surāshtra and Mālwa; he destroyed Sindhurāja and other kings; he made the kings of the north bear his commands.' The Surāshtra king referred to is probably a ruler of the Khir or Chudāsana tribe

## Chapter II.

THE  
CHAULUKYAS,  
A.D. 961-1242.  
Siddharāja  
Jayasingha,  
A.D. 1094-1143.

Barbariās come between Kiratas and Siddhas. Finally (As. Res. XV. 47 footnote) Barbara is the northmost of the Seven Konkanas. The names Barbari in Ptolemy and Barharikon in the Perplus look like some local place-name, perhaps Baulhara, altered to a Greek form. The Hindu tribe names, from the sameness in sound as well as from their position on the north-west border of India, suggest the Mongol tribe Jnan-Juān or Var-Var, known to the western nations as Avārs who drove the Little Ymehi out of Balkh in the second half of the fourth century, and, for about a hundred years, ruled to the north and perhaps also to the south of the Hindu Kush. (Specht in *Journal Asiatique* 1883. II 390-410; Howarth in *Jour R A S XXI* 721-810.) It seems probable that some of these Var-Vars passed south either before or along with the White Huns (A.D. 450-550). Var, under its Mongol plural form Avarti (Howarth, *Ibid.* 722), closely resembles Avartiya one of the two main divisions of the Kadās of Kacch (Mr. Erskine's List in *J. Bom. Geo Soc* II 59-60 for Aug. 1838). That among the forty-seven clans included under the Avartiyas four (Nos. 30, 35, 42, and 43) are Babariyas, suggests that the Kāthīs received additions from the Var-Vars at different times and places. Dr. Bühler (*Ind. Ant.* VI. 186) thinks that the Babato or Barhar or Var-Var who gave trouble to Siddharāja represent some early local non-Aryan tribe. The fact that they are called Rak-hasas and Mlecchas and that they stopped the ceremonies at Siddpur north of Anahlavāḍa seems rather to point to a foreign invasion from the north than to a local uprising of hill tribes. Though no Muhammadan invasion of Gujarat during the reign of Siddharāja is recorded a Jesalmir legend (Forbes' *Rās Mala*, I. 175) tells how Lanja Bhiran the Bhatti prince who married Siddharāja's daughter was hated by his mother-in-law as the bulwark of Anahlavāḍa against the power of the king who grows too strong. This king may be Bahahm the Indian victor of the Ghaznavid Bahram Shāh (A.D. 1116-1157). Bahahm (*Elliot*, II. 279; *Bugge's Feristā*, I. 151) collected an army of Arabs, Persians, Afghans, and Khiljis, repaired the fort of Nagor in the province of Sewalik, and committed great devastations in the territories of the independent Indian rulers. He threw off allegiance to Ghazni and advancing to meet Bahram Shāh near Multān was defeated and slain. Except that they were nomadismers and that Bahahm's is the only known invasion from the north during Siddharāja's reign nothing has been found connecting Barbari and Bahahm. At the same time that the Barhar or Var-Var of the Gujarāt writers may have been non-Hindu mercenaries from the north-west frontier whom Siddharāja admitted as Hindu subjects is made not unlikely by two incidents preserved by the Muhammadan historians. The *Tarikh-i-Sorāth* (Bayley's *Gujarāt*, 36 Note \*) tells how in A.D. 1178 from the defeated army of Shahāh-ud-din Ghori the Turkish Afghān and Moghal women were distributed the higher class to high caste and the commoner to low caste Hindus. Similarly how the better class of male captives were admitted among Chakāval and Wāḍhal Rajputs and the lower among Khānts, Kohs, Bābriās, and Mers. Again about thirty years later (A.D. 1210) when his Turk mercenaries, who were not converted to Islam, revolted against Shams-ud-din Altamsh they seized Delhi and built Hindu temples (*Elliot*, II. 237-239). These cases seem to make it likely that among Bahahm's mercenaries were some un-Islamised North Indian Var-Vars and that they were admitted into Hinduism by Siddharāja and as the story states served him as other Rajputs. Some of the new-comers as noted above seem to have merged into the Kāthīs. Others founded or joined the Bābariās who give their name to Bābariāvāḍa a small division in the south of Kāthiāvāḍa. Though the tribe is now small the 72 divisions of the Bābariās show that they were once important. One of their leading divisions preserves the early form Var (Kāthiawār *Gazetteer*, 132-133) and supports their separate northern origin, which is forgotten in the local stories that they are descended from Jetvas and Ahirs and have a Brāhman element in their ancestry. (Tod's *Western India*, 413; Kāthiawār *Gazetteer*, 132-123.) Of the Var-Vars in their old seats a somewhat doubtful trace remains in the Barbaris a tribe of Hazārās near Horat (Bellev in *Imp. and As. Quar. Review* Oct. 1891 page 328) and in the Panjāb (Ibbetson's *Census*, 586) Bhābras a class of Panjāb Jains.

**Chapter II.**  
**THE**  
**CHALUKYAS,**  
**A.D. 961 - 1212.**  
 Siddharaja  
 Jayasingha,  
 A.D. 1094 - 1143.

whose head-quarters were at Junágadh. According to the Prabandha-chintāmaṇi Siddharāja went in person to subdue Noghan or Navaghani the Khir ruler of Surāshtra; he came to Vardhamānapura that is Vadhvan and from Vadhvan attacked and slew Noghan. Jinaprabhasūri the author of the Tīrthakalpa says of Gīrnār that Jayasinha killed the king named Khengār and made one Sajjana his viceroy in Surashtra. So many traditions remain regarding wars with Khengār that it seems probable that Siddharaja led separate expeditions against more than one king of that name. According to tradition the origin of the war with Khengār was a woman named Rānakadevī whom Khengār had married. Rānakadevī was the daughter of a potter of Majevādi village about nine miles north of Junágadh, so famous for her beauty that Siddharaja determined to marry her. Meanwhile she had accepted an offer from Khengār whose subject she was and had married him. Siddharaja enraged at her marriage advanced against Khengār, took him prisoner, and annexed Sorath. That Khengār's kingdom was annexed and Sajjana, mentioned by Jinaprabhasūri, was appointed Viceroy is proved by a Gīrnār inscription dated A.D. 1120 (S. 1176).

An era called the Simha Samvatsara connected with the name of Jayasinha and beginning with A.D. 1113-1114 (S. 1169-70), occurs in several inscriptions found about Prabhāsa and South Kāthiavāda. This era was probably started in that year in honour of this conquest of Khengār and Sorath<sup>1</sup>. The earliest known mention of the Simha Samvatsara era occurs in a step-well at Māngrol called the Sodhali Yāv. The inscription is of the time of Kumārāpala and mentions Sahajiga the father of Mūlaka the grantor as a member of the bodyguard of the Chālukyas. The inscription states that Sahajiga had several sons able to protect Saurāshtra, one of whom was Somarāja who built the temple of Sahajigeśvara, in the enclosure of the Somanatha temple at Prabhāsa; another was Mūlaka the *nāyaka* of Surashtra, who is recorded to have made grants for the worship of the god by establishing cesses in Mangalapura or Māngrol and other places. The inscription is dated A. D. 1146 (Monday the 13th of the dark half of Āśvīn Vikrama S. 1202 and Simha S. 32). This inscription supports the view that the Simha era was established by Jayasinha, since if the era belonged to some other local chief, no Chālukya viceroy would adopt it. The Simha era appears to have been kept up in Gujarāt so long as Anahilapura rule lasted. The well known Verāval inscription of the time of Arjunadeva is dated Hijri 662, Vikrama S. 1320, Valabhi S. 945, Simha S. 151, Sunday the 13th of Ashādhā Vadi. This inscription shows that the Simha era was in use for a century and a half during the sovereignty of Anahilavāda in Surāshtra.

Regarding Sajjana Siddharāja's first viceroy in Surāshtra, the Prabandhachintāmaṇi says that finding him worthy the king appointed Sajjana the *daṇḍādhipati* of Surāshtradēśa. Without consulting his master Sajjana spent three years' revenue in building a stone temple of

<sup>1</sup> Abhayatilaka Gaṇi who revised and completed the Dvyāśraya in Vikrama S. 1312 (A.D. 1256) says, in his twentieth Sarga, that a new era was started by Kumārāpala. This would seem to refer to the Simha era.

## THE CHAULUKYAS.

Neminátha on Girnár instead of a wooden temple which he removed. In the fourth year the king sent four officers to bring Sajjana to Aṇahilaváḍa. The king called on Sajjana to pay the revenues of the past three years. In reply Sajjana asked whether the king would prefer the revenue in cash or the merit which had accrued from spending the revenue in building the temple. Preferring the merit the king sanctioned the spending of the revenues on the Tirtha and Sajjana was reappointed governor of Sorath.<sup>1</sup> This stone temple of Sajjana would seem to be the present temple of Neminátha, though many alterations have been made in consequence of Muhammadan sacrilege and a modern enclosure has been added. The inscription of Sajjana which is dated A.D. 1120 (S. 1176) is on the inside to the right in passing to the small south gate. It contains little but the mention of the Sádhū who was Sajjana's constant adviser. On his return from a second pilgrimage to Somnātha Siddharāja who was encamped near Raivataka that is Girnár expressed a wish to see Sajjana's temple. But the Bráhmans envious of the Jains persuaded the king that as Girnár was shaped like a *ling* it would be sacrilege to climb it. Siddharāja respected this objection and worshipped at the foot of the mountain. From Girnár he went to Satruñjaya. Here too Bráhmans with drawn swords tried to prevent the king ascending the hill. Siddharāja went in disguise at night, worshipped the Jain god Adis'vara with Ganges water, and granted the god twelve neighbouring villages. On the hill he saw so luxuriant a growth of the *sallaki* a plant dear to elephants, that he proposed to make the hill a breeding place for elephants a second Vindhya. He was reminded what damage wild elephants would cause to the holy place and for this reason abandoned his plan.

Siddharāja's second and greater war was with Málwa. The cotemporary kings of Málwa were the Paramára ruler Naravarman who flourished from A.D. 1104 to 1133 (S. 1160-1189) and his son and successor Yaśovarman who ruled up to A.D. 1143 (S. 1199) the year of Siddharāja's death. As the names of both these kings occur in different accounts of this war, and, as the war is said to have lasted twelve years, it seems that fighting began in the time of Naravarman and that Siddharāja's final victory was gained in the time of Yaśovarman in Siddharāja's old age about A.D. 1134 (S. 1190). This view is supported by the local story that his expedition against Yaśovarman was undertaken while Siddharāja was building the Sahasraliṅga lake and other religious works. It is not known how the war arose but the statement of the Prabandhachintāmaṇi that Siddharāja vowed to make a scabbard of Yaśovarman's skin seems to show that Siddharāja received grave provocation. Siddharāja is said to have left the building of the Sahasraliṅga lake to the masons and architects and himself to have

## Chapter II.

THE  
CHAULUKYAS,  
A.D. 961-1242.  
Siddharāja  
Jayasingha,  
A.D. 1094-1143.

<sup>1</sup> The Kumárapála-charita states that Sajjana died before the temple was finished, and that the temple was completed by his son Paraśurāma. After the temple was finished Siddharāja is said to have come to Somnātha and asked Paraśurāma for the revenues of Sorath. But on seeing the temple on Girnár he was greatly pleased, and on finding that it was called Karva-vihāra after his father he sanctioned the outlay on the temple.

## Chapter II.

## THE

CHAUUKYA,  
A.D. 961-1242.Siddharāja  
Jayasīṃha,  
A.D. 1094-1143.

started for Málwa. The war dragged on and there seemed little hope of victory when news reached Siddharāja that the three south gates of Dhárā could be forced. With the help of an elephant an entrance was effected. Yaśovarman was captured and bound with six ropes, and, with his captured enemy as his banner of victory, Siddharāja returned to Apahilapura. He remembered his vow, but being prevented from carrying it out, he took a little of Yaśovarman's skin and adding other skin to it made a scabbard. The captured king was thenceforward kept in a cage. It was this complete conquest and annexation of Málwa that made Siddharāja assume the style of Avantínátha 'Lord of Avantī,' which is mentioned as his *biruda* or title in most of the Chaulukya copperplates.<sup>1</sup> Málwa henceforward remained subject to Apahilaváda. On the return from Málwa an army of Bhils, who tried to block the way were attacked by the minister Sántu and put to flight.

Siddharāja's next recorded war is with king Madanavarman the Chandela king of Mahobaka the modern Mahobá in Bundelkhand. Madanavarman, of whom General Cunningham has found numerous inscriptions dating from A.D. 1130 to 1164 (S. 1186-1220),<sup>2</sup> was one of the most famous kings of the Chandela dynasty. An inscription of one of his successors in Kálanjar fort records that Madanavarman 'in an instant defeated the king of Gurjjara, as Krishna in former times defeated Kamsa,' a statement which agrees with the Gujarát accounts of the war between him and Jayasīṃha. In this conflict the Gujarát accounts do not seem to show that Siddharāja gained any great victory; he seems to have been contented with a money present. The Kirtikaumudī states that the king of Mahobaka honoured Siddharāja as his guest and paid a fine and tribute by way of hospitality. The account in the Kumárapálacharita suggests that Siddharāja was compelled to come to terms and make peace. According to the Kirtikaumudī, and this seems likely, Siddharāja went from Dhárā to Kálanjara. The account in the Prabandhachintāmani is very confused. According to the Kumárapálacharita, on Siddharāja's way back from Dhárā at his camp near Patan a bard came to the court and said to the king that his court was as wonderful as the court of Madanavarman. The bard said that Madanavarman was the king of the city of Mahobaka and most clever, wise, liberal, and pleasure-loving. The king sent a courtier to test the truth of the bard's statement. The courtier returned after six months declaring that the bard's account was in no way exaggerated. Hearing this Siddharāja at once started against Mahobaka and encamping within sixteen miles of the city sent his minister to summon Madanavarman to surrender. Madanavarman who was enjoying himself took little notice of the minister. This king, he said, is the same who had to fight twelve years with Dhárā; if, as is probable, since he is a *kabádi* or wild king, he wants money, pay him what he wants. The money

<sup>1</sup> Ind. Ant VI 194ff. Dr. Bühler (Ditto) takes Avantínátha to mean Siddharāja's opponent the king of Málwa and not Siddharāja himself.

<sup>2</sup> Archaeological Survey Report, XXI. 86

<sup>3</sup> Jour. B. A. Soc. (1848), 319.

was paid. But Siddharāja was so struck with Madanavarman's indifference that he would not leave until he had seen him. Madanavarman agreed to receive him. Siddharāja went with a large bodyguard to the royal garden which contained a palace and enclosed pleasure-house and was guarded by troops. Only four of Siddharāja's guards were allowed to enter. With these four men Siddharāja went in, was shown the palace garden and pleasure-houses by Madanavarman, was treated with great hospitality, and on his return to Patan was given a guard of 120 men.

The Dvyāsraya says that after his conquest of Ujjain Siddharāja seized and imprisoned the king of a neighbouring country named Sim. We have no other information on this point.

The Dohad inscription dated A.D. 1140 mentions the destruction of Sindhurāja that is the king of Sindh and other kings. The Kīrtikaumudī also mentions the binding of the lord of Sindhu. Nothing is known regarding the Sindh war. The Kīrtikaumudī mentions that after a war with Arjorāja king of Sāmbar Siddharāja gave his daughter to Arjorāja. This seems to be a mistake as the war and alliance with Arjorāja belong to Kumārāpāla's reign.

Siddharāja, who like his ancestors was a Śaiva, showed his zeal for the faith by constructing the two grandest works in Gujarāt the Rudramahālaya at Siddhpur and the Sahasralinga lake at Patan. The Jain chroniclers always try to show that Siddharāja was favourably inclined to Jainism. But several of his acts go against this claim and some even show a dislike of the Jains. It is true that the Jain sage Hemāchārya lived with the king, but the king honoured him as a scholar rather than as a Jain. On the occasion of the pilgrimage to Somanātha the king offered Hemāchārya a palanquin, and, as he would not accept the offer but kept on walking, the king blamed him calling him a learned fool with no worldly wisdom. Again on one occasion while returning from Mālwa Siddharāja encamped at a place called Śrīnagara, where the people had decorated their temples with banners in honour of the king. Finding a banner floating over a Jain temple the king asked in anger who had placed it there, as he had forbidden the use of banners on Jain shrines and temples in Gujarāt. On being told that it was a very old shrine dating from the time of Bharata, the king ordered that at the end of a year the banner might be replaced. This shows the reverse of a leaning to Jainism. Similarly, according to the Prabandhachintāmaṇi, Hemāchārya never dared to speak to the king in favour of Jainism but used to say that all religions were good. This statement is supported by the fact that the opening verses of all works written by Hemāchārya in the time of Siddharāja contain no special praise of Jain deities.

So great is Siddharāja's fame as a builder that almost every old work in Gujarāt is ascribed to him. Tradition gives him the credit of the Dabhoi fort which is of the time of the Vāghelā king Viradhavala, A.D. 1220-1260. The Prabandhachintāmaṇi gives this old verse regarding Siddharāja's public works : ' No one makes a great temple (Rudramahālaya), a great pilgrimage (to Somanātha), a great Āsthāna (darbhār hall), or a great lake (Sahasralinga)

## Chapter II.

THE  
CHAULUKYAS,  
A.D. 961-1242.  
Siddharāja  
Jayasingha,  
A.D. 1094-1143.

Chapter II.  
THE  
CHAULUKYAS,  
A.D. 961-1212.  
Siddharāja  
Jayasīngha,  
A.D. 1094-1113.

such as Siddharāja made.<sup>1</sup> Of these the Rudramahālaya, though very little is left, from its size and the beauty of its carving, must have been a magnificent work the grandest specimen of the architecture of the Solanki period. The remains of the Sahasralīnga lake at Anahilapura show that it must have been a work of surprising size and richness well deserving its title of *mahāsara* or great lake. Numerous other public works are ascribed to Siddharāja.

At this period it seems that the kings of Gujarāt Sāmbhar and other districts, seeing the great reputation which his literary tastes had gained for Bhoja of Dhārā used all to keep ~~Pandits~~. Certain carvings on the pillars of a mosque at the south-west of the modern town of Dhārā show that the building almost as it stands was the Sanskrit school founded by Bhoja. The carvings in question are beautifully cut Sanskrit grammar tables. Other inscriptions in praise of Naravarman show that Bhoja's successors continued to maintain the institution. In the floor of the mosque are many large shining slabs of black marble, the largest as much as seven feet long, all of them covered with inscriptions so badly mutilated that nothing can be made out of them except that they were Sanskrit and Prakrit verses in honour of some prince. On a rough estimate the slabs contain as many as 4000 verses.<sup>3</sup> According to the old saying any one who drank of the Sarasvatī well in Dhārā became a scholar. Sarasvatī's well still exists near the mosque. Its water is good and it is still known as Akkal-kui or the Well of Talent. As in Dhārā so in Ajmer the Arhāt-dinkā Jhopdā mosque is an old Sanskrit school, recent excavations having brought to light slabs with entire dramas carved on them. So also the Gujarāt kings had their Pandits and their halls of learning. Śrīpāla, Siddharāja's poet-laureate, wrote a poetical eulogium or *prastuti* on the Sahasralīnga lake. According to the Prabandha-chintāmaṇi Siddharāja gathered numerous Pandits to examine the eulogium. As has already been noticed Siddharāja's constant companion was the great scholar and Jain *āchārya* Hemachandra also called Hemāchārya, who, under the king's patronage, wrote a treatise on grammar called Siddhahema, and also the well-known Dvyāśrayakosha which was intended to teach both grammar and the history of the Solankis. Hemachandra came into even greater

<sup>1</sup> The original verse is महालयो महायात्रा महास्थानं महासरः यत्कृतं सिद्धराजेन क्रियते तत्र केनचित् ॥

<sup>2</sup> These, as quoted by Rāo Sāheh Mahipatrām Rāprām in his Sadhara Jesangh, are, the erection of charitable feeding-houses every *yajana* or four miles, of Dabhol fort, of a *kunda* or reservoir at Kipadvanj, of the Malavya lake at Dholkā, of small temples, of the Rudramahālaya, of the Rān's step-well, of the Sahasralīnga lake, of reservoirs at Silor, of the fort of Sāela, of the Daśasahasra or ten thousand temples, of the Muna lake at Virangām, of the *gadhs* or forts of Dadharapur Vadhvān Anantapur and Chabari, of the Sardhār lake, of the *gadhs* of Jhinjhavāda, Virpur, Bhāuula, Vasingapura, and Tūān, of the palaces of Kandola and Silhi Jagapura, of the reservoirs of Dedādrī and Kīrtī-stambha and of Jitpur-Anantpura. It is doubtful how many of these were actually Siddharāja's works.

<sup>3</sup> One of the best preserved slabs was sent by Sir John Malcolm when Resident of Mdwā to the Museum of the B. B. R. A. S., where it still lies. It has verses in twelfth century Prakrit in honour of a king, but nothing historical can be made out of it.

prominence in the time of Kumārapāla, when he wrote several further works and became closely connected with the state religion. Several stories remain of Siddharāja assembling poets, and holding literary and poetic discussions.

Record is preserved of a *sabhā* or assembly called by the king to hear discussions between a Śvetāmbara Jaina *ācharya* named Bhattāraka Devasūri and a Digambara Jaina *ācharya* named Kumudachandra who had come from the Karnātuk. Devasūri who was living and preaching in the Jain temple of Arishthanemi at *Arishthanemi*,<sup>1</sup> that is the modern Ahmadābād, was there visited by Kumudachandra. Devasūri treated his visitor with little respect telling him to go to Patan and he would follow and hold a religious discussion or *vāda*. Kumudachandra being a Digambara or sky-clad Jaina went naked to Patan and Siddharāja honoured him because he came from his mother's country. Siddharāja asked Hemachandra to hold a discussion with Kumudachandra and Hemachandra recommended that Devasūri should be invited as a worthy disputant. At a discussion held before a meeting called by the king Kumudachandra was vanquished, probably because the first principle of his Digambara faith that no woman can attain *nirvāṇa*, was insulting to the queen-mother, and the second that no clothes-wearing Jain can gain *mukti* or absorption, was an insult to the Jain ministers. The assembly, like Brāhmanical *sabhās* at the present day, appears to have declined into noise and Siddharāja had to interfere and keep order. Devasūri was complimented by the king and taken by one Ahada with great honour to his newly built Jaina temple.<sup>2</sup>

In spite of prayers to Somanūtha, of incantations, and of gifts to Brāhmins, Siddharāja Jayasinha had no son. The throne passed into the line of Tribhuvanapāla the great-grandson of Bhīmadeva I. (A.D. 1071-62) who was ruling as a feudatory of Siddharāja at his ancestral appanage of Dahithālī. Tribhuvanapāla's pedigree is Bhīmadeva I.; his son Kshemarāja by Bakuladevī a concubine; his son Haripāla; his son Tribhuvanapāla. By his queen Kāsmīradevī Tribhuvanapāla had three sons Mahipāla, Kīrttipāla, and Kumārapāla, and two daughters Premaladevī and Devaladevī. Premaladevī was married to one of Siddharāja's nobles a cavalry general named Kābhada or Krishnadeva: Devaladevī was married to Anorāja<sup>3</sup> or Anarāja

## Chapter II.

THE  
CHAULUKYAS,  
A.D. 961-1242.  
Siddharāja  
Jayasinha,  
A.D. 1094-1143.

Kumārapāla,  
A.D. 1143-1174.

<sup>1</sup> See above page 170.

<sup>2</sup> Devasūri was born in S. 1131 (A.D. 1078), took *dikṣā* in S. 1152 (A.D. 1096), became a Sūri in S. 1174 (A.D. 1118), and died on a Thursday in the dark half of Śrāvaṇa S. 1226 (A.D. 1170). His famous disciple Hemachandra was born on the fullmoon of Kartika S. 1145 (A.D. 1089),<sup>3</sup> became an ascetic in S. 1150 (A.D. 1094), and died in S. 1229 (A.D. 1173).

<sup>3</sup> The Prākṛit local name was Āno, of which the Sanskritised forms would appear to be Arno, Arnava, A'nika, and A'nalla as given in the Hammīramahākāvya.<sup>4</sup> The genealogy of these kings of Śākambhari or Śāmbhar is not settled. The Nadol copper-plate dated Samvat 1218 gives the name of its royal grantor as Alan and of Alan's father as Māharāja (Tod's Rajasthan, I. 804), the latter apparently a mistake for Anarāja which is the name given in the Dvyāśraya. Alan's date being V. 1218, the date of his father A'na would fit in well with the early part of Kumārapāla's reign. The order of the two names Āhana and Analla in the Hammīramahākāvya would seem to be mistaken and ought to be reversed.

## Chapter II.

## THE

CHAULUKYAS,  
A.D. 961 - 1242.  
Kumárapála,  
A.D. 1143 - 1174.

king of Sákambhari or Sámbar, the Analladeva of the Hammira-mahákavya. Kumárapála himself was married by his father to one Bhupáladeví. According to the Dvyáśraya, Tribhuvanapála was on good terms with Siddharāja serving him and going with him to war. The Kumárapálacharita also states that Kumárapála used to attend the court of Siddharāja. But from the time he came to feel that he would have no son and that the bastard Kumárapála would succeed him Siddharāja became embittered against Kumárapála. According to the Jain chronicles Siddharāja was told by the god Somanátha, by the sage Hemachandra, by the goddess Ambikā of Kodinār,<sup>1</sup> and by astrologers that he would have no son and that Kumárapála would be his successor. According to the Kumárapálacharita so bitter did his hate grow that Siddharāja planned the death of Tribhuvanapála and his family including Kumárapála. Tribhuvanapála was murdered but Kumárapála escaped. Grieved at this proof of the king's hatred Kumárapála consulted his brother-in-law Krishnadeva who advised him to leave his family at Dahithalí and go into exile promising to keep him informed of what went on at Anahilapura. Kumárapála left in the disguise of a *jaṭādhāri* or recluse and escaped the assassins whom the king had ordered to slay him. After some time Kumárapála returned and in spite of his disguise was recognized by the guards. They informed the king who invited all the ascetics in the city to a dinner. Kumárapála came but noticing that the king recognized him in spite of his disguise, he fled. The king sent a trusted officer with a small force in pursuit. Kumárapála persuaded some husbandmen, the chief of whom was Bhūnasimha, to hide him in a heap of thorns. The pursuers failing to find him returned. At night Kumárapála was let out bleeding from the thorns, and promised the husbandmen that the day would come when their help would be rewarded. He then shaved his topknot or *jaṭā* and while travelling met with a lady named Devaśrī of Udainbara village who pitying him took him into her chariot and gave him food. Kumárapála promised to regard her as a sister. He then came to Dahithalí where the royal troops had already arrived. Siddharāja sent an army which invested the village leaving Kumárapála without means of escape. He went to a potter named Sajjana or Alinga who hid him in the flues of his brick-kiln throwing hay over him. The troops searched the village, failed to find Kumárapála, and retired. The potter then helped Kumárapála from his hiding place and fed him. A former friend named Bosari joined Kumárapála and they went away together Kumárapála commending his family to the care of Sajjana. On the first day they had no food. Next day Bosari went to beg and they together ate the food given to Bosari in a monastery or *maṭh* where they slept. In time they came to Cambay where they called upon Hemachārya and asked him their future. Hemachārya knew and recognized Kumárapála. Kumárapála asked when fate would bless him. Before Hemachārya

<sup>1</sup> Kodinār is a town in Gáikwār territory in South Káthiávāda. This temple of Ambikā is noticed as a place of Jain pilgrimage by the sage Jīnaprabhasūri in his Tīrthakalpa and was a well-known Jain shrine during the Anahilavāda period.

could reply Udayana, one of the king's ministers, came. Hemácharya said to Udayana, 'This is Kumárapála who shall shortly be your king.' Hemácharya also gave Kumárapála a writing stating that he would succeed to the throne. Kumárapála acknowledged his obligations to Hemácharya and promised to follow his advice. Udayana took him to his house and gave him food and clothes. Siddharája came to know of this and sent his soldiers who began to search. Kumárapála returned to Hemácharya who hid him in a cellar covering its door with manuscripts and palm leaves. The soldiers came but failed to search under the manuscripts and returned. Kumárapála acknowledged his obligations to Hemácharya and said he owed him two great debts one for telling him the day on which he would come to the throne; the other for saving his life. Kumárapála left Cambay at midnight, the minister Udayana supplying him with provisions. From Cambay he went to Vaṭapadrapura probably Baroda, where feeling hungry he entered the shop of a Vánia named Katuka and asked for parched gram. The Vánia gave the gram and seeing that Kumárapála had no money accepted his promise of future payment. From Baroda he came to Bhrigukachh or Broach where he saw a soothsayer and asked him his future. The soothsayer, seeing the bird *kali-devi* perched on the temple flagstaff, said 'You will shortly be king.' Kumárapála shaved his matted hair and went from Broach to Ujjain where he met his family. But as here too the royal troops followed him he fled to Kolhápura where he came across a Yogí who foretold his succession to a throne and gave him two spells or *mantras*. From Kolhápura Kumárapála went to Káñchí or Conjeveram and from there to the city of Kálambapattana.<sup>1</sup> The king of Kálambapattana Pratápasimha received him like an elder brother and brought him into his city, built a temple of Sivananda Kumárapálesvara in his honour, and even issued a coin called a Kumárapála. From Kálambapattana Kumárapála went to Chitrakúṭa or Chitor and from there to Ujjain whence he took his family to Siddhapura going on alone to Anahilapura to see his brother-in-law Krishnadeva. According to the Vicháraśreṇí Siddharája died soon after in A.D. 1143 on the 3rd of Kárttika Suddha Samvat 1199.

In the dissensions that followed the king's death Kumárapála's interests were well served by his brother-in-law Krishnadeva. Eventually the names of three candidates, Kumárapála and two others, were laid before the state nobles sitting in council to determine who should be king. Of the three candidates the two others were found wanting, and Kumárapála was chosen and installed according to the Vicháraśreṇí on the 4th of Márgaśírsa Suddha and according to the Kumárapálaprabandha on the 4th of Márgaśírsa Vadhyā. At the time of his succession, according to the Prabandhachintāmaṇi and the Kumárapálaprabandha, Kumárapála was about fifty years of age.

## Chapter II.

## THE

CHAULUKYAS,

A.D. 961 - 1242.

Kumárapála,  
A.D. 1143 - 1174.

<sup>1</sup> The Kumárapálaprabandha has Kelambapattana and Kolambapattana probably Kolam or Quilon.

## Chapter II.

THE  
CHAUUKYAS,  
A.D. 961-1242.  
Kumárapála,  
A.D. 1143-1174.

On his accession Kumárapála installed his wife Bhopaladeví his anointed queen or *puttaráñi*; appointed Udayana who had befriended him at Cambay minister; Báhaḍa or Vāgbhaṭa son of Udayana<sup>1</sup> chief councillor or *mahámātya*; and Alinga second councillor or *mahápradhāna*. Ahada or Arabhaṭṭa, apparently another son of Udayana, did not acknowledge Kumárapála and went over to Anurāja Anáka or Anoka king of Śupādalaksha or the Śāmbhar territory who is probably the same as the Analladeva of the Hammíramahākāvya.<sup>2</sup>

The potter Sajjana was rewarded with a grant of seven hundred villages near Chitrakūṭa or Chitoda fort in Rājputāñā, and the author of the Prabandhachintāmaṇi notices that in his time the descendants of the potter ashamed of their origin called themselves descendants of Sagara. Bhūmasimha who hid Kumárapála in the thorns was appointed head of the bodyguard; Devaśrī made the sister's mark on the royal forehead at the time of Kumárapála's installation and was granted the village of Devayo;<sup>3</sup> and Katuka the Vāñiā of Baroda, who had given Kumárapála parched grain was granted the village of Vṇṭapadra or Baroda. Bosari Kumárapála's chief companion was given Lātamandala, which seems to mean that he was appointed viceroy of Lāṭa or South Gujarāt.

Kanhada or Krishnadeva Kumárapála's brother-in-law and adviser overvaluing his great services became arrogant and disobedient insulting the king in open court. As remonstrance was of no avail the king had Krishnadeva waylaid and beaten by a band of athletes and taken almost dying to his wife the king's sister. From this time all the state officers were careful to show ready obedience.

The old ministry saw that under so capable and well served a ruler their power was gone. They accordingly planned to slay the king and place their own nominee on the throne. The king heard of the plot: secured the assassins: and employed them in murdering the conspirators. According to the Prabandhachintāmaṇi, Ahada or Arabhaṭṭa who had gone over to the Śāmbhar king and was in charge of the Śāmbhar infantry, bribed the local nobles as a preliminary to a war which he had planned against Kumárapála. He so far succeeded as to bring Anāka or Anoka the Śāmbhar king with the whole of his army to the borders of Gujarāt to fight Kumárapála.<sup>4</sup> Kumárapála went to meet Anoka. But, in consequence of intrigues, in the battle that followed the Gujarāt army did not obey orders. Kumárapála advanced in front on an elephant, and Bahada trying to climb on Kumárapála's elephant was thrown to the ground and slain. Anoka was also pierced with arrows and the Śāmbhar army was defeated and plundered of its horses.<sup>4</sup>

<sup>1</sup> The Kumárapálaprabanda says that Udayana was appointed minister and Vāgbhaṭa general. Sollá the youngest son of Udayana did not take part in politics.

<sup>2</sup> Kirtane's Hammíramahākāvya, 13.

<sup>3</sup> Dhavalakka or Dhalká according to the Kumárapálaprabanda.

<sup>4</sup> According to the Kumárapálacharita Kumárapála's sister who was married to Anāka having heard her husband speak slightly of the kings of Gujarāt took offence, resented the language, and bandied words with her husband who beat her. She came to her brother and incited him to make an expedition against her husband.

The Dvyásraya, probably by the aid of the author's imagination, gives a fuller account of this war. One fact of importance recorded in the Dvyásraya is that Ánaka though defeated was not slain, and, to bring hostilities to an end, gave his daughter Jalhaná to Kumárapála in marriage. The Kumárapálacharita calls the Sámbar king Arnorāja and says that it was Kumárapála who invaded the Sámbar territory. According to this account Kumárapála went to Chandrávatí near Abu and taking its Paramára king Vikramasimha with him marched to Śákambharior Sámbar and fought Arnorāja who was defeated but not killed. Kumárapála threatened to cut out Arnorāja's tongue but let him go on condition that his people wore a headdress with a tongue on each side. Arnorāja is said to have been confined in a cage for three days and then reinstalled as Kumárapála's feudatory. Vikramasimha of Chandrávatí, who in the battle had sided with Arnorāja, was punished by being disgraced before the assembled seventy-two feudatories at Anahilaváḍa and was sent to prison, his throne being given to his nephew Yaśodhavalá. After his victory over Arnorāja Kumárapála fought, defeated, and, according to the Kirtikaumudí, beheaded Ballála king of Málwa who had invaded Gujarát. The result of this contest seems to have been to reduce Málwa to its former position of dependence on the Anahilaváḍa kings. More than one inscription of Kumárapála's found in the temple of Udayáditya as far north as Udayapura near Bhilsa shows that he conquered the whole of Málwa, as the inscriptions are recorded by one who calls himself Kumárapála's general or *daṇḍanáyaka*.

Another of Kumárapála's recorded victories is over Mallikárjuna said to be king of the Konkan who we know from published lists of the North Konkan Siláháras flourished about A.D. 1160. The author of the Prabandhachintámáni says this war arose from a bard of king Mallikárjuna speaking of him before king Kumárapála as *Rájapitámaha* or grandfather of kings.<sup>3</sup> Kumárapála annoyed at so arrogant a title looked around. Ámbadā,<sup>4</sup> one of the sons of Udayana, divining the king's meaning, raised his folded hands to his forehead and expressed his readiness to fight Mallikárjuna. The king sent him with an army which marched to the Konkan without halting. At the crossing of the Kaláviní<sup>5</sup> it was met and defeated by Mallikárjuna. Ámbadā returned in disgrace and shrouding himself his umbrella and his tents in crape retreated to Anahilaváḍa. The king finding Ámbadā though humiliated ready to make a second venture gave him a larger and better appointed force. With this army Ámbadā again started for the Konkan, crossed the Kaláviní, attacked Mallikárjuna, and in a hand-to-hand fight

## Chapter II.

THE  
CHAULUKYAS,  
A.D. 961 - 1242.  
Kumárapála,  
A.D. 1143 - 1174.

<sup>1</sup> The Dvyásraya does not say that Kumárapála's sister was married to A'na.

<sup>2</sup> This was a common title of the Siláhára kings. Compare Bombay Gazetteer, XIII. 487 note 1.

<sup>3</sup> Ámbadā is his proper name. It is found Sanskritised into Ámrabhaṣa and Ámbaka.

<sup>4</sup> This is the Káveri river which flows through Chikhli and Balsár. The name in the text is very like Karabená the name of the same river in the Násik cave inscriptions (Bom. Gaz. XVI. 571) Kaláviní and Karabená being Sanskritised forms of the original Káveri. Perhaps the Kaveri is the Akabarou of the Periplus (A.D. 247).

Chapter II.  
THE  
CHAULUKYAS,  
A.D. 961-1242.  
Kumárapála,  
A.D. 1143-1174.

climbed his elephant and cut off his head. This head cased in gold with other trophies of the war he presented to the king on his triumphant return to Anahilápura. The king was greatly pleased and gave Āmbaḍā the title of *Rājapitāmaha*. Of this Mallikārjuna two stone inscriptions have been found one at Chiplūn dated A.D. 1156 (Saka 1078) the other at Bassein dated A.D. 1160 (Saka 1082). If the story that Mallikārjuna was slain is true the war must have taken place during the two years between A.D. 1160 and 1162 (Saka 1082, 1084) which latter is the earliest known date of Mallikārjuna's successor Aparāditya.

The Kumárapālacharita also records a war between Kumárapála and Samara king of Sarāshtra or south Kāthiāvāda, the Gujarāt army being commanded by Kumárapála's minister Udayana. The Prabandhachintāmaṇi gives Sausara as the name of the Sarāshtra king<sup>1</sup>: possibly he was some Gohilvād Mehr chief. Udayana came with the army to Vadhwān, and letting it advance went to Pālitāna. While he was worshipping at Pālitāna, a mouse carried away the burning wick of the lamp. Reflecting on the risk of fire in a wooden temple Udayana determined to rebuild the temple of stone. In the fight with Sausara the Gujarāt army was defeated and Udayana was mortally wounded.<sup>2</sup> Before Udayana died he told his sons that he had meant to repair the temple of Ādiśvara on Satruñjaya and the Sakunikā Vihāra at Broach and also to build steps up the west face of Gīrnār. His sons Bāhada and Āmbaḍā promised to repair the two shrines. Subsequently both shrines were restored, Kumárapála and Hemachārya and the council of Anahilapura attending at the installation of Suvṛittinātha in the Sakunikā Vihāra. The Gīrnār steps were also cut, according to more than one inscription in A.D. 1166 (S. 1222).<sup>3</sup> This war and Udayana's death must have occurred about A.D. 1149 (S. 1205) as the temple of Ādnātha was finished in A.D. 1156-57 (S. 1211). Bāhada also established near Satruñjaya a town called Bāhadapura and adorned it with a temple called Tribhuvanapalavasati.<sup>4</sup> After the fight with Sausara Kumárapála was threatened with another war by Karṇa<sup>5</sup> king of Dāhala or Chedi. Spies informed the king of the

<sup>1</sup> Sausara or Sāsar seems the original form from which Samara was Sanskritised. Sāsar corresponds with the Mehr name Chachar.

<sup>2</sup> The Kumárapālacharita says that Samara was defeated and his son placed on the throne.

<sup>3</sup> The translation of the inscription runs: Steps made by the venerable A'mbaka, Samvat 1222. According to the Kumárapālprabandha the steps were built at a cost of a lākh of *drammas* a *dramma* being of the value of about 5 *annas*. According to the Prabandhachintāmaṇi an earthquake occurred when the king was at Gīrnār on his way to Pomanatha. The old ascent of Gīrnār was from the north called *Chhatraśila* that is the umbrella or overhanging rocks. Hemachārya said if two persons went up together the *Chhatraśila* rocks would fall and crush them. So the king ordered A'mrabhaṭṭa to build steps on the west or Junāgaḍh face at a cost of 63 *lāks* of *drammas*.

<sup>4</sup> The site of Bāhadapura seems to be the ruins close to the east of Pālitāna where large quantities of conch shell bangles and pieces of brick and tile have been found.

<sup>5</sup> This would appear to be the Kalachuri king Gayā Karṇa whose inscription is dated 902 of the Chedi era that is A.D. 1152. As the earliest known inscription of Gayā Karṇa's son Narasimhadeva is dated A.D. 1157 (Chedi 907) the death of Gayā Karṇa falls between A.D. 1152 and 1157 in the reign of Kumárapála and the story of his being accidentally strangled may be true.

impending invasion as he was starting on a pilgrimage to Somanátha. Next day he was relieved from anxiety by the news that while sleeping on an elephant at night king Karna's necklace became entangled in the branch of a banyan tree, and the elephant suddenly running away, the king was strangled.

The Prabandhachintámani records an expedition against Sámbar which was entrusted to Cháhada a younger brother of Báhada. Though Cháhada was known to be extravagant, the king liked him, and after giving him advice placed him in command. On reaching Sámbar Cháhada invested the fort of Bábránagar but did not molest the people as on that day 700 brides had to be married.<sup>1</sup> Next day the fort was entered, the city was plundered, and the supremacy of Kumárapála was proclaimed. This Bábránagar has not been identified.\* There appears to be some confusion and the place may not be in Sámbar but in Bábariáváda in Káthiáváda. Cháhada returned triumphant to Patan. The king expressed himself pleased but blamed Cháhada for his lavish expenditure and conferred on him the title of *Ríja-gharatta* the King-grinder.

Though the Gujarát chronicles give no further details an inscription in the name of Kumárapála in a temple at Udepur near Bhilsa dated A.D. 1166 records that on Monday, *Akshaya tritiyá* the 3rd of Vaiśákha Sud (S. 1222), Thakkara Cháhada granted half the village of Saugaváda in the Rangáriká district or *bhukti*. Just below this inscription is a second also bearing the name of Kumárapála. The year is lost. But the occasion is said to be an eclipse on Thursday the 15th of Paush Sudhi when a gift was made to the god of Udayapura by Yasodhavala the viceroy of Kumárapála.<sup>2</sup>

<sup>1</sup> So many marriages on one day points to the people being either Kádva Kunbis or Bharváda among whom the custom of holding all marriages on the same day still prevails.

<sup>2</sup> The text of the inscription is:

- (1) .....पौषसुदीगुरौ अग्नेह श्रीमदण-
- (2) हिलपाटके [समस्त] राजावलीभिराजितशरममहारकमहा-
- (3) [राजाधिराजनिजत] साकंभरीभूपालश्रीमदवन्तिनाथश्रीमत्कु
- (4) [मारपाळ] .....नियुक्तमहामात्यश्रीजसोधन—
- (5) ल श्रीकरणादौ समस्तमुद्राव्यापारान्परिपन्थयतीत्येवं
- (6) काले [प्रवर्तमाने महाराजा] भिराजश्रीकुमारपाळदेवेन विज
- (7) .....श्रीमदुदयपुरो .....शेचकान्वये महाराज—
- (8) पुत्र .....महाराजपुत्रवसन्तपाळ एवं अन
- (9) .....लिखिता यात्रा । अद्य सोमग्रहणपर्वणि
- (10) .....छयवने समाहृततीर्थोदके स्नात्वा जगद्गु
- (11) .....सुखपुण्यजयवृद्धये उदयपुरकारि
- (12) .....कारापित देवश्री.....

Lines broken below.

## Chapter II.

THE  
CHAULUKYAS,  
A.D. 961-1242.  
Kumárapála,  
A.D. 1143-1174.

## Chapter II.

THE  
CHAULUKYAS,  
A.D. 961-1242.  
Kumárapála,  
A.D. 1143-1174.

Similar inscriptions of Kumárapála's time and giving his name occur near the ruined town of Kerádu or Kiráṭa-Kúpa near Bálmer in Western Rájputána. The inscriptions show that Kumárapála had another *Amútya* or minister there, and that the kings of the country round Kerádu had been subject to Gujarát since the time of Siddharája Jayasimha. Finally the inscription of Kumárapála found by Colonel Tod in a temple of Brahma on the pinnacle of Chitoda fort<sup>1</sup> shows that his conquests extended as far as Mewáda.

According to the Kumárapálachintámaṇi Kumárapála married one Padmávatí of Padmapura. The chronicler describes the city as to the west of the Indus. Perhaps the lady belonged to Padmapura a large town in Kashmír. Considering his greatness as a king and conqueror the historical record of Kumárapála is meagre and incomplete. Materials may still come to light which will show his power to have been surprisingly widespread.

Mr. Forbes<sup>2</sup> records the following Bráhmanical tradition of a Mewáda queen of Kumárapála, which has probably been intentionally omitted by the Jain chroniclers.

Kumárapála, says the Bráhman tradition, had wedded a Sisodaní Ráni, a daughter of the house of Mewáda. At the time that the sword went for her the Sisodaní heard that the Rája had made a vow that his wives should receive initiation into the Jain religion at Hemáchárya's convent before entering the palace. The Ráni refused to start for Patan until she was satisfied she would not be called on to visit the Áchárya's convent. Jayadeva Kumárapála's household bard became surety and the queen consented to go to Anahilapura. Several days after her arrival Hemáchárya said to the Rája 'The Sisodaní Ráni has never come to visit me.' Kumárapála told her she must go. The Ráni refused and fell ill, and the bard's wives went to see her. Hearing her story they disguised her as one of themselves and brought her privately home to their house. At night the bard dug a hole in the wall of the city, and taking the Ráni through the hole started with her for Mewáda. When Kumárapála became aware of the Ráni's flight he set off in pursuit with two thousand horse. He came up with the fugitives about fifteen miles from the fort of Idar. The bard said to the Ráni, 'If you can enter Idar you are safe. I have two hundred horse with me. As long as a man of us remains no one shall lay hands on you.' So saying he turned upon his pursuers. But the Ráni's courage failed and she slew herself in the carriage. As the fight went on and the pursuers forced their way to the carriage, the maids cried 'Why struggle more, the Ráni is dead.' Kumárapála and his men returned home.<sup>3</sup>

The Paramára chiefs of Chandrávatí near A'bu were also feudatories of Kumárapála. It has been noted that to punish him for siding with Arṇorája of Sámbar Kumárapála placed Vikrama Simha the Chandrávatí chief in confinement and set Vikrama's

<sup>1</sup> Annals of Rájasthan, I. 803

<sup>2</sup> Rás Málá (New Edition), 154.

<sup>3</sup> Rás Málá (New Edition), 154.

nephew Yaśodhavalā on his throne. That Kumārapāla conquered the chiefs of Sāmbhar and Mālwa is beyond question. Among his names is the proud title Avantī-nātha Lord of Mālwa.

The Kumārapālaprabandha gives the following limits of Kumārapāla's sway. The Turushkas or Turks on the north; the heavenly Ganges on the east; the Vindhya mountains on the south; the Sindhu river on the west.<sup>1</sup> Though in tradition Kumārapāla's name does not stand so high as a builder as the name of Siddharāja Jayasimha he carried out several important works. The chief of these was the restoring and rebuilding of the great shrine of Somaśvara or Somanātha Patan. According to the Prabandhachintāmaṇi when Kumārapāla asked Devasūri the teacher of Hemachārya how best to keep his name remembered Devasūri replied: Build a new temple of Somanātha fit to last an age or yuga, instead of the wooden one which is ruined by the ocean billows. Kumārapāla approved and appointed a building committee or pañchakula headed by a Brāhman named Gaṇḍa Bhāva Brihaspati the state officer at Somanātha. At the instance of Hemachārya the king on hearing the foundations were laid vowed until the temple was finished he would keep apart from women and would take neither flesh nor wine. In proof of his vow he poured a handful of water over Nīlakantha Mahādeva, probably his own royal god. After two years the temple was completed and the flag hoisted. Hemachārya advised the king not to break his vow until he had visited the new temple and paid his obeisance to the god. The king agreed and went to Somanātha, Hemachārya preceding him on foot and promising to come to Somanātha after visiting Satruñjaya and Girnār. On reaching Somanātha the king was received by Gaṇḍa-Brihaspati his head local officer and by the building committee, and was taken in state through the town. At the steps of the temple the king bowed his head to the ground. Under the directions of Gaṇḍa-Brihaspati he worshipped the god, made gifts of elephants and other costly articles including his own weight in coin, and returned to Anahilapura.

It is interesting to know that the present battered sea-shore temple of Somanātha, whose garbhāgāra or shrine has been turned into a mosque and whose spire has been shattered, is the temple of whose building and consecration the above details are preserved. This is shown by the style of the architecture and sculpture which is in complete agreement with the other buildings of the time of Kumārapāla.<sup>2</sup>

## Chapter II.

THE  
CHAULUKYAS,  
A.D. 961-1242.  
Kumārapāla,  
A.D. 1143-1174.

<sup>1</sup> The text is : यः कौबेरिमा तुरुष्कमैन्द्रीमा त्रिदिवापगं

याम्यामा विन्ध्यमा सिन्धुं पश्चिमा यो हाताभयत्

<sup>2</sup> It is also interesting, if there is a foundation of fact to the tale, that this is the temple visited by the Persian poet Sa'adi (A.D. 1200-1230) when he saw the ivory idol of Somanātha whose arms were raised by a hidden priest pulling a cord. According to Sa'adi on pretence of conversion he was admitted behind the shrine, discovered the cord-puller, threw him into a well, and fled. Compare Journal Royal Asiatic Society Bengal VII. 2 pages 885-886. That Sa'adi ever visited Somanātha is doubtful. No ivory human image can ever have been the chief object of worship at Somanātha.

## Chapter II.

THE  
CHAULUKYAS,  
A.D. 961-1242.  
Kumārāpāla,  
A.D. 1143-1174.

Kumārāpāla's temple seems to have suffered in every subsequent Muhammadan invasion, in Alaf Khan's in A.D. 1300, in Mozaffar's in A.D. 1390, in Mahmūd Begada's about A.D. 1490, and in Muzaffar II.'s about A.D. 1530. Time after time no sooner had the invader passed than the work of repair began afresh. One of the most notable restorations was by Khengār IV. (A.D. 1279-1333) a Chulūsamā king of Junāgadh who is mentioned in two Gīrnār inscriptions as the repairer of Somanātha after its desecration by Ala-ud-din Khilji. The latest sacrilege, including the turning of the temple into a mosque, was in the time of the Ahmadābād king Muzaffar Shāh II. (A.D. 1511-1535). Since then no attempt has been made to win back the god into his old home.

In the side wall near the door of the little shrine of Bhadrakālī in Patan a broken stone inscription gives interesting details of the temple of Somanātha. Except that the right hand corners of some of the lines are broken, the inscription is clear and well preserved. It is dated A.D. 1165 (Valabhi 850). It records that the temple of the god Someśa was first of gold built by Soma; next it was of silver built by Rāvana; afterwards of wood built by Krishna, and last of stone built by Bhīmadeva. The next restoration was through Gaṇḍa-Brihaspati under Kumārāpāla. Of Gaṇḍa-Brihaspati it gives these details. He was a Kanyākubja or Kanoj Brāhman of the Pāś'upata school, a teacher of the Mālwa kings, and a friend of Siddharāja Jayasinha. He repaired several other temples and founded several other religious buildings in Somanātha. He also repaired the temple of Kedāres'vara in Kumaon on learning that the Khas'a king of that country had allowed it to fall into disrepair. After the time of Kumārāpāla the descendants of Gaṇḍa-Brihaspati remained in religious authority in Somanātha.

Kumārāpāla made many Jain benefactions.<sup>1</sup> He repaired the temple of Sāgala-Vasahikā at Stambha-tīrtha or Cambay where Hemāchārya received his initiation or *dīkshā*. In honour of the lady who gave him barley flour and curds he built a temple called the Karambaka-Vihāra in Patan. He also built in Patan a temple called the Mouse or Mushaka-Vihāra to free himself from the impurity caused by killing a mouse while digging for treasure. At Dhaudhuka Hemāchārya's birthplace a temple called the Jholikā-Vihāra or cradle temple was built. Besides these Kumārāpāla is credited with building 1444 temples.

Though Kumārāpāla was not a learned man, his ministers were men of learning, and he continued the practice of keeping at his court scholars especially Sanskrit poets. Two of his leading Pandits were Rāmachandra and Udayachandra both of them Jains. Rāmachandra is often mentioned in Gujarāti literature and appears to have been a great scholar. He was the author of a book called the Hundred Accounts or Prabandhas'ata. After Udayana's death Kumārāpāla's chief minister was Kapardi a man of learning skilled in Sanskrit poetry. And all through his reign his principal adviser

was Hemachandra or Hemáchárya probably the most learned man of his time. Though Hemáchárya lived during the reigns both of Siddharāja and of Kumárapāla, only under Kumárapāla did he enjoy political power as the king's companion and religious adviser. What record remains of the early Solankis is chiefly due to Hemachandra.

## Chapter II.

THE  
CHAULUKYAS,  
A.D. 961-1242.  
Kumárapāla,  
A.D. 1143-1174.

The Jain life of Hemáchárya abounds in wonders. Apart from the magic and mystic elements the chief details are. Cháchiga a Modh Vánia of Dhandhuka<sup>1</sup> in the district of Ardháshtama had by his wife Páhini<sup>2</sup> of the Chámunda *gōtra*, a boy named Chángodeva who was born A.D. 1083 (Kartik fullmoon Samvat 1115). A Jain priest named Devachandra A'chárya (A.D. 1078-1170; S. 1134-1226) came from Patan to Dhandhuka and when in Dhandhuka went to pay his obeisance at the Modh Vasahikí. While Devachandra was seated Chángodeva came playing with other boys and went and sat beside the *áchárya*. Struck with the boy's audacity and good looks the *áchárya* went with the council of the village to Cháchiga's house. Cháchiga was absent but his wife being a Jain received the *áchárya* with respect. When she heard that her son was wanted by the council, without waiting to consult her husband, she handed the boy to the *áchárya* who carried him off to Karnávatí and kept him there with the sons of the minister Udayana. Cháchiga, disconsolate at the loss of his son, went in quest of him vowing to eat nothing till the boy was found. He came to Karnávatí and in an angry mood called on the *áchárya* to restore him his son. Udayana was asked to interfere and at last persuaded Cháchiga to let the boy stay with Devachandra.

In A.D. 1097, when Chángodeva was eight years old Cháchiga celebrated his son's consecration or *dikshá* and gave him the name of Somachandra. As the boy became extremely learned Devachandra changed his name to Hemachandra the Moon of gold. In A.D. 1110 (S. 1166) at the age of 21, his mastery of all the S'ástras and Siddhántas was rewarded by the dignity of Súri or sage. Siddharāja was struck with his conversation and honoured him as a man of learning. Hemachandra's knowledge wisdom and tact enabled him to adhere openly to his Jain rules and beliefs though Siddharāja's dislike of Jain practices was so great as at times to amount to insult. After one of their quarrels Hemáchárya kept away from the king for two or three days. Then the king seeing his humility and his devotion to his faith repented and apologised. The two went together to Somanátha Patan and there Hemáchárya paid his obeisance to the *līnga* in a way that did not offend his own faith. During Siddharāja's reign Hemáchárya wrote his well known grammar with aphorisms or *sūtras* and commentary or *vr̥tti* called Siddha-Hemachandra, a title compounded of the king's name and his own. As the Bráhmans found fault with the absence of any detailed references to the king in the work Hemachandra

<sup>1</sup> The head-quarters of the Dhandhuka sub-division sixty miles south-west of Ahmadábád.

<sup>2</sup> Another reading is Láhini.

Chapter II.  
THE  
CHAULUKYAS,  
A.D. 961-1242.  
Kumárapála,  
A.D. 1143-1174.

added one verse at the end of each chapter in praise of the king. During Siddharāja's reign he also wrote two other works, the *Haimināmamālā* "String of Names composed by Hema(chandra)" or *Abhidhānachintāmaṇi* and the *Anekārthanāmamālā* a Collection of words of more than one meaning. He also began the *Dvyās'rayakosha*<sup>1</sup> or Double Dictionary being both a grammar and a history. In spite of his value to Kumárapála, in the beginning of Kumárapála's reign Hemáchárya was not honoured as a spiritual guide and had to remain subordinate to Bráhmans. When Kumárapála asked him what was the most important religious work he could perform Hemáchárya advised the restoring of the temple of Somanátha. Still Hemáchárya so far won the king to his own faith that till the completion of the temple he succeeded in persuading the king to take the vow of *ahimsá* or non-killing which though common to both faiths is a specially Jain observance. Seeing this mark of his ascendancy over the king, the king's family priest and other Bráhmans began to envy and thwart Hemáchárya. On the completion of the temple, when the king was starting for Somanátha for the installation ceremony, the Bráhmans told him that Hemáchárya did not mean to go with him. Hemáchárya who had heard of the plot had already accepted the invitation. He said being a recluse he must go on foot, and that he also wanted to visit Gírnár, and from Gírnár would join the king at Somanátha. His object was to avoid travelling in a palanquin with the king or suffering a repetition of Siddharāja's insult for not accepting a *pálki*. Soon after reaching Somanátha Kumárapála asked after Hemáchárya. The Bráhmans spread a story that he had been drowned, but Hemáchárya was careful to appear in the temple as the king reached it. The king saw him, called him, and took him with him to the temple. Some Bráhmans told the king that the Jain priest would not pay any obeisance to Siva, but Hemáchárya saluted the god in the following verse in which was nothing contrary to strict Jainism: 'Salutation to him, whether he be Brahma, Vishnu, Hara, or Jina, from whom have fled desires which produce the sprouts of the seed of worldliness.'<sup>2</sup> After this joint visit to Somanátha Hemachandra gained still more ascendancy over the king, who appreciated his calmness of mind and his forbearance. The Bráhmans tried to prevent the growth of his influence, but in the end Hemachandra overcame them. He induced the king to place in the sight of his Bráhmanical family priests an image of Śāntinátha Tīrthaṅkara among his family gods. He afterwards persuaded Kumárapála publicly to adopt the Jain faith by going to the hermitage of Hemachandra and giving

<sup>1</sup> Prabandhachintāmaṇi.

<sup>2</sup> भवर्षीजाङ्कुरजनना रागाद्याः क्षयमुपागता यस्य ।

ब्रह्मा वा विष्णुर्वा इरो जिनो वा नमस्तस्मै ॥

यत्र तत्र समये यथा तथा योति सोऽस्यभिधया यथा तथा ।

पीतदोषककुषः स चेद्भवानेक एव भगवन्नमोस्तु ते ॥

numerous presents to Jain ascetics. Finally under his influence Kumárapála put away all Bráhmanical images from his family place of worship. Having gone such lengths Kumárapála began to punish the Bráhmans who insulted Hemachandra. A Bráhman named Vámarás'i, a Pandit at the royal court, who composed a verse insulting Hemachandra, lost his annuity and was reduced to beggary, but on apologising to Hemachandra the annuity was restored. Another Bráhmanical officer named Bháva Brihaspati, who was stationed at Somanátha, was re-called for insulting Hemachandra. But he too on apologising to Hemachandra was restored to Somanátha. Under Hemachandra's influence Kumárapála gave up the use of flesh and wine, ceased to take pleasure in the chase, and by beat of drum forbade throughout his kingdom the taking of animal life. He withdrew their licenses from hunters, fowlers and fishermen, and forced them to adopt other callings. To what lengths this dread of life-taking was carried appears from an order that only filtered water was to be given to all animals employed in the royal army. Among the stories told of the king's zeal for life-saving is one of a Bania of Sámbar who having been caught killing a louse was brought in chains to Anahilavada, and had his property confiscated and devoted to the building at Anahilavada of a Louse Temple or Yúká-Vihára. According to another story a man of Nador in Marwár was put to death by Kelhana the chief of Nador to appease Kumárapála's wrath at hearing that the man's wife had offered flesh to a field god or *kshetrapála*. Hemachandra also induced the king to forego the claim of the state to the property of those who died without a son.

During Kumárapála's reign Hemachandra wrote many well known Sanskrit and Prakrit works on literature and religion. Among these are the Adhyátmopanishad or Yogaśāstra a work of 12,000 verses in twelve chapters called Prakāśas, the Trisāsthī-sālākāpurushacharitra or lives of sixty-three Jain saints of the Utsarpinī and Avasarpinī ages; the Pati-ishtaparvan, a work of 3500 verses being the life of Jain Sthaviras who flourished after Mahāvira; the Prakṛita Śabdānśāsana or Prakrit grammar; the Dvyāśraya<sup>1</sup> a Prakrit poem written with the double object of teaching grammar and of giving the history of Kumárapála; the Chhandouśāsana a work of about 6000 verses on prosody; the Līngāśāsana a work on genders, the Deśanāmālikā in Prakrit with a commentary a work on local and provincial words; and the Alaukārachūdāmaṇi a work on rhetoric. Hemachandra died in A.D. 1172 (S. 1229) at the age of 84. The king greatly mourned his loss and marked his brow with Hemachandra's ashes. Such crowds came to share in the ashes of the pyre that the ground was hollowed into a pit known as the Haima-Khadda or Hema's Pit.

Kumárapála lived to a great age. According to the author of the Prabandhachintāmaṇi he was fifty when he succeeded to the

## Chapter II.

THE  
CHAULUKYAS,  
A.D. 961 - 1244.  
Kumárapála,  
A.D. 1143 - 1174.

<sup>1</sup> संवत् १२२९ वैशाखशुद्धि ३ सोमे अग्रह श्रीमदणहिकपट्टके समस्तराजावलीवि-  
ख्यसिंहमहाराजाधिराजपरमेश्वर अजयपालदेवकल्याणविजयराज्ये तस्यादप्योपजीविनि महा-  
मात्यश्रीसोमेश्वरे श्रीकरणादी.

## Chapter II.

THE  
CHAULUKYAS,  
A.D. 961-1242.  
Kumārāpāla,  
A.D. 1143-1174.

throne, and after ruling about thirty-one years died in A.D. 1174 (S. 1230). He is said to have died of *lūta* a form of leprosy. Another story given by the Kumārāpālaprabandha is that Kumārāpāla was imprisoned by his nephew and successor Ajayapāla. The Kumārāpālaprabandha gives the exact length of Kumārāpāla's reign at 30 years 8 months and 27 days. If the beginning of Kumārāpāla's reign is placed at the 4th Māgśar Sud Samvat 1299, the date of the close, taking the year to begin in Kārtika, would be Bhādrapada Suddha Samvat 1229. If with Gujarāt almanacs the year is taken to begin in Āśvādha, the date of the close of the reign would be Bhādrapada of Samvat 1230. It is doubtful whether either Samvat 1229 or 1230 is the correct year, as an inscription dated Samvat 1229 Vaishākha Suddha 3rd at Udayapura near Bhilsā describes Ajayapāla Kumārāpāla's successor as reigning at Anahilapura. This would place Kumārāpāla's death before the month of Vaishākha 1229 that is in A.D. 1173.<sup>1</sup>

Ajayapāla,  
A.D. 1174-117

As Kumārāpāla had no son he was succeeded by Ajayapāla the son of his brother Mahīpāla.<sup>2</sup> According to the Kumārāpālaprabandha Kumārāpāla desired to give the throne to his daughter's son Pratāpamalla, but Ajayapāla raised a revolt and got rid of Kumārāpāla by poison. The Jain chroniclers say nothing of the reign of Ajayapāla because he was not a follower of their religion. The author of the Sukritasāṅkīrtana notices a small silver canopy or pavilion shown in Ajayapāla's court as a feudatory's gift from the king of Sapādalakṣhu<sup>3</sup> or Sēwālik. The author of the Kīrtikāmmudī dismisses Ajayapāla with the mere mention of his name, and does not even state his relationship with Kumārāpāla. According to the Prabandhachintamani Ajayapāla destroyed the Jain temples built by his uncle. He showed no favour to Āmbadā and Kumārāpāla's other Jain ministers. Ajayapāla seems to have been of a cruel and overbearing temper. He appointed as his minister Kapardi because he was of the Brāhmanical faith.<sup>4</sup> But considering his manners arrogant he ordered him to be thrown into a caldron of boiling oil. On another occasion he ordered the Jain scholar Rāmachandra to sit on a red-hot sheet of copper. One of his nobles Āmra-bhaṭa or Āmbadā refused to submit to

<sup>1</sup> Regarding the remarkable story that not long before their deaths both Hemacharya and Kumārāpāla inclined towards if they did not become converts to Islam (Tod's Western India, 181) no fresh information has been obtained. Another curious saying of Tod's (Ditto, 182) also remains doubtful. Kumārāpāla expelled the tribe of Lār from his kingdom. That this tribe of Lār can have had to do either with Lāta or South Gujarat or with the caste of Lād Vanis seems unlikely. The alternative is Pārsis from Lār on the Persian Gulf whom Tod (Annals of Rajasthan, I. 285) notices as sending an expedition from Laristan to Gujarāt. In this connection it is worthy of note that Lār remained the seat of a Gueber prince till A.D. 1600 the time of Shah Abas (D'Herbelot Bib. Or. II. 477). A repetition of the Parsi riots (Cambay Gazetteer, VI. 215) may have been the cause of their expulsion from Gujarāt.

<sup>2</sup> See the Dvayāraya. A Patan inscription lying at Verāval also calls Ajayapāla the brother's son of Kumārāpāla.

<sup>3</sup> It is stated in a grant of Bhīma II. dated S. 1283, that Ajayadeva, as he is there called, made the Sapādalakṣha or Sāmbar king tributary. Ind. Ant. VI. 199ff.

<sup>4</sup> The Udayapura inscription mentions Somēśvara as the minister of Ajayapāla in Samvat 1229 (A.D. 1173). See above page 193.

the king, saying that he would pay obeisance only to Vitarāja or Tirthaṅkara as god, to Hemachandra as guide, and to Kumārapāla as king. Ajayapāla ordered the matter to be settled by a fight. Āmbadā brought some of his followers to the drum-house near the gates, and in the fight that followed Āmbadā was killed. In A.D. 1177 (S. 1233), after a short reign of three years, Ajayapāla was slain by a doorkeeper named Vijjaladeva who plunged a dagger into the king's heart.<sup>1</sup>

Ajayapāla was succeeded by his son Mūlarāja II. also called Bāla Mūlarāja as he was only a boy when installed. His mother was Nāikidevi the daughter of Paramardī, apparently the Kādamba king Permādi or Siva Chitta who reigned from A.D. 1147 to 1175 (S. 1203-1231).<sup>2</sup> The authors of the Kirtikaumudī<sup>3</sup> and the Sukritasankīrtana say that even in childhood Mūlarāja II. dispersed the Turnshka or Muhammadan army.<sup>4</sup> The Prabandha-chintāmaṇi states that the king's mother fought at the Gādarāra-ghatta and that her victory was due to a sudden fall of rain. Mūlarāja II. is said to have died in A.D. 1179 (S. 1235) after a reign of two years.

Mūlarāja II. was succeeded by Bhīma II. The relationship of the two is not clearly established. Mr. Forbes makes Bhīma the younger brother of Ajayapāla. But it appears from the Kīrtikaumudī and the Sukritasankīrtana that Bhīma was the younger brother of Mūlarāja. The Sukritasankīrtana after concluding the account of Mūlarāja,<sup>5</sup> calls Bhīma '*asya bandhu*' 'his brother,' and the Kīrtikaumudī, after mentioning the death of Mūlarāja, says that Bhīma his younger brother '*annjanmūṣya*' became king.<sup>6</sup>

## Chapter II.

THE  
CHAULUKYAS,  
A.D. 961-1242.

Mūlarāja II.  
A.D. 1177-1179.

<sup>1</sup> The abuse of Ajayapāla is explained if Tod's statement (Western India, 191) that he became a Musalmān is correct.

<sup>2</sup> Fleet's Kānarese Dynasties, 93.

<sup>3</sup> Chapter II Verse 57.

<sup>4</sup> We know much less about this event than its importance deserves, for with the exception of a raid made in A.D. 1197 by one of the Ghori generals this victory secured Gujārāt from any serious Muhammadan attack for more than a century. We learn from various grants made by Bhīmaśāhā II. (Ind. Ant VI. 195, 198, 200, 201) that Mūlarāja's regular epithet in the *Pramāṇa* was "He who overcame in battle the ruler of the Garjjanakas, who are hard to defeat" and Dr. Bühler has pointed out (Ibid., 201) that Garjjanaka is a Sanskritising of the name Ghori. As a matter of fact, however, the leader of the Muhammadan army was Muḥammad of Ghor, and the battle took place in A.D. 1178 (A. 574). One of the two Muhammadan writers who mentions the invasion (Muhammad 'Ufi, who wrote at Delhi about A.D. 1211) says that Muhammad was at first defeated, but invaded the country a second time two years later "and punished the people for their previous misconduct." But this is only mentioned incidentally as part of an anecdote of Muhammad's equity, and there is some confusion with Muhammad's victory in the second battle of Narāyan (in Jaipur territory) in A.D. 1192, as a better, though slightly later authority, Minhāj-us Sirāj, speaks of no second expedition to Gujārāt led by Muhammad himself. Minhāj-us-Sirāj's account of the defeat is as follows (Elliott, II. 204): He (Muhammad) conducted his army by way of Uch and Multān towards Nahrwālā. The Rājā of Nahrwālā, Bhīmdeo, was a minor, but he had a large army and many elephants. In the day of battle the Muhammadans were defeated and the Sultan was compelled to retreat. This happened in the year 574 H. (1178 A.D.). Further on we read (Elliott, II. 300): "In 593 H. (1197 A.D.) he (Muhammad's general Kutb-ud-din) went towards Nahrwālā, defeated Rājā Bhīmdeo, and took revenge on the part of the Sultan." As no conquest of the country is spoken of, this expedition was evidently a mere raid. The only inaccuracy in the account is the mention of Bhīma instead of Mūlarāja as the king who defeated the first invasion.—(A. M. T. J.)

<sup>5</sup> Sarga II, Verse 47.

<sup>6</sup> Sarga II, Verse 60.

## Chapter II.

## THE

CHAULUKYAS,  
A.D. 961 - 1242.Bhīma II.  
A.D. 1179 - 1242.

Múlarāja we know came to the throne as a child. Of Bhīma also the Kīrtikāmundī says that he came to the throne while still in his childhood, and this agrees with the statements that he was the younger brother of Múlarāja. Bhīma probably came to the throne in A.D. 1178 (S. 1234). There is no doubt he was reigning in A.D. 1179 (S. 1235), as an inscription in the deserted village of Kerálu near Bīlmer of Anāhilavāda dated A.D. 1179 (S. 1235) states that it was written 'in the triumphant reign of the illustrious Bhīmadeva.'<sup>1</sup> A further proof of his reigning in A.D. 1179 (S. 1235) and of his being a minor at that time is given in the following passage from the Tabakāt-i-Nāsiri: In A.D. 1178 (Hijri 574) the Rāi of Nahrwālā Bhīmedo, was a minor, but he had a large army and many elephants. In the day of battle the Muhammadans were defeated and the Sultān was compelled to retreat.<sup>2</sup> Merutunga says that Bhīma reigned from A.D. 1179 (S. 1235) for sixty-three years that is up to A.D. 1242 (S. 1298), and this is borne out by a copperplate of Bhīma which bears date A.D. 1210 (S. 1296<sup>3</sup> Mārga Vadi 14th Sunday<sup>4</sup>).

Bhīma was nicknamed Bhōlo the Simpleton. The chroniclers of this period mention only the Vāghelās and almost pass over Bhīma. The author of the Kīrtikāmundī says 'the kingdom of the young ruler was gradually divided among powerful ministers and provincial chiefs'; and according to the Sukṛitasankīrtana 'Bhīma felt great anxiety on account of the chiefs who had forcibly eaten away portions of the kingdom.' It appears that during the minority, when the central authority was weak, the kingdom was divided among nobles and feudatories, and that Bhīma proved too weak a ruler to restore the kingly power. Manuscripts and copperplates show that Bhīmadeva was ruling at Anāhilavāda in S. 1217, 1251, 1261, 1263, and 1264,<sup>5</sup> and copperplates dated S. 1283, 1288, 1295, and 1296 have also been found. Though Bhīma in name enjoyed a long unbroken reign the verses quoted above show that power rested not with the king but with the nobles. It appears from an inscription that in A.D. 1224 (S. 1280) a Chālukya noble named Jayantasimha was supreme at Anāhilavāda though he mentions Bhīma and his predecessors with honour and respect.<sup>6</sup>

It was probably by aiding Bhīma against Jayantasimha that the Vāghelās rose to power. According to the chroniclers the Vāghelās succeeded in the natural course of things. According to the Sukṛitasankīrtana Kumārapāla appeared to his grandson Bhīma and directed him to appoint as his heir-apparent Vīradhavalā son of Lavanaprasāda and grandson of Amorāja the son of Dhavalā king of Bhīmapālī. Next day in court, in the presence of his nobles, when Lavanaprasāda and Vīradhavalā entered the king said to

<sup>1</sup> The Vicharaśroni also gives S. 1235 as the beginning of his reign.

<sup>2</sup> Elliot's History of India, II. 294. This event properly belongs to the reign of Mula-raj. See above page 195 note 5.

<sup>3</sup> Ind. Ant. VI. 207.

<sup>4</sup> Chapter II. Verse 61.

<sup>5</sup> Kishore's and Peterson's Reports on Sanskrit Manuscripts.

<sup>6</sup> Ind. Ant. VI. 197.

Lavanaprasáda : Your father Arṇorāja seated me on the throne : you should therefore uphold my power : in return I will name your son Vīradhavaḷa my heir-apparent.<sup>1</sup> The author of the Kīrtikaumudī notes that Arṇorāja son of Dhavaḷa, opposing the revolution against Bhīma, cleared the kingdom of enemies, but at the cost of his own life. The author then describes Lavanaprasáda and Vīradhavaḷa as kings. But as he gives no account of their rise to supremacy, it seems probable that they usurped the actual power from Bhīma though till A.D. 1242 (S. 1295) Bhīma continued to be nominal sovereign.

Bhīma's queen was Līlādevī the daughter of a Chohān chief named Samarasimha.<sup>2</sup>

## Chapter II.

THE  
CHAULUKYAS  
A.D. 961 - 1242.

Bhīma II.  
A.D. 1179 - 1242.

---

<sup>1</sup> The text is दन्वास्मै दोग्यते युवराज्यं राज्यं निरं कुरु.

<sup>2</sup> The text is चाहु राण that is चाहुमाग राणक. The term Rāṇaka would show him to be a Chohān chief.

## CHAPTER III.

## THE VÁGHELÁS

(A.D. 1219-1304).

## Chapter III.

THE VÁGHELÁS,  
A.D. 1219-1304.Arnorāja,  
A.D. 1170-1200.

WHILE Bhímadeva II. (A.D. 1178-1241) struggled to maintain his authority in the north, the country between the Śibarmatī and the Narbadā in the south as well as the districts of Dholkā and Dhandhukā in the south-west passed to the Vāghelās a branch of the Solāṅkis sprung from Anāka or Arnorāja, the son of the sister of Kumārapāla's (A.D. 1113-1173) mother. In return for services to Kumārapāla,<sup>1</sup> Anāka, with the rank of a noble or Śāmanā, had received the village of Vyūghrapalli or Vāghelā, the Tiger's Lair, about ten miles south-west of Anahilavāda. It is from this village that the dynasty takes its name of Vāghela.

Lavanaprasāda,  
A.D. 1200-1233.

Anāka's son Lavanaprasāda, who is mentioned as a minister of Bhímadeva II. (A.D. 1179-1242)<sup>2</sup> held Vāghelā and probably Dhavalagadha or Dholkā about thirty miles to the south-west. The Kīrtikaumudī or Moonlight of Glory, the chief cotemporary chronicle,<sup>3</sup> describes Lavanaprasāda as a brave warrior, the slayer of the chief of Nadulā the modern Nāndol in Mārwar. "In his well-ordered realm, except himself the robber of the glory of hostile kings, robbers were unknown. The ruler of Mālava invading the kingdom turned back before the strength of Lavanaprasāda. The southern king also when opposed by him gave up the idea of war." The ruler of Mālava or Mālwa referred to was Sohada or Subhatavarman.<sup>4</sup> The southern king was the Devagiri Yādava Singhana II. (A.D. 1209-1247)<sup>5</sup>

Lavanaprasāda married Madanarājñī and by her had a son named Vīradhavalā. As heir apparent Vīradhavalā, who was also called Vīra Vāghelā or the Vāghelā hero,<sup>6</sup> rose to such distinction as a warrior that in the end Lavanaprasāda abdicated in his favour. Probably to reconcile the people to his venturing to oppose his sovereign Bhímadeva, Lavanaprasāda gave out that in a dream the Luck of Anahilavāda

<sup>1</sup> Anāka survived Kumārapāla and served also under Bhímadeva II. Seeing the kingdom of his weak sovereign divided among his ministers and chiefs Anāka strove till his death to re-establish the central authority of the Solāṅki dynasty. Kāthavate's Kīrtikaumudī, xiii.

<sup>2</sup> Rās Mālā (New Edition), 200.

<sup>3</sup> Kīrtikaumudī, Bombay Sanskrit Series Number XXV.

<sup>4</sup> Ind. Ant VI. 188 footnote. According to Merutunga a cotemporary chronicler an epigram of Bhīma's minister turned back Subhatavarman.

<sup>5</sup> Ind. Ant VI. 188.

<sup>6</sup> According to one story Madanarājñī left her husband's house taking Vīradhavalā with her, and went to live with Deva Rāja Pattakīla the husband of her deceased sister. On growing up Vīradhavalā returned to his father's house. Rās Mālā (New Edition), 201.

appeared bewailing her home with unlighted shrines, broken walls, and jackal-haunted streets, and called on him to come to her rescue.<sup>1</sup> Though he may have gone to the length of opposing Bhímadeva by force of arms, Lavaṇaprasáda was careful to rule in his sovereign's name. Even after Lavaṇaprasáda's abdication, though his famous minister Vastupála considered it advisable, Víradhavaḷa refused to take the supreme title. It was not until the accession of Víradhavaḷa's son Víśaladeva that the head of the Vághelás took any higher title than Rájaka or chieftain. Lavaṇaprasáda's religious adviser or Guru was the poet Someśvara the author of the Kirtikaumudí and of the Vastupálacharita or Life of Vastupála, both being biographical accounts of Vastupála. The leading supporters both of Lavaṇaprasáda and of Víradhavaḷa were their ministers the two Jain brothers Vastupála and Tejapála the famous temple-builders on Ábu, Satruñjaya, and Girnár. According to one account Tejapála remained at court, while Vastupála went as governor to Stambhatírtha or Cambay where he redressed wrongs and amassed wealth.<sup>2</sup>

One of the chief times of peril in Lavaṇaprasáda's reign was the joint attack of the Devagiri Yádava Singhapa or Singhapa from the south and of four Márwár chiefs from the north. Lavaṇaprasáda and his son Víradhavaḷa in joint command marched south to meet Singhapa at Broach. While at Broach the Vaghelás' position was made still more critical by the desertion of the Godhraha or Godhrá chief to Málwa and of the Láṭa or south Gujarát chief to Singhapa. Still Lavaṇaprasáda pressed on, attacked Singhapa, and gave him so crushing a defeat, that, though Lavaṇaprasáda had almost at once to turn north to meet the Málwa army, Singhapa retired without causing further trouble.<sup>3</sup> Someśvara gives no reason for Singhapa's withdrawal beyond the remark 'Deer do not follow the lion's path even when the lion has left it.' The true reason is supplied by a Manuscript called Forms of Treaties.<sup>4</sup> The details of a treaty between Singhapa and Lavaṇaprasáda under date Samvat 1288 (A.D. 1232) included among the Forms seem to show that the reason why Singhapa did not advance was that Lavaṇaprasáda and his son submitted and concluded an alliance.<sup>5</sup> In this copy of the treaty Singhapadeva is called the great king of kings or paramount sovereign *Mahárájádhirāja*, while Lavaṇaprasáda, Sanskritised into Lavaṇaprasada is called a Rána and a tributary chief *Manúmanútes'vara*. The place where the treaty was concluded

## Chapter III.

THE VAGHELÁS,  
A.D. 1219-1304,  
Lavaṇaprasáda,  
A.D. 1200-1233.

<sup>1</sup> Dr. Bahler in Ind. Ant. VI. 189.

<sup>2</sup> According to the Kirtikaumudí, Káthavate's Ed. XIV. note I, under Vastupála low people ceased to earn money by base means, the wicked turned pale; the righteous prospered. All honestly and securely plied their calling. Vastupála put down piracy, and, by building platforms, stopped the mingling of castes in milk shops. He repaired old buildings, planted trees, sank wells, laid out parks, and rebuilt the city. All castes and creeds he treated alike.

<sup>3</sup> Káthavate's Kirtikaumudí, xv.

<sup>4</sup> The use of the date Monday the fullmoon of Vaiśākha, Samvat 1288 (A.D. 1232) in the second part of the Forms seems to shew that the work was written in A.D. 1232.

<sup>5</sup> Though the object is to give the form of a treaty of alliance, the author could not have used the names Singhapa and Lavaṇaprasada unless such a treaty had been actually concluded between them. Apparently Singhapa's invasion of Gujarát took place but a short time before the book of treaties was compiled. Bhandárkar's Search for Sanskrit Manuscripts (1882-83), 40-41.

**Chapter III**THE VAGHELAS,  
A.D. 1219-1304.Lavanaprasāda,  
A.D. 1200-1233.

is styled "the victorious camp," and the date is Monday the fullmoon of Vaisākha in the year Samvat 1288 (A.D. 1232). The provisions are that, as before, each of the belligerents should confine himself to his own territory; neither of them should invade the possessions of the other; if a powerful enemy attacked either of them, they should jointly oppose him; if only a hostile general led the attack, troops should be sent against him; and if from the country of either any noble fled into the territory of the other taking with him anything of value he should not be allowed harbourage and all valuables in the refugee's possession should be restored.<sup>1</sup> His good fortune went with Lavanaprasāda in his attack on the Mārwar chiefs whom he forced to retire. Meanwhile S'ankha<sup>2</sup> who is described as the son of the ruler of Sindh but who seems to have held territory in Broach, raised a claim to Cambay and promised Vastupāla Lavanaprasāda's governor, that, if Vastupāla declared in his favour<sup>3</sup>, he would be continued in his government. Vastupāla rejected S'ankha's overtures, met him in battle outside of Cambay, and forced him to retire. In honour of Vastupāla's victory the people of Cambay held a great festival when Vastupāla passed in state through the city to the shrine of the goddess Ekalla Vīra outside of the town.<sup>4</sup>

Another of the deeds preserved in the Forms is a royal copperplate grant by Lavanaprasāda or Lāvanyaprasāda of a village, not named, for the worship of Somanātha. Lavanaprasāda is described as the illustrious Rajaka,<sup>5</sup> the great chief, the local lord or *Mandalesārtra*, the son of the illustrious Rajaka Anand born in the illustrious pedigree of the Chaulukya dynasty. The grant is noted as executed in the reign of Bhūmadeva II<sup>6</sup> while one Bhūdhaya was his great minister. Though Bhūmadeva was ruling in A.D. 1232 (Samvat 1288) Lavanaprasāda apparently had sufficient influence to make grants of villages and otherwise to act as the real ruler of Gujarāt. It was apparently immediately after this grant (A.D. 1232?) that Lavanaprasāda abdicated in favour of Virādhavala.<sup>7</sup>

Virādhavala,  
A.D. 1233-1238.

Soon after his accession Virādhavala, accompanied by his minister Tejapāla, started on an expedition against his wife's brothers Sangama and Chamunda the rulers of Vamanasthali or Vantthali near Junāgadh. As in spite of their sister's advice Sangama and Chamunda refused to pay tribute the siege was pressed. Early in the fight the cry arose 'Virādhavala is slain.'<sup>8</sup> But on his favourite horse Uparavata, Virādhavala put himself at the head of his troops, slew both the brothers, and gained the

<sup>1</sup> Bhandarkar's Search for Sanskrit Manuscripts (1882-83), 40.

<sup>2</sup> According to other accounts S'ankha, a Broach chieftain, took up the cause of a certain Savad or Musalmān merchant with whom Vastupāla had quarrelled. In the fight Luvapāla a Gola, one of Vastupāla's chief supporters, was slain and in his honour Vastupāla raised a shrine to the Lord Luvapāla. Rās Māla (New Edition), 201-202.

<sup>3</sup> Kathavate's Kirtikanandī, xv.-xvi.

<sup>4</sup> Kathavate's Kirtikanandī, xv.-xvi.

<sup>5</sup> The modern Gujarati Rājā.

<sup>6</sup> Bhūmadeva's name is preceded by the names of his ten Chaulukya predecessors in the usual order. The attributes of each are given as in published Chaulukya copper-plates. Ind Ant VI 180-213.

<sup>7</sup> Bhandarkar's Search for Sanskrit Manuscripts (1882-83), 39.

hoarded treasure of Vantali.<sup>1</sup> In an expedition against the chief of Bhadresvara, probably Bhadresar in Kacch, Viradhavala was less successful and was forced to accept the Kacch chief's terms. The chroniclers ascribe this reverse to three Rájput brothers who came to Viradhavala's court and offered their services for 3,00,000 drammas (about £7500). "For 3,00,000 drammas I can raise a thousand men" said Viradhavala, and the brothers withdrew. They went to the court of the Bhadresar chief, stated their terms, and were engaged. The night before the battle the brothers sent to Viradhavala saying 'Keep ready 3000 men, for through a triple bodyguard we will force our way' The three brothers kept their word. They forced their way to Viradhavala, dismounted him, carried off his favourite steed Uparavata, but since they had been his guests they spared Viradhavala's life.<sup>2</sup>

Another of Viradhavala's expeditions was to East Gujarát. Ghughula, chief of Godhra or Godhrá, plundered the caravans that passed through his territory to the Gujarát ports. When threatened with punishment by Viradhavala, Ghughula in derision sent his overlord a woman's dress and a box of cosmetics. The minister Tejahpála, who was ordered to avenge this affront, dispatched some skirmishers ahead to raid the Godhra cattle. Ghughula attacked the raiders and drove them back in such panic that the main body of the army was thrown into disorder. The day was saved by the prowess of Tejahpála who in single combat unhorsed Ghughula and made him prisoner. Ghughula escaped the disgrace of the woman's dress and the cosmetic box with which he was decorated by biting his tongue so that he died. The conquest of Ghughula is said to have spread Viradhavala's power to the borders of Maháráshtra.<sup>3</sup> The chroniclers relate another success of Viradhavala's against Muizz-ud-dín apparently the famous Muhammad Gori Sultan Muizz-ud-dín Bahramsháh, the Sultan of Delhi (A.D. 1191-1205)<sup>4</sup> who led an expedition against Gujarát. The chief of Ábu was instructed to let the Musalmán force march south unmolested and when they were through to close the defiles against their return. The Gujarát army met the Musalmáns and the Ábu troops hung on their rear. The Musalmáns fled in confusion and cartloads of heads were brought to Viradhavala in Dholká. The chroniclers give the credit of this success to Vastupála. They also cred Vastupála with a stratagem which induced the Sultan to think well of Viradhavala and prevented him taking steps to wipe out the disgrace of his defeat. Hearing that the Sultán's mother, or, according to another story, the Sultán's religious adviser, was going from Cambay to Makka Vastupála ordered his men to attack and plunder the vessels in which the pilgrimage was to be made. On the captain's complaint Vastupála had the pirates arrested and the property restored. So grateful was the owner, whether mother or guide, that Vastupála was taken to Delhi and arranged a friendly treaty between his master and the Sultán.<sup>5</sup>

## Chapter III.

THE VAGHELAS,  
A.D. 1219-1304.Viradhavala,  
A.D. 1233-1238.<sup>1</sup> Káthavate's Kírtikaumudí, xxiii.<sup>2</sup> Káthavate's Kírtikaumudí, xxiii.-xxiv.<sup>3</sup> Káthavate's Kírtikaumudí, xxiv.-xxv.<sup>4</sup> Káthavate's Kírtikaumudí, xxiii.<sup>5</sup> Elliot and Dowson, II. 209.

## Chapter III.

THE VAGHFLI'S,  
A.D. 1219-1304.  
Vīradhavalā,  
A.D. 1233-1238.

Their lavish expenditure on objects connected with Jain worship make the brothers Vastupāla and Tejahpāla the chief heroes of the Jain chroniclers. They say when the Musalmān trader Sayad was arrested at Cambay his wealth was confiscated. Vīradhavalā claimed all but the dust which he left to Vastupāla. Much of the dust was gold dust and a fire turned to dust more of the Sayad's gold and silver treasure. In this way the bulk of the Sayad's wealth passed to Vastupāla. This wealth Vastupāla and his brother Tejahpāla went to bury in Hadālaka in Kāthiāvāḍa. In digging they chanced to come across a great and unknown treasure. According to the books the burden of their wealth so preyed on the brothers that they ceased to care for food. Finding the cause of her husband Tejahpāla's anxiety Anupamā said 'Spend your wealth on a hill top. All can see it; no one can carry it away.' According to the chroniclers it was this advice, approved by their mother and by Vastupāla's wife Lalitādevī, that led the brothers to adorn the summits of Ābu, Gīrnār, and Śatruñjaya with magnificent temples.

The Śatruñjaya temple which is dedicated to the twenty-third Tīrthaṅkara Neminātha is dated A.D. 1232 (Samvat 1288) and has an inscription by Someśvara, the author of the Kīrtikaumudī telling how it was built. The Gīrnār temple, also dedicated to Neminātha, bears date A.D. 1232 (Samvat 1288). The Ābu temple, surpassing the others and almost every building in India in the richness and delicacy of its carving, is dedicated to Neminātha and dated A.D. 1231 (Samvat 1287). Such was the liberality of the brothers that to protect them against the cold mountain air each of their masons had a fire near him to warm himself and a hot dinner cooked for him at the close of the day. The finest carvers were paid in silver equal in weight to the dust dissolved out of their carvings.<sup>1</sup>

The author Someśvara describes how he twice came to the aid of his friend Vastupāla. On one occasion he saved Vastupāla from a prosecution for peculation. The second occasion was more serious. Simha the maternal uncle of king Vīśaladeva whipped the servant of a Jain monastery. Enraged at this insult to his religion Vastupāla hired a Rajput who cut off Simha's offending hand. The crime was proved and Vastupāla was sentenced to death. But according to the Jains the persuasions of Someśvara not only made the king set Vastupāla free, but led him to upbraid his uncle for beating the servant of a Jain monastery. Soon after his release Vastupāla was seized with fever. Feeling the fever to be mortal he started for Śatruñjaya but died on the way. His brother Tejahpāla and his son Jayantapāla burned his body on the holy hill, and over his ashes raised a shrine with the name Svargārohanaprāsāda. The shrine of the ascent into Heaven.<sup>2</sup>

<sup>1</sup> Kāthiāvāt's Kīrtikaumudī, xx., J. B. R. A. S. XVIII. Number XLVIII. 28. The Jain writers delight in describing the magnificence of the pilgrimages which Vastupāla conducted to the holy places. The details are 4500 carts, 700 palanquins, 1800 camels, 2900 writers, 12,100 white-robed and 1100 naked or sky-clad Jains, 1450 singers, and 2000 boys. Kāthiāvāt's Kīrtikaumudī, xvi.

<sup>2</sup> Kāthiāvāt's Kīrtikaumudī, xviii. 19.

In A.D. 1238 six years after his father's withdrawal from power Viradhavala died. One hundred and eighty-two servants passed with their lord through the flames, and such was the devotion that Tejahpála had to use force to prevent further sacrifices.<sup>1</sup>

Of Viradhavala's two sons, Vírāma Visala and Pratápamalla, Vastupála favoured the second and procured his succession according to one account by forcing the old king to drink poison and preventing by arms the return to Anahilavāda of the elder brother Vírāma who retired for help to Jāhālipura (Jabalpur). Besides with his brother's supporters Visala had to contend with Tribhuvanapála the representative of the Anahilavāda Solankis. Unlike his father and his grandfather Visala refused to acknowledge an overlord. By A.D. 1243 he was established as sovereign in Anahilavāda. A later grant A.D. 1261 (Samvat 1317) from Kadi in North Gujarāt shows that Anahilavāda was his capital and his title *Mahārājādhirāja* King of Kings. According to his copperplates Visaladeva was a great warrior, the crusher of the lord of Mālwa, a hatchet at the root of the turbulence of Mewād, a volcanic fire to dry up Singhana of Devagiri's ocean of men.<sup>2</sup> Visaladeva is further described as chosen as a husband by the daughter of Karmāta<sup>3</sup> and as ruling with success and good fortune in Anahilavāda with the illustrious Nágada as his minister.<sup>4</sup> The bards praise Visaladeva for lessening the miseries of a three years' famine,<sup>5</sup> and state that he built or repaired the fortifications of Visalanagara in East and of Darbhavati or Dābhoi in South Gujarāt.

During Visaladeva's reign Vághela power was established throughout Gujarāt. On Visaladeva's death in A.D. 1261 the succession passed to Arjunadeva the son of Visaladeva's younger brother Pratápamalla.<sup>6</sup> Arjunadeva proved a worthy successor and for thirteen years (A.D. 1262-1274; Samvat 1318-1331) maintained his supremacy. Two stone inscriptions one from Verával dated A.D. 1264 (Samvat 1320) the other from Kacch dated A.D. 1272 (Samvat 1328) show that his territory included both Kacch and Kāthiavāda, and an inscription of his successor Sāraṅgadeva shows that his power passed as far east as Mount Abu.

The Verával inscription of A.D. 1264 (Samvat 1320), which is in the temple of the god Śiva, describes Arjunadeva as the king

### Chapter III.

THE VAGHELAS,  
A.D. 1219-1304.

Visaladeva,  
A.D. 1243-1261.

Arjunadeva,  
A.D. 1262-1274.

<sup>1</sup> Rās Mālā, 202.

<sup>2</sup> Ind. Ant. VI. 191. The word for Mewād is Medapāta the Med or Mher land.

<sup>3</sup> The Karmāta king would probably be Someśvara (A.D. 1252) or his son Narasimha III. (A.D. 1254) of the Hoysala Ballalas of Dvārasamudra. Fleet's Kānarese Dynasties, 64, 69.

<sup>4</sup> These details are mentioned in a grant of land in Māndal in Ahmadābād to Brāhmins to fill a drinking fountain, repair temples, and supply offerings. Ind. Ant. VI. 210-213.

<sup>5</sup> Rās Mālā (New Ed.), 212. A Jaina Pattāvali or succession list of High-priests notices that the famine lasted for three years from Samvat 1315 (A.D. 1259). The text may be translated as follows: Vikrama Samvat 1315, three years' famine the king (being) Visaladeva. Bhandarkar's Search for Sanskrit Manuscripts for 1883-84, 15, 323.

<sup>6</sup> See Ep. Ind. I.

<sup>7</sup> The inscription was first noticed by Colonel Tod: Rajasthan, I. 705: Western India, 506.

**Chapter III.**

THE VĀGHELĀS,  
A.D. 1219-1304.

Arjunadeva,  
A.D. 1262-1274.

of kings, the emperor (*chakravartin*) of the illustrious Chaulukya race, who is a thorn in the heart of the hostile king Nihsankamalla, the supreme lord, the supreme ruler, who is adorned by a long line of ancestral kings, who resides in the famous Apahillapātaka. The grant allots certain income from houses and shops in Somanātha Patan to a mosque built by Piroz a Muhammadar shipowner of Ormuz which is then mentioned as being under the sway of Amīr Rukn-ud-dīn.<sup>1</sup> The grant also provides for the expenses of certain religious festivals to be celebrated by the Shiite sailors of Somanātha Patan, and lays down that under the management of the Muslim community of Somanātha any surplus is to be made over to the holy districts of Makka and Madina. The grant is written in bad Sanskrit and contains several Arabic Persian and Gujarāṭī words. Its chief interest is that it is dated in four eras, "in 662 of the Prophet Muhammad who is described as the teacher of the sailors, who live near the holy lord of the Universe that is Somanātha; in 1320 of the great king Vikrama; in 945 of the famous Valabhi; and in 151 of the illustrious Simha." The date is given in these four different eras, because the Muhammadan is the donor's era, the Samvat the era of the country, the Valabhi of the province, and the Simha of the locality.<sup>2</sup> The Kacch inscription is at the village of Rav about sixty miles east of Bhūj. It is engraved on a memorial slab at the corner of the courtyard wall of an old temple and bears date A.D. 1272 (Samvat 1328). It describes Arjunadeva as the great king of kings, the supreme ruler, the supreme lord. It mentions the illustrious Māladeva as his chief minister and records the building of a step-well in the village of Rav.<sup>3</sup>

Sāraṅgadeva,  
A.D. 1275-1296.

Arjunadeva was succeeded by his son Sāraṅgadeva. According to the Vichārasreṇī Sāraṅgadeva ruled for twenty-two years from A.D. 1274 to 1296 (Samvat 1331-1353). Inscriptions of the reign of Sāraṅgadeva have been found in Kacch and at Abu. The Kacch inscription is on a *pālita* or memorial slab now at the village of Khokhar near Kanthkot which was brought there from the holy village of Bhadreswar about thirty-five miles north-east of Māndvi. It bears date A.D. 1275 (Samvat 1332) and describes Sāraṅgadeva as the great king of kings, the supreme ruler, the supreme lord ruling at Apahillapataka with the illustrious Māladeva as his chief minister.<sup>4</sup> The Abu inscription dated A.D. 1294 (Samvat 1350) in the temple of Vastupāda regulates certain dues payable to the Jain temple and mentions Sāraṅgadeva as sovereign of Apahillapātaka and as having for vassal Viśaladeva ruler of the old capital of Chandrāvati about twelve miles south of Mount Abu.<sup>5</sup> A third inscription dated A.D.

<sup>1</sup> This is not Sultān Rukn-ud-din of the slave kings, who ruled from A.D. 1234 to A.D. 1235. Elliot and Dowson, II.

<sup>2</sup> All four dates tally. The middle of A.D. 1264 (Samvat 1320) falls in Hijra 662. As the Valabhi era begins in A.D. 318-319 and the Simha era in A.D. 1113, 916 of Valabhi and 151 of Simha tally with A.D. 1264.

<sup>3</sup> Bombay Government Selections CIII. New Series, 71.

<sup>4</sup> From an unpublished copy in the possession of Rāo Sāheb Dalpatram Pranjivan Khakhar, late Educational Inspector, Kacch. Only the upper six lines of the inscription are preserved.

<sup>5</sup> Asiatic Researches, XVI. 311; Rās Malā, 213.

1287 (Samvat 1343), originally from Somanátha, is now at Cintra in Portugal. It records the pilgrimages and religious benefactions of one Tripurántaka, a follower of the Nakulísú Pásupata sect, in the reign of Sáraṅgadeva, whose genealogy is given. A manuscript found in Ahmadábád is described as having been finished on Sunday the 3rd of the dark fortnight of Jyeshtha in the Samvat year 1350, in the triumphant reign of Sáraṅgadeva the great king of kings, while his victorious army was encamped near Áśápalli (Ahmadábád).<sup>1</sup>

Sáraṅgadeva's successor Karnaḍeva ruled for eight years A.D. 1296 - 1304 (Samvat 1352 - 1360). Under this weak ruler, who was known as Ghelo or the Insane, Gujarát passed into Musalmán hands. In A.D. 1297 Alaf Khán the brother of the Emperor Ala-u-dín Khilji (A.D. 1296 - 1317) with Nasrat Khán led an expedition against Gujarát. They laid waste the country and occupied Anahilaváda. Leaving his wives, children, elephants, and baggage Karnaḍeva fled to Ramadeva the Yádava chief of Devagiri.<sup>2</sup> All his wealth fell to his conquerors. Among the wives of Karnaḍeva who were made captive, was a famous beauty named Kauládeví, who was carried to the harem of the Sultán. In the plunder of Cambay Nasrat Khán took a merchant's slave Malik Káfur who shortly after became the Emperor's chief favourite. From Cambay the Muhammadans passed to Káthiaváda and destroyed the temple of Somanátha. In 1304 Alaf Khán's term of office as governor of Gujarát was renewed. According to the Mirát-i-Ahmadí after the renewal of his appointment, from white marble pillars taken from many Jain temples, Alaf Khán constructed at Anahilaváda the Jáma Masjid or general mosque.

In A.D. 1306 the Cambay slave Káfur who had already risen to be Sultán Ala-u-dín's chief favourite was invested with the title of Malik Naib and placed in command of an army sent to subdue the Dakhan. Alaf Khán, the governor of Gujarát, was ordered to help Malik Káfur in his arrangements. At the same time Kauládeví persuaded the Emperor to issue orders that her daughter Devaladeví should be sent to her to Delhi. Devaladeví was then with her father the unfortunate Karnaḍeva in hiding in Báglán in Násik. Malik Káfur sent a messenger desiring Karnaḍeva to give up his daughter. Karnaḍeva refused and Alaf Khán was ordered to lead his army to the Báglán hill and capture the princess. While for two months he succeeded in keeping the Muhammadan army at bay, Karnaḍeva received and accepted an offer for the hand of Devaladeví from the Devagiri Yádava chief Sankaradeva. On her way to Devagiri near Elura Devaladeví's escort was attacked by a party of Alaf Khán's troops, and the lady seized and sent to Delhi where she was married to prince Khizar Khán.

### Chapter III.

THE VAGHELAS,  
A.D. 1219 - 1304.

Karnaḍeva,  
A.D. 1296 - 1304.

<sup>1</sup> Professor Bhandarkar's Report for 1883-84, 17-18.

<sup>2</sup> The hardie story is that king Karṇa had two Nágas Bráhmaṇa ministers Mádhava and Kesava. He slew Kesava and took Mádhava's wife from her husband. In revenge Mádhava went to Delhi and brought the Muhammadans. After the Muhammadan conquest Mádhava presented Ala-u-dín with 360 horses. In return Mádhava was appointed civil minister with Alaf Khán as military governor commanding a lách of horsemen, 1500 elephants, 20,000 foot soldiers and having with him forty-five officers entitled to use kettledrums. Rás Malá, 214.

**Chapter III.**  
**THE VÁGHELÁS,**  
**A.D. 1219-1304.**

Nothing more is known of Karnadeva who appears to have died a fugitive.

Though the main cities and all central Gujarát passed under Musalmán rule a branch of the Vághelás continued to hold much of the country to the west of the Sábarmatí, while other branches maintained their independence in the rugged land beyond Ambá Bhawání between Vírpur on the Mahí and Posiná at the northmost verge of Gujarát.<sup>1</sup>

-----


**GENEALOGY OF THE VÁGHELÁS.**

Dhavala,  
 A.D. 1160  
 Married Kamárapála's Aunt.  
 |  
 Arjorája,  
 A.D. 1170  
 Founder of Vághela.  
 |  
 Lavanaprasáda,  
 A.D. 1200  
 Chief of Dholká.  
 |  
 Viradhavala,  
 A.D. 1233-1239  
 Chief of Dholká.  
 |  
 Visaladeva,  
 A.D. 1243-1261  
 King of Anahilaváda.  
 |  
 Arjunadeva,  
 A.D. 1262-1274.  
 |  
 Sáraṅgadeva,  
 A.D. 1274-1295.  
 |  
 Karnadeva or Ghelo,  
 A.D. 1296-1304.

---

<sup>1</sup> Rás Malá, 222. The Jhálás were firmly fixed in the plains between the Lesser Ran of Kacch and the Gulf of Cambay. The Koli branches of these clans with other tribes of pure or of adulterated aboriginal descent, spread over the Chunvál near Viramgám and appeared in many remote and inaccessible tracts of hill or forest. On the east, under the protection of a line of Rájput princes, the banner of the goddess Káli floated from the hill of Pávágad; while in the west the descendants of Khengár held their famous fortress of Junágadh from within its walls controlling much of the peninsula over which they had maintained undisputed sway. Chiefs of Junágadh origin were scattered over the rest of the peninsula among whom were the Gohils of Gogo and Piram, and of the sea-washed province which from them derived its name of Gohilvád.





# PROVINCE of GUZERAT

Scale of Miles

## *PART II.*

### **MUSALMAN GUJARAT.**

**A.D. 1297 - 1760.**

This history of Musalmán Gujarát is based on translations of the *Mirát-i-Sikandari* (A.D. 1611) and of the *Mirát-i-Ahmedi* (A.D. 1758) by the late Colonel J. W. Watson. Since Colonel Watson's death in 1889 the translations have been revised and the account enriched by additions from the Persian texts of *Farishtah* and of the two *Mirāts* by Mr. Fazl Lutfullah Farídi of Surat. A careful comparison has also been made with other extracts in Elliot's *History of India* and in Bayley's *History of Gujarát*.



# MUSALMÁN GUJARÁT.

A.D. 1297-1760.

## INTRODUCTION.

MUHAMMADAN rule in Gujarát lasted from the conquest of the province by the Delhi emperor Alá-ud-din Khilji (A.D. 1295-1315), shortly before the close of the thirteenth century A.D., to the final defeat of the Mughal viceroy Morín Khán by the Maráthás and the loss of the city of Ahmedábád at the end of February 1758.

This whole term of Musalmán ascendancy, stretching over slightly more than four and a half centuries, may conveniently be divided into three parts. The First, the rule of the early sovereigns of Delhi, lasting a few years more than a century, or, more strictly from A.D. 1297 to A.D. 1403; the Second, the rule of the Ahmedábád kings, a term of nearly a century and three-quarters, from A.D. 1403 to A.D. 1573; the Third, the rule of the Mughal Emperors, when, for little less than two hundred years, A.D. 1573-1760, Gujarát was administered by viceroys of the court of Delhi.

In the course of these 450 years the limits of Gujarát varied greatly. In the fourteenth century the territory nominally under the control of the Musalmán governors of Patán (Anahilaváda) extended southwards from Jhálór, about fifty miles north of Mount Abu, to the neighbourhood of Bombay, and in breadth from the line of the Málwa and Khándesh hills to the western shores of peninsular Gujarát.<sup>1</sup> The earlier kings of Ahmedábád (A.D. 1403-1450), content with establishing their power on a firm footing, did not greatly extend the limits of their kingdom. Afterwards, during the latter part of the fifteenth and the beginning of the sixteenth centuries (A.D. 1450-1530), the dominions of the Ahmedábád kings gradually spread till they included large tracts to the east and north-east formerly in the possession of the rulers of Khándesh and Málwa. Still later, during the years of misrule between A.D. 1530 and A.D. 1573, the west of Khándesh and the north of the Konkan ceased to form part of the kingdom of Gujarát. Finally, under the arrangements introduced by the emperor Akbar in A.D. 1583, more lands were restored to Málwa and Khándesh. With the exception of Jhálór and Sirohi on the north, Dungarpur and Bānsvāda on the north-east, and Alirájpur on

Introduction.

MUSALMÁN  
GUJARAT.  
A.D. 1297-1760.

Territorial  
Limits.

<sup>1</sup> The first notice of the exercise of sovereignty by the Musalmán rulers of Gujarát, over lands further south than the neighbourhood of Surat is in A.D. 1428, when king Ahmed I. (A.D. 1412-1443) contested with the Dakhan sovereign the possession of Máhm (north latitude 19° 40'; east longitude 72° 47'). As no record remains of a Musalmán conquest of the coast as far south as Danda Rájapuri or Janjira, about fifty miles south of Bombay, it seems probable that the North Konkan fell to the Musalmáns in A.D. 1297 as part of the recognised territories of the lords of Anahilapura (Patán). *Rás Málá*, I, 350. One earlier reference may be noted. In A.D. 1422 among the leading men slain in the battle of Sirañgpur, about fifty miles north-east of Ujjain in Central India, was Sávant chief of Danda Rájapuri that is Janjira. *Mirát-i Sikandari* (Persian Text), 40, and *Farihtah* (Persian Text), II, 468.

**Introduction.**

MUSALMÁN  
GUJARAT,  
A.D. 1297 - 1760.

Sorath.

the east, since handed to Rájputána and Central India, the limits of Gujarát remain almost as they were laid down by Akbar.

Though, under the Musalmáns, peninsular Gujarát did not bear the name of Káthiaváda, it was then, as at present, considered part of the province of Gujarát. During the early years of Musalmán rule, the peninsula, together with a small portion of the adjoining mainland, was known as Sorath, a shortened form of Sauráshtra, the name originally applied by the Hindus to a long stretch of sea-coast between the banks of the Indus and Daman.<sup>1</sup> Towards the close of the sixteenth century the official use of the word Sorath was confined to a portion, though by much the largest part, of the peninsula. At the same time, the name Sorath seems then, and for long after, to have been commonly applied to the whole peninsula. For the author of the *Mirát-i-Ahmedi*, writing as late as the middle of the eighteenth century (A.D. 1756 : A.H. 1170), speaks of Sorath as divided into five districts or *zillás*, Hálár, Káthiaváda, Gohlváda, Bábriaváda, and Jetváda, and notices that though Navanagar was considered a separate district, its tribute was included in the revenue derived from Sorath.<sup>2</sup> In another passage the same writer thus defines Sauráshtra :

Sauráshtra or Sorath comprehends the Sukár of Sorath the Sukár of Islamnagar or Navanagar and the Sukár of Kachh or Bhujnagar. It also includes several *zillás* or districts, Nayad which they call Jatwan, Halar or Navanagar and its vicinity, Káthiaváda, Gohlváda, Bábriaváda, Chorvar, Panchál, Okhagír in the neighbourhood of Jagat otherwise called Dwárka, Prádhás Kheir or Patán Sonnáth and its neighbourhood, Naghr also called Salgogah, and the Nalkantha.<sup>3</sup>

<sup>1</sup> The details of Akbar's settlement in A.D. 1583 show Sorath with sixty three subdivisions and Navanagar (Islamnagar) with seventeen. Similarly in the *Amín Akbari* (A.D. 1590) Sorath with its nine divisions includes the whole peninsula except Káthiaváda in the north, which was then part of Ahmedabad. *Gladwin*, II. 64 and 65-71.

<sup>2</sup> Bird's History of Gujarat, 118.

<sup>3</sup> Nayad is the present Navadkantha about ten miles south-west of Rádhanpur containing Jayir and Vardá in the west near the Ran and spreading east to Sam and Munjpur thirty to forty miles south-west of Patán. Halar is in the north-west of the peninsula, Káthiaváda in the centre, Gohlváda in the south-east; Bábriaváda south-west of Gohlváda, Chorvar or Chorvar north-west of Viraval; Panchál in the north-east centre; Okhagír or Okhamundál in the extreme west. Nalkantha is the hollow between Káthiaváda and the mainland. Besides these names the author of the *Mirát-i-Ahmedi* gives our more district in Sorath and others in Gujarát. The name he gives in Sorath is Nágher or Naghr which he says is also called Salgogah. Salgogah is apparently Sálbet and its neighbourhood, as Koliáár, Madhnápur, Chingurá, and Patán in south Káthiaváda are still locally known as Nagher, a tract famous for its fruitfulness. The *Mirát-i-Ahmedi* contains the following additional local names: For Kadi thirty-five miles north-west of Ahmedábád, Daulat; for Dholka twenty-five miles south-west of Ahmedábád, Práth-Naghr for Cambay, Támbánagrá, for Virámgam forty miles north-west of Ahmedábád, Jhálawár; for Mithupur twenty-two miles south-east of Rádhanpur and some of the country between it and Patán, Párpas, for the tract ten miles south-east of Rádhanpur to the neighbourhood of Patán, Kákre; for the town of Rádhanpur in the Palanpur Political Superintendency and its neighbourhood, Vágnáth, for the town of Palanpur and its neighbourhood up to Dasa and Duniwála, Dhamlár; for Báláshinor forty-two miles east of Ahmedábád with a part of Kapadvanj in the Kaira district, Masálwála; for Baroda, Párkher; for the subdivision of Jambúsar in the Broach district fifteen miles north-west of Broach city, Bhanam; for Ahmednagar that is Chota Udepur and the rough lands east of Godhra, Pálwára.

The present Sorath stretches no further than the limits of Jámághāh, Bántwa, and a few smaller holdings.

The name Káthiávāḍa is of recent origin. It was not until after the establishment of Musalmán-power in Gujarát that any portion of the peninsula came to bear the name of the tribe of Káthis. Even as late as the middle of the eighteenth century, the name Káthiávāḍa was applied only to one of the sub-divisions of the peninsula. In the disorders which prevailed during the latter part of the eighteenth century, the Káthis made themselves conspicuous. As it was from the hardy horsemen of this tribe that the tribute-exacting Maráthás met with the fiercest resistance, they came to speak of the whole peninsula as the land of the Káthis. This use was adopted by the early British officers and has since continued.

Under the Ahmedábád kings, as it still is under British rule, Gujarát was divided politically into two main parts; one, called the *kháilsah* or crown domain administered directly by the central authority; the other, on payment of tribute in service or in money, left under the control of its former rulers. The amount of tribute paid by the different chiefs depended, not on the value of their territory, but on the terms granted to them when they agreed to become feudatories of the kings of Ahmedábád. Under the Gujarát Sultans this tribute was occasionally collected by military expeditions headed by the king in person and called *mubkaym* or country-seizing circuits.

The internal management of the feudatory states was unaffected by their payment of tribute. Justice was administered and the revenue collected in the same way as under the Anahápur kings. The revenue consisted, as before, of a share of the crops received in kind, supplemented by the levy of special cesses, trade, and transit dues. The chief's share of the crops differed according to the locality; it rarely exceeded one-third of the produce, it rarely fell short of one-sixth. From some parts the chief's share was realised directly from the cultivator by agents called *mantais*; from other parts the collection was through superior landowners.<sup>1</sup>

The Ahmedábád kings divided the portion of their territory which was under their direct authority into districts or *sarkars*. These districts were administered in one of two ways. They were either assigned to nobles in support of a contingent of troops, or they were set apart as crown domains and managed by paid officers. The officers placed in charge of districts set apart as crown domains were called *mukhtars*.<sup>2</sup> Their chief duties were to preserve the peace and to collect the revenue. For the maintenance of order, a body of soldiers from the army head-quarters at Ahmedábád was detached for service in each of these divisions, and placed under the command of the district governor. At the same time, in addition to the presence of this detachment of regular troops, every district contained certain

## Introduction.

MUSALMÁN  
GUJARAT.  
A.D. 1297-1760.  
Káthiávāḍa.

UNDER THE  
KINGS.  
1503-1573.

States.

Districts.

Crown Lands

<sup>1</sup> Ras Māla, I. 211.

<sup>2</sup> Mukhtār and *uktā*, the district administered by a *mukhtār*, come from the Arabic root *kataḍ*, he cut, in allusion to the public revenue or the lands cut and apportioned for the pay of the officers and their establishments.

Introduction.  
UNDER THE  
KINGS,  
A. D. 1403 - 1573.

fortified outposts called *thánās*, varying in number according to the character of the country and the temper of the people. These posts were in charge of officers called *thánādūrs* subordinate to the district governor. They were garrisoned by bodies of local soldiery, for whose maintenance, in addition to money payments, a small assignment of land was set apart in the neighbourhood of the post. On the arrival of the tribute-collecting army the governors of the districts through which it passed were expected to join the main body with their local contingents. At other times the district governors had little control over the feudatory chiefs in the neighbourhood of their charge.

Fiscal.

For fiscal purposes each district or *sarkār* was distributed among a certain number of sub-divisions or *paraganās*, each under a paid official styled *āmīl* or *tahsildār*. These sub-divisional officers realised the state demand, nominally one-half of the produce, by the help of the headmen of the villages under their charge. In the sharehold and simple villages of North Gujarāt these village headmen were styled *patels* or according to Musalmān writers *mukaddams* and in the simple villages of the south they were known as *devāīs*. They arranged for the final distribution of the total demand in joint villages among the shareholders, and in simple villages from the individual cultivators. The sub-divisional officer presented a statement of the accounts of the villages in his sub-division to the district officer, whose record of the revenue of his whole district was in turn forwarded to the head revenue officer at court. As a check on the internal management of his charge, and especially to help him in the work of collecting the revenue, with each district governor was associated an accountant. Further that each of these officers might be the greater check on the other, king Ahmed I. (A.D. 1412 - 1443) enforced the rule that when the governor was chosen from among the royal slaves the accountant should be a free man, and that when the accountant was a slave the district governor should be chosen from some other class. This practice was maintained till the end of the reign of Muzaflar Shah (A.D. 1511-1525), when, according to the *Mirāt-i-Ahmedi*, the army became much increased, and the ministers, condensing the details of revenue, farmed it on contract, so that many parts formerly yielding one rupee now produced ten, and many others seven eight or nine, and in no place was there a less increase than from ten to twenty per cent. Many other changes occurred at the same time, and the spirit of innovation creeping into the administration the wholesome system of checking the accounts was given up and mutiny and confusion spread over Gujarāt.<sup>2</sup>

Assigned Lands.

The second class of directly governed districts were the lands assigned to nobles for the maintenance of contingents of troops. As in other parts of India, it would seem that at first these assignments were for specified sums equal to the pay of the contingent. When such assignments were of long standing, and were large enough to swallow the whole revenue of a district, it was natural to simplify the

<sup>1</sup> Further particulars regarding these village headmen are given below.

<sup>2</sup> Bird's History of Gujarāt, 192; *Mirāt-i-Sikandari*, Persian Text, 44.

arrangement by transferring the collection of the revenue and the whole management of the district to the military leader of the contingent. So long as the central power was strong, precautions were doubtless taken to prevent the holder of the grant from unduly rackrenting his district and appropriating to himself more than the pay of the troops, or from exercising any powers not vested in the local governors of districts included within the crown domains. As in other parts of India, those stipulations were probably enforced by the appointment of certain civil officers directly from the government to inspect the whole of the noble's proceedings, as well in managing his troops as in administering his lands.<sup>1</sup> The decline of the king's power freed the nobles from all check or control in the management of their lands. And when, in A.D. 1536, the practice of farming was introduced into the crown domains, it would seem to have been adopted by the military leaders in their lands, and to have been continued till the annexation of Gujarāt by the emperor Akbar in A.D. 1573.

It was the policy of Akbar rather to improve the existing system than to introduce a new form of government. After to some extent contracting the limits of Gujarāt he constituted it a province or *sibah* of the empire, appointing to its government an officer of the highest rank with the title of *sibahdār* or viceroy. As was the case under the Ahmedābād kings, the province continued to be divided into territories managed by feudatory chiefs, and districts administered by officers appointed either by the court of Dehli or by the local viceroy. The head-quarters of the army remained at Ahmedābād, and detachments were told off and placed under the orders of the officers in charge of the directly administered divisions. These district governors, as before, belonged to two classes, paid officers responsible for the management of the crown domains and military leaders in possession of lands assigned to them in pay of their contingent of troops. The governors of the crown domains, who were now known as *farajdārs* or commanders, had, in addition to the command of the regular troops, the control of the outposts maintained within the limits of their charge. Like their predecessors they accompanied the viceroy in his yearly circuit for the collection of tribute.

As a check on the military governors and to help them in collecting the revenue, the distinct class of account officers formerly established by king Ahmed I. (A.D. 1412-1413) was again introduced. The head of this branch of the administration was an officer, second in rank to the viceroy alone, appointed direct from the court of Dehli with the title of *dirān*. Besides acting as collector-general of the revenues of the province, this officer was also the head of its civil administration. His title *dirān* is generally translated minister. And though the word minister does not express the functions of the office, which corresponded more nearly with those of a chief secretary, it represents with sufficient accuracy the relation in which the holder of the office of *dirān* generally stood to the viceroy.

## Introduction.

UNDER THE  
MUGHAIS,  
A.D. 1553-1573.

Assigned Lands.

UNDER THE  
MUGHAIS,  
A.D. 1573-1760.  
Administration.

Crown Lands.

**Introduction.**

UNDER THE  
MUGHALS,  
A.D. 1573-1760.

Revenue  
Officials.

For its revenue administration each district or group of districts had its revenue officials called *amīns* who corresponded to the collector of modern times. There were also *amīns* in the customs department separate from those whose function was to control and administer the land revenue. Beneath the *amīn* came the *āmīl*<sup>1</sup> who carried on the actual collection of the land revenue or customs in each district or *parganāh*, and below the *āmīl* were the *jūils*, *mushrifis*, or *kārkāns* that is the revenue clerks. The *āmīl* corresponded to the modern *māmlūtlār*, both terms meaning him who carries on the *amal* or revenue management. In the leading ports the *āmīl* of the customs was called *mūtasaddi* that is civil officer.

Village  
Officials.

The *āmīl* or *māmlūtlār* dealt directly with the village officials, namely with the *mukaddam* or headman, the *patwār* or lease manager, the *kānūngō* or accountant, and the *harāldār* or grain-yard guardian. The *harāldār* superintended the separation of the government share of the produce; apportioned to the classes subject to forced labour their respective turns of duty; and exercised a general police superintendence by means of subordinates called *pasāitās* or *vāṭṭamīs*. In ports under the *mūtasaddi* was a harbour-master or *shāh-bandar*.

DESĀIS.

Crown sub-divisions had, in addition, the important class called *desāis*. The *desāi*'s duty appears at first to have been to collect the *sūlāmī* or tribute due by the smaller chiefs, landholders, and *vāntadars* or sharers. For this, in Akbar's time, the *desāi* received a remuneration of 2½ per cent on the sum collected. Under the first viceroy Mūza, Azīz Kokaltash (A.D. 1573-1575) this percentage was reduced to one-half of its former amount, and in later times this one-half was again reduced by one-half. Though the Muhammadan historians give no reason for so sweeping a reduction, the cause seems to have been the inability of the *desāis* to collect the tribute without the aid of a military force. Under the new system the *desāi* seems merely to have kept the accounts of the tribute due, and the records both of the amount which should be levied as tribute and of other customary rights of the crown. In later times the *desāis* were to a great extent superseded by the district accountants or *majmūdārs*, and many *desāis*, especially in south Gujarat, seem to have sunk to *patels*.

Land Tax.

Up to the viceroyalty of Mīrza Isā Tarkhān (A.D. 1612-1641), the land tax appears to have been levied from the cultivator in a fixed sum, but he was also subject to numerous other imposts. Land grants in *wāṭṭīyah* carried with them an hereditary title and special exemption from all levies except the land tax. The levy in kind appears to have ceased before the close of Mughal rule. In place of a levy in kind each village paid a fixed sum or *jama* through the district accountant or *majmūdār* who had taken the place of the *desāi*. As in many cases the *jama* really meant the lump sum at which the crown villages were assessed and farmed to the chiefs and *patels*, on the collapse of the empire many villages thus farmed to chiefs and landlords were

<sup>1</sup> In Marwāī and in the north and north-east this official was styled *tahsildār* and in the Dakhan *karnāvisdār*.

retained by them with the connivance of the *mujmudárs desáís* and others.

The administration of justice seems to have been very complete. In each *kasbah* or town *kázis*, endowed with glebe lands in addition to a permanent salary, adjudicated disputes among Muhammadans according to the laws of Islám. Disputes between Muhammadans and unbelievers, or amongst unbelievers, were decided by the department called the *sadrát*, the local judge being termed a *sadr*. The decisions of the local *kázis* and *sads* were subject to revision by the *kázi* or *sadr* of the *síbah* who resided at Ahmedábád. And as a last resort the Ahmedábád decisions were subject to appeal to the *Kázi-ul-Kuzáit* and the *Sadís-Sudáin* at the capital.

The revenue appears to have been classed under four main heads: 1. The *Khazánuh-i-Ámirah* or imperial treasury which comprehended the land tax received from the crown *parqanás* or districts, the tribute, the five per cent customs dues from infidels, the import dues on stuffs, and the *sáyer* or land customs including transit dues, slave, market dues, and miscellaneous taxes. 2. The treasury of arrears into which were paid government claims in arrear either from the *ámirás* or from the farmers of land revenue; *takávi* advances due by the *rayáts*; and tribute levied by the presence of a military force. 3. The treasury of charitable endowments. Into this treasury was paid the 2½ per cent levied as customs dues from Muhammadans.<sup>1</sup> The pay of the religious classes was defrayed from this treasury. 4. The treasury, into which the *jaziáh* or capitation tax levied from *zimnis* or infidels who acknowledged Muhammadan rule, was paid. The proceeds were expended in charity and public works. After the death of the emperor Farrukhsiyar (A.D. 1713-1719), this source of revenue was abolished. The arrangements introduced by Akbar in the end of the sixteenth century remained in force till the death of Aurangzib in A.D. 1707. Then trouble and perplexity daily increased, till in A.D. 1721-25, Hamid Khán usurped the government lands, and, seeking to get rid of the servants and assignments, gradually obtained possession of the records of the registry office. The keepers of the records were scattered, and yearly revenue statements ceased to be received from the districts.<sup>2</sup>

Akbar continued the system of assigning lands to military leaders in payment of their contingents of troops. Immediately after the annexation in A.D. 1573, almost the whole country was divided among the great nobles.<sup>3</sup> Except that the revenues of certain tracts were

## Introduction.

UNDER THE  
MUGHALS,  
A.D. 1573-1760.

Justice.

Fiscal.

Assigned Lands.

<sup>1</sup> *Zakat*, literally purification or cleansing, is the name of a tax levied from Muslims for charitable purposes or religious uses. In the endowments-treasury the customs dues from Muslims at 2½ per cent (the technical 1 in 10) as contrasted with the five per cent levied from infidels (the technical 2 in 10) were entered. Hence in these accounts *zakat* corresponds with the customs dues, and is divisible into two kinds *khushki zakat* or land customs and *tari zakat* or sea customs.

<sup>2</sup> Bird's History of Gujarat, 93. Though under the Mughal viceroys the state demand was at first realized in grain, at the last the custom was to assess each sub-division, and probably each village, at a fixed sum or *jama*. The total amount for the sub-division was collected by an officer called *mujmudár*, literally keeper of collections, the village headmen, *patels* or *mukuddams*, being responsible each for his own village.

<sup>3</sup> Bird's History of Gujarat, 325.

**Introduction.**

UNDER THE  
MUGHALS,  
A.D. 1573-1760.

**Assigned Lands.**

set aside for the imperial exchequer the directly governed districts passed into the hands of military leaders who employed their own agents to collect the revenue. During the seventeenth century the practice of submitting a yearly record of their revenues, and the power of the viceroy to bring them to account for misgovernment, exercised a check on the management of the military leaders. And during this time a yearly surplus revenue of £800,000 (Rs. 60,00,000) from the assigned and crown lands was on an average forwarded from Gujarat to Delhi. In the eighteenth century the decay of the viceroy's authority was accompanied by the gradually increased power of the military leaders in possession of assigned districts, till finally, as in the case of the Nawābs of Broach and Surat, they openly claimed the position of independent rulers.<sup>1</sup>

**Minor Offices.**

Of both leading and minor officials the Mirāt-i-Ahmedi supplies the following additional details. The highest officer who was appointed under the seal of the minister of the empire was the provincial *dirān* or minister. He had charge of the fiscal affairs of the province and of the revenues of the *khālsa* or crown lands, and was in some matters independent of the viceroy. Besides his personal salary he had 150 *sawārs* for two provincial *thunās* Arjanpur and Khambālia. Under the *dirān* the chief officers were the *pīshkār dirān* his first assistant, who was appointed under imperial orders by the patent of the *dirān*, the *darooghah* or head of the office, and the *sharif* or *mushrif* and *tehwildār* of the *daftār khānāhs*, who presided over the accounts with *munshis* and *muharrirs* or secretaries and writers. The *kāzis*, both town and city, with the sanction of the emperor were appointed by the chief law officer of the empire through the chief law officer of the province. They were lodged by the state, paid partly in cash partly in land, and kept up a certain number of troopers. In the *kāzi's* courts *wakīls* or pleaders and *muftīs* or law officers drew 8 as. to Re. 1 a day. Newly converted Musalmāns also drew 8 as. a day. The city censor or *muhfusih* had the supervision of morals and of weights and measures. He was paid in cash and land, and was expected to keep up sixty troopers. The news-writer, who was sometimes also *bakhshi* or military paymaster had a large staff of news-writers called *wākīl-nigār* who worked in the district courts and offices as well as in the city courts. He received his news-reports every evening and embodied them in a letter which was sent to court by camel post. A second staff of news-writers called *sawānī-nigār* reported rumours. A third set were the *harkārās* on the viceroy's staff. Postal *chunkis* or stations extended from Ahmedābād to the Ajmīr frontier, each with men and horse ready to carry the imperial post which reached Shīr Jhānābād or Delhi in seven days. A line of posts also ran south through Broach to the Dakhan. The *faujdlārs* or military police, who were sometimes commanders of a thousand and held estates, controlled both the city and the district police. The *kotwal* or head of the city night-watch was appointed by the viceroy. He had fifty troopers and a hundred foot. In the treasury department were the *amin* or chief, the *darooghah*, the

<sup>1</sup> Bird's History of Gujarāt, 341.

*mushrif*, the treasurer, and five messengers. In the medical department were a Yūnān or Greek school and a Hindu physician, two under-physicians on eight and ten annas a day, and a surgeon. The yearly grant for food and medicine amounted to Rs. 2000.<sup>1</sup>

Besides the class of vernacular terms that belong to the administration of the province, certain technical words connected with the tenure of land are of frequent occurrence in this history. For each of these, in addition to the English equivalent which as far as possible has been given in the text, some explanation seems necessary. During the period to which this history refers, the superior holders of the land of the province belonged to two main classes, those whose claims dated from before the Musalman conquest and those whose interest in the land was based on a Musalman grant. By the Musalman historians, landholders of the first class, who were all Hindus, are called *zamindārs*, while landholders of the second class, Musalmāns as a rule, are spoken of as *jāgīrdars*. Though the term *zamindār* was used to include the whole body of superior Hindu landholders, in practice a marked distinction was drawn between the almost independent chief, who still enjoyed his Hindu title of *rāja*, *rāval*, *rāo*, or *jām*, and the petty claimant to a share in a government village, who in a Hindu state would have been known as a *garásid*.<sup>2</sup>

The larger landholders, who had succeeded in avoiding complete subjection, were, as noticed above, liable only for the payment of a certain fixed sum, the collection of which by the central power in later times usually required the presence of a military force. With regard to the settlement of the claims of the smaller landholders of the superior class, whose estates fell within the limits of the directly administered districts, no steps seem to have been taken till the reign of Ahmed Shāh I (A.D. 1441-1445). About the year A.D. 1420 the peace of his kingdom was so broken by agrarian disturbances, that Ahmed Shāh agreed, on condition of their paying tribute and performing military service, to re-grant to the landholders of the *zamindār* class as hereditary possessions a one-fourth share of their former village lands. The portion so set apart was called *riutu* or share, and the remainder, retained as state land, was called *taluk*. This agreement continued till the year A.D. 1545, during the reign of Mubarriz Shāh II. (A.D. 1541-1553), an attempt was made to annex these private shares to the crown. This measure caused much discontent and disorder. It was reversed by the emperor Akbar who, as part of the settlement of the province in A.D. 1583, restored their one-fourth share to the landholders, and, except that the Marathas

## Introduction.

UNDER THE  
MUGHALS,  
A.D. 1573-1760.

## Land Tenures.

Hereditary  
Hindu  
Landholders

<sup>1</sup> Mirāt-i-Ahmedī Persian Text page 115.

<sup>2</sup> The title *rāja* is applicable to the head of a family only. The payment of tribute to the Mughals or Marāṭhas does not affect the right to use this title. *Rāva* and *rāv* seem to be of the same dignity as *rāja*. *Rāval* is of lower rank. The sons of *rājas*, *rāvas*, *rāvs*, and *rāvāls* are called *kayars* and their sons *thakurs*. The younger sons of *thakurs* became *bhūmīs*, that is landowners or *garasids*, that is owners of *garas* or a mouthful. *Jām* is the title of the chiefs of the Juleja tribe both of the elder branch in Kachh and of the younger branch in Navsāgar, or Little Kachh in Kathiawar. R. S. Mada, II, 277.

**Introduction.**

UNDER THE  
MUGHALS,  
A.D. 1573-1760.

**Levies.**

afterwards levied an additional quit-rent from these lands, the arrangements then introduced have since continued in force.<sup>1</sup>

During the decay of Musalmán rule in Gujarat in the first half of the eighteenth century, shahholders of the *garásia* class in government villages, who were always ready to increase their power by force, levied many irregular exactions from their more peaceful neighbours, the cultivators or inferior landholders. These levies are known as *rol* that is a forced contribution or *pál* that is protection. All have this peculiar characteristic that they were paid by the cultivators of crown lands to petty marauders to purchase immunity from their attacks. They in no case partook of the nature of dues imposed by a settled government on its own subjects. *Tora garás*, more correctly *toda garás*, is another levy which had its origin in eighteenth century disorder. It was usually a readymoney payment taken from villages which, though at the time crown or *khalsa*, had formerly belonged to the *garasia* who exacted the levy. Besides a readymoney payment contributions in kind were sometimes exacted.

**Service Lands.**

The second class of superior landholders were those whose title was based on a Musalmán grant. Such grants were either assignments of large tracts of land to the viceroy, district-governors, and nobles, to support the dignity of their position and maintain a contingent of troops, or they were allotments on a smaller scale granted in reward for some special service. Land granted with these objects was called *jágir*, and the holder of the land *jágirdár*. In theory, on the death of the original grantee, such possessions were strictly resumable; in practice they tended to become hereditary. No regular payments were required from holders of *jágirs*. Only under the name of *peshkash* occasional contributions were demanded. These occasional contributions generally consisted of such presents as a horse, an elephant, or some other article of value. They had more of the nature of a freewill offering than of an enforced tribute. Under the Musalmans contributions of this kind were the only payments exacted from proprietors of the *jágirdár* class. But the Marathas, in addition to contributions, imposed on *jágirdárs* a regular tribute, similar to that paid by the representatives of the original class of superior Hindu landholders.

Under Musalmán rule great part of Gujarat was always in the hands of *jágirdárs*. So powerful were they that on two occasions under the Ahmedábád kings, in A.D. 1554 and A.D. 1572, the leading

<sup>1</sup> Under the Marathas the title *zamindar* was bestowed on the farmers of the land revenue, and this practice was adopted by the earlier English writers on Gujarat. In consequence of this change small landholders of the superior class, in directly administered districts, came again to be called by their original Hindu name of *garasia*. Mr. Elphinstone (History, 79 and note 13) includes under the term *zamindar* (1) half-subdued chieftains, (2) independent governors of districts, and (3) farmers of revenue. He also notices that until Anrangzib's time such chiefs as enjoyed some degree of independence were alone called *zamindars*. But in Colonel Walker's time, A.D. 1805, at least in Gujarat (Bombay Government Selections, XXXIX, 25) the term *zamindar* included *devars*, *majmundars* (district accountants), *patils*, and *talukars* (village heads).

nobles distributed among themselves the entire area of the kingdom.<sup>1</sup> Again, during the eighteenth century, when Mughal rule was on the decline, the *patildars* by degrees won for themselves positions of almost complete independence.<sup>2</sup>

The changes in the extent of territory and in the form of administration illustrate the effect of the government on the condition of the people during the different periods of Musalmán rule. The following summary of the leading characteristics of each of the main divisions of the four-and-a-half centuries of Musalmán ascendancy may serve as an introduction to the detailed narrative of events.

On conquering Gujaráť in A.D. 1297 the Musalmáns found the country in disorder. The last kings of Apahajpur or Patan, suffering under the defects of an incomplete title, held even their crown lands with no firmness of grasp, and had allowed the outlying territory to slip almost entirely from their control. Several of the larger and more distant rulers had resumed their independence. The Firis and Kolis of the hills, forests, and rough river banks were in revolt. And stranger chiefs, driven south by the Musalmán conquests in Upper India, had robbed the central power of much territory.<sup>3</sup> The records of the early Musalmán governors (A.D. 1297-1391) show suspicion on the side of the Delhi court and disloyalty on the part of more than one viceroy, much confusion throughout the province, and little in the way of government beyond the exercise of military force. At the same time, in spite of wars and rebellions, the country, in parts at least, seems to

### Introduction.

CONDITION OF  
GUJARAT,  
A.D. 1297-1760.

Under the  
Early Viceroys,  
1297-1403.

<sup>1</sup> Details of A.D. 1571 given in the *Mut-i-Akbari* show that the chief nobles were bound to furnish cavalry contingents varying from 1000 to 25,000 horse and held lands estimated to yield yearly revenues of £160,000 to £1,625,000. *Ind's Gujarat*, 109-127.

<sup>2</sup> According to the European travellers in India during the seventeenth century, provincial governors, and probably to some extent all large holders of service lands, employed various methods for adding to the profits which the assigned lands were meant to yield them. Of these devices two seem to have been specially common: the practice of supplying a body of horse smaller than the number agreed for, and the practice of purveyance, that is of levying supplies without payment. Sir Thomas Roe, from A.D. 1615 to 1618 English ambassador at the court of the emperor Jahangir, gives the following details of these irregular practices. The Patan (that is Patna in Bengal) viceroy's government was estimated at 4000 horse, the yearly pay of each trooper being £20 (Rs. 2000), of which he kept only 1500, being allowed the surplus as dead pay. 'On one occasion this governor wished to present me with 100 loaves of the finest sugar, as white as snow, each loaf weighing fifty pounds. On my declining, he said, 'You refuse these loaves, thinking I am poor, but being made in my government the sugar costs me nothing, as it comes to me gratis.' Sir Thomas Roe in Kerr's *Voyages*, IX, 282-284. The same writer, the best qualified of the English travellers of that time to form a correct opinion, thus describes the administration of the Musalmán governors of the seventeenth century. 'They practise every kind of tyranny against the natives under their jurisdiction, oppressing them with continual exactions, and are exceedingly averse from any way being opened by which the king may be informed of their infamous proceedings. They grind the people under their government to extract money from them, often hanging men up by the heels to make them confess that they are rich, or to ransom themselves from faults merely imputed with a view to fleece them.' Sir Thomas Roe in Kerr's *Voyages*, IX, 334.

<sup>3</sup> Of these settlements the principal was that of the Kathol chief who in the thirteenth century established himself at Idar, now one of the *stans* of the Mahi Kantha. In the thirteenth century also, Gohils from the north and Solha Parmárs and Kathis from Sindh entered Gujarat. *Ras Mala*, II, 269.

**Introduction.**

CONDITIONS OF  
GUJARAT,  
A.D. 1297-1760.

Under the  
Kings,  
1403-1573.

have been well cultivated, and trade and manufactures to have been flourishing.<sup>1</sup>

The period of the rule of the Ahmedābād kings (A.D. 1403-1573) contains two divisions, one lasting from A.D. 1403 to A.D. 1530, on the whole a time of strong government and of growing power and prosperity; the other the forty-three years from A.D. 1530 to the conquest of the province by the emperor Akbar in A.D. 1573, a time of disorder and misrule. In A.D. 1403 when Gujarāt separated from Dehli the new king held but a narrow strip of plain. On the north were the independent chiefs of Sirohi and Jhalor, from whom he occasionally levied contributions. On the east the Raja of Idar, another Rājput prince, was in possession of the western skirts of the hills and forests, and the rest of that tract was held by the mountain tribes of Bhils and Kohls. On the west the peninsula was in the hands of nine or ten Hindu tribes, probably tributary, but by no means obedient.<sup>2</sup> In the midst of so unsettled and warlike a population, all the efforts of Muzaftar I., the founder of the dynasty, were spent in establishing his power. It was not until the reign of his successor Ahmed I. (A.D. 1412-1443) that steps were taken to settle the different classes of the people in positions of permanent order. About the year A.D. 1420 two important measures were introduced. Of these one assigned lands for the support of the troops, and the other recognised the rights of the superior class of Hindu landholders to a portion of the village lands they had formerly held. The effect of these changes was to establish order throughout the districts directly under the authority of the crown. And though, in the territories subject to feudatory chiefs, the presence of an armed force was still required to give effect to the king's claims for tribute, his increasing power and wealth made efforts at independence more hopeless, and gradually seemed the subjection of the greater number of his vassals. During the latter part of the fifteenth and the first quarter of the sixteenth century the power of the Ahmedābād kings was at its height. At that time their dominions included twenty-five divisions or *sarkars*. Among nine of these namely Pātan, Ahmedābād, Sūnth, Godhra, Champāner, Baroda, Broach, Nāndod or Rājpipla, and Surat the central plain was distributed. In addition in the north were four divisions, Sirohi, Jhalor, Jodhpur, and Nāgor now in south-west and central Rājputāna; in the north-east two, Dungarpur and Bānsvāda, now in the extreme

<sup>1</sup> Gujarāt of about the year A.D. 1300 is thus described: 'The air of Gujarāt is healthy, and the earth picturesque, the vineyards bring forth blue grapes twice a year, and the strength of the soil is such that the cotton plants spread their branches like willow and plane trees, and yield produce for several years successively. Besides Cambay, the most celebrated of the cities of Hind in population and wealth, there are 70,000 towns and villages, all populous, and the people abounding in wealth and luxuries.' Elliot's History of India, III. 31, 32, and 33. Marco Polo about A.D. 1292, says: 'In Gujarāt there grows much pepper and ginger and indigo. They have also a great deal of cotton. Their cotton trees are of very great size, growing full six paces high, and attaining to an age of twenty years.' Yule's Edition, II. 324. The cotton referred to was probably the variety known as *derkapus* (*Gossypium religiosum* or *peruvianum*), which grows from ten to fifteen feet high, and bears for several years. Royle, 149-150.

<sup>2</sup> Elphinstone's History, 762.

south of Rājputāna; in the east and south-east three, Nandurhār now in Khāndesh Mulher or Bāglān now in Nasik, and Rām Nagar or Dharāmpur now in Surat; in the south four, Dandā-Rājapuri or Janjira, Bombay, Bassein, and Daman now in the Konkan; in the west two, Sorath and Navānagar now in Kathiavāda, and Kachh in the north-west. Besides the revenues of these districts, tribute was received from the rulers of Ahmednagar, Burhānpur, Berār, Golkonda, and Bijāpur, and customs dues from twenty-five ports on the western coast of India and from twenty-six foreign marts, some of them in India and others in the Persian Gulf and along the Arabian coast.<sup>1</sup> The total revenue from these three sources is said in prosperous times to have amounted to a yearly sum of £11,160,000 (Rs. 11,16,00,000). Of this total amount the territorial revenue from the twenty-five districts yielded £5,840,000 (Rs. 5,84,00,000), or slightly more than one-half. Of the remaining £5,620,000 (Rs. 5,62,00,000) about one-fifth part was derived from the Dakhan tribute and the rest from customs-dues.<sup>2</sup>

The buildings at Ahmedābad, and the ruins of Chāmpāner and Mehmedābad, prove how much wealth was at the command of the sovereign and his nobles, while the accounts of travellers seem to show that the private expenditure of the rulers was not greater than the kingdom was well able to bear. The Portuguese traveller Duarte Barbosa, who was in Gujarāt between A.D. 1511 and A.D. 1514, found the capital Chāmpāner a great city, in a very fertile country of abundant provisions, with many cows, sheep and goats and plenty of fruit, so that it was full of all things.<sup>3</sup> Ahmedābad was still larger, very rich and well

## Introduction.

—  
CONDITION OF  
GUJARAT,  
A.D. 1297-1760.

Under the  
Kings,  
1403-1573.

<sup>1</sup> Burd's History of Gujarat, 110, 129, and 130.

<sup>2</sup> The passage from the Mirāt-i-Ahmedi, Burd '09, is: 'A sum of 25 *lakh*s of *huns* and one *koti* of *dirhams*, that were two parts greater, being altogether nearly equal to 5 *kotis* and 62 *lakh*s of rupees, was collected from the Dakhan tribute and the customs of the European and Arab ports.' The word *hun* from an old Karnatak word for gold, is the Musalman name for the coin known among Hindus as *varāha* or the wild-beast coin and among the Portuguese as the *pagoda* or temple coin. Prinsep Ind. Ant., Thomas' Ed. II. i. T. 18. The old specimens of this coin weigh either 60 grains the *muda* or half *pagoda*, or 120 grains the *hun* or full *pagoda*. Thomas, Chron. Pat. Ks. II. 224, note. The star *pagoda*, in which English accounts at Madras were formerly kept, weighs 52.56 grains, and was commonly valued at 8s. or Rs. 4 (Prinsep as above). At this rate in the present sum the 25 *lakh*s of *huns* would equal one *koti* (100 *lakh*s) of rupees. The *dirhams* 'two parts greater' than the *hun*, would seem to be a gold coin, perhaps a variety of the Persian *ashkan* (worth about 9s. English. Marsden, N. O. 155). Taking the two parts of a *hun* as *filanims* or sixteenths, this would give the *dirhams* a value of Rs. 4½, and make a total customs revenue of 125 *lakh*s of rupees. This statement of the revenues of the kingdom is, according to the author of the Mirāt-i-Ahmedi, taken from such times as the power of the Gujarat kings continued to increase. The total revenue of the twenty-five districts (£5,840,000) is the amount recovered in the year A.D. 1571. But the receipts under the head of Tribute must have been compiled from accounts of earlier years. For, as will be seen below, the neighbouring kings ceased to pay tribute after the end of the reign of Bahadur (A.D. 1536). Similarly the customs-revenues entered as received from Daman and other places must have been taken from the accounts of some year previous to A.D. 1560.

<sup>3</sup> The remains at Chāmpāner in the British district of the Panch Mahāls are well known. Of Mehmedābad, the town of that name in the district of Kaira, eighteen miles south of Ahmedābad, a few ruins only are left. In A.D. 1590 this city is said to have contained many grand edifices surrounded with a wall eleven miles (7 *kos*) square with at every ½ mile (¼ *kos*) a pleasure house, and an enclosure for deer and other game. (Ain-i-Akbari; Gladwin, II. 61.) The Mirāt-i-Ahmedi makes no special reference to the sovereign's share of the revenue. The greater part of the £5,620,000 derived from

**Introduction.**

CONDITION OF  
GUJARAT,  
A.D. 1297-1760

Under the  
Kings,  
1403-1573.

supplied, embellished with good streets and squares, with houses of stone and cement. It was not from the interior districts of the province that the Ahmedshahid kings derived the chief part of their wealth, but from those lying along the coast, which were enriched by manufactures and commerce.<sup>1</sup> So it was that along the shores of the gulf of Cambay and southward as far as Bombay the heart of the Gujarati kingdom, besides many small sea-ports, Barbosa chooses out for special mention twelve 'towns of commerce, very rich and of great trade.' Among these was Din, off the south coast of Kathiawada, yielding so large a revenue to the king as to be 'a marvel and amazement.' And chief of all Cambay, in a goodly, fertile, and pretty country full of abundant provisions; with rich merchants and men of great prosperity; with craftsmen and mechanics of subtle workmanship in cotton, silk, ivory, silver, and precious stones, the people well dressed, leading luxurious lives, much given to pleasure and amusement.

The thirty-eight years between the defeat of king Bahadur by the emperor Humayun in A.D. 1535 and the annexation of Gujarat by Akbar in A.D. 1573 was a time of confusion. Almost the superiority of Gujarat over the neighbouring powers was lost, and the limits of the kingdom shrank, at home, after the attempted confiscation (A.D. 1545) of their shares in village lands the disaffection of the superior landowners became general, and the court, beyond the narrow limits of the crown domains, ceased to exercise substantial control over

tribute and customs would probably go to the king, besides the lands specially set apart as crown domains, which in A.D. 1571 were returned as yielding a yearly revenue of £90,000 (900,000,000 *tankas*). This would bring the total income of the crown to a little more than 6½ millions sterling.

<sup>1</sup> So Sikandar Lodi emperor of Delhi, A.D. 1488-1517, is reported to have said: 'The magnificence of the kings of Delhi rests on wheat and barley, the magnificence of the kings of Gujarat rests on coral and pearls.' Bird, 32.

<sup>2</sup> The twelve Gujarat ports mentioned by Barbosa are: On the south coast of the peninsula, two: Patemra (Patan Somnath, now Veraval) very rich and of great trade; Smata-Mangalor (Mangrui), a town of commerce; and Din. On the shores of the gulf of Cambay four: Gozum (Goghe) a large town; Barbesy (Broach), Gandari or Gindar (Gandhar) a very good town; and Cambay. On the western coast five: Ravel (Rander), a rich place; Surat, a city of very great trade; Dabul (Dandev), a place of great trade; Basse (Bassim) a good seaport in which much goods are exchanged; and Tanamvamlu (Phana-Mahim) a town of great Moorish mosque, but of little trade. (Stanley's *Barbosa*, 69-68). The only one of these ports whose identification seems doubtful is Ravel, described by Barbosa (page 67) as a pretty town of the Moors on a good river twenty leagues south of Gandhar. This agrees with the position of Rander on the Tapti, nearly opposite Surat which appears in Al Biruni (A.D. 1030) as Rahamir one of the capitals of south Gujarat and is mentioned under the name Ravor, both in the *Am-i-Akbari* (A.D. 1590) and in the *Mirât-i-Ahmedi* for the year A.D. 1571, as a place of trade, 'in ancient times a great city.' In his description of the wealth of Cambay, Barbosa is supported by the other European travellers of the fifteenth and early sixteenth centuries. According to Nicolo de Conti (A.D. 1420-1441), the town including its suburbs, was twelve miles in circuit abounding in spikenard, lac, indigo, myrobalans, and silk. Athanasius Nikitin (A.D. 1468-1474) found it a manufacturing place for every sort of goods as long gowns, deer-skins and blankets, and Varthema (A.D. 1503-1508) says it abounds in grain and very good fruits, supplying Africa, Arabia and India with silk and cotton stuffs, it is impossible to describe its excellence. Barbosa's account of Ahmedabad is borne out by the statement in the *Am-i-Akbari* (Gladwin II. 63) that the whole number of the suburbs (*purus*) of the city was 360, and in the *Mirât-i-Ahmedi*, that it once contained 380 suburbs each of considerable size, containing good buildings and markets filled with everything valuable and rare, so that each was almost a city. Bird, 311.\*

either its chief nobles or the more turbulent classes. In spite of these forty years of disorder, the province retained so much of its former prosperity, that the boast of the local historians that in A.D. 1573 Gujarat was in every respect allowed to be the finest country in Hindustan is supported by the details shortly afterwards (A.D. 1590) given by Abul Fazl in the *Ain-i-Akbari*. The high road from Patan to Baroda was throughout its length of 150 miles (100 *kos*) lined on both sides with mango trees; the fields were bounded with hedges; and such was the abundance of mango and other fruit trees that the whole country seemed a garden. The people were well housed in dwellings with walls of brick and mortar and with tiled roofs; many of them rode in carriages drawn by oxen: the province was famous for its painters, carvers, mlayars, and other craftsmen.<sup>1</sup>

Like the period of the rule of the Ahmedabad kings, the period of Mughal rule contains two divisions, a time of good government lasting from A.D. 1573 to A.D. 1700, and a time of disorder from A.D. 1700 to A.D. 1760. Under the arrangements introduced by the emperor Akbar in A.D. 1583, the area of the province was considerably curtailed. Of its twenty-five districts nine were restored to the states from which the vicar of the Ahmedabad kings had wrested them; Jalor and Jodhpur were transferred to Rajputana; Nagor to Ajmer; Muller and Nandharur to Khandesh; Bombay, Bassen, and Daman were allowed to remain under the Portuguese; and Dand-Rajpuri (Dijna) was made over to the Nizamshahi (A.D. 1490-1595) rulers of the Dekkan Ahmednagar. Of the remaining sixteen, Sirohi, Dungarpur, and Banswara now in Rajputana, Kachh, Sindh in Rewa Kantha, and Raimnagar (Dharampur) in Surat were, on the payment of tribute, allowed to continue in the hands of their Hindu rulers. The ten remaining districts were administered directly by imperial officers. But as the revenues of the district of Surat had been separately assigned to its revenue officer or *mutasaddi*, only nine districts with 181 sub-divisions or *parautmils* were entered in the collections from the viceroy of Gujarat. These nine districts were in continental Gujarat. Patan with seventeen sub-divisions, Ahmedabad with thirty-three, Godhra with eleven, Chhambaner with thirteen, Baroda with four, Broach with four, and Rajpura (Nandod) with twelve. In the peninsula were South with sixty-two and Navanagar with seventeen sub-divisions. This lessening of area seems to have been accompanied by even more than a corresponding reduction in the state demand. Instead of £5,810,050 (Rs. 5,81,00,500), the revenue recovered in A.D. 1571, two years before the province was annexed, under the arrangement introduced by the emperor Akbar, the total amount, including the receipts from Surat and the tribute of the six feudatory

**Introduction.**

CONDITION OF  
GUJARAT,  
A.D. 1297-1760

Under the  
Mughals,  
1573-1760.

<sup>1</sup> Gladwin's *Ain-i-Akbari*, II, 62-63. Compare Terry (*Voyage*, 40, 131) in 1615: Gujarat a very goodly huge and exceeding rich province with, besides its most spacious populous and rich capital Ahmedabad, four fair cities (Bombay Baroda Broach and Surat) with great trade to the Red Sea, Achin, and other places. At the same time (Ditto, 179-180) though the villages stood very thick, the houses were generally very poor and base, all set close together some with earthen walls and flat roofs, most of them cottages miserably poor little and base set up with sticks rather than timber.

**Introduction.**

CONDITION OF  
GUJARAT.  
A.D. 1297-1760.

Under the  
Mughals,  
1573-1760.

districts, is returned at £1,999,113 (Rs. 1,99,91,130) or little more than one-third part of what was formerly collected.<sup>1</sup>

According to the *Mirāt-i-Ahmedi* this revenue of £1,999,113 (Rs. 1,99,91,130) continued to be realised as late as the reign of Muhammad Shah (A.D. 1719-1748). But within the next twelve years (A.D. 1748-1763) the whole revenue had fallen to £1,235,000 (Rs. 1,23,50,000). Of £1,999,113 (Rs. 1,99,91,130), the total amount levied by Akbar on the annexation of the province, £520,501 (Rs. 52,05,010), or a little more than a quarter, were set apart for imperial use and royal expense, £55,000 (Rs. 5,50,000) were assigned for the support of the viceroy and the personal estates of the nobles, and the remainder was settled for the pay of other officers of rank and court officials. Nearly £30,000 (Rs. 3,00,000) were given away as rewards and pensions to religious orders and establishments.<sup>2</sup>

<sup>1</sup> The decrease in the Mughal collections from Gujarat compared with the revenues of the Ahmedabad kings may have been due to Akbar's moderation. It may also have been due to a decline in prosperity. Compare Roe's (1617) account of Tolu about fifty miles south-east of Ajmer. It was the best and most populous country Roe had seen in India. The district was level with fertile soil abounding in corn cotton and cattle and the villages were so numerous and near together as hardly to exceed a *kos* from each other. The town was the best built Roe had seen in India tiled two storied houses good enough for decent shopkeepers. It had been the residence of a Rajput Raja before the conquests of Akbar Shah and stood at the foot of a good and strong rock about which were many excellent works of hewn stone, well cut, with many tanks arched over with well-turned vaults and large and deep descents to them. Near it was a beautiful grove two miles long and a quarter of a mile broad all planted with mangoes tamarinds and other fruit trees, divided by shady walks and interspersed with little temples and idol altars with many fountains wells and summer houses of carved stone curiously arched so that a poor hampered Englishman might have been content to dwell there. This observation may serve universally for the whole country that ruin and devastation operate everywhere. For since the property of all has become vested in the king no person takes care of anything so that in every place the spoil and devastations of war appear and nowhere is anything repaired. Roe in Kerr's Voyages, IX. 320-321.

<sup>2</sup> Bird's History of Gujarat. Another detailed statement of the revenue of Gujarat given in the *Mirāt-i-Ahmedi*, apparently for the time when the author wrote (A.D. 1700) gives: Revenue from crown lands £2,107,518, tribute-paying divisions or *sarkars* £12,700; Malh Kantha tribute £178,701, Wabak Kantha tribute £151,768, and Sagar Kantha tribute £121,151, in all £2,559,878 adding to this £20,000 for Kachh, £40,000 for Dimgapur, and £5000 for Sirohi gives a grand total of £2,614,878. According to a statement given by Bird in a note at page 108 of his History, the revenue of Gujarat under Jehangir (A.D. 1605-1627) averaged £1,250,000, under Aurangzeb (A.D. 1658-1707) £1,519,622, and under Muhammad Shah (A.D. 1719-1748) £1,218,300. In this passage the revenue under the emperor Akbar (A.D. 1556-1605) is given at £608,446. This total is taken from Gladwin's *Am-i-Akbari*. But at vol. II, page 73 of that work there would seem to be some miscalculation, for while the total number of *dams* (1/4th of a rupee) is 13,68,02,301, the conversion into rupees is Rs. 10,95,123 instead of Rs. 1,09,20,057½. The corresponding returns given by Mr. Thomas (loc. cit. of the Meg. Emp. page 52) are under Akbar, A.D. 1591, £1,092,412; under Shah Jahan, A.D. 1648, £1,325,000; and under Aurangzeb, A.D. 1658 £2,173,220, A.D. 1663-1666 £1,399,500, A.D. 1697 £2,350,700, and A.D. 1707 £1,519,623. The varieties in the currency employed in different parts of the accounts cause some confusion in calculating the Gujarat revenue. Under the Ahmedabad kings the accounts were kept in *tankas* or 1/4th of rupees, while under the Mughals *dams* or 1/4th of a rupee took the place of *tankas*. The revenues from Surat Baroda Broach and other districts south of the Mahi were returned in *chamtas*, a coin varying in value from something over 3/4ths of a rupee to slightly less than 1/2; the revenues from Rādhanpur and Morvi were entered in *mahmuds*, a coin nearly identical in value with the *chamtas*, while, as noticed above, the tribute and customs dues were returned in a gold currency, the tribute in *huns* of about 8s. (Rs. 4) and the customs in *brahmits* of 9s. (Rs. 4½).

## MUSALMAN PERIOD.

Besides lightening the state demand the emperor Akbar introduced three improvements: (1) The survey of the land; (2) The payment of the headmen or *mukaddams* of government villages; and (3) The restoration to small superior landholders of the share they formerly enjoyed in the lands of government villages. The survey which was entrusted to Rāja Todar Mal, the revenue minister of the empire, was completed in A.D. 1575. The operations were confined to a small portion of the whole area of the province. Besides the six tributary districts which were unaffected by the measure, Godhra in the east, the western peninsula, and a large portion of the central strip of directly governed lands were excluded, so that of the 181 sub-divisions only 64 were surveyed. In A.D. 1575, of 1,261,814 acres (12,360,594 *bighās*), the whole area measured, 4,920,818 acres (8,374,198 *bighās*, or about two-thirds were found to be fit for cultivation, and the remainder was waste. In those parts of the directly governed districts where the land was not measured the existing method of determining the government share of the produce either by selecting a portion of the field while the crop was still standing, or by dividing the grain heap at harvest time, was continued. In surveyed districts the amount paid was determined by the area and character of the land under cultivation. Payment was made either in grain or in money, according to the instructions issued to the revenue-collectors, 'that when it would not prove oppressive the value of the grain should be taken in ready money at the market price.'<sup>1</sup> The chief change in the revenue management was that, instead of each year calculating the government share from the character of the crop, an uniform demand was fixed to run for a term of ten years.

Another important effect of this survey was to extend to cultivators in simple villages the proprietary interest in the soil formerly enjoyed only by the shahholders of joint villages. By this change the power of the military nobles to make undue exactions from the cultivators in their assigned lands was to some extent checked. It was, perhaps, also an indirect effect of this more definite settlement of the crown demand that the revenue agents of government and of the holders of assigned lands, finding that the revenues could be realised without their help, refused to allow to the heads of villages certain revenue dues which, in return for their service, they had hitherto enjoyed. Accordingly, in A.D. 1589-90, these heads of villages appealed to government and Akbar decided that in assigned districts as well as in the crown domains from the collections of government lands two-and-a-half per cent should be set apart as a perquisite for men of this class.<sup>2</sup>

<sup>1</sup> *Am-i-Akbari* (Gladwin), I. 305. The *Am-i-Akbari* mentions four ways of calculating the state share in an unsurveyed field: (1) to measure the land with the crops standing and make an estimate; (2) to reap the crops, collect the grain in barns, and divide it according to agreement; (3) to divide the field as soon as the seed is sown, and (4) to gather the grain into heaps on the field and divide it there.

<sup>2</sup> The men to whom this 2½ per cent was granted are referred to in the *Mirāt-i-Ahmadi* as *desais*. Whatever doubt may attach to the precise meaning of the term *desai* it seems clear that it was as village headmen that the *desais* petitioned for and received this grant. These *desais* were the heads of villages with whom, as noticed above, the government agent for collecting the revenue dealt, and who, agreeing for the

## Introduction

POSITION OF  
GUJARAT,  
A.D. 1297-1760.

Under the  
Mughals,  
1573-1760.

**Introduction.**

CONDITION OF  
GUJARAT.  
A.D. 1297 - 1760.

Under the  
Mughals,  
1573 - 1760.

When the heads of villages laid their own private grievance before government, they also brought to its notice that the Kūh and Rājput landowners, whose shares in government villages had been resumed by the crown in A.D. 1545, had since that time continued in a state of discontent and revolt and were then causing the ruin of the subjects and a deficiency in the government collections. An inquiry was instituted, and, to satisfy the claims of landowners of this class, it was agreed that, on furnishing good security for their conduct and receiving the government mark on their contingent of cavalry, they should again be put in possession of a one-fourth share of the land of government villages. While the province was managed agreeably to these regulations, says the author of the *Mirāt-i-Ahmedī*, its prosperity continued to increase.<sup>1</sup>

Though these measures did much to check internal disorder, Gujarat, for several years after it came under Mughal control, continued disturbed by insurrections among the nobles, and so imperfectly protected from the attacks of foreign enemies that between the years A.D. 1573 and 1609 each of its three richest cities, Ahmedabad, Cambay and Surat, was in turn taken and plundered.<sup>2</sup> During the rest

whole village contribution, themselves carried out the details of allotment and collection from the individual cultivators. In the sharehold villages north of the Nerbada, the headman who would be entitled to this 2½ per cent was the representative of the body of village shareholders. South of the Nerbada, in villages originally colonised by officers of the state, the representatives of these officers would enjoy the 2½ per cent. In south Gujarat the *desais* or heads of villages also acted as district hereditary revenue officers, but it was not as distinct hereditary revenue officers, but as heads of villages, that they received from Akbar this 2½ per cent assignment. In north Gujarat there were *desais* who were only district revenue officers. These men would seem to have received no part of Akbar's grant in 1589-90, for as late as A.D. 1706 the emperor Aurangzib, having occasion to make inquiries into the position of the *desais*, found that hitherto they had been supported by cesses and illegal exactions, and ordered that a stop should be put to all such exactions, and a fixed assignment of 2½ per cent on the revenues of the villages under their charge should be allowed them. It does not appear whether the *desais* succeeded in obtaining Aurangzib's grant of 2½ per cent as district revenue officers in addition to Akbar's (A.D. 1589) assignment of 2½ per cent as heads of villages.

<sup>1</sup> Bird's History of Gujarat, 403.

<sup>2</sup> Ahmedabad (A.D. 1573) by Muzaffar Shāh the last king of Gujarat; Cambay (A.D. 1573) by Muhammad Husain Miṭṭa; and Surat (A.D. 1609) by Malik Ambar the famous general of the king of Ahmednagar. In such unsettled times it is not surprising that the European travellers of the late sixteenth and early seventeenth centuries, between Ahmedabad and Cambay found native merchants marching in large weekly caravans which rested at night within a space barricaded by carts. (Kerr, IX, 127 and 201.) The English merchants, on their way from one factory to another, were accompanied by an escort, and, in spite of their guard, were on more than one occasion attacked by large bands of Rājputs. (Kerr, IX, 127, 187, 201, 203.) As regards the state of the different parts of the province, Nicholas Uffet, who went from Agra to Surat about 1610, describes the north, from Jhātor to Ahmedabad, as throughout the whole way a sandy and woody country, full of thievish beastly men, and savage beasts such as lions and tigers; from Ahmedabad to Cambay the road was through sands and woods much infested by thieves, from Cambay to Broach it was a woody and dangerous journey; but from Broach to Surat the country was goodly, fertile, and full of villages, abounding in wild date trees. (Kerr, VIII, 303.) Passing from the mouth of the Tapti to Surat Mr. Copland (21st Dec. 1613) was delighted to see at the same time the goodliest spring and harvest he had ever seen. 'Often of two adjoining fields, one was as green as a fine meadow, and the other waving yellow like gold and ready to be cut down, and all along the roads were many goodly villages.' (Kerr, IX, 119.) At that time the state of north-west Gujarat was very different. Terry, 1617 (Voyage, 401), describes the passage of nineteen days from Māndu near Dhāc to Ahmedabad as short journeys in

of the seventeenth century, though the country was from time to time disturbed by Koli and Rājput risings, and towards the end of the century suffered much from the raids of the Marāthās, the viceroys were, on the whole, able to maintain their authority, repressing the outbreaks of the disorderly classes, and enforcing the imperial claims for tribute on the more independent feudatory chiefs. Throughout the greater part of the seventeenth century the general state of the province seems to have been prosperous. Its cities were the wonder of European travellers. Surat, which only since the transfer of Gujarāt to the Mughal empire had risen to hold a place among its chief centres of trade, was, in A.D. 1664, when taken by Shivāji, rich enough to supply him with plunder in treasure and precious stones worth a million sterling<sup>1</sup>; and at that time Cambay is said to have been beyond comparison greater than Surat, and Ahmedābad much richer and more populous than either.<sup>2</sup>

From the beginning of the eighteenth century disorder increased. Unable to rely for support on the imperial court, the viceroys failed to maintain order among the leading nobles, or to enforce their tribute from the more powerful feudatories. And while the small Koli and Rājput landholders, freed from the control of a strong central power, were destroying the military posts, taking possession of the state share of village lands, and levying dues from their more peaceful neighbours, the burden of the Marāthā tribute was year by year growing heavier. During the last ten years of Musalman rule so entirely did the viceroy's authority forsake him, that, according to the author of the *Mirāt-i-Ahmedi*, when the great landholders refused to pay their tribute, the viceroy had no power to enforce payment. And so faithless had the great landowners become that the viceroy could not pass the city gate without an escort.<sup>3</sup>

# Introduction.

CONDITION OF  
GUJARAT.  
A.D. 1297 - 1760.

Under the  
Mughals,  
1673-1760.

<sup>1</sup> a wilderness where a way had to be cut and made even and the great space required for the Mughal's camp and made idam by grubbing up trees and bushes. And between Cambay and Ahmedabad De la Valle, A.D. 1623 (Travels, Hakluyt Ed. I. 92), resolved to go with the kafilā since the insecurity of the ways did not allow him to go alone. Still at that time Gujarat as a whole (see above page 220 note 2) was an exceeding rich province, a description which twenty years later (1638) is borne out by Mandelslo (Travels, French Edition, 56): No province in India is more fertile; none yields more fruit or victuals. With the boast of the author of the *Mirāt-i-Ahmedi* (A.D. 1756) that Gujarāt was the richest province in India compare Khāfi Khān's (A.D. 1719) remark (Elliot, VII. 530), It is a province which no other province in India can equal.

<sup>2</sup> Oric's Historical Fragments, 12.

<sup>3</sup> The following are some of the notices of Ahmedābad and Cambay by the European travellers of the seventeenth century: Cambay, 1598, trade so great that if he had not seen it he would not have believed it possible (Caesar Frederick); 1623, indifferent large with sufficiently spacious suburbs and a great concourse of vessels (De la Valle, Hakluyt Edition, I. 66-67); 1638, beyond comparison larger than Surat (Mandelslo, 101-108); 1663-1671, twice as big as Surat (Baldæus in Churchill, III. 506). Ahmedābad, 1598, a very great city and populous (Caesar Frederick); 1623, competently large with great suburbs, a goodly and great city, with large fair and straight but sadly dusty streets (De la Valle, Hakluyt Edition, I. 95); 1627, large and beautiful with noisy broad and comely streets, a rich and uniform bazār, and shops redundant with gums perfumes spices silks cottons and calicoes (Herbert's Travels, 3rd Edition, 66); 1638, great manufactures, satin and velvet, silk and cotton (Mandelslo, 80); 1696, the greatest city in India, nothing inferior to Venice for rich silks and gold stuffs (Gemelli Careri in Churchill, IV. 188).

<sup>4</sup> Bird, 411.

## Introduction.

CONDITION OF  
GUJARAT,  
A.D. 1397-1760.

Self-governed  
Zamindars.

The above summary contains frequent references to three classes of *zamindars*. (1) The *zamindars* of the self-governed states; (2) The greater *zamindars* of the crown districts; and (3) The lesser *zamindars* of the crown districts.

In the case of the *zamindars* of self-governed states the principle was military service and no tribute. The author of the *Mirāt-i-Ahmedi* says that finally the *zamindars* of the self-governed states ceased to do service. In spite of this statement it seems probable that some of this class served almost until the complete collapse of the empire, and that tribute was rarely levied from them by an armed force. In the *Mirāt-i-Ahmedi* account of the office of *sābahdār* or *nizām subah* the following passage occurs: When occasion arose the *nizāms* used to take with their armies the contingents of the Rānās of Udepur Dūngarpur and Bānsvada, which were always permanently posted outside their official residences (in Ahmedabad). This shows that these great *zamindars* had official residences at the capital, where probably their contingents were posted under *uākils* or agents. It therefore seems probable that their tribute too would be paid through their representatives at the capital and that a military force was seldom sent against them. Accordingly notices of military expeditions in the tributary *sarkārs* are rare though they were of constant occurrence in the crown districts.

Crown  
Zamindars.

The position of the *zamindars* of the *khālṣa* or crown districts was very different from that of the *zamindars* of self-governed territories. The *khālṣa zamindars* had been deprived of the greater portion of their ancestral estates which were administered by the viceregal revenue establishment. In some instances their capitals had been annexed. Even if not annexed the capital was the seat of a *ḡanjdar* who possessed the authority and encroached daily on the rights and privileges of the chieftain. The principal chiefs in this position were those of Rājpipla and Idar in Gujarāt and the Jām of Navānagar in Kāthiāvāda. Of the three, Rājpipla had been deprived of his capital Nanded and of all the fertile districts, and was reduced to a barren sovereignty over rocks hills and Bhils at Rājpipla. Idar had suffered similar treatment and the capital was the seat of a Muhammadan *ḡanjdar*. Navānagar, which had hitherto been a tributary *sarkār*, was during the reign of Anrangzib made a crown district. But after Anrangzib's death the Jām returned to his capital and again resumed his tributary relations.

Smaller  
Zamindars.

The lesser holders, including *grāsīs wāntādārs* and others, had suffered similar deprivation of lands and were subject to much encroachment from the government officials. Throughout the empire widespread discontent prevailed among subordinate holders of this description as well as among all the *zamindars* of the crown districts, so that the successes of Shivaji in the Dakhan found ardent sympathisers even in Gujarāt. When the *zamindars* saw that this Hindu rebel was strong enough to pillage Surat they began to hope that a day of deliverance was near. The death of Anrangzib (A.D. 1707) was the signal for these restless spirits to bestir themselves. When the Marāthās began regular inroads they were hailed as deliverers from the yoke

of the Mughal. The Rájpipla chief afforded them shelter and a passage through his country. The encouragement to anarchy given by some of the Rájput viceroys who were anxious to emancipate themselves from the central control further enabled many chieftains *girástas* and others to absorb large portions of the crown domains, and even to recover their ancient capitals. Finally disaffected Muhammadan *faujdárs* succeeded in building up estates out of the possessions of the crown and founding the families which most of the present Muhammadan chieftains of Gujarat represent.

When the imperial power had been usurped by the Maráthha leaders, the chiefs who had just shaken off the more powerful Mughal yoke were by no means disposed tamely to submit to Maráthha domination. Every chief resisted the levy of tribute and Momin Khán reconquered Ahmedábád. In this struggle the Maráthhas laboured under the disadvantage of dissensions between the Peshwa and the Gaikwár. They were also unaware of the actual extent of the old imperial domain and were ignorant of the amount of tribute formerly levied. They found that the *faujdárs*, who, in return for Maráthha aid in enabling them to absorb the crown *paraganahs*, had agreed to pay tribute, now joined the *zamindárs* in resisting Maráthha demands, while with few exceptions the *desais* and *majmudárs* either openly allied themselves with the *zamindárs* or were by force or fraud deprived of their records. So serious were the obstacles to the collection of the Maráthha tribute that, had it not been for the British alliance in A.D. 1802, there seems little doubt that the Gaikwár would have been unable to enforce his demands in his more distant possessions. The British alliance checked the disintegration of the Gaikwár's power, and the permanent settlement of the tribute early in this century enabled that chief to collect a large revenue at a comparatively trifling cost. Not only were rebels like Malharao and Kanaji suppressed, but powerful servants like Vithalrav Deváji, who without doubt would have asserted their independence, were confirmed in their allegiance and the rich possessions they had acquired became part of the Gaikwár's dominions.

It must not be supposed that while the larger chiefs were busy absorbing whole *paraganahs* the lesser chiefs were more backward. They too annexed villages and even Mughal posts or *thánahs*, while *wántidárs* or sharers absorbed the *talpat* or state portion, and, under the name of *torg garis*,<sup>1</sup> daring spirits imposed certain rights over crown villages once their ancient possessions, or, under the name of *pál* or *rol*, enforced from neighbouring villages payments to secure immunity from pillage. Even in the Baroda district of the thirteen Mughal posts only ten now belong to the Gaikwár, two having been conquered by *girástas* and one having fallen under Bronch. In Sauráshtra except Ráppur and Gogha and those in the Amreli district, not a single Mughal post is in the possession either of the British Government or of the

## Introduction.

(COND)ITION OF  
GUJARAT,  
A.D. 1297 - 1700.

Maráthha  
Ascendancy,  
1760 - 1802.

Gaikwár Saved  
by British  
Alliance,  
1802.

## Power of Chiefs.

<sup>1</sup> The usual explanation of *tola garis* is the word *tola* meaning the beam-end above each house door. The sense being that it was a levy exacted from every house in the village. A more likely derivation is *tola* a heap or money-bag with the sense of a ready-money levy. *Tola* differed from *rol* in being exacted from the *garis* or land once the property of the levier's ancestors.

**Introduction.**

CONDITION OF  
GUJARAT,  
A.D. 1297-1802.

Power of  
Local Chiefs.

Gáikwár. A reference to the Mughal posts in other parts of Gujarát shows that the same result followed the collapse of Musalmán power.

Since the introduction of Musalmán rule in A.D. 1297 each successive government has been subverted by the ambition of the nobles and the disaffection of the chiefs. It was thus that the Gujarát Sultáns rendered themselves independent of Dehli. It was thus that the Sultán's territories became divided among the nobles, whose dissensions reduced the province to Akbar's authority. It was thus that the chiefs and local governors, conniving at Maratha inroads, subverted Mughal rule. Finally it was thus that the Gáikwár lost his hold of his possessions and was rescued from ruin solely by the power of the British.

# CHAPTER I.

## EARLY MUSALMÁN GOVERNORS.

A.D. 1297-1403.

EXCEPT the great expedition of Mahmúd Ghaznawi against Somnáth in A.D. 1021<sup>1</sup>; the defeat of Muhammad Muiz-ul-dín or Shaháb-ud-dín Ghori by Bhím Dev II. of Anahilaváda about A.D. 1178<sup>2</sup>; and the avenging sack of Anahilaváda and defeat of Bhím by Kutb-ud-dín Ibak in A.D. 1194, until the reign of Alá-ud-dín Khilji in A.D. 1295-1315, Gujarat remained free from Muhammadan interference<sup>3</sup>. In A.D. 1297, Ulugh Khán general of Alá-ud-dín and Nasrat Khán Wazir were sent against Anahilaváda. They took the city expelling Karan Waghela, usually called *Ghelo* The Mad, who took refuge at Devgad with Rámdeva the Yadav sovereign of the north Dakhan.<sup>4</sup> They next seized Khandgát (the modern Cambay), and, after appointing a local governor, returned to Delhi. From this time Gujarat remained under Muhammadan power, and Ulugh Khán, a man of great energy, by repeated expeditions consolidated the conquest and established Muhammadan rule. The Kanakdeva Rása says that he plundered Somnáth, and there is no doubt that he conquered Jhílor (the ancient Jhalmar) from the Songarha Chohans.<sup>5</sup> After Ulugh Khan had governed Gujarat for about twenty years, at the instigation of Malik Kafur, he was recalled and put to death by the emperor Alá-ud-dín.<sup>6</sup>

Ulugh Khán's departure shook Muhammadan power in Gujarat, and Kamál-ud-dín, whom Mubarak Khilji sent to quell the disturbances, was slain in battle. Sedition spread till Am-ul-Mulk Multán arrived

### Chapter I.

#### Early Musalmán Governors.

• Alá-ud-dín  
Khilji  
Emperor,  
1295-1315  
Ulugh KHAN;  
1297-1317.

AM-UL-MULK  
Governor,  
1318.

<sup>1</sup> Somnath (north latitude 0° 55', east longitude 70° 23'), the temple of Mahadev 'Lord of the Moon,' near the southern extremity of the peninsula of Kathiawar.

<sup>2</sup> Anahilaváda (north latitude 23° 48', east longitude 72° 2'), Nohrawá or Patan on the south bank of the Saraswati river, sixty-five miles north-east of Ahmedabad, was from A.D. 716 to A.D. 1298 the capital of the Rájput dynasties of Gujarat. As a result of Muhammad Ghori's defeat the *Chahá* i-Somath (Burgess, II. 213) states that the Turkish Afghan and Mughal prisoners, according to the rule of the Kurán (XXIV, 24) were divided, the wicked women to the wicked men and the good women to the good men. Of the male prisoners the better class after having their heads shaved were enrolled among the Chakawal and Wadhel tribes of Rájputs. The lower class were allotted to the Kohs, Khauts, Badmas, and Mer. All were allowed to keep their wedding and funeral ceremonies and to remain apart from other classes.

<sup>3</sup> The Mirat-i-Ahmadi gives an account of an expedition by one Alukhán a noble of Sultan Sangha's against Anahilaváda in A.D. 1257. He is said to have built the large stone mosque without the city. Alukhán returned unsuccessful, but not without laying tribute.

<sup>4</sup> Devgad near Danlatabad in the Dakhan, about ten miles north-west of Anrangabad (north latitude 19° 57', east longitude 75° 18'). The Mirat-i-Ahmadi has Devgañh Chundab, which is in the Central Provinces.

<sup>5</sup> Jhílor (north latitude 25° 23', east longitude 72° 40') in the Rájput state of Jodhpur, seventy miles south-west by south from the city of Jodhpur.

<sup>6</sup> Bayley (Gujarat, 39 note) shows strong ground for holding that, though Gujarat was conquered by Ulugh Khán a brother of Alá-ud-dín, its first governor was not Ulugh Khan but Alp Khán, a brother-in-law of Alá-ud-dín. According to this account Ulugh Khan died in A.D. 1299 and Alp Khán at Malik Kafur's instigation was killed in A.D. 1315. Zia Barni (Elliot, III. 169) supports this account.

**Chapter I.**

**Early  
Musalmán  
Governors.**

AIN-UL-MILK  
Governor,  
1318.

Order  
Established,  
1318.

Muhammad  
Tughlak  
Emperor,  
1325-1351.  
TAY-UL-MILK  
Governor,  
1320.

The Emperor  
Gives an  
Insurrection,  
1317.

with a powerful army, defeated the rebels and restored order. He was succeeded by Zafar Khán, who after completing the subjection of the country was recalled, and his place supplied by Hisám-ud-dín Parnár.<sup>1</sup> This officer, showing treasonable intentions, was imprisoned and succeeded by Malik Wájid-ud-dín Kuráshi, who was afterwards ennobled by the title of Taj or Sadr-ul-Mulk. Khusráw Khán Parnár was then appointed governor, but it is not clear whether he ever joined his appointment. The next governor to whom reference is made is Taj-ul-Mulk, who about A.D. 1320, was, for the second time, chosen as governor by Sultán Ghás-ud-dín Tughlak. He was succeeded by Malik Mukbil, who held the titles of Khán Jahán and Náib-ul-Mukhtar, and who was appointed by Sultan Muhammad Tughlak, A.D. 1325-1351. Subsequently the same emperor granted the government of Gujarát to Ahmad Ayáz, Malik Mukbil continuing to act as his deputy. Afterwards when Ahmad Ayáz, who received the title of Khwajah Jahan, proceeded as governor to Gujarát, Malik Mukbil acted as his minister. And about A.D. 1338, when Khwajah Jahan was sent against the emperor's nephew Karshásp and the Raja of Kampla<sup>2</sup> who had sheltered him, Malik Mukbil succeeded to the post of governor. On one occasion between Baroda and Dabhoi Malik Mukbil, who was escorting treasure and a caravan of merchants to Delhi, was plundered by some bands of the Amírání Sadah or Captains of Hundreds free-lances and freebooters, most of them New Musalmans or Mughal converts, and the rest Turk and Afghán adventurers. This success emboldened these handitti and for several years they caused loss and confusion in Gujarát. At last, about A.D. 1316, being joined by certain Muhammadan nobles and Hindu chieftains, they broke into open rebellion and defeated one Azíz, who was appointed by the emperor to march against them. In the following year, A.D. 1317, Muhammad Tughlak, advancing in person, defeated the rebels, and sacked the towns of Cambay and Surat. During the same campaign he drove the Gohil chief Mokheráji out of his stronghold on Parn Island near Gogha on the Gulf of Cambay, and then, landing his forces, after a stubborn conflict, defeated the Gohils, killing Mokheráji and capturing Gogha. Afterwards Muhammad Tughlak left for Daulatabád in the Dakhan, and in his absence the chiefs and nobles under Malik Tughán, a leader of the Amírání Sadah, again rebelled, and, obtaining possession of Patan, imprisoned Muizz-ud-dín the viceroy. The insurgents then plundered Cambay, and afterwards laid siege to Broach. Muhammad Tughlak at once marched for Gujarát and relieved Broach, Malik Tughán retreating to Cambay, whither he was followed by Malik Yúsuf, whom the emperor sent in pursuit of him. In the battle that ensued near Cambay, Malik Yúsuf was defeated and slain, and

<sup>1</sup> According to Zia Barni (Elliot, III. 218) Hisám-ud-dín was the mother's brother, according to others he was the brother of Hasan afterwards Khusraw Khán Parnár the favourite of Mubarak Sháh. On coming to Gujarát Hisám-ud-dín collected his Parnar kindred and revolted, but the nobles joining against him seized him and sent him to Delhi. To their disgust Mubarak in his infatuation for Hisám-ud-dín's nephew or brother, after slapping Hasan-ud-dín on the face set him at liberty.

<sup>2</sup> In the Káritak, probably on the Tungabhadra near Vijayanagar Briggs' Muhammadan Power in India, I. 418 and 428. Briggs speaks of two Kamplás one on the Ganges and the other on the Tungabhadra near Bijanagar.

all the prisoners, both of this engagement and those who had been previously captured, were put to death by Malik Tughán. Among the prisoners was Muizz-ul-din, the governor of Gujjarát. Muhammad Tughlak now marched to Cambay in person, whence Malik Tughán retreated to Pátan, pursued by the emperor, who was forced by stress of weather to halt at Asiwal.<sup>1</sup> Eventually the emperor came up with Malik Tughán near Kadi and gained a complete victory, Malik Tughán fleeing to Thatha in Sindh. To establish order throughout Gujjarát Muhammad Tughlak marched against Ghnár,<sup>2</sup> reduced the fortress,<sup>3</sup> and levied tribute from the chief named Khengár. He then went to Kaehh, and after subduing that country returned to Sorath. At Gondal he contracted a fever, and before he was entirely recovered, he advanced through Kaehh into Sindh with the view of subduing the Sumra chief of Thatha, who had sheltered Malik Tughán. Before reaching Thatha he succumbed to the fever, and died in the spring of A.D. 1351. Shortly before his death he appointed Nizám-ul-Mulk to the government of Gujjarát.

In A.D. 1351, Fíruz Tughlak succeeded Muhammad Tughlak on the throne of Delhi.\* Shortly after his accession the emperor marched to Sindh and sent a force against Malik Tughán. About A.D. 1360 he again advanced to Sindh against Jám Báburna. From Sindh he proceeded to Gujjarát, where he stayed for some months. Next year, on leaving for Sindh for the third time, he bestowed the government of Gujjarát on Zafar Khán in place of Nizám-ul-Mulk. On Zafar Khán's death, in A.D. 1373 according to Farishtah and A.D. 1371 according to the Mirát-i-Ahmedí, he was succeeded by his son Daryá Khán who appears to have governed by a deputy named Shams-ul-din Anwar Khán. In A.D. 1376, besides presents of elephants horses and other valuables, one Shams-ul-din Dáinghání offered a considerable advance on the usual collections from Gujjarat. As Daryá Khán would not agree to pay this sum he was displaced and Shams-ul-din Dáinghání was appointed governor. Finding himself unable to pay the stipulated amount this officer rebelled and withheld the revenue. Fíruz Tughlak sent an army against him, and by the aid of the chieftains and people, whom he had greatly oppressed, Shams-ul-din was slain. The government of the province was then entrusted to Farhat-ul-Mulk Rásti Khán. In about A.D. 1388, a noble named Skandar Khán was sent to supersede Farhat-ul-Mulk, but was defeated and slain by him. As the emperor Fíruz Tughlak died shortly after no notice was taken of Farhat-ul-Mulk's conduct and in the short reign of Fíruz's successor Ghias-ul-din Tughlak, no change was made in the government of Gujjarát. During the brief rule of Abn Bakr, Farhat-ul-Mulk continued

## Chapter I.

Early  
Musalmán  
Governors.

Muhammad  
Tughlak  
Emperor,  
1325-1351

Taj-ul-Mulk  
Governor,  
1320.

Subduer  
Kaehh and  
Káhh,  
1350.

Fíruz Tughlak  
Emperor,  
1351-1388

ZAFAR KHÁN  
Governor.

FARHAT-UL-  
MULK,  
Governor,  
1376-1381

<sup>1</sup> Asiwal (north latitude 23° 0'; east longitude 72° 36'), a town of some size, afterwards, A.D. 1413, made the capital of the Musalmán kings of Gujjarat and called Ahmedabad.

<sup>2</sup> Ghnár (north latitude 21° 30'; east longitude 70° 42'), in the Sorath sub-division of the peninsula of Kathiawár.

<sup>3</sup> Both the Mirát-i-Ahmedí and the Tárikh-i-Fíruz Sháhí say that the fortress was taken. The Sparkot or etalel of Jamálgub, in the plain about two miles west of Mount Ghnár, is probably meant.

## Chapter I.

Early  
Musalmán  
Governors.

Muhammad  
Tughlak II  
Emperor,  
1391-1393

undisturbed. But in A.D. 1391, on the accession of Násir-ul-dín Muhammad Tughlak II., a noble of the name of Zafar Khán was appointed governor of Gujarát, and despatched with an army to recall or, if necessary, expel Farhat-ul-Mulk.

This Zafar Khán was the son of Wajih-ul-Mulk, of the Tank tribe of Rájputs who claim to be of Suryaवंशि descent and together with the Gurjjaras appear from very early times to have inhabited the plains of the Punjab. Of Wajih-ul-Mulk's rise to power at the Delhi court the following story is told. Before he sat on the throne of Delhi, Firáz Tughlak, when hunting in the Punjab, lost his way and came to a village near Thanesar, held by chiefs and sons of the Tank tribe. He was hospitably entertained by two brothers of the chief's family named Saháran and Sádhar, and became enamoured of their beautiful sister. When his hosts learned who the stranger was, they gave him their sister in marriage and followed his fortunes. Afterwards Firáz persuading them to embrace Islám, conferred on Saháran the title of Wajih-ul-Mulk, and on Sadhar the title of Shamsúir Khán. Finally, in A.D. 1351, when Firáz Tughlak ascended the throne, he made Shamsúir Khán and Zafar Khán, the son of Wajih-ul-Mulk, his cup-bearers, and raised them to the rank of nobles.

ZAFAR KHÁN  
Governor,  
1391-1403.

Battle of Jijaur;  
Farhat ul Mulk  
Slain,  
1391.

In A.D. 1391, on being appointed viceroy, Zafar Khán marched without delay for Gujarát. In passing Nágara<sup>1</sup> he was met by a deputation from Cambay, complaining of the tyranny of Rásti Khán. Consoling them, he proceeded to Pátan, the seat of government, and thence marched against Rásti Khán. The armies met near the village of Khambhoi,<sup>2</sup> a dependency of Pátan, and Farhat-ul-Mulk Rásti Khán was slain and his army defeated. To commemorate the victory, Zafar Khán founded a village on the battle-field, which he named Jijaur (the city of victory), and then, starting for Cambay, redressed the grievances of the people.

Zafar Khán  
Attacked Idar,  
1393.

Zafar Khán's first warlike expedition was against the Páy of Idar,<sup>3</sup> who, in A.D. 1393, had refused to pay the customary tribute, and this chief he humbled. The contemporary histories seem to show that the previous governors had recovered tribute from all or most of the chiefs of Gujarát except from the Ray of Jámangadh<sup>4</sup> and the Raja of Rájputra,<sup>5</sup> who had retained their independence. Zafar Khán now planned an expedition against the celebrated Hindu shrine of Somnáth, but, hearing that Adil Khán of Asir-Bunhápur had invaded Sultánpur and Nandurbar,<sup>6</sup> he moved his troops in that direction, and Adil Khán retired to Asir.<sup>7</sup>

<sup>1</sup> Nágara (north latitude 27° 10', east longitude 73° 50'), in the Rathod state of Jodhpur, eighty miles north east of Jodhpur city.

<sup>2</sup> The Taluk it-i Akbar has Khamboi or Khampur. The place is Khambhoi about twenty miles west of Pátan.

<sup>3</sup> Idar is the principal state of the Main Kántha. The town of Idar is in north latitude 23° 50' and east longitude 73° 3'.

<sup>4</sup> Jámangadh in the Sorath sub-division of Kathiawar. This is Briggs' Rai of Jodhpur. Jámangadh was formerly called Jirangul, both names meaning ancient fortress.

<sup>5</sup> Rájputra is in the Rewa Kántha division of Gujarát.

<sup>6</sup> Sultánpur and Nandurbar now form part of the British district of Khándesh.

<sup>7</sup> Asir is now Nagvat north latitude 21° 26'; east longitude 76° 26'), beyond the north-eastern frontier of Khándesh.

In A.D. 1394, he marched against the Rájá of Jánágadh and exacted tribute. Afterwards, proceeding to Somnāth, he destroyed the temple, built an Assembly Mosque, introduced Islām, left Musalmán law officers, and established a *thána* or post in the city of Pátan Somnāth or Déva Putan. He now heard that the Hindus of Mándu<sup>1</sup> were oppressing the Muslims, and, accordingly, marching thither, he beleaguered that fortress for a year, but failing to take it contented himself with accepting the excuses of the Rájá. From Mándu he performed a pilgrimage to Ajmer.<sup>2</sup> Here he proceeded against the chiefs of Sāmbhar and Dandwāna, and then attacking the Rájputs of Delvāda and Jhalāvāda,<sup>3</sup> he defeated them, and returned to Pátan in A.D. 1396. About this time his son Tātār Khan, leaving his baggage in the fort of Pānpat,<sup>4</sup> made an attempt on Dehli. But Ikbāl Khān took the fort of Pānpat, captured Tātār Khān's baggage and forced him to withdraw to Gujarat. In A.D. 1397, with the view of reducing Idar, Zafar Khān besieged the fort, laying waste the neighbouring country. Before he had taken the fort Zafar Khān received news of Timur's conquests, and concluding a truce with the Idar Rájá, returned to Pátan.<sup>5</sup> In A.D. 1398, hearing that the Somnāth people claimed independence, Zafar Khān led an army against them, defeated them, and established Islām on a firm footing.

## Chapter I.

Early  
Musalmán  
Governors.

ZAFAR KHÁN  
Governor,  
1391-1403.

Exact's Tribute  
from Idar &c.,  
1394.

Lays Siege to  
Idar Fort,  
1397.

Establishes  
Islām at  
Somnāth,  
1398.

<sup>1</sup> Mándu (north latitude 22° 20', east longitude 75° 27'), one of the most famous forts in India, the capital of the Pathan dynasty of Malwa, A.D. 1401-1561, stands on the east of the Narmada about twenty-five miles south of Dhār. During a considerable part of the fifteenth century Mándu was either directly or indirectly under Gujarāt. An account of Mándu is given in the Appendix.

<sup>2</sup> Ajmer (north latitude 26° 29', east longitude 71° 43') the chief town of the district of the same name to which Sāmbhar and Dandwāna belong.

<sup>3</sup> Delvāda and Jhalāvāda are somewhat doubtful. The context suggests either Jhalor in Marwar or Jhalavāda in the extreme south-east of Rājputana south of Kotah. The combination Delvāda and Jhalāvāda seems to favour Kāthiāvāda since there is a Delvāda in the south of the peninsula near Dū and a Jhalāvāda in the north-east. But the Delvāda of the text can hardly be near Dū. It apparently is Delvāda near Bkhugji about twenty miles north of Udaipur. The account of Ahmed Shah's expedition to the same place in A.D. 1431 (below page 239) confirms this identification.

<sup>4</sup> Pānpat (north latitude 29° 23', east longitude 77° 2'), seventy-eight miles north of Dehli.

<sup>5</sup> Fārishtah (II. 365) calls the Idar chief Rāulal.

## CHAPTER II.

## A'HMEDA'BA'D KINGS.

A.D. 1403-1573. „

Chapter II.  
Ahmedābād  
Kings.  
A.D. 1403-1573.

THE rule of the Ahmedābād kings extends over 170 years and includes the names of fifteen sovereigns. The period may conveniently be divided into two parts. The first, lasting for a little more than a century and a quarter, when, under strong rulers, Gujarāt rose to consequence among the kingdoms of Western India, the second, from A.D. 1536 to A.D. 1573, an evil time when the sovereigns were minors and the wealth and supremacy of Gujarāt were wasted by the rivalry of its nobles.

The date on which Zafar Khān openly threw off his allegiance to Delhi is doubtful. Farishtah says he had the Friday prayer or *khutbah* repeated in his name after his successful campaign against Jhalāvāda and Delvāda in A.D. 1396. According to the *Mirāt-i-Sikandar* he maintained a nominal allegiance till A.D. 1403 when he formally invested his son Tātār Khān with the sovereignty of Gujarāt, under the title of Nāsir-ud-dīn Muhammad Shāh.

Muhammad I  
1403-1404

On ascending the throne in A.D. 1403, Muhammad Shāh made Asāwal his capital, and, after humbling the chief of Nāndod or Nādot in Rājputra, marched against Dehli by way of Pātan. On his way to Pātan the king sickened and died. His body was brought back to Pātan, and the expedition against Dehli came to nothing. It seems probable that this is a courtly version of the tale; the fact being that in A.D. 1403 Tātār Khān imprisoned his father at Asāwal, and assumed the title of Muhammad Shāh, and that Tātār Khān's death was caused by poison administered in the interest, if not at the suggestion, of his father Zafar Khān.<sup>1</sup>

Zafar Khān  
reigns as  
Muzaffar.  
1407-1419.

After the death of Muhammad Shāh, Zafar Khān asked his own younger brother Shams Khān Dandāni to carry on the government, but he refused. Zafar Khān accordingly sent Shams Khān Dandāni to Nāgor in place of Jalāl Khān Khokhar, and in A.D. 1407-8, at Bīrpur, at the request of the nobles and chief men of the country, himself formally mounted the throne and assumed the title of Muzaffar Shāh. At this time Alp Khān, son of Dilawar Khān of Mālwa, was rumoured to have poisoned his father and ascended the throne with the title of Sultān Hushang Ghorī. On hearing this Muzaffar Shāh marched against

<sup>1</sup> Compare Farishtah, II. 355-356. After his death Muhammad was known as Khudāi-gān-i-Shahīd, Our Lord the Martyr, according to the custom of the Sultans of Delhi, all of whom had three names, their family name, their throne name, and their after-death name whose letters contain the date of the monarch's decease. Thus the emperor Akbar's after-death title is 'Arsh-i-Ashdām, The Habler of the Heavenly Throne; the emperor Jehangir's is Jamiat Makani, The Dweller in Heaven; the emperor Shāh Jehān's is Firdaus Makani, He Whose Home is Paradise; and the emperor Aurangzib's is Khuld Makani, The Occupier of the Eternal Residence. Similarly the after-death title of Muzaffar Shāh, Zafar Khān's father, is Khudāgagan-i-Kabir, The Great Lord.

Hushang and besieged him in Dhár.<sup>1</sup> On reducing Dhár Muzaffar handed Hushang to the charge of his brother Shams Khán, on whom he conferred the title of Nasrat Khán. Hushang remained a year in confinement, and Músa Khán one of his relations usurped his authority. On hearing this, Hushang begged to be released, and Muzaffar Sháh not only agreed to his prayer, but sent his grandson Ahmed Khán with an army to reinstate him.\* This expedition was successful; the fortress of Mándu was taken and the usurper Músa Khán was put to flight. Ahmed Khán returned to Gujarát in A.D. 1409-10. Meanwhile Muzaffar advancing towards Dehli to aid Sultan Mahmúd (A.D. 1393-1413), prevented an intended attack on that city by Sultan Ibrahim of Jaunpúr. On his return to Gujarát Muzaffar led, or more probably despatched, an unsuccessful expedition against Kambhkot.<sup>2</sup> In the following year (A.D. 1410-11), to quell a rising among the Kols near Asáwal, Muzaffar placed his grandson Ahmed Khán in command of an army. Ahmed Khán camped outside of Pátan. He convened an assembly of learned men and asked them whether a son was not bound to exact retribution from his father's murderer. The assembly stated in writing that a son was bound to exact retribution. Armed with this decision, Ahmed suddenly entered the city, overpowered his grandfather, and forced him to drink poison. The old Khán said: 'Why so hasty, my boy. A little patience and power would have come to you of itself.' He advised Ahmed to kill the evil counsellors of murder and to drink no wine. Remorse so embittered Ahmed's after-life that he was never known to laugh.

On his grandfather's death, Ahmed succeeded with the title of Násir-ud-dunya Wad-dín Abúl fateh Ahmed Sháh. Shortly after Ahmed Sháh's accession, his cousin Moid-ud-dín Fírúz Khán, governor of Parvda, allying himself with Husám or Nizám-ul-Mulk Bhandári and other nobles, collected an army at Nakhád in Kara, and, laying claim to the crown, defeated the king's followers. Jivandas, one of the insurgents, proposed to march upon Patan, but as the others refused a dispute arose in which Jivandas was slain, and the rest sought and obtained Ahmed Sháh's forgiveness. Moid-ud-dín Fírúz Khán went to Cambay and was there joined by Masti Khán, son of Muzaffar Sháh, who was governor of Surat; on the king's advance they fled from Cambay to Broach, to which town Ahmed Sháh laid siege. As soon as the king arrived, Moid-ud-dín's army went over to the king, and Masti Khán also submitted. After a few days Ahmed Sháh sent for and forgave Moid-ud-dín, and returned to Asáwal victorious and triumphant.

In the following year (A.D. 1413-14)<sup>3</sup> Ahmed Sháh defeated Asa Bhil, chief of Asáwal, and, finding the site of that town suitable for his capital, he changed its name to Ahmedábád, and busied himself

## Chapter II.

Ahmedábád  
Kings,

A.D. 1403-1573.

Muzaffar.  
1407-1410.Ahmed I.  
1411-1441.Budda  
Ahmedábád,  
1413.

<sup>1</sup> Dhár (north latitude 22° 35'; east longitude 75° 20'), the capital of the state of Dhár thirty-three miles west of Mhow in Central India.

<sup>2</sup> The Tabakát-i-Akbári has Kantlikot a dependence of Kachh. This is probably correct.

<sup>3</sup> The date is doubtful. Farishtah (II, 630) gives A.D. 1412, the Ain-i-Akbári (Blochman's Edition, I, 607) A.D. 1411.

## Chapter II.

Ahmedabad  
Kings.

A.D. 1403-1573.

Ahmed I.  
1411-1441.  
Defends the  
Isar Chhat,  
1411.

in enlarging and fortifying the city.<sup>1</sup> During this year Moid-ul-din Firiz Khan and Masti Khan again revolted, and, joining the Idar Raja, took shelter in that fortress. A force under Fatah Khan was despatched against the rebels, and finally Firiz Khan and the Idar Raja were forced to flee by way of Kheri in a town in the district of Kadi. Moid-ul-din now persuaded Rukn Khan governor of Modasa, fifty miles north of Ahmedabad, to join. They united their forces with those of Badli-nli, Masti Khan, and Rannat Raja of Idar and encamped at Rangpura an Idar village about five miles from Modasa and began to strengthen Modasa and dig a ditch round it. The Sultan camped before the fort and offered favourable terms. The besieged bent on treachery asked the Sultan to send Nizam-ul-Mulk the minister and certain other great nobles. The Sultan agreed, and the besieged imprisoned the envoys. After a three days' siege Modasa fell. Badli-nli and Rukn Khan were slain, and Firiz Khan and the Raja of Idar fled. The imprisoned nobles were released unharmed. The Raja seeing that all hope of success was gone, made his peace with the king by surrendering to him the elephants horses and other baggage of Moid-ul-din Firiz Khan and Masti Khan, who now fled to Nagor, where they were sheltered by Shams Khan Dandani. Ahmed Shah after levying the stipulated tribute departed. Moid-ul-din Firiz Khan was afterwards slain in the war between Shams Khan and Rana Mokal of Chitor. In A.D. 1414-15 Uthman Ahmed and Sheikh Malik, in command at Patan, and Suleiman Afghin called Azam Khan, and Isa Salik rebelled, and wrote secretly to Sultan Hushang of Malwa, inviting him to invade Gujarat, and promising to seat him on the throne and expel Ahmed Shah. They were joined in their rebellion by Jhalu Satarsalji of Patli and other chiefs of Gujarat. Ahmed Shah despatched Latif Khan and Nizam-ul-Mulk against Sheikh Malik and his associates, while he sent Imad-ul-Mulk against Sultan Hushang, who retired, and Imad-ul-Mulk, after plundering Malwa, returned to Gujarat. Latif Khan, pressing in hot pursuit of Satarsal and Sheikh Malik, drove them to Sorath. The king returned with joyful heart to Ahmedabad.

Supposed  
to have  
voluntarily  
1411.

Spread of Islam  
1411.

Though, with their first possession of the country, A.D. 1297-1318, the Muhammadans had introduced their faith from Patan to Broach, the rest of the province long remained unconverted. By degrees, through the efforts of the Ahmedabad kings, the power of Islam became more directly felt in all parts of the province. Many districts, till then all but independent, accepted the Muhammadan faith at the hands of Ahmed Shah and agreed to the payment of a regular tribute. In A.D. 1411 he led an army against the Ravi of Junagadh and defeated him. The Ravi retired to the hill fortress of Ginnar. Ahmed Shah, though unable to capture the hill, gained the fortified citadel of Junagadh. Finding further resistance vain, the chief tendered his submission, and Junagadh was admitted among the tributary states.

<sup>1</sup> Four Ahmedis who had never missed the afternoon prayer helped to build Ahmedabad. Saeed Sheikh Ahmed Khattu, Sultan Ahmed, Sheikh Ahmed, and Mulla Ahmed. Compare Bombay Gazetteer, IV, 249 note 5.

<sup>2</sup> Called in the Tabakat-i-Akhbari the Raja of Mandal.

This example was followed by the greater number of the Sorath chiefs, who, for the time, resigned their independence. Sayad Abul Khair and Sayad Kasim were left to collect the tribute, and Ahmed Shah returned to Ahmedabad. Next year he marched against Sidhpur,<sup>1</sup> and in A.D. 1115 advanced from Sidhpur to Dhar in Malwa. At this time the most powerful feudatories were the Ray of Junagadh, the Ray of Champner,<sup>2</sup> the Raja of Nandol, the Ray of Idar, and the Raja of Jhalavada. Trimbekdas of Champner, Pınja of Idar, Siri of Nandol, and Mandhk of Jhalavada, alarmed at the activity of Ahmed Shah and his zeal for Islam, instigated Sultan Hushang of Malwa to invade Gujarat. Ahmed Shah promptly marched to Modasa,<sup>3</sup> forced Sultan Hushang of Malwa to retire, and broke up the conspiracy, reproving and punishing the chiefs concerned. About the same time the Sorath chiefs withheld their tribute, but the patience and unceasing activity of the king overcame all opposition. When at Modasa Ahmed heard that, by the treachery of the son of the governor, Nasir of Asir and Ghurat of Ghazul Khan of Malwa had seized the fort of Thaher in Sorpur in Khandesh, and, with the aid of the chief of Nandol, were marching against Sultanpur and Nandurbār. Ahmed sent an expedition against Nasir of Asir under Malik Mahmud Barkan Turki. When the Malik reached Nandol he found that Ghurat Khan had fled to Malwa and that Nasir had retired to Thaher. The Malik advanced, besieged and took Thaher, capturing Nasir whom Ahmed forgave and dignified with the title of Khan.<sup>4</sup>

After quelling these rebellions Ahmed Shah despatched Nizam-ul-Mulk to punish the Raja of Mandal near Virangām, and himself marched to Malwa against Sultan Hushang, whom he defeated, capturing his treasure and elephants. In A.D. 1118, in accordance with his policy of separately engaging his enemies, Ahmed Shah marched to chastise Trimbekdas of Champner, and though unable to take the fortress he laid waste the surrounding country. In A.D. 1119 he ravaged the lands round Sankheda<sup>5</sup> and built a fort there and a mosque within the fort; he also built a wall round the town of Mangni<sup>6</sup> and then marched upon Mandi. On the way ambassadors from Sultan Hushang met him suing for peace, and Ahmed Shah, returning towards Champner, again laid waste the surrounding country. During the following year (A.D. 1120) he remained in Ahmedabad bringing his own dominions into thorough subjection by establishing fortified posts and by humbling the chiefs and destroying their strongholds. Among other works he built the forts of Dohad<sup>7</sup> on the

## Chapter II.

Ahmedabad  
Kings,

A.D. 1103 - 1573.

Ahmed I.  
1411 - 1441.Ahmed I.  
Quells a Second  
Rebellion,  
1116.Expedition  
against Malwa,  
1117.Attacks  
on Champner,  
1118.

<sup>1</sup> Sidhpur (north latitude 25° 30', east longitude 72° 20'), on the Samsvati, fifty-eight miles north of Ahmedabad.

<sup>2</sup> Champner (north latitude 22° 30'; east longitude 73° 30'), in the British district of the Panch Mahals, from A.D. 1483 to A.D. 1560 the chief city of Gujarat, now in ruins.

<sup>3</sup> Modasa (north latitude 23° 27'; east longitude 73° 21'), fifty miles north-east of Ahmedabad.

<sup>4</sup> Mirat-i-Bikandari Persian Text, 31, 35; Firishtah, II, 363, 361.

<sup>5</sup> Sankheda is on the left bank of the Or river about twenty miles south-east of Baroda.

<sup>6</sup> Mangni Mahan or Manki, famous for its witches, eight miles east of Sankheda.

Mr. J. Pollen, I.C.S., J.L.D. Compare Bonn Gov. Rep. N. S. XXII, 98.

<sup>7</sup> Dohad (north latitude 22° 50'; east longitude 74° 10'), seventy-seven miles north-east of Baroda, now the chief town of the sub-division of the same name in the British district of the Panch Mahals. Mr. J. Pollen, I.C.S., J.L.D.

Chapter II.  
Ahmedábád  
Kings,  
A.D. 1403-1573.

Ahmed I  
1411-1441  
War with Málwa,  
1422.

Defeats the  
Ídar Chief,  
1425.

Málwa frontier and of Jítpur in Lámáváda.<sup>1</sup> In A.D. 1421 he repaired the fort in the town of Káhróth, otherwise called Meimún in Lámáváda, which had been built by Ulugh Khán Sanjar in the reign of Sultán Alá-ud-dín (A.D. 1295-1315) and changed the name to Sultanpur. He next advanced against Málwa and took the fort of Mesar. After an unsuccessful siege of Mándu he went to Ujjain.<sup>2</sup> From Ujjain he returned to Mándu, and failing to capture Mándu, he marched against Sarangpur.<sup>3</sup> Sultán Hushang sent ambassadors and concluded a peace. In spite of the agreement, while Ahmed Sháh was returning to Gujarát, Sultán Hushang made a night attack on his army and caused much havoc. Ahmed Sháh, collecting what men he could, waited till dawn and then fell on and defeated the Málwa troops, who were busy plundering. Sultán Hushang took shelter in the fort of Sarangpur to which Ahmed Sháh again laid siege. Failing to take the fort Ahmed retreated towards Gujarát, closely followed by Sultán Hushang, who was eager to wipe out his former defeat. On Hushang's approach, Ahmed Sháh, halting his troops, joined battle and repulsing Hushang returned to Ahmedábád.

In A.D. 1425 Ahmed Sháh led an army against Ídar, defeating the force brought to meet him and driving their leader to the hills. Ídar was always a trouble-some neighbour to the Ahmedábád kings and one difficult to subdue, for when his country was threatened, the chief could retire to his hills, where he could not easily be followed. As a permanent check on his movements, Ahmed Sháh, in A.D. 1427, built the fort of Ahmednagar,<sup>4</sup> on the banks of the Hátprati eighteen miles south-west of Ídar. In the following year the Ídar chief, Ráy Púnja, attacked a foraging party and carried off one of the royal elephants. He was pursued into the hills and brought to bay in a narrow pathway at the edge of a steep ravine. Púnja was driving back his pursuers when the keeper of the Sultán's elephant urged his animal against the Ráy's horse. The horse swerving lost his foothold and rolling down the ravine destroyed himself and his rider.<sup>5</sup>

During the two following years Ahmed Sháh abstained from foreign conquests, devoting himself to improving his dominions and to working out a system of paying his troops. The method he finally adopted was payment half in money and half in land. This arrangement attached the men to the country, and, while keeping them dependent on the state, enabled them to be free from debt. Further to keep his officials in check he arranged that the treasurer should be one of the king's slaves while the actual paymaster was a native of the particular locality. He also appointed *amils* that is sub-divisional revenue officers. After Ráy Púnja's death Ahmed Sháh marched upon Ídar, and did not return until Ráy Púnja's son agreed to pay an annual tribute of £300 (Rs. 3000). In the following year, according to Farishtah (II. 361) in spite of the young chief's promise

<sup>1</sup> Jítpur about twelve miles north-east of Bilásinor.

<sup>2</sup> Ujjain (north latitude 23° 10'; east longitude 75° 47'), at different times the capital of Málwa.

<sup>3</sup> Sarangpur about fifty miles north-east of Ujjain.

<sup>4</sup> Ahmednagar (north latitude 23° 31'; east longitude 73° 1') in the native state of Ídar.

Mirát-i-Sikandari Persian Text, 13.

to pay tribute, Ahmed Sháh attacked Ídar, took the fort, and built an assembly mosque. Fearing that their turn would come next the chief of Jhalaváda and Kánha apparently chief of Durgarpur fled to Nasir Khán of Asir. Nasir Khán gave Kánha a letter to Ahmed Sháh Bahmani, to whose son Alí-ud-dín Násir's daughter was married, and having detached part of his own troops to help Kánha they plundered and laid waste some villages of Nandurbár and Sultánpur. Sultán Ahmed sent his eldest son Muhammad Khán with Mukarrabul Mulk and others to meet the Dakháms who were repulsed with considerable loss. On this Sultán Ahmed Bahmani, under Kadr Khán Dakham, sent his eldest son Alí-ud-dín and his second son Khan Jehán against the Gujaratis. Kadr Khan marched to Daulatábád and joining Nasir Khán and the Gujarat rebels fought a great battle near the pass of Mánek Púj, six miles south of Nandgaon in Nasik. The confederates were defeated with great slaughter. The Dakham princes fled to Daulatábád and Kánha and Nasir Khán to Kalandá near Chálishgaon in south Khandesh.

In the same year (A.D. 1429), on the death of Kutub Khán the Gujarati governor of the island of Mahom, now the north part of the island of Bombay,<sup>1</sup> Ahmed Sháh Bahmani smarting under his defeats, ordered Hasan Izzat, otherwise called Mahk-ut-Tujjar, to the Konkan and by the Mahk's activity the North Konkan passed to the Dakháms. On the news of this disaster Ahmed Sháh sent his youngest son Za'far Khán with an army under Mahk Bakhár Khan, to retake Mahom. A fleet, collected from Dar Gogha and Cambay sailed to the Konkan, attacked "Thína" by sea and land, captured it and regained possession of Mahom. In A.D. 1431 Ahmed Shah advanced upon Champaur, and Ahmed Shah Bahmani anxious to retrieve his defeat at Mahom, marched an army into Baglan and laid it waste. This news brought Ahmed Shah back to Nandurbár. Destroying Nándol<sup>2</sup> he passed to Tambel, a fort in Baglan which Ahmed Shah Bahmani was besieging, defeated the besiegers and relieved the fort. He then went to Thána, repaired the fort, and returned to Gujarát by way of Sultánpur and Nandurbár. In A.D. 1432, after contracting his son Patch Khan in marriage with the daughter of the Rájá of Máhu to the south of Bassem Ahmed Sháh marched towards Nasik and exacted tribute and presents from the Rájá of Durgarpur.<sup>3</sup> From Durgarpur he went to Mewar, enforcing his

## Chapter II.

Ahmedábád  
Kings.

A.D. 1405-1573

Ahmed I  
1411-1441Governor  
Mahom,  
1429of Bombay  
1431

<sup>1</sup> There are two Mahoms on the North Konkan coast, one about twenty-two miles south of Bassem (north latitude 19° 10', east longitude 72° 17'), and the other in the northern extremity of the island of Bombay (north latitude 19° 2' east longitude 72° 54'). The southern Mahom, to which Fadishah (II, 370-371) is careful to apply the term *palah* of island, is the town referred to in the text. The northern Mahom, now known as Kelva Mahom, was, as is noted in the text, the head-quarters of a Hindu chief.

<sup>2</sup> Thína (north latitude 19° 11', east longitude 72° 0'), the head-quarters of the British district of that name, about twenty-four miles north by east of Bombay, was from the tenth to the sixteenth century A.D. the chief city in the Northern Konkan.

<sup>3</sup> Baglan, now called Saluma, is the northern subdivision of the British district of Nasik. In A.D. 1590 the chief commanded 8000 cavalry and 5000 infantry. The country was famous for fruit. Amir Aklári (Gladwin), II, 173. The chief, a Ráthod, was converted to Islam by Aurangzeb (A.D. 1656-1707).

<sup>4</sup> Durgarpur (north latitude 23° 50', east longitude 73° 50') in Rájputána, 150 miles south west of Alwar.

**Chapter II.**  
**Ahmedabad**  
**Kings.**  
 A.D. 1403-1453.

Ahmed I.  
 1411-1441

claims on Bindi and Kota, two Hāra Rajput states in south-east Rajputāna. He then entered the Delvāda country, levelling temples and destroying the palace of Rana Mokalsingh, the chief of Chitor. Thence he invaded Nagor in the country of the Rāthods, who submitted to him. After this he returned to Gujarat, and during the next few years was warring principally in Māhwa, where according to Farishtah, his army suffered greatly from pestilence and famine. Ahmed died in A.D. 1441 in the fifty-third year of his life and the thirty-third of his reign and was buried in the mausoleum in the Mauck Chawk in Ahmedabad. His after-death title is Khudagān-i-Maghfir the Forgiveness Lord in token that, according to his merciful promise, Allah the pitiful, moved by the prayer of forty believers, had spread his forgiveness over the crime of Ahmed's youth, a crime bewailed by a lifelong remorse.

Sultān Ahmed is still a name of power among Gujarāt Musalmāns. He is not more honoured for his bravery, skill, and success as a war leader than for his piety and his justice. His piety showed itself in his respect for three great religious teachers: Sheikh Rukn-ud-din the representative of Sheikh Moin-ud-din the great Khwājah of Ajmer, Sheikh Ahmed Khattn who is buried at Sarkhej five miles west of Ahmedabad, and the Bukhāran Sheikh Buhān-ud-din known as Kutbi Alam the father of the more famous Shah Alam. Of Ahmed's justice two instances are recorded. Sitting in the window of his palace watching the Sabarmati in flood Ahmed saw a large earthen jar float by. The jar was opened and the body of a murdered man was found wrapped in a blanket. The potters were called and one said the jar was his and had been sold to the headman of a neighbouring village. On inquiry the headman was proved to have murdered a grain merchant and was hanged. The second case was the murder of a poor man by Ahmed's son-in-law. The Kazi found the relations of the deceased willing to accept a blood fine and when the fine was paid released the prince. Ahmed hearing of his son-in-law's release and in the case of the rich fine is no punishment and ordered his son-in-law to be hanged.<sup>1</sup>

Muhammad II  
 1441-1452

Ahmed Shah was succeeded by his generous pleasure-loving son Muhammad Shah, Ghias-ud-dunya Wad-din, also styled Zairbaksh the Gold Giver. In A.D. 1446 Muhammad marched against Bir Rai of Idar, but on that chief agreeing to give him his daughter in marriage, he confirmed him in the possession of his state. His next expedition was against Kanha Rai of Dūngarpur, who took refuge in the hills, but afterwards returned, and paying tribute, was given charge of his country. Muhammad married Bibi Mughli, daughter of Jām Jīna of Tiettha in Sindh. She bore a son, Fatch Khān, who was afterwards Sultan Mahmūd Begada. In A.D. 1450, Muhammad marched upon Chāmpāner, and took the lower fortress. Gangadās of Chāmpāner had a strong ally in Sultan Mahmūd Khilji, the ruler of Malwa, and on his approach Muhammad Shah retired to Godhra, and Mahmūd

<sup>1</sup> Mirāt-i-Sikandar Persian Text, 15, 46.

<sup>2</sup> Godhra (north latitude 22° 45' ; east longitude 73° 30'), the chief town of the subdivision of that name in the British district of the Panch Mahals. The Muat-erikandari (Persian Text, 49) gives, probably rightly, Kothra a village of Savli or Savli about twenty miles north of Baroda.

Khulji continued his march upon Gujarāt at the head of 80,000 horse. Muhammad Shah was preparing to fly to Din, when the nobles, disgusted at his cowardice, caused him to be poisoned. Muhammad Shah's after-death title is Khūdugūn-i-Karīm the Gracious Lord.

In A.D. 1451 the nobles placed Muhammad's son Jalāl Khān on the throne with the title of Kutb-ud-dīn. Meanwhile Sultān Mahmūd of Malwa had laid siege to Sultānpur.<sup>1</sup> Malik Alā-ud-dīn bin Sohrāh Kutb-ud-dīn's commander surrendered the fort, and was sent with honour to Mālwa and appointed governor of Māndū. Sultān Mahmūd, marching to Sīrsa-Pāli, summoned Broach, then commanded by Sīdī Marjūn on behalf of Gujarāt. The Sīdī refused, and, fearing delay, the Mālwa Sultan after plundering Baroda proceeded to Nadiad, where Brahmans astonished him by their bravery in killing a mad elephant. Kutb-ud-dīn Shah now advancing met Sultān Mahmūd at Kapadvanj, where, after a doubtful fight of some hours, he defeated Sultān Mahmūd, though during the battle that prince was able to penetrate to Kutb-ud-dīn's camp and carry off his crown and jewelled girdle. The *Muāt-i-Sikandarī* ascribes Kutb-ud-dīn's victory in great measure to the gallantry of certain mihdatāfs of Dhadka called Darwāziyāhs. Muzaffar Khān, who is said to have incited the Malwa Sultān to invade Gujarāt, was captured and beheaded, and his head was hung up at the gate of Kapadvanj. On his return from Kapadvanj Kutb-ud-dīn built the magnificent Hauzī Kutb or Kankariyā Tank about a mile to the south of Ahmedābād. According to the *Muāt-i-Sikandarī* (Persian Text, 50-51) this war between Malwa and Gujarāt was controlled by the spiritual power of certain holy teachers. The war was brought on by the prayers of Shēh-i-Kamāl Malwa, whose shrine is in Ahmedabad behind Khudawand Khān's mosque near Shāh-i-Alam's tomb, who favoured Malwa. Kutb-ud-dīn's cause was aided by the blessing of Kutb-i-Alam who sent his son the famous Shāh Alam time after time to persuade Kamāl to be loyal to Gujarāt. At last Kamāl produced a writing said to be from heaven giving the victory to Malwa. The young Shāh Alam tore this charter to shreds, and, as no evil befel him, Kamāl saw that his spiritual power paled before Shāh Alam and fell back dead. Shāh Alam against his will accompanied Kutb-ud-dīn some marches on his advance to Kapadvanj. Before leaving him Shāh Alam blessed a mean camp elephant and ordered him to destroy the famous Malwa champion elephant known as the Butcher. He also, against his wish for he knew the future, at the Sultān's request bound his own sword round Kutb-ud-dīn's waist. In the battle the commissariat elephant ripped the Butcher and some years later Kutb-ud-dīn by accident gashed his knee with the saint's sword and died.

## Chapter II

### Ahmedābād Kings.

A.D. 1403-1573

Kutb-ud-dīn  
1451-1459

War with Malwa  
1451.

Birth of  
Kapadvanj,  
1451.

<sup>1</sup> Sultānpur (north latitude 21° 43', east longitude 74° 10'), in the north of the Shāhādā sub-division of the British district of Khambhā, till A.D. 1704 a place of consequence and the head quarters of a large district.

<sup>2</sup> Kapadvanj (north latitude 23° 2'; east longitude 73° 1'), the chief town of the sub-division of that name in the British district of Kaira.

<sup>3</sup> Dhadka (north latitude 22° 12', east longitude 72° 25'), the chief town of the sub-division of that name in the British district of Ahmedābād.

## Chapter II.

Ahmedabad  
Kings.

A.D. 1403-1473.

Kutb-ud-din  
1454-1459War with Nagor,  
1451-1459War with Chitor,  
1455-1459.

In the same year Sultan Mahmūd Khilji attempted to conquer Nāgor then held by Firūz Khān, a cousin of the Ahmedabad Sultan. Kutb-ud-din Shah despatched an army under the command of Sayad Atāullah and, as it drew near Sāmbhar,<sup>1</sup> the Mālwa Sultan retired and shortly after Firūz Khān died. Kūmbha Rāna of Chitor<sup>2</sup> now began interfering in the Nāgor succession on behalf of Shams Khān, who had been dispossessed by his brother Mujāhid Khān, and expelled Mujāhid. But as Shams Khan refused to dismantle the fortifications of Nāgor, the Chitor chief collected an army to capture Nāgor, while Shams Khān repaired to Kutb-ud-din Shah for aid and gave that sovereign his daughter in marriage. Upon this Kutb-ud-din sent Rai Anupchand Mānek and Malik Gadai with an army to Nāgor to repulse the Rana of Chitor. In a battle near Nāgor the Gujarat troops were defeated, and the Rāna after laying waste the neighbourhood of that city, returned to Chitor. In A.D. 1455-56, to avenge this raid, Kutb-ud-din Shah marched against Chitor. On his way the Devra Raja of Sirohi<sup>3</sup> attended Kutb-ud-din Shah's camp, praying him to restore the fortress of Abu,<sup>4</sup> part of the ancestral domain of Sirohi, which the Rana of Chitor had wrested from his house. The king ordered one of his generals, Malik Shaaban, to take possession of Abu and restore it to the Devra chieftain while he himself continued to advance against Kumbhalmer. Malik Shaaban was entangled in the defiles near Abu, and defeated with great slaughter, and shortly after Kutb-ud-din Shah, making a truce with Chitor, retired to his own country. On his return the Mālwa sovereign proposed that they should unite against Chitor, conquer the Rana's territories, and divide them equally between them. Kutb-ud-din agreed and in A.D. 1456-57 marched against the Rāna by way of Abu, which fortress he captured and handed to the Devra Raja. Next advancing upon Kumbhalmer, he plundered the country round, and then turned towards Chitor. On his way to Chitor, he was met by the Rāna, and a battle was fought, after which the Rāna fell back on his capital, and was there besieged by the Gujarat army. The siege was not pressed, and, on the Rāna agreeing to pay tribute and not to harass Nāgor, Kutb-ud-din withdrew to Gujarat, where he gave himself up to licentious excess. Meanwhile, the Rana by calling Mandi-ach<sup>5</sup> to Mālwa, came to terms with the Sultan of Māndu, and within three months attacked Nāgor. Kutb-ud-din Shah, though so overcome with drink as to be unable to sit his horse, mustered his troops and started in a palanquin. As soon as the Rana heard that the Gujarat army was in motion he retired, and the king returned Ahmedabad. A.D. 1458, he again led an army by way of Sirohi

<sup>1</sup> Sāmbhar (north latitude 26° 53'; east longitude 75° 13'), a town in the province of Ajmer, about fifty-one miles north-north-east from the city of Ajmer.

<sup>2</sup> Chitor (north latitude 24° 52'; east longitude 74° 14'), for several centuries before A.D. 1567 the capital of the principality of Udaipur.

<sup>3</sup> Sirohi (north latitude 24° 59'; east longitude 72° 56'), the capital of the principality of the same name in the province of Ajmer.

<sup>4</sup> Abu (north latitude 24° 45'; east longitude 72° 49') in the state of Sirohi.

The Raja is called Krishna Kishan or Kāsh Devra. Abu is still held by the Sirohi Devra.

<sup>5</sup> Mandi-ach (north latitude 24° 4'; east longitude 75° 9'), the chief town of a large district of the same name in the province of Mālwa.

and Kumbhalmer against Chitor, and laid waste the country. Soon after his return, according to one account by an accidental sword wound, according to another account poisoned by his wife, Kutb-ud-din died in May A.D. 1659 after a reign of seven years and seven days. He was brave with a sternness of nature, which, under the influence of wine, amounted to fierceness. His after-death title is Sultān-i-Ghāzi the Warrior King.

\* On the death of Kutb-ud-din Shāh, the nobles raised to the throne his uncle Daud, son of Ahmed Shah. But as Daud appointed low-born men to high offices and committed other foolish acts, he was deposed, and in A.D. 1159 his half-brother Fatch Khan the son of Muhammad Shah, son of Ahmed Shah by Bibi Mughh a daughter of Jam Jūna of Thāthra in Sindhi, was seated on the throne at the age of little more than thirteen with the title of Mahmut Shah.

The close connection of Fatch Khan with the saintly Shah Ann is a favourite topic with Gujarati historians. According to the *Muāz-i-Sikandar* (Persian Text, 66-70) of his two daughters Jām Jūna intended Bibi Mughh the more beautiful for the Saint and Bibi Mughh the less comely for the Sultan. By bribing the Jām's envoys the king secured the prettier sister. The enraged Saint was consoled by his father who said: "My son, to you will come both the cow and the calf." After Muhammad II's death, fear of Kutb-ud-din's designs against the young Fatch Khan forced Bibi Mughh to seek safety with her sister, and on her sister's death she married the Saint. Kutb-ud-din made several attempts to seize Fatch Khan. But by the power of the Saint when Kutb-ud-din attempted to seize him Fatch Khan in body as well as in dress became a girl. According to one account Kutb-ud-din met his death in an attempt to carry off Fatch Khan. As he rode into the Saint's quarter Death in the form of a mad camel met the king. The king struck at the phantom, and his sword cleaving the air gashed his knee. This was the Saint's sword, which against his will, for he knew it would be the death of the king, Kutb-ud-din forced Shāh Ann to lend round him before the battle of Kapadvanj.

The death of his uncle, the late Sultān Daud, who had become a religious devotee, relieved Fatch Khan of one source of danger. Shortly after certain of the noble nobles, Seif-ul-Mulk, Kabir-ud-din Sultān, and others, had ul-Mulk, Bannu-ul-Mulk and Hasan-ul-Mulk represented to the Sultān that the minister Shaibān Imād-ul-Mulk contemplated treason and wished to set his son on the throne. Having seized and imprisoned the minister in the Bhadra citadel and set five hundred of their trusted retainers as guards over him, the rebels retired to their homes. At nightfall Abdullah, the chief of the elephant stables, going to the young Sultān represented to him that the nobles who had imprisoned Imād-ul-Mulk were the real traitors and had determined to place Halāb Khān, an uncle of the Sultān's, on the throne. The Sultān consulting his mother and some of his faithful friends ordered Abdullah at daybreak to equip all his elephants in full armour and draw them up in the square before the Bhadra. He then seated himself on the throne and in a voice of feigned anger ordered one of the courtiers to bring out Shaibān Imād-ul-Mulk, that he might wreak his vengeance

## Chapter II.

## Ahmedābād

## Kings.

A.D. 1103-1573.

Mohmud I  
(Bogadi),  
1459-1513

Details of  
Chronology,  
1159.

**Chapter II.****Āhmedābād  
Kings.**

A.D. 1103-1573.

Mahmūd I.  
(Bogadā).  
1459-1513.Improves the  
Subhary,  
1159-1161.Helps the King  
of the Dakhan,  
1161.

upon him. As these orders were not obeyed the Sultān rose, and walking up the Bhadra called: "Bring out Shaābān!" The guards brought forth Imad-ul-Mulk, and the Sultān ordered his fetters to be broken. Some of the nobles' retainers made their submission to the Sultān, others fled and hid themselves. In the morning, hearing what had happened, the refractory nobles marched against the Sultān. Many advised the Sultān to cross the Sabarnati by the postern gate and retire from the city, and, after collecting an army, to march against the nobles. Giving no ear to these counsels the young Sultān ordered Abdullāh to charge the advancing nobles with his six hundred elephants. The charge dispersed the malecontents who fled and either hid themselves in the city or betook themselves to the country. Some were killed, some were trampled by the Sultān's orders under the elephants' feet, and one was pardoned.<sup>1</sup> His religious ardour, his love of justice, his bravery, and his wise measures entitle Mahmūd to the highest place among the Gujarāt kings. One of the measures which the Mirāt-i-Sikandari specially notices is his continuance of land grants to the son of the holder, and in cases where there was no male issue of half the grant to the daughter. His firm policy of never onsting the landholder except for proved oppression or exaction was productive of such prosperity that the revenue increased two three and in some cases tenfold. The roads were safe from freebooters and trade was secure. A rule forbidding soldiers to borrow money at interest is favourably noticed. A special officer was appointed to make advances to needy soldiers with the power to recover from their pay in fixed instalments.<sup>2</sup> Mahmūd also devoted much attention to the culture of fruit trees.<sup>3</sup> In A.D. 1161, or A.D. 1162 according to Farishtah, Nizām Shāh Bahmanū (A.D. 1161-1163), king of the Dakhan, whose country had been invaded by Sultān Mahmūd Khulji of Mālwa, applied for help to the Gujarāt king. Mahmūd Shāh at once started to Nizām Shāh's aid, and on his way receiving another equally pressing letter from the Dakhan sovereign, and being joined by the Bahmani general Khwājāh Jehān Gāwan, he

<sup>1</sup> Persian Text, Mirāt-i-Sikandari, 75-76.

<sup>2</sup> The Portuguese merchant and traveller Barbosa (A.D. 1541-1544) gives the following details of Mahmūd Begadā's cavalry. The Moors and Gentles of this kingdom are bold riders mounted on horses bred in the country, for it has a wonderful quantity. They ride on small saddles and use whips. Their arms are very thick round shields edged with silk; each man has two swords, a dagger, and a Turkish bow with very good arrows. Some of them carry maces, and many of them coats-of-mail, and others tunics quilted with cotton. The horses have housings and steel headpieces, and so they fight very well and are light in their movements. The Moorish horsemen are white and of many countries, Turks and Mamelukes, military slaves from Georgia Circassia and Mingchia, Arabs Persians Khorasān Turkomans, men from the great kingdom of Dehli, and others born in the country itself. Their pay is good and they receive it regularly. They are well dressed with very rich stuffs of gold silk cotton and goat's wool, and all wear caps on their heads, and their clothes long, such as morisco sluits and drawers, and leggings to the knee of good thick leather worked with gold knots and embroidery, and their swords richly ornamented with gold and silver are borne in their girdles or in the hands of their pages. Their women are very white and pretty also very richly decked out. They live well and spend much money. Stanley's Barbosa, 55-56.

<sup>3</sup> Mahmūd's favourite trees were the mango *ambo* Mangifera indica, *rān* Mimosa pudica, *pimbu* Eugenia jambolana, *gular* Ficus glomerata, tamarind *ānli* Tamarindus indica, and the shrubby *phyllanthus ānli* Emblica officinalis.

pushed on with all speed by way of Burhānpur.<sup>1</sup> When Sultān Mahmūd Khilji heard of his approach, he retired to his own country by way of Gondwana,<sup>2</sup> from thirst and from the attacks of the Gonds, losing 5000 to 6000 men. The king of Gujarāt, after receiving the thanks of the Dakhan sovereign, returned to his own dominions. In A.D. 1462 Sultān Mahmūd Khilji made another incursion into the Dakhan at the head of 90,000 horse, plundering and laying waste the country as far as Danlatabad. Again the Dakhan sovereign applied for help to Mahmūd Shāh, and on hearing of Mahmūd's advance the Malwa Sultān retired a second time to his own dominions. Mahmūd Shāh now wrote to the Malwa Sultān to desist from harassing the Dakhan, threatening, in case of refusal, to march at once upon Māndū. His next expedition was against the pirate zamīndars of the hill fort of Barūr and the bandar of Dān or Dahann, whose fort he took, and after imposing an annual tribute allowed the chief to continue to hold his hundred villages.<sup>3</sup>

Mahmūd Shāh next turned his thoughts to the conquest of the mountain citadel of Gurnar in central Kāthiavāda.<sup>4</sup> In A.D. 1467 he made an attack on the fort of Jūnāgadh, and receiving the submission of Rāv Mandlik, the local ruler, returned to his capital. In the following year, hearing that the Jūnāgadh chief continued to visit his idol temple in state with a golden umbrella and other ensigns of royalty, Mahmūd despatched an army to Jūnāgadh, and the chief sent the obnoxious umbrella to the king, accompanied by fitting presents. In A.D. 1469 Mahmūd once more sent an army to ravage Sorath, with the intention of finally conquering both Jūnāgadh and Gurnar. While Mahmūd was on the march the Rāv Mandlik suddenly joined him, and asking why the Sultān was so bent on his destruction when he had committed no fault, agreed to do whatever Mahmūd might command. The king replied there is no fault like infidelity, and ordered the Rāv to embrace Islam. The chief, now thoroughly alarmed, fled by night and made his way into Gurnar. In A.D. 1472-73 after a siege of nearly two years, forced by the failure of his stores, he quitted the fort and handing the keys to the king, repeated after him the Muhammadan profession of faith. Though the Rāv's life was spared Sorath from this date became a crown possession, and was governed by an officer appointed by the king and stationed at Jūnāgadh. At the close of the war Mahmūd Shāh repaired the fort Jehānpānah, the present outer or town wall of Jūnāgadh, and, charmed with the beauty of the neighbourhood, settled sayads and learned men at Jūnāgadh and other towns

## Chapter II.

### Ahmedābād Kings.

A.D. 1403-1573.

\* Mahmud I.  
(Begada).  
1459-1513.

Expedition  
against  
Jūnāgadh,  
1467.

Capture of  
Gurnar,  
1472.

<sup>1</sup> Burhānpur (north latitude 21° 18' ; east longitude 76° 20'), under the Musahāns the capital of Khandesh, now within the limits of the Berārs.

<sup>2</sup> Gondwana, a large hilly tract lying between north latitude 19° 50' and 24° 30' and east longitude 77° 38' and 87° 20'.

<sup>3</sup> The Muātt-i-Sikandari (Persian Text, page 89) gives the hill fort of Barudar. The Persian *r* may be a miswritten *g* and the *d* a mistake for *x* that is Baguwar or Baguwacab. The seaport Dān may be Dungi hill six miles from the coast. But Dān for Dahann a well-known port in north Phana is perhaps more likely. Farishtah (Biggs, IV. 51) gives Bayur for Barū and Dura for Dān. Compare Tabakat-i-Akbari in Bayley's Gujarat, page 178 note 2.

<sup>4</sup> Gurnar the diadem of Kāthiavāda. See above page 231 note 2.

**Chapter II.**  
**Ahmedábád**  
**Kings,**  
**A.D. 1103-1573.**

**Mahmūd I.**  
**(Bégada).**  
**1459-1513.**  
 Disturbances  
 in Champāner,  
 1172.

in Sorath. He induced the nobles to build houses, himself raised a palace and made the new city his capital under the name of Mustafábád and enforced his claims as overlord on all the neighbouring chiefs. It is true that in the times of Ahmed Sháh these chieftains, including even the Júnágadh Ráy himself, had paid tribute. But Mahmūd established Ahmedábid rule so firmly that the duty of collecting the tribute was entrusted to an officer permanently settled in the country. The author of the *Mirát-i-Sikandari* dilates on the dense woods round Júnágadh, full of mango, *ráen*, *jámbu*, *gúlar*, *ámli*, and *áonla*<sup>1</sup> trees, and notes that this forest tract was inhabited by a wild race of men called Khánts.<sup>2</sup>

During Mahmūd Sháh's prolonged absence from his capital, Malik Jamál-ud-dín was appointed governor of Ahmedábád, with the title of Muháliz Khán that is Care-taker. At this time Jesingh, son of Gangádás the chief of Champāner, harassed the country round Pavágad. The king appointed Bahá-ul-Mulk, who had the title of Imad-ul-Mulk, to the command of Sankheda; Malik Sárang Kiwám-ul-Mulk to the command of Godhra; and Taj Khan bin Sakár to the command of Norkha and Dákhna on the Mahi. In consequence of these precautions Jesingh abstained from rebellion. At this time the Ráy Mandlik received the title of Khán Jalam, and lands were bestowed on him, while the golden idols, which had been taken from the Júnágadh temples, were broken and distributed among the soldiers.

Conquest of  
 Kachh.

Mahmūd Sháh's next expedition was against the turbulent inhabitants of the confines of Sindh. These were Jádejás, though they are described as Rajputs of the Sumra and Sodha tribes.<sup>3</sup> They appear to have readily submitted, and to have voluntarily sent men to Júnágadh to be instructed in Islám and to settle in Gujarat. Shortly afterwards they again became troublesome, and the king advancing into Kachh completely defeated them. About this time a learned man, Mulla Mahmūd Samarkandi on his way from the Dakhan to Central Asia, complained to the king that he had been robbed by the pirates of Jagat or Dwárka.<sup>4</sup> On hearing of this outrage Mahmūd Sháh marched to Jagat, took the fort, and destroyed the idol temples. The pirates, in the first instance, retired to the island of Shankhodár or Bet, but from this, too, after a stout resistance they were driven with great slaughter. The king built a mosque at Jagat, entrusted the government to Farhat-ul-Mulk, and himself returned to Júnágadh. Before this Dwárka had never been conquered. Bhím, the Raja of Dwarka, was sent to Muháliz Khán, the governor of Ahmedábád, with orders that he was to be hewn in pieces and a piece fastened to every gate of the city. After settling the affairs of Sorath, the king turned

Jagat  
 Destroyed.

<sup>1</sup> *Mangifera indica*, *Mimusops hexandra*, *Eugenia jambolana*, *Ficus glomerata*, *Tamarindus indica*, and *Embilica officinalis*.

<sup>2</sup> Khánts are still found chiefly in Sorath. See Bombay Gazetteer, VIII. 112.

<sup>3</sup> The *Tabakát-i-Akbari* says they were Jats. Sir H. Elliot (*History of India*, I. 496) represents the Sumras to be Agnikula Rajputs of the Parmara stock. The Jádejás had been ruling in Kachh since A.D. 1350-1365.

<sup>4</sup> Dwárka (north latitude 22° 15'; east longitude 69°), on the north-western shore of Káthiawár, famous for its temple of Krishna.

his face towards Ahmedábád.\* On the way hearing that a fleet of Malabár craft were annoying the Gujarát ports, he marched to Goglin, equipped a fleet to oppose the pirates, and stopping at Cambay returned to Ahmedábád.

In A.D. 1480, when Mahmúd Sháh was at Jânágadh, Khudáwand Khán and others, who were weary of the king's constant warfare, incited his eldest son Ahmed to assume royal power. But Inád-ul-Mulk, by refusing to join, upset their plans, and on the king's return the conspiracy was stamped out. In the previous year (A.D. 1479) Mahmúd Sháh sent an army to ravage Chámpánér, which he was determined to conquer. About this time, hearing that the neighbourhood was infested with robbers, he founded the city of Mehmúdábád on the banks of the Vátrak, about eighteen miles south of Ahmedábád. In A.D. 1482 there was a partial famine in Gujarát, and the Chámpánér country being exempt from scarcity the commandant of Morámlí or Rasúlábád, a post in the Gáckwár's Sónlí district on the Chámpánér frontier, made several forays across the border. In return the chief attacked the commandant and defeated him, killing most of his men and capturing two elephants and several horses. On hearing this Mahmúd Sháh set out for Baroda with a powerful army. When Mahmúd reached Baroda the Rával of Chámpánér, becoming alarmed, sent ambassadors and sued for forgiveness. The king rejected his overtures, saying: 'Except the sword and the dagger no message shall pass between me and you.'<sup>1</sup> The Rával made preparations for a determined resistance, and sent messengers to summon Ghiás-ud-dín Khiljí of Málwa to his aid. To prevent this junction Mahmúd Sháh entrusted the siege to his nobles and marched to Dohad, on which Sultán Ghiás-ud-dín withdrew to Mándú. On his return from Dohad the Sultán began building a Jáma Mosque at Chámpánér to show that he would not leave the place till he had taken the hill-fort of Pávágadh. After the siege had lasted more than twenty months (April 1483 - December 1484), the Musalmáns noticed that for an hour or two in the morning most of the Rájputs were off duty bathing and dressing. A morning assault was planned and the first gate carried. Then Malik Ayáz Sultáni finding a practicable breach passed through with some of his men and took the great gate. The Rával and his Rájputs, throwing their women children and valuables into a huge fire, rushed out in a fierce but unavailing charge.<sup>2</sup>

The Rával and his minister Dúngarshi fell wounded into the conqueror's hands, and, on refusing to embrace Islám, were put to death. The Rával's son, who was entrusted to Seif-ul-Mulk, and instructed by him in the Muhammadan religion, afterwards, in the reign of Muzaffar Sháh (A.D. 1523 - 1526), was ennobled by the title of Nizám-ul-Mulk. On the capture of Pávágadh in A.D. 1484, Mahmúd Sháh built a wall round the town of Chámpánér, and made it his capital under the name of Muhammadábád. Under Mahmúd's orders the neigh-

## Chapter II.

## Ahmedábád

## Kings,

A.D. 1403 - 1573.

Mahmu'd

(Begada)

1459 - 1513.

Conspiracy,

1480.

War against  
Chámpánér,  
1482 - 1484.Capture of  
Pávágadh,  
1484.

<sup>1</sup> The Tabakát-i-Akbari has 'To-morrow the sword of adamant shall answer your message.'  
<sup>2</sup> Farishtah, II. 396 - 397.

Chapter II.  
 Ahmedábád  
 Kings,  
 A.D. 1103 - 1573.  
 Mahmúd  
 (Begada),  
 1459-1513.

bourhood became stocked with mangoes, pomegranates, figs, grapes, sugarcane, plantains, oranges, custard apples, *khurnis* or *ruens* (*Mimusops indica* or *hexandra*), jackfruit, and cocoapalms, as well as with roses, chrysanthemums, jasmims, *champás*, and sweet pandanus. A sandal grove near Chámpáner is said to have had trees large enough to help the Musalmán nobles to build their mansions. At the instance of the Sultán a Khurásáni beautified one of the gardens with fountains and cascades. A Gujarati named Hálor learning the principle improved on his master's design in a garden about four miles west of Chámpáner, which in his honour still bears the name Hálor.<sup>1</sup>

In Mahmúd's reign an instance is mentioned of the form of compensation known as *vaktar*. Some merchants bringing horses and other goods for sale from Irák and Khurásán were plundered in Sirohi hunts. The king caused them to give in writing the price of their horses and stuffs, and paying them from his own treasury recovered the amount from the Rájá of Sirohi.

In A.D. 1194-95 Mahmúd went against Bahádur Khán Gílání, a vassal of the Bahmanis, who from Goa and Dábhól<sup>2</sup> had so harassed the Gujarát harbours that, from the failure of the supply of betelnut, coriander seed had to be eaten with betel leaves. The Bahmán Sultán, fearing the consequences to himself, marched against Bahádur Khán, and, capturing him alive, struck off his head, and sent it to the Gujarát monarch, who returned to his own country. In A.D. 1199-1500, hearing that Násir-ud-dín of Málwa had killed his father Ghiás-ud-dín and seated himself on the throne, the Sultán prepared to advance against him, but was appeased by Násir-ud-dín's humble attitude. The next seven years passed without any warlike expedition. In A.D. 1507,<sup>3</sup> near Daman on his way to Cheul, Mahmúd heard of the victory gained at Cheul over the Portuguese by the Gujarát squadron under Malik Ayáz Sultán, in concert with the Turkish fleet.<sup>3</sup> In A.D. 1508 Mahmúd succeeded in placing his nephew Miran Muhammad Adil Khán Fárúkí on the throne of Asir-Burhānpur. From 1508 Mahmúd remained at his capital till his death in December A.D. 1513 at the age of sixty-seven years and three months, after a reign of fifty-four years and one month. Mahmúd was buried at Sarkhej,<sup>4</sup> and received

\*The Khándesh  
 Succession,  
 1508.

<sup>1</sup> Mirát-i-Sikandar, 112-114.

<sup>2</sup> Dábhól (north latitude 17° 34'; east longitude 73° 16'), on the north bank of the river Váshishti (called Halewarko and Kalewarko by the early navigators. See Badger's Varthema, page 114 note 1) in the British district of Ratnágiri. About this time, according to Athanasius Nikitin (A.D. 1468-1474), Dábhól was the great meeting place for all nations living along the coast of India and Ethiopia. In A.D. 1501 it was taken by the Portuguese. Between A.D. 1626 and 1630 an English factory was established here, but by the end of the century trade had left Dábhól and has never returned.

<sup>3</sup> Cheul; now Revdanda (north latitude 18° 33'; east longitude 71° 59'), from about A.D. 1500 to 1650 a place of much trade.

<sup>4</sup> Mahmúd Begada greatly impressed travellers, whose strange tales of him made the king well-known in Europe. Varthema (1503-1508) thus describes his manner of living: 'The king has constantly 20,000 horsemen. In the morning when he rises there come to his palace 50 elephants, on each of which a man sits astride, and the said elephants do reverence to the king, and, except this, they have nothing else to do. When the

the after-death title of Khúdáigán-i-Halím or the Meek Lord. Immediately before his death Sultán Mahmúd was informed that Sháh Ismáíl Safawí of Persia had sent him a friendly embassy headed by Yádgár Beg Kázil-básh. As the Kázil-báshes were known to be Shíahs the Sultán, who was a staunch Sunní, prayed that he might not be forced to see a Shíah's face during his last days. His prayer was heard. He died before the Persian embassy entered the city.<sup>1</sup> During the last days of Sultán Mahmúd, Sayad Muhammad of Jaunpur, who claimed to be the Mahdí or Messiah, came from Jaunpur and lodged in Tajkhán Sálár's mosque near the Jamálpur gate of Ahmedábád. His sermons drew crowds, and were so persuasive that he gained a large body of followers, who believed his eloquence to be due to *hál* or inspiration. Mahmúd's ministers persuaded him not to see the Jaunpur preacher.

## Chapter II.

Ahmedábád  
Kings,

A.D. 1403-1573.

Mahmúd\*  
(Begada),  
1459-1513.

king eats, fifty or sixty kinds of instruments, drums trumpets flageolets and fifes play, and the elephants again do him reverence. As for the king himself, his mustachios under his nose are so long that he ties them over his head as a woman would tie her tresses, and he has a white beard that reaches to his girdle. As to his food, every day, he eats poison (Hulibras's Prince whose daily food was asp and basilisk and toad), not that he fills his stomach with it, but he eats a certain quantity, so that when he wishes to destroy any great person he makes him come before him stripped and naked, and then eats certain fruits which are called *chofole* (*garphal*, nutmeg), like a muscatel nut. He also eats certain leaves called *tamboli* (*pan* or betel leaf like the leaves of a sour orange, and with these he eats lime of oyster shells. When he has chewed this well he spurs it out on the person he wishes to kill, and so in the space of half an hour the victim falls to the ground dead. The Sultán has also three or four thousand women, and every night that he sleeps with one, she is found dead in the morning.' Barbosa (A.D. 1511) goes further (Stanley's Trans. 17), saying that so soaked was the king with poison that if a fly settled on his hand it swelled and immediately fell dead. This was the result of his early training. For, on Varthema's companion asking how it was that the king could eat poison in this manner, certain merchants, who were older than the Sultán, answered that his father had fed him upon poison from his childhood. (Badger's Varthema, 110.) Of the origin of Mahmúd's surname Begada two explanations are given: (1) 'From his mustachios being large and twisted like a bullock's horn, such a bullock being called Begado; (2) that the word comes from the Gujarát *be*, two, and *gad*, a fort, the people giving him this title in honour of his capture of Júnágadh (A.D. 1472) and Chámpner (A.D. 1484).' (Bird's History of Gujarát, 202; Mirát-i-Ahmedí Persian Text, 74.) Varthema's account of the poison-eating is probably an exaggeration of the Sultán's habit of opium-eating to which from his infancy he was addicted. The Mirát-i-Sikandari (Persian Text, 751) speaks of the great physical power of Mahmúd and of his wonderful appetite. Mahmúd's daily food weighed forty *seers* the *ser* being 15 *bahúlís* a little over a pound. He used to eat about three pounds (5 *seers*) of parched gram to dessert. For breakfast, after his morning prayer, Mahmúd used to consume a cupfull of pure Makkah honey with a second cupfull of clarified butter and fifty small plantains called *sohan kelas*. At night they set by his bed two plates of *sambúnis* or minced mutton sausages. In the morning Mahmúd seeing the empty plates used to give thanks. 'Oh Allah,' he said, 'hadst thou not given this unworthy slave rule over Gujarát, who could have filled his stomach.' His virile powers were as unusual as his appetite. The only woman who could bear his embraces unharmed was a powerful Abyssinian girl who was his great favourite. Of the wealth and weapons kept in store the Mirát-i-Sikandari gives the following details regarding the great expedition against Júnágadh (Persian Text, 94): The Sultán ordered the treasurer to send with the army gold coins worth five *krors*, 1700 Egyptian Allemant Moorish and Khurasáni swords with gold handles weighing 2½ to 3 pounds (4-5 *seers*), 1700 daggers and poignards with gold handles weighing 1 to 1½ pounds (2-3 *seers*), and 2000 Arab and Turki horses with gold-embroidered housings. All this treasure of coin and weapons the Sultán spent in presents to his army (Ditto, 94-95).

\*Ferihtab, II. 404. The Mirát-i-Sikandari (Persian Text, 148, 149) calls the Persian ambassador Ibráhim Khán.

Chapter II.  
Ahmedábád  
Kings.  
A.D. 1403 - 1573.  
Mahmūd  
(Begada),  
1459-1513.

Mahmūd Begada's court was adorned by several pious and high-minded nobles. In life they vied with one another in generous acts; and after death, according to the Persian poet Urfi, they left their traces in the characters and carvings of stone walls and marble piles. First among these nobles the *Mirāt-i-Sikandari* (Persian Text, 132, 142) mentions Dáwar-ul-Mulk, whose god-fearing administration made his estates so prosperous that they were coveted by princes of the blood. As Thánadár of Amron in north Káthiáváda, he spread the light of Islám from Morvi to Bhúj, and after his death his fame as a spirit-ruling guardian drew hosts of sick and possessed to his shrine near Morvi. The second was Malik Ayáz, governor of Diu, who built the strong fortress afterwards reconstructed by the Portuguese. He also built a tower on an under-water rock, and from the tower drew a massive iron chain across the mouth of the harbour. A substantial bridge over the creek, that runs through the island of Diu, was afterwards destroyed by the Portuguese. The third was Khudáwánd Khán Álim, the founder of Álimpura a suburb to the south of Ahmedábád, adorned with a mosque of sandstone and marble. He introduced the cultivation of melons, figs and sugarcane into Gujarát from Bijápur. The fourth was Imád-ul-Mulk Ásas who founded Ísanpur, a suburb between Sháh Alam's suburb of Islámpur and Batwa, and planted along the road groves of *khirnis* and mangoes. The fifth was Táikhán Silár, so loved of his peers that after his death none of them would accept his title. The sixth was Malik Sárang Kiwám-ul-Mulk, a Rájput by birth, the founder of the suburb of Sárangpur and its mosque to the east of Ahmedábád. The seventh and eighth were the Khurasáni brothers Aázam and Moázam, who built a cistern, a mosque, and a tomb between Ahmedábád and Sarkhej.

Besides Khalíl Khán, who succeeded him, Mahmūd had three sons: Muhanmad Kála, Apá Khán, and Ahmed Khán. Kála, son of Rání Rúp Manjhri died during his father's lifetime as did his mother, who was buried in Mánek Chauk in Ahmedábád in the building known as the Rání's Hazíra. The second son Apá Khán was caught trespassing in a noble's *harim*, and was ordered by the Sultan to be poisoned. The third son was the Ahmed Khán whom Khudáwánd Khán sought to raise to the throne during Sultán Mahmūd's lifetime.

Muzaffar II.  
1513-1526.

Muhammad was succeeded by Khalíl Khán, the son of Rání Hírábái the daughter of a Rájput chieftain named Nágá Rána who lived on the bank of the Mahi. On ascending the throne, at the age of twenty-seven, Khalíl adopted the title of Muzaffar Sháh. For some time before his father's death, Prince Khalíl Khán had been living at Baroda and shortly after his accession he visited that neighbourhood, and founded a town which he named Daulatábád. In A.D. 1514 Ráv Bhím, the son of Ráv Bhán of Ídar, defeated Ain-ul-Mulk, governor of Pátan, who was coming to Ahmedábád to pay his respects to the king. This officer had turned aside to punish the Ráv for some disturbance he had created, but failing in his purpose, was himself defeated. On the approach of Muzaffar Sháh, Ídar was abandoned by the Ráv, who made his peace with difficulty and only by agreeing to pay a heavy tribute. Meanwhile the king marched to Godhra, and so to Málwa by way of Dohad, whose fort he caused to be repaired, and soon after went on to Dhár.

Expedition  
against Ídar,  
1514.

After a short stay in Málwa, thinking it mean to take advantage of the distracted condition of Mahmúd of Málwa, who was at war with his nobles, Muzaffar returned to Muhammadábád (Chámpáner). At this time Ráimal, nephew of the late Ráv Bhím of Ídar, expelled the Ráv's son Bhármal by the aid of his father-in-law Rána Sága of Chitor, and succeeded to the chieftainship of Ídar. The king was displeased at the interference of the Rána, and directed Nizám Khán, the governor of Ahmednagar, to expel Ráimal and reinstate Bhármal. Nizám Khán took Ídar and gave it to Bhármal. Ráimal betook himself to the hills where Nizám Khán incautiously pursuing and engaging him lost many men. When the rains were over the Sultán visited Ídar. Shortly after, Nizám Khán, the governor of Ahmednagar, fell sick and was called to court. He left Ídar in charge of Zahir-ul-Mulk at the head of a hundred horse. Ráimal made a sudden raid on Ídar and killed Zahir-ul-Mulk and twenty-seven of his men. On hearing of this reverse Sultán Muzaffar ordered Nizám Khán to destroy Bijápur.<sup>1</sup> In A.D. 1517, the nobles of Málwa besought Muzaffar's interference, alleging that the Hindu minister Medáni Rái was planning to depose the Málwa Sultán, Mahmúd Khilji, and usurp the throne. Muzaffar Sháh promised to come to their help, and shortly after Sultán Mahmúd Khilji, escaping from the surveillance of Medáni Rái, himself sought the aid of the Gujarát monarch. In A.D. 1518 Muzaffar Sháh marched by Godhna into Málwa, and on his arrival at Dhár, that town was evacuated by Medáni Rái. The Gujarát king next besieged Mándu and Medáni Rái summoned the Chitor Rána to his aid. When the Rána had reached Sárangpur, Muzaffar Sháh detaching a force caused the Rána to retire, while the Gujarát soldiers exerted themselves so strenuously that they captured Mándu, recovering the girdle which Kutb-ud-dín had lost at the battle of Kapadvanj. This conquest virtually placed Malwa in Muzaffar's power, but he honourably restored the kingdom to Sultán Mahmúd Khilji, and, withdrawing to Gujarát, proceeded to Muhammadábád. In A.D. 1519, news was received of the defeat and capture of Sultán Mahmúd Khilji by the Rána of Chitor. Muzaffar Sháh sent a force to protect Mándu. But the Rána, who distinguished himself by releasing the Sultán of Málwa and keeping his son in his stead as a hostage, enjoyed continued good fortune. Some time before these events a *bhūt* or bard in the presence of Nizám Khán, the governor of Ídar, boasted that the Rána of Chitor would never fail to help Rána Ráimal of Ídar. The angry governor said 'Whose dog is Rána Sága to help Ráimal while we are here.' Nizám Khán called a dog Sága, chained him in the fort, and dared the Rána to carry him away. His successes enabled Sága to answer the challenge. In consequence of dissensions at head-quarters Nizám Khán withdrew to Ahmednagar leaving a small garrison in Ídar. When Rána Sága appeared before Ídar the garrison resisted but were slain to a man. The Rána advanced to Ahmednagar and severely defeated Nizám Khán who withdrew to Ahmedábád, while the Rána plundered Vishálnagar.<sup>2</sup> In A.D. 1521, Malik Ayáz Sultáni, the governor of

## Chapter II.

Ahmedábád  
Kings,

A.D. 1403 - 1575.

Muzaffar II.  
1513-1526.Disturbances  
in Málwa,  
1517.Capture of  
Mándu,  
1518.War with Chitor,  
1519.<sup>1</sup> Farishtah, II. 408.<sup>2</sup> Mirát-i-Sikandari, 166-167; Farishtah, II. 411.

**Chapter II.**  
**Ahmedábád**  
**Kings.**  
**A.D. 1403-1573.**

**Muzaffar II.**  
**1513-1526.**  
 • The Rana of  
 Chitor Submits,  
 1521,

Dies,  
 1526.

**Sikandar,**  
**1526.**

**Mahmūd II.**  
**1526.**

Sorath, was sent with a large and carefully equipped force to revenge this inroad. Dissensions between Malik Ayáz and the Gujarát nobles prevented this expedition doing more than burn and despoil both Dungarpur and Bānsvāda. Muzaffar Sháh, greatly displeased with the result, was preparing to march against Chitor, when he was dissuaded by a submissive embassy from that chief, who sent his son to Ahmedábád with valuable presents for the king. Shortly afterwards, on the death of Malik Ayáz, Muzaffar Sháh confirmed his elder son Malik Is-hak in his father's rank and possessions. Malik Is-hak remained in Sorath which was confirmed as his *jāgir*. In the following year the Sultán went about his dominions strengthening his frontier posts, especially the fort of Modása, which he rebuilt. About A.D. 1524 prince Bāhádur Khán, ostensibly dissatisfied with the smallness of his estates but really to remove himself from the jealousy of his brother Sikandar who being appointed heir-apparent was seeking his life, left Gujarát and withdrew to Hindustán. King Muzaffar, after formally appointing his son Sikandar Khán his heir, died at Ahmedábád in A.D. 1526, after a reign of fourteen years and nine months. Muzaffar was buried in the shrine of Sheikh Ahmed Khattu at Sarkhej near his father's grave. He was the most learned and one of the most pious of the Ahmedábád Sultáns. So extreme an abstainer was he that not only during his whole life did he eschew intoxicating drugs and liquor but he never again rode a favourite horse because the horse was cured by a draught of wine. He was an accomplished musician, a finished horseman, a practised swordsman, and withal so modest and humble in his dress and temper that observing once to a favourite page how simple and yet graceful his own turban was the boy laughed: 'Ay, if the turbans of Mullahs and Bohoras are graceful, then is your Majesty's.' The Sultán said 'I should have been proud to have my turban likened to a Mullah's, why compare it with the headdress of a schismatic Bohora.' Muzaffar was careful never to pain the feelings of those around him. He suspected Kiwám-ul-Mulk who was in charge of his drinking water but contented himself with breathing over the water one of the verses of the Kuráán which make poison harmless.<sup>1</sup> During his reign cultivation increased so much in Jhalāvāda that it became necessary to reserve certain waste land for pasture. In 1526 the rains held off so long that famine began to rage. The Sultán exclaimed, 'Oh Allah! If thou scourgest the country for the sins of its king take his life and spare thy creatures.' The prayer was heard and the soul of the guardian Sultán passed in a flood of gracious rain.<sup>2</sup>

After Sikandar Sháh had been in power a few months he was murdered by Imád-ul-Mulk Khush Kadam, who seated a younger brother of Sikandar's, named Násir Khán, on the throne with the title of Mahmūd II. and governed on his behalf. The only event of Sikandar's reign was the destruction of an army sent against his brother

<sup>1</sup> The verse supposed to possess the highest virtue against poison is the last verse of Chap. cvi. of the Kuráán. . . . Serve the Lord of this House who supplieth them with food against hunger and maketh them free from fear.

<sup>2</sup> Mirát-i Sikandari (Pers. Manuscript), 174, 175, 191.

Latif Khán who was helped by Rána Bhím of Munga.<sup>1</sup> The nobles deserted Imád-ul-Mulk's cause, and prince Bahádúr Khán, returning to Gujarát from Hindustán, was joined by many supporters prominent among whom was Táji Khán, proprietor of Dhandhuka. Bahádúr marched at once on Chámpáner, captured and executed Imád-ul-Mulk and poisoning Násir Khán ascended the throne in A.D. 1527 with the title of Bahádúr Sháh. His brother Latif Khán, aided by Rája Bhím of the Kohistan or hill land of Pál,<sup>2</sup> now asserted his claim to the throne. He was defeated, and fell wounded into the hands of the Gujarát army and died of his wounds and was buried at Halol. Rája Bhím was slain. As Bhím's successor Ráisingh plundered Dohad, a large force was sent against him, commanded by Táji Khán, who laid waste Ráisingh's country and dismantled his forts. Soon after Bahádúr Sháh visited Cambay, and found that Malik Is-hák the governor of Sorath had, in the interests of the Portuguese, attempted to seize Diu but had been repulsed by the Gujarát admiral Mahmúd Áka. The Sultán entrusted Diu to Kiwám-ul-Mulk and Júnághadh to Mujahid Khán Bhikan and returned to Ahmedábád. In 1527 he enforced tribute from Idar and the neighbouring country. During one of his numerous expeditions he went to hunt in Nándod and received the homage of the Rája. As the Portuguese were endeavouring to establish themselves on the coast of Sorath, and, if possible, to obtain Diu, the king was constantly at Cambay Diu and Gogha to frustrate their attempts, and he now directed the construction of the fortress of Broach. At this time Muhammad Khán, ruler of Ásir and Burhánpur, requested Bahádúr's aid on behalf of Imád-ul-Mulk, ruler of Berar. Bahádúr Sháh started at once, and at Nandurbár was joined by Muhammad Khán Asíri, and thence proceeded to Burhánpur, where he was met by Imád Sháh from Gávalgad. After certain successes he made peace between Burhán Nizám Sháh and Imád Sháh Gávali, and returned to Gujarát. Jám Fírúz the ruler of Tatha in Sindh now sought refuge with Bahádúr Sháh from the oppression either of the Ghoris or of the

## Chapter II.

Ahmedábád  
Kings,  
A.D. 1403-1573.

Bahá'dur.  
1527-1536.

Portuguese  
Intrigues,  
1526.

Khandesh  
Affairs,  
1528.

<sup>1</sup> Both the *Mirát-i-Sikandari* (287) and *Faiztáh* (II. 419) place Munga in Nandurbár-Sultánpur. The further reference to Rána Bhím of Pál seems to apply to the same man as the Rána Bhím of Munga. Munga may then be Mohangad that is Chota Udepur. <sup>2</sup> *Mirát-i-Sikandari* Persian Text, 225-226. *Faiztáh*, II. 425-428. The Gujarát Musalman historians give a somewhat vague application to the word Pál which means a bank or step downwards to the plain. In the *Mirát-i-Ahmedí* (Páhlánpur Edition, page 168) Pálvarah, whose climate is proverbially bad, includes Godhra, Alí Mohan and Rajpípla that is the rough eastern fringe of the plain land of Gujarát from the Mahi to the Tapti. As the Rája of Nándod or Rajpípla was the leading chief south of Idar Colonel Watson took references to the Rája of Pál to apply to the Rája of Rajpípla. An examination of the passages in which the name Pál occurs seems to show that the hill country to the east rather than to the south of Pávagad or Chámpáner is meant. In A.D. 1527 Latif Khán the rival of Bahádúr Sháh after joining the Rája Bhím in his *kohistan* or highlands of Pál when wounded is taken into Halol. The same passage contains a reference to the Rája of Nándod as some one distinct from the Rája of Pál. In A.D. 1531 Ráisingh of Pál tried to rescue Mahmúd Khilji on his way from Mándá in Malwa to Chámpáner. In A.D. 1551 Násir Khán fled to Chámpáner and died in the Pál hills. These references seem to agree in allotting Pál to the hills of Bária and of Mohan or Chhota Udepur. This identification is in accord with the local use of Pál. Mr. Pollen, I.C.S., LL.D., Political Agent, Rewa Kántha, writes (8th Jan. 1895): Bhis Kolis and traders all apply the word Pál to the Bária Pál which besides Bária takes in Sanjeli and the Navánagar-Saliát uplands in Godhra.

Chapter II.  
Ahmedābād  
Kings,  
A.D. 1403-1573.  
Bahā'dur,  
1527-1536.

Mughals and was hospitably received. In A.D. 1528 Bahā'dur made an expedition into the Dakhan which ended in a battle at Daulatābād. The issue of this battle seems to have been unfavourable as hardly any reference to the campaign remains. Next year (A.D. 1529) at the request of Jaāfar or Khizr Khān, son of Imād Shāh Gāvali, who was sent to Gujarāt to solicit Bahā'dur's help, he again marched for the Dakhan. As he passed through Māler Bihārjī the Rāja of Bāglān gave him his daughter in marriage and in return received the title of Bahr Khān. From Bāglān Bahr Khān was told off to ravage Cheul which by this time had fallen into the hands of the Portuguese. Bahā'dur himself advanced to Ahmednagar, took the fort and destroyed many of the buildings. Purandhar also was sacked of its stores of gold.<sup>1</sup> From Ahmednagar Bahā'dur Shāh passed to Burhānpur, and there his general Kaisar Khān gained a victory over the united forces of Nizām Shāh, Malik Berīd, and Ain-ul-Mulk. After having the public sermon read in his name both in Ahmednagar and in Burhānpur Bahā'dur returned to Gujarāt and for some time refrained from interfering in the affairs of the Dakhan.

Turks at Diu,  
1526-1530.

Between A.D. 1526 and 1530 certain Turks under one Mústafa came to Gujarāt, traders according to one account according to another part of a Turkish fleet expected to act against the Portuguese. Diu was assigned them as a place of residence and the command of the island was granted to Malik Tūghlān, son of Malik Ayāz, the former governor. In A.D. 1530 the king marched to Nāgor, and gave an audience both to Prathirāj Rāja of Dīngarpur and to the ambassadors from Rāna Rataṃsi of Chitor. The Rāna's ambassadors complained of encroachments on Chitor by Mahmūd of Mālwa. Mahmūd promised to appear before Bahā'dur to explain the alleged encroachments. Bahā'dur waited. At last as Mahmūd failed to attend Bahā'dur said he would go and meet Mahmūd. He invested Māndu and received with favour certain deserters from Mahmūd's army. The fortress fell and Sultān Mahmūd and his seven sons were captured. The success of the siege was due to Bahā'dur's personal prowess. He scaled an almost inaccessible height and sweeping down from it with a handful of men took the fort, a feat which for daring and dash is described as unsurpassed in the history of Musalmān Gujarāt.<sup>2</sup> After passing the rainy season at Māndu Bahā'dur Shāh went to Burhānpur to visit his nephew Mirān Muhammad Shāh. At Burhānpur Bahā'dur under the influence of the great priest-statesman Shāh Tāhir, was reconciled with Burhān Nizām and gave him the royal canopy he had taken from Mālwa. Bahā'dur offered Shāh Tāhir the post of minister. Shāh Tāhir declined saying he must make a pilgrimage to Makkah. He retired to Ahmednagar and there converted Burhān Nizām Shāh to the Shāh faith.<sup>3</sup> In the same year, hearing that Maḥsingji, Rāja of

Capture of Māndu  
1530.

<sup>1</sup> Purandhar about twenty miles south by east of Poona, one of the greatest of Dakhan hill forts.

<sup>2</sup> Mirāt-i-Sikandari, 238, 239; Farihtah, II, 430. According to the Mirāt-i-Sikandari (239) the Sultan enquired on which side was the loftiest height. They told him that in the direction of Songad-Chitauri the hill was extremely high. These details show that the cliff scaled by Bahā'dur was in the extreme south-west of Māndu where a high nearly isolated point stretches out from the main plateau. For details see Appendix II, Māndu.

<sup>3</sup> Mirāt-i-Sikandari, 241, 242; Farihtah, II, 432.

Halvad,<sup>1</sup> had killed the commandant of Dasáda Bahádur despatched Khán Khánín against him. Virangám and Mándal were reft from the Jhálá Chieftains, and ever after formed part of the crown dominions. When Sultan Mahmúd Khulji and his sons were being conveyed to the fortress of Chámpáner, Ráisingh, Rája of Pál, endeavoured to rescue them. The attempt failed, and the prisoners were put to death by their guards. In A.D. 1531, on Bahádur's return from Burhánpur to Dhár, hearing that Silehdi the Rájput chief of Ráisin in east Málwa kept in captivity certain Muhammadan women who had belonged to the *harim* of Sultan Násir-ud-dín of Málwa, Bahádur marched against him and forced him to surrender and embrace Islám. The chief secretly sent to the Rána of Chitor for aid and delayed handing over Ráisin. On learning this Bahádur despatched a force to keep Chitor in check and pressed the siege. At his own request, Silehdi was sent to persuade the garrison to surrender. But their reproaches stung him so sharply, that, joining with them, and after burning their women and children, they sallied forth sword in hand and were all slain. Ráisin fell into Bahádur's hands, and this district together with those of Bhílsa and Chanderi were entrusted to the government of Sultan Alam Lodhi. The king now went to Gondwána to hunt elephants, and, after capturing many, employed his army in reducing Gágraun and other minor fortresses.<sup>2</sup> In A.D. 1532 he advanced against Chitor, but raised the siege on receiving an enormous ransom. Shortly afterwards his troops took the strong fort of Rantanbhur.<sup>3</sup> About this time on receipt of news that the Portuguese were usurping authority the Sultan repaired to Dm. Before he arrived the Portuguese had taken to flight, leaving behind them an enormous gun which the Sultan ordered to be dragged to Chámpáner.

Before A.D. 1532 was over Bahádur Sháh quarrelled with Humáyún, emperor of Delhi. The original ground of quarrel was that Bahádur Sháh had sheltered Sultan Muhammad Zamín Mírza the grandson of a daughter of the emperor Bábar (A.D. 1482-1530). Humáyún's anger was increased by an insolent answer from the Gujarát king. Without considering that he had provoked a powerful enemy, Bahádur Sháh again laid siege to Chitor, and though he heard that Humáyún had arrived in Gwálior, he would not desist from the siege. In March 1535 Chitor fell into the hands of the Gujarát king but near Mandasúr his army was shortly afterwards routed by Humáyún. According to one account, the failure of the Gujarát army was due to Bahádur and his nobles being spell-bound by looking at a heap of salt and some cloth soaked in indigo which were mysteriously left before Bahádur's tent by an unknown elephant. The usual and probably true explanation is that Ráimí Khán the Turk, head of the Gujarát artillery, betrayed Bahádur's interest.<sup>4</sup> Still though Ráimí Khán's treachery may have had a share in Bahádur's defeat it seems probable that in valour, discipline, and tactics the Gujarát army was

## Chapter II.

Ahmedábád  
Kings,

A.D. 1403-1573.

Bahádur,  
1527-1536.Quarrel with  
Humáyún,  
1532.Fall of Chitor,  
1535.<sup>1</sup> Halvad is a former capital of the chief of Dhraagadhra in Kathiáwád.<sup>2</sup> Gágraun in Central India about seventy miles north-east of Ujjain.<sup>3</sup> Rantanbhur about seventy-five miles south by east of Jaipur.<sup>4</sup> Mirát-i-Sikandarí Persian Text, 266, 268; Farishtah, II. 430.

Chapter II.  
Ahmedabad  
Kings,  
A.D. 1403-1573.  
Bahadur,  
1527-1536.  
Mughal Conquest  
of Gujarat,  
1535.  
Are Driven Out,  
1536.  
The Portuguese  
at Diu,  
1536.

Death of  
Bahadur,  
1536

Muhammad II  
(Asiri),  
1536

inferior to the Mughals. Bahadur Sháh, unaccustomed to defeat, lost heart and fled to Mándú, which fortress was speedily taken by Humáyún. From Mándú the king fled to Chámpáner, and finally took refuge in Diu. Chámpáner fell to Humáyún, and the whole of Gujarát, except Sorath, came under his rule. At this time Sher Sháh Súr revolted, in Bihár and Jaunpur, and Humáyún returned to Agra to oppose him leaving his brother Hindál Mírza in Ahmedabad, Kásam Beg in Broach, and Yádgár Násir Mírza in Pátan. As soon as Humáyún departed, the country rose against the Mughals, and his old nobles requested the king to join them. Bahadur joined them, and, defeating the Mughals at Kaníj near Mahmúdábád, expelled them from Gujarát. During Humáyún's time of success Bahadur Sháh, being forced to court the Portuguese, had granted them leave to erect a factory in Diu. Instead of a factory the Portuguese built a fort. When he recovered his kingdom, Bahadur, repenting of his alliance with the Portuguese, went to Sorath to persuade an army of Portuguese, whom he had asked to come to his assistance, to return to Goa. When the Portuguese arrived at Diu five or six thousand strong the Sultán hoping to get rid of them by stratagem, repaired to Diu and endeavoured to get the viceroy into his power. The viceroy excused himself, and in return invited the king to visit his ship. Bahadur agreed, and on his way back was attacked and slain, in the thirty-first year of his life and the eleventh of his reign. According to the author of the *Mirát-i-Sikandari* the reason of Bahadur's assassination was that a paper from him to the kings of the Dakhan, inviting them to join him in an alliance against the Portuguese, had fallen into the hands of the Portuguese viceroy. Whatever may have been the provocation or the intention, the result seems to show that while both sides had treacherous designs neither party was able to carry out his original plan, and the end was unpremeditated, hurried on by mutual suspicions.<sup>1</sup> Up to the defeat of Sultán Bahadur by Humáyún, the power of Gujarát was at its height. Cadets of noble Rájput houses, Prithuráj, the nephew of Rána Sanga of Chitor, and Narsingh Deva the cousin of the Rája of Gwálior, were proud to enrol themselves as the Sultán's vassals. The Rája of Baglana readily gave Bahadur Sháh his daughter. Jámi Fírúzi of Tatha in Sindh and the sons of Bahlúl Lodhi were suppliants at his court. Malwa was a dependency of Gujarát and the Nizám Sháh of Ahmednagar and Nasírkhan of Burhánpur acknowledged him as overlord, while the Fárúkis of Khándesh were dépendent on Bahadur's constant help.<sup>2</sup>

On the death of king Bahadur in A.D. 1536, the nobles of Gujarát invited his sister's son Muhammad Sháh Asiri to succeed him. Muhammad Sháh died shortly after his accession, and the nobles conferred the crown on Mahmúd Khán, son of Latíf Khán, brother of Bahadur Sháh, and he ascended the throne in A.D. 1536, when only eleven years of age. The government of the country was carried on by Darya Khán and Imád-ul-Mulk, who kept the king under

A detailed account of the death of Sultán Bahadur is given in the Appendix.  
*Mirát-i-Sikandari* Persian Text, 283. Compare *Farishtah*, II, 427.

strict surveillance. Darya Khán resolved to overthrow Imád-ul-Mulk and acquire supreme power. With this object, he obtained an order from the king, whom, on the pretence of a hunting expedition, he removed from Ahmedábád, directing Imád-ul-Mulk to retire to his estates in Jháláváda. Six months later, taking the Sultán with him, Darya Khán led an army into Jháláváda, and defeating Imád-ul-Mulk in a battle at Pátri, fifty two miles west of Ahmedábád, pursued him to Burhánpur, and there defeated Imád-ul-Mulk's ally the ruler of Khándesh and forced Imád-ul-Mulk to fly to Málwa.<sup>1</sup> After this success Darya Khán became absorbed in pleasure, and resigned the management of the kingdom to Alam Khán Lodhi. The king, dissembling his dissatisfaction at the way he was treated, pretended to take no interest in affairs of state. Alam Khán Lodhi, seeing the carelessness of Darya Khán, began to entertain ambitious designs, and retiring to his estate of Dhandhúka invited the king to join him. Mahmúd Sháh, believing him to be in earnest, contrived to escape from surveillance and joined Alam Khán. On discovering the king's flight, Darya Khán raised to the throne a descendant of Ahmed Sháh by the title of Muzaffar Sháh, and striking camp in his name set out with an army towards Dhandhúka. Alam Khán and the king met him at Dhúr in Dholka, and a battle was fought in which Mahmúd and Alam Khán were defeated. The king fled to Rámpur, and thence to Páliád, while Alam Khán fled to Sádra. Darya Khán occupied Dhandhúka; but his men, dissatisfied at being placed in opposition to the king, rapidly deserted, some joining Alam Khán and some Mahmúd Sháh. Soon after the king joined Alam Khán and marched on Ahmedábád, whither Darya Khán had preceded them. The citizens closed the gates against Darya Khán, but he forced an entry by way of the Burhánpur wicket. Hearing of the king's approach Darya Khán fled to Mubárah Sháh at Burhánpur, leaving his family and treasure in the fortress of Chámpáner.

The king entered Ahmedábád, and soon after captured Chámpáner. Alam Khán now obtained the recall of Imád-ul-Mulk, who received a grant of Broach and the port of Surat. Shortly afterwards Mahmúd Sháh began to show favour to men of low degree, especially to one Charji, a birdcatcher, who he ennobled by the title of Muháfiz Khán. Charji counselled Mahmúd to put to death Sultán Alá-ud-dín Lodhi and Shujáát Khán, two of the principal nobles; and the king, without consulting his ministers, caused these men to be executed. The nobles joining together besieged Mahmúd Sháh in his palace, and demanded that Muháfiz Khán should be surrendered to them, but the king refused to give him up. The nobles then demanded an audience, and this the king granted, Muháfiz Khán, though warned of his danger, being foolishly present. On entering the royal presence Alam Khán signalled to his followers to slay Muháfiz, and he was killed in spite of the king's remonstrances. Mahmúd then attempted to kill himself, but was prevented and placed under guard, and the chief nobles took it in turn to watch him. Strife soon arose between Alam Khán and Mujáhid

## Chapter II.

Ahmedábád  
Kings.

A.D. 1103-1573.

Mahmúd II.  
1536-1554.Escapes from  
Control.Loose & Evil  
Favourites.<sup>1</sup> Mirát-i-Ikandari, Persian Text, 292.

**Chapter II.**  
**Ahmedābād**  
**Kings,**  
 A.D. 1503-1573.  
**Mahmūd II**  
 1536-1554.  
 Quarrels among  
 the Nobles.

Disturbance  
 1545.

Death of  
 Mahmūd,  
 1554.

Khān and his brother, and the two latter nobles contrived the king's escape and sacked the houses of Alam Khān and his followers. Alam Khān escaped to Pethāpur in the Mahi Kānthā. He then joined Darya Khān, whom he called from the Dakhan, and obtained help in money from Imād-ul-Mulk of Surat and from Alp Khan of Dholka. Imād-ul-Mulk wrote to the Sultān a king forgiveness for the rebels. But before the Sultān, who was mercifully disposed, could grant them pardon, Alam Khān and Darya Khān again committed themselves by acts of open revolt. The Sultān displeased with the part Imād-ul-Mulk had taken in the rising summoned him to Chāmpner where, with the Sultān's connivance, his camp was given over to pillage. The Sultān disclaimed all knowledge of this attack and at Imād-ul-Mulk's request allowed him to go on pilgrimage to Makkah. In A.D. 1515 as he was preparing to start for Makkah Imād-ul-Mulk was killed. He was succeeded in Surat by Khudāwand Khān Rūmī, who had held Surat under him, and who, in spite of Portuguese opposition and intrigue, had five years before completed the building of Surat Castle.<sup>1</sup> Meanwhile Alam Khān and Darya Khān were driven from Gujarāt and forced to take shelter with the sovereign of Dehli. The king now appointed as his own minister Afzal Khān, the minister of the late Bahādur Shāh, and though Afzal Khān lived in retirement, his counsel was taken on measures of importance. Other great nobles were Sayad Mukōrak, Fatch Khān Baloch, and Abdul Karīm Khān, who received the title of Itmād Khān, and was so entirely in the Sultān's confidence that he was admitted to the harem. Mahmūd now consulted Asif Khān as to the propriety of conquering Mālwa. Asif Khān advised him rather to deprive the Rajput chiefs and proprietors of their *wāntas* or hereditary lands. The attempt to follow this advice stirred to resistance the chief men of Idar, Sirohi, Dūngarpur, Bānsyāda, Lūnāvāda, Rājpipla, Dohad, and the banks of the Mahi. The king strengthened his line of outposts, establishing one at Sirohi and another at Idar, besides fresh posts in other places. At the same time he began to persecute the Hindus, allowing them to be killed on the slightest pretence, branding Rājputs and Kohis, forcing them to wear a red rag on the right sleeve, forbidding them to ride in Ahmedābād, and punishing the celebration of Holi and Diwālī. In A.D. 1554 Burhān, a servant of the king's, conceived the idea of killing him and reigning in his stead. He accordingly gave his master an intoxicating drug, and when he was overcome with sleep stabbed him to the heart. Then summoning the principal nobles in the king's name, he put to death Asaf Khān the prime minister and twelve others, and endeavoured to have himself accepted as Sultān. No one aided him; even his

<sup>1</sup> A poet of the time, Mulla Muhammad of Astarābād, enshrined the date H. 947 (A.D. 1540) in the words:

SIDD BUWAD RAR SINAH-O-JANAI FIRANGI'IN BINAI.  
 Māy this fabric press like a pillar on the breast  
 and the life of the Frank.

Faustah. II. 147. The letter values that make 947 are: S=60, d=4, h=2, w=6, d=4, h=2, =200, s=60, y=10, n=50, h=5, w=6, j=3, a=1, n=50, f=80, =200, =50, y=20, y=10, a=1, y=10, n=50, h=2, n=50, a=1, y=10. Total 947.

<sup>2</sup> Mirāt-i-Sikandari, Persian Text, 326-27.

accomplices deserted him. Imád-ul-Mulk Rumi,<sup>1</sup> Ulugh Khán, and others joined to oppose him, and when marching against them he was cut down by Shirwán Khán. Mahmúd's persecutions had raised such bitter hate among the Hindus, that they regarded Burhán as a saviour, and after Burhán's death are said to have made a stone image of him and worshipped it.<sup>2</sup> Mahmúd moved his capital from Ahmedábád to Mohamúdábád, eighteen miles south of Ahmedábád where he built a palace and enclosed a deer park. At each corner of the park he raised a palace the stone walls and ceilings of which were ornamented with beautiful and precious gold traceries and arabesques.<sup>3</sup> His strict regard for public morals led him to forbid Muhammadan women visiting saints' tombs as the practice gave rise to irregularities. He died at the age of twenty-eight after a reign of eighteen years.

On the death of Burhán, the nobles elected as sovereign a descendant of the stock of Ahmed Shah of the name of Ahmed Khán, and proclaimed him king by the title of Ahmed Sháh II. At the same time they agreed that, as the king was young, Ítimád Khán should carry on the government and they further divided the country among themselves, each one undertaking to protect the frontiers and preserve the public peace. Mubárák Shah of Khándesh, considering this a good opportunity, preferred a claim to the crown and marched to the frontier. An army led by the chief Gujarát nobles and accompanied by the young king met the invaders at the village of Rampur Kotriá in Broach, the Gujarát army encamping on the north bank and the Khándesh army on the south bank of the Nerbada. Násir-ul-Mulk, one of the Gujarát nobles, taking certain of his friends into his confidence, determined to remain neutral till the battle was over and then to fall on the exhausted troops and possess himself of both kingdoms. Sayad Mubárák, a descendant of the saint Sháhí Alam, who led the van of the Gujarát army, becoming aware of Násir-ul-Mulk's design opened communications with Mubárák Sháh of Khándesh and induced him to withdraw.<sup>4</sup> Násir-ul-Mulk, who still aspired to supreme power, gaining several nobles to his side near Baroda, surprised and defeated the forces of Ítimád Khán and Sayad Mubárák. The Sayad withdrew to his estate of Kapadvanj and he was joined by Ítimád Khán, while Násir-ul-Mulk, taking Sultán Ahmed with him to Ahmedábád, assumed the entire government of the country. After a short time he assembled an army and marched against Sayad Mubárák and Ítimád Khán encamping at Kamand, the village now called Od Kámod, ten miles north-east of Ahmedábád at the head of 50,000 horse. Ítimád feared to attack so

Chapter II.  
Ahmedábád  
Kings,  
A.D. 1403-1573.

Mahmúd II.  
1536-1554.

Ahmed II.  
1554-1561.  
Ítimád Khan  
Regent.

<sup>1</sup> This Imad-ul-Mulk is different from the Imad-ul-Mulk mentioned above (page 258) as receiving a grant of Broach and Sorat. The latter had before this retired to Surat, and was killed there in A.D. 1545. (Bird, 266.) Imad-ul-Mulk II, who attacked Burhán, was originally called Malik Arshín (Bird, 272). He is also called the leader of the Turks and Rumi. This Imad-ul-Mulk Rumi, who was the father of Changíz Khán, was ultimately killed in A.D. 1560 at Surat by his own son-in-law Khudáwánd or Iktisár Khán.

<sup>2</sup> Mirát-i-Sikandari, Persian Text, 326-27.

<sup>3</sup> This seems to be the palace referred to in the Tabak't-i-Akbari (Sir Henry Elliot's History of India, V. 369): After his second settlement of Gujarát (A.D. 1573, II. 981) Akbar left Ahmedábád for Mohamúdábád and rested in the lofty and fine palace of Sultán Mahmúd of Gujarát.

<sup>4</sup> Mirát-i-Sikandari, Persian Text, 332.

Chapter II.  
Ahmedábád  
Kings,  
A.D. 1403-1573.  
Ahmed II.  
1554-1561.

Partition of  
the Provinces.

strong a force. But Sayad Mubárak, who knew of the defection of Ulugh Khán and Imád-ul-Mulk, surprised Násir-ul-Mulk's army at night. During the confusion Ulugh Khán and Imád-ul-Mulk, disgusted with the assumption of Násir-ul-Mulk, deserted him and bringing the young Sultán with them joined Sayad Mubárak and Ítimád Khán. Násir-ul-Mulk was forced to fly, and after a short time died in the mountains of Pál.<sup>1</sup> Ikhtiyár-ul-Mulk, Fateh Khán Balúch, and Hasan Khán Dakhani now set up another king, a descendant of Ahmed, named Sháhu. A battle was fought near Mehmúdábád in which Sháhu and his supporters were defeated and Hasan Khán Dakhani was slain. Before the battle Fateh Khán Balúch had been induced to forsake Sháhu, and Ikhtiyár-ul-Mulk, taking Sháhu with him, fled. The nobles now divided Gujarat into the following shares :

Ahmed Sháh for Private Purse ...	{ Ahmedábád and the Daskrohi sub-division.
Ítimád Khán and Party ...	{ Kadi, Jháláváda, Pítlád, Nadiád, Bhil, Rádhampur, Sani, Múnjpur, Godhra, and Sorath.
Sayad Mubárak and Party ...	{ Patan and Cambay, with its Chorasi or 84 villages, Dholka, Gogha, and Dhandhuka
	{ Chámpáner, Sarnal, Bálasaor, and Kapadvanj.
Imád-ul-Mulk Rúmi and Party ...	{ Broach, Baroda, and Surat as far as the Sultampur-Namlurbár frontier.
Nobles under Ítimád Khán ..	Modása and surrounding districts

Of these shares Ítimád Khán bestowed the country of Sorath on Tátár Khan (Ghori); the districts of Rádhampur, Sani, and Múnjpur on Fateh Khán Baluch; Nadiád on Malik-nsh-Shah, and some of the dependencies of Jháláváda on Alaf Khán Habshi. Sayad Mubárak conferred the territory of Patan on Músa Khán and Sher Khán Fuládi, Imád-ul-Mulk Rúmi bestowed the district of Baroda on Alaf Khán Habshi and the port of Surat on his wife's brother Khudáwand Khán Rúmi.

Dissensions.

About this time (A.D. 1552) Alam Khán returned, and, through the influence of Sayad Mubárak, was allowed to remain. The Sayad gave him and Azam Humáyun Chámpáner, and Ítimád Khán gave Godhra to Alp Khán Khatri, a follower of Alam Khán. Alam Khán and Ítimád Khán shortly after expelled Alaf Khán Habshi from Jháláváda, and he fled to Imád-ul-Mulk Rúmi at Broach, and at his intercession Alaf Khán received the Bhil district. Alam Khán's success tempted him to try and get rid of Ítimád Khán and govern in his stead. Ítimád Khán, discovering his intention, made him leave the city and live in his own house in the Asáwal suburb. Alam Khán now made overtures to Imád-ul-Mulk Rúmi and became very friendly with him. One day Alam Khán proposed to get rid of Ítimád Khán;

<sup>1</sup> For Pál compare note 2 page 253.

but seeing that Imád-ul-Mulk Rûmî did not take to his proposal, he next endeavoured to ruin Sayad Mubárah. But when the Gujarát army marched against him the Sayad made peace, and Alam Khán's intrigues being apparent, he was attacked and compelled to fly. He now went to Berár and sought aid of Mubárah Sháh, who marched an army towards the Gujarát frontier. The Gujarát nobles, taking Ahmed Shah with them, advanced to oppose him, and he retired. Alam Khán now repaired to Sher Khán Fauládi at Pátan, and they together seized Ítimád Khán's district of Kauli, but, through the exertions of Ikhtiyár-ul-Mulk, Alam Khán was slain and Sher Khán forced to retire to Pátan. Imád-ul-Mulk Rûmî and Ítimád Khán now carried on the government, but dissension springing up between them, Ítimád Khán fled to Mubárah Sháh in Khándesh, and induced him to lead an army against Gujarát. The nobles, fearing this combination, made peaceful overtures and it was eventually settled that the lands of Sultánpur and Nandurbár should be given to Mubárah Sháh, and that Ítimád Khán should be restored to his former position. Since this date the districts of Sultánpur and Nandurbár have been permanently severed from Gujarát and have formed a part of Khándesh, to which province they now belong. Ahmed Sháh, finding himself more strictly guarded than ever, contrived to flee to Sayad Mubárah at Sayadpur, who, though vexed at his coming, would not refuse him shelter. At this time Haji Khán, a Delhi noble, on his way from Chitor to help Humayún, passed through Gujarát with a well equipped force, and arrived at Pátan. The Gujarát nobles, especially Ítimád Khán and Imád-ul-Mulk Rûmî, conceiving that he came at the Sayad's invitation, and that the flight of the king was part of the plot, determined to crush the Sayad ere Haji Khan could join him, and on their march to Sayadpur meeting Sayad Mubárah near Mehmúdábád defeated him. The Sayad fell and was buried on the field of battle. His estates were resumed, though eventually Dholka was restored to his son Sayad Mírán.

The army and the two protectors returned to Ahmedábád. Dissensions again sprang up between them, and Imád-ul-Mulk Rûmî summoned to his aid his son Changíz Khán from Broach, while Ítimád Khán sent for Tátár Khán G'ori from Sorath. Tátár Khán arrived first and Ítimád Khán further strengthened by contingents from the Fauladis of Pátan and Fatch Khan Balúch from Rádhanpur ordered Imád-ul-Mulk Rûmî to return to his estate; and he, seeing it would be useless for him to contend against so overwhelming a force, retired to his possessions at Broach. Shortly after, having marched against Surat at the request of the inhabitants who were wearied of the tyranny of Khudáwánd Khán, he was decoyed by that chief to an entertainment and was there assassinated. His son Changíz Khán marched against Surat to take vengeance for his father's death, and, finding the fortress too strong for him, summoned to his aid the Portuguese, to whom, as the price of their assistance, he surrendered the districts of Daman and Sanján.<sup>1</sup> The Portuguese, bringing a strong

**Chapter II.**  
**Ahmedábád**  
**Kings,**

A.D. 1403 - 1573.

Ahmed II.  
1554 - 1561.

Sultánpur and  
Nandurbár  
handed to  
Khándesh,  
1560.

Defeat and  
Death of Sayad  
Mubárah.

Death of Imád-  
ul Mulk Rûmî.

Daman District  
ceded to the  
Portuguese,  
1550.

<sup>1</sup> The fort of Daman was taken by the Portuguese in A.D. 1550, and, according to Portuguese accounts (Faria y Souza in Kerr's Voyages, VI. 413) the country round was

**Chapter II.**  
**Ahmedábád**  
**Kings,**  
**A.D. 1403 - 1573.**

**Ahmed II**  
**1554-1561.**

**Assassinated,**  
**1560.**

**Muzaffar III.**  
**1561-1572.**  
**A Minor.**

fleet up the Tápti, cut off the supplies, and Khudáwánd Khán was forced to surrender, and was slain by Changíz Khán in revenge for his father's death. Shortly afterwards Changíz Khan quarrelled with Jhujhár Khán Habshi of Baroda because the Habshi had installed his nephew, son of Afif Khán Habshi, without consulting Changíz. Jhujhár and his nephew being defeated fled to Ítimád Khán, who allotted them a grant of land. At this time Fatch Khan Balúch, the proprietor of Radhanpur and Sami, was Ítimád Khán's chief supporter, and with his assistance Ítimád Khán marched to besiege Changíz Khán in Broach. Tátár Khan Ghori and other nobles, fearing lest Ítimád Khán should become too powerful, endeavoured to make peace. As their efforts failed, Tátár Khán wrote to the Fankahs to attack Fatch Khán Balúch. They did so, and Fatch Khán, after being defeated near Radhanpur, took refuge in the fort of Fatchkot or Dhulkot, which is close to the town. Ítimád Khán raised the siege of Broach and came to Ahmedábád, where he busied himself in checking the intrigues of king Ahmed, who was doing all in his power to become independent. Finally, in A.D. 1560-61, at the instigation of Wajih-ul-Mulk and Razí-ul-Mulk Ítimád Khán caused Ahmed II. to be assassinated. The murder took place in the house of Wajih-ul-Mulk. The Sultan's body was thrown in the sands of the Sabarmati and the story circulated that the Sultan had been killed by robbers. Ahmed's nominal reign had lasted about eight years.

Ítimád Khán then raised to the throne a youth, whom he styled Muzaffar Sháh III., and who, he asserted, was a posthumous son of Mahmúd Sháh,<sup>1</sup> and then marched towards Pátan to take his revenge on the Fankahs for their attack on Fatch Khán Balúch. The nobles unwilling to crush the Fankahs, fearing lest their turn might come next, entered into secret correspondence with them, and withdrew when battle was joined. The nobles were now independent in their respective *jágirs*, in which according to the *Tabakát-i-Akbari* they allowed no interference though still owning nominal allegiance to the throne.<sup>2</sup> Ítimád Khan, forced to return unsuccessful to Ahmedábád, with a view of again attacking the Fankahs, summoned Tátár Khán Ghori from Jámagadh. The nobles remained aloof, and even Tátár

annexed by them in 1558. According to a statement in Bird's History, 128, the districts surrendered by Changíz Khan contained 700 towns (villages) yielding a yearly revenue of £130,000 (Rs. 43,00,000). Surjan, since known as St John's Head (north latitude 20° 13', east longitude 72° 47'), between Daman and Brásem, seems to be one of the two Sindans, the other being in Kachh, mentioned by the ninth or twelfth century Arab geographers. According to Idrisi (Jaubert's Edition, 172) the mainland Sindán was a great town with a large import and export trade and well peopled with rich warlike and industrious inhabitants. Idrisi's (Elliot, I. 85) notice of an island of the same name to the east is perhaps a confused reference to the Kachh Sindán which is generally supposed to be the Sindan of the Arab geographers. In A.D. 842, Sindán then a city of some size, is mentioned by Al-Biládhuri (Reynard's Fragments, 216-217) as having been taken by a Musalmán slave Fazl son of Máhán. This Fazl is related to have sent an elephant from Sindán to the Khalífah Al Maamún the Abbási (A.D. 813-833) and to have built an Assembly Mosque at Sindán. (Al-Biládhuri in Elliot, I. 129.)

<sup>1</sup> According to Abul Fazl (Akbarnáma, III. 404; Elliot, V. 730) Muzaffar was a base-born boy of the name of Nathu.

<sup>2</sup> *Tabakát-i-Akbari* in Elliot's India, V. 339 note 2.

Khán Ghori made excuses, which so exasperated Ítimád Khán that he sought to slay him. Tátár Khán escaped to Sorath, and there openly sided with the Pauládis. Sayad Mirán also left Ahmedábád for his estate at Dholka, and joining Tátár Khán at Ránpur they both went over to the Pauládis at Pátan. Meanwhile Ítimád Khán, again collecting an army, marched once more towards Pátan. He was met by the Pauládis near the village of Jhatíná, about thirty miles south of Pátan, where he was defeated and compelled to return to Ahmedábád. Sayad Mirán now intervened and made peace. Ítimád Khán still thirsting for revenge on the Pauládis, invited Changíz Khán, son of Ináid-ul-Mulk Rúní, to the capital, and by courteous treatment induced him to join in another expedition against the Pauládis. Like the other nobles Changíz Khán was lukewarm; and as Músa Khán Pauládi died while Ítimád Khán was marching on Pátan, Changíz Khán assigned this as a reason for not proceeding further, averring that it was not fit to war with people in misfortune. Ítimád Khán perforce returned to Ahmedábád.

Though Ítimád Khán had disgusted the nobles, both by causing the assassination of Ahmed Sháh and by his enmity with the Pauládis, as he had charge of Muzaffar Sháh and possession of the capital, the government of the country was in his hands. At this time the Mirzas,<sup>1</sup> who were the sons of Sultán Hussain of Khurásán, quarrelling with Jalál-ud-din Muhammad Akbar, entered Gujráat, and joined Changíz Khán. Changíz Khán now proposed to Sher Khán Pauládi that they should expel Ítimád Khán and divide Gujarat between them, the capital and the country south of the Sábarmati falling to the share of Changíz Khán, and that to the north to Sher Khán Pauládi. Sher Khán agreed, and Changíz Khán joining him they marched on Ahmedábád. Sayad Mirán induced Sher Khán to stay in Kadi. But Changíz Khán refused to listen to him, and a battle was fought between him, Ítimád Khán, and the Sayad on the right bank of the Khari about eight miles south of Ahmedábád. Ítimád Khán was defeated, and fled with the king to Modása, while Changíz Khán took possession of the capital. Sher Khán Pauládi now advanced to the Sábarmati, and, after dividing the province as had been agreed, Sher Khán retired to Kadi. Ítimád Khán entreated Mirán Muhammad Sháh, king of Khándesh, to march to his aid, and Changíz Khán invited Ítimád Khán to return. He came to Mehmudábád, where hearing that Muhammad Sháh had sustained a defeat and retired to his own country, he took Muzaffar Sháh with him and returned through Modása to Dungarpur. Changíz Khán remained in Ahmedábád, and Sher Khán withdrew to Kadi. After this success all the chief nobles of Gujarat, including the Habshis, joined Changíz Khán, who was now at the zenith of his power, and began to think of subduing Sher Khán Pauládi,

## Chapter II.

### Ahmedábád Kings.

A.D. 1403 - 1573.

### Muzaffar III. 1561 - 1572.

Ítimád Khán and  
the Pauládis.

The Mirzas,  
1571.

They Defeat  
Ítimád Khán.

<sup>1</sup> These Mirzas were the great grandsons of a Muhammad Sultán Mirza, the ruler of Khurásán, who, on being driven out of his dominions, sought refuge in India. This prince and his family on the ground of their common descent from Taimur, were entertained first by Bahír (A.D. 1526 - 1531), and afterwards by Humayún (A.D. 1531 - 1556). Before this quarrel Akbar had treated the Mirzas with great honour. Elliot's History, VI. 122.

Chapter II  
Ahmedabad  
Kings,  
A.D. 1403-1573  
Muzaffar III.  
1561-1572.  
Death  
of Changiz  
Khan

who on his part was anxious and fearful. At this time Bijli Khán a Habsli eunuch who was offended with Changiz Khán, because he had resumed the grant of Cambay, persuaded Alif Khán and Jhujhár Khan Habsli that Changiz Khán had determined to kill them. The Habsli Kháns, resolving to be beforehand, invited Changiz Khán, with whom they were intimate, to play a game of *chaugán* or polo.<sup>1</sup> Changiz agreed and when near the Farhat-ul-Mulk mosque, between the Bhadar and the Three Gates, Alif Khán, after making Jhujhár Khán a signal, attracted Changiz Khán's notice to the horse on which he was riding saying it was the best of the last batch imported from the Persian Gulf. As Changiz Khan turned to look at the horse, Jhujhár Khán cut him down. The Habslis now plundered Changiz Khan's house, while the Mírzá's, mounting, went south and took possession of Broach, Baroda, and Champaner. Sher Khan advanced from Kadi, and ordered the Habslis to hand him over Ahmedabad. While treating with him the Habslis secretly summoned Ítimád Khán, who, returning with Muzaffar Shah, entered the city. It was arranged that Ítimád Khán should take the place of Changiz Khán, and that the division of Gujarat between Changiz Khán and Sher Khán should be maintained. Ítimád Khán found the Habslis so domineering that he withdrew from public affairs. Afterwards Alaf Khan and Jhujhár Khan, quarrelling over the division of Changiz Khán's property, Alaf Khan left Ahmedabad and joined Sher Khan, who, advancing from Kadi, laid siege to Ahmedabad. Ítimád Khán now sought aid from the Mírzá's, and Mírza Ibráhím Husam marched from Broach and harassed Sher Khán's army with his Mughal archers.

Ítimád Khán  
and the  
Emperor Akbar,  
1572

At the same time Ítimád Khan turned for help to the emperor Akbar, who, glad of any pretext for driving the Mírzá's from their place of refuge in Gujarat, was not slow in availing himself of Ítimád Khan's proposal. Early in July 1572 he started for Ahmedabad, and with his arrival in the province, the history of Gujarat as a separate kingdom comes to an end.

<sup>1</sup> The modern game of polo. Lane, in his translation of the Thousand and One Nights (1. 76 1883 Edition) calls it the golf-stick but the nature of the game described there does not in any way differ from polo. *Chaugan* is the Persian and *As-sulpan-u-d-kaah* the Arabic word for the game.

## CHAPTER III.

### MUGHAL VICEROYS.

A D 1573-1758.

To the nobles thus fighting among themselves, news was brought that the emperor Akbar was at Dīsa. Ibrāhīm Husain Mirza returned to Broach and the army of the Fāulādīs dispersed. From Dīsa the imperial troops advanced to Pātan and thence to Jhotāna thirty miles south of Pātan. Sultān Muzaffar, who had separated from the Fāulādīs, fell into the hands of the emperor, who granted him his life but placed him under charge of one of his nobles named Karam All.<sup>1</sup> When the imperial army reached Kadi, Itmād Khān, Ikhtiyār Khān, Alaf Khān and Jhujhār Khān met Akbar and Sayad Hāmid also was honoured with an audience at Hājipur.<sup>2</sup> The emperor imprisoned Alaf Khān and Jhujhār Khān Habsli and encouraged the other Gujarāt nobles. Ikhtiyār-ul-Mulk now fled to Lamāvada, and the emperor, fearing that others of the Gujarāt nobles might follow his example, sent Itmād Khān to Cambay and placed him under the charge of Shalibaz Khān Kanbo.<sup>3</sup> From Ahmedabād Akbar advanced to Cambay. At this time Ibrāhīm Mirza held Baroda, Muhammad Husain Mirza held Surat, and Shah Mirza held Champiner. On leaving Cambay to expel the Mirzas, Akbar appointed Mirza Āziz Kokaltash his first viceroy of Gujarāt. At Baroda Akbar heard that Ibrāhīm Mirza had treacherously killed Rustam Khān Rūmi, who was Changiz Khīr's governor of Broach. The emperor recalled the detachment he had sent against Surat, and overtaking the Mirza at Sarnal or Thīsa on the right bank of the Mahi about twenty-three miles north-east of Nadiād, after a bloody conflict routed him. The Mirza fled by Ahmednagar to Sirohi, and Akbar rejoined his camp at Baroda. The emperor now sent a force under Shāh Kul Khān to invest the fort of Surā', and following in person pitched his camp at Gopī Tālao, a suburb of that city. After an obstinate defence of one month and seventeen days, the garrison under Hamzabān, a slave of Humayūn's who had joined the Mirzas, surrendered. Hamzabān was in treaty with the Portuguese. Under his invitation a large party of Portuguese came to

#### Chapter III.

Mughal  
Viceroys.

Akbar  
Emperor,  
1573-1605

<sup>1</sup> The emperor Akbar took Muzaffar Shah with him to Agra, and settled on him the district of Srāngpur and Ujjain in Malwa with a revenue of Rs 20,00,000 (50 *lakhs* of *tank*) (Elliot, V. 353). When Mun'im Khān Khān Khānān was going to Bengal the emperor made Muzaffar over to him. Mun'im Khān gave his daughter Shāhzādah Khānam in marriage to Muzaffar, but shortly afterwards having reason to suspect him imprisoned him, whence Muzaffar finding an opportunity fled to Gujarāt in A.D. 1581 (H. 989) according to Fārishtah (II. 460), 1583 according to the Virāt-i Sikandari.

<sup>2</sup> Both the Tabakāt-i-Akhbari (Elliot, V. 312) and Fārishtah (I. 491) name four other nobles Mir Abu Turāb, Sayad Ahmed Bhukhārī, Malik Ashraf, and Wajih-ul-Mulk. The Sayad Ahmed of these two writers is a misprint for the Sayad Hāmid of the text.

<sup>3</sup> Virāt-i-Sikandari, 115; Tabakāt-i-Akhbari in Elliot, V. 313.

**Chapter III.****Mughal  
Viceroys.**

**Akbar**  
Emperor,  
1573-1605.  
Akbar captures  
Broach and  
Surat, and  
advances to  
Ahmedabad,  
1573.

Surat during the siege, but seeing the strength of the imperial army, represented themselves as ambassadors and besought the honour of an interview<sup>1</sup>. While at Surat the emperor received from Bihār or Vihārjī the Rājā of Baglāna, Sharsuddīn Husain Mīrza whom the Rājā had captured.<sup>2</sup> After the capture of Surat, the emperor ordered the great Submāni cannon which had been brought by the Turks with the view of destroying the Portuguese forts and left by them in Surat, to be taken to Agra. Surat was placed in the charge of Kalīj Khān. The emperor now advanced to Ahmedābād, where the mother of Changiz Khān came and demanded justice on Jhujhār Khān for having wantonly slain her son. As her complaint was just, the emperor ordered Jhujhār Khān to be thrown under the feet of an elephant. Muhammad Khān, son of Sher Khān Faulādi, who had fled to the Idar hills, now returned and took the city of Pātan, besieging the imperial governor, Sayad Ahmed Khān Bārha, in the citadel. At this time Mīrza Muhammad Husain was at Rānpūr near Dhāndhūka. When Sher Khān Faulādi, who had taken refuge in Sorath, heard of Muhammad Khān's return to Pātan, he met Mīrza Muhammad Husain, and uniting their forces they joined Muhammad Khān at Pātan. The viceroy Mīrza Āziz Kokaltāsh with other nobles marched against them, and after a hard-fought battle, in which several of the imperial nobles were slain, Mīrza Āziz Kokaltāsh was victorious. Sher Khān again took refuge in Sorath, and his son fled for safety to the Idar hills, while the Mīrza withdrew to the Khāndesh frontier. As the conquest of Gujarāt was completed, Akbar returned to Agra.

From A.D. 1573, the date of its annexation as a province of the empire, to A.D. 1758, the year of the final capture of Ahmedābād by the Marāthās, Gujarāt remained under the government of officers appointed by the court of Delhi. Like the rule of the Ahmedābād kings, this term of 184 years falls into two periods: the first of 124 years from A.D. 1573 to the death of Aurangzīb in A.D. 1707, a time on the whole of public order and strong government; the second from A.D. 1707 to A.D. 1758, fifty-one years of declining power and growing disorder.

**SECTION I.—A.D. 1573-1707.**

**Mirza Āziz**  
First Viceroy,  
1573-1575.

Before leaving Gujarāt Akbar placed the charge of the province in the hands of Mīrza Āziz Kokaltāsh.<sup>3</sup> At the same time the emperor rewarded his supporters by grants of land, assigning Ahmedābād with Pītlād and several other districts to the viceroy Mīrza Āziz, Pātan to the Khān-i-Kalān Mīr Muhammad Khān, and Baroda to Nawāb Aurang Khān. Broach was given to Kutb-ud-dīn Muhammad, and Dholka Khānpur and Sami were confirmed to Sayad Hāmīd and Sayad Mahmūd Bukhārī. As soon as the emperor was gone Ikhtiyār-ul-

<sup>1</sup> These details of the Surat expedition are taken from the *Tabakat-i-Akbari* in Elliot, V. 313-316 and Abūl Fazl's *Akbar-namah* in Elliot, VI. 42.

<sup>2</sup> The emperor Jehāngir in his *Diary* (*Tuzuk-i-Jehāngīrī*, Persian Text, Sir Sayad Ahme.'s Edition, page 196) says that Bihārjī or Vihārjī was the hereditary title of the chiefs of Baglān. The personal name of the Baglan Bihārjī of his time was Partāp.

<sup>3</sup> According to the *Ain-i-Akbari* (Blochmann, I. 325) the province of Gujarāt over which the Kokaltash was placed did not pass further south than the river Mahi.

Mulk and Muhammad Khán, son of Sher Khán, who had taken shelter in the Ídar hills, issued forth, and the viceroy marched to Ahmednagar to hold them in check. Mírza Muhammad Husain advancing rapidly from the Nandurbár frontier, took the fort of Broach, and went thence to Cambay which he found abandoned by its governor Husain Khan Karkarah, while he himself marched to Ahmednagar and Ídar against Ikhtiyár-ul-Mulk. The viceroy ordered Sayad Humíd Bukhári, Nawab Namrang Khán, and others to join Kutb-ud-dín Muhammad Khán. They went and laid siege to Cambay, but Mírza Muhammad managed to evacuate the town and join Ikhtiyár-ul-Mulk and Muhammad Khán. After several unsuccessful attempts to scatter the enemy the viceroy retired to Ahmedábad, and the rebels laid siege to the city. Kutb-ud-dín Khán, Savad Mírán, and others of the imperial party succeeded in entering the city and joining the garrison. After the siege had lasted two months Akbar, making his famous 600 mile (100 kos) march in nine days from Agra, arrived before Ahmedábad, and, at once engaging the enemy, totally defeated them with the loss of two of their leaders Mírza Muhammad Husain and Ikhtiyár-ul-Mulk.

On the day before the battle Akbar consulting a Hazára Afghan versed in drawing omens from sheeps' shoulder-blades, was told that victory was certain, but that it would be won at the cost of the life of one of his nobles. Seif Khan, brother of Zain Khán Koka, coming in prayed that he should be chosen to receive the crown of martyrdom. At the end of the day the only leading noble that was killed was Seif Khan<sup>1</sup>.

After only eleven days' stay, Akbar again entrusting the government of Gujarat to Mírza Azíz Koka, returned to Agra. Mírza Azíz Koka did not long continue viceroy. In A.D. 1575, in consequence of some dispute with the emperor, he retired into private life. On his resignation Akbar conferred the post of viceroy on Mírza Khán, son of Behráin Khan, who afterwards rose to the high rank of Khán Khánín or chief of the nobles. As this was Mírza Khán's first service, and as he was still a youth, he was ordered to follow the advice of the deputy viceroy, Wazír Khán, in whose hands the administration of the province remained during the two following years. Soon after the insurrection of 1573 was suppressed the emperor sent Raja Todar Mal to make a survey settlement of the province. In A.D. 1575 after the survey was completed Wajih-ul-Mulk Gujaráti was appointed *darín* or minister. Some historians say that in A.D. 1576 Wazír Khán relieved Mírza Azíz Koka as viceroy, but according to the *Mirát-i-*

## Chapter III.

Mughal  
Viceroys.

Akbar  
Emperor,  
1573-1605.  
Mírza Azíz  
First Viceroy,  
1573-1575.

Insurrection  
Quelled by  
Akbar,  
1573.

Mírza Khán  
Second Viceroy,  
1575-1577.

Survey by Rája  
Todar Mal.

<sup>1</sup> Tuzukí Jehángíri or Jehangír's Memoirs, Pers. Text, Sayad Ahmed Khán's Edition page 20. For Akbar's march compare Tabakat-i-Akbari in Elliot, V. 365 and Blochman's *Am-i-Akbari*, I. 325 and note. The *Mirát-i-Ahmedi* (Pers. Text, 131) records these further details: When starting from his last camp Akbar began to mount his horse on the day of the battle that took place near Ahmedábad. The royal steed unable to bear the weight of the hero laden with the spirit of victory sat down. Raja Bhagwándás Kuchwáth ran up to the rather embarrassed emperor and offered him his congratulations saying: 'This, your Majesty, is the surest sign of victory. There are also two further signs: the wind blows from our back and the kites and vultures accompany our host.'

## Chapter III.

Mughal  
Viceroys.

Akbar  
Emperor,  
1573-1605.  
Mírza Kírán  
Second Viceroy,  
1575-1577.

Ahmedí Mirza Khán held office with Wazír Khán as his deputy. One Prágdás, a Hindu, succeeded Wajih-ul-Mulk as *diwan*. Troops were sent to reduce the Nándod and Idar districts, and the fort of Sirohi was captured by Tarsu Khán, the military governor of Patan. Afterwards, through the intervention of Palar Khán Jálora, the Sirohi Rájá, at an interview with Rájá Todar Mal, presented £ 500 (Rs. 12,000) and other articles and was allowed to serve the provincial governor of Gujarát with 1500 horse.

During Wazír Khán's administration Muzaffar Husain Mírza, son of Ibrahim Husain Mirza, raised an insurrection in Gujarát. This Mírza Muzaffar was as an infant carried to the Dakhan from Surat shortly before its investment by Akbar. He lived peacefully till under the influence of an ambitious retainer Míhr Ah by name, he gathered an army of adventurers and entered Nandurbár. Wazír Khán distrusting his troops shut himself in a fortress, and wrote to Rájá Todar Mal, who was in Patan settling revenue affairs. The Mírza defeated the imperial forces in Nandurbár and failing to get possession of Cambay marched straight to Ahmedábád. On the advance of Rájá Todar Mal the Mírza fell back on Dholka. The Rájá and the Khán pursuing defeated him, and he retired to Júnágadh. The Rájá then withdrew, but the Mírza again advanced and besieged him in Ahmedábád. In an attempt to escalade the city wall Míhr Ah was killed. Muzaffar Mírza withdrew to Khándesh and the insurrection came to an end.

SHAHÁB-UD-DÍN  
Third Viceroy,  
1577-1583.

Sends a Force  
against  
Júnágadh.

In the end of A.D. 1577, as Wazír Khán's management was not successful, the post of viceroy was conferred upon Shaháb-ud-dín Ahmed Khán, the governor of Málwa. Shaháb-ud-dín's first step was to create new military posts and strengthen the old ones. At this time Fateh Khán Shirwáni, the commander of Amín Khán Ghori's army, quarrelled with his chief, and, coming to Shaháb-ud-dín, offered to capture the fort of Júnágadh. Shaháb-ud-dín entertained his proposal, and sent his nephew Mírza Khán and 1000 horse with him. When the troops crossed the Sorath frontier, they were met by envoys from Amín Khán, agreeing, in his name, to pay tribute and surrender the country, provided he were permitted to retain the fortress of Júnágadh and were allotted a sufficient grant of land. Mírza Khán rejected these proposals and continued his march against Júnágadh. Amín Khán made a vigorous resistance and applied for aid to the Jám of Navánagar. At this juncture Fateh Khán died, and Mírza Khán went and besieged Mángarúl. The Jám's minister Isá now joined Amín Khán with 4000 horse, and he, quitting Júnágadh, marched to Mángarúl.<sup>2</sup> On their approach Mírza Khán retired to the town of

<sup>1</sup> Tabakat-i-Akhari in Elliot, V. 405.

<sup>2</sup> Mángarúl (north latitude 21° 8'; east longitude 70° 10'), a seaport on the south coast of Kachhiaváda, about twenty miles west of Somnath. This town, which is supposed to be the Monoglossum emporium of Ptolemy (A.D. 150) (see Bird, 115), is spelt Manglár by the Muhammadan historians. Barbosa (A.D. 1511-1514), under the name of Surati-mogaler, calls it a 'very good port where many ships from Malabar touch for horses, wheat, rice, cotton goods, and vegetables.' In A.D. 1531 the city was taken by the Portuguese general Sylveira with a vast booty and a great number of prisoners (Cherchill's Travels III. 529). It is incidentally mentioned in the Ain-i-Akbari (A.D. 1590). In A.D. 1638 Mandelslo describes it as famous for its linen cloth, and in A.D. 1700 it is mentioned by Hamilton (New Account, I. 136) as a place of trade.

Kodinar<sup>1</sup> followed by Amín Khán. Here a pitched battle was fought, and Mírza Khán was defeated with the loss of his baggage. Many of his men were slain, and he himself, being wounded, escaped with difficulty to Ahmedabad. Shahab ud-dín, who had meanwhile been giving his attention to revenue matters, and to the more correct measurement of the lands of the province, was rudely recalled from these peaceful occupations by his nephew's defeat. At the same time news was brought of the escape of the former king, Muzaffar Khán, who, eluding the vigilance of the imperial servants, appeared in Gujarát in A.D. 1583. Muzaffar remained for some time in the Rájpipla country, and thence came to one Lóna or Lúmlha Káthi, at the village of Khíri in the district of Sardhár in Sorath.

Before he could march against Muzaffar, Shaháb-ud-dín was recalled, and in A.D. 1583 or 1584<sup>2</sup> Ítimád Khán Gujaráti was appointed viceroy. At this time a party of 700 or 800 Mughals, called Wazír Kháns, separating from Shaháb-ud-dín, remained behind in hope of being entertained by the new viceroy. As Ítimád Khán declared that he was unable to take them into his service, they went off in a body and joined Muzaffar at Khíri, and he with them and three or four thousand fighting horse marched at once on Ahmedabad. On hearing this Ítimád Khán, leaving his son Sher Khán in Ahmedabad, followed Shaháb-ud-dín to Kadi, and entreated him to return. Shaháb-ud-dín at first affected indifference telling Ítimád that as he had given over charge he had no more interest in the province. After two days he consented to return if Ítimád stated in writing that the country was on the verge of being lost and that Ítimád being unable to hold it was obliged to relinquish charge to Shahab ud dín. Ítimád Khán made the required statement and Shaháb-ud-dín returned with him.<sup>3</sup> Meanwhile Muzaffar Shah reached Ahmedabad, which was weakly defended, and in A.D. 1583, after a brief struggle, took possession of the city. While the siege of Ahmedabad was in progress Shahab-ud-dín and Ítimád Khán were returning, and were within a few miles of the city, when news of its capture reached them. They continued their advance, but had barely arrived at Ahmedabad when Muzaffar Shah totally defeated them taking all their baggage. Seeing the issue of the fight, most of their army went over to Muzaffar Shah, and the viceroy and Shaháb-ud-dín with a few men fled to Pátan. Kutb-ud-dín Muhammad Khán Atkah, one of the imperial commanders, who was on the Khándesh frontier, now advanced by forced marches to Baroda. Muzaffar marched against him with a large army, recently strengthened by the union of the army of Sayad Danlát ruler of Cambay. Kutb-ud-dín threw himself into Baroda, and, in spite of the treachery of his troops, defended the city for some time. At last, on Muzaffar's assurance that his life should be spared Kutb-ud-dín repaired to the enemies' camp to treat for peace. On his arrival he was treated with respect, but next day was treacherously put to death. The fort of Broach was also at this

## Chapter III.

Mughal  
Viceroys.

Akbar  
Emperor,  
1573-1605.  
SHAHÁB-UD-DÍN  
Third Viceroy,  
1577-1583.

ÍTIMÁD KHÁN  
GUJARÁTI  
Fourth Viceroy,  
1583-4.

Muzaffar captures  
Ahmedabad,  
1583.

<sup>1</sup> This has been rendered by Bird, 353, 'the mountain of Dinar,' as if Koh Dínár.

<sup>2</sup> H. 992 (1584 A.C.) according to the *Tabakat-i-Akbari* (Elliot, V. 428).

<sup>3</sup> *Mirát-i-Sikandari*, 422. Compare Blochman's *Ain-i-Akbari*, I. 336.

## Chapter III.

Mughal  
Viceroys.Akbar  
Emperor,  
1573-1605.MIRZA ABDUR-  
RAHIM KHAN  
(KHAN KHANAN)  
Fifth Viceroy  
1573-1587.Defeat  
of Muzaffar,  
1584.

time traitorously surrendered to Muzaffar by the slaves of the mother of Nanrang Khān, chief-holder of the district.

On learning of the Gujarāt insurrection the emperor, at the close of A.D. 1583, conferred the government of the province on Mirza Abul-rahīm Khān, son of Be'iram Khān, who had formerly (A.D. 1575) acted as viceroy. Muzaffar, who was still at Broach, hearing of the advance of the new viceroy with a large army, returned rapidly to Ahmedābād, and in A.D. 1584 fought a pitched battle with Mirza Abdur-Rahīm Khān between Sirkhej and Shah Bhukan's tomb.<sup>1</sup> In this engagement Muzaffar was entirely defeated, and fled to Cambay pursued by Mirza Abul-rahīm Khān. Muzaffar now hearing that Mirza Abul-rahīm Khān had been joined by Nanrang Khān and other nobles with the imperial army from Mālwa, quitted Cambay, and made for his old place of shelter in Rajpīpla. Finding no rest in Rajpīpla, after fighting and losing another battle in the Rajpīpla hills, he fled first to Patan and then to Idar, and afterwards again repaired to Lūmbhā Kathi in Khiri. In reward for these two victories, the emperor bestowed on Mirza Abul-rahīm Khān the title of Khan Khānān. Broach now submitted, and Muzaffar sought shelter with Amin Khān Ghori at Jūnāgadh, by whom he was allotted the waste town of Gūndal as a residence. Muzaffar made one more attempt to establish his power. He advanced to Morvi, and thence made a raid on Radhanpūr and plundered that town, but was soon compelled to return to Kāthiāvada and seek safety in flight. Amin Khān, seeing that his cause was hopeless, on pretence of arming him, induced Muzaf-

<sup>1</sup> Mirāt-i Sikandari, 426; Farishtah, I, 503; Elliot, V, 431. In honour of this victory the Khan Khānān built on the site of the battle a palace and garden enclosing all with a high wall. This which he named Jitpur the City of Victory was one of the chief ornaments of Ahmedābād. In November 1615 the English merchant Winterton writes (Beur's Voyages, IX, 327) 'A house from Sirkhej is a pleasant house with a large garden all round on the banks of the river which Chon-Chu-Naw (Khan Khānān) built in honour of a great victory over the last king of Gujarāt. No person inhabits the house. Two years later (1615) another English merchant Dodsworth (Ken, IX, 103) describes the field of Victory as strongly walled all round with brick about 1½ miles in circuit all planted with fruit trees and delightfully watered having a costly house called by a name signifying Victory in which Khan Khānān for some time resided. In 1615, the emperor Jehangir (Memoirs Persian Text, 210-213) on his way to Sirkhej visited the Khan-Khānān's Bagh Farh or Garden of Victory which he had built at a cost of two lakhs of rupees ornamenting the garden with buildings and surrounding it with a wall. The natives he notices call it Fatch-Wah. In 1626 the English traveller Herbert (Travels, 66) writes 'Two miles nearer Ahmedābād than Sirkhej are the curious gardens and palace of Khan Khānān where he defeated the last of the Cambay kings and in memory built a stately house and spacious gardens the view whereof worthily attracts the traveller. Mandelslo writing in 1638 is still louder in praise of Tschetbāg the Garden of Victory. It is the largest and most beautiful garden in all India because of its splendid buildings and abundance of fine fruits. Its site is one of the pleasantest in the world on the border of a great tank having on the water side many pavilions and a high wall on the side of Ahmedābād. The lodge and the caravansarai are worthy of the prince who built them. The garden has many fruit trees oranges, citrons, pomegranates, dates, almonds, mulberries, tamarinds, mangoes, and cocoanuts so closely planted that all walking in the garden is under most pleasing shade (Mandelslo's Travels, French Ed. 111-112). When (A.D. 1750) the Mirāt-i-Ahmedi was written several of the buildings and the remains of the summer house were still to be seen (Bird's History of Gujarāt, 376). A few traces of the buildings known as Fatch Bādi or Victory Garden remain (1879). (Ahmedābād Gazetteer, 292.)

far to give him about £10,000.<sup>1</sup> When he had obtained the money, on one pretext or another, Amín Khán withheld the promised aid. The Khán Khánán now marched an army into Sorath against Muzaffar. The Jám of Navánagar and Amín Khán sent their envoys to meet the viceroy, declaring that they had not sheltered Muzaffar, and that he was leading an outlaw's life, entirely unaided by them. The viceroy agreed not to molest them, on condition that they withheld aid and shelter from Muzaffar, and himself marched against him. When he reached Upleta, about fifteen miles north-west of the fortress of Jínágarh, the viceroy heard that Muzaffar had sought shelter in the Barda hills in the south-west corner of the peninsula. Advancing to the hills, he halted his main force outside of the rough country and sent skirmishing parties to examine the hills. Muzaffar had already passed through Navánagar and across Gujarát to Dánta in the Mahi Kantha. Here he was once more defeated by the Parántej garrison, and a third time took refuge in Rájpípla. The viceroy now marched on Navánagar to punish the Jám. The Jám sent in his submission, and the viceroy taking from him, by way of fine, an elephant and some valuable horses, returned to Ahmedábád. He next sent a detachment against Ghazni Khán of Jhú'or who had favoured Muzaffar. Ghazni Khán submitted, and no further steps were taken against him.

In A.D. 1587 the Khán Khánán was recalled and his place supplied by Ismail Kuli Khán. Ismail's government lasted only for a few months, when he was superseded by Mírza Azíz Kokaltásh, who was a second time appointed viceroy. In A.D. 1591, Muzaffar again returned to Sorath. The viceroy, hearing that he had been joined by the Jám, the Kachh chief, and Daulat Khán (Ghori the son of Amín Khán, marched with a large army towards Sorath, and, halting at Virangám, sent forward a detachment under Naurang Khán, Sayad Kásim, and other officers. Advancing as far as Morvi,<sup>2</sup> Naurang Khán entered into negotiations with the Jám, who, however, refused to accede to the demands of the imperial commander. On this the viceroy joined Naurang Khán with the bulk of his army, and after a short delay marched on Navánagar. On his way, at the village of Dhokar near Navánagar, Muzaffar and the Jám opposed him, and an obstinate battle in which the imperialists were nearly worsted, ended in Muzaffar's defeat. The son and minister of the Jám were slain, and Muzaffar, the Jám, and Daulat Khán who was wounded, fled to the fortress of Jínágarh. The viceroy now advanced and plundered Navánagar, and remaining there sent Naurang Khán, Sayad Kásim, and Gújar Khán against Jínágarh. The day the army arrived before the fortress Daulat Khán died of his wounds. Still the fortress held out, and though the viceroy joined them the siege made little progress as the imperial troops were in great straits for grain. The viceroy returned to Ahmedábád, and after seven or eight months again marched against Jínágarh. The Jám, who was still a fugitive, sent envoys

## Chapter III.

Mughal  
Viceroys.

Akbar  
Emperor,  
1583-1605  
Mírza ABDUR-  
RAHÍM KHÁN  
(KHÁN KHANÁNA)  
Fifth Viceroy,  
1583-1587.

ISMAÍL KULÍ  
KHÁN  
Sixth Viceroy,  
1587.

Mírza AZÍZ  
KOKALTÁSH  
Seventh Viceroy,  
1588-1592.

Muzaffar seeks  
Refuge in  
Kathiavada.

Is attacked by  
the Imperial  
Army.

<sup>1</sup> Two *lákhs* of *mahmudis*. The *mahmudi* varied in value from about one-third to one-half of a rupee. See Introduction page 222 note 2.

<sup>2</sup> Morvi (north latitude 29° 48'; east longitude 70° 30'), a town in Kathiavada, about twenty-one miles south of Kachh.

## Chapter III.

Mughal  
Viceroys.Akbar  
Emperor,  
1583-1605.Mírza Ázíz  
KOKALTÁSH  
Seventh Viceroy,  
1587.Muzaffar Flies  
to Kachh,Commits Suicide,  
1591-92.SULTÁN MURÁD  
BAKSH  
Eighth Viceroy,  
1592-1600.

and promised to aid the viceroy if his country were restored to him. The viceroy assented on condition that, during the operations against Jánágadh, the Jám should furnish his army with grain. The Jám agreed to provide grain, and after a siege of three months the garrison surrendered.

News was next received that Muzaffar had taken refuge at Jagat.<sup>1</sup> The viceroy at once sent Naurang Khán and others with an army in pursuit. On reaching Jagat it was found that Muzaffar had already left for a village owned by a Rajput named Sewa Wádhel. Without halting Naurang Khán started in pursuit, nearly surprising Muzaffar, who escaping on horseback with a few followers, crossed to Kachh. Sewa Wádhel covering Muzaffar's retreat was surprised before he could put to sea and fought gallantly with the imperial forces till he was slain. Naurang Khán then came to Arámra, a village belonging to Singrám Wádhel, Rájá of Jagat, and after frustrating a scheme devised by that chief to entrap a body of the troops on board ship under pretence of pursuing Muzaffar's family, led his men back to Jánágadh. The viceroy, hearing in what direction Muzaffar had fled, marched to Morvi, where the Jám of Navánagar came and paid his respects. At the same time the Kachh chief who is called Khengóí by Farishtah and in the Mirát-i-Ahmedi and Bhára in the Mirát-i-Sikandri, sent a message that if the viceroy would refrain from invading his country and would give him his ancestral district of Morvi and supply him with a detachment of troops, he would point out where Muzaffar was concealed. The Khán-i-Ázam agreed to these terms and the chief captured Muzaffar and handed him to the force sent to secure him. The detachment, strictly guarding the prisoner, were marching rapidly towards Morvi, when, on reaching Dhrol, about thirty miles east of Jámnagar, under pretence of obeying a call of nature, Muzaffar withdrew and cut his throat with a razor, so that he died. This happened in A.D. 1591-92. The viceroy sent Muzaffar's head to court, and though he was now recalled by the emperor, he delayed on pretence of wishing to humble the Portuguese. His real object was to make a pilgrimage to Makkah, and in A.D. 1592, after obtaining the necessary permission from the Portuguese, he started from Verával.<sup>2</sup> During this viceroyalty an imperial *farmán* ordered that the state share of the produce should be one-half and the other half should be left to the cultivator and further that from each half five per cent should be deducted for the village headmen. All other taxes were declared illegal, and it was provided that when lands or houses were sold, half the government demand should be realized from the seller and half from the buyer.

The emperor, who was much vexed to hear of the departure of the viceroy, appointed prince Sultán Murád Baksh in his stead with as his minister Muhammad Sádikhán one of the great nobles. In A.D. 1593-94 Mírza Ázíz Kokaltásh returned from his pilgrimage and

<sup>1</sup> Jagat (north latitude 22° 15'; east longitude 69° 1'), the site of the temple of Dwárka, at the western extremity of the peninsula of Káthiáváda.

<sup>2</sup> Verával (north latitude 20° 55'; east longitude 70° 21'), on the south-west coast of Káthiáváda. On the south-east point of Verával bay stood the city of Dev or Mungi Pátan and within its walls the temple of Pomanátha.

repaired to court, and next year on prince Murád Bakhsh going to the Dakhan, Súrjasingh was appointed his deputy. In A.D. 1594-95 Bahádur, son of the late Muzaffar Sháh, excited a rebellion, but was defeated by Súrjasingh. In A.D. 1600, owing to the death of Sultán Murád, Mírza Áziz Kokaltásh was a third time appointed viceroy of Gujarát, and he sent Shams-ud-dín Husain as his deputy to Ahmedábád. Further changes were made in A.D. 1602 when Mírza Áziz sent his eldest son Shaidmán as deputy; his second son Khurram as governor of Júnágadh; and Sayad Báyzíd as minister. Khurram was afterwards relieved of the charge of Sorath and Júnágadh by his brother Abdulláh.

In A.D. 1605 Núr-ud-dín Muhammad Jehángir ascended the imperial throne. Shortly after his accession the emperor published a decree remitting certain taxes, and also in cases of robbery fixing the responsibility on the landowners of the place where the robbery was committed. The decree also renewed Akbar's decree forbidding soldiers billeting themselves forcibly in cultivators' houses. Finally it directed that dispensaries and hospital wards should be opened in all large towns. In the early days of Jehangir's reign disturbance was caused in the neighbourhood of Ahmedábád by Bahádur a son of Muzaffar Sháh. Jehángir despatched Patrás Rája Vikramájit as viceroy of Gujarát to put down the rising. The Rája's arrival at Ahmedábád restored order. Some of the rebel officers submitting were reinstated in their commands; the rest fled to the hills.<sup>1</sup> On the Rája's return Jehángir appointed Kalij Khán to be viceroy of Gujarát; but Kalij Khán never joined his charge, allowing Mírza Áziz Kokaltásh to act in his place. In A.D. 1606, on the transfer of Mírza Áziz to the Lahor viceroyalty, Sayad Murtaza Khán Bukhári, who had recently been ennobled in consequence of crushing the rebellion under Jehangir's son Khusráo, was entrusted with the charge of Gujarát, Sayad Báyzíd being continued as minister. Sayad Murtaza, who is said to have further ingratiated himself with the emperor by the present of a magnificent ruby, appears to have been more of a scholar than a governor. His only notable acts were the repair of the fort of Kadi<sup>2</sup> and the populating of the Bukhára quarter of Ahmedábád. During his tenure of power disturbances broke out, and Rái Gopináth, son of Rája Todar Mal, with Rája Sursingh of Jodhpur, were sent to Gujarát by way of Málwa Surat and Baroda. They overcame and imprisoned Kalán, chief of Belpár,<sup>3</sup> but were defeated by the Mándwa<sup>4</sup> chieftain, and withdrew to Ahmedábád. Rái Gopináth, obtaining reinforcements, returned to Mándwa and succeeded in capturing the chief. He then marched against the rebellious Kolis of the Kánkrej, and took prisoner their

## Chapter III.

Mughal  
Viceroys.

Akbar  
Emperor,  
1583-1605.  
Mírza Áziz  
Kokaltásh  
Ninth Viceroy,  
1600-1606.

Jehangir  
Emperor,  
1605-1627.

Kalij Khán  
Tenth Viceroy,  
1606.

Sayad Murtaza  
Eleventh Viceroy,  
1606-1609.

<sup>1</sup> Jehángir's Memoirs, Persian Text, 23; Blochman's Ain-i-Akbari, I. 470. Bahádur died about A.D. 1614: Jehangir's Memoirs, 134.

<sup>2</sup> Now belonging to His Highness the Gaikwár about twenty-seven miles north-west of Ahmedábád.

<sup>3</sup> Belpár, belonging to the Thákor of Umeta in the Rewa Kántha.

<sup>4</sup> This Mándwa is probably the Mándwa under His Highness the Gaikwár in his district of Atarsumba, but it may be Mándwa on the Narbada in the Rewa Kántha. Atarsumba is about ten miles west of Kapadvanj in the British district of Kaira.

**Chapter III.****Mughal  
Viceroys.**

**Jehāngīr**  
Emperor,  
1605-1607  
**Mīrza Āzīz**  
**KOKALTASHI**  
Twelfth Viceroy,  
1609-1611.

leader, whom, on promising not to stir up future rebellions, he afterwards restored to liberty.

The first connection of the English with Gujarāt dates from Sayad Murtaza's viceroyalty. In A.D. 1608 he allowed Captain Hawkins to sell goods in Surat.

In A.D. 1609 the Khān-i-Azam Mīrza Āzīz Kokaltāsh was for the fourth time appointed viceroy of Gujarāt. He was allowed to remain at court and send his son Jehāngīr Kuli Khān as his deputy with Mohandās Divān and Masūd Beg Hamadām.<sup>1</sup> This was the beginning of government by deputy, a custom which in later times was so injurious to imperial interests.

Sack of Surat by  
Malik Āmbar,  
1609.

In 1609 Malik Āmbar, chief minister of Nizām Shīh's court and governor of Daulatābād, invaded Gujarāt at the head of 50,000 horse, and after plundering both the Surat and Baroda districts retired as quickly as he came. To prevent such raids a body of 25,000 men was posted at Ramnagar<sup>2</sup> on the Dakhan frontier, and remained there for four years. The details of the contingents of this force are :

The Viceroy of Ahmedābād	...	...	...	1000	Men.
The Nobles of his Court	...	...	...	5000	"
The Chiefs of Sāler and Mulher (Bāglān)	...	...	...	3000	"
The Son of the Kachh Chief	...	...	...	2500	"
The Chief of Navanagar	...	...	...	2500	"
The Chief of Idar	...	...	...	2000	"
The Chief of Dīngarpūr	} Now under the fully Tracts Agency, Rājputana.			2000	"
The Chief of Binsvada				2000	"
The Chief of Rāmāgar (Dharampur)	...	...	...	1000	"
The Chief of Rāpīpla	...	...	...	1000	"
The Chief of Ah (Ahirāpur under the Bhopāwar Agency)	...	...	...	300	"
The Chief of Mohan (a former capital of the state of Chhota Udepur in the Rewa Kānthā)	...	...	...	350	"

Total ... 25,650 Men.

**ABDULLAH KHAN**  
**FIRUZ JANG**  
Thirteenth  
Viceroy,  
1611-1616.

In A.D. 1611 Abdullāh Khān Bahādur Fīrūz Jang was appointed thirteenth viceroy of Gujarāt, with Ghīās-ud-dīn as his minister, under orders to proceed to the Dakhan to avenge the recent inroad.<sup>3</sup> The viceroy marched to the Dakhan but returned without effecting anything. In A.D. 1616, he was again, in company with prince Shāh

<sup>1</sup> Jehāngīr's Memoirs, Persian Text, 75.

<sup>2</sup> Now belonging to the Rājā of Dharampur, east of the British district of Surat.

<sup>3</sup> In this year (A.D. 1611) the English East India Company sent vessels to trade with Surat. The Portuguese made an armed resistance, but were defeated. The Mughal commander, who was not sorry to see the Portuguese beaten, gave the English a warm reception, and in A.D. 1612-13 a factory was opened in Surat by the English, and in A.D. 1614 a fleet was kept in the Tāpti under Captain Downton to protect the factory. In A.D. 1616, Sir Thomas Roe came as ambassador to the emperor Jehāngīr, and obtained permission to establish factories, not only at Surat but also at Broach Camlay and Gogha. The factory at Gogha seems to have been established in A.D. 1613. The emperor Jehāngīr notes in his memoirs (Persian Text, 105) that Mukarrāh Khān, viceroy from A.D. 1616-1618, regardless of cost had bought from the English at Gogha a turkey a lemur and other curiosities. On his return from Jehāngīr's camp at Ahmedābād in January 1618 Roe obtained valuable concessions from the viceroy. The governor of Surat was to lend ships to the English, the resident English might carry arms, build a house, practise their religion, and settle their disputes. Kerr's Voyages, IX. 253. The Dutch closely followed the English at Surat and were established there in A.D. 1618.

Jehán, directed to move against Ahmednagar. This second expedition was successful. The country was humbled, and, except Malik Ambar, most of the nobles submitted to the emperor. During this viceroy's term of office an imperial decree was issued forbidding nobles on the frontiers and in distant provinces to affix their seals to any communications addressed to imperial servants.

In A.D. 1616 on their return to Delhi, Mukarrab Khán, a surgeon who had risen to notice by curing the emperor Akbar and was ennobled by Jehángir, and who, since A.D. 1608, had been in charge of Surat or of Cambay, was appointed fourteenth viceroy of Gujarát, with Muhammad Sáfí as his minister. In the following year (A.D. 1617) the emperor Jehángir came to Gujarát to hunt wild elephants in the Dahad forests. Bitt owing to the density of the forest only twelve were captured. Early in A.D. 1618 he visited Cambay which he notes only vessels of small draught could reach and where he ordered a gold and silver *tanka* twenty times heavier than the gold *mohar* to be minted. From Cambay after a stay of ten days he went to Ahmedábád and received the Rájá of Ídar. As the climate of Ahmedábád disagreed with him Jehángir retired to the banks of the Mahi.<sup>1</sup> Here the Jám of Naváñagar came to pay homage, and presented fifty Kachh horses, a hundred gold *mohars*, and a hundred rupees, and received a dress of honour. The emperor now returned to Ahmedábád, where he was visited by Rai Bhara of Kachh, who presented 100 Kachh horses 100 *ashrafis*<sup>2</sup> and 2000 rupees. The Rái, who was ninety years of age,

## Chapter III.

Mughal  
Viceroys.

Jehángir  
Emperor,  
1605-1627.

MUKARRAB  
KHÁN  
Fourteenth  
Viceroy,  
1616.

Elephant-hunting  
in the Panch  
Mahals,  
1616.

<sup>1</sup> At first Jehángir, who reached Ahmedábád in the hot weather (March A.D. 1618), contented himself with abusing its sandy streets, calling the city the 'abode of dust' *girdabad*. After an attack of fever his dislike grew stronger, and he was uncertain whether the 'home of the moon' *sumuistan*, the 'place of sickness' *hamaristan*, the 'thorn brake' *zakandari*, or 'hell' *jahannamahad*, was its most fitting name. Even the last title did not satisfy his dislike. In derision he adds the verse, 'Oh essence of all goodnesses by what name shall I call thee.' Elliot's History of India, VI. 368; Jehángir's Memoirs Persian Text, 231. Of the old buildings of Ahmedabad, the emperor (Memoirs, Persian Text, 208-210) speaks of the Kankariya tank and its island garden and of the royal palaces in the Bhadar as having nearly gone to ruin within the last fifty years. He notes that his Bakhshi had repaired the Kankariya tank and that the viceroy Mukarrab Khán had partly restored the Bhadar palaces against his arrival. The emperor was disappointed in the capital. After the accounts he had heard it seemed all at once with its narrow streets, its shops with ignoble fronts, and its dust, though to greet the emperor as he came on elephant-back scattering gold the city and its population had put on their holiday dress. The emperor speaks (Memoirs, Persian Text page 211) of having met some of the great men of Gujarát. Chief among these was Sayad Muhammad Bukhári the representative of Shahi Alam and the sons of Shah Wajih-ud-dín of Ahmedábád. They came as far as Cambay to meet the emperor. After his arrival in the capital Jehángir with great kindness informally visited the house and garden of Sikandar Gujarati the author of the *Mirát-i-Sikandari*, to pick some of the author's famous figs off the trees. Jehangir speaks of the his'arian as a man of a refined literary style well versed in all matters of Gujarát history, who six or seven years since had entered his (the imperial) service (Memoirs, 207-211). On the occasion of celebrating Shah Jehán's twenty-seventh birthday at Ahmedábád Jehangir records having granted the territory from Mándi to Cambay as the estate of his son Shah Jehán (Prince Khurram). Memoirs, Persian Text, 210-211. Before leaving Gujarát the emperor ordered the expulsion of the Sevadas or Jain priests, because of a prophecy unfavourable to him made by Mán Sing Sewda (Memoirs, Persian Text, 217).

<sup>2</sup> This was probably the gold *ashrafi* or scrapp of which Hawkins (1609-1611) says, 'Serrafus Ekberi, which be ten rupees a-piece.' Thomas Chron. Pat. Kings of Delhi, 425.

## Chapter III.

Mughal  
Viceroys.Jehāngir  
Emperor,  
1605-1627PRINCE SHAH  
JEHAN  
Fifteenth Viceroy,  
1618-1622.Shah Jehān  
Rebels,  
1622-1623.  
Builds the  
Shāh Bagh  
at Ahmedabad.  
SULTAN DAWAR  
BAKSH  
Sixteenth Viceroy,  
1622-1624.

had never paid his respects to any emperor. 'Jehāngir, much pleased with the greatest of Gujarāt Zamindars, who, in spite of his ninety years was hale and in full possession of all his senses, gave him his own horse, a male and female elephant, a dagger, a sword with diamond-mounted hilt, and four rings of different coloured precious stones. As he still suffered from the climate, the emperor set out to return to Agra, and just at that time (A.D. 1618-19) he heard of the birth of a grandson, afterwards the famous Abūl Muzaffar Muhiyy-ud-din Muhammad Aurangzib who was born at Dohad in Gujarāt.<sup>1</sup> In honour of this event Shāh Jehān held a great festival at Ujjain.

Before the emperor started for Agra, he appointed prince Shāh Jehān fifteenth viceroy of Gujarāt in the place of Mukarrab Khān whose general inefficiency and churlish treatment of the European traders he did not approve. Muhammad Safi was continued as minister. As Shāh Jehān preferred remaining at Ujjain he chose Rustam Khān as his deputy; but the emperor, disapproving of this choice, selected Rājā Vikramājī in Rustam Khān's stead. Shortly after, in A.D. 1622-23, Shāh Jehān rebelled, and in one of the battles which took place Rājā Vikramājī was killed. Shāh Jehān, during his viceroyalty, built the Shāh Bagh and the royal baths in the Bhadar at Ahmedābād. After the death of Vikramājī, his brother succeeded as deputy viceroy. While Shāh Jehān was still in rebellion, the emperor appointed Sultān Dāwar Baksh the son of prince Khusrāo, sixteenth viceroy of Gujarāt, Muhammad Safi being retained in his post of minister. Shāh Jehān, who was then at Māndu in Mālwa, appointed on his part Abdullāh Khān Bahādur Fīrūz Jang viceroy and a *khājāsara* or eunuch of Abdullāh Khān his minister. Sultān Dāwar Baksh, the emperor's nominee, was accompanied by Khān-i-Azam Mirza Āzīz Kokaltāsh to instruct him in the management of affairs. Prince Shah Jehān had directed his minister to carry away all the treasure; but Muhammad Safi, who appears to have been a man of great ability, at once imprisoned the prince's partisans in Ahmedābād, and, among others, captured the eunuch of Abdullāh Khān. When this news reached the prince at Māndu, he sent Abdullāh Khān Bahādur with an army to Gujarāt by way of Baroda. Muhammad Safi Khān met and defeated him, and forced him to fly and rejoin the prince at Māndu. For his gallant conduct Muhammad Safi received the title of Saif Khān, with an increase in his monthly pay from £70 to £300 (Rs. 700 - 3000) and the command of 3000 horse. Meanwhile Sultān Dāwar Baksh, with the Khān-i-Azam, arrived and assumed the charge of the government, but the Khān-i-Azam died soon after in A.D. 1624, and was buried at Sarkhej. Sultān Dāwar Baksh was

<sup>1</sup> The peaked masonry tomb over Aurangzib's after-birth with its mosque, enclosure, and intact endowment is one of the curiosities of Dohad. In a letter to his eldest son Muhammad Mubazzam then (A.D. 1704) viceroy of Gujarāt the aged Aurangzib writes: My son of exalted rank, the town of Dohad, one of the dependencies of Gujarāt, is the birth-place of this sinner. Please to consider a regard for the inhabitants of that town incumbent on you, and continue in office its decrepid old Faujdār. In regard to that old man listen not to the whisperings of those suffering from the disease of self-interest. "Verily they have a sickness in their hearts and Allah addeth to their ailments" (Letters of the Emperor Aurangzib: Persian Text, Cawnpur Edition, Letter 31.)

re-called, and Khán Jehán was appointed deputy viceroy with Yúsuf Khán as his minister. On his arrival at Ahmedábád, prince Sháh Jehán employed Khán Jehán in his own service, and sent him as his ambassador to the emperor. Saif Khán, who acted for him, may be called the seventeenth viceroy, as indeed he had been the governing spirit for the last eight or ten years. He held the post of viceroy of Gujarát until the death of the emperor in A.D. 1627.

On the death of the emperor Jehángir, his son Abul Muzaffar Shaháb-ud-dín Sháh Jehán ascended the throne. Remembering Saif Khán's hostility he at once caused him to be imprisoned, and appointed Sher Khán Túar eighteenth viceroy with Khwájah Hayát as his minister. When the emperor was near Surat, he appointed Mír Shamsuddín to be governor of Surat castle. In A.D. 1627, Sháh Jehán on his way to Delhi visited Ahmedábád and encamped outside of the city near the Kánkariya lake. Sher Khán was advanced to the command of 5000 men, and received an increase of salary and other gifts. At the same time Khán Jehán was appointed his minister, and Mírza Isa Tar-khán was made viceroy of Thatta in Sindh. In A.D. 1628 Khwájah Abul Hasan was sent to conquer the country of Násik and Sangamner which is ravaged, and returned after taking the fort of Chándod and levying tribute from the chief of Báglán. In A.D. 1630, Jamal Khán Karáwal came to the Gujarát-Khándesh frontier and captured 130 elephants in the Sultánpur forests, seven of which valued at a lách of rupees were sent to Delhi. In A.D. 1631-32 Gujarát was wasted by the famine known as the *Satiásia Kál* or '87 famine. So severe was the scarcity that according to the Bádsháh Náma, rank sold for a cake, life was offered for a loaf, the flesh of a son was preferred to his love. The emperor opened soup kitchens and alms-houses at Surat and Ahmedábád and ordered Rs. 5000 to be distributed.<sup>1</sup>

Sher Khán was re-called in A.D. 1632, but died ere he could be relieved by Islám Khán, the nineteenth viceroy of Gujarát, along with whom Khwájah Jehán was chosen minister. Islám Khán's monthly salary was £100 (Rs. 1000), and his command was raised from 5000 to 6000. In A.D. 1632, Khwájah Jehán went on pilgrimage to Makkah, and was succeeded as minister by Agha Afzal with the title of Afzal Khán. Afzal Khan was soon appointed commander of Baroda, and Riáyat Khán succeeded him as minister. The post of viceroy of Gujarát appears to have been granted to whichever of the nobles of the court was in a position to make the most valuable presents to the emperor. Government became lax, the Kolis of the Kánkrej committed excesses, and the Jám of Navánagar withheld his tribute. At this time Bákar Khán presented the emperor with golden and jewelled ornaments to the value of Rs. 2,00,000 and was appointed viceroy, Riáyat Khán being continued as minister. In A.D. 1633 Sipáhdar Khán was appointed viceroy, and presented the emperor with costly embroidered velvet tents with golden posts worthy to hold the famous *Takhli-Túús* or Peacock Throne which was just completed at a cost of one *kror* of rupees. Riáyat Khán was continued as minister.

## Chapter III.

Mughal  
Viceroys.

SAIF KHÁN  
Seventeenth  
Viceroy,  
1621-1627.

Shah Jehan  
Emperor,  
1627-1658.  
SHER KHÁN TÚAR  
Eighteenth  
Viceroy,  
1627-1632.

Famine,  
1631-32.

ISLÁM KHÁN  
Nineteenth  
Viceroy,  
1632.

Disorder,  
1632.

BÁKAR KHÁN  
Twentieth  
Viceroy,  
1632.

SIPÁHDAR  
KHÁN  
Twenty-first  
Viceroy,  
1633.

<sup>1</sup> Elliot, VII. 24.

## Chapter III.

Mughal  
Viceroys.

Shah Jehan  
Emperor,  
1627-1658.  
SAIF KHAN  
Twenty-second  
Viceroy,  
1633-1635.

AZAM KHAN  
Twenty-third  
Viceroy,  
1635-1642.

Punishes the  
Kolis,

Subdues  
the Kathis.

In A.D. 1635 Saif Khán was appointed twenty-second viceroy, with Riáyat Khán as minister. During Saif Khán's tenure of power Mírza Ísa Tarkhán received a grant<sup>1</sup> of the province of Sorath, which had fallen waste through the laxity of its governors. Before he had been in power for more than a year Saif Khán was recalled. As he was preparing to start, he died at Ahmedábád and was buried in Sháhi Akám's shrine to which he had added the dome over the tomb and the mosque to the north of the enclosure.

At the end of A.D. 1635 Azam Khán was appointed twenty-third viceroy, with Riáyat Khán in the first instance, and afterwards with Mír Muhammad Sábir, as minister. The men who had recently been allowed to act as viceroys had shown themselves unfit to keep in order the rebellious chiefs and predatory tribes of Gujarat. For this reason the emperor's choice fell upon Azam Khán, a man of ability, who perceived the danger of the existing state of affairs, and saw that to restore the province to order, firm, even severe, measures were required. When Azam Khán reached Sindhpur, the merchants complained bitterly of the outrages of one Kanji, a Chínvalia Koli, who had been especially daring in plundering merchandise and committing highway robberies. Azam Khán, anxious to start with a show of vigour, before proceeding to Ahmedábád, marched against Kanji, who fled to the village of Bhádar in the Kherah district of Kadi, sixty miles north-east of Ahmedábád. Azam Khán pursued him so hotly that Kanji surrendered, handed over his plunder, and gave security not only that he would not again commit robberies, but that he would pay an annual tribute of £1000 (Rs. 10,000). Azam Khán then built two fortified posts in the Koli country, naming one Azamábád after himself, and the other Khalilábád after his son. He next marched to Káthiáváda<sup>2</sup> and subdued the Káthis, who were continually ravaging the country near Dhandhúka, and to check them erected a fortified post called Sháhpúr, on the opposite side of the river to Chuda-Ránpur. Agha Fázil known as Fázil Khán, who had at one time held the post of minister, and had, in A.D. 1636, been appointed governor of Baroda, was now selected to command the special cavalry composing the bodyguard of prince Muhammad Anrangzib. At the same time Sayad Ilahdíad was appointed governor of Surat fort, Ísa Tarkhán remaining at Júnágadh. In A.D. 1637, Mír Muhammad Sábir was chosen minister in place of Riáyat Khán, and in A.D. 1638 Muíz-zul-Mulk was re-appointed to the command of Surat fort. Shortly after Azam Khán's daughter was sent to Delhi, and espoused to the emperor's son Muhammad Shujá Bahádur. In A.D. 1639, Azam Khán, who for his love of building was known as Udhai or the Whiteant, devoted his attention to establishing fortified posts to check rebellion and robbery in the country of the Kolis and the Káthis. So complete were his arrangements that people could travel safely all over Jháláváda,

<sup>1</sup> The words used in the text is *tuyál*. In meaning it does not differ from *jágír*.

<sup>2</sup> This is one of the first mentions in history of peninsular Gujarat as Káthiáváda, or as anything other than Sorath or Fauráshtra. The district referred to was probably united to the eastern possessions of the Kháchar Káthis and Panchál.

Kāthiavāda, Navānagar, and Kāchh. The Jām, who of late years had been accustomed to do much as he pleased, resented these arrangements, and in A.D. 1640 withheld his tribute, and set up a mint to coin *loris*.<sup>1</sup> When Azam Khān heard of this, he marched with an army against Navānagar, and, on arriving about three miles from the city, he sent the Jām a peremptory order to pay the arrears of tribute and to close his mint, ordering him, if any disturbance occurred in that part of the country, at once to send his son to the viceroy to learn his will. He further ordered the Jām to dismiss to their own countries all refugees from other parts of Gujarāt. The Jām being unable to cope with Azam Khān, acceded to these terms, and Azam Khān, receiving the arrears of tribute, returned to Ahmedābād. As Azam Khān's stern and somewhat rough rule made him unpopular, Sayad Jalāl Bukhārī whose estates were being deserted from fear of him brought the matter to the emperor's notice.

In consequence in A.D. 1642 the emperor recalled Azam Khān and appointed in his place Mīrza Īsa Tarkhan, then governor of Sorath, twenty-fourth viceroy of Gujarāt. And as it was feared that in anger at being re-called Azam Khān might oppress some of those who had complained against him, this order was written by the emperor with his own hand. Thanks to Azam Khān's firm rule, the new viceroy found the province in good order, and was able to devote his attention to financial reforms, among them the introduction of the share, *shāyqatān*, system of levying land revenue in kind. When Mīrza Īsa Tarkhān was raised to be viceroy of Gujarāt, he appointed his son Inayat-ullāh to be governor of Jūnāgadh, and Muiz-zul-Mulk to fill the post of minister. During the viceroyalty of Mīrza Īsa Sayad Jalāl Bukhārī a descendant of Saint Shāhī Ahmī was appointed to the high post of Sadr-us-Sudūr or chief law officer for the whole of India. This was a time of prosperity especially in Surat, whose port dues which were settled on the Pādshah Begam had risen from two and a half to five lakhs. Mīrza Īsa Tarkhan's term of power was brief. In A.D. 1644 the emperor appointed prince Muḥammad Aurangzib to the charge of Gujarāt, Muiz-zul-Mulk being ordered by the emperor to continue to act as his minister. An event of interest in the next year (A.D. 1645) is the capture of seventy-three elephants in the forests of Dohad and Chāmpāner.<sup>2</sup>

## Chapter III.

Mughal  
Viceroys.

Shah Jehan  
Emperor,  
1627-1658

Azam Khān  
Twenty-third  
Viceroy,  
1635-1642.

Revolt of  
the Jām of  
Navānagar,  
1640.

Īsa Tarkhān  
Twenty-fourth  
Viceroy,  
1642-1644.

<sup>1</sup> The author of the Mirāt-i-Ahmedi says that in his time, A.D. 1746-1762, these Navānagar *loris* were current even in Ahmedābād, two *loris* and two-thirds being equal to one imperial rupee. They were also called *plims*. The Mirāt-i-Ahmedi (Persian Text, 225) calls them *mahmūdis*. The legend on the reverse was the name of the Gujarāt Sultan Muẓaffar and on the obverse in Gujarāt the name of the Jām. Usually two *mahmūdis* and sometimes three went to the imperial rupee. The author says that in Ahmedābād up to his day (A.D. 1756) the account for *gha* clarified butter was made in *mahmūdis*. When the order for melting the *mahmūdis* was passed a mint was established at Jūnāgadh but was afterwards closed to suit the merchants from Diu and other parts who transmitted their specie to Ahmedābād.

<sup>2</sup> The traveller Mandelslo, who was in Ahmedābād in 1638, says: "No prince in Europe has so fine a court as the governor of Gujarāt. Of none are the public appearances so magnificent. He never goes out without a great number of gentlemen and guards on foot and horse. Before him march many elephants with housings of brocade and velvet, standards, drums, trumpets, and cymbals. In his palace he is served like a king and suffers no one to appear before him unless he has asked an audience." (Travels, French

Chapter III.

Mughal  
Viceroys.

Shah Jehar  
Emperor,  
1627-1658.

Prince  
Muhammad  
Arangzib  
Twenty fifth  
Viceroy,  
1644-1646.

Shah-Tan  
Khan  
Twenty-sixth  
Viceroy,  
1646-1648

Prince  
Muhammad  
Dara Shikoh  
Twenty-seventh  
Viceroy,  
1648-1652

Prince Aurangzib's rule in Gujarat was marked by religious disputes. In 1641 a quarrel between Hindus and Muslims ended in the prince ordering a newly built (1638) temple of Chintaman near Saraspur, a suburb of Ahmedabad, above a mile and a half east of the city, to be desecrated by slaughtering a cow in it. He then turned the building into a mosque, but the emperor ordered its restoration to the Hindus. In another case both of the contending parties were Muslims, the orthodox believers, aided by the military under the prince's orders, who was enraged at Sayad Rāju one of his followers joining the heretics, attacking and slaughtering the representatives of the Mahdawijehi sect in Ahmedabad. Sayad Rāju's spirit, under the name of Rāju Shahid or Rāju the martyr, is still worshipped as a disease-scaring guardian by the Pinjāris and Mansūris and Dūdhwālas of Ahmedabad.<sup>1</sup> In consequence of the part he had taken in promoting these disturbances, prince Aurangzib was relieved and Shāistah Khān appointed twenty-sixth viceroy of Gujarat. In the following year Muazzul-Mulk, who had till then acted as minister, was recalled, and his place supplied by Hāfiz Muhammad Nāsir. At the same time the governorship of Surat and Cambay was given to Ali Akbar of Isfahan. This Ali Akbar was a Persian horse merchant who brought to Agra several horses of pure Arabian breed. For six of these Shāhī Jehān paid Rs. 2000. The seventh a bay so pleased the emperor that he paid Rs. 15,000 for it, named it the Princess Ruby, and considered it the gem of the imperial stud. In A.D. 1646 Ali Akbar was assassinated by a Hindu and Muazzul-Mulk succeeded him as governor of Surat and Cambay. As Shāistah Khān failed to control the Gujarat Kols, in A.D. 1648 prince Muhammad Dara Shikoh was chosen viceroy, with Ghairat Khān as his deputy and Hāfiz Muhammad Nāsir as minister, while Shāistah Khān was sent to Malwa to relieve Shah Nawāz Khān. While Dara Shikoh was viceroy an ambassador landed at Surat from the court of the Turkish Sultan Muhammad IV (A.D. 1648-1687).<sup>2</sup> In A.D. 1651, Mir Yahyā was appointed minister in place of Hāfiz Muhammad Nāsir, and in A.D. 1652 prince Dara was sent to Kandahar. On

Edition, 151.) Of the general system of government he says. The viceroy is absolute. It is true he summons leading lords of the country to deliberate on judgments and important matters. But they are called to ascertain their views not to adopt them. On the one hand the king often changes his governors that they may not grow over-powerful. On the other hand the governors knowing they may be recalled at any time take immense sums from the rich merchants especially from the merchants of Ahmedabad against whom false charges are brought with the view of forcing them to pay. As the governor is both civil and criminal judge if the merchants did not temper his grief they would be ruined beyond remedy. (Ditto, 151.) The frequent changes of viceroys in Gujarat is explained by Terry, 1615-17 (Voyage to East Indies, 361): To prevent them from becoming popular the king usually removes his viceroys after one year sending them to a new government remote from the old one. Terry adds a curious note. When the king sends any one to a place of government they never cut their hair till they return into his presence as if they desired not to appear beautiful except in the king's sight. As soon as he sees them the king bids them cut their hair (Ditto, 365). It does not seem to have been cheating to keep up fewer horse than the number named. Terry (Voyage to East Indies, 391) says. He who hath the pay of five or six thousand must always have one thousand or more in readiness according to the king's need of them, and so in proportion all the rest.

<sup>1</sup> Mirat-i-Ahmed Persian Text, II. 16-47. Pinjāris are cotton weavers, Mansūris are Pinjāris who worship Mansūr a tenth century (3rd century Hijrah) saint.

<sup>2</sup> Mirat-i-Ahmed Persian Text, 287;

the transfer of the prince Shāistah Khān became viceroy for the second time, with Mīr Yahyā as minister and Sulṭān Yār governor of Baroda with the title of Himmāt Khān. Mīrza Isā Tarkhāt was summoned to court from his charge of Sorath and his son Muḥammad Sāhib was appointed his successor. In A.D. 1653 an ill-advised imperial order reducing the pay of the troopers, as well as of the better class of horsemen who brought with them a certain number of followers, created much discontent. During this year several changes of governors were made. Muḥammad Nāsir was sent to Surat, Himmāt Khān to Dholka, the governor of Dholka to Baroda, Kutr-ud-dīn to Jūnāgadh, Sayad Shekhan son-in-law of Sayad Diler Khān to Tharad under Pātān, and Jagmal, the holder of Sūmand, to Dholka. In the same year Shāistah Khān made an expedition against the Chuvālīa Kolis, who, since Azam Khān's time (A.D. 1612), had been ravaging Viramgām, Dholka, and Kadi, and raiding even as far as the villages round Ahmedābād.

In spite of Shāistah Khān's success in restoring order the emperor in A.D. 1654 appointed in his place prince Muḥammad Murād Bakhsh twenty-ninth viceroy of Gujārat. Dīnāt Khān, and immediately after him Rehmāt Khān, was appointed minister in place of Mīr Yahyā. Muḥammad Khān Jhalori relieved Mīr Shams-ud-dīn as governor of Pātān and Godhra was entrusted to Sayad Hasam, son of Sayad Diler Khān, and its revenues assigned to him. When prince Murād Bakhsh reached Jhabua on his way to Ahmedābād, the chief presented him with 1500 (Rs. 15,000) as tribute; and when he reached Ahmedābād, Kānji, the notorious leader of the Chuvālīa Kolis, surrendered through Sayad Shekhan, and promised to remain quiet and pay a yearly tribute of 1000 (Rs. 10,000). Dildost, son of Sarfaraz Khān, was appointed to the charge of the post of Bijāpur under Pātān; while Sayad Shekhan was made governor of Sadra and Pīplad, and Sayad Ali paymaster, with the title of Radawī Khān. Many other changes were made at the same time, the prince receiving a grant of the district of Jūnāgadh. One Pirjī, a Bohora, said to have been one of the richest merchants of Surat, is noted as sending the emperor four Arab horses and prince Murād as presenting the emperor with eighteen of the famous Gujārat hulloks. During the vicerealty of Darā Shukoh sums of Rs. 1,00,000 to Rs. 2,00,000 used to be spent on articles in demand in Arabia. The articles were sent under some trustworthy officer and the proceeds applied to charitable purposes in the sacred cities.

At the end of A.D. 1657, on the receipt of news that Shāh Jehān was dangerously ill prince Murād Bakhsh proclaimed himself emperor by the title of Murawwaj-ud-dīn and ordered the reading of the Friday sermon and the striking of coin in his own name.<sup>1</sup> His next step was to put to death the minister Ali Nāki, and direct his men to seize the fort of Sumt then held by his sister the Begam Sāhibah and to take possession of the property of the Begam. He imprisoned Abdul-Ḥatīf, son of Islām Khān, an old servant of the empire. Darā Shukoh representing Murād's conduct to the emperor obtained an order to

## Chapter III.

## Mughal Viceroys.

Shah Jehan  
Emperor,  
1627-1658.  
Suḥrasrah  
Kutān  
Twenty-ninth  
Viceroy,  
1652-1654.

PRINCE MURAD  
Bakhsh  
Twenty-ninth  
Viceroy,  
1654-1657

Murād proclaims  
himself Emperor,  
1657

<sup>1</sup> Jhabua, now under the Bhopāwar Agency.

<sup>2</sup> Mirāt-i Ahmedi, Persian Text, 249.

## Chapter III.

Mughal  
Viceroys.Shah Jehan  
Emperor.

1627-1658.

KASIM KHAN  
Thirtieth  
Viceroy.

1657-1659

Victory of  
Maul and  
Ahmedabad.

transfer him to the governorship of the Berárs. Murád Bakhlsh borrowing £55,000 (5½ *lákhs* of rupees) from the sons of Santidás Jamhári, £4000 (Rs. 40,000) from Ravidás partner of Santidás, and £8800 (Rs. 88,000) from Sámual and others, raised an army and arranged to meet his brother prince Aurangzib, and with him march against the Mahārāja Jasvatsingh of Jodhpur and Kásum Khán, whom Sháh Jehán had appointed viceroys of Malwa and Gujarat, and had ordered to meet at Ujjain and march against the princes. Murád Bakhlsh and Aurangzib, uniting their forces early in A.D. 1658, fought an obstinate battle with Jasvantsingh, in which they were victorious, and entered Ujjain in triumph. From Ujjain prince Murád Bakhlsh wrote Muatazzil Khán his eunuch an order allotting to Mankchand £15,000 (Rs. 1,50,000) from the revenues of Surat, £10,000 (Rs. 1,00,000) from Cambay, £10,000 (Rs. 1,00,000) from Pithlād, £7500 (Rs. 75,000) from Dholka, £5000 (Rs. 50,000) from Broach, £1500 (Rs. 15,000) from Viramgám, and £3000 (Rs. 30,000) from the salt works, in all £55,000 (5½ *lákhs* of rupees). Further sums of £1000 (Rs. 10,000) are mentioned as due to Ravidás partner of Santidás, and £8800 (Rs. 88,000) to Sámual and others. From Ujjain the princes advanced on Agra. At Dholpur they fought a still more obstinate battle with the imperial forces commanded by prince Dara Shikoh and after a long and doubtful contest were victorious. Prince Dara Shikoh fled to Delhi, and the princes advanced and took possession of Agra. After confining his father, Aurangzib marched for Mathura, and having no further use of Muád, he there seized and imprisoned him. From Mathura, Aurangzib went to Delhi from which Dara Shikoh had meanwhile retired to Lahor.

Aurangzib  
seizes Muád  
1658.Aurangzib  
Emperor  
1658-1707.  
SHAH NAWAZ  
KHAN SALAVI  
Thirty-first  
Viceroy.  
1659.Prince Dara  
Rebels.Is Defeated,  
1659.JASVANTSINGH,  
Thirty-second  
Viceroy,  
1659-1662.

In A.D. 1653, while his father was still alive, Aurangzib assumed the imperial titles and ascended the throne. In A.D. 1659 he appointed Sháh Nawáz Khán Salavi thirty-first viceroy of Gujarat, with Rahmat Khán as minister. On this occasion Santidás received a decree directing that the provincial officials should settle his accounts and Kutb-ud-din Kheshgi was appointed to Sorath. Sháh Nawaz Khán was the father-in-law of both Aurangzib and Muád Bakhlsh. Shortly after his appointment, while Murád's wife was paying a visit to her father, prince Dara Shikoh leaving Kachh, where he had been hospitably received by the Ráj, made a sudden descent on Gujarat. The viceroy, won over by the entreaties of his daughter who saw in the success of Dara a hope of release for her husband, joined the prince who entered Ahmedábád. After raising funds from Surat and Ahmedábád he collected an army of 22,000 horse and appointing Sayad Ahmed deputy viceroy, marched towards Ajmir, once more to try his chance of empire. He was defeated and fled to Ahmedábád, where Sardár Khán, who had confined Sayad Ahmed, closed the gates of the city in his face. The unhappy prince retired to Kachh, but finding no support fled to Sindh, where he was treacherously seized and handed to his brother by the chief of Jún. The emperor Aurangzib, forgiving Jasvantsingh his opposition at Ujjain, conferred on him the government of Gujarat, and in the place of Rahmat Khán appointed Makramat Khán to act as minister. Sardár

Khán was thanked for his loyal conduct and made governor of Broach. Praise was also given to Sher and Abid of the Bábi family. Presents were bestowed on Kutb-ud-din, governor of Sorath, and, shortly after, for his refusal to help prince Dára, Tamáchi chief of Kachh was rewarded. These measures removed all signs of disaffection at the accession of Aurangzib. A decree was issued directing Rahmat Khan the minister to forbid the cultivation of the bliang plant *Mohlasib* or censors were appointed to prevent the drinking of wine or the use of intoxicating drugs and preparations. On the formal installation of Aurangzib in A.D. 1658-59 the Ahmedabad Kázi was ordered to read the sermon in his name. The Kazi objected that Sháh Jehán was alive. Shekh Abdul Wahhab, a Shon Bohora of Pattan, whom on account of his learning and intelligence Aurangzib had made Kazi of his camp, contended that the weakness and age of Sháh Jehán made a success necessary. The Bohora prevailed and the sermon was read in Aurangzib's name.

In A.D. 1662 Jasyamsingh received orders to march to the Dakhan and join prince Muázam against Shiváji the Maratha leader, and Kutb-ud-din, governor of Sorath, was directed to act for him in his absence. In this year Mahábat Khan was appointed thirty-third viceroy of Gujarat, and Sardá Khan, the governor of Broach, was sent to Idar to suppress disturbances. About A.D. 1664 Ramnath or Satarsaji Jámól Nayanagar, being by a Ráthod mother a child named Lakha whom the late chief's brother Rásminghji with the aid of the Ray of Kachh and other Jolejis, set aside and himself mounted the throne. Mahk Ísa a servant of the family, took Lakha to Ahmedabad and invoked the aid of the viceroy. Kutb-ud-din marching on Navánagar, defeated and slew Rásmingh, took possession of Navanagar, and annexed the territory, changing the name of the city into Islamnagar. Rásmingh's son, Tamáchi then an infant, escaped and was sheltered in Kachh. In the same year (A.D. 1664) a Bábi personating Dára Shukoh, was joined by many Kóis and disturbed the peace of the Chinvál, now a portion of the Ahmedabad collectorate north of Virangam. With the aid of Sherkhan Bábi, Mahábat Khan quelled these disturbances, and established two new military posts, one at Gájna under Cantabay and one at Belpár under Petlád.

In this year an imperial decree was received requiring the discontinuance of the following abuses: The charging of blackmail by executive subordinates; A tax on private individuals on their cutting their own trees; Forced purchases by state servants; The levy by local officers of a tax on persons starting certain crafts; The levy of a tax on laden carts and on cattle for sale. The closing of Hindu shops on the Jain *Pachusan* and at the monthly eleventh or *Ekadasi*; Forced labour; The exclusive purchase of new grain by revenue officers; The exclusive sale by officers of the vegetables and other produce of their gardens; A tax on the slaughtering of cattle in addition to that on their sale; Payments to the Ahmednagar Kóis to prevent Musalmáns praying in the Ahmednagar mosque; The re-opening of certain Hindu temples; The aggressive conduct and obscenity practised during the Holi and Diváli holidays; The sale by Hindus of toy horses and elephants

## Chapter III.

Mughal  
Viceroys.

Aurangzib  
Reign,  
1658-1707  
JASYAMSINGH  
Thirty-third  
Viceroy,  
1659-1662

Jasyamsingh  
at Idar  
-by op,  
1662.

MAHÁBAT  
KHAN  
Thirty-third  
Viceroy,  
1662-1668.

Capture of  
Navanagar  
(Islamnagar),  
1664. •

## Chapter III

Mughal  
Viceroys.Aurangzib  
Emperor,  
1658-1707.Mughal  
KingsThirty-third  
Viceroy.

1662-1668.

Shivaji Plundered

Surat,

1664.

Copper Coins  
Introduced,  
1665.Khan Jahan  
Thirty-fourth  
Viceroy,  
1665-1671.

during Musalmán holidays; The exclusive sale of rice by certain rich Banias; The exclusive purchase by Imperial officers of roses for the manufacture of rosewater; The mixed gatherings of men and women at Musalmán shrines; The setting up of *nezas* or holy hands and the sitting of harlots on roadsides or in markets; The charging by revenue officers of security rates; The special tax in Parānti, Modasa, Vadnagar, Bisnagar, and Harsol on Musalmán owners of mango trees; The levy of duty both at Surat and Ahmedabad from English and Dutch merchants.<sup>1</sup>

In the same year (A.D. 1664) Shivaji made a rapid descent on Surat, then undefended by walls, and, by plundering the city, created great alarm over the whole province. The viceroy Mahabat Khan marched to Surat with the following chiefs and officers: Jagmū, proprietor of Savand; the governor of Dholka; Shadmal, chief of Idar; Sayyid Hasan Khan, governor of Idar; Muhammad Abd with 200 superior landholders of the district of Kadi; the Raja of Dimgapur; Sahas Singh Raja of Wadhwan and other chiefs of Jhalavadh; Lal Khan chief of Mandva in the Gekwar's dominions near Atarsundia; the chief of Elol under Ahmednagar in the Mahi Kantha Agency; Prithmaj of Haldaryas; and the chief of Belpur. Before the viceroy's army arrived at Surat Shivaji had carried off his plunder to his head-quarters at Raygad.<sup>2</sup> After remaining three months at Surat levying tribute from the superior landholders, the viceroy returned to Ahmedabad, and Inayat Khan, the revenue collector of Surat, built a wall round the town for its protection. About this time Kutub-din Khan, governor of Sorath, was sent with an army to aid the Maharaja Jasvantsingh in the Dakhan and Sarikar Khan was appointed in his place. In A.D. 1666 the Marāthas again attacked and plundered Surat, and in the same year the deposed emperor Shah Jehan died. Aurangzib attempted to induce the English to supply him with European artillerymen and engineers. The request was evaded. In this year the viceroy, Mahabat Khan, in place of the old iron coins, introduced a copper coinage into Gujarat. Sardar Khan, the governor of Junagadh, was put in charge of Islamnagar (Navanagar) and 500 additional horsemen were placed under him. Special checks by branding and inspection were introduced to prevent nobles and others keeping less than their proper contingent of horse. In the same year the cultivator who paid the rent was acknowledged to be the owner of the land and a system of strengtheners or *lokhar* after due security was introduced.

In A.D. 1668, Bahadur Khan Khan Jehan, who had formerly been viceroy of Allahabad, was appointed viceroy of Gujarat, with Hajji Shahi Khan, and afterwards Khwajah Muhammad Hashim, as his ministers. Khan Jehan joined his government in A.D. 1669, and in A.D. 1670 Shivaji again plundered Surat. In A.D. 1670 Shivaji made

<sup>1</sup> Mirat-i-Ahmedi, Persian Text, 274, 279.

<sup>2</sup> Raygad (north latitude 18° 14'; east longitude 73° 30'), the name given in A.D. 1662 to Kari, a hill fortress in the Mahāl sub-division of the Kolaba collectorate. Shivaji took the place and made it his capital in A.D. 1662.

an attempt on Janjira,<sup>1</sup> the residence and stronghold of the Sidi or Abyssinian admirals of Bijapur. Sidi Yákút the commander of Janjira applied for aid to the governor of Surat. On his offering to become a vassal of the emperor and place his fleet at the emperor's disposal, Sidi Yákút received the title of Yákút Khán, and a yearly subsidy of £15,000 (Rs. 1,50,000) payable from the port of Surat. About the same time Sayad Diler Khán, who had accompanied Maharaja Jasyantsingh to the Dakhan, was recalled by the viceroy Khán Jehán and appointed governor of Sorath in place of Sardár Khán, who was sent to Idar. Sayad Haddar, in charge of the military post of Haddarabad, about twenty-four miles south of Ahmedabad, reported that he had put down the rebellion but recommended that a small fort should be built. In A.D. 1670 the emperor summoned Diler Khán to discuss Dakhan affairs, and sent him to the seat of war, replacing him in the government of Sorath by Sardár Khán.

In A.D. 1671, Bahadur Khán Khán Jehán was sent as viceroy to the Dakhan. He was relieved by the Maharaja Jasyantsingh, who, as viceroy, received an assignment of the districts of Dhandhuka and Pithor. In A.D. 1673 through the intercession of the viceroy, Jam Tamacha, the son of Rainsingh, on condition of serving the viceroy and of keeping order was restored to Navanagar, and twenty-five villages were granted to certain dependent Jádépí Rápputs. So long as the emperor Aurangzib lived the city of Navanagar (Islamnagar) remained in the hands of a Musalmán noble, the Jam residing at Khambhaha, a town about thirty miles south-west of the head-quarters of the state. In A.D. 1707 on Aurangzib's death, the Jam was allowed to return to Navanagar where he built a strong fort. Similarly so long as Aurangzib lived, the Jam forbore to work the pearl fisheries in the Gulf of Kachh, but afterwards again made use of this source of revenue. Early in 1674 an order issued forbidding the levy from Musalmáns of *rahúdar* or transit dues, of taxes on fish vegetables grass firewood and other forest produce, on Muhammadan artisans, and many other miscellaneous dues. The officer in charge of Morvi, which was then an imperial district, was ordered to strive to increase its population and revenue, and the chief of Porbandar, also an imperial district, on condition of service and of protecting the port was allowed a fourth share of its revenue. Much discontent was caused by enforcing this; and in 1674 confiscating all *wazírah* land, that is all land held on religious tenure by Hindús.

About the close of the year A.D. 1674, Maharaja Jasyantsinghji was relieved and sent to Kabul, and Muhammad Amin Khán Umdat-ul-Mulk, who had just been defeated at Kabul, was appointed thirty-sixth viceroy of Gujarát, receiving an assignment of the districts of Pátan and Viramgam. Among the military posts mentioned in the Mirát-i-Ahmedi is that of Sádra or Sháhdarah the present head-quarters of the Mahi Kantha Agency, also called Islámábád,<sup>2</sup> which was under the

### Chapter III. Mughal Viceroys.

Aurangzib  
Emperor,  
1658-1707.  
Khán Jehán  
Thirty-fourth  
Viceroy,  
1668-1671.

Sidi Yákút the  
Mughal Admiral,  
1670.

Maharaja  
Jasyantsingh  
Thirty-fifth  
Viceroy,  
1671-1674.

Muhammad  
Amin Khán  
Umdat-ul-Mulk  
Thirty-sixth  
Viceroy,  
1674-1683.

<sup>1</sup> Janjira (north latitude 17° 59' to 18° 32') that is *Janjira*, the island, on the western coast, about forty-four miles south of Bombay.

<sup>2</sup> Another post of Islámábád was at Pundra in the *parganah* of Azamábád on the Warak about twenty-one miles east-south-east of Ahmedabad. Azamábád was built

## Chapter III.

Mughal  
Viceroys.

Aurangzib  
Emperor,  
1658-1707.  
Muhammad  
Amin Khan  
Viceroy,  
1674-1685.

Increase  
Power of the  
Baba Family.

command of Sayad Kamil, son of Sayad Kamil. The Babi family were now rising into importance. Muhammad Muzaffar, son of Sher Khan Babi, was governor of Kadi, and Muhammad Mubáriz, another son of Sher Babi, was in charge of one of the posts under Kadi Kamál Khán Jhalakī, who had been removed from the government of Palanpur and replaced by Muhammad Fiteh, was now restored to his former post. About the same time, at the representation of Mulla Hasan Gujarati, twenty-one villages were taken from Bijapur and Kadi and Patan and formed into the separate division of Visalnagar. In A.D. 1676, the fort of Júnagádh was put into repair, and Sheikh Nizám-ud-dín Ahmed, minister of Gujarát, was sent to Malwa, and was succeeded by Mahomed Shauk. The Kankrej Kohs were again rebellious, and Muhammad Amin Khan Umdat-ul-Mulk went against them and remained four months in their country, subduing them and enforcing tribute. In the end of A.D. 1678 the viceroy paid his respects to the emperor at Ajmir. The emperor forbade the flogging of Musalmán officials as contrary to the Muhammadan law and directed that if guilty of any fault they should be imprisoned or degraded from office, but not fined. An order was also given to change the name of the new Visalnagar district to Rasahnagar.

Revolt of Idar,  
1679.

At this time (A.D. 1679) the emperor was doing his utmost to crush both the Rana of Udaipur and the Rathods of Marwar. While the emperor was at Chitor, Bhimsing the Rana's youngest son raided into Gujarát plundering Vahnagar Visalnagar and other towns and villages. The chief of Idar, thinking the opportunity favourable for regaining his independence, expelled the Muhammadan garrison from Idar and established himself in his capital. Muhammad Amin Khan sent Muhammad Bahlol Khan Shurwani who with the help of the Kasbatis of Parantij re-took Idar, and the chief pursued by Bahlol Khan fled to the hills, where he died in a cave from want of his usual dose of opium to which he was much addicted. His body was found by a woodcutter who brought the head to Bahlol Khán. The head was recognized by the chief's widow, who from that day put on mourning. Muhammad Bahlol Khan was much praised, and was appointed to the charge of Idar, and at the same time the minister Muhammad Sharif was succeeded by Alulá Latif.<sup>1</sup>

To this time belongs an imperial decree imposing the *jazyah* or head tax on all subjects not professing the Muhammadan faith, and another regulating the levy from Musalmáns of the *zakat* or poor rate.<sup>2</sup> In 1681 a severe famine led to riots in Ahmedábad. As the

by Amin Khan during his viceroyalty (A.D. 1635-1642) and at his request by permission of the emperor Sháh Jahán was erected into a *panchmahal*. For the pay of the garrison twelve villages were attached from the neighbouring *paragánahs* of Bahyal and Kapadvanj.

<sup>1</sup> The *Mirát-i-Ahmadi* (Persian Text, 311), adds that Bahlol's following of *Kasbatis* was so poorly equipped that he had to mount many of them, for whom he could not find horses, on bullocks. The sense of security in the mind of the Idar chief bred by contempt at the sight of this motley crowd was the chief cause of Bahlol's success.

<sup>2</sup> The *zakat* or purification is the tax required by law to be given annually to the poor. It is levied on camels, oxen, buffaloes, sheep, goats, horses, asses, mules, and gold or silver whether in money or ornaments or vessels. The tax is not levied on any

viceroy Muhammad Amín was returning in state from the Id prayers Abu Bakr an Ahmedabád Sheikh instigated the people to throw stones and dust. The viceroy's bodyguard attacked the mob, but owing to the viceroy's forbearance no serious results followed. On hearing of the riot the emperor ordered the city to be put under martial law. The more politic viceroy contented himself by inviting Sheikh Abu Bakr and others to a banquet. After dinner he gave a piece of a poisoned watermelon to Abu Bakr, who died and the riot with him. In A.D. 1683 Muhammad Amín the viceroy died. According to the *Mirát-i-Ahmedi*, Muhammad Amín was one of the best of Gujarát governors. The emperor Aurangzib used to say 'No viceroy of mine keeps order like Amín Khán.'

Amín Khán was succeeded by Mukhtár Khán as thirty-seventh viceroy, Abdul Latíf continuing to hold the office of minister. Fresh orders were passed forbidding import dues on merchandise, fruit, grass, firewood, and similar produce entering Ahmedabad. In 1682 a decree was received ordering pauper prisoners to be provided with rations and dress at the cost of the state. In 1683 the Sabarmati rose so high that the water reached as far as the *Tín Darwázah* or Triple Gateway in the west of Ahmedabad city. In consequence of disturbances in Sorath the viceroy called on the minister to advance funds for an expedition. The minister refused to make advances without special orders from the emperor. On a reference to court the minister was directed to make advances in emergent cases. In A.D. 1684, at the request of the inhabitants of that city Abdúr Rahmán Krom, the governor of Deva Patan, was removed and in his place Muhammad Sayad chose Sardár Khán as governor of Sorath. In the following year on the death of Sardár Khán at Thatha in Sindh, where he had gone as viceroy, he was, in the first instance, succeeded in the government of Sorath by Sayad Muhammad Khán. Not long after Sorath was assigned as a personal estate to the emperor's second son prince Muhammad Azam Sháh Bahádúr and during the prince's absence Sháhwardi Khán was sent to manage its affairs. In A.D. 1684 a famine in Gujarát raised the price of grain in Ahmedabad to such a degree that Sheikh Muhy-ud-dín, the son of the Kázi and regulator of prices, was mobbed.

On the death of the viceroy in 1684 prince Muhammad Azam Sháh was nominated to succeed him with Kartalab Khán, governor of Sorath, as his deputy. Before the prince took charge Kartalab Khán was raised to the post of viceroy, and Muhammad Tahir appointed minister. In addition to his command as viceroy of Gujarát, Kartalab Khán was afterwards placed in charge of Jodhpur. In this rearrangement besides his previous personal estate, the district of Petlád was assigned to prince Muhammad Azam Sháh, and Sher Afghan Khán, son of Sháhwardi Khán, was appointed governor of Sorath. In A.D.

## Chapter III.

Mughal  
Viceroys.

Aurangzib  
Emperor,  
1658-1707.

MUKHTÁR  
KHÁN  
Thirty-seventh  
Viceroy,  
1683-1684.

Famine,  
1684.

SURJAT KHÁN  
(KARTALAB  
KHÁN)  
Thirty-eighth  
Viceroy,  
1684-1703.

one who owns less than a minimum of five camels, thirty oxen, forty-five sheep, five horses, two hundred *dirhems* or twenty *diráms*. The proportion to income is generally one-fortieth; the amount may be paid either in kind or in money. Compare Stanley Lane Poole's *Arabian Society in the Middle Ages*, 14.

## Chapter III.

Mughal  
Viceroys.Aurangzib  
Emperor,  
1658-1707.SHUJAAT KHAN  
(KARTALAB  
KHAN)Thirty-eighth  
Viceroy,  
1684-1703.He Quells a  
Mutiny,  
1689.

1687, Sher Afghan Khán was relieved by Bahlol Shirwání, but in the following year was restored to his command. In A.D. 1689, on the news of the death of its governor Inayat Khán, Kártalab Khán started to settle the affairs of Jodhpur. As soon as he left Ahmedabad, a rumour spread that a new viceroy was coming, and the troops, with whom as well as with the people of Gujarát Kártalab was most popular, grew mutinous. On hearing of this disturbance Kártalab Khán at once returned to Ahmedabad and quelled the mutiny. His firmness so pleased the emperor that he gave him the title of Shujaát Khán, and placed the governor of Jodhpur under his orders. Shujaát Khán now proceeded to Jodhpur, where Dúrgadas Ráthod, who had incited since Akbar to rebellion, and Ajítsingh, the son of Maharája Jasvantsingh, were causing disturbance. Finding that a strong resident governor was required to keep the insurgents in check, Shujaát Khan appointed Kázim Beg Muhammad Amín, a brave and resolute soldier, to be his deputy and returned to Ahmedabad. During this viceroyalty the pay of the leader or *jumadar* of a troop of fifty horse was fixed at £10 (Rs. 100); of a *do-aspath* or two-horse trooper at £6 (Rs. 60); and of an *ek-aspath* or one-horse trooper at £3 (Rs. 30) a month. An imperial order was also issued directing the levy on merchandise to be taken at the place and time of sale instead of the time and place of purchase. As this change caused loss to the revenue the old system was again adopted. In A.D. 1690 the minister Amanat Khán, with the title of Ísmad Khán, was made military governor of Surat, and Sayad Mulsín was chosen minister in his place. To prevent the peons of great officials extorting fees and dues officials were forbidden to entertain peons without payment.

Revolt of Matias  
and Momnas,  
1691.

In the following year (A.D. 1691) an attempt on the part of the emperor to suppress a body of Musalmán sectarians led to a somewhat serious insurrection. Sayad Shahjí was the religious preceptor of the Matias of Khandesh and the Momnas of Gujarát—two classes of converted Hindus closely allied to the Khojas of Kathiaváda, all of them being followers of Sayad Imám-ud-dín an Ismailah missionary who came to Gujarat during the reign of Mahmúd Begada (A.D. 1159-1163). Hearing that his followers paid obeisance to their veiled spiritual guide by kissing his toe, the emperor ordered the guide to be sent to court to be examined before the religious doctors. Afraid of the result of this examination, the Sayad committed suicide and was buried at Karantah nine miles south of Ahmedabad. The loss of their leader so enraged his followers that, collecting from all sides, they marched against Broach, seized the fort, and slew the governor. The insurgents held the fort of Broach against the governor of Baroda who was sent to punish them, and for a time successfully resisted the efforts of his successor Nazar Ali khán. At last, at an unguarded spot, some of the besiegers stole over the city wall and opening the gates admitted their companions. The Momnas were defeated and almost all slain as they sought death either by the sword or by drowning to merit their saint's favour in the next world.

Disturbances in  
Káthiaváda,  
1692;

In A.D. 1692 Shujaát Khán, during his tribute-gathering campaign in Jhalaváda and Sorath, stormed the fort of Than, the head-quarters

of the plundering Káthis and after destroying the fort returned to Ahmedabad. Shujáat Khán was one of the ablest of Gujarát viceroys. He gave so much of his attention to the management of Jodhpur, that he used to spend about six months of every year in Mírwar. He beautified Ahmedabad by building the college and mosque still known by his name near the Lal Gate. In A.D. 1612 two hundred cart-loads of marble were received from the ancient buildings at Pátan and the deputy governor Safdar Khán Babi wrote that if a thousand cart-loads more were required they could be supplied from the same source. At this time the emperor ordered that Sheikh Akram-ud-din, the local tax-collector, should levy the head tax from the Hindus of Palanpur and Jhalor. The viceroy deputed Muhammad Mujahid, son of Kamál Khán Jhalori, governor of Palanpur to help in collecting. As Durgadas Ráthod was again stirring tumults and sedition in Mírwar, the viceroy went to Jodhpur, and by confirming their estates to the chief vassals and landholders and guaranteeing other public measures on condition of service, persuaded them to abandon their alliance with Durgadas against whom he sent his deputy Kazim Beg, who expelled him from Mírwar. After appointing Kunvar Mulhamsingh, governor of Mertha in Mírwar, Shujáat Khán returned to Ahmedabad. In A.D. 1613, at the request of Sher Afghan Khán governor of Sorath, the walls of the fort of Jagat were restored. In this year the viceroy went to Jháliváda to exact tribute. On his return to Ahmedabad Safdar Khán Babi, governor of Pátan, wrote to the viceroy, and at his request the forts of Kambhán and Sámprah were repaired. The viceroy now went to Jodhpur and from that returned to Ahmedabad. A circumstance in connection with a sum of Rs. 7000 spent on the repairs of forts illustrates the close imperial supervision of provincial accounts. The item having come to imperial notice from the provincial disbursement sheets was disallowed as unfair and ordered to be refunded under the rule that such charges were to be met out of their incomes by the local governors and military deputy governors. Imperial officers were also from time to time deputed to collect from the books of the *desá's* statements of provincial disbursements and receipts for periods of ten years that they might render an independent check. In this year the emperor hearing that Ajítsingh and Durgadís were again contemplating rebellion ordered the viceroy to Jodhpur. Muhammad Mahabiz Babi was at the same time appointed deputy governor of Vadnagar, and an order was issued that the revenue of Pátan should be paid to Shujáat Khán instead of as formerly into the imperial treasury. In this year also Safdar Khán Babi, governor of Pátan, was succeeded by Mubáriz Khán Babi. Not long afterwards under imperial orders the viceroy directed Muhammad Mubáriz Babi to destroy the Vadnagar temple of Hateshwar-Mahádev the Nágari Bráhmans' special guardian.

In A.D. 1616, Muhammad Bahlol Shírwáni, governor of Baroda, died, and his place was supplied by Muhammad Beg Khán. During this year the viceroy again went to Jodhpur and remained there for some months. In A.D. 1617 Buláki Beg the mace-bearer arrived from the imperial court to settle disputes connected with the Navánagar succes-

## Chapter III.

Mughal  
Viceroys.

Aurangzib  
Emperor,  
1658-1707.  
SHIRAZ KHÁN  
(KÁRTALAB  
KHÁN)  
Thirty eighth  
Viceroy,  
1654-1703.

Disturbances  
in Marwar.

## Chapter III.

Mughal  
Viceroys.

Aurangzib  
Emperor,  
1658-1707

SHUJĀ'AT KHĀN  
(KĀURĀLAB  
KHAN)

Thirty-eighth  
Viceroy,  
1684-1703.

Durgadas Rathod  
reconquered to  
the Emperor,  
1697.

sion, and to inquire into complaints made by the inhabitants of Sorath. In 1693 an imperial circular was addressed to all officers in charge of districts ordering them to show no respect or consideration for royalty in their efforts to capture or kill the rebel prince Akbar. About the same time Durgādās Rāthod, in whose charge were the son and daughter of prince Akbar, made an application to Shujā'at Khān, proposing a truce, and saying that he wished personally to hand the children to their grandfather. Shujā'at Khān agreed and Durgādās restored Akbar's children to the emperor. Aurangzib finding the children able to repeat the whole Kurān was much pleased with Durgāda, and made peace with him, assigning him as a personal estate the lands of Mertha in Jodhpur, and afterwards adding to this the grant of Dhamdhūka and other districts of Gujarat. In consequence of a failure of crops the price of grain rose so high that the government share of the produce was brought to Ahmedābād and sold in public to the poor and needy. About this time Muhammad Mubārīz Babi was killed by a Koli who shot him with an arrow while he was sacking the village of Sāmprah<sup>1</sup>. Safdar Khān Bābi was appointed deputy governor of Pātan in his stead.

In the same year it was reported to the emperor that the money-changers and capitalists of Ahmedābād in making payments passed money short of weight to poor men and in receiving charged an exchange of two to three *tanuks* the rupee. The Subah and minister were ordered to stop the currency of rupees more than two *sauks* short.<sup>2</sup>

Scarcity,  
1698.

In A.D. 1698, on the death of Ītimād Khān, his son Muhammad Muhsin was made minister, and he was ordered to hand the district of Mertha to Durgidas Rathod. Among other changes Muhammad Mumīn was raised to the command of the fort of Jodhpur and Khwājah Abdul Hamīd was appointed minister. Owing to a second failure of rain 1698 was a year of much scarcity in Mārwar and north Gujarat. The accounts of this year notice a petition addressed to the viceroy by a Sinor Brāhmin, praying that he might not be seized as a carrier or labourer<sup>3</sup>. In connection with some revenue and civil affairs, a difference of opinion arose between Shujā'at Khān and Safdar Khān Bābi, deputy governor of Pātan. Safdar Khān resigned, and, until a successor was appointed, Muhammad Bahlol Shīrwani was directed to administer the Pātan district. In the same year the emperor bestowed the government of Sorath on Muhammad Beg Khān. In A.D. 1699 Durgādās Rāthod obtained from the emperor not only a pardon for Ajitsingh, son of the late Mahārāja Juvantsingh, but procured him

<sup>1</sup> This Sāmprah according to the *Mirāt-i-Ahmedi*, Persian Text, II. 127, was a small police post or *thana* in Pargana Bahyal twenty miles north-east of Ahmedābād. It is now in the Gackwar's territory. Bahyal was under Pātan, so in the text the place is described as under Pātan.

<sup>2</sup> The *saukh* or little black-dotted red seed of the *Abrus precatorius* is called *ghāngchi* in Hindi and cock's-eye, *chashm-i-khurus*, in Persian. As a weight the seed is known as a *rat* 96 going to the *tola*. It is used in weighing precious stones. Blochmann's *Ain-i-Al-harī*, I. 16 note 1 and *Mirāt-i-Ahmedi* Persian Text, 366.

<sup>3</sup> Sinor in Baroda territory on the right bank of the Narbada about thirty miles south of Baroda.

an assignment of lands in, as well as the official charge of, the districts of Jhalor and Sāchor in Marwār. Mujaahid Khan Jhālōrī, who as representing a family of landholders dating as far back as the Gujarāt Sultāns, had held Jhalor and Sāchor, now received in their stead the lands in Palampur and Dīsa which his descendants still hold. In this year also (A.D. 1699) Amanat Khān, governor of Surat, died, and the Marāthās making a raid into the province, Shujaāt Khān sent Nazar Ali Khān to drive them out. About this time an imperial order arrived, addressed to the provincial *dhūān* directing him to purchase 1000 horses for the government at the average rate of £20 (Rs. 200).

In A.D. 1700 on the death of Fīrūz Khān Mewāṭī, deputy governor of Jodhpūr, the viceroy appointed in his place Muḥammad Zāhid from Viāngam.\* Rāja Ajītsingh of Marwar was now ordered to repair to court, and as he delayed, a *mohsal* or speed fine was imposed upon him in agreement with Shujaāt Khān's directions. About this time an order came to Kamal Khān Jhālōrī for the despatch to the emperor of some of the Palampur *chitāḥs* or hunting leopards which are still in demand in other parts of India. In the same year the manager of Dhandhuka on behalf of Durgādās Rathod, asked the viceroy for aid against the Kāthīs, who were plundering that district. The viceroy ordered Muḥammad Beg, governor of Sorath, to march against them. At this time Shujaāt Khān despatched Nazar Ali Khān with a large force to join the imperial camp which was then at Paulda in Kolhāpur. Shujaāt Khān, who had so long and ably filled the office of viceroy in a most critical time, died in A.D. 1703. In his place prince Muḥammad Azam Shāh, who was then at Dhar in Mālwa, was appointed thirty-ninth viceroy of Gujarat, as well as governor of Ajmer and Jodhpur; and until his arrival the minister Khwajah Abdnī Hamid Khān was ordered to administer the province. Owing to the recall of the late governor's troops from many of the posts disorders broke out in the Patan districts and the Kolis plundered the country and made the roads impassable.

On his way from the Dakhan to Ahmedābād, the chief of Jhālwa, a state now under the Bhopawar Agency, paid his respects to the new viceroy and presented him with a tribute of £1600 (Rs. 16,000). Among other arrangements the prince sent to Jodhpur Jāfar Kūh, son of Kazim Beg, as deputy governor, and appointed Durgādās Rathod governor of Pātan. Shortly after, on suspicion of his tampering with the Rathod Rajpūts, an order came from the emperor to summon Durgādās to the prince's court at Ahmedābād, and there confine him or slay him.<sup>1</sup> Safdar Khān Bābi, who, in displeasure with Shujaāt Khān had retired to Mālwa, returned and offered to slay or capture Durgādās, who was accordingly invited to the prince's court at Ahmedābād. Durgādās came and pitched his camp at the village of Bāreja on the Sābarmatī near Ahmedābād. On the day Durgādās was to present himself, the prince, on pretence of a hunt, had ordered the attendance of a strong detachment of the army.

## Chapter III.

Mughal  
Viceroys.

Aurangzib  
Emperor,  
1658-1707.  
SHUJAAT KHAN  
KATHIWAR  
KHAN)  
Thirty-eighth  
Viceroy,  
1691-1703.

PRINCE  
MUHAMMAD  
AZAM  
Thirty-ninth  
Viceroy,  
1703-1706.

Intrigue against  
Durgadas Rathod,  
1703.

<sup>1</sup> Mirāt-i-Ahmedi, Persian Text, 372.

## Chapter III.

Mughal  
Viceroys.Aurangzib  
Emperor,  
1658-1707.PRINCE  
MUHAMMAD  
AAZAM  
Thirty-ninth  
Viceroy,  
1703-1705.Durgadas  
Rathod  
Escapes.

When all was ready and Safdar Khān Babi and his sons appeared mailed and gauntleted the prince sent for Durgadas. As this day was an eleventh or *agādās* Durgadas had put off waiting on the prince until the fast was over. Growing suspicious of the number of messengers from the prince, he burned his bairi and bled. Safdar Khān Babi was sent in pursuit. He was overtaking Durgadas when Durgadas' grandson praying his grandfather to make good his escape, stayed behind with a band of followers, engaged the pursuers, and after a gallant combat, he and his Rājputs were slain. The grandson of Durgadas was killed in a hand-to-hand fight with Salabat Khān, the son of Safdar Khān Babi. Emerald rings are to this day worn by youths of the Babi families of North Gujarāt in memory of the emerald earrings which adorned the young Rājput and were afterwards worn by Salabat as trophies of this fight. Meanwhile Durgadas had reached Unjth-Unāwa, forty miles east of Patan, and from Unjth made his way to Patan. From Patan, taking his family with him, he retired to Tharād, and from that to Marwār, where he was afterwards joined by Ajitsingh of Marwār, whom the emperor opposed on the ground of illegitimacy. The imperial troops followed and took possession of Patan, putting to death the head of the city police.

In his old age the emperor Aurangzib became more and more strict in religious matters. In 1702 an imperial order foiled the making of almanacs as contrary to the Muhammadan law. Hindus were also forbidden to keep Muhammadan servants.

Surat,  
1700-1703.

About this time (A.D. 1700) news arrived that the Marāthīs with a force of 10,000 horse were threatening Surat from the foot of the Kāsira pass and the confines of Sultānpur and Nandurbār. The viceroy despatched a body of troops to guard Surat against their incursions. Disputes between the government and the Portuguese were also injuring the trade of the province. In A.D. 1701 the viceroy received an order from Court directing him to destroy the temple of Somnāth beyond possibility of repair. The despatch adds that a similar order had been issued at the beginning of Aurangzib's reign. In A.D. 1703, at the request of the merchants of Gujarāt, with the view of inducing the Portuguese to let ships from Surat pass unmolested and release some Musalmāns who had been imprisoned on their way back from Makkah, orders were issued that certain confiscated Portuguese merchandise should be restored to its owners. An imperial order was also received to encourage the art of brocade weaving in Ahmedabād. In A.D. 1704, Safdar Khān Babi was raised to be governor of Bijāpur, about fifty miles north-east of Ahmedabād. Sarandāz Khān was at the same time appointed to Sorath instead of Muhammad Beg Khān, who was placed in charge of the lands round Ahmedabād. As the Marāthīs once more threatened Surat, Mustafa Kuli, governor of Broach, was sent with 1000 horse to defend the city.

Certain passages in Aurangzib's letters to prince Aāzam when (A.D. 1703-1705) viceroy of Gujarāt, show how keen and shrewd an interest the aged emperor maintained in the government of his viceroys. In Letter 19 he writes to prince Aāzam: To take the government of Sorath

from Fatch Jang Khán Bābi and give it to your chamberlain's brother is to break a sound glass vessel with your own hands. These Bābis have been time out of mind a respected race in Gujarāt and are well versed in the arts of war. There is no sense in giving the management of Sorath to anyone but to a Bābi. Sorath is a place which commanders of five thousand like Hasan Alikhán and Safshikan Khán have with difficulty administered. If your officers follow the principles laid down by the late Shujaāt Khán, it will be well. If they do not, the province of Gujarat is such that if order is broken in one or two places, it will not soon be restored. For the rest you are your own master. I say not, do this or do that; look that the end is good, and do that which is easiest. In another passage (Letter 37 to the same prince Aázam) Aurangzib writes: You who are a well intentioned man, why do you not retahate on oppressors? Over Hajipur Ammipúr and other posts where atrocities occur every day, and at Kapadvanj where the Kolis rob the highways up to the posts, you have made your chamberlain and artillery superintendent your commandant. He entrusted his powers to his carrion-eating and fraudulent relatives. Owing to his influence the oppressed cannot come to you. . . . You ought to give the command to one of the Gujaratis like Safdar Khan Bada or one of the sons of Bahul Shirwani who have earned reputations during the administration of the late Shujaāt Khán and who are popular with the people. Else I tell you plainly that on the Day of Justice we shall be caught for neglecting to punish the oppressions of our servants.

In A.D. 1705, as the climate of Gujarāt did not agree with prince Aazam, Ibrahim Khán, viceroy of Kashmir, was appointed forthwith viceroy of Gujarāt, and his son Zabardast Khan, viceroy of Lahor, was appointed to the government of Ajmir and Jodhpur. Prince Aazam at once went to Burhanpur in Khándesh, handing charge of Gujarāt to the minister Abdúl Hamíd Khan until the new viceroy should arrive. Durgadas Ráthod now asked for and received pardon. Abdúl Hamíd Khán was ordered to restore the lands formerly granted to Durgadās, and Durgadās was directed to act under Abdúl Hamíd's orders. In A.D. 1705 the emperor learned that Khánji, a successor of Kntb the high priest of the Ismaili Bohorás had sent out twelve missionaries to win people to his faith, and that his followers had subscribed Rs 1,11,000 to relieve those of their number who were imprisoned. The emperor ordered that the twelve missionaries should be seized and sent to him and appointed Sunni Mullás to preach in their villages and bring the Bohorás' children to the Sunni form of faith.

About this time (A.D. 1705) the Marathás, who had long been hovering on the south-east frontiers of the province, hursting into south Gujarāt with an army 15,000 strong, under the leadership of Dhanáji Jadhav, defeated the local forces and laid the country waste. Abdúl Hamíd Khán, who was then in charge of the province, ordered all governors of districts and officers in charge of posts to collect their men and advance to Surat. Between Nazar Ali Khán and Safdar Khán Bābi, the officers in command of this

**Chapter III.****Mughal  
Viceroys.**

**Aurangzib**  
Emperor,  
1658-1707.

PRINCE  
MIRANMAD  
AAZAM  
Forty-fourth  
Viceroy,  
1703-1705.

IBRAHIM KHÁN  
Fortieth Viceroy,  
1705.

The Marathás  
enter Gujarāt.

**Chapter III.****Mughal  
Viceroys.****Aurangzib  
Emperor,  
1658-1707.****IBRAHIM KHÁN  
Fortieth Viceroy,  
1705.****Battle of  
Ratanpúr.  
Defeat of the  
Musalmans,  
1705.****Battle of the  
Baba Pirah  
Ford. Second  
Defeat of the  
Musalmans,  
1705.****Koli  
Disturbances.****PRINCE  
MUHAMMAD  
BIDAR BAKHT  
Forty-first  
Viceroy,  
1705-1706.**

army, an unfortunate jealousy prevailed. Not knowing where the Maráthás were to be found, they halted on the Narbada near the Bába Pirah ford. Here they remained for a month and a half, the leaders contenting themselves with sending out spies to search for the enemy. At last, hearing of the approach of the Maráthás, they sent to head-quarters asking for artillery and other reinforcements. In reply, Abdúl Hamíd Khán, a man of hasty temper, upbraided them for their inactivity and for allowing so much time to pass without making their way to Surat. Orders were accordingly at once issued for an advance, and the army next halted at Ratanpúr in Rájpipla. Here, apparently from the jealousy of the commanders, the different chiefs pitched their camps at some distance from each other. Finding the enemy's forces thus scattered, the Maráthás under the command of Dhanaji Jadhav, lost no time in advancing against them. First attacking the camp of Safdar Khan Bábi, they defeated his troops, killed his son, and took prisoner the chief himself. Only a few of his men, with his nephew Muhammad Aázam, escaped to the camp of Nazar Ali Khán. Next, the Maráthas attacked the army under Muhammad Purdil Khán Shurwán; and it also they defeated. Of the Musalman army those who were not slain, drowned in the Narbada, or captured, reached Broach in miserable plight, where they were relieved by Akbar Ali Khán. Nazar Ali Khan burned his tents and surrendered to the Maráthás, by whom he was well treated.

The Maráthás now heard that Abdúl Hamíd Khán was coming with an army to oppose them. Thinking he would not risk a battle, they went to the Baba Pirah ford, and there crossed the Narbada. That very day Abdúl Hamíd Khán, with Muhammad Sher and Muhammad Salabat, sons of Safdar Khán Bábi, and others came to the spot where the Maráthas were encamped. All night long they were harassed by the Maráthás, and next morning found the enemy ready for a general attack. The Muhammadans, weary with watching, dispirited from the defeats of Safdar Khan and inferior in number to their assailants, were repulsed and surrounded. The two sons of Safdar Khán Bábi, and two other nobles, seeing that the day was lost, cut their way through the enemy and escaped, Abdúl Hamíd Khán, Nazar Ali Khán, and many others were taken prisoners. The Maráthás plundered the Muhammadan camp, declared their right to tribute, levied sinus from the adjacent towns and villages and extorted heavy ransoms which in the case of Abdúl Hamíd Khán was fixed at as large a sum as £30,000 (Rs 3 *lákhs*). The Kols, seeing the disorganized state of Gujarát, began ravaging the country, and plundered Baroda for two days. At Ahmedabád Muhammad Beg Khán, who had been appointed governor of Sorath, was recalled to defend the capital. When the news of the defeat at Bába Pirah reached Dehli, the emperor despatched prince Muhammad Bidar Bakht with a large army to drive out the invaders. Before this force reached Gujarát the Maráthás had retired.

Prince Muhammad Bidar Bakht arrived in A.D. 1705 as forty-first viceroy, and appointed Amánat Khán governor of the ports of Surat and Camláy. News was now received that Ajítsingh of Jodhpur and Verisálji of Rájpipla were about to rebel, and the prince took

measures to check their plans. About this time the emperor, hearing that an attack had been made on the Muhammadan post at Dwárka, ordered the temple to be levelled to the ground. It seems doubtful whether this order was carried out. Nazar Ali Khán, who had formerly enjoyed a grant of Halvad in Jhaláwáda, had been driven out by Chandrasingh, chief of Vínkár; but, on condition of his expelling Chandrasingh, these lands were again granted to him. Kamál Khán Jhalori, leaving under his son Fírúz Khán at Pálanpur a body of men for the defence of his charge, advanced to Ahmedabád to guard the city from Maráthá attack. He petitioned that according to Gujarát custom his troops should receive rations so long as they were employed on imperial service. To this request the emperor agreed and issued orders to the provincial minister. Shortly after Durgádas Ráthod took advantage of the general confusion to rejoin Ajitsingh, and an army was sent to Tharad against them. Ajitsingh was at first forced to retire. Finally he succeeded in defeating Kúnvar Mulkaosingh, and marching on Jodhpur recovered it from Jaafar Kúh, son of Kázim Beg. Durgádas meanwhile had taken shelter with the Kohs. At the head of a band of robbers, meeting Shah Kúh the son of Kázim Beg on his way to join his appointment as deputy governor of Patan, Durgádas attacked and killed him. And soon after at Chamár in the Chhuvál, laying in wait for Maasúm Kúh, the governor of Virangám, he routed his escort, Maasúm Kúh escaping with difficulty. On condition of being appointed governor of Patan Safdar Khán Bábi now offered to kill or capture Durgádas. His offer was accepted, and as from this time Durgádas is no more heard of, it seems probable that Safdar Khán succeeded in killing him. As the disturbed state of the province seemed to require a change of government Ibrahim Khán, who had been appointed viceroy in the previous year, was ordered to join his post. This order he reluctantly obeyed in A.D. 1705.

### SECTION II.—*Fifty Years of Disorder, 1707-1757.*

With the death of the emperor Aurangzib, early in A.D. 1707, the period of strong government which had latterly from year to year been growing weaker came to an end. As soon as Aurangzib's death was known, the Maráthas under Bálájí Vishvánáth burst into east Gujarat, marching by Jálga and Godhra, where they were met effectually opposed by the governor Murad Baksh. From Godhra they went to and plundered the town of Mahmda in Kaira, and proposed marching on Ahmedabád by way of Nadiád. The viceroy prepared to resist them, and, enlisting special troops, camped outside of the city near the Kankariya lake. Of the warlike population on the north bank of the Sabarmati opposite Ahmedabád nearly eight thousand Musalmán horse and three thousand foot together with four thousand Rájputs and Kohs in three days gathered at the Kankariya camp. The viceroy was also joined by Abdúl Hádi Pandemal the viceroy's minister, Abdúl Hamíd Khán provincial minister, Muhammad Beg Khán, Nazar Ali Khán, Safdar Khán Bábi, and several other deputy governors with their retinues and artillery. Though strong in numbers the practised eye of the viceroy failed to find in the host that

### Chapter III.

#### Mughal Viceroys.

Aurangzib  
Emperor  
1658-1707.

PLANCE  
MUHAMMAD  
BEGAR BAKUR  
Forty-first  
Viceroy,  
1705-1706.

Durgádas  
Ráthod again

THE SUFÍ KIRÁN  
Forty-second  
Viceroy,  
1706

The Mughal  
Army  
and heavy troops  
1707.

## Chapter III.

Mughal  
Viceroys.

Bahá'dur  
Shah I.  
Emperor,  
1707-1712.  
IBRÁHÍM KHÁN  
Forty-second  
Viceroy,  
1706.

firmness and unity of purpose which could alone ensure victory over the Maráthas hordes. The Maráthas did much mischief, plundering as far as Batva, only four-and-a-half miles from the viceroy's camp. The author of the *Murát-i-Ahmedi*, whose father was an actor in these scenes, describes the panic in the capital of Gujarát which since its capture by Muzáffar in A.D. 1583 had been free from the horrors of war. Crowds of scared and terror-stricken men women and children laden with as much of their property as they could carry were pressing from the suburbs into the city. In the city the streets were crowded with squatters. The cries of parents bereft of children, added to the din and turmoil of the soldiery, was like the horror of the Day of Resurrection. The dejected faces of the soldiers beaten in the late engagements added to the general gloom. The viceroy, thoroughly alarmed, concluded a treaty with Balap, and on receiving a tribute of £21,000 (Rs. 2,10,000) the Maráthas withdrew. Meanwhile, in the contest between the princes for the throne of Dehli, prince Muhammad Áázam Shah was defeated and slain, and prince Muhammad Muazzam Shah mounted the throne with the title of Bahá'dur Shah. Ibráhm Khán was confirmed in the post of viceroy of Gujarát, but, fearing that the emperor might be displeased at his concession of tribute to the Maráthas, he went to Dehli to explain his conduct, and there resigned office.

GHÁZÍ-UD-DÍN  
Forty-third  
Viceroy,  
1708-1710.

In A.D. 1708, in consequence of Ibráhm Khán's resignation, Gházi-ud-dín Khán Bahá'dur Fírúz Jang was appointed forty-third viceroy of Gujarát. The leaning of the new emperor towards Shiáh tenets and his order to insert in the Friday sermon the words the lawful successor of the Prophet after the name of 'Alí, the fourth Khálfah, besides giving general dissatisfaction, caused a small disturbance in Ahmedábad. On the first Friday on which the sermon was read the Turáni or Purk soldiers publicly called on the preacher to desist on pain of death. The preacher disregarding their threats on the next Friday was pulled down from the pulpit by the Turánis and branded with a mace. In the same year (A.D. 1708), hearing that the representative of Shahi Alam had a copy of a Kurán written by the Imam Ali Fakíson of Musa Razá (A.D. 810-820), the emperor expressed a wish to obtain a sight of it, and the viceroy sent it to him at Mandu in charge of Sayad Akíl and Saláhat Khán Baba. In A.D. 1709, Shariát Khán, brother of Abulul Hamíd Khán, was appointed minister in place of his brother, who obtained the office of chief Kazi. Much treasure was sent to the imperial camp by order of the emperor. Ajítsingh of Marwár now rebelled and recovered Jadhpur. As the emperor wished to visit Ajmír the viceroy of Gujarát was directed to join him with his army. At this time the pay of a horseman is said to have been £3 8s. (Rs. 34) and of a footman 8s. (Rs. 4) a month. During his administration Fírúz Jang introduced the practice, which his successors continued, of levying taxes on grain piece-goods and garden produce on his own account, the viceroy's men by degrees getting into their hands the whole power of collecting. In A.D. 1710, when on tour exacting tribute, the viceroy fell ill at Dánta and was brought to Ahmedábád, where he died. As Fírúz Jang had not submitted

satisfactory accounts, his property was confiscated, and in A.D. 1711 Anwarat Khán, governor of Surat, was appointed deputy viceroy with the title of Shahmat Khán. When Shahmat Khán was levying tribute from the Kadi and Bijapur districts, he heard that a Maratha force had advanced to the Bába Púrah ford on the Nerbada. He at once marched to oppose them, summoning Sayad Ahmed Giláni, governor of Sarath, to his assistance. When he reached Ankleshvar, the Marathas met him, and a battle was fought in which the Marathas were defeated. Shahmat Khán then proceeded to Surat, and, after providing for its safety returned to Ahmedabad. In spite of their reverse at Ankleshvar the Marathas from this time began to make yearly raids into Gujarat.

In A.D. 1712, the emperor died, and was succeeded by his son Abúl Fateh Muizz-ud-din Jehándar Shah, and Asif-ud-daulah Asad Khan Bahadur was appointed forty-fourth viceroy of Gujarat. As Muhammad Beg Khán, who was then at Kharkol, was a favourite of the new viceroy and through his interest was appointed deputy, he went to Ahmedabad, and Shahmat Khán was transferred to Malwa as viceroy. In the meantime Muhammad Beg Khán was appointed governor of Surat, and Sarbuland Khan Bahadur was sent to Ahmedabad as deputy viceroy. On his way to Gujarat, Sarbuland Khan was robbed in the Sagbora wilds to the east of Rajpúra. On his arrival he promptly marched against the rebellious Kolis of the Chumval and subdued them. At the end of the year, as Farrukhsiyar son of Azim-us-Shan, second son of the late emperor, was marching with a large army on the capital, Sarbuland Khan returned to Delhi.

This expedition of Farrukhsiyar was successful. He put Jehándar Shah to death and mounted the throne in A.D. 1713. As he had been raised to the throne mainly by the aid of Sayads Husain Ali and Abdullah Khan, the new emperor fell under the power of these nobles. Husain Ali was sent against Ajitsingh of Marwar, and concluded a treaty with that chief, whereby Ajitsingh engaged to send his son to court and to give his daughter to the emperor in marriage: and the marriage was solemnised in A.D. 1715. In A.D. 1714, shortly after this treaty was concluded, Ajitsingh sent his son Ahleysingh to court, and on him in place of one Sayad Ahmed Gilani was conferred the post of governor of Sarath. Ajitsingh remained at court and sent his deputy with Fatehsingh to Jámagadh. Abdul Hamid Khán was appointed revenue officer of Surat. After some time he resigned his Surat office and went to court, where on being made superintendent of the shrems of Sheikh Ahmed Khattin he returned to Ahmedabad. In A.D. 1713 Muhtarm Khán was appointed to succeed him in Surat. Early in A.D. 1714, Shahmat Khán, who had been appointed forty-fifth viceroy of Gujarat, was superseded by Daud Khan Panni as forty-sixth viceroy. The reckless courage of Dáúd Khán Panni was renowned throughout India. His memory survives in the tales and proverbs of the Dakhan. On giving battle he used to show his contempt for his enemies by wearing nothing stronger than a muslin jerkin. So stern was his discipline that none of his Afghán soldiers dared to touch a leaf of the standing crops where they were encamped. When at

## Chapter III.

Mughal  
Viceroys.

Bahadur  
Shah I  
Emperor,  
1707-1712  
Gujarat-  
Forty-third  
Viceroy,  
1708-1710.

Jehándar  
Shah  
Emperor,  
1712-1713.  
Asif-ud-daulah  
Forty-fourth  
Viceroy,  
1712-13.

Farrukhsiyar  
Emperor,  
1713-1719

Sarbuland  
Khan  
Forty-fifth  
Viceroy,  
1713.

**Chapter III.****Mughal  
Viceroys**

**Farrukhsiyar**  
Emperor,  
1713-1719.

**DAUD KHAN**  
Viceroy,  
1714-15.

**Religious Riots**  
in Ahmedabad,  
1711.

Ahmedabad he was either engaged in scattering the Kolis or in coursing with greyhounds. He preferred life under canvas on the Sābarmati sands to the viceregal surroundings of the Bhadar Palace. His civil work he used to trust to Dakhan Brāhmanas and Paudits. He was much devoted to the use of bhāng. Until Daud Khān's arrival Abdu'l Hamid Khān was appointed viceroy and took charge of the province from Shāhmat Khān. At this time, on the security of Raja Mulikamsingh of Nāgor, a sum of ₹5000 (Rs. 50,000) was granted to the brother of Durgādās Rāthod. In A.D. 1714 in Ahmedabad Harīrām, the agent of Madan Gopal a successful North Indian banker, who came to Ahmedabad as treasurer with Firūz Jang, while celebrating the Holi with his friends, seized a Musalman gentleman and handled him with great roughness. Aggrieved with this treatment the Musalman complained to a preacher of much eloquence and influence, Mulla Muhammad Ali. The preacher took the Muslim to the Assembly Mosque and sent for Mulla Abdūl Āziz the chief or leading member of the Sunni Bohora community. He answered the call with a strong party of his men, and on his way was joined by numbers of Musalmans both soldiers and citizens. With cries of 'Din' 'Din' they went to the mosque and carried off the insulted man and the priest and the Bohra leader to the house of the Kazi Khar-ul-lah. The kazi closed his doors against the crowd who returned abusing him to the Jewellers' quarter pillaging and killing as they went. They next swarmed towards Madan Gopal's Haveli in the Jewellers' quarters. But the Nagarsheth Kapurchand Bhansali closed its strong gates and with his Musalman soldiers met the swarm with firearms. The viceroy who was camped at the Shahi Bagh sent soldiers and under the influence of the leading citizens of both classes the disturbance was quelled. When the particulars of the riots were known in the imperial camp the Hindus, clamouring against Mulla Muhammad Ali and Sheikh Abdūl Āziz Gujarāti, struck business and closed their shops. The emperor ordered mace-bearers to proceed to Gujarat and bring the Musalman ringleaders together with the Hindu Nagarsheth Kapurchand Bhansali. Some Bohoras at the imperial camp, sending advance news to Ahmedabad, the Mulahi and the Bohora Sheth and after him the Bhansali started for the imperial camp. On reaching the camp the Mulla, who was very impressive and eloquent, preached a sermon in the Assembly Mosque and his fame reaching the emperor he was called to court and asked to preach. He and the Sheth were now able to explain their case to the emperor and the Bhansali was imprisoned. It is said that the Bhansali made the Mulla the medium of his release and that he and the Bohora returned to Gujarāt while the Mulla remained in honour at court till he died. About the same time a great flood in the Sābarmati did much damage.

Abdūl Hamid Khān was now chosen governor of Sorath in place of Abheysingh, and Mornin Khān was appointed from Dehli, governor of Surat, and was at the same time placed in charge of Baroda, Broach, Dholka, Petlad, and Nadiād. Daud Khān the viceroy now went into Kāthiavāḍa and Navānagar to collect tribute, and on his return to Ahmedabad, married the daughter of the chief of Halvad in the

**Jhálaváda** sub-division of **Káthiaváda**. It is related that this lady, who was with child, on hearing of Dáud Khán's death cut open her womb and saved the child at the sacrifice of her own life.<sup>1</sup> Dáud Khán, though an excellent soldier and strict disciplinarian failed to distinguish himself as a civil administrator. He introduced *Dakhani pandits* into official posts, who levied a fee called *chithyáman* from landholders and took taxes from the holdings of Sayads and otherwise made themselves unpopular.

About this time Momín Khán, governor of Surat, arrived in Gujaráť; and placing his deputies in Petlád, Dholka, Baroda, and Nachád, went himself to Surat in A. u. 1715. Here he was opposed by the commandant of the fort, Zia Khan, who was obliged to give way, his subordinate, Sayad Kasim, being defeated by Fúlá-ud-dín Khán. At this time much ill-feeling was caused by the plunder by Muhammadan troops of the shops of some Hindu merchants in Ahmedábád. On this account, and for other reasons, Dáud Khán was recalled, and Gházni Khán Jhálori was directed to act in his place until the arrival of a new viceroy. In this year, A. D. 1715, the Mahárája Ajítsingh was appointed forty-seventh viceroy of Gujaráť, and his son Kinyar Abheysingh was appointed governor of Sorath. Ajítsingh sent Vajerij Bhandári to act as his deputy until his arrival, and Fatehsingh Kayath was chosen deputy governor of Sorath. Perhaps one of the most remarkable appointments of this time was that of Haidar Kuli Khán to be minister as well as military commandant of Baroda, Nándod, Arhar-Mátar in the district<sup>2</sup> of Kaira, and of the ports of Surat and Cambay. Haidar Kuli chose an officer to act for him as minister, and after appointing deputies in his different charges himself went to Surat.

The Mahárája Ajítsingh, on reaching Ahmedábád, appointed Gházni Khán Jhálori governor of Pálanpur and Jawán Mard Khán Babi governor of Ráidhanpur.<sup>3</sup> During this year an imperial order conferred on Haidar Kuli Khan, Sorath and Gohilvád or south-east Káthiaváda<sup>4</sup> then in charge of Fatehsingh, the viceroy's deputy. On receiving this order Haidar sent Sayad Akil as his deputy, and that officer went to Jambhiser, and collecting men, set out to join his appointment. He

### Chapter III.

#### Mughal Viceroy.

Farrukhsiyar  
Emperor,  
1713-1719.

DAUD  
KHAN PANSI  
Forty-sixth  
Viceroy,  
1714-15.

Further Notes  
in Ahmedábád,  
1715.

MAHARAJA  
AJITSINGH  
Forty-seventh  
Viceroy,  
1715-16.

<sup>1</sup> Mirát-i-Ahmeli, Persian Text, 427-434.

<sup>2</sup> Arhar-Matar is according to the Mirát-i-Ahmeli (Persian Text, II, 126) the present Kaira, a division of Matz. The Mirát-i-Ahmeli places it twenty miles south-west of Ahmedabad. It is four miles south-west of Kaira.

<sup>3</sup> In the beginning of Ajítsingh's administration the Sacrifice Id of the Musalmáns very nearly ended up a riot. An overzealous police officer belonging to the Káshipur section of Ahmedábád, hoping to please the Hindu viceroy, by force deprived some of the Samu Bohoras of that quarter of a cow which they had purchased for the sacrifice. The Bohoras in a mass appealed to the Kazi who not succeeding in his representation to the viceroy was obliged to allay the popular excitement by publicly sacrificing a cow after the Id prayers. Mirát-i-Ahmeli Royal Asiatic Society MS., I, 567-568.

<sup>4</sup> This is the first known mention of Gohilvád, the Gohils country, as a separate district.

<sup>5</sup> During the governorship of Haidar Kuli at Surat the Mirát-i-Ahmeli (Royal Asiatic Society MS., I, 567-568) notices the death of Mulla Abdul Ghafur the founder of the wealthy family of the Mullás of Surat. Haidar Kuli confiscated Abdul Ghafur's property representing to the emperor that the Mulla died issueless. But the Mulla's son Abdál Hye proceeding to Delhi not only obtained from the emperor an order of restitution of property, but the title of chief of merchants, Umda-tut-Tujjār, and an elephant.

**Chapter III.****Mughal  
Viceroys.****Farrukhsiyar**  
Emperor,  
1713-1719.**MAHARAJA**  
**AJITSINGH**  
Forty-seventh  
Viceroy,  
1715-16**Disagreement**  
between the  
Viceroy and  
Haidar Kuli  
Khan,  
1715.**KHAN DARAUN**  
**NASIR JANG**  
Babdur  
Forty-eighth  
Viceroy,  
1716-1719.**Famine**  
1719.

first camped at Lohánah, where the province of Sorath begins, and from Lohánah marched against Pálitina and plundered the town. The viceroy, who was by no means well disposed to Haidar Kuli Khan, sent a message that if any injury was done in Sorath he would take vengeance on the aggressors; and as neither Ajítsingh nor Haidar Kuli Khan was of a very compliant temper, civil war was on the point of breaking out. By the help of Salabat Khán Babi, the deputy in Godhváda, matters were arranged, and Sayad Akil returned from Sorath. Haidar was anxious to send Salabat Khán as deputy to Sorath. But as Salabat demanded too high a salary, Raza Kuli, brother of the late governor of Baroda, was chosen. When this officer, with his brother Maasum Kuli, reached Ameli Fatchsingh, the viceroy's deputy, evacuated Jámigadh. After this Haidar Kuli Khán, in company with Kázim Beg, governor of Baroda, marched against and defeated the chief of Munjpúr, now under Rádhanpúr, who had refused to pay the usual tribute. The viceroy went to Sorath to collect the imperial revenue, and, owing to his excessive demands, met with armed resistance from the Jam of Navánagar. Finally, the matter of tribute was settled, and after visiting the shrine of Dwárka, the viceroy returned to Ahmedabad.

In A.D. 1716, while the viceroy was at Dwárka, in consequence of numerous complaints against Ajítsingh and his Marwarí followers, the emperor sent Samsum-ud-daulah Khán Daraún Nasir Jang Bahádur as forty-eighth viceroy of Gujarat. As it was expected that Ajítsingh would not give up his government without a contest, an army was prepared to compel him to leave. On the arrival of the army Ajítsingh marched straight on Ahmedabad and encamped at Sarkhej, but Nahar Khán persuaded him to retire to Jallpur without giving battle. In A.D. 1717, after the departure of Ajítsingh Haidar Kuli Khán, who had been appointed deputy viceroy, leaving Surat set out for Ahmedabad. When Haidar arrived at Petlad, some of the Ahmedabad nobles, among whom was Safdar Khán Babi, went out to meet him. A dispute arose between one of Haidar's water carriers and a water-carrier in the army of the Babas, which increased to a serious affray, which from the camp followers spread to the soldiers and officers, and the Babas' baggage was plundered. Safdar Khán took serious offence, and returning to Ahmedabad collected his kinsmen and followers and marched against Haidar Kuli Khán. In a battle fought on the following day Safdar Khán was defeated. The other Babas escaped to Palanpur, and Safdar Khán, who in the first instance had fled to Atansmala, joined his party at Palanpur. Muhammad Fíríz Jhalorí, governor of Palanpur, with the title of Ghazni Khán, afterwards succeeded in reconciling the Babas and Haidar Kuli Khán. A.D. 1719 was a year of great famine. Abdúl Hamíd Khán, who had filled so many appointments in Gujarat, went to court, and was made governor of Sorath. Haidar Kuli Khán now marched against the Mahi Kohis. In the meantime news was received of the appointment of a new viceroy, and Ghazni Khán, governor of Palanpur, was ordered to stay at Ahmedabad for the defence of the city.

Early in A.D. 1719, the emperor Farrákhsiyar was deposed and put to death by the Sayads, and a prince named Rafiâ-nd-Darajât, a grand-son of the emperor, was raised to the throne. Rafiâ-nd-Darajât was put to death by the Sayads after a reign of three months, and his brother Rafiâ-nd-daulah, who succeeded him, also died after a few days' reign. The Sayads then raised to the throne prince Raushan Akhtar with the title of Muhammad Shah. After the murder of Farrákhsiyar, the most powerful vassal in the neighbourhood of Delhi was Ajítsingh of Márwar. To win him to their side the Sayads granted him the viceroyalty of Gujarât, and Mihr Ali Khân was appointed to act for him until his arrival, while Muhammad Bahâdur Bâbi, son of Salabat Muhammad Khân Bâbi, was placed in charge of the police of the district immediately round Ahmedabad. Shortly after, through the influence of the Maharâja Ajítsingh, Nahir Khan superseded Mihr Ali Khân as deputy viceroy. Nahir Khan was also appointed to the charge of Dholka, Dohad and Petlad, and made superintendent of customs. About this time the head tax was repealed, and orders were issued that its levy in Gujarât should cease.

In the same year, A.D. 1719, Pilâji Gâkhwâr marched on Surat with a large army and defeated the imperial troops commanded by Sayad Akel and Muhammad Panah, the latter commander being taken prisoner and forced to pay a heavy ransom. Pilâji, finding Gujarât an easy prey, made frequent incursions, and taking Songad in the extreme south-east established himself there. Mihr Ali Khân, who had been acting for Nahir Khân, marched against and subdued the Kolis, who were committing piracy in the Mahi estuary. From this year Mughal rule in Gujarât was doomed. Pilâji Gâkhwâr was established at Songad, and in the anarchy that ensued, the great Gujarât houses of the Babis and Jhalours, as well as the newly arrived Momin Khân, turned their thoughts to independence. Ajítsingh so hated Muhammadan rule that he secretly favoured the Marathas, and strove to establish his own authority over such portions of Gujarât as bordered on Marwâr. In after years, Sarbuland Khân made a vigorous attempt to reassert imperial dominion, but the seeds of dissolution were sown and efforts at recovery were vain.

In A.D. 1720, Ajítsingh the viceroy sent Anopsingh Bhandári to Gujarât as his deputy. In this year Nizam-ul-Mulk, viceroy of Ujjain, was superseded by Sayad Dilawar Khân. While Dilawar Khân was yet on the Malwa frontiers the Nizam desirous of possessing himself of the Dakhan and its resources retired to Bithûrpan, pursued by Sayad Dilawar Khân, who giving battle was killed, the Nizam retiring to Aurangâbâd in the Dakhan. Alam Ali Khân, deputy viceroy of the Dakhan, was directed to march against him, while from north Gujarât Anopsingh Bhandári was ordered to send 10,000 horse to Surat, and Nahir Khân, the deputy viceroy, was instructed to proceed thither in person. The Nizam and Alam Ali Khân met near Bâlâpur in the Berârs and a battle was fought in which the Nizam was successful and Alam Khân was slain. At this time Anopsingh Bhandári committed many oppressive acts, of which the

## Chapter III.

Mughal  
Viceroys.

Muhammad  
Shah  
Emperor,  
1721-1748.  
MAHARAJA  
AJITSINGH  
Rajpoot  
Viceroy,  
1719-1721.

Pilâji Gâkhwâr  
at Songad,  
1719.

Decay  
of Imperial  
Power,  
1720.

## Chapter III.

Mughal  
Viceroys.Muhammad  
Shah  
Emperor,  
1721-1748.Nizam-ul-Mulk  
Prime Minister,  
of the Empire,  
1721.HAIDAR KULI  
KHAN  
Fifth Viceroy,  
1721-22.Disorder in  
Ahmedabad,  
1721.Leaves Delhi  
for Gujarat,  
1722.

chief was the murder of Kapurchand Bhansáli, the leading merchant of Ahmedabad. The cause of Kapurchand's murder was that he had hired a number of armed retainers who used to oppose the Bhandári's orders and set free people unjustly imprisoned by him. To remove this meddler from his way the Bhandári got him assassinated. In A.D. 1721, Nizám-ul-Mulk was appointed prime minister of the empire, Abdúl Hamíd Khán was recalled from Sorath, and in his stead Asad Kuli Khán, with the title of Amír-ul-Umara, was appointed governor of Sorath and sent Muhammad Sharif Khán into Sorath as his deputy.

In A.D. 1721, in conjunction with Muhammad Amín and Saádat Khán, Haider Kuli Khán freed the emperor from the tyranny of the Sayads, and was rewarded with the title of Mu'iz-ul-daulah Haider Kuli Khán Bahádur Zafar Jang and the viceroyalty of Gujarát. He obtained the appointment of minister for his brother Jangar Kuli Khán. Maísúm Kuli Khán was dignified by the title of Shujaát Khán Bahádur and appointed deputy viceroy. As soon as this change was notified, the people of Ahmedabad, who were discontented with the rule of Anopsingh, attacked his palace, the Bhadar, and he escaped with difficulty. In consequence of the enmity between Haider Kuli Khán and the Márwaris, Shujaat Khán, the deputy viceroy, attacked the house of Nohur Khán who had been Ajitsingh's minister, and forced him to pay £10,000 (Rs. 1 *lakh*) and leave the city. Shujaát Khán next interfered with the lands of Safdar Khán Babi, the deputy governor of Goolhra, and his brothers. On one of the brothers reparing to Delhi and remonstrating, Haider Kuli, who, above all things, was a Muhammadan and anxious to strengthen himself with the Muhammadan nobility of Gujarát, restored their lands to the Babis. In consequence of this decision ill-feeling sprung up between Shujaat Khán and the Babis, and when Shujaát Khán went to exact tribute he forced Muhammad Khán Babi, governor of Kaira, to pay a special fine of £1000 (Rs. 10,000). Shortly after one of the viceroy's officers, Kásim Ali Khán, while employed against the Kohis of that part of the country, was killed at Pethápur. Shujaát Khán advanced, and revenged Kasim Ali's death by burning the town. Next, he passed into Sorath, and after exacting tribute, crossed to Kachh. The chief opposed him, and in the fight that followed was beaten and forced to pay about £22,500 (Rs. 22 *lákhs*).<sup>1</sup> In A.D. 1721, a Sayad was sent to Sorath as deputy governor in place of Muhammad Sharif and Haider Kuli was appointed governor of Kadi, the Chúnvál, and Halvad (called Muhammadnagar), and put in charge of Tharád, Arjanpur, Bhámnárah, Pethápur, and Kherálu in place of Vakhatsingh, son of the Maharája Ajitsingh.

Early in A.D. 1722, Nizám-ul-Mulk took up the office of prime minister of the empire, to which he had been appointed in the previous year. Strenuous efforts were made to embroil him with Haider Kuli

<sup>1</sup> The sum is 6,75,000 *mahmúdis*. Like the *changtzi* (see above page 222 note 2) the *mahmudi* seems to have varied in value from one-third to one-half of a rupee.

Khán, as the Nizám's austerity and craft were a source of not less anxiety to the Delhi court than Haidar Kúh's more daring and restless ambition. Haidar Kúh Khán, unable to contend with the Nizám, left Delhi and retired to Gujarát. On his way the villagers of Dabháli opposed him killing one of his chief men named Alif Beg Khán. Haidar burned the village and put all the people to death, a severity which caused such terror that throughout his rule no difficulty was experienced in realizing tribute or in keeping the roads safe. About this time, among other changes, Muhammad Bahadúr, son of Salabat Khán Bábi, was placed in charge of Sadra and Virpur, with the title of Sher Khán. Shortly after his arrival the viceroy marched against, and subdued the rebellious Kolis of the Chunval, appointing Rustam Ali Khán his governor there. Then, returning to Ahmedábád, he took up his residence in the Bhadra. There is little doubt that at this time Haidar Kúh aimed at bringing all Gujarát under his rule. He seized the imperial hoases which passed through Ahmedábád on their way to Delhi, and confiscated many estates and gave them to his own men. On his way to enforce tribute from the Dungarpur chiefs, he levied £8000 (Rs. 80,000) from Lamávada. Through the mediation of the Udepur Rana, and as he agreed to pay a tribute of £10,000 (1 *lakh* of rupees), the Rával of Dungarpur escaped. Haidar Kúh next proceeded to Bijapur, north of Ahmedábád, but hearing that the emperor was displeased at his assumption of the power of giving and changing grants of land, he returned to Ahmedábád and restored several estates which he had confiscated. The court continued to distrust him, and at the close of A.D. 1722 appointed Jumlát-ul-Mulk Nizám-ul-Mulk fifty-first viceroy.

Haidar Kúh Khán, finding himself no match for the Nizám, was induced to retire quietly, and accordingly left Gujarát by way of Dungarpur. Shuját Khán and Rustam Ali Khán accompanied him as far as Dungarpur, and then returned to Ahmedábád. In the meantime the Nizám had reached Ujjain, and thence directed Saldar Khán Bábi to carry on the government till he should arrive, appointing at the same time his uncle Hámid Khán as deputy viceroy and Fidwi Khán as minister. Subsequently the Nizám came to Gujarat and chose officers of his own for places of trust, the chief of whom was Momín Khán, who was appointed governor of Surat. The Nizám then returned to Delhi, but, after a short time, disgusted with his treatment at court, he retired to the Dakhan, where, making Haidarabad his capital, he gradually began to act as an independent ruler. Meanwhile in Gujarat dissensions sprang up between Hámid Khán and other officers, but matters were arranged without any outbreak of hostility. Tribute was exacted from the chiefs on the banks of the Vátrák and from Modhera an unruly Koli village was burned down, and garrisons were placed in the Koli country. In A.D. 1723 Rustam Ali Khán and Shuját Khán were ordered from Delhi to march on Jodhpur, which they captured and plundered, and then returned to Ahmedábád.

In A.D. 1723 Piláji Gáikwár, who had been long hovering on the frontier, marched on Surat and was opposed by Momín Khán, whom he defeated. After levying contributions from the surrounding country,

**Chapter III.****Mughal  
Viceroys.**

Muhammad  
Shah  
Emperor,  
1721-1748.

Haidar Kúh  
Khán  
Fiftieth Viceroy,  
1721-22.

Shows Signs of  
Independence  
and is Recalled,  
1722.

Nizám-ul-Mulk  
Fifty-first  
Viceroy,  
1722.

Hámid Khán  
Deputy Viceroy;  
Momín Khán  
Governor of  
Surat,  
1722.

Increase of  
Marátha Power,  
1723.

## Chapter III.

Mughal  
Viceroys.

Muhammad  
Shah  
Emperor,  
1721-1748.  
SARBULAND  
KHÁN  
Fifty-second  
Viceroy,  
1723-1730.

Appoints  
Shujaat  
Khán  
his Deputy.

Nizám-ul-Mulk  
and Sarbuland  
Khan

Sarbuland  
Khan's  
Deputy  
Defeated,  
1724.

he returned to his head-quarters at Songad, and from this overran a considerable portion of the Surat territory, building several forts in the Rájpipla country. At the same time Kántáji Kadam Bānde, invading Gujarát from the side of Dohad, began to levy fixed contributions. Though before this occasional demands had often been made, A.D. 1723 was the first year in which the Maráthás imposed a regular tribute on Gujarát. Momín Khán was now appointed provincial minister, and Rustam Ali Khán succeeded him as revenue officer of Surat, and, as the Nizám had gone to the Dakhan without the emperor's leave, Mubáriz-ul-Mulk Sarbuland Khán Bahadur Diláwar-Jang was appointed fifty-second viceroy of Gujarát. He selected Shujaat Khán as his deputy, and made other arrangements for the government of the province. Hámid Khán, uncle and deputy of the Nizám, prepared to oppose Shujaat Khán, but through the intervention of Bábis Salábat Khán, Safdar Khan, and Jawán Mard Khán, Hámid Khán evacuated the Bhadra, and withdrew to Dohad. Shujaat Khán now went to collect tribute, leaving Ibráhím Kúli Khán at Ahmedábád, while Rámraú was posted at Mahmudha in Kaira, with orders to watch the movements of Hámid Khán. As the viceroy was in need of money, he farmed to one Jivan Jugal the districts of Jambúsar, Makkúbbad or Anod about twenty-two miles north of Broach, Dholka, and Broach. In A.D. 1724, he came to Ahmedábád with Ali Muhammad Khán father of the author of the *Mi'at-i-Ahmedí*, as his private minister.

Rustam Ali, governor of Surat, having succeeded twice or thrice in defeating the Maráthás under Píláji Gáikwar, now offered, in conjunction with his brother Shujaat Khán, that if 20,000 men were placed under their orders, they would march against the Nizám. The emperor accepted this offer, allowing Rustam Ali to draw on the Surat treasury to the extent of £20,000 (Rs. 2 *laks*). Rustam Ali accordingly, with the aid of Ahmed Kúli his brother's son, equipped an army. In the meantime the Nizám was not idle. He promised to Kántáji Kadam Bānde a one-fourth share of the revenue of Gujarát, provided he should be able, in concert with Hámid Khán, to re-conquer the province from Mubáriz-ul-Mulk. Shujaat Khán, who was now at Kach, instead of following the advice of his minister and carefully watching Hámid Khán's movements from Kapadvanj, went to a distant part of the province. Hámid Khán seeing his opportunity, united his forces with those of Kántáji Kadam, and marched to Kapadvanj. Shujaat Khán hearing of this, advanced towards Ahmedábád and encamped at Dabhora under Bahyal, eighteen miles east of Ahmedábád and thence proceeded to Mota Medra, about six miles east of the capital. When he came so near Ahmedábád, many of his soldiers went without leave into the city to visit their families. The Maráthás attacked his rear guard, and his men giving way took to flight. Hámid Khán seeing that Shujaat Khán had but a small force, marched between him and the capital. A battle was fought, in which Shujaat Khán was slain, and his two sons Husán Kúli and Mustafa Kúli were taken prisoners. Shujaat Khán's head was cut off and sent to Safdar Khán Bábi, to be sent to Ibráhím Kúli his son, who was doing duty as commandant at Ahmedábád. Hámid Khán took up his quarters in

the Shāhi Bāgh, and got possession of all Ahmedābād except the city. Hāmid Khān now sent a message to the emperor, that the Marāthās had been successful in defeating Shujāat Khān and conquering Gujarāt, but that he had defended Ahmedābād against them. The emperor sent him a dress of honour, but after a few days discovered that Hāmid's message was false. The Marāthās now marched through the country, collecting their *chaauth* or one-fourth and their *sardeshmukhi* or one-tenth shares of the revenue. Kāntāji went to Virāngām and besieged the town, but on the promise of one of the chief inhabitants to raise a sum of £35,000 (Rs. 3½ *lāks*) the Marāthās retired. Hāmid Khān who was now independent began to bestow lands and districts many of which remained with the grantees and were never recovered by future governors. Ibrāhīm Khān, son of Shujāat Khān, in revenge for his father's death, determined to assassinate Hāmid Khān. The attempt failed. Hāmid Khān escaped and Ibrāhīm Kūli was slain.

Rustam Ali Khān, governor of Surat, in the hope of being revenged on Hāmid Khān, invited the aid of Pīlāji Gāukwār, and it was agreed that they should meet on the north bank of the Narbada. Pīlāji promised to aid Rustam Khān, and the allied armies, crossing the Mahi, encamped at Aras in the plain between Anand and the Mahi. Hāmid Khān, accompanied by Mīr Nathu, Muhammad Sulabat Rohila, and Kāntāji Kadam, marched to oppose Rustam Khān. Hāmid Khān also entered into secret negotiations with Pīlāji Gāukwār, who resolved to remain neutral and side with the conqueror. A battle was fought, in which, though Pīlāji took no part, Hāmid Khān was defeated and put to flight, and Mīr Nathu was killed. After the fight Rustam Ali reclaimed on the field of battle and liberated his nephews, plundering Hāmid Khān's camp. Pīlāji plundered Rustam Ali's camp and then moved off, while Kāntāji carried away what was left in the camp of Hāmid Khān. Hāmid Khān reproached Kāntāji for his inactivity; but he pleaded in excuse that he was watching the mode of warfare amongst Muhammadās, and promised to attack Rustam Ali shortly. Now, as the Marāthās really desired to ruin Rustam Ali, who was their bitter foe, they after a few days surrounded him and cut off his supplies. Rustam Ali stood a blockade of eight days, and then forced his way through his enemies and went to Nāpād, about fourteen miles west of the Vāsad railway station in the Anand sub-division of the Kaira district, and thence through Kalamsar to Nāpa or Nāba under Pethād. The Marāthās still pursuing Rustam Ali retired to Vasu under Pethād, ten miles east of Nadiād and about twenty-five miles south of Ahmedābād, where he gave battle, and by a furious charge broke the Marātha line. The Marāthās rallied, and Rustam Ali and his men were defeated, Rustam Ali being slain and his nephews again taken prisoners. Rustam was buried on the field of battle and his head sent to Ahmedābād.

Hāmid Khān returned to Ahmedābād with the Marāthās, who saw that their only means of effecting a permanent footing in the province was by supporting him. Hāmid Khān then assigned a one-fourth share of the revenue of the territory north of the Mahi to Kāntāji, and to Pīlāji a corresponding interest in the territory south of the Mahi,

## Chapter III.

Mughal  
Viceroys.

Muhammad  
Shāh  
Emperor,  
1721-1748.  
SARBI DAND  
KILĀY  
Fifty-second  
Viceroy,  
1723-1730.

The Marāthās  
engaged as  
Allies.

Battle of Aras.  
Hāmid Khān  
defeated by  
Rustam Ali,  
1723.

Marāthās join  
Hāmid Khān  
against  
Rustam Ali.

**Chapter III.****Mughal  
Viceroys.**

Muhammad  
Shah  
Emperor,  
1721-1748.  
SABIR KHAN  
Khan  
Fifty-second  
Viceroy,  
1723-1730.

Mubarriz-ul Mulk  
sent against the  
Marathas,  
1725.

Hamid Khan  
and other  
Marathas  
Retire.

Mubarriz-ul-  
Mulk enters  
Ahmedabad,  
1725.

including Surat and Baroda. After this Hámid Khán acted tyrannically. He extorted large sums from the rich, and poisoned the two sons of Shujáát Khán. When the news of Kántáji's and Piláji's success reached the Dakhan, Trimbakráv Dhábáde, son of Khanderáv Senápati, came with a large army and laid siege to Cambay. While the siege was being pressed a quarrel among the Marátha leaders culminated in strife and bloodshed. Trimbakráv Senápati was wounded and the Marátha army had to disperse and retire.<sup>1</sup> Salábat Khán, leaving Ahmedábád, went to Virangám, and after some time, placing his nephew at Virangám, he went into Goluváda. When the news of the defeat and death of Rustam Áh reached Delhi, the emperor ordered Mubarriz-ul-Mulk to take a strong army and proceed in person to Gujarát and expel Hámid Khán and the Maráthas. Mubáriz-ul-Mulk marched on Gujarát with a large army, assisted by Mahárája Abheysingh of Jodhpur, Chatausingh Rája of Narwar in Bundelkhand, Gandrasingh, and the Mahárána of Udepur. On his arrival at Ajmír Mubáriz-ul-Mulk was received by his private minister Áh Muhammad Khan, who afterwards joined Jawán Mard Khan Bábi in Rádhampur, and united their troops with those under Mubarriz-ul-Mulk. At that time Salábat Khán was removed from his government, and Safdar Khan Bábi died. In obedience to the imperial order, Mubáriz-ul-Mulk marched from Ajmír and came to the Gujarát frontier. On his approach Hámid Khán returned to Ahmedábád. He placed Rúpsingh and Sardar Muhammad Ghorni in charge of the city and himself withdrew to Mehmúdábád. Mubáriz-ul-Mulk now sent Sheikh Ahyár in advance with an army against Ahmedábád. When Sheikh Ahyár arrived before the city, Muhammad Ghorni, who was dissatisfied with Hámid Khán for bringing in the Marathas, persuaded Rúpsingh to fly. In the meantime Mubáriz-ul-Mulk with the main body of his forces reached Sídhpur. Hámid Khán accompanied by a detachment of Marátha horse, now returned to Ahmedábád; but Muhammad Ghorni closed the gates, and would not suffer him to enter the city. Mubáriz-ul-Mulk marched to Mesána. About this time Ali Muhammad Khán, the father of the author of the *Mirát-i-Ahmadi*, who was now with Mubáriz-ul-Mulk at Mesána, advised him to combate the influential Muhammadan family of Bábi. Under his advice, Salábat Muhammad Khán Bábi was appointed governor of Virangám, and Jawán Mard Khán governor of Pátan. Shortly afterwards Murdhardás, the Gujaráti minister of Hámid Khán, deserted his master's declining cause. When Kántáji heard that Mubáriz-ul-Mulk had arrived at Pethápur, only eighteen miles from Ahmedábád, he retired to Mehmúdábád. Before the close of A.D. 1725, Mubáriz-ul-Mulk reached Ahmedábád, where he was well received by the officials and merchants.

<sup>1</sup> See note 1 page 312. The author of the *Mirát-i-Ahmadi* (Persian Text Royal Asiatic Society's Library Edition, I. 658) says Trimbakráv was slain. This seems an oversight as in another passage (Ditto, 738-739 see below page 312) he states that Trimbakráv was killed in 1731. The latter statement is in agreement with Grant Duff (History of the Maráthas, I. 364).

Hámid Khán and Kantáji, who had by this time reached the banks of the Mahi, were now joined by Piláji Gáikwár. The Maráthas leaders, seeing that the only way to preserve their footing in the province was to espouse the cause of Hámid Khán, united their forces with his, and prepared to march on Ahmedabad. Mubáriz-ul-Mulk deputed his son Khánahzáid Khán with an army to oppose them, and made several appointments, among other changes raising Ali Muhammad Khán to the post of minister. Khánahzáid Khán met the Maráthas near Sojitra, about ten miles north-west of Petlád, and defeated them, pursuing them as far as the Mahi. Then, returning, he was reinforced by his brother Shah Nawaz Khan, and marched against the Maráthas, who were encamped at Kapadvanj. Another battle was fought, and the Maráthas were again defeated and pursued as far as the hills of Ali-Mohan now Chota Udepur in the extreme east of the province. Khánahzáid Khán now appointed Hasan-ud-dín governor of Baroda, Broach, Jambisar, and Mahbubabad. Meanwhile Antáji Bháskar, a Maratha noble, entering Gujarát from the side of Idar, laid siege to the town of Vadnagar, which, according to the old Gujarát proverb, with Umreth in the Kana district, are the two golden feathers of the kingdom of Gujarát. Vadnagar was inhabited by wealthy Brahmins of the Nagar caste who prayed Mubáriz-ul-Mulk to march to their relief; but as both his sons were in pursuit of the other Maráthas bands defeated at Kapadvanj, the viceroy had no troops to spare from the Ahmedabad garrison. The Nágas accordingly, seeing no prospect of help, paid a sum of £10,000 (Rs. 4 lakhs) and Antáji Bháskar retired. Kantáji and Piláji, encouraged by this raid of Antáji's, entered Gujarát from different quarters. Kantáji again laid siege to Vadnagar. The Nágas, unable to pay the contribution demanded, leaving their property fled and Kantáji in his attempts to unearth the buried treasure burned down the town. Shortly afterwards Umreth in the Kana district suffered a similar fate at the hands of Kantáji. In one of his raids Piláji Gáikwár advanced as far as Baroda was met by Khánahzáid Khán, the son of the viceroy. Distrusting the issue of a battle Piláji fled to Cambay, and from Cambay withdrew to Sorath. For these services the emperor raised Khánahzáid Khán to the rank of a noble, with the title Gháib Jang. About this time Ali Muhammad Khán was dismissed from the post of minister, and in his stead first Muhammad Sayad Beg and afterwards Muhammad Sulaiman were appointed. Not long afterwards Ali Muhammad Khán was again entrusted with a command and raised to be governor of Dholka.

The Maráthas retired to the Dakhan, but, returning in A.D. 1726, compelled Mubáriz-ul-Mulk to confirm his predecessor's grants in their favour. The emperor refused to acknowledge any cessions of revenue to the Maráthas; and the viceroy, hard pressed for money, unable to obtain support from the court and receiving little help from his impoverished districts, was forced to impose fresh taxes on the citizens of Ahmedábad, and at the same time to send an army to collect their tribute from the Mahi chiefs. As part of the agreement between Mubáriz-ul-Mulk and the Maráthas chiefs Piláji was to receive a share in the

## Chapter III.

Mughal  
Viceroys.

Muhammad  
Shah  
Emperor,  
1721-1748.

SACR CANE  
Khan

Fifty-second  
Viceroy,  
1723-1730.

Defeat of the  
Maráthas at  
Sojitra and  
Kapadvanj,  
1725.

Maratha  
Expedition  
against  
Vadnagar,  
1725.

Mubáriz-ul-Mulk  
pays the Maráthas  
• Tribute,  
1726.

## Chapter III.

Mughal  
Viceroys.

Muhammad  
Shah  
Emperor,  
1721-1748  
SAIBULAD  
KHÁN  
Fifty-second  
Viceroy,  
1723-1730.

Alliance with  
the Peshwa,  
1727.

Pilaji Garkwār  
obtains Baroda  
and Dabhoi,  
1727.

Capture of  
Champaner by  
the Marathās,  
1728.

revenue of the districts south of the Mahi. But Peshwa Bājirāv Baklī, to whom, as agent of his rival Khandegāv Dabhade, Pilāji was obnoxious, sent Udāji Pavār to drive Pilāji away. In this Udāji was successful, and defeating Pilāji forced him to seek the aid of Kāntāji. Kāntāji, perceiving that if the Peshwa became supreme his own independence would suffer, joined Pilāji, and marching together upon Baroda they endeavoured, but without success, to prevent the Mulsalmān governor Saūr-ud-dīn Khān from entering the city. About this time want of funds forced Mubārīz-ul-Mulk to sell the greater part of the Dholka district to different landholders.

In the following year, A.D. 1727, Bājirāv Peshwa began to negotiate with Mubārīz-ul-Mulk, undertaking that if the one-fourth and one-tenth shares in the revenue of the province were guaranteed to him, he would protect Gujurāt from other invaders. Though he did not consent to these proposals, the viceroy so far accepted the alliance of the Peshwa as to allow the governor of Baroda to aid Udāji Pavār against Pilāji. Pilāji and Kāntāji outmanoeuvred Udāji and prevented him from effecting a junction with the governor of Baroda, who in the end was forced to abandon both that city and the stronghold of Dabhoi, while Udāji retired to Malwa. Pilāji Garkwār now obtained possession of Baroda. Mubārīz-ul-Mulk, still sorely pressed for funds, marched into Sorath to exact tribute. On reaching Vramgām, Salābat Muhammad Khān Bābi, on behalf of the Jām of Navānagar, presented the viceroy with £10,000 (Rs. 1 lākh), and for this service was rewarded with the gift of an elephant. Mubārīz-ul-Mulk then marched against Chhāya, the capital of the chief of Porbandar in the south-west of Kāthiāvāda. This chief, by putting to sea, hoped to escape the payment of tribute. But on hearing that the viceroy proposed to annex his territory and appoint an officer to govern it, he returned and agreed to pay a tribute of £4000 (Rs. 10,000).<sup>1</sup> On his way back to Ahmedābād, Mubārīz-ul-Mulk passed through Halvad in Jhālāvāda, and there married the daughter of Jhālā Pratāpsingh, the chief of that district, whom he accordingly exempted from the payment of tribute. About this time the viceroy received orders from the emperor to restore certain land which he had confiscated, and as he neglected to obey, certain estates of his in the Panjab were resumed. In the meantime Kṛishnāji, foster son of Kāntāji, made a sudden attack upon Chāmpāner and captured that fortress, and from that time Kāntāji's agents remained permanently in Gujurāt to collect his share of the tribute.

In A.D. 1728 the minister Momīn Khān died, and in his place the emperor selected Momīn Khān's brother Abd-ul-Ghāni Khān. About this time Asad Ali, governor of Jūnāgadh, also died, and on his death-bed appointed Salābat Muhammad Khān Bābi deputy governor of that fortress. Salābat Muhammad Khān sent his son Sher Khān Bābi to act on his behalf. When the emperor heard of the death of Asad Ali, he appointed Ghulām Muhy-ud-dīn Khān, son of the late Asad Ali, governor. Ghulām Muhy-ud-dīn did not proceed to Jūnāgadh but continued Sher Khān Bābi as his deputy. Mubārīz-ul-Mulk, now

<sup>1</sup> The amount was 1,25,000 mahmūdīs.

perceiving that neither Píláji nor Kántáji afforded any protection to Gujarát, but rather pillaged it, closed with the offers of Bájráv Peshwa, and in A.D. 1729 formally granted to him the one-fourth and one-tenth shares of the revenue of the province. The Peshwa accordingly sent his brother Chinnájiráv to collect the tribute. Chinnáji plundered Dholka and the country near Chámpáner, while Muhriz-ul-Mulk exacted tribute from the chiefs on the banks of the Vátrak. Kántáji now entered Gujarát and prepared for war in case Chinnáji and the viceroy should unite against him. His movements were not interfered with, and after collecting his share of the tribute, he retired to Sorath. The viceroy now marched against the Kolis, and after destroying many of them together with their wives and children, returned to Ahmedábád by way of Modasa and Ahmednagar. Ghulam Muhy-ud-dín Khán, governor of Júnágadh, who had not yet proceeded to his command, appointed a second deputy. Through the influence of the viceroy this appointment was not confirmed, and instead Sher Khán Bibi, son of Salabat Muhammad Khán, was placed in charge of that fortress.

In Surat the year A.D. 1729 was marked by a severe flood in the Tapti and by a somewhat serious local disturbance. The chief cause of the disturbance was Mulla Muhammad Ali, a rich Musalmán trader of Surat. This man who, as Unda-tut-tujjár or chief of the merchants, had already a special rank in the city, was tempted to take advantage of the disorders of the time to raise himself to the position of an independent ruler. With this object he chose as his head-quarters the island of Piram in the Gulf of Cambay, near the port of Goghla, and there spent considerable sums in strengthening the island and tempting settlers to place themselves under his protection. As Piram was not popular Mulla Muhammad fixed on the village of Athva, on the left bank of the Tapti, about twelve miles from its mouth. Here he began to build a fort, but was ordered to desist by Sohrab Khán, the governor of Surat, from which city the proposed stronghold was only three miles distant. Mulla Muhammad so far from obeying, persuaded Beglar-Beg Khán the commander of the fort of Surat to side with him. Accordingly, next day, Beglar-Beg Khán bombarded the governor Sohráb Khán's residence, proclaiming that his own brother Teghbeg Khán was appointed governor of Surat. In the end Mulla Muhammad Ali induced the chief merchants of the city to pray for the removal of Sohráb who pending receipt of orders from the emperor was made to hand over his official residence in the city to Teg-Beg Khán.

In the same year, A.D. 1729, Jawán Mard Khán Babi was chosen governor of Poitád, Ali Muhammad Khán was made collector of Ahmedábád, and Ali Muhammad's son, the author of the Mirát-i-Ahmedi and his brother were appointed governor and superintendent of the customs of that district. Ali Muhammad Khán shortly resigned and was succeeded by Rú-ín Khán. At this time Jawán Mard Khán Babi, while punishing the Kolis of Bálór, probably Bhátod about fifteen miles east of Broach, was killed by a man of that tribe, and in revenge for his death the town of Bálór was plundered. On the death of Jawán Mard Khán, at the request of Salábat Muhammad Khán Babi, his eldest son Kamál-ud-dín Khán Babi received the districts of

**Chapter III.****Mughal  
Viceroys.**

Muhammad  
Shah  
Emperor,  
1721-1748.

SALBOLAND  
KHAN  
Fifty-second  
Viceroy,  
1723-1730.

Grant of Tribute  
to the Peshwa,  
1729.

Mulla  
Muhammad  
Ali causes a  
Disturbance  
at Surat,  
1729.

Nadial given  
in Fann,  
1729.

## Chapter III.

Mughal  
Viceroys.

Muhammad  
Shah  
Emperor,  
1721-1748  
SARBUKANO  
KHAN  
Fifty-second  
Viceroy,  
1723-1730.

Athva Fort,  
1730.

The Viceroy  
in Kathiavada  
and Kachh,  
1730.

Riots at  
Ahmedabad.

MAHARAJA  
ABHEYSINGH  
Fifty-third  
Viceroy,  
1730-1733.

Sami and Munjpur and the title of Jawān Mard Khān. At the same time the second son, Muhammad Anwar, with the title of Safdar Khān, was appointed to the government of Rādhanpur. The viceroy now went to Nadiad, where Rāi Kishandās, agent of Jawān Mard Khān, received the district of Petlād in fann. From Nadiad Mubārīz-ul-Mulk went to collect tribute from Sandārsingh, the chief of Bhādarva in the Rewa Kantha about fifteen miles north of Baroda, on the banks of the Mahi, who, after some fighting, agreed to pay a sum of £2000 (Rs. 20,000). On his way back to Ahmedabad the viceroy levied tribute from the chief of Umeta, fifteen miles west of Baroda. As Rāi Kishandās failed to pay the sum agreed on for the fann of Petlād, an order was issued for his imprisonment. To save himself from the indignity he committed suicide.

When Kāntaji returned from Sorath he camped at Sīnand, and his advanced guard carried off some of the viceroy's elephants which were grazing there. Men were sent in pursuit, but in vain, and the Marāṭhas escaped. Meanwhile, at Surat, Mulla Muhammad Ali continued to build the fort at Athva. At last his accomplice Beglar-Beg Khān the commander of the Surat fort, began to perceive that if the Athva fort were completed the Mulla would be in a position to obstruct the trade of the port of Surat. He consequently ordered him to stop building. In spite of this the Mulla succeeded in persuading Sohrāb Khān to allow him to go on with his fort promising in return to get him confirmed as governor of Surat. Sohrāb Khān agreed, and the fort was completed and Sohrāb Khān was duly appointed governor. As the fort was immediately below Surat the revenue of Surat was greatly diminished, and Sohrāb Khān, when it was too late, saw his mistake.

In A.D. 1730 Mubārīz-ul-Mulk went into Gohlyāda in south east Kathiavada and levied tribute from Bhāvsingh, chief of Sīhor; thence he proceeded to Mādhanpur, a town under Porbandar, and laid it waste. While engaged at Mādhanpur, Momīn Khān, son-in-law of the late Momīn Khān, owing to some misunderstanding with the viceroy suddenly set out for Ahmedabad and from Ahmedabad proceeded to Agra. The viceroy now marched in the direction of Kachh and refusing the offer of a yearly tribute of about £53,000 (10,00,000 *māhmūdīs*), advanced against Bhuj. He experienced great difficulty in crossing the Ran, and as the Rao had cut off all supplies, and as at the same time news arrived of disturbances in Ahmedābād, he was obliged, after a month and a half, to retire to Rādhanpur. The author of the *Mirāt-i-Ahmedī* was ordered to suppress the Ahmedābād riots, which had arisen out of the levy of some fresh taxes, and was invested with the title of Hasan Muhammad Khān. In this year Udaikaran, Desāi of Virangām, was murdered by a Kasbātī<sup>1</sup> of that town named Ali, and Salāhāt Muhammad Khān Babi, who was sent to investigate this murder, died on his way at Pāldi, a village on the right bank of the Sūbarnati opposite to Ahmedābād.

News was now (A.D. 1730) received that Mahārāja Abheysingh of Jodhpur had been appointed viceroy and had reached Pālanpur.

<sup>1</sup> Kasbātis are the descendants of the Musalman garrisons of some towns of north Gujarat. The Kasbātis of Virangām were originally Tānk Rajputs.

The friends of order endeavoured to arrange a peaceable transfer between the Mahārāja and the late viceroy, but Mubārīz-ul-Mulk determined to try the chances of war, and prepared for resistance. At this time Mīr Ismāil, deputy of Ghulām Muhy-ul-dīn Khān; arrived and took charge of the government of Jūnāgadh from Sher Khān Bābi. Mahārāja Abheysingh, after making various appointments, set out with his brother Vakhatsingh and 20,000 men to take over the government of Gujārāt. When he reached Pālanpur and saw that Mubārīz-ul-Mulk was determined on resistance, he sent an order to Sardār Muhammad Ghori appointing him his minister and directing him to take possession of the city of Ahmedābād and drive out the late viceroy. As Sardār Muhammad was not strong enough to carry out these orders he awaited the Mahārāja's arrival. When the Mahārāja reached Sūlhpur he was joined by Safdar Khān Bābi and Jawān Mard Khān Bābi from Rādhanpur. They then advanced together to Adālaī, distant only about eight miles from the capital, their army increasing daily. Mubārīz-ul-Mulk was already encamped between Adālaī and the city, and on the approach of the Mahārāja a battle was fought in which the Mahārāja was defeated. Abheysingh changed his position, and another and bloodier engagement took place, in which both sides tried to kill the opposing commander. But as both Mubārīz-ul-Mulk and the Mahārāja fought disguised as common soldiers, neither party succeeded. At first the Mahārāja who had the advantage in position repulsed the enemy, but Mubārīz-ul-Mulk fought so desperately in the river-bed that the Rāthods gave way. They rallied and made one more desperate charge, but were met, repulsed, and finally pursued as far as Sarkhej. The Mahārāja, who had not expected so determined an opposition, now sent Momīn Khān and Awarasingh to negotiate with Mubārīz-ul-Mulk, who was still determined to resist to the uttermost. It was finally agreed that Mubārīz-ul-Mulk should receive a sum of £10,000 (Rs. 1 *lakh*) and should surrender Ahmedābād to the Mahārāja. Mubārīz-ul-Mulk accordingly quitted the city and left for Agra by way of Udepur.

The Mahārāja entering Ahmedābād, appointed Ratansingh Bhamlāri his deputy, and placed Fidā-ud-dīn Khān, cousin of Momīn Khān, in charge of the city police. Shortly afterwards Karīmād Khān Jhālōri, governor of Pālanpur, who had accompanied the Mahārāja into Gujārāt, d'ed. After the death of Salābat Muhammad Khān Bābi, his son, Sher Khān Bābi, was dismissed from the government of Jūnāgadh. He retired to his estate of Gogha, and when the Mahārāja arrived in Ahmedābād he paid his respects, presenting the viceroy with an elephant and some horses. The Mahārāja confirmed the lands assigned to his father, and reported his action to the emperor. Momīn Khān was made ruler of Cambay, and Fidā-ud-dīn Khān, his cousin, was made governor of the lands near that city, the revenue of which had been assigned to the Mahārāja. So great was the fear of the Marāthās, that Mustafīd Khān, the governor elect of Surat, instead of proceeding direct by land, went to Cambay. From Cambay he moved to Broach, and from Broach entered into negotiations with Pilāji Gāikwār, promising, if allowed to retain

## Chapter III.

Mughal  
Viceroys.

Mahammad  
Shah  
Emperor,  
1721-1748.

MAHARAJA  
ABHEYSINGH  
Fifty-third  
Viceroy,  
1730-1733.

Mubārīz ul Mulk  
Resists the New  
Viceroy.

Battle of Adālaī;  
the Maharaja  
defeated by  
Mubārīz-ul-Mulk,  
1730.

Mubārīz-ul-Mulk  
Retires.

Government of  
Abheysingh.

Momīn Khān  
Ruler of Cambay,  
1730.

**Chapter III.****Mughal  
Viceroys.**

**Muhammad  
Shah  
Emperor,  
1721-1748**  
**MARATHA  
ABHEYSINGH  
Fifty-third  
Viceroy,  
1730-1733.**

**The Peshwa and  
Viceroy against  
Pilaji Gokwár,  
1731.**

**The Peshwa  
Withdraws.**

**Defeats his  
Opponents.**

**Abdúlláh Beg  
appointed the  
Nizam's Deputy  
at Broach**

possession of Surat, to pay Piláji the one-fourth share of its revenues. Piláji agreed, but Sohráb Khán, who was still in possession of Surat, refused to hand it over to Mustafid Khán. In this year also Vakhatsingh, brother of the Mahárája Abheysingh, was appointed governor of Pátán, and sent a deputy to act for him. About the same time Mír Fakhr-ud-dín, a follower of the late viceroy Mubáriz-ul-Mulk, leaving him secretly, came to Ahmedábad, and in an interview with the Mahárája obtained for himself the post of deputy governor of Jámágwálí. When he proceeded to take up his appointment he was opposed by Mír Ismáíl, and was killed in a battle fought near Amreli in central Káthiáváda. Muhammad Pahár, son of Karúpdád Khán Jhálóri, was appointed governor of Pálanpúr in succession to his father, and Jawán Mard Khán was sent to Vadnagar.

In the following year, A.D. 1731, Bájráv Peshwa, entering Gujarát at the head of an army, advanced against Baroda, then in the possession of Piláji Gáikwár. Afterwards, at the invitation of the Mahárája, he visited Ahmedábad and had a meeting with the viceroy in the Sháhi Bágh. At this meeting it was agreed that Bájráv should assist Azmatulláh, the governor of Baroda, in taking possession of that town and in expelling Piláji Gáikwár. By this arrangement the viceroy hoped by playing off the Peshwa against Piláji, to succeed in getting rid of the latter, while the Peshwa intended that if Piláji was forced to give up Baroda, he himself should gain possession of that city. Accordingly the Peshwa, together with an army from the viceroy, marched on Baroda. They had scarcely laid siege to the city when the Peshwa heard that Nizám-ul-Mulk was advancing on Gujarát against him. Abandoning all operations against Baroda, the Peshwa withdrew, with all speed, to the Dakhan. On his way he encountered the army of Trimbakráv Senápati, who, together with Piláji Kantaji and Udáji Pavár, had united to resist the pretensions of the Peshwa in Gujarát, and were also secretly leagued with the Nizam. An engagement was fought in which the Peshwa was victorious and Trimbakráv was slain.<sup>1</sup> The Peshwa at once pushed on to the Dakhan, contriving to avoid the Nizam, though his baggage was plundered by that chief, who had camped at Ghula Káurej, on the river Tápti, about ten miles above Surat.

During these changes the city of Broach, which on account of the strength of its fort the Marathís had failed to take, was governed by Abdúlláh Beg, an officer originally appointed to that command by Mubáriz-ul-Mulk. Dissatisfied that the government of Gujarát should be in the hands of Abheysingh, Abdúlláh Beg, in A.D. 1731, entered into negotiations with the Nizam, offering to hold Broach as the Nizam's deputy. Nizám-ul-Mulk agreed, appointed Abdúlláh his deputy, and ennobled him with the title of Nek Alam Khán. About the same time Vakhatsingh, brother of the viceroy, withdrew to his chiefship of Nágor in Jodhpur, and Azmat-ulláh went to Ágra. After his safe arrival in the Dakhan Bájráv Peshwa entered into an agreement

<sup>1</sup> See note on page 306.

with the Nizám under the terms of which the grants of Dholka, Broach, Jambugar, and Makbulábad were continued to the Nizám. Momin Khán received the farm of Petlád, and Kántáji was confirmed in the share he had acquired of the revenues of Gujarát. In A.D. 1732 the paymaster, Amánatálir Khán, died, and was succeeded by Ghulám Hasan Khan, who sent Mujahid-ud-dín Khán to act as his deputy. Through the influence of Mulla Muhammad Ali, Sohráb Ali was now confirmed as governor of Surat, and Mustafid Khán was obliged to return to Ahmedábád.

Piláji Gáikwár as the agent of the deceased Khandaráv Dálháde Senipáti, as the owner of the fort of Songad, and as the ally of the Bhils and Kolis, was naturally a thorn in the side of the viceroy Abheysingh. The recent acquisition of the town of Baroda and of the strong fortress of Dabhoi had made Piláji still more formidable. Under these circumstances, Abheysingh, who had long wished to recover Baroda and Dabhoi determined to assassinate Piláji, and this was effected by a Múrvádi at the holy village of Dákor. The Marathás slew the assassin and withdrew across the Mahi, burning the body of Piláji at the village of Sámoh or Saonh, fourteen miles north of Baroda. They then evacuated the district of Baroda, retiring to the fortress of Dabhoi. On hearing of the death of Piláji the viceroy immediately advanced against the Maráthás, and, after taking possession of Baroda, laid siege to Dabhoi. He failed to capture this fortress, and as the rainy season had set in and provisions were scarce, he was obliged to retire. He then went to Baroda, and after placing Sher Khán Bahi in charge of the city, returned to Ahmedábád. In this year, A.D. 1732, Gujarat was wasted by famine.

Meanwhile at Surat Múlla Muhammad Ali of Athva was again the cause of disturbance. Resisting with force the demand of a sum of £10,000 (Rs. 1 *lakh*) by Sohráb Khan, the governor of Surat, he succeeded in driving Sohráb Khán out of the city, and the government of Surat was then usurped by Teghbeg Khán, a brother of Beglar-Beg Khán. The success of the Múlla against Soráb Khán made him so forgetful of his position that he arrogated to himself all the emblems of the governor's office and wrote to the emperor asking a patent of the governorship of Surat in the name of his son Múlla Fakhr-ud-dín. The messengers bearing these communications were intercepted at Broach by the partisans of Teghbeg, who determined to remove this powerful cause of anxiety. Teghbeg Khán, inviting Muhammad Ali to an entertainment, placed him in confinement, and after keeping him in prison for two years, in A.D. 1734 put him to death. Teghbeg also took possession of the fort of Athva, and plundered it. Sohráb Khán, seeing that he could not recover Surat, went with Sayad Wali to Gogha, where his relatives lived, and from that, proceeding to Bhávnagar settled there. When the emperor heard what had happened, he appointed Momin Khán to Surat and Teghbeg Khán to Cambay. Momin Khán sent Sayad Núrullah to act for him, but he was defeated by Teghbeg Khán, who afterwards contrived, in A.D. 1733, to be formally appointed governor of Surat with the title of Bahádur.

### Chapter III.

#### Mughal Viceroy.

Muhammad Shah  
Emperor,  
1721-1748.  
MAHARAJA  
ABHEYSINGH  
Fifty-third  
Viceroy,  
1730-1733.

The Viceroy  
procures the  
Death of  
Piláji Gáikwár,  
1732;

and takes Baroda.

Famine,  
1732.

Affairs at Surat,  
1732.

Teghbeg Khán  
Governor of  
Surat.

## Chapter III.

**Mughal  
Viceroys.**

**Muhammad  
Shah**  
Emperor,  
1721-1748.  
**MAHARAJA  
RATANSINGH**  
Fifty-third  
Viceroy,  
1730-1733.

**RATANSINGH  
BHANDARI**  
Deputy Viceroy,  
1733-1737.

The Maráthás  
Return.

Contest for the  
government of  
Gogha.

Disturbance  
at Viramgám,  
1734.

Baroda  
recovered by the  
Maráthás,  
1734.

When Umábái, widow of Khanderáv Senápati, heard of the assassination of Piláji Gaikwár, she determined to avenge his death. Collecting an army and taking with her Kántáji Kaḷam and Dámají Gaikwár, son of Piláji, she marched upon Ahmedábád. As the Maráthás failed to do more than slay a Rájput leader named Jívaráj they came to terms. In the end it was agreed that in addition to the one-fourth and the one-tenth shares of the revenue a sum of £8000 (Rs. 80,000) should be paid from the Ahmedábád treasury, Jawán Mard Khán being kept as a hostage till the payments were made. For his services on this occasion Jawán Mard Khán was made governor of Viramgám. During this year an imperial order appointed Khushálchand Sheth, son of Sántidas, Nagar Sheth or chief merchant of Ahmedábád. The Maráthás plundered Itasúlábád a mile south of Ahmedábád and its excellent library was pillaged. Umábái now marched upon Baroda, and the governor, Sher Khán Bábi, prepared to oppose the Maráthás. But Umábái, sending a message to Sher Khán, explained that she had just concluded a peace with the Mahárája, and was suffered to pass unmolested. The emperor, satisfied with the arrangements made by the Mahárája, presented him with a dress of honour. In this year the Mahárája went to court by way of Jodhpur, and appointed Ratansingh Bhandári as his deputy, and the author of the *Mirát-i-Ahmedí* as news recorder. In the same year, A.D. 1733, Ghulám Muhy-ud-dín Khán, governor of Júnágadh died, and his son Mír Hazabr Khán was selected to fill his place.

Meanwhile as the Maráthás had not received their rights, Jádoji Dálháde, son of Umábái, returned to Gujarat. Peace was concluded on the former basis, and Jádoji marched into Sorath to exact tribute. In this year the Kóhs of the Chúnvál and Kánkrej committed many excesses, and a Rájput noble was robbed in the Pátan district. In the meantime Sohráb Khán, the former governor of Surat, who had been kindly received by Bhávsinghji the chief of Sihor, began to raise a following and was appointed collector of arrears in Sorath. He chose Sayad Núrullah as his deputy, and sent him to recover the revenue for the current year.

On the death of Salábat Khán Bábi, though the Mahárája had endeavoured to get Sher Khán Bábi appointed in place of his father, Gogha had been granted to Burhán-ul-Mulk, who chose Sohráb Khán as his deputy. At this time Sher Khán Bábi was at Baroda, and his younger brother, though he resisted, was compelled to leave Gogha. The deputy governor of Sorath complained to the governor of the oppressive conduct of Sohráb Khán. But Burhán-ul-Mulk supported Sohráb and having obtained for himself the government of Sorath, sent Sohráb Khán as his deputy to Júnágadh. In A.D. 1734, Ratansingh Bhandári, the deputy viceroy, who held in hatred Bhávsingh, son of Udaikaran, the hereditary officer of Viramgám, persuaded Jawán-Mard Khán to imprison him and send him to Ahmedábád. Jawán-Mard Khán went so far as to arrest Bhávsingh, but was forced by his supporters to release him.

In this year Sher Khán Bábi, governor of Baroda, went to visit his lands at Bálásinor, leaving Muhammad Sarbúz in command at Baroda,

Máhadáji Gaikwár, brother of Piláji, who then held Jambúsar, sending to Songad to Dámáji for aid, marched on Baroda with a strong force. The garrison made a brave defence, and Sher Khán hearing of the attack at Bálásinor, called for aid from Ratansingh Bhandári, the deputy viceroy, who directed Momín Khán, the governor of Cambay, to join Sher Khán and drive back the Maráthás. Sher Khán started at once for Baroda. But Máhadáji leaving a sufficient force before the town pushed on with the bulk of his army to meet Sher Khán, and, though he and his men fought bravely, defeated him, and then returned to Baroda, Sher Khán retiring to Bálásinor. Momín Khán, who arrived after Sher Khán's defeat, did not deem it prudent to engage the Maráthás, and retired to Cambay. In the meantime the garrison of Baroda, hopeless of succour, surrendered the town, and since that day Baroda has continued to be the head-quarters of the Gaikwár family.

Since Jawán Mard Khán's capture of Bhávsingh of Vírangám he had become much disliked. For this reason Ratansingh Bhandári, the deputy viceroy, transferred him to Kudi and Bijápúr, and in his place appointed Sher Khán Bábi, whose father Muhammad Salábat Khán, Bábi had been a popular governor of Vírangám. At this time Dhanuríp Bhandári, governor of Petlád, died, and the farm of the districts of Náhád, Arhar-Mátar, Petlád, and Mahadhra was given to Momín Khán. Mulla Muhammad Ali managed to write letters from his confinement at Surat to the Nizám; and as that chief was now not far from Surat, he wrote urgently to Teghbég Khan to release him. Teghbég Khán put the Mulla to death, and bribing the Nizám's messenger, gave out that he had died of joy at his release. Khushálchand, the chief of the merchants of Ahmedabád, having had a difference with Ratansingh, was forced to leave the city, and sought shelter at Cambay and afterwards at Júnágadh. Jawán Mard Khán, who was of an ambitious temperament, now conceived the design of conquering Ídar from Anand-singh and Ráisingh, brothers of the Mahárája Abheysingh. He accordingly marched upon Ídar, taking with him as allies Aghráji Koli of Katosan and Koli Anra of Elol Kánrah. In this strait Anand-singh and Ráisingh sought the aid of Malhárráv Holkár and Ránoji Sindia, who were at this time in Máliwa. The Maráthá chiefs at once marched to the help of Ídar, and Jawán Mard Khán, disbelieving the report of Maráthá aid, continued to advance until he found himself opposed by an overwhelming force. Negotiations were entered into, and Jawán Mard Khán agreed to pay a sum of £17,500 (Rs. 1,75,000). Of the total amount £2500 (Rs. 25,000) were paid at once, and Zoríwar Khán, brother of Jawán Mard Khán, and Ajabsingh, agent of Aghráji Koli, were kept as hostages until the balance should be paid. In this year Teghbég Khán of Surat caused a wealthy merchant named Ahmed Chalabi to be assassinated, and confiscated his property. He also caused a fanatic named Sayad Ali to be put to death by certain Afgháns, as he considered that he might excite sedition.

In the following year (A.D. 1735) Dholka was assigned to Ratan-singh Bhandári, and through the influence of Burhán-ul-Mulk, Sohráb

## Chapter III.

Mughal  
Viceroys.

Muhammad  
Shah  
Emperor,  
1721-1748.  
RATANSINGH  
BHANDÁRI  
Deputy Viceroy  
in charge,  
1733-1737.

Change of  
Governor at  
Vírangám.

Jawán Mard  
Khán fails in  
an attempt on  
Ídar.

Rivalry of Ratan-  
singh Bhandári and  
Sohráb Khan,  
1735.

Chapter III.

Mughal  
Viceroys.

Muhammad  
Shah  
Emperor,  
1721-1748.

RATANSINGH  
BHANDARI  
Deputy Viceroy  
in charge,  
1733-1737.

Battle of Dholi.  
Defeat and Death  
of Sohrab Khan,  
1735.

Rivalry between  
Ratansingh  
Bhandari and  
Momin Khan,  
1735.

MARATHA  
AFFAIRS.  
Dámaji Gaikwár  
and Kántaji,  
1735.

Battle of  
Anand-Mogri.  
Defeat of  
Kántaji.

Khán was appointed governor of Vírangám. Ratansingh resented this, and eventually Vírangám was conferred on the Mahárája Abheysingh. When this order reached Sohrab Khán, he forwarded it to Burhán-ul-Mulk, and in consequence of Burhán-ul-Mulk's remonstrances, the arrangements were changed and Sohrab Khán appointed governor. Upon this Sohrab Khán, leaving Sádak Ali as his deputy in Júnágadh, marched for Vírangám; while Ratansingh Bhandári, hearing of Sohrab Khán's approach, summoned Momin Khán and others to his assistance, and with his own army proceeded to Dholka and plundered Koth. From Koth he advanced and pitched at Harálah, about ten miles from Sohrab Khán's camp, and here he was joined by Momin Khán and others whom he had summoned to support him. After the union of these forces he marched to Dholi, six miles from Dhandhuka, at which place Sohrab Khán was then encamped. Ratansingh Bhandári now proposed that peace should be concluded, and that Sohrab Khán should enjoy Vírangám until final orders were passed by the emperor. Sáfdar Khán Bábi and others went to Sohrab Khán and endeavoured to bring him to consent to these terms, but he would not listen, and on both sides preparations were made for battle. During the following night Ratansingh Bhandári planned an attack on Sohrab Khán's camp. The surprise was complete. Sohrab Khán's troops fled, and himself, mortally wounded, shortly afterwards died. By the death of Sohrab Khán the family of Kázim Beg Khán became extinct. He was buried at Sihor in Káthiáváda.

After this success a single horseman attacked and wounded Ratansingh Bhandári in two places. The horseman was at once slain, but no one was able to recognize him. Ratansingh, who in two months had recovered from his injuries, now determined to attack Momin Khán, as that officer in the recent struggle had taken part with Sohrab Khán. Momin Khán hearing of Ratansingh's intentions, withdrew to Cambay. In the course of this year, on the expiry of the period of the farm of Mahudha, Arhar-Mátar, and Nadiad, these districts were transferred from Momin Khán to Sáfdar Khán Bábi. Kahanchand, a man of low origin, was appointed to Vírangám in place of Sher Khán Bábi, and instead of Sohrab Khán, Muhsin Khán Khálvi was made deputy governor of Sorath.

About this time Dámaji Gaikwár, who had been chosen by Umábái as her representative in Gujarát, appointed Rangoji to act as his agent. Kántaji being dissatisfied with this arrangement, in which his rights were ignored, marched into Gujarát. Rangoji met him, and a battle was fought at Anand-Mogri, twenty-five miles south-east of Kaira, in which Kántaji was defeated and his son killed. In consequence of this reverse Kántaji retired to Petlád. Momin Khán, who with his army was drawn up near Petlád to oppose Rangoji, was compelled to retire to Cambay, where peace was concluded on condition that Dámaji should receive the one-fourth share of the revenues of the country north of the Mahi. As the districts where these battles were fought were held in farm by Sáfdar Khán Bábi, he suffered much loss, and consequently retired to Rádhanpur. Rangoji was joined by Dámaji Gaikwár, and these two leaders went together to Dholka. While they

were there, Bhávsingh of Vírangám invited them to that town, both on account of the annoyance he suffered from the Márvádís and that he might take vengeance on the Kasbátís for the murder of his father Udaikaran. He accordingly treacherously admitted the Maráthás and slew Daulat Muhamínad Tánk, brother of the murderer of his father, and expelled the rest of the Kasbátís, while Kalián, the Márvádi administrator, was permitted to go to Ahmedábád. Leaving Rangóji at Vírangám, Dámáji marched into Sorath to levy tribute from the chiefs, and after collecting a portion of his dues, returned to the Dakhan. In the following year (A.D. 1736) Rangóji advanced as far as Bávla near Dholka wasting the country. Ratansingh Bhandári, the deputy viceroy, marched against him, and forced him to retire to Vírangám. Ratansingh pursued the Maráthás to Vírangám, attacked and defeated them capturing their baggage; but failed to prevent them taking shelter in the town. About this time some Maráthá horse who were at Sarnal, otherwise called Thássa, joined the Kolís of those parts, advanced with them against Kapadvanj and without any serious resistance succeeded in capturing the town. Meanwhile though Ratansingh had summoned Momín Khán to his aid, he delayed coming, as he began to scheme independence at Canday.

• Ratansingh Bhandári heard that Pratápráv, brother of Dímáji, and Deváji Takpar were advancing on Ahmedábád with 10,000 horse. At first he thought this a device to draw him from Vírangám, to whose walls his men had reached. On ascertaining from trusty spies that the report was true, he raised the siege of Vírangám, returned rapidly to Ahmedábád, and pushing forward to meet Pratápráv, exacted tribute from the chiefs on the banks of the Vátrak. As Pratápráv drew near, the governor of the Bhil district retired before him, and he continuing his advance, passed through Valad and Pethápur, and so by way of Chhála reached Dholka. Here through Muhammad Ismaíl, the governor of Dholka, he demanded from the Bhandári his share of the revenue. Afterwards, leaving 2000 horse in Dholka, he went to Dhandhúka. In the meantime Kántáji, who was a follower of Bajráv Peshwa, joining with Malháráv Holkar, advanced upon Idar, and coming against Danta, plundered that town. Some Nágur Bráhmans of the town of Vadnagar, who were settled in Danta, tried to escape to the hills, but were intercepted and pillaged. The Maráthás then proceeded to Vadnagar and plundered the town. From Vadnagar they went as far as Palanpur, where Pahar Khán Jhálóri, being unable to oppose them, agreed to pay a tribute of £10,000 (Rs. 1. *lakk*). Kántáji and Malháráv Holkar then marched into Múrwár, while Pratápráv and Rangóji crossed over from Dhandhúka into Káthiávada and Gohilváda. About this time Muhammad Pahár Khán Jhálóri was appointed deputy governor of Pátan on behalf of Vakhatsingh. As no settlement of his demands on the revenues of Dholka had yet been made, Pratápráv returned to that town and sent Narhar Pandit to receive the tribute due to him. Afterwards proceeding to Baroda with Rangóji they were summoned to Sorath by Dámáji to assist him. • Sher Khán Bábi, who up to his time had been at Kaira, now came to Ahmedábád, and as the deputy viceroy

## Chapter III.

Mughal  
Viceroys.

Muhammad  
Shah  
Emperor,  
1721-1748.

RAFANSINGH  
BHANDARI  
Deputy Viceroy  
in charge,  
1733-1737.

The Maráthás  
help Bhávsingh  
to expel the  
Vírangám  
Kasbátís.

The Garkvár  
and Peshwa  
plunder the  
Country.

## Chapter III.

Mughal  
Viceroys.Muhammad  
Shah  
Emperor,  
1721-1748.MOMIN KHAN  
Fifty-fourth  
Viceroy,  
1737.

was displeased with Momin Khán's conduct when Viramgám was besieged, he appointed Sher Khán his own deputy at Petlád, Arhar-Mátar, and Nadiád. Afterwards on Momin Khán's remonstrance Subháchand Márvádi was appointed to examine the accounts and receive the revenue in place of Sher Khán. In A.D. 1737 Dánáji's brother Prátápráv, returning to his country after exacting tribute from the chiefs of Sorath, died of small-pox at Kámkar near Dholka. Momin Khán seeing that Sher Khán had not yet left Kara, collected some men and came to Petlád, while Sher Khán went to Dehgám and awaited the departure of Rangoji. Ratansingh Bhandari made preparations to help Sher Khán and Momin Khán returned to Cambay.

At this time as the Mahárája Abheysingh was not in favour at court, Momin Khán was appointed fifty-fourth viceroy. As he was unable to effect anything by himself he persuaded Jawán Mard Khán Babi to join him by a promise of the government of Pátan and directed him to proceed and take up that appointment. Now the Jhaloris were allies of the Ráthods, and Pahir Khán Jhalori, then in command of Pátan, opposed Jawán Mard Khán, but was finally obliged to vacate Pátan. Momin Khán, who had not hitherto produced the order appointing him viceroy, now made it public and began to act as viceroy with the title of Najm-ul-daulah Momin Khán Bahádur Firúz Jang, and in A.D. 1737 sent a copy of this order to Abdúl Husain Khán, the deputy minister, and to Mustafid Khán, who held the office of Kázi.

Sher Khán Babi, wishing to remain neutral, retired to Balásinor and Momin Khán summoned Rangoji, who was in the neighbourhood of Cambay, to his assistance. Rangoji agreed to aid him in expelling the Márvadis, on condition that, if successful, he should be granted one-half of the produce of Gujarát except the city of Ahmedábád, the lands in the neighbourhood of the city, and the port of Cambay. This disastrous alliance with the Maráthás gave the last blow to Mughal power in Gujarát, which otherwise might have lingered for at least a quarter of a century. Momin Khán lived to repent his conduct.

When Ratansingh Bhandari heard of the appointment of Momin Khán to be viceroy he wrote to Mahárája Abheysingh for orders. Meanwhile he sent Muhammadan officials to Cambay to persuade Momin Khán to take no further steps until a reply should be received to the reference Momin Khán had made to Agra. The reply of the Mahárája was that Ratansingh should resist Momin Khán if he could. Ratansingh prepared to defend Ahmedábád while Momin Khán collecting an army, camped at the Náransar lake.

From the Náransar lake where Momin Khán remained encamped for one and a half months collecting his partisans he advanced to Sojitra, where he was joined by Jawán Mard Khán Babi; and proceeding together they came to Vasu under Petlád, about twenty-six miles from Ahmedábád, and from Vasu to Kaira, about eighteen miles from the capital. At Kaira they encamped on the banks of the Vátrak, where, owing to the incessant rain, they were forced to remain for about a month. When the rain abated and the rivers were fordable, Momin Khán, moving to Ahmedábád, encamped in front of the city

on the Kānkariya tank and prepared for a siege. About the same time Momín Khán's manager, Vajerám, whom he had sent to Songad to solicit Dámáji to march in person to his assistance, arrived and informed him that Dámáji would join him shortly. Zoráwar Khán, who had been left at the Maratha camp as security for the payment of the tribute, was recalled, and instead the district of Parántij was formally assigned to the Maráthás in payment of their demands. Some of the Mahārāja's guns, which were being sent to Ahmedábád by his agents at Surat through Cambay for facility of transit, were about this time captured by a party of Momín Khán's men. When Ratansingh Bhandari wrote to the Mahārāja of Momin Khán's advance on Ahmedábád, the Mahārāja was much displeased, and went from thence to the emperor's presence in anger. The nobles fearing the consequences, recalled him, and persuaded the emperor to re-appoint him viceroy of Gujarát.

Momín Khán was secretly enjoined to disregard the Mahārāja's appointment and persevere in expelling the Ráthods, and was assured of the emperor's approbation of this line of conduct. He therefore continued to prosecute the siege with vigour. In the meantime another order was received from the imperial court, confirming the reappointment of the Mahārāja and appointing Fidá-ud-dín Khán to guard the city with 500 men, directing also that Momín Khán should return to Cambay. It was further stated that, as Ratansingh Bhandari had acted oppressively, some other person should be appointed deputy to fill his place, and that in the meantime a Rájput noble, named Abhaikaran, was to carry on the government. Shortly before this Muhammad Bákir Khán, son of Muázzam Khán, joined Momín Khán from Surat, while Sadik Ali Khán and his nephew reinforced him from Junágadh. When Momín Khán was informed of the purport of the imperial order he agreed to return to Cambay, provided Ratansingh Bhandari would quit the city, hand over charge to Abhaikaran, and admit Fidá-ud-dín Khán and his men into the city.

Ratansingh Bhandari determined not to leave the city, and prepared to defend himself to the last. Dámáji Gaikwár now joined Momín Khán from Songad. Momín Khán met Dámáji at P'sampur, three miles from Ahmedabad, and made great show of friendship, calling him his brother. When Ratansingh Bhandari heard of the arrangements made between Dámáji and Momín Khán, he sent a message to Dámáji saying, 'Momín Khán has promised Rangoji half of the revenues of Gujarát excepting the city of Ahmedabad, the lands immediately round it, and Cambay. If you will join me, I will give you half of everything not excepting the city nor Cambay, and will send to your camp some of my chief landholders as security if you agree.' Dámáji showed this to Momín Khán, and asked him what he proposed to do. Momín Khán now perforce agreed to do the same; but instead of Cambay offered to make over to the Maráthás the whole district of Viramgám. Dámáji, accepting these terms, ceased to negotiate with Ratansingh. He then went on pilgrimage to Dádésar, and returning in the same year, A.D. 1738, he and Rangoji began active operations against Ahmedábád. Their bombardment did so much

### Chapter III.

#### Mughal Viceroys.

Muhammad  
Shah  
Emperor,  
1721-1748.  
Momin Khan  
Fifty-fourth  
Viceroy,  
1737.

Lays Siege to  
Ahmedabad.

MAHARAJA  
ARHYSINGH  
Fifty-fifth  
Viceroy,  
1737.

Momin Khan  
continues the  
Siege of  
Ahmedabad.

Defence of the  
City by  
Ratansingh  
Bhandari.

## Chapter III.

Mughal  
Viceroys.

Muhammad  
Shah  
Emperor,  
1721-1748.  
MAHARAJA  
ARHYSINGH  
Fifty-fifth  
Viceroy,  
1737.

Momín Khán  
captures  
Ahmedabad,  
1738.

MOMÍN KHÁN  
Fifty-sixth  
Viceroy,  
1738-1743.  
Prosperity of  
Ahmedabad,  
1738.

damage to the city that Momín Khán repented having called them to his aid, and foresaw that if the Maráthás once gained any portion of the city it would be no easy matter to drive them out. Momín Khán now sent the writer of the *Mirāt-i-Ahmedi* to Ratansingh Bhandári, in hopes that he might withdraw peaceably, but Ratansingh refused to listen to any terms. After some time the Musalmáns under Kázim Ali Khán and others, and the Maráthás under Bábnráv endeavoured to take the city by storm, but after a bloody contest were forced to retire. Next day Ratansingh, seeing that he could not long hold the city, entered into a negotiation with Momín Khán, and, on receiving a sum of money for his expenses, and on being allowed to retire with the honours of war, left the city.

Momín Khán entered Ahmedábád. On the capture of the city, in accordance with Momín Khán's engagement, half of it was handed to the Maráthás. Momín Khán sent news of what had taken place to the emperor, and appointed Fida-nd-dín Khán his deputy. Dámáji, who in the meantime had been to Sorath, now returned and was met by Rangoji, who accompanied him as far as the banks of the Mahi, whence Rangoji proceeded to Dholka. After spending a few days at Dholka, Rangoji returned to Ahmedabad and took charge of his share of the city, which comprised the Rákhra, Khánjehán, and Jamálpur quarters as far as the Astoria and Raipur gates. The city was thus equally divided, and the Astoria and Raipur gates were guarded by the Maráthas. At that time the inhabitants of Ahmedábád were chiefly Muhammadans, and the Maráthás, accustomed to extortion, attempting to oppress them, they rose against the strangers, and after a severe affray expelled the greater part of them from the city. Momín Khán, though secretly pleased, affected ignorance and sent Fida-nd-dín Khán to reassure Rangoji. This with some difficulty he succeeded in doing and Rangoji remained in the city. Jawán Mard Khán was sent to Pátan, and, instead of Parántij, the district of Kherálu was granted to Zoráwar Khán Bábi.

With the cessation of Marátha oppression, Ahmedábád began to recover its splendour and opulence. The emperor was much pleased with Momín Khán, and, raising his rank, presented him with a dress of honour, a sword, and other articles of value. At the close of the rainy season Momín Khán went to levy tribute from the chiefs on the banks of the Súbarmati, and Rangoji was asked to accompany him. They marched to Adálaj whence Fida-nd-dín Khán, the deputy viceroy, returned to the city accompanied by Dámáji as deputy of Rangoji. Jawán Mard Khán and Sher Khán Bábi now joined the viceroy's camp, and, about the same time Hathising, chief of Pethápur, paid a visit to the viceroy and settled his tribute. From Adálaj they advanced to Mánasa, and were met by the Mánasa chief. From Mánasa they proceeded to Kadi, and from Kadi to Bījápur. After Momín Khán left the people of Ahmedábád were badly treated, and Rangoji, leaving his brother Akoji in camp, returned to the capital, whence he marched towards Víramgám and Sorath. Momín Khán went from Bījápur to Ídar, and there levied tribute from the chiefs of Mohanpur and Ranasau.

When Momín Khán arrived at Idar, Anandsingh and Ráisingh, brothers of Mahárája Abheysingh, went to him and paid the tribute of Mohanpur and Ranásan as being within the limits of the Idar territory. The matter was amicably settled, and the two brothers accompanied the viceroy as far as the Idar frontier, where Anandsingh returned to Idar, and Ráisingh, at Momín Khán's request, remained with him, Momín Khán undertaking to pay the expenses of his men. Prathiraj, the chief of Mánasa, agreed to pay £2300 (Rs. 23,000) and the chief of Varsola £1000 (Rs. 10,000) as tribute. At this time Sher Muhammad Khán Bábi was appointed to succeed Mír Dost Ali as deputy governor of Sorath. The Maráthas, who had attempted to deprive some of the Rasúlábád and Batwa Sayads of their land, were attacked by the Muhammadan population, and a few men were wounded on either side. Momín Khán, receiving tribute from various chiefs, had now reached Palanpur, and Páhar Khán Jhálari, the governor of that place, was introduced to the viceroy by Sher Khán Bábi. As news was now received that Deváji Tákpar was advancing through the Baroda districts, Momín Khán marched towards Ahmedábád, dismissing Páhar Khán Jhálari on the Palanpur frontier. Jawán Mard Khán Bábi, appointing his brother Saldar Khán Bábi as his deputy at Patan, pushed forward in advance for Ahmedábád. Mámúr Khán, who had been chosen by Mír Huzabr Ali as his deputy in Sorath, now arrived and complained to Momín Khán regarding Sher Khán Bábi's appointment. Momín Khán said that, as neither had assumed charge of their duties, they should await final orders from the emperor. He then advanced to Hájipur, and thence encamped on the side of the city near Bahrámpur and occupied himself in strengthening the city defences. From that camp he proceeded to Ísanpur four miles south of Ahmedábád on his way to levy tribute from the Koli chiefs of the banks of the Vátrak. After this he proceeded to Kúlej on the Vátrak and levied tribute from the Koli chiefs of that neighbourhood. Hearing that Dámáji had left Songad, and crossing the Mahi had gone to Arís, Momín Khán struck his camp and returned to the city, while Dámáji going to Dholka marched from that to Sorath. Momín Khán now permitted Sher Khán to return to his lands in Gogha, whence he proceeded to Júnagadh and took charge of the office of deputy governor.

In 1738, Mír Huzabr Khán, the governor of Sorath, died, and as Sher Khán had occupied Júnagadh, and taken into his employ all the troops of Mír Dost Ali, Mámúr Khán was obliged to resign his pretensions and return. The emperor now appointed Himmat Ali Khán, nephew of Momín Khán, governor of Sorath, and he wrote to his uncle to choose a fitting deputy. Momín Khán, as the Marátha incursions into Sorath increased yearly, and as Sher Khán Bábi was a man able to hold his own with them, suffered him to remain as deputy. When Dámáji returned to Víramgám, after levying tribute from the chiefs of Sorath, he was obliged to march against Kánji Koli, the chief of Chhaniár in the Chhúnvál. As he could not prevail against them he was forced to call on Momín Khán for aid. Momín Khán sent Fidá-ud-dín Khán at the head of a well-equipped army. On their approach the

## Chapter III.

Mughal  
Viceroys.

Muhammad  
Shah  
Emperor,  
1721-1748.  
Momín KHÁN  
Fifty-sixth  
Viceroy,  
1738-1743.

The Viceroy  
collects Tribute,  
1738.

Sher Khán Bábi  
Deputy Governor  
of Sorath,  
1738.

## Chapter III.

Mughal  
Viceroys

Muhammad  
Shah  
Emperor,  
1721-1748.

Momin Khan  
Fifty-sixth  
Viceroy,  
1738-1743.

The  
Deputy Viceroy  
collects tribute,  
1739.

Kolis fled, and the village was burned, and Fidá-ud-dín Khán returned to the capital. Dámáji, leaving Rangoji as his deputy, returned to Songad. In this year, A.D. 1738, Hindustán was invaded by the great Persian Nádir Sháh, Delhi sacked, and the emperor made prisoner. Except that coin was struck in Nádir's name, the collapse of Mughal power caused little change in Gujarát.

In A.D. 1739 Fidá-ud-dín Khán was sent to levy tribute from the chiefs on the banks of the Sábarmati, and, accompanied by Jawán Mard Khán Babi and Rája Raisingh of Idar, marched to Charárah. As the village of Pánnal under Bijápur had been assigned to the author of the *Murát-i-Ahmedi*, he accompanied Fidá-ud-dín Khán, who marched to Ahmednagar, and demanded tribute from Jitsingh of Mohanpur and Ramísan. Jitsingh resisted and a doubtful battle was fought. Next day Fidá-ud-dín Khán changed his position and again attacked Jitsingh, who being defeated agreed to pay £1000 (Rs 10,000). They then went to Idar, where they were hospitably received by Rája Raisingh, who presented the leaders with horses. From Idar they proceeded to Vadnagar, which was under Jawán Mard Khán, who also received them courteously and presented horses. The army then marched to Visalnagar. On the arrival of the troops at Visalnagar, Jawán Mard Khán requested Fidá-ud-dín Khán to subdue Jámáji the Koli chief of Thara-Jámpur in the Kámkrej, who was then at Bálisúna under Pátan and who was continually plundering the country. Fidá-ud-dín Khán marched to Bálisúna, but Jámáji fled to Thara-Jámpur without risking a battle and the Muhammadans plundered Thara-Jámpur. From Bálisúna Fidá-ud-dín marched to Kadi, and allowing Jawán Mard Khán to return to Patan proceeded to Ahmedabád.

At Ahmedábád disputes between Rangoji and Momin Khán regarding the government of the city were frequent. In one serious disturbance Momin Khán was worsted and forced to sue for peace and grant Rangoji his half share both in the government and revenue, which, since the affray in A.D. 1738, Momin Khán had withheld. A formal agreement was drawn up but did not long remain in force. About this time Momin Khán's nephew Muhammad Momin Khán Bakhshi received a patent granting him the title of Nazar Ali Khán. The year A.D. 1739 was marked by a disastrous flood in the Sábarmati. In this year also the Marathas under Chimmaji Apa achieved the memorable success of taking the fort of Bassein from the Portuguese.

Capture of  
Bassein by  
the Marathas,  
1739.

Tribute  
Expedition,  
1740

In A.D. 1740 on his return from Sorath, Dámáji Gaikwár took Rangoji to the Dakhan and appointed Mulhárráv Khúni his deputy at Ahmedabád. Fidá-ud-dín Khán met the new deputy at Isampur and escorted him to the city. Shortly after Fidá-ud-dín Khán and Nazar Ali Khán started to collect tribute, and Jawán Mard Khán sent his brother Zorávar Khán Babi to accompany them. They advanced against Dábhora under Bahyal eighteen miles east of Ahmedábád in the Bhil district and fought with the chief, who agreed to pay tribute. Thence they went to Atarsumba, where the Kolis after a vain attempt to carry off their cannon agreed to pay tribute. The force then proceeded to Mándva and levied a contribution from the Mándva chief. They next went to Kapadvanj, and passing

through Bálásinor reached Vírpur under Lamáváda. Here, from Sultánsingh, agent of the Lamáváda chief, they received two horses and £300 (Rs 3000) as tribute. While at Lamáváda an order of recall came from Momín Khán, who intimated that Malharráy Khúm had laid up large stores of grain and contemplated war. Fídá-ud-dín Khán at once pushed forward through Bálásinor and Kapadvanj, advancing rapidly towards the capital. On the way he received a second despatch from Momín Khán saying that, as the risk of war had for the present passed, they should advance to Petlad, where they would find Malharráy Khúm and settle with him about the revenue accounts. They continued their march, and in two days reached Kara, being joined on the way by Muhammad Kúh Khán, who was charged with messages from Momín Khán. At Kara they found Muhammad Husam, nephew of Fídá-ud-dín Khán who had been sent with a force to Mahodha. As Malharráy Khúm was at Púj near Kara, Fídá-ud-dín Khán expressed a wish to meet him, and it was agreed that both sides should go to the Petlad district and there settle the disputed collections. Shortly after they met and arrangements were in progress when the Kols of the Bhil district rebelled and Abdúl Husam Khán and Vajerám were sent against them. After burning two or three villages this detachment rejoined the main body, and not long after all returned to Ahmedabád. During A.D. 1740 Bajiráv Peshwa died.

In A.D. 1741 Momín Khán went to Cambay, and while residing at Ghinspur near that city received information that Damaji had again appointed Rangoji his deputy in place of Malharráy Khémí, and shortly after Rangoji arrived at Petlad. At this time Momín Khán turned his attention to the falling off in the customs revenue of Cambay and appointed Ismaíl Muhammad collector of customs. As he was anxious to clear some misunderstanding between Rangoji and himself, Momín Khán set out to visit Rangoji and assure him of his good wishes. At this time Bhávsingh of Víramgám, who found the Maráthas even more troublesome than the Muhammadans, as soon as he heard of Malharráy's recall, suddenly attacked the fort of Víramgám and with the aid of some Arabs and Rohillas expelled the Marátha garrison and prepared to hold the fort on his own account. Shortly after Rangoji demanded that a tower in Ahmedabád, which had been raised a story by Momín Khán so as to command the residence of the Marátha deputy at the Jamálpur gate, should be reduced to its original height. At the same time he suggested that Momín Khán and he, uniting their forces, should advance and expel Bhávsingh from Víramgám. Momín Khán agreed to both proposals. The addition to the tower was pulled down, and Momín Khán and Rangoji, marching against Víramgám, laid siege to the town. Bhávsingh made a gallant defence, and Momín Khán, who was not sorry to see the Maráthas in difficulties, after a time left them and marched to Kadi and Bijápur to levy tribute. Rangoji continued the siege, and as Bhávsingh saw that even without Momín Khán the Marátha army was sufficient to reduce the place, he agreed to surrender Víramgám, provided the fort of Pátdi and its dependent villages were granted

**Chapter III.****Mughal  
Viceroys.**

Muhammad  
Shah  
Emperor,  
1721-1748.  
MOMÍN KHÁN  
Fifty-sixth  
Viceroy,  
1738-1743.

The Viceroy  
at Cambay,  
1741.

Bhávsingh  
surrenders  
Víramgám  
and receives  
Pátdi.

## Chapter III.

Mughal  
Viceroys.Muhammad  
Shah

Emperor,

1721-1748.

MOMIN KHAN

Fifty-sixth

Viceroy.

1738-1743

Siege of Broach  
by the Maráthas,  
1741.Battle of Dholka,  
Defeat of the  
Maráthas,  
1741.Contests between  
the Muhammadans  
and Maráthas.

to him. Rangoji agreed, and thus the Maráthas again obtained possession of Viramgám, while Bhávsingh acquired Pátdi,<sup>1</sup> a property which his descendants hold to this day.

When Momín Khán arrived at Mánsa, about twenty-six miles north-west of Ahmedábád, hearing that Dámáji had crossed the Mahi with 10,000 men, he at once returned to the capital. Dámáji arrived at Mánsa and besieged it. The chiefs and Kolis defended the place bravely for about a month, when it fell into Dámáji's hands, who not only cleared the prickly-pear stockade which surrounded it, but also burned the town. From Mánsa Dámáji marched to Sorath. On his return he laid siege to Broach, a fort which, from its natural strength as well as from its favourable position on the Narbáda, it had been the constant ambition both of Dámáji and of his father, Píláji to capture. On the approach of Dámáji, Nek Alam Khan, who held the place in the interests of the Nizam, prepared to defend the fort, and wrote to the Nizam for aid. In reply the Nizam warned Dámáji not to attack his possessions. On receiving this letter Dámáji raised the siege and returned to Songad. It seems probable that concessions were made to tempt Dámáji to retire from Broach, and that the Gáikwár's share in the Broach customs dates from this siege.

\* In A.D. 1741 in a battle between Káim Kúli Khán, governor of Dholka, and Rangoji's deputy, the Maráthas were defeated. Momín Khán, at the request of Rangoji, made peace between them. Fidá-ud-dín Khan, who had recently been raised in rank with the title of Bahádur, starting to collect tribute burned down the refractory Koli village of Dabhora, and placing a post there, passed to Satmbla, Balasoor and Thasra. After the battle at Dholka, the building by Rangoji of the fort of Borsad, caused renewed fighting between the Muhammadans and Maráthas of Dholka. At the request of Muhammad Hadi Khán, governor of Dholka, Fidá-ud-dín Khán, passing through Mahudha to Petlad pushed forward to help him. In the meantime a battle was fought, in which the Maráthas under Malháráy attacked Muhammad Hadi Khán, and after a short contest withdrew. Next day the Muhammadans, strengthened by the arrival of Fidá-ud-dín Khan, besieged Sojitra. A letter was written to Rangoji, asking the meaning of the attack, and he replied excusing himself and attributing it to the ignorance of Malháráy. Muhammad Hadi Khán and the author of the *Mirát-i-Ahmedí* eventually met Rangoji at Borsad, and settled that he and Fidá-ud-dín Khán should come together and arrange matters. But Rangoji in his heart intended to fight and wrote to his deputy Rámáji at Ahmedábád to be ready for war. Malháráy now joined Rangoji at Borsad. At this time many misunderstandings and several fights between the Maráthas and the Muhammadans were appeased by Momín Khán and Rangoji, who; in spite of the ill-feeling among their subordinates and a certain distrust of each other's designs, appear throughout to have maintained a warm

<sup>1</sup> Pátdi (north latitude 23° 10'; east longitude 71° 44'), at the south east angle of the Rau of Cutch, fifty-two miles west of Ahmedábád.

mutual regard. Dāmāji from his stronghold at Songad was too much occupied in Dakhaṇ politics to give much attention to Gujarāt. Rangoji, on the other hand, gained so much influence with the Gujarāt chiefs, that at one time he succeeded in engaging Sajasingh Hazārī in his service, and also induced Rāja Raisingh of Idar to join him. But Momīn Khān detached Raisingh from this alliance, by placing him in charge of the post of Anālīra and granting him the districts of Modasa, Meghrej, Ahmednagar, Parantij, and Harsol. Moreover the customary Gujarāt sum at first sent daily by Rangoji to Rāja Raisingh for the expenses of his troops had begun to fall into arrears. Rāja Raisingh made his peace with Momīn Khān through the mediation of Nazar Ali Khān, Momīn Khān's nephew, who appears to have been one of the leading spirits of the time.

In A.D. 1712 in another fight between the Marāthās and Muhammadans in Ahmedābād, the Muhammadans gained a slight advantage. After this Rangoji left the city, appointing as before Dāmāji as his deputy, and joining Jagjiwan Pavar went to Borsad, where he had built a fort. At this time one Jivandas came with authority from the Nizām to act as collector of Dholka part of the lands assigned to the Nizām as a personal grant, but failed to enforce his position. Shortly after this Rāja Anand-sing of Idar was killed, and his brother Raising, taking leave, went to Idar to settle matters. Momīn Khān had his patent increased to the personal rank of commander of 6000 with a contingent of 6000 cavalry. He received a dress of honour, a jewelled turban, a plume, six pieces of cloth, an elephant, the order of Mahi-maratib,<sup>1</sup> and the title of Najm-ud-daulah Momīn Khān Bahādūr Dilawar Jang. Differences again broke out between Momīn Khān and Rangoji, and again matters were settled by a friendly meeting between the two chiefs at Borsad, where Rangoji had taken up his residence. Momīn Khān now went to Petlad, and from that to Cambay, where he was taken ill, but after six weeks came to Vasu, where Rangoji visited him. Here though again unwell he went to Dholka, and shortly afterwards he and Rangoji marched upon Limbdi, which at this time is mentioned as under Virāngam. While before Limbdi, Rangoji was summoned by Dāmāji to help him against Bāpu Nāik, and at once started to his assistance. Momīn Khān now marched into Gohlvād and proceeded by Lohāna to Gogha, then made the charge of a resident deputy of Sher Khān Babi. Here he received tribute from the chief of Sihor, and from that, marching into Hālār, went against Navānagar. The Jām resisted for twenty days, and eventually, on his agreeing to pay £5000 (Rs. 50,000) as tribute, Momīn Khān returned to Ahmedābād. During his absence in spite of stubborn resistance Nazar Ali Khān and Vajerām had collected tribute from the Koli chiefs. Rangoji, who had now left Dāmāji, joined battle with Bāpu Nāik ere he crossed the Mahi, and Bāpu Nāik turned back. Rangoji therefore remained at Borsad, but hearing that Momīn Khān's illness had become serious, he went once or twice to Ahmedābād to visit him.

### Chapter III.

#### Mughal Viceroys.

Muhammad  
Shah  
Emperor,  
1721-1748.  
MOMIN KHAN  
Fifty-sixth  
Viceroy,  
1738-1743.

Disturbance at  
Ahmedabad,  
1742.

The Viceroy  
collects Tribute  
in Kathiawar.

<sup>1</sup> The Mahi-maratib was a banner having the likeness of a fish at its top.

## Chapter III.

Mughal  
Viceroys.

Muhammad  
Shah  
Emperor,  
1721-1748.

Death of Momín  
Khán,  
• 1713.  
Fida-ud-din  
acts as Viceroy,  
1743.

Muftakhr Khán  
Defeats the  
Marathas

Damaji Gaikwar  
Returns to  
Gujarat.

Abdúl Azíz  
Khán  
• of Junnar,  
Viceroy  
(by a forged  
order).

Mutiny of the  
Troops.

In A.D. 1713 Momín Khán died. His wife, fearing lest Fida-ud-dín Khán and Muftakhr Khán, Momín Khán's son, would deprive her of her estate, sought the protection of Rangoji. In the meantime Fida-ud-dín Khán and Muftakhr Khán received an imperial order to carry on the government until a new viceroy should be appointed. At this time a man named Anandram, who had been disgraced by Momín Khán, went over to Rangoji and incited him to murder Fida-ud-dín Khán and Muftakhr Khán. Rangoji with this intention invited them both to his house, but his heart failed him, and shortly afterwards Fida-ud-dín Khán went to Cambay. Rangoji now determined at all hazards to assassinate Muftakhr Khán. With this object he took Muftakhr Khán's associates, Vajgrám and Kám Kúli Khán, into his confidence. Muftakhr Khán accidentally heard of his designs, and remained on his guard. As Rangoji had failed to carry out his promise to raise Sher Khán Bábí to the post of deputy viceroy, Sher Khán advanced to Dholka and began plundering some Cambay villages. Rangoji, after another futile attempt to assassinate Muftakhr Khán, sent for his deputy Rámóji, who was then in the neighbourhood, and prepared to fight. Muftakhr Khán, on his part, summoned Fida-ud-dín Khán from Cambay, and in a few days they succeeded in uniting their forces. Sher Khán Bábí deserting the cause of Rangoji, the Maráthás were worsted and Rangoji's house was besieged. Rangoji, being hard pressed, agreed to give up Anandram and to surrender both Borsad and Virámgam, Sher Khán Bábí becoming his security. In this way Fida-ud-dín Khán became sole master of Gujarat.

Shortly after Dámóji Gaikwar returned from Satara and came to Cambay. In the meantime Rangoji, who had been living with Sher Khán Bábí, his security, contrived, with the connivance of Sher Khán, to escape together with his family. Fida-ud-dín Khán was so greatly enraged with Sher Khán for this treachery, that Sher Khán leaving Ahmedábád on pretence of hunting, escaped to Balasmor, where his wife joined him. Fida-ud-dín Khán put Anandram to death, while Rangoji through the aid of Sher Khán Bábí's wife, made good his escape to Borsad. Fida-ud-dín Khán had set out to collect tribute, when news arrived that Khanderao Gaikwar, brother of Damaji had crossed the Mahi and joining Rangoji had laid siege to Petlad. On hearing this, Fida-ud-dín at once returned to Ahmedábád, and sent Valabhdas Kotwál to Khanderao to complain of the misconduct of Rangoji.

After the death of Momín Khán, Jawán Mard Khán Bábí was the greatest noble in Gujarat. He began to aspire to power, and Fida-ud-dín, who was not good in the field, had thoughts of appointing him as a deputy. While matters were in this state, and Jawán Mard Khán was already laying claim to the revenue of the district round Ahmedábád, an order was received appointing Abdúl Azíz Khán the commander of Junnar, near Poona, to be viceroy of Gujarat. This order was forged by Abdúl Azíz Khán in Jawán Mard Khán's interests, whom he appointed his deputy. Though Fida-ud-dín Khán doubted the genuineness of the order, he was not powerful enough to remove Jawán Mard Khán, who accordingly proclaimed himself deputy viceroy. At this time the troops, clamorous on account of arrears,

placed both Fidá-ud-dín Khán and Muftakhir Khán under confinement. Jawán Mard Khán assumed charge of the city and stationed his own men on guard. While Fidá-ud-dín Khán and Muftakhir Khán were in confinement, Khanderáy Gáikwár sent them a message that if they would cause the fort of Petlád to be surrendered to him, he would help them. To this they returned no answer. Fidá-ud-dín Khán now entreated Jawán Mard Khán to interfere between him and his troops. Jawán Mard Khán accordingly persuaded the mutineers to release Fidá-ud-dín Khán, who eventually escaped from the city and went to Agra.

Meanwhile Rangoji continued to press the siege of Petlád and the commander, Agha Muhammad Husam, after in vain appealing for help to Jawán Mard Khán, was forced to surrender. Rangoji demolished the fort of Petlád and marched upon Ahmedabad. As he approached the city Jawán Mard Khan sent the writer of the *Mirát-i-Ahmed* and Ajabsingh to negotiate with Rangoji, who demanded all his former rights and possessions.

News had now reached Delhi that a false viceroy was governing Gujarát, and accordingly Muftakhir Khán was chosen fifty-seventh viceroy, the order explaining that Abdúl Azíz had never been appointed viceroy, and directing Jawán Mard Khán to withdraw from the conduct of affairs. Muftakhir Khan was perplexed how to act. He succeeded in persuading his troops that he would be able to pay them their arrears, and he sent a copy of the order to Jawán Mard Khán; and, as he dared not displace him, he informed Jawán Mard Khán that he had appointed him as his deputy, and that he himself would shortly leave Ahmedabad. Jawán Mard Khan, so far from obeying, ordered Muftakhir Khán's house to be surrounded. Eventually Muftakhir Khán, leaving the city, joined Rangoji, and then retired to Cambay.

Khanderáy Gáikwár returned, and, with the view of enforcing his claims, uniting with Rangoji, marched to Banjar, about five miles south of Ahmedabad. Jawán Mard Khán issuing from the city camped near the Kankariya lake. Nanhar Pandit and Krishnáji on behalf of the Maráthha leaders were sent to Jawán Mard Khán to demand their former rights and possessions. Jawán at first refused, but in the end gave way and the Maráthhas appointed Dadu Morár deputy of the city. Sher Khán Babi now returned to Bálásnor. Khanderáy and Kanáji then went to Dholka. Rangoji to Petlád, and Khanderáy Gáikwár to Sorath. Fidá-ud-dín Khán requested Rangoji to help Muftakhir Khán; he replied that he was willing to help him, but had no money. Rangoji then accompanied Fidá-ud-dín Khán to Cambay, where Muftakhir Khán was. Negotiations were entered into, and the Kháns tried to collect £10,000 (Rs. 1 *lakh*) which Rangoji asked for to enable him to make military preparations to aid them. They raised £8000 (Rs. 80,000) with great difficulty and admitted Rangoji's Náib to a share in the administration. Rangoji withdrew to Borsad with the £8000 (Rs. 80,000) under the pretext that when the remaining £2000 (Rs. 20,000) were paid he would take action. Fidá-ud-dín Khán, annoyed at Rangoji's conduct, went to reside at Dhowan, a village belonging to Jálam Jáha Koli.

## Chapter III.

Mughal  
Viceroys.

Muhammad  
Shah  
Emperor,  
1721-1748.

Maráthas  
Capture  
Petlád

MUFTAKHIR  
KHAN  
Fifty-seventh  
Viceroy,  
1713-14.

Appoints Jawán  
Mard Khan his  
Deputy.

The Maráthas  
in Ahmedabad.

## Chapter III.

Mughal  
Viceroys.

Muhammad  
Shah  
Emperor,  
1721-1748  
MORAR NÁK  
KHAN

Fifty-seventh  
Viceroy,  
1743-44

Battle of Kun  
Kathodra  
Defeat and  
Death of  
Abdul Aziz  
Khan,  
1744.

FAKHR UD-  
DAULAH  
Fifty-eighth  
Viceroy,  
1744-1748.

Jawan Mard  
Khan Babi,  
Deputy Viceroy

\*Khanderáv  
Gaikwár called  
to Satárá.

In A.D. 1744 Jawán Mard Khán, after appointing one of his brothers, Zoráwar Khán, his deputy at Pátan, and keeping his other brother Safdar Khán at Ahmedábád, advanced from the city to Kadi to collect tribute. His next step was to invite Abdul Azíz Khán, the commander of Junnar, near Poona, to join him in Gujarat. Abdul Azíz accordingly set out from Junnar, taking with him Fatehyah Khán, commander of the fort of Mulher in Bagher and Rustamray Maratha. Directing his march in the first instance to Surat he was there watched in the interests of Damáji Gaikwár, by Devaji Takpar, the lieutenant of that chief, who, seeing that on leaving Surat, Abdúl Azíz continued to advance to Ahmedabad, pursued him to Kun Kathodra, about fifteen miles north west of Surat, and there attacked him. In the engagement Devaji Takpar, who had gained over Rustamray Maratha, one of the leading men in Abdúl Azíz's army, was victorious. Abdúl Azíz Khán retired, but was so closely followed by the Marathás, that at Pánoh he was forced to leave his elephant, and, mounting a horse, fled with all speed towards Breach. On reaching the Narbada he failed to find any boats, and as his pursuers were close upon him, putting his horse at the water, he tried to swim the river, but, sticking fast in the mud, he was overtaken and slain by the Marathas.

On hearing of the death of Abdúl Azíz Jawan Mard Khán thought of joining Muftakhr Khan. Ere he could carry this plan into effect, the emperor receiving, it is said, a present of £20,000 (Rs. 2 *laks*) for the nomination, appointed Fakhr-ud-daulah Fakhr-ud-din Khán Shujáát Jang Bahádur fifty-eighth viceroy of Gujarat. The new viceroy forwarded a blank paper to a lender of his acquaintance named Sitarám, asking him to enter in it the name of a fitting deputy. Sitarám filled in the name of Jawán Mard Khán, and Fakhr-ud-daulah was proclaimed viceroy. About this time Safdar Khan Babi, after levying tribute from the Salarnati chiefs, returned to Ahmedabad, and Khanderáv Gaikwár, as he passed from Sonath to Songad, appointed Rangoji his deputy. On being appointed deputy Rangoji sent Krishnaji instead of Morár Náik as his deputy to Ahmedabad, and himself proceeded to Arhan-Matar on the Vatrak, and from that moved to Kaira to visit Jawan Mard Khán, with whom he established friendly relations. In the same year Ah Muhammad Khan, superintendent of customs, died, and in his place the author of the *Mirát-i-Ahmedi* was appointed. In this year, too, Pahar Khan Jhalori died, and his uncle, Muhammad Bahádur, was appointed governor of Pálanpur in his stead.

About this time Umáidei, widow of Khanderáv Dábháde, summoned Khanderáv Gaikwár to help her in her attempt to lessen the power of the Peshwa. As Damáji Gaikwar could not be spared from the Dakhan Khanderáv was appointed his deputy in Gujarát, and he chose one Rámchandra to represent him at Ahmedábád. When Fakhr-ud-daulah advanced to join his appointment as viceroy he was received at Bálásinor with much respect by Sher Khan Babi. Jawán Mard Khán Babi, on the other hand, determining to resist Fakhr-ud-daulah to the utmost of his power, summoned Gangádhara with a body of Marátha horse from Petlád, and posting them at Ísanpur, about ten miles south-west of the city, himself leaving the fortifications of Ahmedábád, encamped at

Asárva, about a mile and a half from the walls. During his progress towards the capital the new viceroy was joined by Raisinghji of Ídar at Kapadvanj, and, advancing together, they arrived at Bhílpur, eighteen miles east of Ahmedabad. On their approach Jawán Mard Khán sent Safdar Khán and Gangádar to oppose them, and the two armies met about six miles from the capital. After some fighting Fakhr-ud-daulah succeeded in forcing his way to the suburb of Rájputra, and next day continuing to drive back the enemy occupied the suburb of Bahrámpura and began the actual siege of the city. At this point affairs took a turn. Fakhr-ud-daulah was wounded and returned to his camp, while Jawán Mard Khán succeeded in winning over to his side Sher Khán Bábi and Raisinghji of Ídar, two of the viceroy's chief supporters. The *Mirát-i-Ahmedí* especially notes that Rája Raisingh asked for money to pay his troops but Fakhr-ud-daulah, not knowing that this rule had long been a dead letter, said that as he held a district on service tenure, it was not proper for him to ask for a money and when on imperial service. Next day Fakhr-ud-daulah was surrounded by Safdar Khán Bábi and the Maráthás, and himself one wife and some children were taken prisoners, while another of his wives and his son, who had managed to escape to Siddhpur, were captured and brought back to Ahmedabad.

After this Khanderao Gáikwár returned to Gujarát to receive his share of the spoil taken from Fakhr-ud-daulah. Reaching Borsad, he took Rangoji with him as far as Ahmedabad, where he met Jawán Mard Khán and obtained from Rangoji a share of the tribute. Khanderao was not satisfied with Rangoji's accounts, and appointing a fresh deputy, he attached Rangoji's property, and before leaving Ahmedabad for Saitli, put him in confinement at Borsad. He also confined Fakhr-ud-daulah in the Ghnáspur outpost on the bank of the river Mahi. Meanwhile in consequence of some misunderstanding between Jawán Mard Khán Bábi and his brother Safdar Khán, the latter retired to Udepur and Jawán Mard Khán went to Visalnagar then in the hands of his brother Zoríwar Khán. From Visalnagar, Jawán Mard Khán proceeded to Rádhanpur, and meeting his brother Safdar Khán, they became reconciled, and returned together to Ahmedabad. Khanderao Gáikwár, who had in the meantime returned from Sorath, encamping at Bolla appointed Trimbakrao Pandit as his deputy at Ahmedabad in place of Moro Pandit. On hearing that Rangoji had been thrown into confinement, Umábái sent for him, and he along with Khanderao Gáikwár repaired to the Dakhan.

Shortly afterwards Punáji Vithal, in concert with Trimbak Pandit, being dissatisfied with Jawán Mard Khán, began to intrigue with Fakhr-ud-daulah. In the meantime Umábái had appointed Rangoji as her deputy, and, as he was a staunch friend of Jawán Mard Khán, he expelled Trimbakrao from Ahmedabad, and himself collected the Maráthá share of the city revenues. Upon this Punáji Vithal sent Gangádhara and Krishnáji with an army, and they, expelling the Muhammadan officers from the districts from which the Maráthás levied the one-fourth share of the revenue, took the management of them into their own hands. Rangoji now asked Sher Khán Bábi to help him. Sher

## Chapter III.

Mughal  
Viceroys.

Muhammad  
Shah  
Emperor,  
1721-1748.  
Fakhr-ud-  
DAULAH  
Fifty-eighth  
Viceroy,  
1744-1749.

Defeat and  
capture of the  
Viceroy by  
Jawán Mard  
Khán Bábi.

Rangoji  
Disgraced  
by Khanderao  
Gáikwár.

Punáji Vithal and  
Fakhr-ud-daulah  
oppose Rangoji  
and Jawán Mard  
Khán.

**Chapter III.****Mughal  
Viceroys.**

Muhammad  
Shah  
Emperor,  
1721-1748  
FAKHR-UD-  
DAULAH  
Fifty-eighth  
Viceroy,  
1744-1748.

\* Siege of  
Kapadvanj  
by Fakhr-ud-  
daulah,  
1746.

At the approach  
of Holkar the  
Siege is raised.

Khán agreed; but as he had not funds to pay his troops, he delayed, and afterwards plundered Mahmudha and Nadiad. As Rangoji failed to join him, Sher Khan proceeded by himself to Kapadvanj, and from Kapadvanj marched against the Maráthha camp, with which Fakhr-ud-daulah was then associated. On the night after his arrival, the Maráthas made an attack on Sher Khán's camp, in which many men on both sides were slain. Next morning the battle was renewed, but on Sher Khán suggesting certain terms the fighting ceased. That very night, hearing that Rangoji had reached Balasmor, Sher Khán stole off towards Kapadvanj. Punáji and Fakhr-ud-daulah followed in pursuit but failed to prevent Rangoji and Sher Khan from joining their forces.

In A.D. 1746 a battle was fought in the neighbourhood of the town of Kapadvanj in which Sher Khán was wounded. He was forced to take shelter with Rangoji in Kapadvanj, while Fakhr-ud-daulah, Gangadhar, and Krishnaji laid siege to that town. At this time the Lamávida chief asked Malharáy Holkar on his way back from his yearly raid into Malwa, to join him in attacking Virpur. Holkar agreed and Virpur was plundered. Rangoji, learning of the arrival of Holkar, begged him to come to his aid, and on promise of receiving a sum of £20,000 (Rs. 2 *lakhs*) and two elephants, Holkar consented. Gangadhar, Krishnaji, and Fakhr-ud-daulah, hearing of the approach of Holkar, raised the siege of Kapadvanj, and marching to Dholka expelled the governor of that district. Shortly afterwards on a summons from Damaji and Khanderao Gaikwar Rangoji retired to Baroda. Meanwhile Fakhr-ud-daulah, Krishnaji, and Gangadhar advanced to Jetalpur in the Daskroi sub-division of Ahmedabad and, taking possession of it, expelled Ambar Habshi, the deputy of Jawán Mard Khan. Damaji and Khanderao Gaikwar passed from Baroda to Vasu, where they were met by Krishnaji and Gangadhar, whom Damaji censured for aiding Fakhr-ud-daulah. On this occasion Damaji bestowed the districts of Baroda, Nadiad and Borsad on his brother Khanderao, an act on which for ever removed any ill feeling on the part of Khanderao. Then, proceeding to Goklej, Damaji had an interview with Jawán Mard Khán. From Goklej he sent Kánoji Takpar with Fakhr-ud-daulah to Sorath, and himself returned to Songad. As Borsad had been given to Khanderao, Rangoji fixed on Umreth as his residence.

In this year, A.D. 1746, Teghbeg Khán, governor of Surat, died, and was succeeded by his brother Safdar Muhammad Khán, who, in acknowledgment of a present of seven horses, received from the emperor the title of Bahadur. At this time Tálib Áli Khán died, and the writer of the *Mirát-i-Ahmedi* was appointed minister by the emperor. In A.D. 1747 Rangoji returned to Ahmedabad, and Jawán Mard Khán had an interview with him a few miles from the city. Shortly after this the Kohs of Melunábad and Mahudha rebelled, but the revolt was speedily crushed by Sháhábáz Rohilla.

Momin Khán II.  
Governor of  
Cambay,  
1748.

During this year Najm Khán, governor of Cambay, died. Muftakhir Khán, son of Najm-ud-daulah Momin Khán I., who had also received the title of Momin Khán, informed the emperor of Najm

Khán's death, and himself assumed the office of governor in which in A.D. 1748 he was confirmed. On hearing of the death of Najm Khan, on pretence of condoling with the family of the late governor, Fida-ud-din Khán marched to Cambay, but as he was not allowed to enter the town he retired. He afterwards went to Umreth and lived with Rangoji Kánoji Tíkpar, who had gone with Fakhr-ud-daulah into Sorath, now laid siege to and took the town of Vanthali. As it was nearly time for the Marathás to return to their country, Kánoji and Fakhr-ud-daulah, retiring to Dholka, expelled Muhammad Jánbá, the deputy governor. Rangoji, who had at this time a dispute with Jawán Mard Khán regarding his share of tribute, now came and joined them, and their combined forces marched upon Samand, where, after plundering the town, they encamped. It was now time for Kánoji to withdraw to the Dakhan. Rangoji and Fakhr-ud-daulah, remaining behind to collect tribute from the neighbouring districts, marched to Isampur, where they were opposed by Jawán Mard Khán. On this occasion both Jawán Mard Khán and Fakhr-ud-daulah sought the alliance of Raja Raisingh of Idar. But, as he offered more favourable terms, Raja Raisingh determined to join Fakhr-ud-daulah. Sher Khan B. also joined Fakhr-ud-daulah, who, thus reinforced, laid siege to Ahmedabad. While these events were passing at Ahmedabad, Harba, an adopted son of Khandaráy Gaikvár, at that time in possession of the fort of Borsad, began to plunder Rangoji's villages under Petad, and, attacking his deputy, defeated and killed him. On this Rangoji withdrew from Ahmedabad, attacked and captured the fort of Borsad, and forced Harba to leave the country. Jawán Mard Khán now sent for Janardhan Pandit, Khandaráy's deputy at Nadiad, and, in place of Rangoji's representative, appointed him to manage the Maratha share of Ahmedabad.

During these years important changes had taken place in the government of Surat. In A.D. 1731, when Mulla Muhammad Ali, the chief of the merchants and builder of the Athva fort, was killed in prison by Teghlég Khán, the Nizam sent Sayad Miththan to revenge his death. Sayad Miththan was forced to return unsuccessful. After Teghlég Khán's death Sayad Miththan again came to Surat and lived there with his brother Sayad Achchan, who held the office of paymaster. Sayad Miththan tried to get the government of the town into his hands, but, as an failing, committed suicide. His brother Sayad Achchan then attacked and took the citadel, expelling the commander; and for several days war was waged between him and the governor Safdar Muhammad Khán with doubtful success. At last Sayad Achchan called to his son Malharráv, the deputy at Baroda, and their combined forces took possession of the whole city. During the sack of the city Malharráv was killed and the entire management of affairs fell into the hands of Sayad Achchan. Safdar Muhammad Khán, the late governor, though obliged to leave the city, was determined not to give up Surat without a struggle, and raising some men opened fire on the fort. Sayad Achchan now begged the Arab Turk English Dutch and Portuguese merchants to aid him. A deed addressed to the emperor and the Nizam, begging that Sayad Achchan should be appointed

## Chapter III.

Mughal  
Viceroys.

Muhammad  
Shah  
Emperor,  
1721-1748.  
FAKHR-UD-  
DAULAH  
Fifty-eighth  
Viceroy,  
1741-1748.

Increased  
Strength of  
Fakhr-ud-daulah's  
Party.

Dissensions  
among the  
Marathás.

SURAT AFFAIRS.  
1748.

**Chapter III.****Mughal  
Viceroys.**

**Muhammad  
Shah**  
Emperor,  
1721-1748  
**FAKR-UD-  
DAULAH**  
Fifty-eighth  
Viceroy,  
1744-1748.

Mulla Fakhr-ud-  
din Escapes to  
Bombay.

Cession of Surat  
Revenue to the  
Golkara,  
1747.

Famine,  
1747.

Maratha  
Discussions.

Fall of Borsad.

**MAHARAJA  
VAKHATSINGH**  
Fifty-ninth  
Viceroy,  
1748.

governor, was signed by all the merchants except by Mr. Lamb the English chief, and though he at first refused, he was in the end persuaded by the other merchants to sign. The merchants then assisted Sayad Achehan, and Safdar Muhammad Khán retired to Sindh.

Meanwhile, on account of some enmity between Mulla Fakhr-ud-din, the son of Mulla Muhammad Ali chief of the merchants, and Sayad Achehan, the Mulla was thrown into prison. Mr. Lamb went to Sayad Achehan, and remonstrating with him suggested that the Mulla should be sent for. Sayad Achehan agreed, but on the way Mr. Lamb carried off Mulla Fakhr-ud-din to the English factory, and afterwards sent him to Bombay in disguise. In the meantime Kedari Garkwar, a cousin of Dámaji's, whom, with Malharay, Sayad Achehan had asked to his help, arrived at Surat, and though Sayad Achehan had been successful without his aid, Kedari demanded the £30,000 (Rs. 3 lakhs) which had been promised him. As the Sayad was not in a position to resist Kedari's demands, and as he had no ready money to give him, he made over to him a third of the revenues of Surat until the amount should be paid. As before this another third of the revenues of Surat had been assigned to Hafiz Masud Khán, the deputy of Yakut Khán of Janjira, the emoluments of the governor of Surat were reduced to one-third of the entire revenue and this was divided between the Mutasaddi and Bakhshi.

In this year (A. D. 1747, S. 1803) there was a severe shock of earthquake and a great famine which caused many deaths. In the following year Jawán Mard Khán endeavoured to recapture Jetalpur, but failed. About the same time Umabai died and Dámaji's brother Khandarav who was on good terms with Anubai wife of Baliray Senapati, the guardian of Umabai's son, procured his own appointment as deputy of his brother Dámaji in Gujarat. On being appointed deputy Khandarav at once marched against Rangoji to recover Borsad, which, as above mentioned, Rangoji had taken from Hariba. Their forces were joined by two detachments, one from Momín Khán under the command of Ngha Muhammad Husain, the other from Jawán Mard Khán commanded by Janárdhan Pandit. The combined army besieged Borsad. After a five months' siege Borsad was taken, and Rangoji was imprisoned by Khandarav. On the fall of Borsad Sher Khan Baba and Raja Rámsingh of Idar, who were allies of Rangoji, returned to Bálasinor and Idar; Fakhr-ud-daulah was sent to Petlad and Fida-ud-din Khán, leaving Unreth, took shelter with Jetha, the chief of Atarsmuba.

In this year the emperor Muhammad Shah died and was succeeded by his son Ahmed Shah (A. D. 1748-1754). Shortly after Ahmed's accession Maharája Vakhatsingh, brother of Maharája Abheysingh, was appointed fifty-ninth viceroy of Gujarát. When he learned what was the state of the province, he pleaded that his presence would be more useful in his own dominions, and never took up his appointment of viceroy. Vakhatsingh was the last viceroy of Gujarát nominated by the imperial court, for although by the aid of the Maráthás Fakhr-ud-daulah was of importance in the province, he had never been able

to establish himself as viceroy. In this year also occurred the death of Khushalehand Sheth, the chief merchant of Ahmedabad.

Khanderao Gaikwar appointed Raghavshankar his deputy at Ahmedabad, and Sardar Khán Bābi issued from Ahmedabad with an army to levy tribute from the chiefs on the banks of the Salarmati. When Fakhr-ul-daulah, the former viceroy, heard of the appointment of Mahārāja Vakhatsingh, seeing no chance of any benefit from a longer stay in Gujarať, he retired to Dehli. In A.D. 1748 Asif Jah, Nizām-ul-Mulk, died at an advanced age, leaving six sons and a disputed succession.

About the same time Bāláji of Peshwa, who was jealous of the power of the Gaikwar, sent a body of troops, and freed Rangoji from the hands of Khanderao Gaikwar. During these years adventurers, in different parts of the country, taking advantage of the decay of the central power, endeavoured to establish themselves in independence. Of these attempts the most formidable was the revolt of one of the Patan Kachhis who established his power so firmly in Patan that Jawán Mard Khán found it necessary to proceed in person to reduce him. Shortly afterwards Jawán Mard Khán deemed it advisable to recall his brothers Sardar Khan and Zoríwar Khan, who were then at Unja under Patan, and took them with him to Ahmedabad. Fidi-ud-din Khan who had been residing at Munsamba now asked permission to return to Ahmedabad, but as Jawán Mard Khán did not approve of this suggestion, Fidi-ud-din departed to Broach and there took up his residence. Janábulah Pandit marched to Kaira and the Bhil district to levy tribute, and Khanderao appointed Shevakram his deputy.

In the meantime at Surat, Sayad Achehan endeavoured to consolidate his rule, and with this view tried to expel Háfiz Masud Habshi, and prevent him again entering the city. But his plans failed, and he was obliged to make excuses for his conduct. Sayad Achehan then oppressed other influential persons, until eventually the Habshí and others joining, attacked him in the citadel. Except Mr. Lamb who considered himself bound by the deed signed in A.D. 1717 in favour of Sayad Achehan all the merchants of Surat joined the assailants. Among the chief opponents of Sayad Achehan were the Dutch, who sending ships brought back Sardar Muhammad Khan from Thatta, and established him as governor of Surat. The English factory was next besieged, and, though a stout resistance was made, the guards were killed, and the factory plundered. In A.D. 1750 Sayad Achehan, surrendering the citadel to the Habshí, withdrew first to Bombay and then to Poona, to Baláji of Peshwa. Shortly afterwards, in consequence of the censure passed upon him by the Bombay Government for his support of Sayad Achehan, Mr. Lamb committed suicide. Wearied by these continual contests for power, the merchants of Surat asked Rája Raghunáthdas, minister to the Nizám, to choose them a governor. Rája Raghunáthdas accordingly nominated his own nephew, Rája Harprasád, to be governor, and the writer of the Mirát-i-Ahmedi to be his deputy. But before Rája Harprasád could join his appointment at Surat, both he and his father were slain in battle.

### Chapter III.

#### Mughal Viceroys.

Ahmed Shah  
Emperor,  
1748-1754.

MAHARÁJA  
VAKHATSINGH  
Fifty-ninth  
Viceroy,  
1748.

Disorder  
spreads.

SURAT AFFAIRS.  
A.D. 1750.

Sayad Achehan  
Unpopular.

Sardar  
Muhammad  
brought back  
by the Dutch.

Sayad Achehan  
Retires.

## Chapter III.

Mughal  
Viceroys.Ahmed Shah  
Emperor,  
1748-1754.Jawán Mard  
Khán and  
the Peshwa,  
1750.The Peshwa  
and Gaikwár,  
1751.Broach  
Independent,  
1752.

In the same year, A.D. 1750, occurred the deaths of Rájá Ráisingh of Ídar, of Safdar Khán Bábi of Bálásinor, and of Fida-ul-dín Khán, who had for some time been settled at Broach. Jawán Mard Khán, who, seeing that they were inclined to become permanent residents in Gujarát, was always opposed to the Gaikwar's power, now entered into negotiations with Bálájiráv Peshwa. He chose Patel Sukhdev to collect the Marátha revenue and asked the Peshwa to help him in expelling Dámáji's agents. The Peshwa, being now engaged in war in the Dakhan with Salábat Jang Bahádur, son of the late Nizám, was unable to send Jawán Mard Khán any assistance. Towards the close of the year Jawán Mard Khán started from Ahmedabád to collect tribute from the Sálarmati chiefs. Returning early in A.D. 1751, at the request of Jetha Patel a subordinate of Bhávsingh Desái, he proceeded to Banol or Vanol under Virangám and reduced the village. Ali Muhammad Khán, the author of the *Mirát-i-Ahmeli*, who about this time was raised in rank with the title of Bahádur, states that owing to the Marátha inroads most of the districts had passed entirely into their possession, in others according to agreements with Jawán Mard Khán they held a half share. Consequently in spite of new taxes, the entire remaining income of the province was only four *lákhs* of rupees, and it was impossible to maintain the military posts or control the rebellious Kols.

It was in this year (A.D. 1751) that the Peshwa deposing Dámájaráv into his power, imprisoned him and forced him to surrender half of his rights and conquests in Gujarát. Taking advantage of the absence of the Gaikwár and his army in the Dakhan, Jawán Mard Khán marched into Sorath. He first visited Gogha and then levying tribute in Gadh-váda advanced into Kathaváda and marched against Navanagar, and, after collecting a contribution from the Jám, returned to Ahmedabad. In the following year (A.D. 1752), as soon as the news reached Gujarát that the Maráthas' share in the province had been divided between the Peshwa and Gaikwár, Momin Khán, who was always quarrelling with the Gaikwár's agent, sending Varájlál his steward to Bálájiráv Peshwa begged him to include Cambay in his share and send his agent in place of the Gaikwar's agent. Bálájiráv agreed, and from that time an agent of the Peshwa was established at Cambay. In the same year Raghunáthráv, brother of the Peshwa, entering Gujarát took possession of the Rewa and Mahi Kántha districts and marched on Surat. Shují Dhángar was appointed in Shevakráin's place as Dámáji's deputy, and Krishnaji came to collect the Peshwa's share.

Up to this time the city of Broach had remained part of the Nizám's personal estate, managed by Abdólláh Beg, whom, with the title of Nek Alam Khán, Ásif Jáh the late Nizám-ul-Mulk had chosen his deputy. On the death of Abdólláh Beg in A.D. 1752 the emperor appointed his son to succeed him with the same title as his father, while he gave to another son, named Mughal Beg, the title of Khertalab Khán. During the contests for succession that followed upon the death of the Nizám in A.D. 1752, no attempt was made to enforce the Nizám's claims on the lands of Broach; and for the future, except for the share of the revenue paid to the Maráthas, the governors of Broach were practically independent.

The Peshwa now sent Pándurang Pandit to levy tribute from his share of Gujarát, and that officer crossing the Mahi marched upon Cambay. Momín Khán prepared to oppose him, but the Pandit made friendly overtures, and eventually Momín Khán not only paid the sum of £700 (Rs. 7000) for grass and grain for the Pandit's troops, but also lent him four small cannon. Pándurang Pandit then marched upon Ahmedábád, and encamping near the Kankariya lake laid siege to the city which was defended by Jawan Mard Khán. During the siege Pándurang Pandit, sending some troops, ravaged Níkol, part of the lands of Ali Muhammad Khán Bahádur, the author of the *Mirát-i-Ahmedi*. Meanwhile, as the operations against Ahmedábád made no progress, Pándurang Pandit made offers of peace. These Jawán Mard Khán accepted, and on receiving from Jawan Mard Khán the present of a mare and a small sum of money under the name of entertainment, the Marátha leader withdrew to Sorath.

About this time the Peshwa released Dámáji Gaúkwár on his promise to help the Peshwa's brother Raghunáthráv, who was shortly afterwards despatched with an army to complete the conquest of Gujarát. Meanwhile Jawán Mard Khán's anxiety regarding the Maráthas was for a time removed by the departure of Pándurang Pandit. And, as the harvest season had arrived, he with his brother Zorawar Khán Bábi, leaving Muhammad Mubáriz Sherwáni behind as his deputy, set out from Ahmedábád to levy tribute from the chiefs of the Sábar Kántha. Certain well informed persons, who had heard of Raghunáthráv's preparations for invading Gujarát, begged Jawán Mard Khán not to leave the city but to depute his brother Zoráwar Khán Bábi to collect the tribute. Jawán Mard Khán, not believing their reports, said that he would not go more than from forty-five to sixty miles from the city, and that, should the necessity of any more distant excursion arise, he would entrust it to his brother. Jawán Mard Khán then marched from the city, levying tribute until he arrived on the Pálanpur frontier about seventy-five miles north of Ahmedábád. Here meeting Muhammad Bahádur Jhálori, the governor of Pálanpur, Jawán Mard Khán was foolishly induced to join him in plundering the fertile districts of Sirohi, till at last he was not less than 150 miles from his head-quarters. Meanwhile Raghunáthráv, joining Dámáji Gaúkwár, entered suddenly by an unusual route into Gujarát, and news reached Ahmedabad that the Maráthas had crossed the Narbada. On this the townspeople sent messenger after messenger to recall Jawán Mard Khán, and building up the gateways prepared for defence, while the inhabitants of the suburbs, leaving their houses, crowded with their families into the city for protection. Raghunáthráv, hearing that Jawán Mard Khán and his army were absent from the city, pressed on by forced marches, and crossing the river Mahi despatched an advance corps under Vithal Sukhdev. Kosáji, proprietor of Nadiád, at Dámáji Gaúkwár's invitation also marched towards Ahmedábád, plundering Mehmúdábád Khokhri, only three miles from the city. In the meantime Vithal Sukhdev reached Kaira, and taking with him the chief man of that place, Muhammad Daurán, son of Muhammad Bábi, continued his march. He was shortly joined by Raghunáthráv, and the combined forces now proceeded to Ahmedábád and encamped by the Kankariya

### Chapter III.

#### Mughal Viceroy.

Ahmed Sha'h  
Emperor,  
1748-1754.

Pándurang  
Pandit Repulsed  
at Ahmedabad,  
1752.

Marátha  
Invasion.

**Chapter III.****Mughal  
Viceroys.****Ahmed Shah  
Emperor,  
1748-1754.****Return of Jawán  
Mard Khán.****He enters  
Ahmedabad.****Gallant Defence  
of the City.**

lake. Next day Raghunáthráv moved his camp to near the tomb of Hazrat Sháh Bhíkan,<sup>1</sup> on the bank of the Sábarmati to the south-west of the city. Raghunáthráv now proceeded to invest the city, distributing his thirty to forty thousand horse into three divisions. The operations against the north of the city were entrusted to Dámájí Gáikwár; those on the east to Gopál Hári; while the troops on the south and west were under the personal command of Raghunáthráv and his officers.

After leaving Sirohi Jawán Mard Khán had gone westwards to Tharád and Váv, so that the first messengers failed to find him. One of the later messengers, Mándan by name, who had not left Ahmedábád until the arrival of Raghunáthráv at the Kánkaryá lake, made his way to Váv and Tharád, and told Jawán Mard Khán what had happened. Jawán Mard Khán set out by forced marches for Rádhanpur, and leaving his family and the bulk of his army at Pátan, he pushed on with 200 picked horsemen to Kadi and from that to Ahmedábád, contriving to enter the city by night. The presence of Jawán Mard Khán raised the spirits of the besieged, and the defence was conducted with ardour. In spite of their watchfulness, a party of about 700 Maráthás under cover of night succeeded in scaling the walls and entering the city. Ere they could do any mischief they were discovered and driven out of the town with much slaughter. The bulk of the besieging army, which had advanced in hopes that this party would succeed in opening one of the city gates, were forced to retire disappointed. Raghunáthráv now made proposals for peace, but Jawán Mard Khán did not think it consistent with his honour to accept them. On his refusal, the Marátha general redoubled his efforts and sprung several mines, but owing to the thickness of the city walls no practicable breach was effected. Jawán Mard Khán now expelled the Marátha deputies, and continuing to defend the city with much gallantry contrived at night to introduce into the town by detachments a great portion of his army from Pátan. At length, embarrassed by want of provisions and the clamour of his troops for pay, he extorted £5000 (Rs. 50,000) from the official classes. As Jawán Mard was known to have an ample supply of money of his own this untimely meanness caused great discontent. The official classes who were the

---

<sup>1</sup>Of the death at the age of nine years of this son of Saint Sháh-i-Alam the Mirát-i-Ahmedi (Printed Persian Text, II. 26) gives the following details: Malik Seif ud-dín, the daughter's son of Sultan Ahmed I., had a son who he believed was born to him by the prayer of Saint Sháh-i-Alam. This boy who was about nine years old died. Malik Seif ud-dín ran to Sháh-i-Alam, who used then to live at Asáwal, two or three miles east of Ahmedábád, and in a transport of grief and rage said to the Saint: 'Is this the way you deceive people? Surely you obtained me the gift of that boy to live and not to die? This I suppose is how you will keep your promise of mediating for our sinful souls before Alláh also?' The Saint could give no reply and retired to his inner apartments. The stricken father went to the Saint's son Sháh Bhíkan, who, going in to his father, entreated him to restore the Malik's boy to life. The Saint asked his son 'Are you prepared to die for the boy?' Sháh Bhíkan said 'I am ready.' The Saint, going into an inner room, spread his skirts before Allah crying 'Rájanji,' a pet name by which the Saint used to address Allah, meaning Dear King or Lord, 'Rájanji, here is a goat for a goat; take thou this one and return the other.' Lamentations in the Saint's harem showed that half of the prayer was granted and the Malik on returning to his house found the other half fulfilled.

repository of all real power murmured against his rule and openly advocated the surrender of the city; and Jawán Mard Khán, much against his will, was forced to enter into negotiations with Raghunáthráv.

Raghunáthráv was so little hopeful of taking Ahmedábád that he had determined, should the siege last a month longer, to depart on condition of receiving the one-fourth share of the revenue and a safe conduct. Had Jawán Mard Khán only disbursed his own money to pay the troops, and encouraged instead of disheartening the official class, he need never have lost the city. At last to Raghunáthráv's relief, Jawán Mard Khán was reduced to treat for peace through Vithal Sukhdev. It was arranged that the Maráthás should give Jawán Mard Khán the sum of £10,000 (Rs. 1 *lakh*) to pay his troops, besides presenting him with an elephant and other articles of value. It was at the same time agreed that the garrison should leave the city with all the honours of war. And that, for himself and his brothers, Jawán Mard Khán should receive, free from any Marátha claim, the districts of Pátan, Vadnagar, Sami, Munjpur, Visalnagar, Tharád, Kheráin, and Rádhanpur with Tervala and Bijápur. It was further agreed that one of Jawán Mard Khán's brothers should always serve the Maráthás with 300 horse and 500 foot, the expenses of the force being paid by the Maráthás. It was also stipulated that neither the Peshwa's army nor his deputy's, nor that of any commander should enter Jawán Mard Khán's territory, and that in Ahmedábád no Marátha official should put up at any of the Khán Bahádur's mansions, new or old, or at any of those belonging to his brothers followers or servants. Finally that the estates of other members of the family, namely Kaira, Kásba Mátar and Bánsa Mahudha, which belonged to Muhammad Khán, Khán Daurán, and Abid Khán were not to be meddled with, nor were encroachments to be allowed on the lands of Káyam Kúli Khán or of Zoráwar Khán. This agreement was signed and sealed by Raghunáthráv, with Dámáji Gaikwár (half sharer), Malhárávrá Holkar, Jye Apa Sindhia, Rámchandar Vithal Sukhdev, Sakharáin Bhagvant, and Málhavrávrá Gopálrávrá as securities. The treaty was then delivered to Jawán Mard Khán, and he and his garrison, marching out with the honours of war, the Maráthás took possession of Ahmedábád on April 2nd, 1753.

On leaving Ahmedábád Jawán Mard Khán retired to Pátan. At Ahmedábád Raghunáthráv with Dámáji arranged for the government of the city, appointing Shripatrávrá his deputy. He then marched into Jháláýáda to levy tribute from the Limbdi and Wadhvái chiefs; and was so far successful that Harbhamji of Limbdi agreed to pay an annual tribute of £4000 (Rs. 40,000). As the rainy season was drawing near Raghunáthráv returned to Dholka, while Patel Vithal Sukhdev forced Muhammad Bahádur, the governor of Pálanpur, to consent to a payment of £11,500 (Rs. 1,15,000). From Dholka Raghunáthráv went to Tárápur, about twelve miles north of Cambay, and compelled Momín Khán to submit to an annual payment of £1000 (Rs. 10,000). At the same time Ali Muhammad Khán Bahádur, the author of the *Mirát-i-Ahmedi*, was appointed collector of customs, and his former grants were confirmed and he was allowed to retain

## Chapter III.

Mughal  
Viceroys.

Ahmed Shah  
Emperor,  
1748-1754.  
Jawán Mard  
Khán  
Surrendered.

The Maráthas  
take  
possession,  
1753.

Collect Tribute.

**Chapter III.****Mughal  
Viceroys.**

**Ahmed Shah  
Emperor,  
1748-1754.  
Mughal Conquest  
Ceases.**

**Failure of an  
Attempt on  
Cambay,  
1753.**

**The Kolis.**

his villages of Sayadpur and Kūjādh close to Ahmedābād, as well as the village of Pānmūl in Bijāpur. Dāmāji Gāikwār, after levying tribute in the Vūtrak Kāntha, went to Kapadvanj, which he took from Sher Khān Bābi. From Kapadvanj he passed to Nadiād and appointed Shevakrāi to collect his half share of the revenue of Gujarāt. In the Ahmedābād mint, coin ceased to be struck in the emperor's name and the suburbs of the city which had been deserted during the siege were not again inhabited. The Kolis commenced a system of depredation, and their outrages were so daring that women and children were sometimes carried off and sold as slaves. After the rains were over (A.D. 1751) Shetnaji, commander of the Ahmedābād garrison, and Shankarji, governor of Viramgām, were sent to collect tribute from Sorath. Though the imperial power was sunk so low, the emperor was allowed to confer the post of Kāzi of the city on Kāzi Rūkn-ul-Hak Khān who arrived at Ahmedābād and assumed office. At the close of the year Shripatrāv, who was anxious to acquire Cambay, marched against Momīn Khān. After two doubtful battles in which the Marāthās gained no advantage, it was agreed that Momīn Khān should pay a sum of £700 (Rs. 7000), and Shripatrāv departed from Ahmedābād early in A.D. 1754. When the Kolis heard of the ill success of the Marāthās at Cambay, they revolted and Rāghoshankar was sent to subdue them. In an engagement near Lūhāra in Bahyal in His Highness the Gāikwār's territory about eighteen miles east of Ahmedābād, Rāghoshankar scattered the Kolis, but they again collected and forced the Marāthās to retire. At this time Shetnaji and Shankarji returned from Sorath, where they had performed the pilgrimage to Dwārka. Shetnaji was sent to the Bhil district against the Kolis. He was unsuccessful, and was so ashamed of his failure that he returned to the Dakhan and Daudu Dātātri was appointed in his place.

**Marāthās  
Attack  
Cambay,  
1754.**

In this year died Nek Alam Khān II. governor of Broach. He was succeeded by his brother Khertalab Khān who expelled his nephew Hāmid Beg, son of Nek Alam Khān. Hāmid Beg took refuge in Surat. At Bālāsōr a dispute arose between Sher Khān Bābi and a body of Arab mercenaries who took possession of a hill, but in the end came to terms. With the Peshwa's permission his deputy Bhagvantrāv marched on Cambay. But Varajlāl, Momīn Khān's steward, who was then at Poona, sent word to his master, who prepared himself against any emergency. When Bhagvantrāv arrived at Cambay he showed no hostile intentions and was well received by Momīn Khān. Subsequently a letter from Bhagvantrāv to Sālim Jamādār at Ahmedābād ordering him to march against Cambay fell into Momīn Khān's hands. He at once surrounded Bhagvantrāv's house and made him prisoner. When the Peshwa heard that Bhagvantrāv had been captured, he ordered Gamesh Apt., governor of Jambūsar, as well as the governors of Viramgām, Dhandhuka, and other places to march at once upon Cambay. They went and besieged the town for three months, but without success. Eventually Shripatrāv, the Peshwa's deputy, sent the author of the Mirāt-i-Ahmedi to negotiate, and it was agreed that Bhagvantrāv should be released and that no alteration should be made in the position of Momīn Khān. Shortly afterwards Shripatrāv was recalled by the Peshwa and his place supplied by an

officer of the name of Rágho. About this time Khertalab Khán, governor of Broach, died, and quarrels arose regarding the succession. Ultimately Hamid Beg, nephew of Khertalab Khán, obtained the post, and he afterwards received an imperial order confirming him as governor, and bestowing on him the title of Nekkám Khán Bahádúr.

At Delhi, during A.D. 1754, the emperor Ahmed Sháh was deposed, and Áziz-ud-din, son of Jahándár Sháh, was raised to the throne with the title of Alamgir II. After his release Bhagvantrav established himself in the Cambay fort of Nápad and not long after began to attack Momín Khán's villages. After several doubtful engagements peace was concluded on Momín Khán paying £1000 (Rs. 10,000) on account of the usual share of the Maráthas which he had withheld. This arrangement was made through the mediation of Tukáji, the steward of Sadáshiv Dámodar, who had come to Gujarát with an army and orders to help Bhagvantrav. As Momín Khán had no ready money Tukáji offered himself as security and Bhagvantrav and Tukáji withdrew to the Dakhan. Momín Khán's soldiery now clamoured for pay. As he was not in a position to meet their demands he sent a body of men against some villages to the west belonging to Limbdi and plundered them, dividing the booty among his troops. In the following year, A.D. 1755, Momín Khán went to Gogha, a port which, though at one time subordinate to Cambay, had fallen into the hands of Sher Khán Báhi, and was now in the possession of the Peshwa's officers. Gogha fell and leaving a garrison of 100 Arabs under Ibráhím, Kúli Khán, Momín Khán returned to Cambay, levying tribute. He then sent the bulk of his army under the command of Muhammad Zamán Khán, son of Fúlá-ud-dín Khán, and Varajlál his own steward, to plunder and collect money in Gohlváda and Káthiávdá. Here they remained until their arrears were paid off, and then returned to Cambay. After this Momín Khán plundered several Petlád villages and finally, in concert with the Kolis of Dhowan, attacked Jambusar and carried off much booty. Momín Khán next marched against Borsad, and was on the point of taking the fort when Sayáji, son of Dámáji Gákwar, who lived at Baroda, hearing of Momín Khán's success, came rapidly with a small body of men to the relief of the fort and surprised the besiegers. The Muhammadan troops soon recovered from the effect of the surprise, and Sayáji fearing to engage them with so small a force retired. On Sayáji's departure Momín Khán raised the siege of Borsad and returned to Cambay.

In the year A.D. 1756 the rains were very heavy, and the walls of Ahmedábád fell in many places. Momín Khán, hearing of this as well as of the discontent of the inhabitants, resolved to capture the city. He sent spies to ascertain the strength of the garrison and set about making allies of the chief men in the province and enlisting troops. About this time Rághoji, the Marátha deputy, was assassinated by a Rohilla. As soon as Momín Khán heard of Rághoji's death he sent his nephew, Muhammad Zamán Khán, with some men in advance, and afterwards himself at the close of the year, A.D. 1756, marched from Cambay and camped on the Vátrak. From this camp they moved to Kaira, and from Kaira to Ahmedábád. After one or two fights in

### Chapter III. Mughal Viceroys.

Alamgir II.  
Emperor,  
1754-1759.

Contest with  
Momín Khán  
renewed,  
1754.

Momín Khán  
takes Gogha,  
1755.

Momín Khán  
recovers  
Ahmedábád,  
17th Oct. 1756.

**Chapter III.****Mughal  
Viceroys.**

**Alamgir II.**  
Emperor,  
1754-1759.

**Jawán Mard**  
Khán allies  
himself with  
the Maráthás.

the suburbs the Muhammadans, finding their way through the breaches in the walls, opened the gates and entered the town. The Kolis commenced plundering, and a hand-to-hand fight ensued, in which the Maráthás were worsted and were eventually expelled from the city. The Kolis attempted to plunder the Dutch factory, but met with a spirited resistance, and when Shambhúrám, a Nágár Bráhmaṇ, one of Momín Khán's chief supporters, heard it he ordered the Kolis to cease attacking the factory and consoled the Dutch.

In the meantime Jawán Mard Khán, who had been invited by the Maráthás to their assistance, set out from Pátan, and when he arrived at Pethápúr and Múnsa he heard of the capture of Ahmedábád. On reaching Kalol he was joined by Harbhamrá́m, governor of Kadi. They resolved to send Zoráwar Khán Bábi to recall Sadáshiv Dámodar, and to await his arrival at Vírangám. Shevakrá́m, the Gaikwár's deputy, had taken refuge at Dholka. Momín Khán himself now advanced, and entering Ahmedábád on the 17th October 1756, appointed Shambhúrám his deputy. Sadáshiv Dámodar now joined Jawán Mard Khán at Vírangám, and at Jawán Mard Khán's advice it was resolved, before taking further steps, to write to the Peshwa for aid. Jawán Mard Khán, although he held large service estates, charged the Maráthás £150 (Rs. 1500) a day for his troops. Jawán Mard Khán and the Maráthás then advanced to Sánand and Jitalpur, and thence marched towards Cambay. On their way they were met, and, after several combats, defeated by a detachment of Momín Khán's army. Momín Khán sent troops to overrun Kadi, but Harbhamrá́m, the governor of Kadi, defeated the force, and captured their guns. When the emperor heard of the capture of Gogha, he sent a sword as a present to Momín Khán; and when the news of the capture of Ahmedábád reached Agra, Momín Khán received many compliments. Bálibírav Peshwa on the other hand was greatly enraged at these reverses. He at once sent off Sadáshiv Rámchandra to Gujarát as his deputy, and Dámáji and Khandarav Gaikwár also accompanied him with their forces. Momín Khán refusing to give up Ahmedábád, prepared for defence. Sadáshiv Rámchandra, Dámáji and Khandarav Gaikwár advanced, and, crossing the Mahi, reached Kaira. Here they were met by Jawán Mard Khán and the rest of the Maráthá forces in Gujarát, and the combined army advancing against the capital camped by the Kámkanya lake.

**Maráthás Invest**  
**Ahmedábád,**  
1756.

The Maráthás now regularly invested the city, but Momín Khán, aided by Shambhúrám, made a vigorous defence. Up to this time Jawán Mard Khán was receiving £150 (Rs. 1500) daily for the pay of his own and his brother's troops. Sadáshiv Rámchandra, considering the number of the troops too small for so large a payment, reduced the amount and retained the men in his own service. After a month's siege, Momín Khán's troops began to clamour for pay, but Shambhúrám, by collecting the sum of £10,000 (Rs. 1 *lák*) from the inhabitants of the town managed for the time to appease their demands. When they again became urgent for pay, Shambhúrám diverted their thoughts by a general sally from all the gates at night. On this occasion many men were slain on both sides, and many of the inhabitants deserted the town. The copper vessels of such of the townspeople as had fled

were melted and coined into money and given to the soldiery. In this state of affairs an order arrived from the imperial court bestowing on Momín Khán a dress of honour and the title of Bahádur. Although the imperial power had for years been merely a name Momín Khán asked and obtained permission from the besiegers to leave the city and meet the bearers of the order. The Maráthás redoubled their efforts. Still though the besiegers were successful in intercepting supplies of grain the garrison fought gallantly in defence of the town.

At this juncture, in A.D. 1757, Rája Shivsingh of Ídar, son of the late Anandsingh, who was friendly to Momín Khán, sent Sajánsingh Hazáří with a force to assist the besieged. On their way to Ahmedábád, Harbhamráam with a body of Maráthás attacked this detachment, while Momín Khán sent to their aid Muhammad Lál Rolulla and others, and a doubtful battle was fought. Shortly afterwards Sadáshiv Rámchandra made an attempt on the fort of Kálikot. The fort was successfully defended by Jamadár Núr Muhammad, and the Maráthás were repulsed. The Maráthás endeavoured in vain to persuade Shambhúrám to desert Momín Khán, and though the garrison were often endangered by the faithlessness of the Kohs and other causes, they remained staunch. Momín Khán, though frequently in difficulties owing to want of funds to pay his soldiery, continued to defend the town. The Maráthás next tried to seduce some of Momín Khán's officers, but in this they also failed, and in a sally Shambhúrám attacked the camp of Sadáshiv Rámchandra, and burning his tents all but captured the chief himself.

When the siege was at this stage, Hassan Kúli Khán Bahádur, viceroy of Ondh, relinquishing worldly affairs and dividing his property among his nephews, set out to perform a pilgrimage to Makkah. Before he started Shuja-ud-daulah, the Nawab of Lucknow, requested him on his way to visit Bálijáráy, and endeavour to come to some settlement of Ahmedábád affairs. Accordingly, adopting the name of Shah Núr, and assuming the dress of an ascetic, Hassan Kúli made his way to Poona, and appearing before the Peshwa offered to make peace at Ahmedábád. Shah Núr with much difficulty persuaded the Peshwa to allow Momín Khán to retain Cambay and Gogha without any Maráthá share, and to grant him a *lák* of rupees for the payment of his troops on condition that he should surrender Ahmedábád. He obtained letters from the Peshwa addressed to Sadáshiv Rámchandra to this effect, and set out with them for Ahmedábád. When he arrived Sadáshiv Rámchandra was unwilling to accede to the terms, as the Ahmedábád garrison were reduced to great straits. Shah Núr persuaded him at last to agree, provided Momín Khán would surrender without delay. Accordingly Shah Núr entered the city and endeavoured to persuade Momín Khán. Momín Khán demanded in addition a few Petlál villages, and to this the Maráthás refused their consent. Shah Núr left in disgust. Before many days Momín Khán was forced to make overtures for peace. After discussions with Dámáji Gáikwár, it was agreed that Momín Khán should surrender the city, receive £10,000 (Rs. 1 *lák*) to pay his soldiery, and be allowed to retain Cambay as heretofore, that is to say that the Peshwa should, as

## Chapter III.

Mughal  
Viceroys.

A'lamgir II.  
Emperor,  
1754-1759.

Ráj of Ídar  
helps Momín  
Khán,  
1757.

Successful  
Sally under  
Shambhúrám.

Negotiations  
for Peace.

**Chapter III.****Mughal  
Viceroys.**

**Alamgir II.  
Emperor,  
1754-1759.**

**Marátha  
Arrangements  
in Ahmedabad.**

**New Coins.**

**Momín Khán  
at Cambay.**

**Expedition from  
Kachh against  
Sindh,  
1758.**

formerly, enjoy half the revenues. In addition to this Momín Khán had to promise to pay the Maráthás a yearly tribute of £1000 (Rs. 10,000) and to give up all claims on the town of Gogha and hand over Shambhurám to the Maráthás. It was also arranged that the £3500 (Rs. 35,000) worth of *ashrafs* which he had taken through Janúdar Sáhni should be deducted from the £10,000 (Rs. 1 *lakh*). Momín Khán surrendered the town on February 27th, 1758.

Sadāshiv Rámchandar and Dámáji Gáikwár entered the city and undertook its management on behalf of the Maráthás. Of the other chiefs who were engaged in prosecuting the siege, Sadāshiv Dnyōdar returned to the Dakhan and Jawán Mard Khán receiving some presents from Sadāshiv Rámchandar departed for Pátan after having had a meeting with Dámáji Gáikwár at a village a few miles from the capital. Shambhurám, the Nágari Bráhman, who had so zealously supported Momín Khán, when he saw that further assistance was useless, tried to escape, but was taken prisoner and sent in chains to Baroda. Sadāshiv Rámchandar, on taking charge of the city, had interviews with the principal officials, among whom was the author of the *Mirat-i-Ahmedi*, and, receiving them graciously, confirmed most of them in their offices. Then, after choosing Náro Pandit, brother of Pándurang Pandit, to be his deputy in Ahmedábád, he started on an expedition to collect tribute in Jhálaváda and Sorath. On receiving the government of the city the Marátha generals ordered new coin bearing the mark of an elephant gold to be struck in the Ahmedábád mint. Sayājiráv Gáikwár remained in Ahmedábád on behalf of his father Dámáji, and shortly afterwards went towards Kapadvanj to collect tribute. Thence at his father's request he proceeded to Sorath to arrange for the payment of the Gáikwár's share of the revenues of that district. On his return to Cambay Momín Khán was much harassed by his troops for arrears of pay. The timely arrival of his steward Varajlál with the Peshwa's contribution of £10,000 (Rs. 1 *lakh*) enabled him to satisfy their demands.

Momín Khán now began to oppress and extort money from his own followers, and is said to have instigated the murder of his steward Varajlál. Sadāshiv Rámchandar went from Porbandar to Jímágad, where he was joined by Sayājiráv Gáikwár. At Jímágad Sher Khán Bábi presented Sadāshiv Rámchandra and Sayājiráv with horses and they spoke of the necessity of admitting a Marátha deputy into Jímágad. Nothing was settled as the Maráthás were forced to return to Ahmedábád. In accordance with orders from the Peshwa, Shambhurám and his sons, who were still in confinement, were sent to Poona. Dámáji Gáikwár was also summoned to Poona, but he did not go. In this year Ráo Lakhpát of Kachh presented Kachh horses and Gujarát bullocks to the emperor, and in return received the title of Mírza Rájá.

About this time the Ráo of Kachh, who planned an expedition against Sindh, solicited aid both from Dámáji Gáikwár and Sadāshiv Rámchandar to enable him to conquer Thatta, and, as he agreed to pay expenses, Sadāshiv sent Ranchordás, and Dámáji sent Shovakrá to help him. In this year also Neknám Khán, governor of Broach, received the title of Bahádur and other honours. In A.D. 1758, Sadāshiv Rámchandar advanced to Kaira and after settling accounts

with Dámáji's agent proceeded against Cambay. Momín Khán, who was about to visit the Peshwa at Poona, remained to defend the town, but was forced to pay arrears of tribute amounting to £2000 (Rs. 20,000). In this year Sher Khán Bábi died at Júnágadh, and the nobles of his court seated his son Muhammad Mahábat Khán in his place.

Shortly after at the invitation of the Peshwa, Dámáji Gáikwár went to Poona, and sent his son Sayájráv into Sorath. After his success at Cambay Sadáshiv Rámchandra levied tribute from the chiefs of Umeta, and then returned. On his way back, on account of the opposition caused by Sardár Muhammad Khán son of Sher Khán Bábi, the chief of Bálásinor, Sadáshiv Rámchandar besieged Bálásinor and forced the chief to pay £3000 (Rs. 30,000). Next marching against Innáváda, he compelled the chief Díp Singh to pay £5000 (Rs. 50,000). Sadáshiv then went to Visalnagar and so to Pálanpur, where Muhammad Khán Bahádúr Jhálón resisted him; but after a month's siege he agreed to pay a tribute of £3500 (Rs. 35,000). Passing south from Pálanpur, Sadáshiv went to Únja-Unáva, and from that to Katosan where he levied £1000 (Rs. 10,000) from the chief Shuja, and then proceeded to Límhdi.

During A.D. 1758 important changes took place in Surat. In the early part of the year Sayad Muñn-ud-din, otherwise called Sayad Achchan, visited the Peshwa at Poona, and received from him the appointment of governor of Surat. Sayad Achchan then set out for his charge, and as he was aided by a body of Marátha troops under the command of Muzaffar Khán Gárdi and had also secured the support of Nekkám Khán, the governor of Broach, he succeeded after some resistance in expelling Ali Nawáz Khán, son of the late Safdar Muhammad Khán, and establishing himself in the government. During the recent troubles, the English factory had been plundered and two of their clerks murdered by Ahmed Khán Habshi, commandant of the fort. The English therefore determined to drive out the Habshi and themselves assume the government of the castle. With this object men-of-war were despatched from Bombay to the help of Mr. Spencer, the chief of the English factory, and the castle was taken in March A.D. 1759, and Mr. Spencer appointed governor. The Peshwa appears to have consented to this conquest. The Marátha troops aided and made a demonstration without the city, and a Marátha man-of-war which had been stationed at Bassein, came to assist the English. A Mr. Glass appears to have been appointed *kiledár* under Governor Spencer.

Shortly afterwards Momín Khán, by the advice of Sayad Husain, an agent of the Peshwa, contracted friendship with the English through Mr. Erskine, the chief of the English factory at Cambay. Momín Khán then asked Mr. Erskine to obtain permission for him to go to Poona by Bombay. Leave being granted, Momín Khán set out for Surat, and was there received by Mr. Spencer. From Surat he sailed for Bombay, where the governor, Mr. Bouchier, treating him with much courtesy, informed the Peshwa of his arrival. The Peshwa sending permission for his further advance to Poona, Momín Khán took leave of Mr. Bouchier and proceeded to Poona.

## Chapter III.

Mughal  
Viceroys.

Alamgir II.  
Emperor,  
1754-1759.

The Maráthas  
levy Tribute.

SURAT AFFAIRS,  
1758.

The English  
take command  
of Surat,  
1759.

Momín Khán  
Visits Poona,  
1759.

## Chapter III.

Mughal  
Viceroys.Alamgir II  
Emperor.  
1754-1759.SADASHIV  
RAMCHANDRA  
Peshwa's  
Viceroy,  
1760.The Maráthás  
in Káshváda,  
1759.

From Limbdi, to which point his tribute toir has been traced, Sadashiv Rámchandra advanced against Dhrangadhia, when the chief who was at Halvad sent an army against him. The Maráthás, informed of the chief's design, detaching a force, attacked Halvad at night, and breaching the walls forced open the gates. The chief retired to his palace, which was fortified, and there defended himself, but was at last forced to surrender, and was detained a prisoner until he should pay a sum of £12,000 (Rs. 1,20,000). The neighbouring chiefs, impressed with the fate of Halvad, paid tribute without opposition. Sadashiv Rámchandra now went to Júnágadh, but ere he could commence operations against the fortress, the rainy season drew near, and returning to Ahmedabád he prepared to depart for Poona. Sayáji Gaikwár, who was also in Sorath collecting tribute, amongst other places besieged Kundla, and levying from that town a tribute of £7500 (Rs. 75,000) returned to the capital. During this time Khanderáv Gaikwár had been levying tribute from the Kolis, and after visiting the Bhil district went to Bijápúr, Ídar, Kadi, Dholka, and Nadiad. The chief of Halvad on paying his £12,000 (Rs. 1,20,000) was allowed to depart, and Dipsingh of Lunaváda, who was also a prisoner, was sent to Lunaváda and there released after paying his tribute. On receiving the news of the capture of the Surat fort by the English the emperor issued an order, in the name of the governor of Bombay, confirming the command of the fort to the English instead of to the Habshis of Janjira, appointing the Honourable East India Company admirals of the imperial fleet, and at the same time discontinuing the yearly payment of £2000 (Rs. 20,000) formerly made to the Habshis on this account. When in the course of the following year, A.D. 1760, this imperial order reached Surat, Mr. Spencer and other chief men of the city went outside of the walls to meet and escort the bearers of the despatch. Sadashiv Rámchandra was appointed viceroy of Ahmedabád on behalf of the Peshwa. Bhagvantrav now conquered Balasinor from Sardar Muhammad Khan Babi, and then marching to Sorath, collected the Peshwa's share of the tribute of that province, according to the scale of the previous year. Sayáji Gaikwár, when Bhagvantrav had returned, set out to Sorath to levy the Gaikwár's share of the tribute. He was accompanied by Harbhamani whom Damáji Gaikwár had specially sent from his own court to act as Kámdár to Sayáji. When Sadashiv Rámchandra reported to the Peshwa the conquest of Balasinor by Bhagvantrav he was highly pleased, and gave Bhagvantrav a dress of honour and allowed him to keep the elephant which he had captured at Lunaváda; and passed a patent bestowing Balasinor upon him. Morín Khán, after making firm promises to the Peshwa never to depart from the terms of the treaty he had made with the Maráthás, left Poona and came to Bombay, where he was courteously entertained by the Governor, and despatched by boat to Surat. From Surat he passed to Cambay by land through Broach. Sayáji Gaikwár had returned to Ahmedabád from Sorath in bad health, and his uncle Khándaráv Gaikwár, who had been vainly endeavouring to subdue the Kolis of Lúhára, came to Ahmedabád and took Sayáji Gaikwár to Nadiad. In 1761 Sadashiv Rámchandra was displaced as viceroy of Gujarát by

**Apa Ganesh.** This officer acted in a friendly manner to Momín Khán, and marching to Cambay, he fixed the Maráthá share of the revenues of that place for that year at £8400 (Rs. 84,000), and then went to Ahmedábád by way of Dákor. Narbherám collected this year the Gaikwár's share of the tribute of Sorath and Sayaji Gaikwár went to Baroda. On his return to Ahmedábád at the end of the year, Sayaji sacked and burned the Koli village of Láhíra in Bahyal about eighteen miles east of Ahmedábád. Jawán Mard Khan now issued from Patan and levied small contributions from the holdings in Vágad, as far as Anjár in Kachh. From Vágad he proceeded to Sorath, and in concert with Muhammad Mahabat Khan of Jímághadh and Muhammad Muzáffar Khán Bábi, between whom he made peace, he levied tribute in Sorath as far as Lohyana, and returned to Patan.

While their power and plunderings were thus prospering in Gujaráť the crushing ruin of Panpat (A.D. 1761) fell on the Maráthas. Taking advantage of the confusion that followed, the Delhi court despatched instructions to the chief Musalmán nobles of Gujarat, directing Momín Khán, Jawán Mard Khan, and the governor of Broach to join in driving the Maráthas out of the province. In consequence of this despatch Sardár Muhammad Khán Bábi, defeating the Maráthá garrison, regained Balásnor, while the governor of Broach, with the aid of Momín Khán, succeeded in winning back Jambúsar. Apa Ganesh, the Peshwa's viceroy, remonstrated with Momín Khán for this breach of faith. In reply his envoy was shown the despatch received from Delhi, and was made the bearer of a message, that before it was too late, it would be wisdom for the Maráthas to abandon Gujarat. Things were in this state when Dánúji Gaikwar, wisely forgetting his quarrels with the Peshwa, marched to the aid of Sadáshiv with a large army. Advancing against Cambay he attacked and defeated Momín Khán, plundering one of his villages. But the Maráthas were too weak to follow up this success, or exact severer punishment from the Musalmán confederates. Apa Ganesh invited Sardár Muhammad Khán Bábi to Kaira, and on condition of the payment of tribute, agreed to allow him to keep possession of Balásnor. Subsequently Dánúji's energy enabled him to enlarge the power and possessions of the Gaikwár's house, besides acquisitions from other chiefs, recovering the districts of Visánagor, Kherálu, Vadnagar, Bájpur, and Patan from Jawán Mard Khan. After the death of the great Dánúji, the importance of the Gaikwár's power sensibly diminished. Had it not been for their alliance with the British, the feeble hands of Sayajiráv I. (A.D. 1771-1778) would probably have been the last to hold the emblem of Gaikwár rule. If in the zenith of Gaikwár power Momín Khán could reconquer, and for so long successfully defend Ahmedábád, what might not have been possible in its decline?

**Chapter III.****Mughal  
Viceroys.**

**A lamgir II.**  
Emperor,  
1754-1759-  
**APA GANESH**  
Viceroy,  
1761.

Panpat,  
1761.



## APPENDIX I.

### The Death of Sulta'n Baha'dur, A.D. 1526-1536.<sup>1</sup>

COLONEL BRIGGS (Muhammadan Power in India, IV. 132) gives the following summary of the events which led to the fatal meeting of Sulta'n Bahádur and the Portuguese viceroy Nono da Cunha in the beginning of 1536-37 :

When in 1529 Nono daCunha came as viceroy to India he held instructions to make himself master of the island of Diu. In the following year a great expedition, consisting of 400 vessels and 15,000 men, met in Bombay and sailed to the Káthiáwáda coast. After vigorous assaults it was repulsed off Diu on the 17th February 1531. From that day the Portuguese made ceaseless efforts to obtain a footing on the island of Diu. In 1531 besides harrying the sea trade of Gujarát the Portuguese sacked the towns of Tára'pur, Balsúr, and Surat, and, to give colour to their pretensions, received under their protection Chánd Khán an illegitimate brother of Bahádur. In 1532, under James de Sylveira, the Portuguese burned the south Kathiáwáda ports of Pattan-Somnáth, Mangrul, Talája, and Muzaffarábád, killing many of the people and carrying off 4000 as slaves. Shortly after the Portuguese took and destroyed Bassein in Thána obtaining 400 cannon and much ammunition. They also burned Daman, Thána, and Bombay. "All this" says the Portuguese historian "they did to straiten Diu and to oblige the king of Gujarát to consent to their raising a fort on the island of Diu." When Bahádur was engaged with the Mughals (A.D. 1532-1534) the Portuguese Governor General deputed an embassy to wait on Humáyún to endeavour to obtain from him the cession of Diu, hoping by this action to work indirectly on the fears of Bahádur. At last in 1534 Bahádur consented to a peace by which he agreed to cede the town of Bassein to Portugal; not to construct ships of war in his ports; and not to combine with Turkish fleets against Portugal.

Permission was also given to the Portuguese to build in Diu. In consideration of these terms the Portuguese agreed to furnish Bahádur with 500 Europeans of whom fifty were men of note. According to the Portuguese historian it was solely because of this Portuguese help that Bahádur succeeded in driving the Mughals out of Gujarát. Bahádur's cession of land in Diu to the Portuguese was for the purpose of building a mercantile factory. From the moment Bahádur discovered they had raised formidable fortifications, especially when by the withdrawal of the Mughals he no longer had any motive for keeping on terms with them, he resolved to wrest the fort out of the hands of the Portuguese. On the plea of separating the natives from the Europeans, Bahádur instructed his governor of Diu to build a wall with a rampart capable of being mounted with guns. But as this created much dispute and ill-will the rampart was given up. Bahádur next attempted to seize Emanuel de Souza the captain of Diu fort. With this object he invited DeSouza to his camp. DeSouza was warned but determined to accept Bahádur's invitation. He went attended by only one servant, an act of courage which

### Appendix I.

THE DEATH  
OF SULTÁN  
BAHÁDUR,  
A.D. 1526-1536.

<sup>1</sup> See above page 256. The Portuguese details have been obtained through the kindness of Dr. Gerson DaCunha.

**Appendix I.**  
**THE DEATH**  
**OF SULTÁN**  
**BAHÁDUR,**  
**A.D. 1526 - 1536.**

Bahádur so greatly admired that he treated him with honour and allowed him to retire in safety. Bahádur next schemed to secure DeSouza in the fort by surprise. With this end he began to pay the Portuguese officers visits at all hours. But DeSouza was always on his guard and Bahádur's surprise visits failed to give him an opportunity. In 1536 DeSouza wrote to the viceroy complaining of the bad feeling of the Gujarát Moors towards the Portuguese in Diu and of the efforts of the king to drive them out of the fort. In consequence of DeSouza's letter Nono da Cunha the viceroy arrived at Diu early in 1536-7. Bahádur went to visit the viceroy on board the viceroy's ship. On his return he was attacked and leaping into the water was killed by a blow on the head and sank.

Of the unplanned and confused circumstances in which the brave Bahádur met his death four Musalmán and four Portuguese versions remain. The author of the *Mirát-i-Sikandar* (Persian Text, 280-281) states that the Portuguese, who offered their help to Bahádur in the days of his defeat by the emperor Humáyún, obtained from him the grant of land at Diu, and on this land built a fort. After the re-establishment of his power the Sultán, who had no longer any need of their help, kept constantly plotting some means of ousting the Portuguese from Diu. With this object Bahádur came to Diu and opened negotiations with the Portuguese viceroy, hoping in the end to get the viceroy into his power. The viceroy, knowing that Bahádur regretted the concessions he had made to them, was too wary to place himself in Bahádur's hands. To inspire confidence Bahádur, with five or six of his nobles all unarmed, paid the viceroy a visit on board his ship. Suspecting fond play from the behaviour of the Portuguese the king rose to retire, but the Portuguese pressed upon him on all sides. He had nearly reached his boat when one of the Portuguese struck him a blow with a sword, killed him, and threw his body overboard.

The same author gives a second version which he says is more generally received and is probably more accurate. According to this account the Portuguese had come to know that Bahádur had invited the Sultáns of the Dakhan to co-operate with him in driving the Portuguese from the Gujarát, Konkán, and Dakhan ports. That the Portuguese viceroy had come with 150 ships and had anchored at Diu off the chain bastion. That Sultán Bahádur, not suspecting that the Portuguese were aware of his insincerity, went in a barge to see the fleet, and when he got in the midst of their ships, the Portuguese surrounded his barge and killed him with lances.

According to Farishtah (II. 442, 443, Pers. Text) on the invasion of Gujarát by the emperor Humáyún, Sultán Bahádur had asked help of the Portuguese. When his power was re-established, Bahádur, hearing of the arrival of between five and six thousand Portuguese at Diu, feared they would take possession of that port. He therefore hastened to Diu from Júnágadh. The Portuguese who were aware that Humáyún had withdrawn and that Bahádur had re-established his power, preferred to attempt to gain Diu by stratagem rather than by force. Bahádur asked the viceroy to visit him. The viceroy feigned sickness and Bahádur with the object of proving his goodwill offered to visit the viceroy on board his ship. On leaving the viceroy's ship to enter his own barge the Portuguese suddenly moved their vessel and Bahádur fell overboard. While in the water a Portuguese struck the king with a lance and killed him.

Abul Fazl's account A.D. 1590 (Akbar-námah in Elliot, VI. 18) seems more natural and in better keeping with Bahádúr's impetuous vigour and bravery than either the Gujarát or Farishtah's narratives. The Portuguese chief was apprehensive that as the Sultan was no longer in want of assistance he meditated treachery. So he sent to inform the Sultan that he had come as requested, but that he was ill and unable to go on shore, so that the interview must be deferred till he got better. The Sultan, quitting the royal road of safety, embarked on the 12th February 1536 (3rd Ruzdhan H. 943) with a small escort to visit the viceroy on board the viceroy's ship. As soon as Bahádúr reached the vessel he found the viceroy's sickness was a pretence and regretted that he had come. He at once sought to return. But the Portuguese were unwilling that such a prey should escape them and hoped that by keeping him prisoner they might get more ports. The viceroy came forward and asked the Sultan to stay a little and examine some curiosities he had to present. The Sultan replied that the curiosities might be sent after him and turned quickly towards his own boat. A European *kúzi* or priest placed himself in the Sultan's way and bade him stop. The Sultan, in exasperation, drew his sword and cleft the priest in twain. He then leaped into his own boat. The Portuguese vessels drew round the Sultan's boat and a fight began. The Sultan and Rámi Khán threw themselves into the water. A friend among the Portuguese stretched a hand to Rámi Khan and saved him: the Sultan was drowned in the waves.

Of the four Portuguese versions of Bahádúr's death the first appears in Correa's (A.D. 1512-1550) *Lendas Da Asia*, A.D. 1497 to 1550; the second in DeBarros' (died A.D. 1570) *Decadas*, A.D. 1497 to 1539; the third in De Couto's (died A.D. 1600?) continuation of DeBarros, A.D. 1529 to 1600, and the fourth in Faria-e-Souza's (died A.D. 1650) *Portuguese Asia* to A.D. 1640. A fifth reference to Bahádúr's death will be found in Castaneda's *Historia* which extends to A.D. 1558.

As Correa was in India from A.D. 1512 till his death in Goa in A.D. 1550, and as his narrative which was never published till A.D. 1856-51 has the highest reputation for accuracy of detail his version carries special weight. According to Correa (*Lendas Da Asia*, Vol. III. Chap. XC.V.) during the monsoon of 1536, Nono Da Cunha the viceroy received by land a letter from Manoel de Souza the captain of Diu fort, telling him of the discontent of the Gujarát Moors with king Bahádúr for allowing the Portuguese to build a fort at Diu. In consequence of this information early in the fair season Nono da Cunha sailed from Goa in his own galleon accompanied by about ten small vessels *frustas* and *katus* under the command of Antomo de Sylveira. Nono reached Diu about the end of December. King Bahádúr was glad that the viceroy should come to Diu almost alone since it seemed to show he was not aware of Bahádúr's designs against the Portuguese. When Bahádúr arrived at Diu he sent a message to the viceroy inviting him to come ashore to meet him as he had important business to transact. The king's messenger found the viceroy ill in bed, and brought back a message that the viceroy would come ashore to meet the king in the evening. Immediately after the king's messenger left, Manoel de Souza, the captain of Diu fort, came on board to see the viceroy. The viceroy told Manoel to go and thank the king and to return his visit. The king expressed his grief at the viceroy's illness and proposed to start at once to see him. He went to his barge and rowed straight to the viceroy's

## Appendix I.

THE DEATH  
OF SULTÁN  
BAHÁDÚR,  
A.D. 1526-1536.

**Appendix I.**

THE DEATH  
OF SULTÁN  
BAHÁDUR,  
A.D. 1526 - 1536.

galleon. The king had with him, besides the interpreter St. Jago, seven men and two pages one carrying a sword and the other a bow. The captain of the fort and some other officers in their own barges followed the king. Bahádur, who was the first to arrive, came so speedily that the viceroy had hardly time to make preparations to receive him. He put on heavy clothes to show he was suffering from ague and ordered all the officers to be well armed. When Bahádur came on board he saw the men busy with their weapons but showed no signs that he suspected foul play. He went straight to the viceroy's cabin. The viceroy tried to get up but Bahádur prevented him, asked how he was, and returned at once to the deck. As Bahádur stood on the deck the captain of the fort boarded the galleon, and, as he passed to the cabin to see the viceroy, Bahádur laughingly upbraided him with being behind time. Then without taking leave of the viceroy Bahádur went to his barge. When the viceroy learned that the king had left he told the captain to follow the king and to take him to the fort and keep him there till the viceroy saw him. The captain rowed after the king who was already well ahead. He called to the king asking him to wait. The king waited. When the captain came close to the king's barge he asked the king to come into his vessel. But the interpreter without referring to the king replied that the captain should come into the king's barge. DeSouza ordered his boat alongside. His barge struck the king's barge and DeSouza who was standing on the poop tripped and fell into the water. The rowers of the royal barge picked him out and placed him near the king who laughed at his wet clothes. Other Portuguese barges whose officers thought the Moors were fighting with the captain began to gather. The first to arrive was Antonio Cardoza. When Cardoza came up the interpreter told the king to make for land with all speed as the Portuguese seemed to be coming to seize and kill him. The king gave the order to make for the shore. He also told the page to shoot the hollow arrow whose whistling noise was a danger signal. When the Moors in the king's barge heard the whistle they attacked Manoel deSouza, who fell dead into the sea. Then Diogo de Mesquita, D'Almeida, and Antonio Correa forced their way on to the king's barge. When the king saw them he unsheathed his sword and the page shot an arrow and killed Antonio Cardoza, who fell overboard and was drowned. D'Almeida was killed by a sword-cut from a Moor called Tiger and Tiger was killed by Correa. At that moment Diogo de Mesquita gave the king a slight sword-cut and the king jumped into the sea. After the king, the interpreter and Rámi Khán, two Moors, and all the rowers leapt into the water. The Portuguese barges surrounded them and the men struck at the three swimmers with lances and oars. The king twice cried aloud 'I am Sultán Bahádur,' hoping that some one would help him. A man who did not know that he was the king struck Bahádur on the head with a club. The blow was fatal and Bahádur sank. The second version is given by Barros (A.D. 1569) in his *Decadas da Asia*, Vol. V page 357 of the 1707 edition. The third version by De Couto (A.D. 1600) in his continuation of Barros' *Decadas*, and the fourth by Faria-e-Souza (A.D. 1650) in his *Portuguese Asia* are in the main taken from De Barros. The following details are from Steevens' (A.D. 1697) translation of Faria given in Briggs' *Muhammadian Power in India*, IV. 135-138.

Bahádur king of Cambay, who had recovered his kingdom solely by the assistance of the Portuguese, now studied their ruin, and repenting of the leave he had granted to build a fort at Diu endeavoured to

take it and to kill the commander and the garrison. Nono da Cunha the Portuguese viceroy understood his designs and prepared to prevent them. Emanuel deSouza who commanded at Din was warned by a Moor that the king would send for him by a certain Moor and kill him. DeSouza determined to go, and, when sent for, appeared with only one servant. Admiring DeSouza's courage the king treated him honourably and allowed him to return in safety. The king's mother tried to dissuade her son from plotting against DeSouza but to no effect. To remove suspicion Bahádur began to pay the Portuguese officers visits at unreasonable hours, but was ever received by DeSouza on his guard. Meanwhile, on the 9th January 1536, Nono da Cunha the Portuguese viceroy set out from Goa for Din with 300 sail. When he put in at Chent he found Nizám-ul-Mulk who pretended he had come to divert his women at sea but really with designs on that place. When Nono reached Din the king was hunting in the mountains and Nono apprised him of his arrival. The king sent for him by a Portuguese apostate of the name of John de St. Jago called Firangi Khán, but Nono da Cunha pleaded illness. The king pretending great friendship came to Din accompanied by Emanuel deSouza, who had brought the last message from DaCunha. At Din the king went on board the viceroy's ship and for a time they discoursed. The king was troubled at a page whispering something to DaCunha, but as DaCunha took no notice his suspicions were allayed. The message was from DeSouza, stating that the captains whom he had summoned were awaiting orders to secure or kill the king. DaCunha thought it strange that DeSouza had not killed the king while he was in his power in the fort; and DeSouza thought it strange that DaCunha did not now seize the king when he was in his power in the ship. DaCunha directed all the officers to escort the king to the palace and then accompany DeSouza to the fort, where DaCunha intended to seize the king when he came to visit him. The king on his part had resolved to seize DaCunha at a dinner to which he had invited him and send him in a cage to the Great-Turk. DeSouza who was going to invite the king to the fort after DaCunha had entered it, came up with the king's barge and delivered his invitation through Rúmi Khán. Rúmi Khán warned the king not to accept it. The king disregarding this warning invited DeSouza into his barge. While stepping into the king's barge DeSouza fell overboard, but was picked up by officers who carried him to the king. At this time three Portuguese barges came up and some of the officers seeing DeSouza hastily enter the king's barge drew close to the king's barge. The king remembering Rúmi Khán's warning ordered Emanuel deSouza to be killed. James deMesquita understanding the order flew at and wounded the king. An affray followed and four Portuguese and seven of the king's men were killed. The king tried to get away in a boat but a cannon shot killed three of his rowers and he was stopped. He next attempted to escape by swimming, but being in danger of drowning discovered himself by crying for help. A Portuguese held out an oar to him; but others struck him fatal blows, so that he sank.

The conclusion to be drawn from these four Musalmán and four Portuguese versions is that on either side the leader hoped by some future treachery to seize the person of the other; and that mutual suspicion turned into a fatal affray a meeting which both parties intended should pass peacefully and lull the other into a false and favourable security.

## Appendix I.

THE DEATH  
OF SULTÁN  
BAHÁDUR,  
A.D. 1526-1586.

## APPENDIX II.

### THE HILL FORT OF MA'NDU.

#### PART I.—DESCRIPTION.

**Appendix II.**  
**THE HILL FORT**  
**OF MA'NDU.**  
**DESCRIPTION.**

MA'NDU, about twenty-three miles south of Dhár in Central India, is a wide waying hill-top, part of the great wall of the Vindhyan range. The hill-top is three to four miles from north to south and four to five miles from east to west. On the north, the east, and the west, Mándu is isolated from the main plateau of Malwa by valleys and ravines that circle round to its southern face, which stands 1200 feet out of the Nímár plain. The area of the hill-top is over 12,000 English acres, and, so broken is its outline, that the encircling wall is said to have a length of between thirty-seven and thirty-eight miles. Its height, 1950 feet above the sea, secures for the hill-top at all seasons the boon of fresh and cool air.

About twenty miles south of Dhár the level cultivated plateau breaks into woody glades and uplands. Two miles further the plain is cleft by two great ravines, which from their deeper and broader southern mouths 700 to 800 feet below the Dhár plateau, as they wind northwards, narrow and rise, till, to the north of Mandu hill, they shallow into a woody dip or valley about 300 yards broad and 200 feet below the south crest of Malwa. From the south crest of the Malwa plateau, across the tree tops of this wild valley, stand the cliffs of the island Mándu, their crests crowned by the great Delhi gateway and its long lofty line of flanking walls. At the foot of the sudden dip into the valley the Álamgir or World-Guarding Gate stands sentinel<sup>1</sup>. Beyond the gateway, among wild reaches of rock and forest, a noble causeway with high domed tombs on either hand fills the lowest dip of the valley. From the south end of the causeway the road winds up to a second gateway, and beyond the second gateway between side walls climbs till at the crest of the slope it passes through the ruined but still lofty and beautiful Delhi or northern gateway, one of the earliest works of Diláwar Khan (A.D. 1400), the founder of Musalmán Mándu.

Close inside of the Delhi gate, on the right or west, stands the handsome Hindola Palace. The name Hindola, which is probably the title of the builder, is explained by the people as the Swingcot palace, because, like the sides of the cage of a swinging cot, the walls of the hall bulge

<sup>1</sup> The following Persian verses are carved on the Álamgir gateway:

In the time of A'lamgir Aurangzi'b (A.D. 1658-1707), the ruler of the World,

This gate resembling the skies in altitude was built anew.

In the year A.H. 1079 (A.D. 1668) the work of renewal was begun and completed

By the endeavour of the exalted Kha'n Muhammad Beg Kha'n.

From the accession of this Emperor of the World Aurangzi'b.

This was the eleventh year by way of writing and history.

below and narrow towards the top. Its great baronial hall and hanging windows give the Hindola palace a special merit and interest, and an air of lordly wealth and luxury still clings to the tree-covered ruins which stretch west to large underground cisterns and hot weather retreats. About a quarter of a mile south stand the notable group of the Jaház Mehel or Ship palace on the west, and the Tapela Mehel or Caldron palace on the south, with their rows of lofty pointed arches below deep stone eaves, their heavy windowless upper stories, and their massive arched and domed roof chambers. These palaces are not more handsomely built than finely set. The massive ship-like length of the Jaház Mehel lies between two large tree-girt ponds, and the Tapela, across a beautiful foreground of water and ruin, looks east into the mass of tangled bush and tree which once formed part of the 130 acres of the Lál Bágh or Royal Gardens.

The flat palace roofs command the whole 12,000 acres of Mándu hill, north to the knolls and broken uplands beyond the great ravine-mount and south across the waving hill-top with its miles of glades and ridges, its scattered villages hamlets and tombs, and its gleaming groves of mangues, *khurris*, banyans, *whouras*, and *pipals*. In the middle distance, out from the tree-tops, stand the lofty domes of Hoshang's tomb and of the great Jānā mosque. Further south lies the tree-girt hallow of the Sagar Talāv or Sea Lake, and beyond the Sagar lake a woody plateau rises about 200 feet to the southern crest, where, clear against the sky, stand the airy cupolas of the pavilion of Rūp Mitrī, the beautiful wife of Bāz Bahādūr (A.D. 1551-1561), the last Sultan of Malwa. Finally to the west, from the end of the Rūp Mitrī heights, rises even higher the bare nearly isolated shoulder of Songad, the citadel or inner fort of Mándu, the scene of the Gujarat Bahādūr's (A.D. 1531) daring and successful surprise. This fair hill-top, beautiful from its tangled wildness and scattered ruins, is a strange contrast to Mándu, the capital of a warlike independent dynasty. During the palmy days of the fifteenth century, of the 12,000 acres of the Mándu hill-top, 560 were fields, 370 were gardens, 200 were wells, 780 were lakes and ponds, 100 were bazar roads, 1500 were dwellings, 200 were rest-houses, 260 were baths, 470 were mosques, and 334 were palaces. These allotments crowded out the wild to a narrow pittance of 1560 acres of knolls and ridges.

From the Jaház Mehel the road winds through fields and woods, gemmed with peafowl and droll with monkeys, among scattered palaces mosques and tombs, some shapely some in heaps, about a mile south to the walled enclosure of the low domed tomb of the establisher of Mándu's greatness, Hoshang Shāh Ghori (A.D. 1405-1432). Though the badly-fitted joinings of the marble slabs of the tomb walls are a notable contrast to the finish of the later Mughal buildings, Hoshang's tomb, in its massive simplicity and dim-lighted roughness, is a solemn and suitable resting-place for a great Pathān warrior. Along the west of the tomb enclosure runs a handsome flat-roofed colonnade. The pillars, which near the base are four-sided, pass through an eight-sided and a sixteen-sided belt into a round upper shaft. The round shaft ends in a square under-capital, each face of which is filled by a group of leafage in outline the same as the favourite Hindu *Singh-mūkh* or horned face. Over the entwined leafy horns of this moulding, stone brackets support heavy stone beams, all Hindu in pattern.<sup>1</sup> Close to the east of Hoshang's tomb is Hoshang's

## Appendix II.

THE HILL FORT  
OF MANDU.

## DESCRIPTION.

<sup>1</sup> Mr. Fergusson (Indian Architecture, page 543) says: "The pillars appear to have been taken from a Jain building." But the refinement on the square capital of each pillar of the Hindu *Singh-mūkh* or horned face into a group of leaves of the same

**Appendix II.**  
**THE HILL FORT**  
**OF MANDU.**  
**DESCRIPTION.**

Jāmā Masjid or Great Mosque, built of blocks of red limestone. Hoshang's mosque is approached from the east through a massive domed gateway and across a quadrangle enclosed on the east north and south by wrecked colonnades of pointed arches. The west is filled by the great pointed arches of the mosque in fair repair. On the roof of the mosque from a thick undergrowth of domelets rise three lofty domes.<sup>1</sup>

In front of the gateway of the Great Mosque, in the centre of a masonry plinth about three feet high, stands an iron pillar about a foot in diameter at the base and twenty feet high. Close to the east of the gateway is the site of Mehmūd's (A.D. 1442) Tower of Victory, traces of which remained as late as A.D. 1840. About fifty yards further east are the ruins of a great building called the Ashrafi Mehel, said to have been a Musalmān college. To the north-east a banner marks a temple and the local state offices. South the road passes between the two lines of small houses and huts that make modern Māndū. Beyond the village, among ruins and huge swollen baobab stems, the road winds south along a downward slope to the richly-wooded lowland, where stretches to the west the wide coolness of the Sagar Talāv or Sea lake. Its broad surface covering 600 acres is green with fanlike lotus leaves, reeds, and water-grasses. Its banks are rough with brakes of tangled bush from which, in uncramped statelyness, rise lofty *mhanras*, mangoes, *karnis*, and *pipals*. To the east round a smaller tank, whose banks are crowned by splendid mangoes and tamarinds, stand the domes of several handsome tombs. Of some

outline shows that the pillars were specially carved for use in a Muslim building. The porch on the north side of the tomb enclosure is described (Ditt, page 543) as composed of pillars avowedly re-erected from a Jain building. This note of Mr. Fergusson's must have gone astray, as the north porch of Hoshang's tomb enclosure is in the plain massive pointed arch and square-shafted style of the tomb and of the great mosque. Mr. Fergusson's note apparently belongs to the second and smaller Jāmā Masjid, about a hundred yards east of the Sea or Sagar lake, the pillars of whose colonnade and porch are still enlivened by rows of the lucky face of the Hindu old hornv.

<sup>1</sup> Hoshang's great mosque has the following much damaged Persian inscription:

The mosque of exalted construction, the temple of heavenly altitude,

Whose every thick pillar is a copy of the (pillars of the) Sacred Temple (the Temple of Makkah).

On account of the greatness of its dignity, like the pigeons of the Temple of Makkah,

Sacred angels of high degree are always engaged in hovering around it,

The result of the events born of the merciless revolution of the skies.

When the sun of his life came as far as the balcony (and was ready to set).

A'azam Humayun (that is Malik Mughl's) said . . .

The administration of the country, the construction of buildings, and the driving back of enemies

Are things which I leave you (the son of A'azam Humayun) as parting advice with great earnestness.

The personification of the kindness of Providence, the Sultan A'la'-ud-din (Mehmud I. A.D. 1436-1469), who is

The outcome of the refulgence of the Faith, and the satisfier of the wants of the people,

In the year A.H. 858 (A.D. 1454),

In the words of the above parting advice, finished the construction of this building.

of these domes the black masses are brightened by belts of brilliant pale and deep-blue enamel. To the north of this overflow-pool a long black wall is the back of the smaller Jāma or congregation mosque, badly ruined, but of special interest, as each of its numerous pillars shows the uninjured Hindu *Śiṅgh-mukha* or horned face. By a rough piece of constructive skill the original cross corners of the end cupolas have been worked into vaulted Musalmán domes.<sup>1</sup>

From the Sea Lake, about a mile across the waving richly-wooded plain, bounded by the southern height of the plateau, the path leads to the sacred Rewa Kund or Narbada Pool, a small shady pond lined with rich masonry, and its west side enriched by the ruins of a handsome Bath or Hammām Khānah. From the north-east corner of the Rewa Pool a broad flight of easy stairs leads thirty or forty feet up the slope on whose top stands the palace of Bāz Bahadur (A.D. 1551-1561) the last independent chief of Mandu. The broad easy flight of steps ends in a lofty arched gateway through which a roomy hall or passage gives entrance into a courtyard with a central masonry cistern and an enclosing double colonnade, which on the right opens into an arched balcony overlooking the Rewa Kund and garden. Within this courtyard is a second court enclosed on three sides by an arched gallery. The roof of the colonnades, which are reached by flights of easy steps, are shaded by arched pavilions topped by cupolas brightened by belts of blue enamel.

<sup>1</sup> This Jāma Mosque has the following Persian inscription dated H. 835 (A.D. 1431)

With good omens, at a happy time, and in a lucky and well-started year,

On the 4th of the month of Allah (Ramazān) on the great day of Friday,

In the year 835 and six months from the Hijrah (A.D. 1431)

Counted according to the revolution of the moon in the Arabian manner,

This Islamic mosque was founded in this world,

The top of whose dome rubs its head against the green canopy of Heaven

The construction of this high mosque was due to Mughis-ud-din-wad dunya (Malik Mughis), the father of Mehmud I. of Malwa (A.D. 1436-1469), the redresser of temporal and spiritual wrongs.

Ulugh (brave), A'azam (great), Humayun (august), the Kha'n of the seven climes and the nine countries,

By the hands of his enterprise this so great mosque was founded,

That some call it the House of Peace, others style it the Ka'bah.

This good building was completed on the last of the month of Shawwa'l (A.H. 835, A.D. 1431).

May the merit of this good act be inserted in the scroll of the Khan's actions!

In this centre may the praises of the sermon read (in the name) of Mehmud Shāh

Be everlasting, so long as mountains stand on the earth and stars in the firmament.

<sup>2</sup> The following Persian inscription carved on the entrance arch shows that though it may have been repaired by Bāz Bahadur, the building of the palace was fifty years earlier (H. 914, A.D. 1508):

"In the time of the Sulta'n of Nations, the most just and great, and the most knowing and munificent Kha'ka'n Na'air Sha'h Khulji (A.D. 1500-1512). Written by Ya'suf, the year (H. 914) (A.D. 1508)."

## Appendix II.

### THE HILL FORT OF MANDU.

#### DESCRIPTION.

**Appendix II.****THE HILL FORT  
OF MANDU.****DESCRIPTION.**

To the south of Báz Bahádar's Palace a winding path climbs the steep slope of the southern rim of Mándu to the massive pillared cupolas of Rúp Matr's palace, which, clear against the sky, are the most notable ornament of the hill-top. From a ground floor of heavy masonry walls and arched gateways stairs lead to a flat masonry terrace. At the north and south ends of the terrace stand massive heavy-roofed pavilions, whose square pillars and pointed arches support lofty deep-grooved domes. The south pavilion on the crest of the Vindhyan cliff commands a long stretch of the south face of Mándu with its guardian wall crowning the heights and hollows of the hill-top. Twelve hundred feet below spreads the dim hazy Nímár plain brightened eastwards by the gleaming coil of the Nerbadi. The north pavilion, through the clear fresh air of the hill-top, looks over the entire stretch of Mándu from the high shoulder of Songad in the extreme south-west across rolling tree-brightened fields, past the domes, the tangled bush, and the broad gray of the Sea Lake, to the five-domed cluster of Hoshang's mosque and tomb, on, across a sea of green tree tops, to the domed roof-chambers of the Jaház and Tapela palaces, through the Delhi gateway, and, beyond the deep cleft of the northern ravine, to the bare level and the low ranges of the Málwa plain.

From the Rewa Pool a path, along the foot of the southern height among noble solitary *shamias* and *khums*, across fields and past small clusters of huts, guides to a flight of steps which lead down to a deep, shady rock-cut dell where a Muhammadan chamber with great open arched front looks out across a fountained courtyard and sloping scalloped water table to the wild western slopes of Mándu. This is Nilkanth, where the emperor Akbar lodged in A.D. 1574, and which Jehángir visited in A.D. 1617.<sup>1</sup>

From the top of the steps that lead to the dell the hill stretches west bare and stony to the Songad or Tárápúr gateway on the narrow neck beyond which rises the broad shoulder of Songad, the lofty south-west limit of the Mándu hill-top.<sup>2</sup>

**PART II—HISTORY.<sup>3</sup>****HISTORY.**

The  
Málwa Sultáns,  
A.D. 1400 - 1570.

The history of Mándu belongs to two main sections, before and after the overthrow by the emperor Akbar in A.D. 1563 of the independent power of the Sultáns of Málwa.

**SECTION I—THE MÁLWA SULTÁNS, A.D. 1400-1570.**

Of early Hindu Mándu, which is said to date from A.D. 313, nothing is known.<sup>4</sup> Hind spire stones are built into the Hindola palace walls; and the pillars of the lesser Jámá mosque, about a hundred yards from the east end of the sea or Sagar Lake, are Hindu apparently Jain. Of these local Hind chiefs almost nothing is known except that their fort was

<sup>1</sup> Translations of its two much-admired Persian inscriptions are given below pages 370-371.

<sup>2</sup> On the Tárápúr gateway a Persian inscription of the reign of the emperor Akbar (A.D. 1556-1605) states that the royal road that passed through this gateway was repaired by Tahir Máhammad Hasan Imad-ud-din.

<sup>3</sup> The Persian references and extracts in this section are contributed by Khán Sáheb Fazl-ul-lah Lutfullah Farídi of Surat.

<sup>4</sup> Sir John Malcolm in Eastwick's Handbook of the Panjáb, 119. This reference has not been traced. Farishtah (Elliot, VI. 563) says Mándu was built by Anand Dev of the Bais tribe, who was a contemporary of Khusráo Parwís the Sassanian (A.D. 691-621).

taken and their power brought to an end by Sultán Shams-ud-din Altamsh about A.D. 1234.<sup>1</sup> Dhár, not Mándu, was at that time the capital. It seems doubtful whether Mándu ever enjoyed the position of a capital till the end of the fourteenth century. In A.D. 1401, in the ruin that followed Timúr's (A.D. 1398-1400) conquest of Northern India, a Pathán from the country of Ghor, Diláwar Khán Ghori (A.D. 1387-1405), at the suggestion of his son Alp Khán, assumed the white canopy and scarlet pavilion of royalty.<sup>2</sup> Though Dhár was Diláwar's head-quarters he sometimes stayed for months at a time at Mándu,<sup>3</sup> strengthening the defences and adorning the hill with buildings, as he always entertained the desire of making Mándu his capital.<sup>4</sup> Three available inscriptions of Diláwar

## Appendix II.

THE HILL FORT  
OF MANDU.

## HISTORY.

The  
Málwa Sultáns,  
A.D. 1400-1570.

<sup>1</sup> The date is uncertain. Compare Elphinstone's History, 323; Briggs' Farishtah, I. 210-211, Tulu-kat-i-Násm in Elliot II. 328. The conquest of Mandu in A.D. 1237 is not Mandu in Malwa as Elphinstone and Briggs supposed, but Mandúr in the Siwálk Hills. See Elliot, Vol. II. page 325 Note 1. The Persian text of Farishtah (I. 115), though by mistake calling it Mandu (not Mándu), notes that it was the Mandu in the Siwálk hills. The poetical date-script also terms it Biladí-Siwálk or the Siwálk countries. The date of the conquest of the Siwálk Mandu by Altamsh is given by Farishtah (Ditto) as A.H. 624 (A.D. 1226). The conquest of Malwa by Altamsh, the taking by him of Bhilsah and Ujjain, and the destruction of the temple of Maha Kál and of the statue or image of Bikramajit are given as occurring in A.H. 631 (A.D. 1233). The Muat-i-Sikandari (Persian Text, 13) notices an expedition made in A.D. 1395 by Zafar Khán (Muzaffar I. of Gujarat) against a Hindu chief of Mandu, who, it was reported, was oppressing the Muslims. A siege of more than twelve months failed to capture the fort. <sup>2</sup> Briggs' Farishtah, IV. 170.

<sup>3</sup> Briggs' Farishtah, IV. 168. According to the Wakáit-i-Mushtáki (Elliot, IV. 552) Diláwar Khán, or as the writer calls him Amín Sháh, through the good offices of a merchant whom he had refrained from plundering obtained the grant of Mandu, which was entirely desolate. The king sent a mole and a horse, and Amín gave up walking and took to riding. He made his friends ride, enlisted horsemen, and promoted the cultivation of the country (Elliot, IV. 552). Farishtah (Pers. Text, II. 160-61) states that when Sultan Muhammad, the son of Firúz Tughlak, made Khwajah Sarwar his chief minister with the title of Khwajah Jehan, and gave Zafar Khán the viceroyalty of Gujarat and Khizr Khán that of Multan, he sent Diláwar Khán to be governor of Malwa. In another passage Farishtah (II. 461) states that one of Diláwar's grandfathers, Sultan Shahab-ud-din, came from Ghor and took service in the court of the Delhi Sultans. His son rose to be an *Amir*, and his grandson Diláwar Khán, in the time of Sultan Firúz, became a leading nobleman, and in the reign of Muhammad, son of Firúz, obtained Málwa in fief. When the power of the Tughlaks went to ruin Diláwar assumed the royal emblems of the umbrella and the red-tent.

<sup>4</sup> Diláwar Khán Ghori, whose original name was Húscin, was one of the grandsons of Sultán Shahab-ud-din Muhammad bin Sam. He was one of the nobles of Muhammad, the son of Firúz Tughlak, who after the death of that monarch, settled in and asserted his power over Málwa. (Pers. Text Farishtah, II. 160) The emperor Jehangir (who calls him Ámíd Sháh Ghori) attributes to him the construction of the fort of Dhár. He says (Memoirs Pers. Text, 201-202): Dhár is one of the oldest cities of India. Rája Bhuj, one of the famous ancient Hindu kings, lived in this city. From his time up to this a thousand years have passed. Dhár was also the capital of the Muhammadan rulers of Malwa. When Sultán Muhammad Tughlak (A.D. 1325) was on his way to the conquest of the Dakhan he built a cut stone fort on a raised site. Its outline is very elegant and beautiful, but the space inside is empty of buildings. Ámíd Sháh Ghori, known as Diláwar Khán, who in the days of Sultan Muhammad the son of Sultan Firúz, king of Delhi, gained the independent rule of Málwa, built outside this fort an assembly mosque, which has in front of it fixed in the ground a four-cornered iron column about four feet round. When Sultán Bahádur of Gujarat took Málwa (A.D. 1530-31) he wished to carry this column to Gujarat. In digging it up the pillar fell and broke in two, one piece measuring twenty-two feet the other thirteen feet. As it was lying here uncared-for I (Jehangir) ordered the big piece to be carried to Agra to be put up in the courtyard of the shrine of him whose abode is the heavenly throne (Akbar), to be utilised as a lamp post. The mosque has two gates. In

**Appendix II.****THE HILL FORT  
OF MANDU.****HISTORY.**

The  
Málwa Sultáns,  
A.D. 1100 - 1570.

Khán (A.D. 1387-1405) seem to show that he built an assembly mosque near the Ship Palace, a mosque near the Dehli Gate, and a gate at the entrance to Songadh, the south-west corner and citadel of Mándu, afterwards known as the Tárápúr Gate.

In A.D. 1398 Alp Khán, son of Diláwar Khán, annoyed with his father for entertaining as his overlord at Dhár Mehmúd Tughlak, the refugee monarch of Dehli, withdrew to Mándu. He stayed in Mándu for three years, laying, according to Farishtah, the foundation of the famous fortress of solid masonry which was the strongest fortification in that part of the world.<sup>1</sup> On his father's death in A.D. 1405 Alp Khán took the title of Sultán Hoshang and moved the capital to Mándu. The rumour that Hoshang had poisoned his father gave Diláwar's brother in arms, Muzaffar Sháh of Gujarát (A.D. 1399-1411), an excuse for an expedition against Hoshang.<sup>2</sup> Hoshang was defeated at Dhár, made prisoner, and carried to Gujarat, and Muzaffar's brother Nasrat was appointed in his place. Nasrat failed to gain the goodwill either of the people or of the army of Málwa, and was forced to retire from Dhár and take refuge in Mándu. In consequence of this failure in A.D. 1408, at Hoshang's request Muzaffar set Hoshang free after a year's confinement, and deputed his grandson Ahmed to take Hoshang to Málwa and establish Hoshang's power.<sup>3</sup> With Ahmed's help Hoshang took Dhár and shortly after secured the fort of Mándu. Hoshang (A.D. 1405-1431) made Mándu his capital and spread his power on all sides except towards Gujarát.<sup>4</sup> Shortly after the death of Muzaffar I. and the accession of Ahmed, when (A.D. 1411) Ahmed was quelling the disturbances raised by his cousins, Hoshang, instead of helping Ahmed as requested, marched towards Gujarát and created a diversion in favour of the rebels by sending two of his nobles to attack Broach. They were soon expelled by Ahmed Sháh. Shortly after Hoshang marched to the help of the chief of Jhálaváda in Káthiaváda,

front of the arch of one gate they have fixed a stone tablet engraved with a prose passage to the effect that Ahmad Sháh Ghori in the year H. 808 (A.D. 1405) had the foundation of this mosque. On the other arch they have written a poetic inscription of which the following verses are a part:

The liege lord of the world.  
The star of the sphere of glory.  
The stay of the people.  
The sun of the zenith of perfection.  
The bulwark of the law of the Prophet, A'mid Sha'h Da'ud.  
The possessor of amiable qualities, the pride of Ghor.  
Dilawar Khan, the helper and defender of the Prophet's faith.  
The chosen instrument of the exalted Lord, who in the city of  
Dhar constructed the assembly mosque  
In a happy and auspicious moment on a day of lucky omen.  
Of the date 808 years have passed (A.D. 1405)  
When this fabric of Hope was completed.

<sup>1</sup> Briggs' Farishtah, IV. 169.

<sup>2</sup> When fellow-nobles in the court of the Tughlak Sultán, Zafar Khán (Sultán Muzaffar of Gujarát) and Dilawar Khán, bound themselves under an oath to be brothers in arms. Farishtah, Pers. Text II. 462.

<sup>3</sup> Briggs' Farishtah, IV. 173; Elphinstone's History, 678.

<sup>4</sup> Though their temples were turned into mosques the Jains continued to prosper under the Ghoris. At Deogarh in Lalitpura in Jhansi in the North-West Provinces an inscription of Samvat 1481, that is of A.D. 1424, records the dedication of two Jaina images by a Jain priest named Holi during the reign of Sháh Alambhaka of Mandapapura, that is of Sháh Alp Khán of Mándu that is Sultán Hoshang Ghori. Archaeological Survey of India, New Series, II. 120.

and ravaged eastern and central Gujarāt.<sup>1</sup> To punish Hoshang for these acts of ingratitude, between A.D. 1418 and 1422, Ahmed twice besieged Mānda, and though he failed to take the fort his retirement had to be purchased, and both as regards success and fair-dealing the honours of the campaign remained with Ahmed.<sup>2</sup> In A.D. 1421 Hoshang went disguised as a horse-dealer to Jājnagar (now Jājpur) in Cuttack in Orissa. He took with him a number of cream-coloured horses, of which he had heard the Rāja was very fond. His object was to barter these horses and other goods for the famous war elephants of Jājnagar. An accident in the camp of the disguised merchants led to a fight in which the Rāja was taken prisoner and Hoshang was able to secure 150 elephants to fight the Gujarāt Sultan.<sup>3</sup> During Hoshang's absence at Jājnagar Ahmed pressed the siege of Mānda so hard that the garrison would have surrendered had Hoshang not succeeded in finding his way into the fort through the south or Tārāpur Gate.<sup>4</sup> For ten years after the Gujarāt campaign, by the help of his minister Malik Mughis of the Khilji family and of his minister's son Mahmūd Khān, Mālwa prospered and Hoshang's power was extended. Hoshang enriched his capital with buildings, among them the Great Mosque and his own tomb, both of which he left unfinished. Hoshang's minister Malik Mughis (who received the title of Ulugh Aāzam Humayūn Khān) appears to have built the assembly mosque near the Sagar Lake in Hoshang's lifetime, A.D. 1431. Another of his buildings must have been a mint, as copper coins remain bearing Hoshang's name, and Mānda Shāhābad as the place of mintage.<sup>5</sup> In A.D. 1432, at Hoshangābad, on the left bank of the Narbada, about 120 miles east of Mānda, Hoshang, who was suffering from diabetes, took greatly to heart the fall of a ruby out of his crown. He said: A few days before the death of Fuz Tughlak a jewel dropped from his crown. Hoshang ordered that he should be taken to Mānda. Before he had gone many miles the king died. His nobles carried the body to the Madrasah or college in Shāhābad or Mānda, and buried him in the college on the ninth day of Zil Hajjah, the twelfth month of A.H. 838 = A.D. 1434. The year of Hoshang's death is to be found in the letters

Ah Shah Hoshang na mund: Mes, Shāh Hoshang stayed not.<sup>6</sup>

On Hoshang's death his son Ghazni Khān, with the title of Sullān Muhammad Ghori, succeeded. Malik Mughis, his father's minister, and the minister's son Mahmūd were maintained in power. In three years

## Appendix II

### THE HILL FORT OF MĀNDU.

#### HISTORY.

The  
Mālwa Sultāns,  
A.D. 1400-1570

<sup>1</sup> Farishtah, Pers. Text II, 161-62.

<sup>2</sup> Briggs' Farishtah, IV, 176, 178, 180-181, 183.     <sup>3</sup> Farishtah, Pers. Text II, 166-67.

<sup>4</sup> Briggs' Farishtah, IV, 180. In connection with the Tārāpur Gate Farishtah says (Pers. Text, II, 468): The fort of Mānda is built on the top of a mountain, and the line of its fortification is about twenty-eight miles in length. In place of a moat it is surrounded by a deep cloister, so that it is impossible to use missiles against it. Within the fort water and provisions are abundant and it includes land enough to grow grain for the garrison. The extent of its walls makes it impossible for an army to invest it. Most of the villages near it are too small to furnish supplies to a besieging force. The south or Tārāpur gate is exceedingly difficult of access. A horseman can hardly approach it. From whichever side the fort may be attempted, most difficult heights have to be scaled. The long distances and intervening hills prevent the watchers of the besieging force communicating with each other. The gate on the side of Delhi is of easier access than the other gates.

<sup>5</sup> It follows that Farishtah (Briggs, IV, 196) is mistaken in stating that Hoshang's son Muhammad gave Mānda the name of Shāhābad, the Abode of Joy.

<sup>6</sup> Farishtah, Pers. Text II, 172-173. It seems to follow that from the first the monument to Hoshang in Hoshangābad was an empty tomb. Compare Briggs' Farishtah, IV, 180-190.

## Appendix II.

THE HILL FORT  
OF MANDUR.

History.

The  
Malwa Sultans,  
A.D. 1100-1570.

(A.D. 1133-1136), as Sultān Muhammad proved dissipated cruel and suspicious, Mehmūd, the minister's son, procured his death by poison. Mehmūd Khulp then asked his father to accept the succession, but his father declined, saying that Mehmūd was fitter to be king. In A.D. 1136 Mehmūd was accordingly crowned with the royal tiara of Hoshang.<sup>1</sup> He conferred on his father the honour of being attended by mace-bearers carrying gold and silver sticks, who, when the Khan mounted or went out, had, like the mace-bearers of independent monarchs, the privilege of repeating the *Bismillah* 'In the name of the compassionate and merciful Allāh.'<sup>2</sup> He gave his father royal honours, the white canopy and the silver quiver, and to his title of Malik Ashraf Khān Jehan he added among others Amīr-ul-Umara and Aazam Humayun.<sup>3</sup> Mehmūd quelled a revolt among his nobles. An outbreak of plague in the Gujrat camp relieved him from a contest with Ahmed Shah.<sup>4</sup> In A.D. 1139 Mehmūd repaired the palace of Sultan Hoshang and opened the mosque built in commemoration of that monarch which Farishtah describes as a splendid edifice with 208 columns.<sup>5</sup> About the same time Mehmūd completed Hoshang's tomb which Hoshang had left unfinished. On the completion of this building Hoshang's remains seem to have been moved into it from their first resting-place in the college. In A.D. 1141 Mehmūd built a

<sup>1</sup> The following more detailed, but also more confused, story is told in the Wakā'at-i-Mushāki (Elbet IV, 552-51). A man named Mehmūd, son of Mughis Khulp, came to Hoshang and entered his service. He was a treacherous man, who secretly aspired to the throne. He became minister, and gave his daughter in marriage to the king. [Farishtah Pers. Text II, 171 says: "Malik Mughis gave his daughter (Mehmūd's sister) in marriage not to Hoshang, but to Hoshang's son Muhammad Shah."] His father Malik Mughis, coming to know of his son's ambitious designs, informed the king of them. It upon Mehmūd feigned illness, and to deceive the king's physicians shut him in a dark room and drank the blood of a newly killed goat. When the physicians came Mehmūd rose hastily, threw up the blood into a basin, and tossing back his head rolled on the floor as if in pain. The physicians called for a light. When they saw that what Mehmūd had spat up was blood they were satisfied of his sickness, and told the king that Mehmūd had not long to live. The king refrained from killing a young man. This strange story seems to be an embellishment of a passage in Farishtah (Pers. Text II, 177). When Khān Jehan, that is Malik Mughis the father of Mehmūd, was ordered by Sultan Muhammad to take the field against the Rippat rebels of Nadoti (Nadot?) many of the old nobles of Malwa went with him. In their absence the party hostile to the Khulps represented to Sultan Muhammad that Mehmūd Khulp was plotting his death. On hearing that the Sultan was enraged against him Mehmūd secluded himself from the Court on pretence of illness. At the same time he worked secretly and bribed Sultan Muhammad's cup-bearer to poison his master. On the death of Sultan Muhammad the party of nobles opposed to Mehmūd, concealing the fact of Muhammad's death, sent word that Muhammad had ordered him immediately to the palace, as he wanted to send him on an embassy to Gujrat. Mehmūd, who knew that the Sultan was dead, returned word to the nobles that he had viewed a long-reckoned conclusion as the sweeper of the shame of his patron Sultan Hoshang, but that if the nobles came to him and convinced him that the good of his country depended on his going to Gujrat he was ready to go and see Sultan Muhammad. The nobles were caught in their own trap. They went to Mehmūd and were seized and imprisoned by him.

<sup>2</sup> Farishtah, Pers. Text II, 180.

<sup>3</sup> Briggs' Farishtah IV, 196. These titles mean 'The Chief of Nobles, the Great, the August.'

<sup>4</sup> It is related that one of the pious men in the camp of Sultan Ahmed of Gujrat had a warning dream, in which the Prophet (to whom be peace) appeared to him and said, "The calamity of (spirit of) pestilence is coming down from the skies. Tell Sultan Ahmed to leave this country." This warning was told to Sultan Ahmed, but he disregarded it, and within three days pestilence raged in his camp. Farishtah Pers. Text, II, 484.

<sup>5</sup> Briggs' Farishtah, IV, 205, gives 230 minarets and 360 arches. This must have been an addition in the Text used by Briggs. These details do not apply to the building. The Persian text of Farishtah, II, 185, mentions 208 columns or pillars (*duyast o hasht i shu'mash*). No reference is made either to minarets or to arches.

garden with a dome and palaces<sup>1</sup> and a mosque at Naálchah about three miles north of the Dehli Gate of Mándu, a pleasing well-watered spot where the plateau of Málwa breaks into glades and knolls.<sup>2</sup> In A.D. 1413 in honour of his victory over Rána Kumbhá of Chitor, Mehmud built a beautiful column of victory,<sup>3</sup> seven storeys high, and a college in front of the mosque of Hoshang Ghorí. Facing the east entrance to the Great Mosque stands a paved ramp crowned by a confused ruin. As late as A.D. 1843 this ruin is described as a square marble chamber. Each face of the chamber had three arches, the central arch in two of the faces being a door. Above the arches the wall was of yellow stone faced with marble. Inside the chamber the square corners were cut off by arches. No roof or other trace of superstructure remained.<sup>4</sup> This chamber seems to be the basement of the column of victory which was raised in A.D. 1413 by Mehmud I. (A.D. 1412-1469) in honour of his victory over Rána Kumbhá of Chitor.<sup>5</sup> Mehmud's column has the special interest of being, if not the original, at least the cause of the building of Kumbhá Rána's still more famed Victory Pillar, which was completed in A.D. 1454 at a cost of £900,000 in honour of his defeat of Mehmud.<sup>6</sup> That the Mándu Column of Victory was a famous work is shown by Abul Fazl's reference to it in A.D. 1590 as an eight-storied minaret.<sup>7</sup> Farishtah, about twenty years later (A.D. 1610), calls it a beautiful Victory Pillar seven storeys high.<sup>8</sup> The emperor Jehangir (A.D. 1605-1627) gives the following account of Mehmud's Tower of Victory<sup>9</sup>: 'Thus day, the 29th of the month *Thi*, corresponding to July-August of A.D. 1617, about the close of the day, with the ladies of the palace, I went out to see the *Haft Manzár* or Seven Storeys, literally Seven Prospects. This building is one of the structures of the old rulers of Malwa, that is of Sultan Mehmud Khifí. It has seven storeys, and on each storey there are four porticos, and in each portico are four windows. The height of this tower is about 163 feet and its circumference 150 feet. From the surface of the ground to the top of the seventh storey there are one hundred and seventy-one steps.' Sir Thomas Herbert, the traveller, in A.D. 1626 describes it from hearsay, or at least at second-hand as a tower 170 steps high, supported by massive pillars and adorned with gates and windows very observable. It was built, he adds, by Khán Jehán who there has buried.<sup>10</sup>

<sup>1</sup> Farishtah, Pers. Text II. 187.

<sup>2</sup> Briggs' Farishtah, IV. 207. 'Male dm Central India, I. 3'. In A.D. 1817 Sir John Malcolm (Central India, I. 32 Note, 1) found one of Mehmud's pillars as a hot weather residence.

<sup>3</sup> Of the siege of Kumbhámer a curious incident is recorded by Farishtah (Pers. Text, II. 185). He says that a temple outside the town destroyed by Mehmud had a marble idol in the form of a goat. The Sultan ordered the idol to be ground into lime and sold to the Rajputs as betel nut lime, so that the Hindus might eat their god. The idol was perhaps a ram, not a goat. The temple would then have been a Sun-temple and the ram, the carrier or *vahan* of the Sun, would have occupied on the porch a position similar to that held by the bull in a Mahadeva temple.

<sup>4</sup> Ruins of Mándu, 13.

<sup>5</sup> In the end of A.H. 816 (A.D. 1412) Mehmud built a seven-storeyed tower and a college opposite the Jámí Mosque of Hoshang Shah. Briggs' Farishtah, IV. 210; Persian Text, II. 188.

<sup>6</sup> Compare Briggs' Farishtah, IV. 323.

<sup>7</sup> Gladwin's *Nis-i-Akbari*, II. 41.

<sup>8</sup> Briggs' Farishtah, IV. 210; Farishtah, Persian Text II. 188.

<sup>9</sup> Memoirs of the emperor Jehangir (Pers. Text) Sir Syed Ahmad's Edition, page 198, eleventh year of Jehangir, A.D. 1617.

<sup>10</sup> Herbert's Khán Jehán is doubtless Mehmud's father the minister Malik Mughis, Khán Jehán Aázam Humáyún. It cannot be Khán Jehán Pir Muhammad, Akbar's general, who after only a few months' residence was slain in Mándu in A.D. 1561, nor can it be Jehangir's great Afghan general, Khán Jehán Lodi (A.D. 1600-1630), as he

## Appendix II.

### THE HILL FORT OF MÁNDU.

#### HISTORY.

The  
Málwa Sultáns,  
A.D. 1400-1570.

## Appendix II.

THE HILL-FORT  
OF MANDU.

HISTORY.

The  
Malwa Sultans,  
A.D. 1100-1570.

Two years later (A.D. 1445) Mahmūd built at Māndu, and endowed with the revenues of several villages a large *Shifa Khānah* or Hospital, with wards and attendants for all classes and separate apartments for managers. He placed in charge of it his own physician Maulana Fazlullāh.<sup>1</sup> He also built a college to the east of the Jama mosque, of which traces remain.<sup>2</sup>

In A.D. 1455, though defeated, Mahmūd brought back from Gujarat the jewelled waistbelt of Gujarat, which in a daring charge he had taken from the tent of the Gujarat king Kutb-ud-din Shāh.<sup>3</sup> In A.D. 1441 Mahmūd's father died at Māndisar. Mahmūd felt the loss so keenly that he tore his hair like one bereft of reason.<sup>4</sup> After his father's death Mahmūd made his son Ghās-ud-din minister, and conferred the command of the army and the title of Nāẓam Humayun on his kinsman Taqī Khān. In A.D. 1469, after a reign of thirty-four years (A.D. 1436-1469) of maturing energy and activity,<sup>5</sup> Mahmūd died. Farishtah says of him: "His tent was his home—the field of battle his resting-place. He was polite, brave, just and learned. His Hindu and Musalmān subjects were happy and friendly. He guarded his lands from invaders. He made good his loss to any one who suffered from robbery in his domains, recovering the amount from the village in whose lands the robbery had taken place, a system which worked so well that theft and robbery became almost unknown. Finally, by a systematic effort he freed the country from the dread of wild beasts."<sup>6</sup>

In A.D. 1469 Mahmūd was succeeded by his son and minister Ghās-ud-din, to whose skill as a soldier much of Mahmūd's success had been due. On his accession Ghās-ud-din made his son Abū'l-Kādir Prime Minister and heir-apparent, and gave him the title of Nāẓm-ud-din. He called his nobles and in their presence handed his sword to Nāẓm-ud-din, saying: "I have passed thirty-four years in senseless fighting. I now devote my life to rest and enjoyment."<sup>7</sup> Ghās-ud-din, who never left Māndu during the whole thirty years of his reign (A.D. 1469-1499), is said to have completed the *Jahāz Mehel* or Ship Palace,<sup>8</sup> and the widespread buildings

was not in Mandu until A.D. 1528, that is more than a year after Herbert left India, Compare Herbert's *Travels*, 107-118; Elliot, VI, 249-323, VII, 7, 8, and 21, and Blochman's *Amir-Akbar*, 503-506.

<sup>1</sup> Briggs' Farishtah, IV, 211.

<sup>2</sup> Ruins of Mandu, 13. Farishtah has three mentions of colleges. One (Pers. Text, II, 175) as the place where the body of Hoshang was carried, probably that prayers ought to be said over it. In another passage in the reign of Mahmūd I, (Pers. Text, II, 180) he states that Mahmūd built colleges in his territories which became the envy of Shirāz and Samarkand. In a third passage he mentions a college (page 488) near the Victory Tower.

<sup>3</sup> Briggs' Farishtah, IV, 217. A different but almost incredible account of the capture of the royal belt is given in the *Mirāt-i-Sikandari*, Pers. Text, 159: When Sultan Kutb-ud-din, son of Sultan Muhammad, defeated Sultan Melosud Khilji at the battle of Kapadvanj, there was such a slaughter as could not be exceeded. By chance, in the heat of the fray, which resembled the Day of Judgment, the wardrobe-keeper of Sultan Kutb-ud-din, in whose charge was the jewelled belt, was by the restiveness of his horse carried into the ranks of the enemy. The animal there became so violent that the wardrobe-keeper fell off and was captured by the enemy, and the jewelled belt was taken from him and given to Sultan Mahmūd of Malwa. The author adds: This jewelled waistband was in the Malwa treasury at the time the fortress of Mandu was taken by the strength of the arm of Sultan Muzaffar (A.D. 1531). Sultan Mahmūd sent this belt together with a fitting sword and horse to Sultan Muzaffar by the hands of his son.

<sup>4</sup> Briggs' Farishtah, IV, 209.

<sup>5</sup> Briggs' Farishtah, IV, 231-235; Pers. Text, II, 503.

<sup>6</sup> Briggs' Farishtah, IV, 236.

<sup>7</sup> Ruins of Mandu, 6.

which round it. It seems probable that the Tapela Palace close to the south-east of the Ship palace and the lake and royal gardens immediately to the north and north-east of the Tapela palace were part of Ghias-ud-din's pleasure-houses and grounds. The scale of the ruins behind the Handola or Swingeot palace to the north, and their connection with the out-land to the west of the Jahaz Mehel, suggest that they also belonged to the palaces and women's quarters of the pleasure-loving Ghias-ud-din.

Of the surprising size and fantastic arrangements of Ghias-ud-din's pleasure city the fine Mandi Shadbad or Meade of Joy, curious details have been preserved. This Meade of Pleasure was a city not a palace. It contained 15,000 inhabitants, all of them women, none either old or plain-featured, and each trained to some profession or craft. Among them were the whole officers of a court besides courtiers, teachers, musicians, dancers, prayer-readers, embroiderers, and followers of all crafts and callings. Whenever the king heard of a beautiful girl he never rested till he obtained her. This city of women had its two regiments of guards, the Archers and the Carabineers, each 500 strong, its soldiers dressed like men in a distinguishing uniform. The archers were beautiful young Turki damsels, all armed with bows and arrows, the carabineers were Abyssinian maidens, each carrying a carbine. Attached to the palace and city was a deer park, where the Lord of Leisure used to hunt with his favourites. Each dweller in the city of women received her daily dole of grain and copper, and besides the women were many pensioners, nuns, parrots and pigeons, who also received the same dole as their owners. So evenly just was Ghias-ud-din in the matter of his allowances, that the prettiest of his favourites received the same allowance as the roughest courtesan.<sup>1</sup>

The Lord of the City of Pleasure was deeply religious. Whenever he was amusing himself two of his companions held in front of him a cloth to remind him of his shroud. A thousand *Hafizahs*, that is women who knew the Koran by heart, constantly repeated its holy verses and, under the orders of the king, whenever he changed his raiment the *Hafizahs* blow on his body from head to foot with their prayer-blessed breath.<sup>2</sup> None of the five daily prayers passed unprayed. If at any of the hours of prayer the king was asleep he was sprinkled with water, and when water failed to arouse him, he was dragged out of bed. Even when dragged out of bed by his servants the king uttered an improper or questionable word.

So keen was his sense of justice that when one of his courtiers pretending he had purchased her, brought to him a maiden of ideal beauty, and her relations, not knowing she had been given to the king, came to complain, though they gladly resigned her, the king grieved over his unconscious wrong. Besides paying compensation he mourned long and truly, and ordered that no more maidens should be brought to his palace.<sup>3</sup> So great was the king's charity that every night below his pillow he placed a bag containing some thousand gold-mohurs, and before evening all were distributed to the deserving. So religious was the king that he paid 50,000 *tankas* for each of the four feet of the ass of Christ. A man came bringing a fifth hoof, and one of the courtiers said, "My Lord, an ass has four feet. I never heard that it had five, unless perhaps the ass of Christ had five." "Who knows," the king replied, "it may be that this

## Appendix II.

THE HILL FORT  
OF MANDU.

HISTORY.

THE

MALWA ALTARS,  
A.D. 1400-1570.<sup>1</sup> Farishtah Pers. Text, II. 504-505.<sup>2</sup> Farishtah Pers. Text, II. 505.<sup>3</sup> Farishtah Pers. Text, II. 507.

**Appendix II.**  
**THE HILL FORT**  
**OF MANDU.**  
*HISTORY.*  
 The  
 Malwa Sultans  
 A.D. 1400-1570.

last man has told the truth, and one of the others was wrong. See that he is paid.' So sober was the king that he would neither look upon nor hear of intoxicants or stimulants. A potion that had cost 100,000 *tankas* was brought to him. Among the 300 ingredients one was nutmeg. The king directed the potion to be thrown into a drain. His favourite horse fell sick. The king ordered it to have medicine, and the horse recovered. "What medicine was given the horse?" asked the king. "The medicine ordered by the physicians," replied his servants. Fearing that in this medicine there might be an intoxicant, the king commanded that the horse should be taken out of the stables and turned loose into the forest.<sup>1</sup>

The king's spirit of peace steeped the land, which, like its ruler, after thirty years of fighting yearned for rest. For fourteen years neither inward malecontent nor foreign foe broke the quiet. In A.D. 1482 Bahlol Lodi advanced from Delhi to subdue Malwa. The talk of Mándu was Bahlol's approach, but no whisper of it passed into the charmed City of Women. At last the son-minister forced his way into the king's presence. At the news of pressing danger his soldier-spirit awoke in Ghiás-ud-din. His orders for meeting the invaders were so prompt and well-planned that the king of Delhi paid a ransom and withdrew. A second rest of fifteen years ended in the son-minister once more forcing his way into the Presence. In A.D. 1500 the son presented his father, now an aged man of eighty, with a cup of sherbet and told him to drink. The king, whose armlet of bezom stone had already twice made poison harmless, drew the stone from his arm. He thanked the Almighty for granting him, unworthy, the happiest life that had ever fallen to the lot of man. He prayed that the sin of his death might not be laid to his son's charge, drank the poison, and died.<sup>2</sup>

Ghiás-ud-din can hardly have shut himself off so completely from state affairs as the story-tellers make out. He seems to have been the first of the Malwa kings who minted gold. He also introduced new titles and ornaments, which implies an interest in his coinage.<sup>3</sup> Farishtah says that

<sup>1</sup> Wakat-i-Mushtaki in Elliot, IV, 551-579. Probably these are stock tales. The Gujarat historians give Muzaffar and Muhammad the Gold-giver (A.D. 1441-1451) credit for the horse-scorpion-essay. See Mirat-i-Sikandar (Pers. Text, 178).

<sup>2</sup> Briggs' Farishtah, IV, 236-239; Wakat-i-Jahangiri in Elliot, VI, 319-350; Wakat-i-Mushirah in Elliot, IV, 551-55; Madam's Central India, I, 35-36. The Mirat-i-Sikandar (Pers. Text, 160) has the following notice of Ghiás-ud-din: "The Sultans of Mándu had reached such a pitch of luxury and ease that it is impossible to imagine night exceeding it. Among them Sultán Ghiás-ud-din was so famous for his luxurious habits, that at present (A.D. 1611) if any one exceeds in luxury and pleasure, they say he is a second Ghiás-ud-din. The orders of the Sultán were that no event of a painful nature or one in which there was any touch of sadness should be related to him. They say that during his entire reign news of a sad nature was only twice conveyed to him: once when his son-in-law died and once when his daughter was brought before him clothed in white. On this occasion the Sultán is related to have simply said: 'Perhaps her husband is dead.' This he said because the custom of the people of India is that when the husband of a woman dies she gives up wearing coloured clothes. The second occasion was when the army of Sultán Bahlol Lodi plundered several of the districts of Chanderi. Though it was necessary to report this to the Sultán, his ministers were unable to communicate it to him. They therefore asked a band of actors (*dhands*) to assume the dress of Afgháns, and mentioning the districts to represent them as being pillaged and laid waste. Sultán Ghiás-ud-din exclaimed in surprise: 'But is the governor of Chanderi dead that he does not avenge upon the Afgháns the ruin of his country?'"

<sup>3</sup> Compare Catalogue of Indian Coins, The Mahomedan States, pages LIV, LV, and 116-121.

Ghiás-ud-din used to come out every day for an hour from his *harim*, sit on the throne and receive the salutations of his nobles and subjects, and give orders in all weighty matters of state. He used to entrust all minor affairs to his ministers; but in all grave matters he was so anxious not to shirk his responsibility as a ruler, that he had given strict orders that all such communications should be made to him at whatever time they came through a particular female officer appointed to receive his orders.<sup>1</sup>

According to most accounts Násir-ud-din was led to poison his father by an attempt of his younger brother Shajpat Khán, supported if not organised by some of Ghiás-ud-din's favourite wives to oust Nasir-ud-din from the succession.<sup>2</sup> In the struggle Nasir-ud-din triumphed and was crowned at Mandu in A.D. 1500.<sup>3</sup> The new king left Mandu to put down a revolt. On his return to Mandu he devoted himself to debauchery and to hunting down and murdering his brother's adherents. He subjected his mother Khureshd Ram to great indignities and torture to force from her information regarding his father's concealed treasures.<sup>4</sup> In a fit of drunkenness he fell into a reservoir. He was pulled out by four of his female slaves. He awoke with a headache, and discovering what his slaves had done put them to death with his own hand.<sup>5</sup> Some time after in A.D. 1512, he again fell into the reservoir, and there he was left till he was dead.<sup>6</sup> Nasir-ud-din was fond of building. His palace at Akharpúr in the Nimar plain about twenty miles south of Mandu was splendid and greatly admired.<sup>7</sup> And at Mandu besides his sepulchre<sup>8</sup> which the emperor Jehangir (A.D. 1617) mentions,<sup>9</sup> an

## Appendix II.

THE HILL FORT  
OF MANDU.

## HISTORY.

The  
Málwa Sultans,  
A.D. 1400-1570.

<sup>1</sup> Farishtah Pers. Text, II, 507.

<sup>2</sup> Farishtah (Pers. Text, II, 508) detailing how Nasir-ud-din came to power, says: "There was a difference between Nasir-ud-din and his brother Alá-ud-din. The mother of these princes, Khureshd Ram, who was the daughter of the Hindu chief of Baglana had taken Alá-ud-din the younger brother's side. After killing his father Nasir-ud-din ordered his mother to be dragged out of the *harim* and Alá-ud-din and his children to be slaughtered like lads."

<sup>3</sup> Briggs' Farishtah, IV, 238-239. Farishtah holds that Nasir-ud-din's murder of his father is not proved. He adds (Pers. Text, II, 515) that Nasir-ud-din was at Deccan where he had gone to quell the rebellion of the nobles when the news of Ghiás-ud-din's death reached him. He argues that as a parricide cannot flourish more than a year after his father's murder, and as Nasir-ud-din ruled for years after that event, he could not have killed his father.

<sup>4</sup> Farishtah Pers. Text, II, 516.

<sup>5</sup> Briggs' Farishtah, IV, 243. "The emperor Jehangir (Memoirs Pers. Text, 181) says that Nasir-ud-din had a disease which made him feel so hot that he used to sit for hours in water."

<sup>6</sup> Wákiát-i-Jehangiri in Elliot, VI, 350. Farishtah (Pers. Text, II, 517-18) says that Nasir-ud-din died of a burning-fever he had contracted by hard drinking and other evil habits, that he showed keen penitence before his death and bequeathed his kingdom to his third son Melanúd. The emperor Jehangir (Memoirs Pers. Text, 181) confirms the account of the Wákiát as to the manner of Nasir-ud-din's death.

<sup>7</sup> Briggs' Farishtah, IV, 243.

<sup>8</sup> The emperor Jehangir thus describes (Memoirs Pers. Text 181) his visit to Nasir-ud-din's grave. "It is related that when during his reign Sher Khán Afghán rúr (A.D. 1540-1556) visited Nasir-ud-din's grave he ordered his attendants to flagellate the parricide's tomb. When I visited the sepulchre I kicked his grave and ordered those with me to do the same. Not satisfied with this I ordered his bones to be dug out and burned and the ashes to be thrown into the Nerbada."

<sup>9</sup> Wákiát-i-Jehangiri in Elliot, VI, 350. The emperor Jehangir (Memoirs Pers. Text, 202) refers to the well-known bridge and water palace about three miles north of Ujjain as the work of Nasir-ud-din. He says: "On Sunday I reached Saahidpur near Ujjain. In this village is a river house with a bridge on which are alcoves both built by Nasir-ud-din Khalji (A.D. 1500-1512). Though the bridge is not specially praiseworthy the water-courses and cisterns connected with it have a certain merit."

**Appendix II.**  
**THE HILL FORT**  
**OF MANDU.**  
*HISTORY.*  
 The  
 Málwa Sultáns,  
 A.D. 1400-1570.

inscription shows that the palace now known by the name of Báḡ Bahádur was built by Násir-ud-dín

Násir-ud-dín was succeeded by his younger son (Mehmúd A.D. 1512-1530), who, with the title of Mehmúd the Second, was crowned with great pomp at Mandu. Seven hundred elephants in gold-embroidered velvet housings adorned the procession.<sup>1</sup> Shortly after his accession Mehmúd II. was driven out of Mandu by the revolt of the commandant Muháfiz Khán, but was restored by the skill and courage of Medani Rái his Rájput commander-in-chief.<sup>2</sup> A still more dangerous combination by Muzaffar II. (A.D. 1511-1526) of Gujarát and Sikandar Sháh Lodí (A.D. 1488-1516) of Dehli, was baffled by the foresight and energy of the same Rájput general. Mehmúd, feeling that his power had passed to the Hindus, tried to disband the Rájputs and assassinate Medani Rái. Failing in both attempts Mehmúd fled from Mandu to Gujarát, where he was well received by Sultán Muzaffar (A.D. 1511-1526).<sup>3</sup> They advanced together against Mandu, and in A.D. 1519, after a close siege of several months, took the fort by assault. The Rájput garrison, who are said to have lost 10,000 men fought to the last, consecrating the close of their defence by a general *jauar* or fire-sacrifice. Sultán Mehmúd entered Mandu close after the storming party, and while Mehmúd established his authority in Mandu, Muzaffar withdrew to Dhar. When Dhar was restored Mehmúd sent this message to Muzaffar at Dhar: "Mandu is a splendid fort. You should come and see it." "May Mandu," Muzaffar replied, "bring good fortune to Sultán Mehmúd. He is the master of the fort. For the sake of the Lord I come to his help. On Friday I will go to the fortress, and having had the sermon read in Mehmúd's name will return." On Muzaffar's arrival at Mandu Mehmúd gave a great entertainment;<sup>4</sup> and Muzaffar

<sup>1</sup> Briggs' *Farishtah*, IV. 216.

<sup>2</sup> Briggs' *Farishtah*, IV. 217-249; Malcolm's *Central India*, I. 38, writes the Rájput's name Maderay. The *Muāt-i-Sikandari* (Persian Text, 149-155), gives the form Medani Rái the Lord of the Battlefield, a title which the author says (page 149) Mehmúd conferred on the Rájput in acknowledgment of his prowess.

<sup>3</sup> The *Muāt-i-Sikandari* (Pers. Text, 154) gives the following details of Mehmúd's flight: Sultán Mehmúd, on pretence of hunting left Mandu and remained hunting for several days. The Hindus, whom Medani Rái had placed on guard over him, slept after the fatigue of the chase. Only some of the more trusted guards remained. Among them was a Rájput named Krishna, a Málwa *zamindar* who was attached to the Sultán. Mehmúd said to Krishna: "Can you find me two horses and show me the way to Gujarát that I may get aid from Sultán Muzaffar to punish these rascals? If you can, do so at once, and, Allah willing, you shall be handsomely rewarded." Krishna brought two horses from the Sultán's stables. Mehmúd rode on one and seated his dearest of wives, Ban Kanyá Khar, on the other. Krishna marched in front. In half the night and one day they reached the Gujarát frontier.

<sup>4</sup> *Tarikh-i-Sher Sháh* in Elliot, IV. 386. The *Muāt-i-Sikandari* (Pers. Text, 160) gives the following details of the banquet: Sultán Mehmúd showed great hospitality and humility. After the banquet as he led the Sultán over the palace, they came to a mansion in the centre of which was a four-cornered building like the Kaabah, carved and gilded, and round it were many apartments. When Sultán Muzaffar placed his foot within the threshold of that building the thousand beauties of Sultán Mehmúd's *harám*, magnificently apparelled and jewelled, all at once opened the doors of their chambers and burst into view like hiris and fairies. When Muzaffar's eyes fell on their charms he bowed his head and said: "To see other than one's own *harám* is sinful." Sultán Mehmúd replied: "These are mine, and therefore your's, seeing that I am the slave purchased by your Majesty's kindness." Muzaffar said: "They are more suitable for you. May you have joy in them. Let them retire." At a signal from Sultán Mehmúd the ladies vanished.

retired to Gujarát leaving a force of 3000 Gujarátis to help to guard the hill.<sup>1</sup> Immediately after Muzaffar's departure, as Sultán Mehmúd was anxious to recover Chauderi and Gágram, which still remained in the possession of Medáni Rái and his supporters, he marched against them. Rána Sága of Chitor came to Medám's aid and a great battle was fought.<sup>2</sup> Mehmúd's hastiness led him to attack when his men were weary and the Rajputs were fresh. In spite of the greatest bravery on the part of himself and of his officers the Musalmán army was defeated, and Mehmúd, weakened by loss of blood, was made prisoner. Rána Sága had Mehmúd's wounds dressed, sent him to Chitor, and on his recovery released him.<sup>3</sup>

In A.D. 1526, by giving protection to his outlawed brother Chánd Khán and to Razí-ul-Mulk, a refugee Gujarát noble, Mehmúd brought on himself the wrath of Bahádúr Sháh of Gujarát (A.D. 1526-1536). The offended Bahádúr did not act hastily. He wrote to Mehmúd asking him to come to his camp and settle their quarrels. He waited on the Gujarát frontier at Kapi Ghat, east of Baiswari, until at last satisfied that Mehmúd did not wish for a peaceful settlement he advanced on Mándu. Meanwhile Mehmúd had repaired the walls of Mándu, which soon after was invested by Bahádúr. The siege was proceeding in regular course by mines and batteries, and the garrison, though overtaxed, were still hard and in heart, when in the dim light of morning Mehmúd suddenly found the Gujarát flag waving on the battlements. According to the *Muht-i-Sikandari* Bahádúr annoyed by the slow progress of the siege asked his spies where was the highest ground near Mándu. The spies said: Towards Songad-Chitor the hill is extremely high. With a few followers the Sultan scaled Songad, and rushing down the slope burst through the wall and took the fort (May 20th, 1526). Mehmúd surrendered. Near Dohad, on his way to his prison at Champaur an attempt was made to rescue Mehmúd, and to prevent their escape he and some of his sons were slain and buried on the bank of the Dohad tank.<sup>4</sup> Bahádúr spent the rainy season (June-October 1526) in Mándu, and Malwa was incorporated with Gujarát.

Mándu remained under Gujarát, till in A.D. 1531, after Bahádúr's defeat by Humáyún at Mandasor Bahádúr retired to Mándu. Humáyún followed. At night 200 of Humáyún's soldiers went to the back of the fortress, according to Farishtah (the south-west angle of Songad<sup>5</sup> by which Bahádúr had surprised Chánd's garrison, scaled the walls by ladders and ropes, opened the gate, and let others in. Mallu Khán, the commandant of the batteries, a native of Málwa, who afterwards gained the title of Kádir Sháh, went to Bahádúr and awakened him. Bahádúr rushed out with four or five attendants. He was joined by about twenty more, and reaching the gate at the top of the *maulán*, apparently the Tárápúr gate by which Humáyún's men had entered, cut through 200 of Humáyún's troops and went off with Mallu Khán to the fort of Songad,

## Appendix II.

### THE HILL FORT OF MANDU.

#### HISTORY.

The  
Málwa Sultáns,  
A.D. 1400-1570.

Sultan Bahádúr  
of Gujarát,  
A.D. 1526-1536.

The Emperor  
Humáyún,  
A.D. 1534-1535.

<sup>1</sup> Briggs' Farishtah, IV, 250-262.

<sup>2</sup> Farishtah Pers. Text, II 527. According to the *Mirát-i-Sikandari* (Pers. Text, 161) Mehmúd marched against Gágram first, and slew Hemkaran, a partisan of Medáni Rái, in a hand-to-hand fight. On this the Rána and Medám Rái joined their forces against Mehmúd.

<sup>3</sup> Briggs' Farishtah, IV, 262-263.

<sup>4</sup> Persian Edition, 239.

<sup>5</sup> Briggs' Farishtah, IV, 267-68. Sultan Bahádúr apparently surprised the party in charge of the Tárápúr or Southern Gate.

<sup>6</sup> Briggs' Farishtah, IV, 269; *Mirát-i-Ahmedi*, Persian Text, I, 76.

<sup>7</sup> Briggs' Farishtah, II, 77.

**Appendix II****THE HILL FORT  
OF MANDU.****HISTORY.**

The  
Malwa Sultans,  
A.D. 1400-1570.

Local  
Musalman Chiefs,  
A.D. 1536-1542.

Sher Shah Sūn,  
A.D. 1542-1545.

the citadel of Māndu. While two of Bahādur's chiefs, Sadr Khān and Sultān Alam Lodī, threw themselves into Songad, Bahādur himself let his horses down the cliff by ropes and after a thousand difficulties made his way to Chāmpānī.<sup>1</sup> On the day after Bahādur's escape Sadr Khān and Sultān Alam Lodī came out of Songad and surrendered to Humāyūn.<sup>2</sup>

In the following year (A.D. 1555) the combined news of Sher Shāh's revolt in Bengal, and of the defeat of his officers at Broach and Cambay, forced Humāyūn to retire from Gujarāt. As he preferred its climate he withdrew, not to Agra but to Māndu.<sup>3</sup> From Māndu, as fortune was against him in Bengal, Humāyūn went (A.D. 1555-56) to Agra.

On Humāyūn's departure three chiefs attempted to establish themselves at Māndu: Bhupat Rai, the ruler of Bijagar, sixty miles south of Māndu; Mallu Khān or Kādū Shāh, a former commandant of Māndu, and Mirān Muhammad Faruki from Burhanpur.<sup>4</sup> Of these three Mallu Khān was successful. In A.D. 1536 when Humāyūn fled from Sher Shāh to Persia, Mallu spread his power from Māndu to Ujjain Sīrangpur and Rantambhor, assumed the title of Kādū Shāh Malwa, and made Māndu his capital. Some time after Sher Shāh, who was now supreme, wrote to Mallu Kādū Shāh ordering him to co-operate in expelling the Mughals. Kādū Shāh, resenting this assumption of overlordship, addressed Sher Shāh as an inferior. When Sher Shāh received Mallu's order he folded it and placed it in the scabbard of his pommel to keep the indignity fresh in his mind. Allah willing, he sent, ye shall ask an explanation for this in person. In A.D. 1542 on 9<sup>th</sup> of Muharrar Kādū Shāh failed to act with Kutb Khān, who had been sent to establish Sher Shāh's overlordship in Malwa, Sher Shāh advanced from Gwalior towards Māndu with the object of punishing Kādū Shāh.<sup>5</sup> As he knew he could not stand against Sher Shāh Kādū Shāh went to Sarangpur to do homage. Though on arrival Kādū Shāh was well received, his kingdom was given to Shujaat Khān, one of Sher Shāh's chief followers, and himself placed in Shujaat Khān's keeping.<sup>6</sup> Suspicious of what might be in store for

<sup>1</sup> Abul Fazl's Akbar Namah in Elliot, VI, 14, Briggs' Farsihtah, II, 77.

<sup>2</sup> Abul Fazl's Akbar Namah in Elliot, V, 192.

<sup>3</sup> Abul Fazl's Akbar Namah in Elliot, VI, 15, Briggs' Farsihtah, II, 80-81.

<sup>4</sup> Abul Fazl's Akbar Namah in Elliot, VI, 18. According to Farsihtah (Pers. Text, II, 532) Mallu, the son of Mallu, was a native of Malwa and a Khilji slave noble. Mallu received his title of Kādū Shāh from Sultan Mahmūd III, of Gujarāt (A.D. 1536-1544) at the recommendation of his minister Inad-ul-Mulk who was a great friend of Mallu. Mu'taz Sikandarī Persian Text, 398.

<sup>5</sup> Farsihtah Pers. Text, II, 532.

<sup>6</sup> Tankh-e-Sher Shāh in Elliot, IV, 391, Briggs' Farsihtah, IV, 271-72.

<sup>7</sup> Farsihtah (Pers. Text, 533-34) refers to the following circumstance as the cause of Kādū Shāh's suspicion. On his way to Sher Shāh's darbar at Ujjain Kādū saw some Mughal prisoners in chains making a road. One of the prisoners seeing him began to sing:

*Maro na tu darta abad a phir khushtā se kār?*

In this plight thou seest me to-day,

Thine own turn is not far away.

When Kādū Shāh escaped, Sher Shāh on hearing of his flight exclaimed:

*Ba na ch karā dār*

*Mallu chātā naqab,*

Thus he treats us with scorn,

Mallu the slave base born.

To this one of Sher Shāh's men replied:

*Kād-e Rasul har haqq*

*La khawā al abār,*

The words of the Prophet are true,

No good can a slave ever do.

him Kádir Sháh fled to Gújarát. Sher Sháh was so much annoyed at Shuját Khan's remissness in not preventing Kádir Sháh's escape that he transferred the command at Dhar and Mandu from Shuját Khan to Hap Khan and Junaid Khán. Shortly after Kádir Sháh brought a force from Gújarat and attacked Mandu. Shuját came to Hap Khán's help and routed Kádir Sháh under the walls of Mándu. In reward Sher Sháh made him ruler of the whole country of Mandu.<sup>1</sup> Shuját Khán established his head-quarters at Mandu with 10,000 horse and 7000 matchlockmen.

During the reign of Sher Sháh's successor Salim Sháh (A.D. 1545-1553), Shuját was forced to leave Malwa and seek shelter in Dúngarpúr. Selim pardoned Shuját, but divided Malwa among other nobles. Shuját remained in Hindustan till in A.D. 1543 on the accession of Salim's successor, Adilsháh, he recovered Malwa and in A.D. 1551,<sup>2</sup> on the decay of Adilsháh's power, assumed independence.<sup>3</sup> He died almost immediately after, and was succeeded by his eldest son Malik Báyazid. Shuját Khan was a great builder. Besides his chief works at Shujawalpur near Ujjain, he left many monuments in different parts of Malwa.<sup>4</sup> So far none of the remains at Mandu are known to have been erected during the rule of Shuját Khan.

On the death of his father Malik Báyazid killed his brother Daulat Khán and was crowned in A.D. 1555 with the title of Baz Bahadur. He attacked the Gondhs but met with so crushing a defeat that he forswore fighting.<sup>5</sup> He gave himself to enjoyment and became famous as a musician,<sup>6</sup> and for his poetic love of Rup Maan or Rup Mati, who according to one account was a wise and beautiful courtesan of Siderampur in Northern India, and according to another was the daughter of a Nuar Ráput, the master of the town of Dharanpur.<sup>7</sup> In A.D. 1560 Pir Muhammad, a general of Akbar's, afterwards ennobled as Khan Jehán, defeated Baz Bahadur, drove him out of Mandu, and made the hill his own head-quarters.<sup>8</sup> In the following year (A.D. 1561), by the help of the Bérar chief Pír Muhammad was slain and Baz Bahadur reinstated. On news of this defeat (A.D. 1562) Akbar sent Abdullah Khán Uzbak with almost unlimited power to reconquer the province. Abdullah was successful, but, as he showed signs of assuming independence, Akbar moved against him and he fled to Gújarat.<sup>9</sup> Akbar remained in Mándu during the greater part of the following years (A.D. 1563), examining with interest the buildings erected by the Khilji kings.<sup>10</sup> At Mandu Akbar married the daughter of Miran Mirbárak Khán of Khandesh.<sup>11</sup> When Akbar left (August 1564) he appointed Kurra Bahádúr Khan governor of Mandu and returned to Agra.<sup>12</sup> In A.D. 1568 the Mirzas Akbar's cousins, flying from Gújarat attacked

**Appendix II.****THE HILL FORT  
OF MANDU.****HISTORY.**

The  
Malwa Sultáns,  
A.D. 1400-1570.

Salim Shah Súr,  
A.D. 1545-1553.

Baz Bahadur,  
A.D. 1555-1570.

<sup>1</sup> *Tárikh-i-Sher Sháh* in Elliot, IV. 397.

<sup>2</sup> *Tárikh-i-Alfi* in Elliot, V. 168; Elphinstone's India, 402-403.

<sup>3</sup> *Tárikh-i-Alfi* in Elliot, V. 168.

<sup>4</sup> Briggs' *Farishtah*, IV. 276.

<sup>5</sup> When Baz Bahadur attacked the Gondhs their chief was dead and his widow, Rám Durgavati, was ruling in his place. The Rám led the Gondhs against the invaders, and hemming them in one of the passes, inflicted on them such a defeat that Baz Bahadur fled from the field leaving his baggage and camp in her hands. *Farishtah Pers. Text*, II. 538.

<sup>6</sup> According to *Farishtah* (Pers. Text, II. 538) Baz Bahadur was already an adept in music.

<sup>7</sup> Malcolm's *Central India*, I. 39, *Ruins of Mandu*, 30.

<sup>8</sup> Briggs' *Farishtah*, II. 210.

<sup>9</sup> Blochman's *Am-i-Akbari*, 321.

<sup>10</sup> Briggs' *Farishtah*, IV. 211.

<sup>11</sup> Briggs' *Farishtah*, IV. 216.

<sup>12</sup> *Tabakát-i-Akbari* in Elliot, V. 291.

**Appendix II.****THE HILL FORT  
OF MANDU.****HISTORY.****The Mughals,  
A.D. 1570-1720.**

Ujjain. From Ujjain they retreated to Māndu and failing to make any impression on the fort withdrew to Gujarāt.<sup>1</sup> The Mirzās' failure was due to the ability of Akbar's general, Hāji Muhammad Khān, to whom Akbar granted the province of Māndu.<sup>2</sup> At the same time (A.D. 1568) the command of Mandu hill was entrusted to Shāh Budāgh Khān, who continued commandant of the fort till his death many years later. During his command, in a picturesque spot overlooking a well-watered ravine in the south of Māndu, between the Sāgar Lake and the Tārāpur Gateway, Budagh Khan built a pleasure-house, which he named, or rather perhaps which he continued to call Nilkanth or Blue Throat. This lodge is interesting from the following inscriptions, which show that the emperor Akbar more than once rested within its walls.<sup>3</sup>

The inscription on the small north arch of Nilkanth, dated A.D. 1574, runs :

(Call it not waste) to spend your life in water and earth (i.e. in building).  
If perchance a man of mind for a moment makes your house his lodging.  
Written by Shāh Budagh Khān in the year A.H. 983-87.<sup>4</sup>

The inscription on the great southern arch of Nilkanth, dated A.D. 1571, runs

This pleasant building was completed in the reign of the great Sultan, the most munificent and just Khān, the Lord of the countries of Arabia and Persia, the shadow of God on the two earths, the ruler of the sea and of the land, the exalter of the standards of those who war on the side of God, Abul Fatah Jalāl-ud-dīn Muhammad Akbar, the warrior king, may his dominion and his kingdom be everlasting.

Written by Faridun Husain, son of Hātim-al-Wardī, in the year A.H. 982.<sup>5</sup>

The inscription on the right wall of Nilkanth, dated A.D. 1591-92, runs :

In the year A.H. 1000, when on his way to the conquest of the Dakhan, the slaves of the Exalted Lord of the Earth, the holder of the sky-like Throne, the shadow of Allah (the Emperor Akbar), passed by this place.

That time wastes your home cease, Soul, to complain,  
Who will not scorn a complainer so vain.

From the story of others this wisdom derive,  
Ere naught of thyself but stories survive.

The inscription on the left wall of Nilkanth, dated A.D. 1600, runs :

The (Lord of the mighty Presence) shadow of Allah, the Emperor Akbar, after the conquest of the Dakhan and

<sup>1</sup> *Talakat-i-Akbari* in Elliot, V. 330-31.

<sup>2</sup> Blochman's *Ain-i-Akbari*, 375.

<sup>3</sup> The emperor Jahāngir thus describes (*Memoirs Pers. Text.* 372) a visit to this building : On the third day of Anarād (July, 1617) with the palace ladies I set out to see Nilkanth which is one of the pleasantest places in Mandu fort. Shāh Budagh Khān, who was one of the trusted nobles of my august father, built this very pleasing and joy-giving lodge during the time he held this province in fief (A.D. 1572-1577). I remained at Nilkanth till about an hour after nightfall and then returned to my state quarters.

<sup>4</sup> An officer who distinguished himself under Humāyūn, one of Akbar's commanders of Three Thousand, long governor of Mandu, where he died. Blochman's *Ain-i-Akbari*, 372.

<sup>5</sup> When opposed to Ārah the word Ājam signifies all countries except Arabia, and in a narrow sense, Persia. The meaning of the word Ājam is dumbness, the Arabs so glorying in the richness of their own tongue as to hold all other countries and nations dumb.

<sup>6</sup> The stones on which this inscription is carved have been wrongly arranged by some restorer. Those with the latter portion of the inscription come first and those with the beginning come last. Munshi Abdur Rulim of Dhār.

Da'ndes (Khandesh) in the year A.H. 1009 set out for Hind (Northern India).

May the name of the writer last for ever!

At dawn and at eve I have watched an owl sitting

On the lofty wall-top of Shirwan Shah's Tomb.<sup>1</sup>

The owl's plaintive hooting convey'd me this warning

"Here pomp, wealth, and greatness lie dumb."

In A.D. 1573, with the rest of Málwa, Akbar handed Mandu to Muzaffar III the dethroned ruler of Gujarát. It seems doubtful if Muzaffar ever visited his new territory.<sup>2</sup> On his second defeat in A.D. 1562 Baz Bahádur retired to Gondwána, where he remained, his power gradually waning, till in A.D. 1570 he paid homage to the emperor and received the command of 2000 horse.<sup>3</sup> His decoration of the Rewa Pool, of the palace close by, which though built by Násir-ud-din Khilji (A.D. 1500-1512) was gradually repaired by Baz Bahádur, and of Rúp Matí's pavilion on the crest of the southern ridge make Baz Bahádur one of the chief beautifiers of Mandu. According to Farishtah (Pers. Text, II. 538-39) in 1562, when Baz Bahádur went out to meet Akbar's general, Adham Khán Atkah, he placed Rúp Matí and his other singers in Saugpur under a party of his men with orders to kill the women in case of a reverse. On learning of Baz Bahádur's defeat the soldiers hastily seized as many of the women as they could and fled. Among the women left for dead was Rúp Matí, who, though dangerously wounded, was not killed. When Adham Atkah entered Saugpur his first care was to enquire what had become of Rúp Matí. On hearing of her condition he had her wound attended to by the best surgeons, promising her as a help to her cure, a speedy union with her beloved. On her recovery Rúp Matí claimed the general's promise. He prevaricated and possessed his own suit. Rúp Matí despaired. One night the impatient Turk sent her a message urging her to come to him. Rúp Matí began time invited him to her own pavilion which she said was specially adorned to be the abode of love. Next night the Atkah went to her house in disguise. Her women directed him to Rúp Matí's couch. Adham found her robed and garlanded, but cold in death. Rúp Matí was buried on an island on a lake at Ujjain, and there, according to the *Ain-i-Akbari*, Baz Bahádur when he died was laid beside her.<sup>4</sup>

#### SECTION II.—MUGHALS (A.D. 1570-1720) AND MARÁTHÍS (A.D. 1720-1820).

About A.D. 1590 Akbar's historian, the great Abul Fazl, described Mandu as a large city whose fortress is twenty-four miles (twelve *kos*) in circuit. He notices that besides in the centre of the hill where stands an eight-storeyed minaret, the city had many monuments of ancient magnificence, among them the tombs of the Khilji Sultans. And that from the dome which is over the sepulchre of Subán Mahmud, the son of Hoshang (this should be the sepulchre of Hoshang built by his successor Sultán Mahmud) water drops in the height of summer to the astonishment of the ignorant. But, he adds, men of understanding know how to account for the water-drops.<sup>5</sup> Abul Fazl farther notices that on Mandu Hill is found a species of tamarind whose fruit is as big as the coconut, the pulp of

#### Appendix II.

THE HILL FORT  
OF MANDU.

*HISTORY.*

The Mughals,  
A.D. 1570-1720.

<sup>1</sup> The maternal uncle of Nanshirwán (A.D. 586-635) the Assinian, Shirwán Sháh was ruler of a district on Mount Caucasus. *Al Masûdî*, Arabic Text *Præfatus* d'Or, II. 4, and *Rauzat-us-Safa*, Persian Text, I. 259.

<sup>2</sup> Blochman's *Ain-i-Akbari*, 353.

<sup>4</sup> Blochman's *Ain-i-Akbari*, 429.

<sup>3</sup> Briggs' *Farishtah*, IV. 279.

<sup>5</sup> Gladwin's *Ain-i-Akbari*, II. 41.

## Appendix II.

THE HILL-FORT  
OF MANDU

## HISTORY.

The Mughals,  
A.D. 1570-1720.

which is very white. This is the African baobab or *Adansonia digitata*, known in Hindustani as *goramli* or white tamarind, whose great fruit is about the size of a cocoanut. Its monster baobabs are still a feature of Mandu. Some among them look old enough to have been yielding fruit 300 years ago. Finally Abul Fazl refers to Mandu as one of twenty-eight towns where Akbar's copper coins were struck.<sup>1</sup> About twenty years later (A.D. 1610) the historian Farishtah<sup>2</sup> thus describes the hill. The fort of Mandu is a work of solid masonry deemed to be one of the strongest fortifications in that part of the world. It is built on an insulated mountain thirty-eight miles in circumference.<sup>3</sup> The place of a ditch round the fortification is supplied by a natural ravine so deep that it seems impossible to take the fort by regular approaches. Within the fort is abundance of water and forage, but the area is not large enough to grow a sufficient store of grain. The hill cannot be invested. The easiest access is from the north by the Delhi Gate. The south road with an entrance by the Tarapur Gate is so steep that cavalry can with difficulty be led up. Like Abul Fazl Farishtah notices that, except during the rains, water constantly oozes from between the chunks in the masonry of the dome of Sultan Hoshang's tomb. He says the natives of India attribute this dripping to universal veneration for Sultan Hoshang, for whose death, they say, the very stones shed tears.

Except that copper coins continued to be minted and that it was nominally one of the four capitals of the empire, during the emperor Akbar's reign Mandu was practically deserted. The only traces of Akbar's presence on the hill are in two of the five inscriptions already quoted from the Nulkamh pleasure house, dated A.D. 1594 and A.D. 1600.

After about fifty years of almost complete neglect the emperor Jehangir, during a few months in A.D. 1617, enabled Mandu once more to justify its title of Shadabad, the Abode of Joy. Early in March A.D. 1617, in the eleventh year of his reign, the emperor Jehangir after spending four months in travelling the 180 mls. from Ajmer by way of Ujjain, arrived at Naalehah on the main land close to the north of Mandu. The emperor notices that most of the forty-six marches into which the 180 miles were divided ended on the bank of some lake, stream or great river in green grass and woody landscape, brightened by poppy fields. We came, he writes, enjoying the beauty of the country and shooting, never weary, as if we were moving from one garden to another.

Of the country round Naalehah Jehangir says: "What can be written worthy of the beauty and the pleasantness of Naalehah. The neighbourhood is full of mango trees. The whole country is one unbroken and restful evergreen. Owing to its beauty I remained there three days. I granted the place to Kamal Khan taking it from Keshava Maru, and I changed its name to Kamalpur. I had frequent meetings with some of the wise men of the *jajirs*, many of whom had assembled here. Naalehah is one of the best places in Malwa. It has an extensive growth of vines, and among its mango groves and vineyards wander streamlets of water. I arrived at a time when, contrary to the northern climes, the vines were in blossom and fruit, and so great was the vintage that the meanest boor could eat grapes to his fill. The poppy was also in flower, and its fields delighted the eye with their many-coloured beauty."

<sup>1</sup> Blochman's *Ain-i-Akbari*, 31.<sup>2</sup> Briggs' Farishtah, IV. 169, 181, 190.<sup>3</sup> *Nauveren Kos*, taking the *Kos* to be two miles.<sup>4</sup> The emperor Jehangir's Memoirs, Pers. Text, Sir Sayad Ahmed's Edition, 173-203.

Of the emperor's entrance into Mándu the Memoirs have the following note: On Monday the 23rd of Ispandád, the last month of the Persian year, that is according to Sir Thomas Roe's account on the 6th of March 1617, when one quarter of the day had passed, I mounted my elephant, and, in good fortune and under kindly influences, made my happy entry into the fort of Mándu. About an hour (three *ghadis*) later I entered the quarters which had been prepared to receive me. During my passage across the hill-top I scattered Rs 1500. Before my arrival Abdul Karim the engineer had been sent by me to repair the buildings of the former kings of Mándu. While my fortunate standards were at Ajmir Abdul Karim repaired such of the old Mándu buildings as were fit to be repaired and built others anew. On the whole he had provided quarters for me the like of which have probably never been built in any other place. Three *lakh*s of rupees were spent on these repairs and buildings. I wish it had been possible to construct buildings like these in all cities likely to be visited by royalty. This fortress he continues stands on the top of a hill about thirty-six miles (18 *kos*) in circumference. They say that before the days of Raja Bikramájit a king was reigning over these parts who name was Jaisingh Deva. In his time a man went to the forest to cut grass. When he brought the grass back he found that the blade of his sickle had turned yellow. The grass-cutter in his surprise went to Mandan, a nonsmith. Mandan knew that the sickle was gold. He had heard that in those parts was to be found the philosopher's stone, whose touch turns iron and copper into gold. He told the grass-cutter to lead him to the place where the sickle had turned yellow and there he found the philosopher's stone. The smith presented this treasure to his king. The king amassed untold wealth, part of which he spent in building Mandan fortress which he completed in twelve years. At the request of the smith on most of the stones in the walls a mark was cut in the form of an anvil. Towards the close of his life when king Jaisingh Deva withdrew his heart from the world he called many Brahmans together on the bank of the Narbada close to Mandan. He gave each Brahman a share of his wealth. And to the Brahman in whom he had the greatest faith he gave the philosopher's stone. Enraged at the gift of a paltry stone the Brahman threw it into the Narbada and there the philosopher's stone still lies. The emperor continues. On the 20th of *Farvardin*, five weeks after my arrival (11th April 1617) in reward for his services in repairing the buildings of Mándu, I conferred on my engineer Abdul Karim the command of 1200 horse, with the title of Mampur Khan.

Mándu had for the emperor the strong attraction of abundance of game. Among numerous entries of *adgar* or lone-bull shooting the following occur. On the 1th of the first month of *Farvardin* (16th) March the watchmen of the chase brought word that they had marked down a lion near the Sagar Lake, which is a construction of the ancient rulers of Mándu. I mounted and proceeded towards the lake. When the lion broke cover he attacked and wounded ten or twelve of the *Ahadis*<sup>1</sup> and other men of my retinue. In the end I brought him down with three gun shots and saved God's creatures from his evil. On the 22nd of the same month (April 3rd, 1617) the watchmen brought news of a tiger. I mounted forthwith and despatched him with three bullets. On the 7th of *Ardi Bihisht* (April 18th, 1617) the watchmen brought word that they had marked down four tigers. At one in the afternoon I started for the

## Appendix II.

THE HILL FORT  
OF MANDU.

HISTORY.

The Mughals,  
A.D. 1570 - 1720.

<sup>1</sup> Literally single-men. The *Ahadis* were a corps of men who stood immediately under the emperor's orders. Blochman's *Ain-i-Akbari*, 20 note 1.

**Appendix II.**  
**THE HILL FORT**  
**OF MANDU.**  
**HISTORY.**  
**The Mughals,**  
**A.D. 1570-1720.**

place with Nūr Jehān Begum. Nūr Jehān asked my leave to shoot the tigers with her gun. I said "Be it so." In a trice she killed these four tigers with six bullets. I had never seen such shooting. To shoot from the back of an elephant from within a closed *hordak* and bring down with six bullets four wild beasts without giving them an opportunity of moving or springing is wonderful. In acknowledgment of this capital marksmanship I ordered a thousand *ashrafs* (Rs. 4500) to be scattered<sup>1</sup> over Nūr Jehān and granted her a pair of ruby wristlets worth a lākh of rupees.<sup>2</sup>

Of the mangoes of Māndu Jehāngir says: In these days many mangoes have come into my fruit stores from the Dakhan, Burhānpur, Gujarāt, and the districts of Malwa. This country is famous for its mangoes. There are few places the mangoes of which can rival those of this country in richness of flavour, in sweetness, in freedom from fibre, and in size.<sup>3</sup>

The rains set in with unusual severity. Rain fell for forty days continuously. With the rain were severe thunderstorms accompanied by lightning which injured some of the old buildings.<sup>4</sup> His account of the beauty of the hill in July, when clear sunshine followed the forty days of rain, is one of the pleasantest passages in Jehāngir's Memoirs. What words of mine can describe the beauty of the grass and of the wild flowers.<sup>5</sup> They of the each hill and dale, each slope and plain. I know of no place so pleasant in climate and so pretty in scenery as Māndu in the rainy season. This month of July, which is one of the months of the hot season, the sun being in Leo, one cannot sleep within the house without a coverlet and during the day there is no need for a fan. What I have noticed is but a small part of the many beauties of Māndu. Two things I have seen here which I had seen nowhere in India. One of them is the tree of the wild plantain which grows all over the hill top, the other is the nest of the *mamolah* or wagtail. Till now no bird-catcher could tell its nest. It so happened that in the building where I lodged we found a wagtail's nest with two young ones.

The following additional entries in the Memoirs belong to Jehāngir's stay at Māndu. Among the presents submitted by Mahābat Khān, who received the honour of kissing the ground at Māndu, Jehāngir describes a ruby weighing eleven *miskāls*.<sup>6</sup> He says: This ruby was brought to Ajmir last year by a Frankish jeweller who wanted two lākhs of rupees for it. Mahābat Khān bought it at Burhānpur for one lakh of rupees.<sup>6</sup>

On the 1st of *Thi*, the fourth month of the Persian year (15th May 1617), the Hindu chiefs of the neighbourhood came to pay their

<sup>1</sup> This scattering of gold silver or copper coin, called in Arabic and Persian *maner*, is a common form of offering. The influence of the evil eye or other baneful influence is believed to be transferred from the person over whom the coin is scattered to the coin and through the coin to him who takes it.

<sup>2</sup> This feat of Nūr Jehān's drew from one of the Court poets the couplet:

*Nūr Jehān qur chah bu surat zanan*  
*Dar soti Marhan zar sher afkanan*  
 Nūr Jehān the tiger-slayer's woman  
 Ranks with men as the tiger-slaving woman.

Sherafkan, that is tiger-slayer, was the title of Nūr Jehān's first husband Ali-Kuli Istajlu.

<sup>3</sup> Tuzuk-i-Jehāngiri Pers. Text, 187.

<sup>4</sup> Tuzak-i-Jehāngiri Pers. Text, 189.

<sup>5</sup> The *miskal* which was used in weighing gold was equal in weight to ninety-six barley-corns. Blochman's *Ain-i-Akbari*, 36.

<sup>6</sup> Tuzak-i-Jehāngiri Pers. Text, 195.

respects and presents their tribute. The Hindu chief of Jitpūr in the neighbourhood of Mándū, through his evil fortune, did not come to kiss the threshold.<sup>1</sup> For this reason I ordered Fidaīkhān to pillage the Jitpūr country at the head of thirteen officers and four or five hundred matchlockmen. On the approach of Fidaīkhān the chief fled. He is now reported to regret his past conduct and to intend to come to Court and make his submission. On the 9th of Yār, the sixth month of the Persian calendar (late July, A.D. 1617), I heard that while raiding the lands of the chief of Jitpūr, Rah-ul-lāb, the brother of Fidaīkhān, was slain with a lance in the village where the chief's wives and children were in hiding. The village was burned, and the women and daughters of the rebel chief were taken captives.<sup>2</sup>

The beautiful surroundings of the Sagar lake offered to the elegant taste of Nūr Jahan a fitting opportunity for honouring the Shab-i-Barāt or Night of Jubilee with special illuminations. The emperor describes the result in these words: On the evening of Thursday the 19th of *Amardād*, the fifth month of the Persian year (early July, A.D. 1617), I went with the ladies of the palace to see the buildings and palaces on the Sagar lake which were built by the old kings of Mándū. The 26th of *Amardād* (about mid-July) was the Shab-i-Barāt holiday. I ordered a jubilee or assembly of joy to be held on the occasion in one of the palaces occupied by Nūr Jahan Begam in the midst of the big lake. The nobles and others were invited to attend this party which was organized by the Begam, and I ordered the cup and other intoxicants with various fruits and minced meats to be given to all who wished them. It was a wonderful gathering. As evening set in the lanterns and lamps gleaming along the banks of the lake made an illumination such as never had been seen. The countless lights with which the palaces and buildings were ablaze shining on the lake made the whole surface of the water appear to be on fire.<sup>3</sup>

The Memoirs continue: On Sunday the 3th of Yār, the sixth Persian month (late July), I went with the ladies of the palace to the quarters of Asaf Khān, Nūr Jahan's brother, the second son of Mirza Ghias Beg. I found Asaf Khān lodged in a garden of great beauty surrounded by other little vales and dells with waterfalls and running streamlets and green and shady mango groves. In one of these dells were from two to three hundred sweet pandanus or *keu la* trees. I passed a very happy day in this spot and got up a wine party with some of my lords-in-waiting, giving them bumpers of wine.<sup>4</sup> Two months later (early September) Jehángir has the following entry regarding a visit from his eldest son and heir prince Khurram, afterwards the emperor Shah Jahan, who had lately brought the war in the Dakhn to a successful close. On the 8th of the month of *Māh* (H. 1026; according to Roe September 2nd, 1617), my son of exalted name obtained the good fortune of waiting upon me in the fort of Mándū after three-quarters and one *ghadi* of the day had passed, that is about half an hour after sunrise. He had been absent fifteen months and eleven days. After he had performed the ceremonies of kissing the ground and the *kurnish* or prostration, I called him up to my bay window or *gharokah*. In a transport of affection I could not restrain myself from getting up and taking him into my arms. The more

## Appendix II.

THE HILL FORT  
OF MANDU.

## HISTORY.

The Mughals,  
A.D. 1570-1720.<sup>1</sup> Tuzuk-i-Jehángiri Pers. Text, 195.<sup>2</sup> Tuzuk-i-Jehángiri Pers. Text, 190.<sup>3</sup> Tuzuk-i-Jehángiri Pers. Text, 192-194.<sup>4</sup> Tuzuk-i-Jehángiri Pers. Text, 192.<sup>5</sup> Tuzuk-i-Jehángiri Pers. Text, 194-5.

**Appendix II.****THE HILL-FORT  
OF MANDU.****HISTORY.**

The Mughals,  
A.D. 1570-1720.

I increased the measure of affection and honours the more humility and respect did he show. I called him near me and made him sit by me. He submitted a thousand *ashrafi's* (— Rs. 1500) and a thousand rupees as a gift or *nazar* and the same amount as sacrifice or *nisaf*. As there was not time for me to inspect all his presents he produced the elephant Saenák, the best of the elephants of Adil Khán of Bijapur. He also gave me a case full of the rarest precious stones. I ordered the military paymasters to make presents to his nobles according to their rank. The first to come was Khan Jehan, whom I allowed the honour of kissing my feet. For his victory over the Rám of Ghatór I had before granted to my fortunate child Kúrram the rank of a commander of 20,000 with 10,000 horse. Now for his service in the Dakhan I made him a commander of 30,000 and 20,000 horse with the title of Shah Jehan. I also ordered that henceforward he should enjoy the privilege of sitting on a stool near my throne, an honour which did not exist and is the first of its kind granted to anyone in my family. I further granted him a special dress. To do him honour I came down from the window and with my own hand scattered over his head as sacrifice a trayfull of precious stones as well as a large trayfull of gold.

Jehangír's last Mándu entry is this: On the night of Friday in the month of *Abán* (October 24th 1617) in all happiness and good fortune I marched from Mandu and halted on the bank of the lake at Nakhlah.

Jehángír's stay at Mándu is referred to by more than one English traveller. In March 1617, the Rev. Edward Terry, chaplain to the Right Honourable Sir T. Roe Lord Ambassador to the Great Moghul, came to Mándu from Barhaupúr in east Khamlesh<sup>1</sup>. Terry crossed a broad river, the Narbada, at a great town called Ancharapur (Akharpur)<sup>2</sup> in the Narmá plain not far south of Mandu hill. The way up, probably by the Bharay pass a few miles east of Mándu, seemed to Terry exceedingly long. The ascent was very difficult, taking the carriages, apparently meaning coaches and wagons, two whole days.<sup>3</sup> Terry found the hill of Mandu stuck round with fan trees that kept their distance so, one from and below the other, that there was much delight in beholding them from either the bottom or the top of the hill. From one side only was the ascent not very high and steep. The top was flat plain and spacious with vast and

<sup>1</sup> A Voyage to East India 1st. Terry gives April 1616, but Roe seems correct in saying March 1617. Compare Wakiát-i-Jehangír in Elliot, VI, 351.

<sup>2</sup> Akharpur lies between Dharapur and Wáru. Malcolm's Central India, I, 81 note.

<sup>3</sup> Carriages may have the old meaning of things carried, that is baggage. The time taken favours the view that wagons or carts were forced up the hill. For the early seventeenth century use of carriages in its modern sense compare Terry (Voyage, 161). Of our wagons drawn with oxen . . . and other carriages we made a ring every night, also Dodsworth (1610), who describes a band of Rajpúts near Baroda cutting off two of his carriages (Kerr's Voyages, IX, 203), and Roe (1616), who journeyed from Ajmur to Mandu with twenty camels, four carts and two coaches (Kerr, IX, 308). Terry's carriages seem to be Roe's coaches, to which De la Valle (v. 1623) Hakluyt's edition, I, 21) refers as much like the Indian chariots described by Strabo (n.c. 50) covered with crimson silk fringed with yellow about the roof and the curtains. (Compare Idrisi (v. 1100-1150, but probably from Al Istikhiri, A.D. 960) Elliot, I, 87). In all Nahrwala or north Gujarat the only mode of carrying either passengers or goods is in chariots drawn by oxen with harness and traces under the control of a driver. When in 1616 Jehangír left Ajmur for Mandu the English carriage presented to him by the English ambassador Sir Thomas Roe was allotted to the Sultanah Núr Jehán Begum. It was driven by an English coachman. Jehángír followed in the coach his own men had made in imitation of the English coach. Corryat (1613, Crudities III., Letters from India, unpagged) calls the English chariot a gallant coach of 150 pounds price.

far-stretching woods, in which were lions tigers and other beasts of prey and many wild elephants. Terry passed through Mándu a few days' march across a plain and level country, apparently towards Dhár, where he met the Lord Ambassador Sir Thomas Roe, who had summoned Terry from Surat to be his chaplain. Sir Thomas Roe was then marching from Ajmir to Mándu with the Court of the emperor Jehángir, whom Terry calls the Great King.

On the 3rd of March, says Roe, the Mughal was to have entered Mándu. But all had to wait for the good hour fixed by the astrologers. From the 6th of March, when he entered Mándu, till the 24th of October, the emperor Jehángir, with Sir Thomas Roe in attendance, remained at Mándu.<sup>1</sup> According to Roe before the Mughal visited Mándu the hill was not much inhabited, having more ruins by far than standing houses.<sup>2</sup> But the moving city that accompanied the emperor soon overflowed the hill-top. According to Roe Jehángir's own encampment was walled round half a mile in circuit in the form of a fortress, with high screens or curtains of coarse stuff, somewhat like Aras hangings, red on the outside, the inside divided into compartments with a variety of figures. This enclosure had a handsome gateway and the circuit was formed into various corners and bulwarks. The posts that supported the curtains were all surmounted with brass tops.<sup>3</sup> Besides the emperor's encampment were the noblemen's quarters, each at an appointed distance from the king's tents, very handsome, some having their tents green, others white, others of mixed colours. The whole composed the most curious and magnificent sight Roe had ever beheld.<sup>4</sup> The hour taken by Jehángir in passing from the Delhi Gate to his own quarters, the two English miles from Roe's lodge which was not far from the Delhi Gate to Jehángir's palace, and other reasons noted below make it almost certain that the Mughal's encampment and the camps of the leading nobles were on the open slopes to the south of the Sea Lake between Baz Bahádur's palace on the east and Songad on the west. And that the palace at Mándu from which Jehángir wrote was the building now known as Baz Bahádur's palace.<sup>5</sup> A few months before it reached Mándu the imperial camp had turned the whole valley of Ajmir into a magnificent city,<sup>6</sup> and a few weeks before reaching Mándu at Thoda, about fifty miles south-east of Ajmir, the camp formed a settlement not less in circuit than twenty English miles, equalling in size almost any town in Europe.<sup>7</sup> In the middle of the encampment were all sorts of shops so regularly disposed that all persons knew where to go for everything.

The demands of so great a city overtaxed the powers of the deserted Mándu. The scarcity of water soon became so pressing that the poor were commanded to leave and all horses and cattle were ordered off the hill.<sup>8</sup> Of the scarcity of water the English traveller Coryat, who was then a guest of Sir Thomas Roe, writes. On the first day one of my Lord's people, Master Herbert, brother to Sir Edward Herbert, found a fountain which, if he had not done, he would have had to send ten courses

## Appendix II.

THE HILL-FORT  
OF MÁNDU.

## HISTORY.

The Mughals,  
A.D. 1570-1720.

<sup>1</sup> Kerr's Voyages, IX, 335; Wákiat-i-Jehángir in Elliot, VI, 377.

<sup>2</sup> Roe writing from Ajmir in the previous year (29th August 1616) describes Mándu as a castle on a hill, where there is no town and no building. Kerr, IX, 267.

<sup>3</sup> Roe in Kerr's Travels, IX, 313.

<sup>4</sup> Roe in Kerr's Travels, IX, 314.

<sup>5</sup> Compare Wákiat-i-Jehángir in Elliot, VI, 377.

<sup>6</sup> Roe in Kerr's Travels, IX, 314.

<sup>7</sup> Roe in Kerr's Travels, IX, 321.

<sup>8</sup> Roe in Kerr's Travels, IX, 335.

**Appendix II.**THE HILL FORT  
OF MANDU.**HISTORY.**The Mughals,  
A.D. 1570-1720.

(*kos*) every day for water to a river called Narbada that falleth into the Bay of Cambaye near Broach. The custom being such that whatsoever fountain or tank is found by any great man in time of drought he shall keep it proper to his without interruption. The day after one of the king's *Hadis* (*Lhādīs*) finding the same and striving for it was taken by my Lord's people and bound.<sup>1</sup> Corryat adds: During the time of the great drought two Moor nobles daily sent ten canals to the Narbada and distributed the water to the poor, which was so dear they sold a little skin for 8 pias (one penny).<sup>2</sup>

Terry notices that among the piles of buildings that held their heads above ruin were not a few unfrequented mosques or Muhamadan churches. Though the people who attended the king were marvellously straitened for room to put their most excellent horses, none would use the churches as stables, even though they were forsaken and out of use. This abstinence seems to have been voluntary, as Roe's servants, who were sent in advance, took possession of a fair court with walled enclosure in which was a goodly temple and a tomb. It was the best in the whole circuit of Mandu, the only drawback being that it was two miles from the king's house.<sup>3</sup> The air was wholesome and the prospect was pleasant, as it was on the edge of the hill.<sup>4</sup> The emperor, perhaps referring rather to the south of the hill, which from the elaborate building and repairs carried out in advance by Abdul Karim seems to have been called the New City, gives a less deserted impression of Mandu. He writes (24th March 1617): Many buildings and relics of the old kings are still standing, for as yet decay has not fallen upon the city. On the 24th I rode to see the royal edifices. First I visited the *Jāmi Masjid* built by Sultan Hoshang Ghori. It is a very lofty building and erected entirely of hewn stone. Although it has been standing 180 years it looks as if built to-day. Then I visited the sepulchres of the kings and rulers of the Khilji dynasty, among which is the sepulchre of the eternally cursed Nasir-ud-din.<sup>5</sup> Sher Shāh to show his horror of Nasir-ud-din, the father-slaver, ordered his people to beat Nasir-ud-din's tomb with sticks. Jehāngir also kicked the grave. Then he ordered the tomb to be opened and the remains to be taken out and burnt. Finally, fearing the remains might pollute the eternal light, he ordered the ashes to be thrown into the Narbada.<sup>6</sup>

The pleasant outlying position of Roe's lodge proved to be open to the objection that out of the vast wilderness wild beasts often came, seldom returning without a sheep, a goat, or a kid. One evening a great lion leapt over the stone wall that encompassed the yard and snapt up the Lord Ambassador's little white neat shock, that is as Roe explains a small Irish mastiff, which ran out barking at the lion. Out of the ruins of the mosque and tomb Roe built a lodge,<sup>7</sup> and here he passed the rains with his "family," including besides his secretary, chaplain, and cook twenty-three Englishmen and about sixty native servants, and during part of the time the sturdy half-crazed traveller Tom Coryate or Corryat.<sup>8</sup> They had

<sup>1</sup> Corryat's *Civilities*, III. Extracts (unpaged). This Master Herbert was Thomas, brother of Sir Edward Herbert, the first Lord Herbert. It seems probable that this Thomas supplied his cousin Sir Thomas Herbert who was travelling in India and Persia in A.D. 1627 with his account of Mandu. See below pages 381-382.

<sup>2</sup> Corryat's *Civilities*, III. Extracts (unpaged).

<sup>3</sup> Terry's *Voyage*, 183; Roe in Kerr, IX, 335.

<sup>4</sup> Roe in Kerr, IX, 335.

<sup>5</sup> *Wākāfi-i-Jehāngiri* in Elliot, VI, 349.

<sup>6</sup> *Wākāfi-i-Jehāngiri* in Elliot, VI, 350.

<sup>7</sup> Terry's *Voyage*, 228.

<sup>8</sup> Terry's *Voyage*, 69.

their flock of sheep and goats, all necessaries belonging to the kitchen and everything else required for bodily use including bedding and all things pertaining thereto.<sup>1</sup> Among the necessaries were tables<sup>2</sup> and chairs, since the Ambassador refused to adopt the Mughal practice of sitting cross-legged on mats "like taylor's on their shopboards." Roe's diet was dressed by an English and an Indian cook and was served on plate by waiters in red taffata cloaks guarded with green taffata. The chaplain wore a long black cassock, and the Lord Ambassador wore English habits made as light and cool as possible.<sup>3</sup>

On the 12th of March, a few days after they were settled at Mándu, came the festival of the Persian New Year. Jehángir held a great reception seated on a throne of gold bespangled with rubies emeralds and turquoises. The hall was adorned with pictures of the King and Queen of England, the Princess Elizabeth, Sir Thomas Smith and others, with beautiful Persian hangings. On one side, on a little stage, was a couple of women singers. The king commanded that Sir T. Roe should come up and stand beside him on the steps of the throne where stood on one side the Persian Ambassador and on the other the old king of Kandahar with whom Sir T. Roe ranked. The king called the Persian Ambassador and gave him some stones and a young elephant. The Ambassador knelt and knocked his head against the steps of the throne to thank him.<sup>4</sup> From time to time during Terry's stay at Mándu, the Mughal, with his stout Persian and Tartar horsemen and some grandoes, went out to take young wild elephants in the great woods that environed Mándu. The elephants were caught in strong coils prepared for the purpose and were manned and made fit for service. In these hunts the king and his men also pursued lions and other wild beasts on horseback, killing some of them with their bows carbines and lances.

The first of September was Jehángir's birthday. The king, says Corryat,<sup>5</sup> was forty-five years old, of middle height, corpulent, of a seemly composition of body, and of an olive coloured skin. Roe went to pay his respects and was conducted apparently to Báiz Bahádur's Gardens to the east of the Rewa Pool. This tangled orchard was then a beautiful garden with a great square pond or tank set all round with trees and flowers and in the middle of the garden a pavilion or pleasure-house under which hung the scales in which the king was to be weighed.<sup>7</sup> The scales were of beaten gold set with many small stones as rubies and turquoises. They were hung by chains of gold, large and massive, but strengthened by silken ropes. The beam and tressels from which the scales hung were covered with thin plates of gold. All round were the nobles of the court seated on rich carpets waiting for the king. He came laden with diamonds rubies pearls and other precious vanities, making a great and glorious show. His sword, targets and throne were corresponding in riches and splendour. His head, neck, breast and arms above the elbows and at the wrist were decked with chains of precious stones, and every finger had two or three rich rings. His legs were as it were fettered with chains of diamonds and rubies as large as walnuts and amazing pearls. He got into the scales crouching or sitting on his legs like a woman. To counterpoise his weight bags said to contain Rs. 9000 in

**Appendix II.**

THE HILL FORT  
OF MANDU.

**HISTORY.**

The Mughals,  
A.D. 1570-1720.

<sup>1</sup> Terry's Voyage, 183.    <sup>2</sup> Terry's Voyage, 186, 198.    <sup>3</sup> Terry's Voyage, 198, 205.

<sup>4</sup> Roe in Kerr's Voyages, IX. 337; Pinkerton's Voyages, VIII. 35.

<sup>5</sup> Terry's Voyage, 103.

<sup>6</sup> Corryat's Crudities, III. Letter 2. Extracts unpagged.

<sup>7</sup> Roe in Kerr's Voyages, IX. 343.

**Appendix II.**  
**THE HILL FORT**  
**OF MANDU.**  
*HISTORY.*  
 The Mughals,  
 A.D. 1570-1720.

silver were changed six times. After this he was weighed against bags containing gold jewels and precious stones. Then against cloth of gold, silk stuffs, cotton goods, spices, and all commodities. Last of all against meal, butter, and corn. Except the silver, which was reserved for the poor, all was said to be distributed to Bannahs (that is Brahmins).<sup>1</sup> After he was weighed Jehangir ascended the throne and had basons of nuts almonds and spices of all sorts given him. These the king threw about, and his great men scrambled prostrate on their bellies. Roe thought it not decent that he should scramble. And the king seeing that he stood aloof reached him a bason almost full and poured the contents into his cloak.<sup>2</sup> Terry adds: 'The physicians noted the king's weight and spoke flatteringly of it.' Then the Mughal drank to his nobles in his royal wine and the nobles pledged his health. The king drank also to the Lord Ambassador, whom he always treated with special consideration, and presented him with the cup of gold curiously enamelled and crusted with rubies turkesses and emeralds.<sup>3</sup>

Of prince Khurram's visit Roe writes: 'A month later (October 2nd) the proud prince Khurram, afterwards the emperor Shah Jehan (A.D. 1626-1657), returned from his glorious success in the Dakhn, accompanied by all the great men, in wondrous triumph.'<sup>4</sup> A week later (October 9th), hearing that the emperor was to pass near his lodging on his way to take the air at the Narbada, in accordance with the rule that the masters of all houses near which the king passes must make him a present, Roe took horse to meet the king. He offered the king an Atlas neatly bound saying he presented the king with the whole world. The king was pleased. In return he praised Roe's lodge, which he had built out of the ruins of the temple and the ancient tomb and which was one of the best lodges in the camp. Jehangir left Mandu on the 24th October. On the 30th when Roe started the hill was entirely deserted.<sup>5</sup>

Terry mentions only two buildings at Mandu. One was the house of the Mughal, apparently Baz Bahadur's palace, which he describes as large and stately, built of excellent stone, well squared and put together, taking up a large compass of ground. He adds: 'We could never see how it was contrived within, as the king's wives and women were there.'<sup>6</sup> The only other building to which Terry refers, he calls "The Grot." Of the grot, which is almost certainly the pleasure-house Nilkanth, whose Persian inscriptions have been quoted above, Terry gives the following details: 'To the Mughals' house, at a small distance from it, belonged a very curious grot. In the building of the grot a way was made into a

<sup>1</sup> Roe in Kerr's Travels, IX. 340-343.

<sup>2</sup> Roe in Kerr's Travels, IX. 344.

<sup>3</sup> Terry's Voyage, 377. Terry's details seem not to agree with Roe's who states (Kerr's Voyages, IX. 344 and Pinkerton's Voyages, VIII. 37). 'I was invited to the drinking, but desired to be excused because there was no avoiding drinking, and their liquors are so hot that they burn out a man's very bowels. Perhaps the invitation Roe declined was to a private drinking party after the public weighing was over.'

<sup>4</sup> Roe in Kerr's Voyage, IX. 347; Elphinstone's History, 191. Kerr (IX. 347) gives September 2 but October 2 is right. Compare Pinkerton's Voyages, VIII. 39.

<sup>5</sup> Ruins of Mandu, 57. As the emperor must have passed on by the Delhi Gate, and as Roe's lodge was two miles from Baz Bahadur's palace, the lodge cannot have been far from the Delhi Gate. It is disappointing that, of his many genial gossipy entries Jehangir does not devote one to Roe. The only reference to Roe's visit is the indirect entry (Wakiat-i-Jehangiri in Elliot, VI. 147) that Jehangir gave one of his nobles a coach, apparently a copy of the English coach, with which, to Jehangir's delight Roe had presented him.

<sup>6</sup> Roe in Kerr's Voyages, IX. 353.

<sup>7</sup> Terry's Voyage, 180.

firm rock which showed itself on the side of the hill canopied over with part of that rock. It was a place that had much beauty in it by reason of the curious workmanship bestowed on it and much pleasure by reason of its coolness.<sup>1</sup> Besides the fountain this grot has still one of the charmingly cool and murmuring scalloped millstones where, as Terry says, water runs down a broad stone table with many hollows like to scallop shells, in its passage over the hollows making so pretty a murmur as helps to tie the senses with the bonds of sleep.

Shāh Jehān seems to have been pleased with Māndu. He returned in A.D. 1621 and stayed at Mandu till he marched north against his father in A.D. 1622.<sup>2</sup> In March A.D. 1623, Shah Jehan came out of Mandu with 20,000 horse, many elephants, and powerful artillery, intending to fight his brother Shāh Parwiz.<sup>3</sup> After the failure of this expedition Shah Jehan returned to Mandu.<sup>4</sup> At this time (A.D. 1623) the Italian traveller Dela Valle ranks Mandu with Agra, Lāhor and Ahmedabad, as the four capitals, each endowed with an imperial palace and court.<sup>5</sup> Five years later the great general Khān Jehan Lodi besieged Mandu, but apparently without success.<sup>6</sup> Khān Jehan Lodi's siege of Māndu is interesting in connection with a description of Mandu in Herbert's Travels. Herbert, who was in Gujarat in A.D. 1626, says Mandu is seated at the side of a declining hill (apparently Herbert refers to the slope from the southern crest northwards to Sagar Lake and the Grot or Nilkanth) in which both for ornament and defence is a castle which is strong in being encompassed with a defensive wall of nearly five miles (probably less than that is ten miles); the whole, he adds, heretofore had been madeificent. But the city later built is of less time yet fresher beauty, whether you behold the temples (in one of which are entombed four kings), palaces or fortresses, especially that tower which is elevated 170 steps, supported by massive pillars and adorned with gates and windows very observable. It was built by Khān Jehan, who there lies buried. The confusedness of these details shows that Herbert obtained them second-hand, probably from Corryat's Master Herbert or Sir P. Roe's staff.<sup>7</sup> The new city of fresher

**Appendix II.**

THE HILL FORT  
OF MANDU.

*HISTORY.*

The Mughals,  
A.D. 1570-1720.

<sup>1</sup> Terry's Voyage, 11.

<sup>2</sup> Wākāt-i-Jehangir or Elliot, VI, 383.

<sup>3</sup> Wākāt-i-Jehangir in Elliot, VI, 7.

<sup>4</sup> Elphinstone's History, 197. <sup>5</sup> Compare Dela Valle (Hakluyt Edition, I, 177) writing in A.D. 1622, Sultan Khurram after his defeat by Jehangir retired to Mandu.

<sup>6</sup> Dela Valle's Travels, Hakluyt Edition, I, 97.

<sup>7</sup> Elphinstone's History, 507.

<sup>7</sup> Herbert's Travels, 81. Corryat's Master Herbert was as already noted named like the traveller Thomas. The two Thomases were distant relations, both being fourth in descent from Sir Richard Herbert of Colebrooke, who lived about the middle of the fifteenth century. A further connection between the two families is the copy of complimentary verses "To my cousin Sir Thomas Herbert," signed Ch. Herbert, in the 1631 and 1665 editions of Herbert's Travels, which are naturally, though somewhat doubtfully, ascribed to Charles Herbert, a brother of our Master Thomas. It is therefore probable that after his return to England Sir Thomas Herbert obtained the Mandu details from Master Thomas who was himself a writer, the author of several poems and pamphlets. Corryat's tale how, during the water-famine at Mandu, Master Herbert annexed a spring or cistern, and then bound a servant of the Great King who attempted to share in its use, shows admirable courage and resolution on the part of Master Thomas, then a youth of twenty years. The details of Thomas in his brother Lord Herbert's autobiography give additional interest to the hero of Corryat's tale of a Tank. Master Thomas was born in A.D. 1597. In 1610, when a page to Sir Edward Cecil and a boy of thirteen, in the German War especially in the siege of Juliers fifteen miles north-east of Aix-la-Chapelle, Master Thomas showed such forwardness as no man in that great army surpassed. On his voyage to India in 1617, in a fight with a great Portuguese carrack,

**Appendix II.**  
**THE HILL FORT**  
**OF MANDU.**  
**HISTORY.**

The  
 Macathās,  
 A.D. 1720-1820.

beauty is probably a reference to the buildings raised and repaired by Abul Karīm against Jehangīr's coming, among which the chief seems to have been the palace now known by the name of Bāz Bahādūr. The tower of 170 steps is Mehmūd Khiljī's Tower of Victory, erected in A.D. 1443, the Khān Jehān being Mehmūd's father, the great minister Khān Jehān Aāzam Humāyūn.

In A.D. 1658 a Rājā Shīvrāj was commandant of Māndu.<sup>1</sup> No reference has been traced to any imperial visit to Māndu during Aurangzib's reign. But that great monarch has left an example of his watchful care in the rebuilding of the Ālāmgīr or Aurangzib Gate, which guards the approach to the stone-crossing of the great northern ryma and bears an inscription of A.D. 1668, the eleventh year of Ālāmgīr's reign. In spite of this additional safeguard thirty years later (A.D. 1696) Māndu was taken and the standard of Udājī Pavār was planted on the battlement.<sup>2</sup> The Marāthās soon withdrew and Māwa again passed under an imperial governor. In A.D. 1708 the Shīva-loving emperor Bahādūr Shāh I. (A.D. 1707-1712) visited Māndu, and there received from Ahmedābād a copy of the *Kurān* written by Imām Āh 'Pakī, son of Imām Mūsā Raza (A.D. 810-829), seventh in descent from Ah, the famous son-in-law of the Prophet, the first of Musalman mystics. In A.D. 1717 Asaph Jah Nizām-ul-Mulk was appointed governor of Mālwa and continued to manage the province by deputy till A.D. 1721. In A.D. 1722 Rājā Gūdhār Bahādūr, a Nagar Brāhman, was made governor and remained in charge till in A.D. 1724 he was attacked and defeated by Chinnaji Pandit and Udājī Pavār.<sup>3</sup> Rājā Gūdhār was succeeded by his relation Dāa Bahādūr, whose successful government ended in A.D. 1732, when through the secret help of the local chiefs Malhārao/Holkar led an army up the Bharav pass, a few miles east of Māndu, and at Tirrellah, between Anghera and Dhār, defeated and slew Dāa Bahādūr. As neither the next governor Muhammad Khān Bangash nor his successor Rājā Jai Singh of Jaipur were able to oust the Marāthās, their success was admitted in A.D. 1734 by the appointment of Peshwa Bājirāo (A.D. 1720-1740) to be governor of Mālwa. On his appointment (A.D. 1734) the Peshwa chose Anand Rāo Pavār as his deputy. Anand Rāo shortly after settled at Dhār, and since A.D. 1734 Māndu has continued part of the territory of the Pavārs of Dhār.<sup>4</sup> In A.D. 1805 Māndu sheltered the heroic Mīna Bai during the birth-time of her son Rāmchandra Rājā Pavār, whose state was saved from the clutches of

Captain Joseph, in command of Heriot's ship *Globe*, was killed. Thomas took Joseph's place, forced the carrack aground, and so riddled her with shot that she never floated again. To his brother's visit to India Lord Herbert refers as a year spent with the merchants who went from Surat to the Great Moghal. After his return to England Master Thomas distinguished himself at Algiers, capturing a vessel worth £1800. In 1622, when Master Thomas was in command of one of the ships sent to fetch Prince Charles (afterwards King Charles I.) from Spain, during the return voyage certain Low Countrymen and Dunkirkers, that is Dutch and Spanish vessels, offended the Prince's dignity by fighting in his presence without his leave. The Prince ordered the fighting ships to be separated; whereupon Master Thomas, with some other ships got betwixt the fighters on either side, and shot so long that both Low Countrymen and Dunkirkers were glad to desist. Afterwards at divers times Thomas fought with great courage and success with divers men in single fight, sometimes hurting and disarming his adversary, sometimes driving him away. The end of Master Thomas was sad. Finding his proofs of himself undervalued he retired into a private and melancholy life, and after living in this sullen humour for many years, he died about 1642 and was buried in London in St. Martin's near Charing Cross.

<sup>1</sup> Khafi Khan in Elliot, VII. 218.

<sup>2</sup> Malcolm's Central India, I. 74.

<sup>3</sup> Malcolm's Central India, I. 61.

<sup>4</sup> Malcolm's Central India, I. 100.

Holkar and Sindhia by the establishment of British overlordship in A.D. 1817.<sup>1</sup>

In A.D. 1820 Sir John Malcolm<sup>2</sup> describes the hill-top as a place of religious resort occupied by some mendicants. The holy places on the hill are the shrine of Hoshang Ghori whose guardian spirit still scares barrenness and other disease fiends<sup>3</sup> and the Rewa or Narkala Pool, whose holy water, according to common belief, prevents the dreaded return of the spirit of the Hindu whose ashes are strewn on its surface, or, in the refined phrase of the Brāhman, enables the dead to lose self in the ocean of being.<sup>4</sup> In A.D. 1820 the Jama Mosque, Hoshang's tomb, and the palaces of Baz Bahadur were still fine remains, though surrounded with jungle and fast crumbling to pieces.<sup>5</sup> In A.D. 1827 Colonel Briggs says<sup>6</sup> "Perhaps no part of India so abounds with tigers as the neighbourhood of the once famous city of Mandu. The capital now deserted by men is overgrown by forest and from being the seat of luxury, elegance, and wealth, it has become the abode of wild beasts and is resorted to by the few Europeans in that quarter for the pleasure of destroying them. Instances have been known of tigers being so bold as to carry off troopers riding in the ranks of their regiments. Twelve years later (A.D. 1839) Mr. Feignsson<sup>7</sup> found the hill a vast uninhabited jungle the rank vegetation tearing the buildings of the city to pieces and obscuring them so that they could hardly be seen." Between A.D. 1812 and 1852 tigers are described as prowling among the regal rooms, the ball-savage marauding Bhil as eating his meal and feeding his cattle in the cloisters of his sanctuaries and the insidious *pipul* as levelling to the earth the magnificent remains.<sup>8</sup> So favourite a tiger retreat was the Jahaz Palace that it was dangerous to venture into it unarmed. Close to the very huts of the poor central village, near the Jama Mosque cattle were frequently seized by tigers. In the south tigers came nightly to drink at the Sagar lake. Huge bonfires had to be burnt to prevent them attacking the houses.<sup>9</sup> In A.D. 1883 Captain Eastwick wrote "At Mandu the traveller will require some armed men, as tigers are very numerous and dangerous. He will do well not to have any dogs with him as the panthers will take them even from under his bed."<sup>10</sup> If this was true of Mandu in A.D. 1883—and is not as seems likely the repetition of an old-world tale—the last ten years have wrought notable changes. Through the interest His Highness Sir Anand Rao Pagar, K.C.S.I., &c., the present Maharaja of Dhar takes in the de capand of his state, travelling in Mandu is now as safe and easier than in many, perhaps than in most, outlying districts. A phantom can drive across the northern ravine-moat through the three gateways and along the hill-top, at least as far south as the Sea Lake. Large stretches of the level are cleared and tilled, and herds of cattle graze free from the dread of wild beasts. The building buildings have been saved from their ruinous tree-growth, the maderwood has been cleared, the marauding Bhil has settled to tillage, the tiger, even the panther, is nearly

## Appendix II.

THE HILL FORT  
OF MANDU.  
HISTORY.  
NOTES,  
A.D. 1820-1893.

<sup>1</sup> Malcolm's Central India, I. 106.

<sup>2</sup> Central India, II. 503.

<sup>3</sup> Ruins of Mandu, 43; Murray 1852 page 34.

<sup>4</sup> Ruins of Mandu, 43; Murray 1852 page 34.

<sup>5</sup> Malcolm's Central India, II. 503.

<sup>6</sup> Briggs' Farishtah, IV. 236 note \*.

<sup>7</sup> Indian Architecture, 541.

<sup>8</sup> Ruins of Mandu, 9.

<sup>9</sup> Ruins of Mandu, 9.

<sup>10</sup> Ruins of Mandu, 13, 25, 35. Some of these extracts seem to belong to a Bombay Subaltern, who was at Mandu about A.D. 1842, and some to Captain Claudius Harris, who visited the hill in April 1852. Compare Ruins of Mandu, 34.

<sup>11</sup> Murray's Handbook of the Panjab, 118.

**Appendix II.**  
**THE HILL FORT**  
**OF MANDU.**  
*HISTORY.*  
 Notices,  
 A.D. 1820-1895.

as rare as the wild elephant, and finally its old wholesomeness has returned to the air of the hill-top.

This sketch notices only the main events and the main buildings. Even about the main buildings much is still doubtful. Many inscriptions, some in the puzzling interlaced *Tughlak* character, have still to be read. They may bring to light traces of the Mándu kings and of the Mughal emperors, whose connection with Mándu, so far as the buildings are concerned, is still a blank. The ruins are so many and so widespread that weeks are wanted to ensure their complete examination. It may be hoped that at no distant date Major Delassau, the Political Agent of Dhar, whose opportunities are not more special than his knowledge, may be able to prepare a complete description of the hill and of its many ruins and writings.

— — — — —

MARÁTHI HISTORY  
OF  
GUJARÁT  
A.D. 1760-1819.

BY  
J. A. BAINES ESQUIRE, C.S.I.,  
LATE OF H. M. S. BOMBAY CIVIL SERVICE.

[CONTRIBUTED IN 1879.]



# HISTORY OF GUJARÁT.

## MARÁTHA PERIOD.

A.D. 1760-1819.

It will be evident from what has been related in the Musalmán portion of this history that long before 1760, the Maráthás had a firm foothold in Gujarát, and were able to dictate to the local chiefs the policy of the Dakhan Court. Long before 1819 too, Marátha influence was on the wane before the rising fortunes of the British. Between these two dates however is comprised the whole or nearly the whole of the period during which the Maráthás were virtually paramount in Gujarát. From each of these two dates the political history took a new departure, and on this account they serve respectively to denote the starting point and terminus of Marátha supremacy. Most of what took place before 1760 is so interwoven with the interests and intrigues of the Muhammadan delegates of the court of Dehli that it has been fully described in the history of the Musalmán Period. It is however necessary, in order to trace the growth of Marátha power, to briefly set forth in a continuous narrative the events in which this race was principally concerned, adding such as transpired independently of Musalmán politics. This task is rendered easier by the very nature of Marátha policy, which has left little to be recorded of its action in Gujarát beyond the deeds and fortunes of its initiators and their adherents.

The connection of the Maráthás with Gujarát can be divided by the chronicler into the following periods. First, the time of predatory inroads from 1661 to 1743, before the leaders of these expeditions had permanently established themselves within the province. Secondly, what may be termed the mercenary period, when the Maráthás partly by independent action, but far more by a course of judicious interference in the quarrels of the Muhammadan officials and by loans of troops, had acquired considerable territorial advantages. Towards the end of this period, as has been already seen, their aid was usually sufficient to ensure the success of the side which had managed to secure it, and at last the capital itself was claimed and held by them. Then came the time of domination, from 1760 to 1801, during which period the Gáikwár influence was occasionally greater than that of the Peshwa. From 1802, internal dissensions at the courts of Poona and Baroda weakened the hold the Maráthás had on the province, and the paramount power had to all intents and purposes passed over to the British long before the downfall of Bájiráv Peshwa and the final annexation of his rights and territory in 1819.

THE  
MARÁTHÁS,  
A.D. 1760-1819.

THE  
MARÁTHAS,  
A.D. 1760 - 1819.

SIVAJI'S First  
Inroad,  
1664

Shortly after, when the Gánkwár made over to the British the work of collecting the tribute from Káthiáváda, Marátha supremacy came to an end.

The first Marátha force that made its appearance in Gujarát was led there early in 1664 by Śiváji. This leader was at the time engaged in a warfare with the Mughals, which, however desultory, required him to keep up a much larger force than could be supported out of the revenues of his dominions. He therefore looked to plunder to supply the deficiency, and Surat, then the richest town of Western India, was marked down by him as an easy prey. His mode of attack was cautious. He first sent one Balurji Nank to spy out the country and report the chances of a rich booty, whilst he himself moved a force up to Junnar on pretence of visiting some forts in that direction recently acquired by one of his subordinates. On receiving a favourable report from Balurji, Śiváji gave out that he was going to perform religious ceremonies at Násik, and taking with him 4000 picked horsemen, he marched suddenly down the Gháts and through the Dáng jungles, and appeared before Surat. There he found an insignificant garrison, so he rested outside the city six days whilst his men plundered at their leisure. On hearing of the tardy approach of a relieving force sent by the governor of Ahmedábád, Śiváji beat a retreat with all his booty to the stronghold of Rávgad. By the time the reinforcement reached Surat, the only trace of the invaders was the emptied coffers of the inhabitants. About the same time, or shortly after, the fleet which Śiváji had equipped at Ahbáig about two years before came up to the mouth of the gulf of Cambay and carried off one or two Mughal ships which were conveying to Makka large numbers of pilgrims with their rich oblations.<sup>1</sup>

SIVAJI'S Second  
Attack,  
1670.

This insult to the Muhammadan religion was enough to incense the bigoted Aurangzeb, apart from the additional offences of the sack of Surat and the assumption in 1665 of royal insignia by Śiváji. He therefore sent an expedition to the Dakhán strong enough to keep the Maráthás for some time away from Gujarát. One of Śiváji's officers, however, seems to have attacked a part of the Surat district in 1666, and to have got off safely with his spoils. In 1670, Śiváji again descended upon that city with about 15,000 men. The only serious resistance he experienced was, as before, from the English factors. He plundered the town for three days, and only left on receiving some information about the Mughals' movements in the Dakhán, which made him fear lest he should be intercepted on his way back to the country about the Gháts.

1671.

Śiváji left a claim for twelve lákhs of rupees to be paid as a guarantee against future expeditions. It is possible, however, that as he does not appear to have taken any immediate steps to recover this sum, the demand was made only in accordance with Marátha policy;

<sup>1</sup> Surat was known as Báb-ul-makkah or the Gate of Makka on account of its being the starting place of the ships annually conveying the Muhammadan pilgrims of India to the shrine of their Prophet.

which looked upon a country once overrun as tributary, and assumed a right to exercise paramount authority over it by virtue of the completed act of a successful invasion. In 1671 the Marátha fleet was ordered to sail up the gulf and plunder Broach, and it is probable that Śivaji intended at the same time to levy tribute from Surat, but the whole expedition was countermanded before the ships sailed.

THE  
MARATHAS  
A.D. 1760-1819.

The conduct of the military authorities in Gujarát with regard to this expedition of 1670 was such as to render it highly probable that the Mughal leaders were in complicity with the Maráthas in order to gain the favour and support of their leader. Shortly before Śivaji's arrival there had been a large garrison in Surat, apparently kept there by the governor, who suspected that some attempt on the town would soon be made. This garrison was withdrawn before Śivaji's attack, and almost immediately after his departure 5000 men were sent back again. The commanders of the Mughal army in the Dakhan were Jasvant Singh the Rájah's chief of Jodhpur and prince Muazzam. Jasvant Singh had been viceroy of Gujarát from A.D. 1659 to 1662, and in A.D. 1671 shortly after Śivaji's second expedition was re-appointed to that post for three years. He had, moreover, been accused of taking bribes from Śivaji during the operations in the Dakhan. Prince Muazzam, again, had every reason for wishing to secure to himself so powerful an ally as Śivaji in the struggle for the imperial crown that took place, as a rule, at every succession. Aurangzeb, reasoning from his own experiences as a son, refused to allow a possible heir to his throne to become powerful at court; and accordingly sent him against Śivaji with an army quite inadequate for such operations. It is therefore not unreasonable to suppose that if there had not been some previous understanding between Śivaji and the Mughal leaders, the troops that were known to be within easy reach of Surat would have been found strong and numerous enough either to have repulsed him altogether or at least to have prevented the three days' sack of the city.

In A.D. 1672 Śivaji took some of the small forts to the south of Surat, such as Páruera and Barv etc., now in the Párdi sub-division of the Surat district, while Moro Trímal got possession of the large fort of Suer in Baglan, which guarded one of the most frequented passes from the Dakhan into Gujarát. The Maráthas were thus able to command the routes along which their expeditions could most conveniently be despatched.

Said Ticker,  
1672.

No further incursion was made till 1675, in which year a Marátha force first crossed the Narbada. On the resumption of hostilities between Śivaji and the Mughals, Husaji Mohite, who had been made Senapati, with the title of Hambirráv, marched up the North Konkan, and divided his army into two forces near Surat. One portion plundered towards Burhanpur, the other commanded by himself plundered the Broach district. Ten years later a successful expedition was made against Broach itself, either preconcerted or

The Narbada  
crossed,  
1675.

THE  
MARATHAS,  
A.D. 1760-1819.

Raid  
by Dabhade,  
1699

1700-1704.

1705.

1706-1711.

1713.

Dabhade,  
1716.

actually led by a younger son of Aurangzeb, who had taken refuge with the Maráthas. Broach was plundered, and the booty safely carried off before the local force could get near the invaders. Gujarát was now left free from inroad for some fourteen years, probably because the attention of the Marátha leaders was concentrated on their quarrels in the Dakhan.

In A.D. 1699 Rám Rája appointed one of his most trusted officers, Khanderáv Dábháde, to collect in Baglán the *chauth*<sup>1</sup> and *sardeshmukhi* imposts which had by that time become regularly instituted. This chief, whose name was afterwards so intimately connected with Gujarát, not only collected all that was due to his master from the village officers in Baglán, but also made an incursion into the Surat districts on his own account. Between 1700 and 1704, Khanderáv attempted two expeditions, but was foiled by the vigilance of the Mughal authorities. In 1705, however, he made a raid on a large scale and got safely across the Narbada, where he defeated two Muhammadan detachments sent against him, and got back to Sálér with his booty. Khanderáv now kept bodies of troops constantly hovering on the outskirts of Gujarát and along the road to Burhánpur. He himself led several expeditions into the Ahmedábád territory, and is said to have once got as far as Sorath in the peninsula, where however he was repelled by the Masalmán governor. In 1711, again he was severely defeated by the Mughals near Anklesvar in the Broach district, and had to withdraw to the borders of Khándesh.

In 1713 some treasure was being conveyed from Surat to Aurangábád escorted by a large force under Muhammad Tabrízí. The party was attacked in the jungles east of Surat and the treasure carried off. Just before this, Sarhuland Khán, the deputy viceroy, on his way to take up his office at Ahmedábád, was attacked and robbed in the wilds of Ságbara on the north bank of the Tápti. As Khanderáv had a short while previous to these occurrences taken up his position near Nándod<sup>2</sup> in the Rájpipla territory, it is probably to him or to his subordinates that these raids are to be attributed. He managed by a system of outposts to cut off communication between Surat and Burhánpur, except for those who had paid him a fee for safe conduct. If this charge was evaded or resisted, he appropriated one-fourth of the property that the traveller was conveying up country.

As the Burhánpur road was one of those most frequented by both pilgrims and merchants, the Delhi authorities were obliged, in 1716, to organize an expedition against Dábháde. The leader of the force was one Zulfikar Beg, an officer inexperienced in Marátha warfare. Dábháde found little difficulty in decoying him into a mountainous country, and there completely defeated him with the usual Marátha accompaniment of plunder.

<sup>1</sup> *Sardeshmukhi* or ten per cent on the revenue. The *chauth* was nominally one-fourth, but both these claims were fluctuating in their proportions to the total revenue.

<sup>2</sup> Now the capital of the Rája of Rájpipla.

Finding himself once more in the Dakhan, Khanderáv Dábháde took the opportunity of rejoining the court at Satára, from which he had long been absent. He was lucky enough to arrive just as the Senápati Manáji Morár had failed on an important expedition and was consequently in disgrace. Rája Sháhu, pleased with Khanderáv's recent success against the Delhi troops, divested Manáji of the title of Senápati, and bestowed it upon the more fortunate leader.

Khanderáv remained away from Gujarát for three years, accompanying, meanwhile, Báláji Vishvanáth the Peshwa to Delhi, where the latter was engaged in negotiations for the confirmation of the Marátha rights to *chauth* and other tribute from certain districts in the Dakhan.

It is evident that at this time there was no definite claim to tribute from Gujarát on the part of the Marátha government; for in spite of the intrigues of Báláji and the weakness of the court party at Delhi no concessions were obtained with regard to it, although the Marátha dues from other parts of the country were fully ratified. The grounds on which Báláji demanded the tribute from Gujarát were, that Sháhu would thereby gain the right to restrain the excesses of Marátha freebooters from the frontier and would guarantee the whole country against irregular pillage. The argument was a curious one, considering that the most troublesome and notorious freebooter of the whole tribe was at the elbow of the envoy, who was so strenuously pleading for the right to suppress him. It is probable that Báláji foresaw that Khanderáv's newly acquired rank would take him for a time from Báglaú to the court, so that meanwhile an arrangement could be made to prevent the growth of any powerful chief in the Gujarát direction who might interfere with the plans of the central government. The Marátha statesman was as anxious to ensure the subordination of distant feudatories as the Mughals to secure the freedom of the Ghát roads to the coast.

In the redistribution of authority carried out about this time by Báláji Vishvanáth, the responsibility of collecting the Marátha dues from Gujarát and Báglaú was assigned to Khanderáv as Senápati or commander-in-chief; but as these dues were not yet settled, at least as regards the country below the Gháts, Khanderáv seems to have remained with the Peshwa in the field.

At the battle of Bálápur, fought against the Nizám-ul-Mulk, one of the officers of Khanderáv, by name Dámáji Gúikwár, so distinguished himself that the Senápati brought his conduct prominently to the notice of Rája Sháhu. The latter promoted Dámáji to be second in command to Khanderáv with the title of Shamsheer Bahádúr, which had been formerly borne by one of the Atole family in 1692. This is the first mention of the present ruling family of Baroda. Before many months both Khanderáv and Dámáji died. The former was succeeded by his son Trimbakráv, on whom his father's title was conferred. Piláji, nephew of Dámáji, was confirmed in his uncle's

THE  
MARÁTHAS.  
A.D. 1760-1819.

Dábháde  
Senápati.

The Peshwa's  
Negotiations,  
1717.

Dámáji Gúikwár,  
1720.

THE  
MARATHAS,  
A.D. 1700-1819.

1723.

\* Mac the Tal  
1723.

Kantap Kadam.

Mac the Tal  
Dec. 1723.

honours and retired to Gujarrat. As soon as he could collect a sufficiently strong force, he attacked the Surat district and defeated the Musalmán commander close to the city itself. After extorting from him a handsome sum as ransom, Piláji returned eastwards. He selected Songad,<sup>1</sup> a fort about fifty miles east of Surat, as his headquarters, and from thence made continual excursions against the neighbouring towns. He once attacked Surat, but although he defeated the Mughal leader, he seems to have contented himself with contributions levied from the adjacent country, and not to have entered the town. Piláji soon obtained possession of some strongholds in the Rajpura country between Nanded and Ságbárn, which he fortified, as Khanderáv Dábháde had formerly done. Here he resided as representative of the Senapati, whose family had removed for a while to the Dakhan. The tribute collected from Baglín and Gujarrat was supposed to be transmitted by Piláji to the royal treasury through the Peshwa: but there is no record of these dues having been levied with any regularity or even fixed at any special amount. Whilst Trimbakráv was taking an active part in the affairs of his royal patron in the Dakhan, Piláji occupied himself in sedulously cultivating the goodwill of the border tribes surrounding his residence in Gujarrat.

The year 1723 is noteworthy as being the date of the first imposition of the regular Marátha demand of one-fourth, *chauth*, and one-tenth, *sardeshmukhi*, of the revenue of Gujarrat. Whilst Piláji was directing his attacks against Surat and the south of the province another of Raja Shahu's officers, who had been sent up towards Málwa, entered Gujarrat by the north-east,<sup>2</sup> and after ravaging the country round Dohad,<sup>3</sup> settled a fixed tribute on the district.

This officer, Kantáji Kadam Bánde, was soon after engaged by one of the parties struggling for the viceroyalty of Ahmedábád to bring his cavalry into the province and take part in the civil war. The leader of the opposite party, Rustam Ali, enlisted the services of Piláji Gaikwán. The Nizám-ul-Mulk, whose influence in the Dakhan was very great, managed to detach Piláji from Rustam Ali's side. This was the easier, as Rustam had already defeated Piláji more than once in attacks by the latter against Surat, of which district Rustam was governor. There are two different accounts of what took place when the rival forces came into action, but both show clearly that the Marátha leaders acted on both sides with utter disregard of their agreements and looked only to plundering the Muhammadan camps whilst the soldiers were engaged in battle. After the defeat of Rustam, the two Marátha chiefs joined forces and proceeded to levy *chauth*, of which the Mughal deputy had granted Piláji a share equal to that of his first ally Kantáji.

This division led to quarrels and at last to an open rupture between the two Maratha leaders, which was only patched up by the

<sup>1</sup> On the western skirts of the Háng forests.

<sup>2</sup> Now to the British districts of the Panch Mahals.

<sup>3</sup> The Muhammadan account is given in the Musaháfa portion of this history. Grant Duff's description differs considerably.

grant of the *chanth* north of the Mahi river to Kantáji and of that to the south to Piláji. The chief ground of quarrel seems to have been the relative position of the Gáikwár as agent for the Senápati, who had a right to collect all dues from Gupwát, and of Kantáji, who claimed superior rank as holding his commission direct from Raja Sháhn. On hearing of this dispute and the consequent partition of the Marátha tribute, Trimbakráv Dábhade himself hastened up to Cambay with an army, but effected nothing, and seems to have retired, leaving Piláji to look after his interests at Ahmedábád. Both the latter, however, and Kantáji soon after withdrew from Gujarát, but were within a short period encouraged to return by the success of a raid made by another leader, Antáji Bháskar, on the north-east district. They both joined Hamid Khán in his resistance to the new viceroy, but received several checks from the Muhammadan army, and after plundering again returned to their strongholds for the rainy season.

Next year they returned for the tribute and plundered as usual. The Peshwa Bajiráv then opened for the first time direct negotiations with the viceroy of Gujarát. The rapid increase of the authority of the Bráhman ministers at the Raja's court in the Dakhan had aroused the jealousy of the Maratha nobles, amongst whom Trimbakráv Dábhade was one of the most influential. Bajiráv, being fully aware of the fact, and having by this time acquired from the Raja the power of acting with foreign powers independently of the throne, determined to undermine Trimbakráv's authority in Gujarát by annexing at the rights said to have been formally granted to him by Hamid Khán over the country south of the Mahi. He therefore applied to the viceroy for a confirmation of the right to levy *chanth* and *sardesh-mukhi* over the whole country, on condition that he would protect it from the incursions of Kantáji, Piláji, and other irresponsible freebooters. The viceroy had still some resources left at his disposal and was in hopes that his repeated applications to Delhi for assistance would soon meet with a favourable answer. He declined therefore to accede to Bajiráv's proposals at once, on the grounds that the court at Delhi had repudiated the concessions made to Piláji and Kantáji by his predecessor's deputy. As however the depredations on the frontier caused serious injury both to the cultivators and the people, he allowed the Peshwa to send a feudatory, Udáji Pavár, chief of Dhár, through the Mughal territories to operate against Piláji. The latter, who was fully aware of these negotiations, persuaded Kantáji to join him in expelling the agents of the Peshwa party, as it was clear that if Piláji's forces were scattered the way would be open for Udáji to attack Kantáji himself. The two then proceeded to Baroda and after a while drove back Udáji, and occupied Baroda and Dabhoi. Here Piláji remained, and next year Kantáji succeeded in taking Chámpáner, thus advancing his posts nearer the centre of the province. With such an advantage gained these two chiefs instituted raids still more frequently than before. In these straits, and finding himself utterly neglected by the emperor, the viceroy re-opened negotiations with the Peshwa, who lost no time in sending his

THE  
MARATHAS,  
A.D. 1760-1819.

c Peshwa,  
1726:

cession  
of Tribute,  
1728.

THE  
MARATHÁS,  
A.D. 1760-1819.

Cession  
of Tribute,  
1728.

brother Chinnáji Appa with an army through Gujarát. Petlad and Dholka were plundered, but Kantáji was left undisturbed, so he took this opportunity of marching to Sorath, where he remained for some time extorting tribute. The viceroy agreed formally to cede the *sardesmukhi* of the whole revenue, land and customs (with the exception of the port of Surat and the districts attached to it) and the *chaugh* of the same district, with five per cent on the revenue from the city of Ahmedábád. Special clauses were inserted in the grant of *chaugh* to suit the convenience of both the Peshwa and the viceroy. The latter stipulated that as few collectors as possible should be kept by the Maráthás in the districts under tribute, and that no extra demands beyond the one-fourth should be made. He also insisted that the percentage should be calculated on the actual collections and not on the *kamál* or highest sum recorded as having been collected.<sup>1</sup> The Maráthás were also to support the imperial authority and to keep up a body of horse. The Peshwa agreed (probably at his own request) to prevent all Marátha subjects from joining disaffected chiefs, or other turbulent characters, thus receiving the right to suppress Kantáji and Piláji, as well as the Blals and Kolis with whom the latter was on such friendly terms.

After this agreement was executed, Bájiráv made over part of the *sardesmukhi* to the Dábháde, as well as the *mokása* or three-fourths of the *staráy* as settled by Báláji Vishvanáth. The considerations set forth in the preamble of this agreement was the great improvement effected by the Marátha rulers as regards the wealth and tranquillity of the Dakhan provinces. This was inserted either to give the transaction the appearance of having been executed on the part of the emperor (for otherwise the viceroy had no concern in the state of the Dakhan), or simply as an expression of gratitude on the part of this special viceroy towards the Maráthás who had just brought to terms the Nizám-ul-Mulk, his former rival and enemy. It is even probable that it was merely intended, as usual with such preambles, to veil the forced nature of the treaty.

The hostile movements of the Pratidinidhi in the Southern Marátha Country induced the Peshwa to return to the Dakhan. Kantáji returned from Sorath to Chámpánér, plundering part of the viceroy's camp on his way. Trimbakráv Dábháde, jealous of the interference of the Peshwa in the affairs of Gujarát, began to intrigue with other chiefs to overturn the power of the Bráhman ministers.

Coalition against  
the Peshwa,  
1730

As soon as Nizám-ul-Mulk became aware of this discontent on the part of Trimbakráv, of whose power he was well informed, he proposed to assist him by an attack on the Peshwa from the east, whilst the Maráthás operated in another direction. Trimbakráv was successful in his overtures with Piláji Gáikwár, the Bándé, the Pavárs, and a few other chiefs resident in Khándesh or the north Dakhan. The troops sent by them to join his standard soon amounted

<sup>1</sup> The Marátha practice was to base their demands on the standard or *tankha* assessment (which was seldom if ever collected), so that by this means they evaded all possibility of claims against them for over-collections.

to 35,000 men, who were collected in Gujarát. He then gave out that he was bent on rescuing the Maráthá Rájá from the thralldom in which he was being kept by the Bráhmanas. The Peshwa, who had discovered the intercourse between Trimbakráv and the Nizám, proclaimed this treason on the part of the Dábháde as a royal officer, and stated that the malcontents were only planning the partition of the inheritance of Shiváji between the Rájá of Kolhápúr and themselves. As soon as he found the Nizám's troops were on the march, he collected his picked men and advanced on the Dábháde in Gujarát.

THE  
MARATHAS,  
A.D. 1760-1819.

The Peshwa's army was inferior in numbers but consisted of better trained men. He closed at once with the allies near Dabhoi, and easily defeated the undisciplined forces of the Páwárs and Bándé. The Dábháde's army, however, had more experience of regular warfare and made a stand. But a stray shot killed Trimbakráv as he was endeavouring to rally the forces of his allies, and as usual in such engagements, the loss of the leader disheartened the army. Utter confusion ensued, in which many of the nobles fell, others ran away, and the Peshwa, without the necessity of pushing further his advantage, made good his retreat to the Dakhan. The Nizám, who was in pursuit, only managed to capture some of the baggage with the rear guard as it was crossing the Tápti near Surat.<sup>1</sup>

Defeat of the  
Allies,  
1731.

Safe again in the Dakhan, the Peshwa at once began negotiations with both the Nizám and the adherents of Trimbakráv Dábháde. He recognized the rights of the former to some possessions in Gujarát independent of the viceroy of Ahmedábád, and agreed to further his designs of severing the Dakhan from the possessions of the emperor. He conciliated the Dábháde family by establishing at Poona an annual distribution of food and presents to Bráhmanas such as had formerly been the practice in the native village of Khandakráv.<sup>2</sup> This institution was known as Dakshiná.

Bájráv acquiesced also in the general tendency amongst Maráthás of all offices to become hereditary, and conferred the title of Senápati on Yeshvantrav the minor son of the deceased Trimbakráv. The widow Umibái became guardian, and Piláji Gáikwár deputy or *mutálik* in Gujarát. This latter appointment seems to have been made by the Peshwa and not by the Dábháde, for Piláji received at the same time a new title, namely that of *Sení Khás Khel* or commander of the special band or perhaps the household brigade. He was also bound on behalf of the Senápati to respect the Peshwa's rights in Máhwa and Gujarát, and to pay half the collections from the territory he administered to the royal treasury through the minister. A provision was also inserted with regard to future acquisitions. This reciprocal agreement was executed at the special command of the Maráthá Rájá Sháhu, who had not yet quite abrogated his authority in favour of the Peshwa. Piláji after these negotiations retired to Gujarát.

<sup>1</sup> At Gala about twelve miles above Surat in the territory of the Gáikwár.

<sup>2</sup> Tilegaon in the north-west of Poona, now a station on the railway to Bombay.

THE  
MARÁTHAS,  
A.D. 1760 - 1819.

Assassination of  
Piláji Gaikwár,  
1732.

1733.

Gaikwars Secure  
Baroda,  
1734.

The Marátha  
Deputy  
Governor,  
1736.

Ahmedábád  
Riots,  
1738.

His influence amongst the Bhils and other troublesome races dwelling in the wild parts of the eastern frontier made Piláji an object of hatred and fear to the Mughal viceroy, who had him assassinated by one of his adherents whilst the latter was pretending to whisper some important and confidential news in Piláji's ear. This event took place at Dákor in the Kaira district. The followers of the Gaikwár slew the assassin and retired south of the Mahi. They were driven by the Mughals out of Baroda, but continued to hold Dabhoi. Dámáji Gaikwár, son of Piláji, was at this time prowling round Surat watching for an opportunity of interfering in the disturbed affairs of that town. One of the candidates for the governorship had offered him one-fourth the revenue of the city for his assistance, but the expedition was deferred on account of the appointment of a rival by the emperor. Dámáji therefore was preparing to act on his own account independently of his ally. The news of his father's assassination, however, took him northwards. He found that the Desai of Pádra near Baroda had stirred up the Bhils and Kohls to revolt, in order to give the relations of Piláji a chance of striking a blow at the murderers of their deceased leader. Umábái Dábláde, too, bent on the same errand, moved down the Gháts with an army. The Maráthas were bought off, however, by the viceroy and peace was restored for a while.

In this year also Jádoji, a younger son of Timbakiáv, made an expedition to collect tribute through Gujarat as far as Sorath. Next year Mádhavráv Gaikwár, brother of Piláji, obtained possession of Baroda during the absence of Sher Khán Babi the governor. Since that date this town has been the capital of the Gaikwár family. Sindha and Holkar soon afterwards joined the chief of Idar against the Mnsalmán deputy, and extorted from the latter a considerable sum as ransom.

Umábái had recognized Dámáji as her agent in succession to Piláji; but as she required Dámáji in the Dakhan the latter had been obliged to leave in his turn a *locum tenens* in Gujarat. There ensued quarrels between this deputy, named Rangoji, and Kantáji Kudam which brought Dámáji back again, and after obtaining from the Muhammedan viceroy, who had espoused the cause of Kantáji, a grant of one-fourth the revenues of the country north of the Mahi he went as usual to Sorath. Kantáji Kudam, who as a partisan of the Peshwa was hostile to the Senápati, harassed the country within reach of his frontier. Dámáji, meanwhile, had again proceeded to the Dakhan, where Umábái was intriguing against the Peshwa and required all the help she could obtain to further the ambitious schemes she was devising in the name of her half-witted son. His deputy Rangoji, by demanding a heavy price for his aid at a time when an aspirant to the viceroyalty of Ahmedábád was in distress, managed to secure for the Maráthas half the revenue of Gujarat with certain exceptions.

Dámáji then moved into Gujarat again, and on his way to join Rangoji extorted Rs. 7000 from the English at Surat as a

guarantee against plundering them. The events of this year have been detailed in full in the history of the Musalmán Period. After getting possession of a great part of the city of Ahmedábád the Maráthás, by their oppressive rule, excited a rising amongst the Musalmán inhabitants. Several quarrels and subsequent reconciliations took place between 1739 and 1741, the Musalmáns distrusting the Maráthás, yet not daring to attempt to oust them. Dámáji, on his way back from one of his Sorath expeditions, laid siege to Broach, which was held by a Muhammadan officer direct from the viceroy of the Dakhan.<sup>1</sup> As the latter personage was still regarded by the Marátha chiefs as a possible ally against the Peshwa, Dámáji at once obeyed the request of the Nizám to raise the siege, but probably obtained a promise of future concessions such as he had acquired at Surat.

Rangoji in the absence of Dámáji took up his residence in Borsad. There he fell into several disputes with the Muhammadan officials, in the course of one of which he was taken prisoner, but escaped the next year (1743). Meanwhile Dámáji had joined with Rághoji Bhonslé in attacking the Peshwa. Whilst Rághoji was preparing his army in the east, Dámáji made a feat against Málwa, which had the desired effect of withdrawing a large portion of the ministerial army. The Gáikwár's troops retreated without giving battle, but to prevent any future junction between Dámáji and the Bhonslé party in Berár, Báráji Peshwa confirmed the Pavár family in their claims to Dhár, which had never been acknowledged as their territory since the defection of the Pavárs to the Dábháde party in 1721. It is worth remarking that though the rank of Senápati had apparently been made hereditary in the Dábháde family (for the owner of the title was quite unfit for the command of an army), the Ghorpadé family applied at this time to have it restored to them on the ground that it once had been held by one of their house. The Peshwa, however, managed to secure their alliance by a grant of land, and their claims to the chief command of the army seem to have been waived.

For the next two years the Marátha force in Gujarát under Rangoji and Deváji Tákpar was employed by the Musalmáns in their quarrels regarding the vicereignty. The Marátha practice of appointing deputies gives rise to some confusion as to the negotiations that took place about this time between the Gáikwár's party and the rival candidates for the office of subledár. For instance, Umábái Dábháde had appointed the Gáikwár family as her agents-in-chief, but the principal members of that house were absent in the Dakhan. Dámáji Gáikwár had appointed Rangoji, who in his turn left one Krishnáji in charge of the Marátha share of the city of Ahmedábád. On the departure, however, of Dámáji from Gujarat, Umábái left Rámáji as her agent. Rámáji, who seems to have

THE  
MARÁTHAS  
A.D. 1760-1819.

1739.

1741.

1742.

1743-44

<sup>1</sup> Broach was constituted part of the Nizám's personal estate on his resigning the vicereignty in 1722.

THE  
MARÁTHAS,  
A.D. 1760-1819.

been employed previously by Dámáji, followed the example of his predecessors and placed one Rámchandra in charge at Ahmedábád. There does not appear to have been any direct agent of the Peshwa in Gujarát at this time.

1745.

On Khanderáv Gaikwár's return from the Dakhan he demanded the accounts of the tribute from Rangoji, and not being satisfied with this agent confined him in Borsad and appointed one Trimbakráy in his place. Umábái caused Rangoji to be set at liberty and sent to her in the Dakhan, after which she reappointed him her agent. He expelled Trimbakráy from Ahmedábád, but was attacked by Krishnáji and Gangádhár, two other late deputies. Dámáji and Khanderáv were obliged at last to come to Gujarát and summon all these deputies to their presence. A private arrangement was concluded under which Khanderáv was allowed by Dámáji to keep Nadiád and Borsad as a private estate and to act as the Gaikwár's deputy at Baroda. Rangoji was to live at Umreth when not on active service. Gangádhár and Krishnáji were censured and forbidden to engage in any independent alliances with the Muhammadan leaders.

1746

After this Dámáji sent a general named Kánoji Tákpár to collect the Sorath tribute whilst he himself retired to Songad.

Rangoji returned to Ahmedábád, and not long after began to quarrel with the viceroy about the Marátha share in the revenue of the city ceded in 1728.

The Gaikwár  
in Surat,  
1747.

In A.D. 1747 Kedárji Gaikwár, cousin of Dámáji, was asked by Sved Achchan, an aspirant to the governorship of Surat, to assist him in maintaining possession of that city. Before Kedárji could reach Surat the disputes as to the succession had been settled by negotiations, and the aid of Marátha troops was no longer required. Kedárji, however, finding himself in a position to dictate terms, demanded three lákhs of rupees for the aid that he was prepared to give, and as the Surat treasury could not afford to pay this sum in cash, one-third of the revenues of Surat was promised to the Gaikwár.

1748

Rangoji meanwhile attacked Haribá, an adopted son of Khanderáv Gaikwár, and recovered from him the town and fort of Borsad, which had been seized during the time that Rangoji had been occupied with his disputes in Ahmedábád. Khanderáv and Dámáji both turned against him and captured the fort after a long siege. Rangoji was then again imprisoned, and not released until the next year when the Peshwa sent a body of troops into Gujarát. In 1748 Umábái, widow of Trimbakráy Dábháde, died, leaving one Báburáv guardian of Yeshvántráv her son. Partly through the solicitations of Khanderáv, who had private influence with the Dábhádes, partly from the fact of previous possession, Dámáji was confirmed as deputy of the Maráthás in Gujarát. He there began to collect an army as quickly as possible, in order to co-operate with Raghunáth Bhonslú against the Peshwa, in answer to an appeal by Sakvúrbái, widow of Sháhn, to support the throne against the ministers, and to secure the

succession of Sambhaji to the Sâtara kingdom. The Peshwa, aware of Dâmaji's ill-will towards himself, did his best to foment disturbances in Gujarât and to extend his own influence there so as to keep Dâmaji away from the Dakhan.

The Peshwa accordingly entered into some negotiations with Jawûr Mard Khân, then in power at Ahmedâbâd, but was unable to lend substantial aid in Gujarât against Dâmaji's agents, as the whole Marâtha power was required in the Dakhan to operate against the son of the late Nizâm-ul-Mulk.

Next year Dâmaji, at the request of Târâbâi, guardian of Râm Râja, ascended the Salpi ghât with a strong force, defeated the Peshwa's army, and advanced as far as Sâtara. From this position he was forced to retire, and whilst in treaty with the Peshwa was treacherously seized by the latter and put into prison. Bâlaji at once demanded arrears of tribute, but Dâmaji declined to agree to any payment, on the ground that he was no independent chief but only the agent of the Senâpati. He therefore refused to bind his principal or himself on account of what was due from his principal. Bâlaji then imprisoned all the members of the Gâikwâr and Dâbhâde family that were at that time in the Dakhan.

The state of Surat was at this time such as to afford a good opportunity to the Peshwa to obtain a footing there independently of the English or of Dâmaji. He had recently had dealings with the former in the expeditions against Âugra of Kolâba, and as the merchants had found him one of the most stable and powerful rulers of the country, they were willing to treat with him for the future security of their buildings and goods in Surat. Taking advantage of Dâmaji's confinement, Bâlaji sent Raghunâthrâv to Gujarât. This leader, afterwards so well known as Raghoba, took possession of a few *tilukas* in the north-east of the province, but was recalled to the Dakhan before he could approach Surat. Jawân Mard Khân also took advantage of Dâmaji's absence to make an expedition into Sorath and Kâthnâvâda where the Gâikwâr family had now established themselves permanently.

The news of these two expeditions made Dâmaji vâry eager to return to his province; and as he had full information as to Bâlaji's plan with regard to Gujarât, he bribed freely, and in order to regain his liberty consented to much harsher terms than he would otherwise have done. He agreed to maintain an army for defence and collection purposes in Gujarât, as well as to furnish a contingent to the Peshwa's army in the Dakhan, and to contribute towards the support of the Râja, now in reality a state-prisoner dependent upon the wishes of his minister. The Gâikwâr was also to furnish the tribute due on account of the Dâbhâde family, whom the Peshwa was apparently trying to oust from the administration altogether. After deducting the necessary expenses of collection and defence, half the surplus revenue was to be handed over to the Peshwa. Even after acceding to all these proposals, the Gâikwâr was not at once released. The Peshwa protracted the negotiations, as he had

THE  
MARATHAS,  
A.D. 1760-1819.

1750.

Dâmaji Gâikwâr  
Arrested,  
1751.

The Peshwa  
and Surat.

Release of  
Dâmaji,  
1752.

THE  
MARÁTHÁS,  
A.D. 1760-1819.

to contend against a factions court party in whose counsels he knew Dámáji would play a leading part when once set at liberty. At last, however, after agreeing to a final request that he would assist Raghunáthráv against Surat, Dámáji was allowed to go. There was at this time one Pándurang Pant levying tribute on behalf of the Peshwa in Cambay and Ahmedábád. The Nawáb of Cambay, not having any reason to like or trust his neighbour the Gáikwár, had persuaded the Peshwa at the time the partition of the Maráthas rights over Gujarát was being settled at Poona, to take Cambay into his share of the province. The Nawáb bought off the agent of his ally with a present of guns and cash. The ruler of Ahmedábád also came to terms with the Maráthás, so Pándurang was at liberty to go and see if he could find equal good fortune in Sorath.

Capture of  
Ahmedabad,  
1753.

Dámáji now came back with a fresh army, which was soon reinforced by Raghunáthráv. They marched towards Ahmedábád, and Jawán Mard Khán was too late to intercept them before they invested the capital. He managed, however, by a bold movement to enter the town, but after a long siege was obliged to capitulate and march out with the honours of war. The Maráthas conferred on him an estate in the north-west of Gujarát, which, however, was recovered by them some time afterwards.

1751.

After taking possession of Ahmedábád in April 1753, Raghunáthráv went to Sorath, and on his return extorted a large sum as tribute from the Nawáb of Cambay. He left a deputy in Ahmedábád, who marched against the same chief again in 1754, but on this occasion he could levy no tribute. As the Nawáb had firmly established himself and considerably enlarged his dominions, the Peshwa's deputy marched against him in person a second time but was defeated and taken prisoner. The nominee of Raghunáthráv procured his release, and the Peshwa's deputy continued to demand arrears of tribute for his master till he obtained an agreement to pay at a future date. He then retired to the Dakhan, and the Nawáb, taking advantage of the lull to strengthen his army, captured Ahmedábád from the Maratha garrison and established himself in the city. After a while Dámáji and Khandaráv Gáikwár, with an agent sent direct by the Peshwa, arrived before the town and commenced a siege. It was not until April 1757 that the Maráthas again entered the city. The Nawab surrendered after the Maráthas had fully ratified the conditions he himself had proposed.

1755.

1757.

1758.

Sayájiráv, son of Dámáji, remained in Ahmedábád on behalf of his father, and the Peshwa's agent Sadáshiv put in a deputy in his turn and went himself to Surat. Here he was soon joined by Sayáji, who had to arrange the shares of the tribute in accordance with the partition treaty of 1751. Next year a body of Maráthas troops was sent to the aid of the Ráv of Kachh, who was engaged in an expedition against Thatta in Sindh. Sadáshiv lent the Nawáb of Cambay some money on the part of the Peshwa to enable him to liquidate the arrears of pay due to his army, but a year afterwards the Maráthas army appeared at the town gates with a demand for

two years' arrears of tribute in full, amounting to Rs. 20,000. The Nawáb managed to raise this sum, and the Maráthás moved south. Dámáji was at this time in Poona.

THE  
MARÁTHÁS,  
A.D. 1760-1819.

The Peshwa had supported Syed Achchan of Surat with the view of putting him under an obligation so as to secure some future advantages, and this year lent him some troops as a bodyguard. The Nawáb of Cambay, who was also indebted to the ministerial party, left his dominions to pay a visit to the Peshwa at Poona. Khandaráv meanwhile plundered Lajnáváda and Idar, whilst Savájráv was similarly engaged in Soráth.

1759.

Dámáji Gáikwár accompanied the Peshwa to Delhi, and was one of the few Marátha leaders that escaped after the defeat at Pá nipat. On his return to Guparát he successfully opposed an expedition by the Nawáb of Cambay against Bálasthor and re-took the estates of Jawán Mand Khan. He also strengthened his position in Soráth and Káthnáváda against the Peshwa's party.

1761.

The Peshwa, being hard pressed by his rival the Nizám, began in this year to make overtures to the East India Company's officers in Bombay, with a view to getting the aid of European artillery and gunners. He at first offered to give up a valuable tract of land in Jámbsar. But the English would accept no territory but the island of Sálsette, the town of Bassein, and the small islands in the harbour of Bombay. These the Marátha government declined to give up, so negotiations were broken off.

1761.

Next year Raghnáthráv, as guardian of the son of Bá láji, named Mádhavráv, who was still a minor, conferred the title of Senápati on one of the Jádhav family who had formerly borne it. The administration of Gupmát, however, which had always accompanied the title when held by the Dabháde family, was left practically in the hands of Dámáji, and no mention of any transfer of it was made at the time Jádhav was appointed commander-in-chief. Discontented with the empty honour thus conferred, Rámchandra, the new Senápati, joined the Nizám's party, and on account of this defection the Peshwa, two years afterwards, cancelled the appointment and restored the office to the Ghorpáde family, one of whose members had held it long before. This put an end to the connection of Gujaraat with the chief military dignity of the Marátha state.

1762.

After Mádhavráv Bá láji came of age he had constantly to be on this guard against the plots of his uncle Raghnáthráv, who had refused to accept the share in the government offered him by the young Peshwa. Raghnáthráv, perhaps instigated by his wife, had no doubt great hopes of obtaining a share in the whole power of the administration, and suspecting Mádhavráv to be aware of his designs, looked upon all the overtures made by the latter as intended in some way or other to entrap him. He therefore collected an army of some 15,000 men in Báglán and Násik, and hoping to be joined on his way by Jánoji-Bhonsló, advanced towards Poona. In his army was Govindráv, son of Dámáji Gáikwár, with a detachment of his father's troops. The Peshwa, without giving Jánoji time to effect

Intrigues of  
Raghoba,  
1768.

THE  
MARATHAS,  
A.D. 1760-1819.

Death of Dāmaji  
Gaikwār,  
1768.

Disputed  
Succession.

a junction with Raghunāthráv, even if he had been prepared to do so, defeated his uncle's army at Dhoraj, a fort in the Ajunta range, and carried off Rāghobá and Govindrav to Poona, where they were placed in confinement.

Not long after this action Dāmaji died. He had brought the fortunes of the Gaikwār house to the highest pitch they ever reached and not long after his death the family influence began to decline. It was his personal authority alone that was able to counteract the usual tendency of quasi-independent Marátha states towards disintegration, especially when they are at a distance from the central power. Khanderáv and Sayájráv had shown frequent signs of insubordination (as for instance in their espousal of the cause of Rangaji) and a desire to establish themselves in an independant position, but the sagacity of Dāmaji foresaw the advantage such a partition would give an enemy like the Peshwa, and his tact enabled him to preserve unity in his family, at least in resistance to what he showed them to be their common foe.

The quarrel for the succession that arose on Dāmaji's death was the first step towards the breaking up of the Gaikwār's power. Dāmaji had three wives. By the first he had Govindráv, who however was born after Sayájráv, the son by the second wife. His sons by the third wife were Mánaji and Fatesingh. Govindráv was in confinement at Poona near the court, and therefore in a position to offer conditions for the confirmation of his rights without loss of time.

In the Hindu law current amongst Maráthas, there are to be found precedents in favour of the heirship of either Govindráv or Sayájráv. Some authorities support the rights of the son of the first wife whether he be the eldest or not, others again regard simply the age of the claimants, deciding in favour of the first born, of whatever wife he may be the son. Rāmráv Shástri, the celebrated adviser of Mādhavráv Peshwa, is said to have expressed an opinion in favour of the rights of Sayájráv. Govindráv, however, was on the spot where his influence could be used most extensively. Savaji, moreover, was an idiot and a puppet in the hands of his half brother Fatesingh. Govindráv applied at once for investiture with the title of Sená-Khas-Khel. A payment of 50½ lakhs of rupees to the Peshwa on account of arrears of tribute and a fine for his conduct in taking part with Rāghobá was a strong argument in his favour, and when he agreed to a tribute previously demanded from his father of Rs. 7,79,000 yearly and to maintain a peace contingent at Poona of 3000 horse, to be increased by a thousand more in time of war, there could be little doubt as to the legitimacy of his claim, and he was duly invested with his father's title and estate.

1771.

For reasons not apparent Sayáji's claims were not brought forward till nearly two years later. Govindráv had never been allowed to join his charge in Gujarát, so that he could exercise no interference in that direction, and the court affairs in the Dukhan left perhaps little time for the disposal of Sayájráv's application, even if it had been made. Sayáji had entrusted his interests to Fatesingh, a man

of considerable ability, who came at once to Poona to get a reversal of the recognition of Govindráv. The Peshwa was glad to have this opportunity of undoing so much of Dámá's work and dividing the Gáikwár family against itself, so using the verdict of Rám Shástri as his weapon, he cancelled the former grant in favour of Govindráv, and appointed Sayajiráv with Fatesingh as his *mutálik* or deputy. The latter, by agreeing to pay an extra sum of 6½ lákhs of rupees annually, got permission to retain the Poona contingent of Gáikwár horse in Gujarát, on the pretext that Govindráv would probably attack his brothers on the earliest opportunity. Thus, whatever happened, all went to the profit of the Peshwa's party and to the injury of the tax-paying Gujarát ryot.

Fatesingh retired in triumph to Baroda, and opened negotiations with the English in Surat, as he had been endeavouring to do for a year past without success. In January 1773, however, he succeeded in getting an agreement from the Chief for Affairs of the British Nation in Surat, that his share in the revenues of the town of Broach, which had been taken by storm in 1772 by the English, should not be affected by the change of masters. In the same year Náráyauráv Peshwa was murdered, and Rághobá was invested by the titular king at Sátara with the ministerial robe of honour. Govindráv Gáikwár, still in Poona, reminded the new Peshwa of the good offices of the Gáikwár family at Dhorap and elsewhere, and found means of getting reinstated as Sená-Khás-Khel. In 1774 he set out for Gujarát, and collecting a fair number of adherents on his way, he attacked Fatesingh. After various engagements of little importance, the latter found himself shut into the city of Baroda, which was invested by Govindráv in January 1775.

In the meantime Rághobá had been driven from power by the intrigues of Brahmans of a different class from that to which he belonged, headed by the afterwards well-known Nána Phadnis. The ex-Peshwa first betook himself towards Malwa, where he hoped to be joined or at least assisted by Holkar and Sindia. As soon however as he got together some scattered forces he marched down the Tápti and opened negotiations with the English through Mr. Gambier, the chief at Sur. The Bombay Government at once demanded the cession of Bassen, Sálsette, and the adjacent islands. Rághobá refused, partly, in all probability, on account of the pride felt by the Marátha soldiery in their achievements before Bassen at the time of the great siege. He however offered valuable territory in Gujarát, yielding a revenue of about eleven lákhs, and to pay six lákhs down and 1½ lákhs monthly for the maintenance of a European contingent with artillery. The English at Bombay were debating whether this offer should not be accepted when news reached them that the Portuguese were about to organise an expedition to re-take Bassen. Negotiations with Rághobá were hastily broken off and a small force sent to forestall the rival Europeans. Before the end of 1774, both Thána and Versova fort in Sálsette had been taken.

Rághobá now heard that Sindia and Holkar had been bought over by the ministerial party and would not come to his assistance.

THE  
MARÁTHAS,  
A.D. 1760-1819.

1773.

1774.

Rághobá  
Peshwa,  
1774.

Rághobá in  
Gujarát,  
1776.

THE  
MARATHAS,  
A.D. 1760-1819.

Quickly moving his force down the river he reached Baroda in January 1775 with 10,000 horse and 100 foot. He joined Govindráv in investing that town, but sent meanwhile an agent to re-open the discussion of his proposals in the Bombay Council. This agent was captured by a party of Fatesingh's horse whilst he was out on an expedition near Párnara on behalf of Govindráv. On his release he repaired to Surat and took steps to get a treaty of alliance signed as soon as possible.

Rághobá  
Defeated.

The ministerial army of 30,000 men under Haripant Phadke entered Gujarat and obliged Govindráv and Rághobá to raise the siege of Baroda and to retire towards the Mahr. Fatesingh's force then joined Haripant. An attack on all sides was made (Feb. 17th). Rághobá, who was in the centre, was first charged, and before Govindráv and Khanderáv Gáikwár could come to his assistance his best officers were wounded, some of his Arab mercenaries refused to fight as large arrears of pay were due to them, and he was defeated on both flanks. He fled to Cambay with only 1000 horse; whilst the two Gáikwárs and Manaji Sindhia (Phadke) led the rest of the scattered army to Kapadvanj, where it was again set in order. The Nawáb of Cambay, fearing lest the Maráthá army should come in pursuit, shut the town gates on the fugitive and refused to give him shelter. Mr. Malet, chief of the English residents, who had been informed of the negotiations in progress between his Government and Rághobá, contrived to get the ex-Peshwa conveyed privately to Bhavnagar and from thence by boat to Surat. Here he arrived on February 23rd.

Reaches Surat.

Treaty of Surat,  
1775.

The stipulations of the treaty negotiated by Narotamdas, agent of Rághobá, and the Bombay Government were: The English to provide a force of 3000 men, of which 800 were to be Europeans and 1700 natives, together with a due proportion of artillery. In return for this Rághobá, still recognized as Peshwa, was to cede in perpetuity Sálsette, Bassem and the islands, Jámbúsar, and Olpád. He also made over an assignment of Rs. 75,000 out of the revenues of Anklesvar, the remaining portion of which district, together with Amod, Hansot, and Balsar was placed under British management as security for the monthly contribution of 1½ lákhs for the support of the troops in his service. He also promised to procure the cession of the Gáikwár's share in the revenues of Broach. Sundry other provisions (dealing with different parts of the Maráthá dominions) were inserted, Rághobá being treated throughout as the representative of the Maráthá kingdom. This treaty was signed on March 6th, 1775, at Surat, but on the previous day there had been a debate in the Council at Bombay as to the propriety of continuing to support Rághobá, as the news from Gujarát made the British authorities doubtful whether the contingent they had already sent to Surat was enough to ensure success.

Colonel Keating  
in Gujarát.

Just before the treaty was drawn up, at the end of February Lieut.-Colonel Keating had been despatched in command of 350 European infantry 800 sepoys 80 European artillerymen and 60 gun lascars with others, in all about 1500 men, ready for active service. This force landed at Surat four days after Rághobá had arrived from Bhavnagar.

Before receiving this token of the intention of the British to support Raghobá, the Nawáb had treated the latter simply as a fugitive, but upon finding that the Bombay Government had determined to make the ex-Peshwa their ally, he paid the customary visits and offered presents as to a superior.

When the news reached Sarat that Govindráy's troops and the rest had been reorganized at Kapadvanj, it was determined to effect a junction with them by landing Colonel Keating's detachment at Cambay and from thence marching north.

Considerable delay occurred in carrying out the first part of this proposal. First of all Raghobá detained the army at Dumas<sup>1</sup> whilst he paid a visit of ceremony to the frequented temple of Bhimpor in the neighbourhood. Then again, the convoy met with contrary winds the whole way up the gulf, and it was not till March 17th that the contingent landed. The Nawáb, accompanied by the British Resident, paid a visit of ceremony and presented *nazaránás* to Raghobá as a sort of atonement for his previous discourtesy and neglect. The Marathas, however, knowing that this change of tone was entirely due to the presence and alliance of the Europeans, paid much more attention to the latter than to the Muhammadans.

The British contingent encamped at a place called Náráyan-Sarovar, just north of the town. Here they waited until the reinforcement from Bombay arrived, bringing the whole force up to the complement stipulated for in the treaty. Raghobá's army under Govindráy Gaikwár was reported to be moving southwards, and Colonel Keating agreed to let it pass the Sábarmati river before joining it. Meanwhile the enemy, said to number 40,000 infantry and 12,000 cavalry, marched north to intercept Govindrav. The latter, however, by forced marches succeeded in crossing the Sábarmati before the arrival of the ministerial army, and encamped a few miles north-east of Cambay at a place called Darmaj or Dara. Here Colonel Keating joined him about the middle of April.

Govindráy's army consisted of about 8000 fighting men and nearly 18,000 camp followers. These latter were chiefly Pindháris who used to attach themselves to the camp of one of the Marátha chiefs, on condition of surrendering to him half their plunder. Each chief had his separate encampment, where he exercised independent authority over his own troops, although bound to general obedience to the commander-in-chief of the whole army. The confusion of this arrangement is described by an eye-witness as utterly destructive of all military discipline. To add to the cumbronsness of such an expedition, most of the Pindháris brought their wives and children with them, the cooking pots and plunder being carried on bullocks and ponies, of which there were altogether nearly 200,000 attached to the troops. In every camp there was a regular

THE  
MARÁTHAS,  
A.D. 1760-1819.

Keating sails  
with Raghobá  
for Cambay.

Raghobá in  
Cambay,  
1775. •

Govindráy  
Gaikwár's  
Army.

<sup>1</sup> At the mouth of the Tápti, now belonging to the little Muhammadan state of Sachin.

THE  
MARÁTHAS,  
A.D. 1760-1819.

Advance of  
the Combined  
Forces.

*bazár* where cash payment or barter passed equally current, so that a premium was thus placed on the pillering of small articles by the Pindháris, whose stipulations as to plunder were confined neither to friend nor enemy.

When all needful preparations had been made, the army, accompanied by a battery of ten guns, besides mortars and howitzers, all of which were manned by Europeans, moved out against the enemy. The latter slowly retreated, burning the crops and forage and destroying the water-supply on its way. On the 20th April the first engagement took place at Usámlí, resulting in the repulse of the ministerial troops. On May 1st a similar skirmish on the banks of the Vátrak drove the ministerialists into Kara. From this post they were driven after a series of slight engagements with the army of Rághobá, which crossed the river at Mátar. Fatesingh now received a reinforcement of 10,000 horse under Khanderáv Gáikwár, but to counterbalance this aid, Sindia and Holkar from some unexplained cause, connected probably with intrigues at Poona, withdrew from further co-operation with him. Colonel Keating was unable to follow up the advantages he had gained owing to the large proportion of cavalry in the enemy's army. He therefore continued his march southwards, after persuading Rághobá to spend the monsoon in Poona, where he would be on the spot to counteract intrigues, instead of at Ahmedábád, as had been at first proposed.

On May 8th the army reached Nadiád, after repulsing on the road two attacks by the enemy's cavalry. This result was obtained chiefly by means of the European light artillery. Nadiád belonged at this time to Khanderáv Gáikwár, and to punish his defection to Fatesingh, Rághobá inflicted a fine of 60,000 rupees on the town. The amount was assessed on the several castes in proportion to their reputed means of payment. The Bháts, a peculiar people of whom more hereafter, objected to being assessed, and slaughtered each other in public so that the guilt of their blood might fall on the oppressor. The Bráhmans, who also claimed exemption from all taxation, more astutely brought two old women of their caste into the market place and there murdered them. Having made this protest, both castes paid their contributions. Rághobá injudiciously wasted seven days over the collection of this fine, and in the end only levied 10,000 rupees.

Defeat of  
Fatesingh,  
1775.

On May 14th the march was resumed, under the usual skirmishing onslaughts of the ministerial party. At Aras, where Rághobá had been defeated shortly before, he was in imminent danger of a second and still more serious discomfiture. An order mistaken by a British company, and the want of discipline on the part of Rághobá's cavalry nearly led to a total defeat with great slaughter. The European infantry and artillery, however, turned the fortunes of the day. The troops of Fatesingh were allowed to approach in pursuit to within a few yards of the batteries, all the guns of which then opened on them with grape, the infantry meanwhile plying their small arms along the whole line. Fatesingh was obliged to withdraw his diminished forces and the army of Rághobá received no further molesta-

tions from him on its way to the Mahi. Colonel Keating then ordered a general move to Broach, where he arrived safely on 27th May, after a troublesome march through the robber-infested country between the Dhādhar river and Amol.

Here they remained until June 5th, when Colonel Keating was about to move south again. Luckily, as it turned out for him, the nearest ford was impassable and he had to march to one higher up at a place variously called Bāba Pāra or Bāva Pir. On his way thither he heard that Haripant, the ministerial commander-in-chief, was halting on the north bank by the ford, he therefore pushed on to make an attack on the rear, but owing partly to timely information received and partly to the confusion caused by the irrepressibility of Rāghobā's cavalry, Haripant had time to withdraw all his force except some baggage and ammunition, which, with a few guns, he was forced in the hurry of his passage across the river to leave behind. Colonel Keating then marched fourteen miles north from the ford and halted before proceeding to Dabhoi, a town belonging to Fatesingh. The general ignorance of tactics and want of discipline in the native army had determined Colonel Keating not to lead his force as far as Poona, but to spend the monsoon near Baroda.

Rāghobā detached one of his generals, Amir Khān, in pursuit of Ganeshpant, whom Hari Pant had left as his deputy in Gujarāt. Ganeshpant with a detachment of the ministerial army had separated from Hari at the Baba Pāra ford and found his way through the wild country on the north of the Tāpti towards Ahmedabad. He was finally caught by Amir Khān.

Dabhoi was at this time in charge of a Brāhman governor, who submitted on the approach of Rāghobā's army. Colonel Keating quartered his force in the town, but Rāghobā, after exacting a bribe of three lakhs of rupees, encamped at Bhūlāpur on the Dhādhar, ten miles from Dabhoi. Here he began to negotiate with Fatesingh in Baroda through the mediation of Colonel Keating. Fatesingh was all the more ready to come to definite terms of agreement, as he knew that Govindray was on the watch to recover Baroda.

It is not certain what the terms proposed and agreed to really were. The only record of them is a copy sent in 1802 to the Resident at Poona by Governor Duncan. According to this document Govindray was to lose his pension and to occupy the same position as before the accession of Rāghobā. Khanderao was to revert to the situation in which he had been placed by Dānaji. The provision of the treaty of the 6th March regarding the Gāikwār's claims on Broach was ratified, and as a reward for the mediation of the Bombay Government, the Gāikwār ceded to the British in perpetuity the sub-divisions of Ohikhli and Variāv near Surat and Koral on the Narbada. Before this treaty could be concluded, Colonel Keating received orders to withdraw his contingent into British territory and to leave Rāghobā to manage for himself. This change of policy was due to the disapproval by the Supreme Government of the treaty of 6th March, which they alleged had been

THE  
MARATHAS,  
A.D. 1760-1819.

The  
Ministerial  
General  
Retreats.

Colonel Keating  
at Dabhoi,  
1776.

Rāghobā and  
the Gāikwār.

THE  
MARÁTHÁS,  
A.D. 1760 - 1819.

Withdrawal  
of the British  
Contingent.

Negotiations  
at Poona.

Rághobá at  
Surat,  
1776.

made inconsistently with the negotiations then being carried on with the ruling powers at Poona as well as with the authority of the Calcutta Government. The treaty was therefore declared to be invalid and the troops in the field were ordered by the Supreme Government to be withdrawn at once into British garrisons. A special envoy, Colonel Upton, was sent from Bengal to negotiate a treaty with the Ministers in accordance with the views current in Calcutta.

As soon as the roads were open Colonel Keating moved towards Surat, but at the solicitation of Rághobá he disobeyed his orders so far as to encamp at Kadod, about twenty miles east of Surat, but not in British territory. Here he awaited the results of the overtures of Colonel Upton. This envoy remained at Poona from the 28th December 1775 till the 1st March 1776, on which date he signed the treaty of Purandhar, in which the office only and not the name of the Peshwa is mentioned. By this compact the Peshwa ceded all claims on the revenue of Broach together with land in the neighbourhood of that town to the British. He also paid twelve lakhs of rupees in compensation for the expenses of the war. Sálsette was to be either retained by the English or restored in exchange for territory yielding three lakhs of rupees annually. The cessions made by Fatesingh Garkwár were to be restored to him if the Peshwa's Government could prove that he had no right to make them without due authorization from Poona. The treaty of the 6th March was declared null and void. Rághobá was to disband his army and take a pension. If he resisted, the English were to give him no assistance. If he agreed to the terms proposed, he was to live at Kopargao<sup>1</sup> on the Gedávari with an ample pension. When he received information as to the terms of the new treaty, he at once declined to accept the pension, and, as he could not understand the position of the Bombay Government with regard to that at Calcutta, he proceeded to offer still more favourable terms for further assistance.

Rághobá was at Mándvi<sup>2</sup> on the Tápti when he was finally given to understand that the British could no longer aid him. He thereupon took refuge in Surat with two hundred followers. The rest of his army which had been ordered to disperse, gathered round Surat, on pretence of waiting for the payment of the arrears due to them. As their attitude was suspicious, and there were rumours of an expedition having started from Poona under Haripant to subdue them, the Bombay Government garrisoned Surat and Broach with all the forces it could spare.

Colonel Upton meanwhile offered Rághobá, on behalf of the ministers, a larger pension with liberty of residing at Benáres. This also was declined, and the ex-Peshwa fled to Bombay, where he lived on a monthly pension allotted him by the Government.

<sup>1</sup> Now in the Ahmednagar district.

<sup>2</sup> In the Surat district some thirty miles east of the city.

On 20th August 1776, a despatch of the Court of Directors arrived confirming the treaty of the 6th March 1775. At first the Bombay Government were inclined to take this as authorizing the retention of all the territory ceded, but on farther deliberation it was decided that as the treaty of Purandhar had been ratified by the Supreme Government subsequent to the signing of the despatch, which was dated 5th April 1776, it was evident that the Court of Directors did not mean to uphold the previous engagement more than temporarily, or until the final treaty had been concluded.

At the end of 1776, a Bombay officer was sent in place of Colonel Upton to be a resident envoy at Poona for the carrying out of the provisions of the treaty. Mr. Mostyn was the person selected, and he arrived in Poona in March 1777. He soon found that the ministers had little intention of adhering to the treaty, so he at once took up the question that he thought it most important to the Bombay Government to have settled, namely the relations of the Peshwa's Court with Fatesingh Gáikwár as regards the cessions of territory. The ministers asserted that the Gáikwárs merely administered Gujarát on the part of the Peshwa and were entirely dependent upon the Poona government, so that they could conclude no agreement with foreign states except with its approbation. Fatesingh did not deny the dependence, but evaded the question of his right to make direct treaties and claimed the restitution of the cessions on the ground that Raghunáthráv had failed to perform his part of the stipulations. The point was discussed for some time, and at last the question of dependence seems to have been let drop, for in February 1778 Fatesingh paid up the arrears of tribute, made the usual presents to the ministers and their favourites, and was again invested with the title of Sená-Khas Khel.

In October a despatch from the Court of Directors reached the Governments of Bengal and Bombay, disapproving of the treaty of Purandhar, but ratifying it on the principle of *factum est*. It was suggested, however, that in case of evasion on the part of the ministers, a fresh treaty should be concluded with Raghobá on the lines of that of 1775.

In November 1778 it was rumored that the ministers in Poona were intriguing with the French, so the Bombay Government took this opportunity of entering into a treaty with Raghobá, who was still in Bombay. He confirmed the grants of 1775, and as security for the pay of the British contingent that was to help in placing him on the Peshwa's throne in Poona, he agreed to assign the revenues of Balsár and the remainder of Anklesvar, as he had done before. He stipulated, however, that his own agents should collect the dues from these districts, and that the British should take charge of them only in case of the full sum due not being paid and then merely as a temporary measure.

On the 22nd November 1778 the force moved out of Bombay, and by dint of mismanagement and internal dissension the campaign was brought to an end by the convention of the 16th January 1779.

THE  
MARATHAS,  
A.D. 1760 - 1819.

Negotiations  
at Poona,  
1777.

Fresh Alliance  
with Raghobá,  
1778.

The Convention  
of Bhadgaon,  
1779.

THE  
MARATHAS,  
A.D. 1790 - 1819.

Negotiation  
with the  
Gaikwār.

Under this agreement all possessions in Gujarāt acquired since the time of Mādhavráv Peshwa were to be restored by the British, together with Sálsette, Uran, and other islands. Rághobá was to be made over to Sindia's charge, and a separate treaty assigned to Sindia the sovereignty of Broach.

The Council at Bombay disavowed the convention and were inclined to adhere only to the clause allotting Broach to Sindia. Mr. Hornby proposed to the Supreme Government an alliance with Fatesingh, engaging to free him from dependence on the Poona Government and to reconcile the disputants within the Gaikwār family itself. After the arrival of General Goddard with reinforcements from Bengal the Governor General approved of the alliance proposed with Fatesingh as head of the Baroda state, but specially declined to admit any participation or support in the family disputes. The British were to conquer for themselves the Peshwa's share of Gujarāt, if they were able to do so.

Rághobá Escapes  
from Sindia,  
1779.

Rághobá, meanwhile, who had been given over to Sindia to be conveyed to Bundelkhand, escaped with the connivance of his custodian and fled to Broach. This was evidently a move calculated by Sindia to bring on hostilities between Nána Phadnis, the head of the ministerial party, and the English. General Goddard, who was conducting the negotiations with Poona on the part both of the Supreme Government and of the Government of Bombay, received Rághobá on June 12th, but evaded any proposals for a direct alliance. At the end of the rains of the same year, information was received by the English that a coalition against them had been formed by the Maráthás, the Nizám, and Hyder Ali of Mysor. The rumour was partially confirmed by the demand by Nana Phadnis for the cession of Sálsette and the person of Rághobá as preliminaries to any treaty. No answer was given, but reinforcements were called for and the overtures with Fatesingh pushed forward. This chief prevaricated about the terms of the treaty and evidently did not like to enter into any special engagement that might perhaps bring down upon him the Poona army. General Goddard therefore advanced on 1st January 1780 against Dabhoi, which was garrisoned by the Peshwa's troops from the Dakhan, whilst the English in Broach expelled the Maráthá officers from their posts and re-took possession of Anklesvar, Hānsot, and Amol. On January 20th Dabhoi was evacuated by the Maráthás and occupied by General Goddard. Fatesingh now showed himself willing to enter into the proposed treaty, and on the 26th January 1780 signed an offensive and defensive alliance.

League against  
the English,  
1780.

Treaty with  
Fatesingh  
Gaikwār.

In the re-opening of hostilities there was no mention of Rághobá, but the ground given was simply the non-fulfilment on the part of the Peshwa of his treaty engagement. Rághobá remained under English supervision in the enjoyment of a large allowance. Dabhoi was occupied by an English civil officer with a detachment of irregulars, and General Goddard moved towards Ahmedábád.

By the treaty of 1780 the Peshwa was to be excluded from Gujarát. To avoid confusion in collection, the district north of the Malu was to belong entirely to the share of the Gaikwár. The English were to enjoy the whole district south of the Tápti, together with the Gaikwár share in the revenue of Surat. In return for the support the English were to give him in withholding tribute from the Peshwa, Fatesingh ceded Sinor on the Nerbada and the Gaikwár's villages round Broach. These cessions, however, were not to have effect until Fatesingh was in possession of Ahmedábád. The contingent of 3000 horse was to be still furnished by the Gaikwár government.

As soon as these conditions were agreed upon, General Goddard went with his own army and the contingent furnished by Fatesingh to Ahmedábád. After encamping before it for five days, he took the city by storm on 15th February 1780.

Sindia and Holkar had combined their forces against the English and were marching up Gujarát, plundering on their way. They were opposed by General Goddard, who marched across the Muih early in March. The allies turned off towards Chámpáner without risking a pitched battle on the plain. Sindia at once opened negotiations with the view of wasting time during the fair season. His first proposal was that Rághobá should be sent to Jhánsi, where Sindia had allotted him an estate, and that Bájiráv, Rághobá's son, should be appointed *diwán* or manager of the Peshwa Madhávrao, who was a minor. Bájiráv himself was under age, so Sindia was, of course, to assume temporarily the reins of government.

Goddard at once refused to force Rághobá to take any course other than the one he should select of his own free will, for Sindia did not appear to be aware that the English were now at war with the ministers on their own account and not as allies of an ex-Peshwa. Negotiations were broken off and Sindia and Holkar dislodged from place after place without any decisive engagement being fought. General Goddard was preparing monsoon quarters for his army, when he heard that a division of a Marátha force which had been plundering the Konkan in order to cut off supplies from Bombay had attacked parts of the Surat Athávisá. He detached some troops under Lieut. Welsh and sent them to the relief, whilst he remained himself on the Nerbada. Lieut. Welsh drove back the marauders and took possession of the forts of Parnera, Indurgad, and Bagvála.

After the monsoon of 1780, General Goddard went to besiege Bassein, leaving Major Forbes in charge of the Gujarát army. This officer posted one body of troops at Ahmedábád for the protection of Fatesingh, another at Surat, and a third at Broach. Two battalions of Bengal infantry were sent to Sinor and some few men to Dabhoi.

An attack was made by Sindia on the newly acquired district of Sinor, but Major Forbes successfully resisted it and Sindia's position with regard to his own dominions was now such as to prevent him from sending more expeditions against Gujarát.

The military necessities of other parts of India were such as to induce General Goddard to apply to Fatesingh for an increase to

THE  
MARATHAS,  
A.D. 1760-1819.

General Goddard  
takes Ahmedábád,  
1780.

Operations  
against Sindia  
and Holkar

1781.

THE  
MARÁTHAS,  
A.D. 1760-1819.

Treaty of Sálbai,  
1782.

his contingent, in accordance with the treaty of 1780. After some personal communications with this Chief in Gujarát, General Goddard was able to arrange with the Gaikwár for the defence of part of that province and thus set free some European troops for service elsewhere.

No further attack was made in this direction during the continuance of the war which came to an end on 17th May 1782. The treaty of Sálbai between an envoy of the Governor General on one side and Mahádaji Sindia as plenipotentiary for the Peshwa and minister of Poona on the other, replaced the Marátha territory in Gujarát exactly where it was on the outbreak of hostilities against Raghubá in 1775. It was, however, specially stipulated that no demand for arrears of tribute during the late hostilities should be made against the Gaikwár, a clause that led to misunderstandings many years later. The town of Broach was given over to Sindia in accordance with the secret negotiation of 1779 and the votes of the Bengal and Bombay Councils. The territory round Broach yielding a revenue of three lakhs of rupees, ceded by the Peshwa, was likewise returned. Raghubá was granted a pension of 25,000 rupees a month and allowed to select his own place of residence. He went to Kopargaoon and there died a few months after the conclusion of the treaty of Sálbai. Thus came to an end one of the chief sources of disturbance to the Poona government. For the next six years no event of any political importance took place in Gujarát, which province was left almost entirely to the administration of the Gaikwar family.

Death of  
Fatesingh,  
1789.

In 1789, however, Fatesingh died, leaving Sayájiráv without a guardian. Mánáji, a younger brother, at once seized the reins of government and began the usual sort of negotiations to secure his recognition by the Poona government. He paid a nazarána of 3,13,000 rupees and agreed to pay up thirty-six lakhs of rupees as arrears, though it is not clear on what account, unless that sum had accrued since the treaty of Sálbai, or was part of the long standing account left open by Dámáji in 1753. Mánáji, however, was not allowed to succeed to the post of guardian without opposition. Govindráv Gaikwár was living at Poona, and, though he had himself little influence with the Peshwa's immediate adherents, he had managed to secure the then powerful Sindia on his side. This chief, since his recognition as plenipotentiary at the treaty of Sálbai, had been gradually making good his position with the Peshwa and his favourites as well as with the leading Marátha nobles, so as to be able to successfully oppose Nána Phadnis when the time came for a coalition of the outlying chiefs against the ministerial party. Govindráv offered his son Anandráv as husband for the daughter of Sindia, a proposal which it is not probable that he ever intended to carry out. A grant of three lakhs of rupees was also promised, in return for which Sindia allowed his garrison in Broach to assist Govindráv's illegitimate son Kánhoji to reach Baroda. Mánáji applied to the Bombay Government on the grounds that the steps taken by Govindráv were contrary to the provisions of the treaty of 1780. As however this treaty had been abrogated by the later agreement at Sálbai, the Bombay Government declined to interfere. Mánáji's agents at Poona

contrived to get Nāna Phadnis to propose a compromise, to which however Govindrāv, at the instigation probably of Sindia, declined to accede. Before any decision was reached Mánáji died.

THE  
MARATHAS,  
A.D. 1760-1819.

Nāna detained Govindrāv in Poona till he had agreed to hold by former stipulations and to cede to the Peshwa the Gaikwār's share in the districts south of the Típti together with his share of the Surat customs. To this the Government of Bombay demurred as an infraction of the provision of the Sálbai treaty whereby the integrity of the Gaikwār's possessions was assured. Nāna Phadnis at once withdrew his proposals. Govindrāv at last joined his brother at Baroda on 19th December, and took up the office of regent.

• 1793.

For two years Gujarāt remained quiet. In 1796 Bájirāv, son of Rághobá, succeeded to the Peshwa's dignity and at once appointed his younger brother, ten years of age, governor of Gujarāt. In accordance with Maráthá custom a deputy was sent to take charge of the province, one Aba Shehkar, and he too seems to have administered vicariously, for next year (1797) we find him amongst those taken prisoners with Nāna Phadnis when that minister was treacherously seized by Daulatrav Sindia in the Dakhan. Aba was released on promising to pay ten lákhs of rupees as ransom. He then joined his appointment as subhedár in order to take measures to get together the money he required.

Aba Shehkar  
Deputy Governor  
of Gujarāt,  
1796.

797

Bájirāv Peshwa was anxious to embroil Aba with Govindrāv, whom he knew to be favourable to Nāna Phadnis and too powerful to be allowed to acquire influence beyond the reach of head-quarter supervision. A cause of quarrel soon arose. Daulatrav pressed Aba for part payment of the above ten lákhs, and the latter being unable to squeeze enough out of his own territory, forced contributions from some of the villages administered by the Gaikwār. Govindrav at once took up arms against him and applied for aid to the English Agent at Surat. In this city Governor Jonathan Duncan had just assumed chief authority in accordance with an agreement between the English and the Nawáb. Duncan was anxious to secure for his government the land round Surat and the Gaikwār's share in the *chaugh* of the town and district. Govindrāv, when this demand was made, referred the Governor to Poona, knowing that under the treaty of Sálbai the British Government had no more right to acquire a share of the Gaikwār territory than the Poona authorities had when they made a somewhat similar demand in 1793, which was withdrawn as stated above. Before the reference could be made, Aba was penned up by Govindrāv's own army in Ahmedábád and forced to surrender that city. He was kept in confinement for more than seven years.

Disputes  
between Aba  
and Govindrāv  
Gaikwār.

1793.

In the same year (1799) the Peshwa, apparently without formally revoking the appointment of his brother Chinnáji as Subhedár, gave Govindrāv a farm for five years of his whole rights in Gujarāt, at the rate of five lákhs of rupees a year. These rights included shares in the Kúthiáváda and Sorath tribute, the revenue of Petlád, Nápád, Ránpur, Dhandhuka, and Gogha, together with rights to certain customs dues in Cambay and a share in the revenue of the city of Ahmedábád.

Gujarāt farmed  
to the Gaikwār,  
1799.

THE  
MARÁTHAS,  
A.D. 1760 - 1819.

Anandráv  
Gaikwár,  
1800.

Govindráv unfortunately died a month before this farm was formally made over by the Peshwa.

As had happened at the death of Dágnáji, so again now, the heir Anandráv was all but an idiot and quite incapable of managing his affairs. The disputes as to the guardianship again set the whole state in confusion. Kánhoji, a son of Govindráv by a Rájputni princess of Dharampor, who had been the first agent of his father in Baroda in 1793, had been put in prison for refusing to give place to Govindráv when the latter at length joined him at Baroda. At the death of Govindráv, Kánhoji managed to obtain his liberty and to secure the ascendancy in the councils of his weak-minded elder brother. He assumed, in fact, the whole government. His arrogant conduct in this new position excited the Arab guard against him and he was again thrown into confinement. His mother Gajrábái, who was a refugee in Surat, endeavoured to get assistance from the English there, and at the same time made overtures to Malhar, son of Khanderao Gaikwár, who had formerly been one of Govindráv's bitterest opponents.

1800

The British and  
Govindráv's  
Party.

Meanwhile the administration of the Gaikwár's affairs passed into the hands of Rávji and Babáji Appa, two brothers who had been brought to Baroda in 1793 by Govindráv himself. Rávji took charge of the civil work, whilst Babáji undertook the military duties, which at that time consisted in great measure in collecting the revenue by show of force. These two ministers, on hearing of the proceedings of Gajrábái, entreated her for the aid of the Bombay Government. In addition to the cessions formerly offered by Govindráv, they were willing to give up Chikhli also. Matters were precipitated by the successes of Malharáv in the field. Rávji offered to subsidize five European battalions, and Governor Duncan took upon himself the responsibility of sending an auxiliary force of 1600 men under Major Walker to act with the troops of Rávji and Babáji north of Ahmedábad. Reinforcements were afterwards sent up, but the campaign was not closed till April 1802, when the fort of Kadi had been taken by storm. Malharáv surrendered and a residence in Nadiad was assigned him with a liberal pension out of the revenues of that subdivision. The fort of Sankheda, which had been held by Ganpatiráv Gaikwár for his cousin Malharáv, was soon after this reduced and the country for a time pacified.

The British and  
the Gaikwár,  
1800.

In March Rávji had an interview at Cambay with Governor Duncan, which was followed on June 6th by a definite treaty, of which the groundwork had been previously sketched in anticipation of the reduction of the revolted Gaikwárs. Two thousand men, besides artillery, were to be subsidized and, a *jámlád* or assignment for their payment was made on the revenue of Dholka and the part of Nadiad not assigned to Malharáv. Chikhli was given to the British in reward for their aid in storming Kadi, and Residents were to be appointed reciprocally. A large sum of money was borrowed by Rávji, partly from Bombay partly from Baroda bankers, to pay off the arrears due to about 7000 Arab mercenaries, who had usurped a great deal of objectionable influence in civil affairs at the Gaikwár's

capital. Major Walker was appointed Resident and proceeded to Baroda on 8th June.

On the same day was signed a secret compact assuring Rájvi of the support of the British Government and awarding him a village out of the territory ceded by the treaty of June 6th. It was deemed advisable by the British Government to have at the Baroda court some leading personage who might, in the present state of the relations between Bombay and Poona, further the designs of the former government in preventing a recurrence of the coalition of Maratha powers. Rájvi was sure of his reward if he served British interests, whilst in case of the reorganization of a Marátha confederacy the state he was administering would probably play but a very subordinate part in subsequent events.

The treaty of June 6th was disapproved by the Court of Directors as being in direct contravention of the treaty of Salbai. Before, however, any orders had been issued by the Home authorities to restore to the Gaikwár the territory he had ceded, the Peshwa, out of regard for whom the treaty had been disavowed, was a fugitive before the army of Holkar, and by December had ratified these very concessions at the treaty of Bassin. By this treaty the Peshwa virtually placed his independence in the hands of the British. He ceded his share of Surat, thus giving them sole control over that district. In payment of the subsidiary force required he handed over territory in Gujarát, the revenue of which amounted to 12,28,000 rupees, and finally he constituted the British Government arbiter in the disputes between his government and that of Baroda. The grants made by the Gaikwar for the support of the subsidiary force amounted in 1802 to 7,80,000 rupees.

Major Walker attempted to negotiate with the Arab guard, but the greater part of them flew to arms and released Kánhoji Gaikwár. The latter then tried to collect an army near Baroda, and succeeded in obtaining possession of the person of Anandráv the titular ruler. The British force then took Baroda by storm, after which most of the Arabs submitted, except a few who joined Kánhoji. The rest took the arrears due to them and left the country. Kánhoji was not subdued till February 1803. Malháráv meanwhile had broken out in rebellion in Káthiávada and was plundering the Marátha possessions there. Bábaji Appáji and a young officer named Vithal Deváji (or Divánji) led the operations against him; and to the latter belongs the honour of having captured this troublesome member of the ruling family. The estate of Nadiád, which had been assigned to Madhavráo by Govindráv, was resumed by Rájvi Appáji and made over in its entirety to the British Government. A treaty, supplementary to that of 1802, was drawn up guaranteeing this cession as well as the *inám* or free gift of the fort and district of Kara, "out of gratitude for the support given in the recent troubles to the Gaikwár's honour and for assistance in securing the good of the State."

THE  
MARATHAS,  
A.D. 1760 - 1810.

The Gaikwár's  
Minister Rájvi.

Treaty of Bassin,  
31st Dec. 1802.

Arabs  
Disbanded.

Malháráv  
in Revolt,  
1803.

THE  
MARATHAS,  
A.D. 1760-1819.

Contingent  
Strengthened,  
1803:

Death of Rāvji,  
1803.

War with Sindia.

The Revenue  
Collecting  
Force.

Very soon after this agreement Rāvji applied for an addition to the subsidiary force, in payment of which he assigned Mātār Muhadhia and the customs of Kim-Kathodra, a station about seventeen miles north of Surat. His reason for strengthening the subsidiary force appears to have been that owing to the reduction of the Arabs, his own force was not enough to guard even the frontier, and that a great part of that duty fell on the European contingent, which was numerically insufficient for service on so extended a scale. This was the last public act of note on the part of Rāvji Appa, who died in July 1803, after adopting one Sitārām to succeed to his estate.

Whilst these arrangements were being carried out at Baroda, Bājirāv Peshwa, chafing at the dependence to which his straits of the previous winter had reduced him with regard to the English, was actively propagating dissension between Sindia and the Calcutta Government. Not long after, the war that had been some time imminent broke out, and a contingent of 7352 men from Gujarāt was ordered to the field. In August or September Broach and Pāvāga<sup>1</sup> both fell to the British.

Under the treaty of Sirjē Anjangaon in December 1803, both Pāvāga and Dohad were restored to Sindia, but Broach remained British. By this means one of the rising Marāṭha powers was extruded from the centre to the outlying portion of the province. The employment of all the British contingent against Sindia's possessions in Gujarāt precluded Major Walker from furnishing any portion of the army that was annually sent to collect the tribute in Kāthiāvādā. Rāvji Appaji had expressly stipulated that some part of the contingent might be so used when it could be spared from its main duties. The Supreme Government agreed to the proposal when made by Governor Duncan, on the grounds of the advantage both to the Gaikwār and the tributaries of employing on this disagreeable duty a strong and well-disciplined force. Already some of the tributaries had made overtures to Major Walker with a view to obtaining British protection against powerful neighbours. Governor Duncan was in favour of accepting the duty of protection and also of helping the Gaikwar's commander in his expeditions through the peninsula on these grounds. Firstly, the officer in command could exercise a certain supervision over the collections in which the British as part assignees had a direct interest. Secondly, a way could thus be opened for the acquisition of a port on the coast from which the intrigues, supposed to be carried on by agents from the Isle of France, could be watched and counteracted. From such a point, too, the views of the Bombay Government as regards Kachh could be promoted. Thirdly, the commandant could take steps to improve the system of forcible collections, and towards abolishing the barbarous features of this rude method of levying tribute. He could also, perhaps, suggest some system by which the advantages of all three parties concerned would be better secured than by reliance on the uncertainty of temporary expeditions. The fourth and last

<sup>1</sup> A celebrated hill fort south of Chāmpāner in the Panch Mahāls district.

reason given savours strongly of the Maráthá policy of the time, of which the leading maxim was *Divide et impera*. It was represented that Bábháji, who had successfully collected the tribute during 1802-03 and whose subordinate and companion Vithal Deváji was a person of similar energy and capability, might possibly acquire too great influence if left in a quasi-independent command at such a distance from the Court. It was politic, then, to join with the force under his command a strong foreign body, thus dividing both the power and the responsibility. The war with Sindia caused these proposals to fall into abeyance for some time.

Meanwhile the Resident at Poona was doing his best to secure for the Gaikwár a further lease for ten years of the farm of the Peshwa's dominions in Gujarát, so that the inconveniences of dual government might be avoided. In October 1804 a ten years' farm was granted in the name of Bhagvantráy Gaikwár at an annual rate of 4½ lakhs of rupees.

This grant led to the consolidation of all previous engagements into a single treaty, which was signed in April 1805. Previous agreements were confirmed and the whole brought into consonance with the treaty of Bassein. Districts yielding 11,70,000 rupees per annum were made over for the support of the subsidiary force, and arrangements were also made for the repayment of the cash loan advanced by the British Government in 1802, when the liquidation of the arrears due to the Arabs was a matter of urgent political necessity. The British contingent was to be available in part for service in Káthiaváda, whenever the British Government thought such an employment of it advisable.

Finally, the British Government was constituted arbiter in all disputes of the Gaikwár, not alone with foreign powers, but also in the adjustment of his financial transactions with the Peshwa his paramount power. These transactions, which ranged back from the capture of Dámáji in 1751, had never been the subject of a formal investigation, and were by this time complicated by the numerous engagements with third parties into which both governments had been obliged to enter at their various moments of distress. Bápiráy, who was apparently intriguing for a Maráthá coalition against his new protectors, was careful not to bring before the notice of the chiefs, whose esteem he wished to gain, a provision which exhibited him as in any way dependent upon the arbitration of a foreign power. He therefore granted the farm for ten years to the Gaikwár, as much by way of remanding for a time the proposed inquiries and settlement of their respective claims as for the purpose of diverting the attention of the British to the administration of this new appanage, whilst leaving him free scope for his intrigues in the Dakhan. He used, moreover, every pretext to defer the consideration of the Gaikwár question until he could make use of his claims to further his own designs. His success in preventing a discussion of these transactions is apparent by the fact that in the financial statement of the Gaikwár's affairs made by Colonel Walker in 1804, no mention of the Poona demand is to be found.

THE  
MARATHÁS,  
A.D. 1760-1819.

Renewal of  
Farm,  
1804.

The British and  
the Gaikwár,  
1805.

THE  
MARATHS,  
A.D. 1760 - 1819.

No important event took place during the next year or two. Bābāji relinquished the command of the force in Kāthiāvāda in favour of Vithalrāv Devāji, whilst he himself took part in the civil administration at Baroda. The Resident, too, seems to have been likewise engaged in internal matters and in securing the country against an invasion by Kānhoji, now a fugitive at the court of Holkar.

1807.

In 1807 the Resident made over Aba Shelukar, late Sar Subhedār of the Peshwa, to the British Government, by whom he could be prevented from engaging in fresh conspiracies. After this Colonel Walker was at last enabled to leave Baroda in order to assist in the settlement of the Kāthiāvāda tribute question, an object he had long had in view, but which the necessity for his continuous presence at the Gāikwār's capital had hitherto prevented him from undertaking.

Kāthiāvāda  
Tribute.

The changes with regard to the collection of the tribute from the chiefs of Kāthiāvāda that were carried out in 1807 deserve a special description. Firstly, they placed the relations of the tributary to the paramount power on quite a new basis. Secondly, by them the British influence over both parties concerned was much increased and the connection between the governments of Bombay and Baroda drawn closer. Thirdly, they were subsequently, as will be seen hereafter, the subject of much discussion and delay in the settlement of the questions at issue between the Peshwa and the Gāikwār. And lastly, their effect was most beneficial to both the chiefs and their subjects in removing the uncertainty that had hitherto pervaded the whole revenue administration of Kāthiāvāda.

Before entering on the details of the settlement itself, some description is necessary of the social and political state of the peninsula at the time the changes were introduced.

State of  
Kāthiāvāda,  
1807.

The greater part of the population of Kāthiāvāda consisted of two classes, chiefs and cultivators, called Bhamnās and ryots. The power of the chief ranged from the headship of a single village up to absolute jurisdiction over several score. The ryots were usually tenants long resident in the province. The chiefs were in almost every case foreigners, invaders from the north and north-east, Muhammadan adventurers from the court of Ahmedābād. Kāthiās animated by the love of plunder and cattle-lifting; and Mīnās and Vāghelās who had settled on the coast on account of the facilities it afforded for their favourite pursuits of wrecking and piracy. More numerous than any others were the Rājputs, driven south by the disturbed state of their native kingdoms or by the restless spirit of military adventure to be found in a class where one profession alone is honourable. There is a certain uniformity in the building up of all these chieftainships. A powerful leader, with a sufficient band of followers, oppressed his weaker neighbours till they were glad to come to terms and place themselves under his protection, so as both to escape themselves and to take their chance of sharing in the plunder of others. It frequently happened in the growth of one of these states that the *bhāyād* or relations of the chief (who are sure to be numerous in a polygamous society) were influential enough to assume, in their turn, a partial independence and to claim recogni-

tion as a separate state. As a rule, however, they continued to unite with the head of the family against external foes, and only disagreed as to domestic administration. It is also noticeable that though so addicted to the profession of arms, the Rajputs cannot be called a military race; they possess few of the true military virtues; hence the slowness of their advance, and their failure in competition with perhaps less courageous though more compact and pliable races. In Kāthiāvāda fortified strongholds, formidable enough to an army moving rapidly without siege trains, arose in all directions, and even villages were surrounded by a high mud wall as a protection against cattle-lifters.

The groundwork of these states being itself so unstable, their relations with each other were conducted on no principle but the law of the stronger. General distrust reigned throughout. Each chief well knew that his neighbours had won their position as he had won his own by the gradual absorption of the weaker, and that they were ready enough whenever opportunity offered to subject his dominions to the same process. The administration of his territory consisted merely in levying, within certain limits sanctioned by long usage, as much revenue as would suffice to maintain himself and his forces in their position with regard to the surrounding states. When a foreign enemy appeared there was no co-operation amongst the local chiefs in resistance. It was a point of honour not to yield except to a superior force. Each chief, therefore, resisted the demands made upon him until he considered that he had done enough to satisfy the family conscience and then, agreeing to the terms proposed, he allowed the wave of extortion to pass on and deluge the domains of his neighbour. It should be remembered that the peninsula had never been subjugated, though overrun times innumerable. The evil of invasion was thus transitory. To a chief the mere payment of tribute tended in no wise to derogate from his independence. In his capacity of military freebooter he acknowledged the principle as just. His country had been won by the sword and was retained by the sword and not by acquiescence in the payment of tribute, so that if he could avoid this extortion he was justified in doing so. If he weakened his state in resisting foreigners he knew that his neighbours would certainly take advantage of the favourable juncture and annex his territory. It was his policy therefore, after resistance up to a certain point, to succumb.

Owing to this local peculiarity and to the general want of union in the province, both the Mughals and Marathas found it advantageous to follow a system of successive expeditions rather than to incur the expense of permanently occupying the peninsula with an army which would necessarily have to be a large one. There is every reason to believe that in adopting the raid system the Musalmāns were only pursuing the practice of their predecessors, who used to take tribute from Jodhpur to Dwārka.

Some of the subhedārs of Ahmedābād divided their tributary district into three circuits of collection and personally undertook the

THE  
MARATHAS,  
A.D. 1760 - 1890.

State of  
Kāthiāvāda,  
1807.

The Revenue  
Raid System.

THE  
MARATHAS,  
A.D. 1760-1810.

The Revenue  
Raid System.

charge of one each year. This was the *mulakgiri* Land-raiding system. Besides this chief expedition, there was the smaller one of the Babi of Junagadh and the still more minute operations of the Rával of Bhávnagar against some of his weaker neighbours. The great Ahmedabád expedition had long been an annual grievance and was conducted with some show of system and under special rules called the *raj-ul-Mulak*. Three of these rules are of importance, and seem to have been generally acquiesced in before the great incursions of Babaji and Vithalráy at the beginning of the nineteenth century. The first was that the paramount power (by which was meant the foreign government which was strong enough to enforce tribute from all the chiefs) had authority to interfere in cases of dismemberment, or in proceedings tending to the depreciation of the revenue, or to the dismemberment of any tributary state. It was again an acknowledged rule that whilst the mulakgiri expedition of the paramount power was in motion no other army should be in the field throughout the whole province. The third provision was not so well established, but it appears to have been understood that the tribute from each state should be regulated by some standard of former date. In practice, however, the measure of the Marátha demand was simply the power to enforce payment.

It is worthy of remark that about the beginning of this century the resistance to the collection of tribute was stronger towards the west than in the east and south of the province. In the Mahi Kántha the lawlessness of the Koh chiefs, who had established themselves in the ravines and on the hills, necessitated the employment of a military force for collections. In the neighbourhood of Bijápúr and Káthi, the chiefs would not pay tribute except under the compulsion of a siege or raid, but the mulakgiri system only reached its full development west of Dholka.

From these explanatory remarks the system and practice of the Maráthas can be clearly understood.

The Maráthas  
in Sorath.

The Maráthas found their way to Sorath very early in their Gujarát career. The first raid probably took place about 1711, when the Muhammadans were occupied near Ahmedabad. After this incursions were frequent, and under Damáji Gákwár became, as has been seen above, annual. This leader did more. He took to wife a daughter of the Gohil chief of the small state of Látli in east central Káthiáwada, whose dowry in land gave him the standpoint he sought in the heart of the peninsula. He managed also to secure his position in what are known as the Amreli Maháls, probably under the force of circumstances similar to those which caused the weaker Rajputs to gravitate towards the stronger of their own tribe. His expedition through the peninsula, generally as near the time of harvest as possible, was made regularly every year as soon as he had amassed a sufficient number of troops on the mainland to admit of a force being detached for mulakgiri. The object of these inroads was plunder, not conquest; the leaders would readily have entered into negotiations for the payment of the tribute had the chieftains been disposed to treat otherwise than after defeat. The expenses

of such an army were heavy, and the more so as the time during which it would be in the field was quite indefinite, and dependent entirely upon the amount of resistance offered. In more than one instance the Maráthá leaders, who usually had no artillery for a siege, were obliged to regularly beleaguer a town. Early in this century the town of Mála successfully defended itself against a remarkably well equipped force under Bábáji, and the Junágadh state was usually avoided by the Maráthás as much as possible on account of the time it would take to reduce its army to terms.

It is not on record that the mulakgiri force habitually devastated the country over which it passed, or caused much greater hardships to the ryots than are inseparable from the passage of an army in the field. There are, however, well authenticated stories of the depredations and damage committed during these expeditions. A village is said to have been deserted by order of the *blumia* in order that the timber of its houses might furnish fuel for the Maráthá army on its march. Tortures were doubtless inflicted on men supposed to be well off, who were suspected to have hidden their property. A Maráthá army was usually, if not always, ill disciplined, as is proved by the testimony of Mr. Forbes, an eye witness of the campaigns of 1773<sup>1</sup>. From the same writer it is learned what an immense proportion the camp followers bore to the actual combatants. If this were the case in a real campaign against a formidable and active enemy, it is likely that the irresponsible element was still larger in an expedition like this of mulakgiri, where the enemy was insignificant and the country at the mercy of the invaders. It is probable therefore that the troops have been credited with misconduct that should in point of fact be attributed to these Pindhars. In after years, when the expeditions were conducted systematically, villages on the line of march were always allowed the alternative of entertaining a pioneer or two as a sort of guarantee. If no *bondhari* of this sort were accepted, the army occupied the place. In many cases the demands for supplies made by these pioneers were so exorbitant that the villagers preferred to compound in turn with them also for their absence. Another method by which a chieftain might avoid the necessity of the army's passing through his territories was by sending to the commander of the expedition an envoy empowered to treat for the amount of tribute and to execute a provisional guarantee for its future liquidation. This deed was destroyed on the subsequent confirmation by the chief himself of the agreement for the sum fixed.

This habit of taking securities in all engagements was so prevalent in all parts of the province, and played so prominent a part in the financial administration of the Gáikwár's home and tributary domains, that its main features are worth describing.

It is a well known characteristic of Hindu dealings that no transaction is carried on by two parties alone if a third can possibly be dragged in. This practice no doubt originated in the former insecure

THE  
MARATHAS,  
1760-1819.

The Maráthás  
in Sorath

Securities.

<sup>1</sup> Oriental Memoirs.

THE  
MARVATHAS,  
A.D. 1760-1819.

Securities.

state of society when no man considered himself safe in person or property from government on the one hand and his neighbour on the other. With classes like Kolis and predatory Rajputs, the feeling is intelligible enough, and from these it spread into other branches of the society. To such a pitch was distrust carried in the early part of the nineteenth century, that the Gaikwár himself could find no one to enter into a contract with him without the guarantee of one of his own subjects. The consequences of this practice and the power it threw into the hands of the Arab mercenaries, who were the principal securities for the public debts, are matters that touch the history of the Baroda State rather than that of the province. The chiefs in their dealings employed a special sort of security which owed its validity not to political consideration like that of the Arab Jamádárs but entirely to its religious and traditional character.

Bhāts and  
Chārāns,  
1807.

A society of the military type like the Rajput has a tendency towards caste and privilege. Without a leader the warlike instincts of the tribe would not carry them beyond petty robberies; whilst with a leader they can achieve greater exploits of valour and destruction. The successful chief then is idolized, and after a certain stage the privileges of the chieftainship become hereditary. Once this system is established, the celebration of ancestors follows, and when circumstances are favourable to the perpetuation of the hereditary position, the genealogy of the chief is a matter of the highest importance, and the person entrusted with the record of this is vested with peculiar sanctity. It is the genealogist's duty to enter in the record, not only the direct line but the names of the more distant relations of the chief by whom he is retained, and also to be the continual chanter of the glorious deeds of their common ancestors. He is therefore a referee of the highest authority in questions of pedigree or of the partition of inheritance. An injury to his person might entail the loss of the pedigree of the ruling family (especially as many of the bards kept no written record) and thus produce a misfortune which would be felt by the whole tribe. The chief, being a warrior, must take his chance in the field with the rest, but the person of the genealogist was sacred and inviolable. Amongst the Rajputs the greatest reverence was paid to purity of pedigree, and each principal family had its Bhāt to record births and deaths amongst its members and to stimulate pride in their lineage by the recital of the wars and exploits of their ancestors.

These Bhāts necessarily multiplied beyond the number of the families that could entertain them, so that many took to banking and some to cultivation. Surrounded as they were by the social system of the Hindus, it was not long before they became differentiated into a distinct caste, and the inviolability of their persons, formerly due only to respect for the pedigree, was now extended to the whole tribe, even though a large proportion of it performed none of the duties of genealogists. Similar to the Bhāts in many respects, notably in that of sacredness of person, were the Chārāns, numerous in Kāthiāváda, where they had founded villages and lived as ordinary

cultivators. This tribe also claimed divine origin like the race whose annals they had the privilege of recording. It is said that Rájá Todar Mal, the celebrated minister of the Dehli empire, was the first to introduce the practice of taking these Bháts as securities for the Rajputs. The assertion is possibly true, but rests merely on tradition, and after ages usually find some great man as a sponsor for all such innovations. It is clear however that for many years before 1807 no dealings of Kolis or Rajputs with the state or with each other took place without the security of a Bhát being taken. This practice seems to have been as prevalent on the mainland as in the peninsula, the Kolis having doubtless borrowed it from their Rajput neighbours after the Bháts had become a separate caste.

Under this system the Bháts acquired considerable wealth, as they usually demanded a percentage on the amount for which they became security. There are instances in which they presumed upon the strength of their engagements and sacred character to bully or dictate to their employer. Such was the case of the Rával of Bhávnagar in 1808, which is also interesting in another way, as showing how the spirit of industry and commerce tends to sap the old observances which have their roots in superstition. This chief engaged in trade, fostered merchants, and increased his revenue. When his security, a Bhát, got troublesome and interfering, he applied to the power to whom he paid tribute to have the old security bond cancelled and a fresh one taken on his own personal responsibility. In doing this, he seems to have been prompted by nothing but his appreciation of the modern code of commercial honour.

To return to the *mulakgiri*. The tribute for which preliminary security had been taken seems to have fluctuated from year to year, but always with reference to a fixed standard. It was one of the Maráthá rules never to recede from a former demand lest they should be thereby setting up a precedent for future years. They preferred to secure a year or two's arrears at the full rate to the payment of all the arrears due at a reduced rate.

In spite of this fiction of a settled *jama* or tribute, the Maráthás, when they had a sufficient force at their back, invariably demanded a larger sum, the excess being called *kharrá-ját* or extra distinct from the actual tribute. This ingenious plan of increasing the collections originated, it is said, with Shivrám Gúdi, and was carried out scrupulously by both Babáji and Vithuráv in their tours. In fact during the last few years of the old system Vithuráv had so good a force with him that the extra demand formed a large proportion of the whole tribute collected and had been paid only under strong protest. The British had not long been established in Ránpur, Gogha, and Dhandhuka before a few petty chiefs of Gohilvád and Sorath applied to the Resident at Baroda for protection against the *mulakgiri* of the Nawáb of Júnághar and the Rával of Bhávnagar, offering to cede the sovereignty of their states to the British on condition that certain rights and privileges were preserved to the chiefs and their families. The conditions they named were not such as were likely to meet with the approval of the British Government, and do

THE  
MARATHÁS,  
A.D. 1760-1819.

Bháts and  
Chárans,  
1:07.

British  
Intervention.

THE  
MAULAKIRI,  
A.D. 1760 - 1819.

British  
Intervention.

Settlement  
of 1807.

not seem to have received much consideration. The proposals had, however, the effect of drawing the attention of the Bombay Government towards the state of Kāthiāvāda, and permission to and the mulakgiri of the Gānkwar by detaching a few companies of British troops was accorded by the Supreme Government. The outbreak of hostilities with Sindia led to the whole question as to the best means of collecting the tribute being for a time deferred. The internal disputes of some of the more turbulent states, a few years afterwards, gave the Resident an opportunity of sending an envoy to one or two courts to see how matters stood, and to open a way for a settlement in conjunction with the Gānkwar. Affairs at Baroda, as mentioned above (page 116), detained the Resident there till 1807, in which year he joined Vithalrāv's army with a British contingent, at a place in the Morvi state.

Before treating directly with the chiefs a circular was sent round to all of them both by the Gānkwar's agent and by Colonel Walker the Resident, containing the basis of the proposals with regard to the tribute about to be submitted to them. The position of the British Government throughout this negotiation is not clearly defined. Vithalrāv in his circular mentions indeed that a British force was with him, but urges the chiefs to come to a settlement entirely with the government he represented. Colonel Walker's note was longer, more explicit, and conciliatory, but at the same time assumes a tone of protection and superiority. The replies of the chiefs were various, and, as a rule, seem to show that they regarded the British Government as the chief mover in these negotiations. They were probably aware of the position in which the engagements of the Gānkwar had placed him with reference to the British, and for some years had had the latter as their neighbours in the east of the peninsula. They were therefore not able at once to take in the whole scope of the action of the British Government in the tribute question.

Many seemed to take the note as a preliminary to a mulakgiri on the part of the East India Company. The Rāja of Mālia, who had just been causing disturbances in the dominions of all his neighbours, had repulsed Bābāp and permitted the self-immolation of a Bhāt rather than fulfil an engagement, openly proposed a joint expedition across the Rān to plunder Kachh and Sindh. From the inquiries made by the Resident and from information gathered from the Gānkwar's accounts, it was anticipated that separate engagements need only be entered into with the twenty-nine chiefs to whom the circular invitation had been issued, provided that the rights and interests of subordinate members of the Bhāyād were clearly defined in the agreement. When, however, these rights came to be investigated in the light of the peculiar rules of Rajput inheritance, it was found that no less than one hundred and fifty-three persons had a claim to settle independently of each other for their tribute. This greatly prolonged the settlement, but at last the agreements were all framed on one principle. The amount settled was determined by a close scrutiny of the collections of past years, and Colonel Walker found it advisable to make great

reductions in the item of extras or *kharújât*, for which the later Gáekwár collectors had such predilection. The engagements were of the following nature.

First, the chief bound himself his heirs and successors to pay at Baroda each year the tribute fixed in perpetuity in 1807. He also procured a counter security for this payment who engaged himself in this capacity for ten years. The Honorable Company's government had then to become security on the part of the Gáekwár for the fixity of the tribute demanded. This participation of the British in the engagement was insisted upon by the chiefs, and in all probability Colonel Walker was not averse from admitting it. Having thus arranged for the payment of the tribute and guaranteed the amount to be demanded, it was proposed to take measures to prevent internal quarrels between the chiefs themselves. The object of a fixed settlement was simply to remove the necessity for overrunning the country from time to time with an irregular army and to protect the chiefs against extortion. It was found that if the army of the paramount power were removed, all means of keeping order in the province would be lost, and the internecine feuds of the chiefs would soon destroy the good effects of the permanent settlement by materially altering the then existing position of the weaker feudatories and rendering them unable to pay the tribute. It was also the wish of the British Government to bring about such a state of things in Káthiávada that the presence of an army to control the chiefs would be wholly uncalculated for and that the chiefs themselves would co-operate to keep order and maintain the permanent settlement.

A second agreement therefore was called for from each signatory state of the nature of a security for good and peaceful conduct. The counter security to this was usually that of another chief. This bond was perpetual. On the execution of both these engagements the chief received a *pirvina* or guarantee that the Gáekwár government would not take from him more than the tribute agreed upon, and to this deed the countersignature of the Resident on behalf of the British Government was affixed. This guarantee, like the promise of the chief himself, was apparently given in perpetuity. It will be noted that the amount of tribute was fixed permanently, but that it was considered advisable to renew the security every ten years. It is also remarkable that, except in the *fulzómán* or bond for good behaviour, the name of the Peshwa's government, the rights of which over the tribute had only been temporarily alienated, does not appear. The total amount of the tribute thus settled was Rs. 9,75,882.

By means of these engagements the relations of the tributaries to their paramount power were made a matter of contract, instead of as heretofore a series of uncertain and arbitrary exactions dependent upon the respective means of coercion and resistance.

Seven years of the lease granted to the Gáekwár in 1804 by the Peshwa still remained unexpired and during at least six of these

THE  
MARÁTHAS,  
A.D. 1760-1819.

Settlement  
of 1807.  
*Financial.*

*Political.*

Peshwa's Share  
in Káthiávada.

THE  
MARÁTHÁS,  
A.D. 1760-1819.  
Peshwa's Share  
in Káthiáváda.

the arrangements that had been made about the Káthiáváda tribute do not seem to have been officially communicated to the Peshwa's government. It was not until 1815, when the Resident at Poona was trying to procure the renewal of the lease for the Gaikwár, that an account of the settlement was drawn up in a draft agreement which the Resident submitted to Bájiráv. In this draft the curious mistake was made of mentioning the settlement instead of only the security bond as decennial. The Peshwa, whose policy was to protract negotiations, submitted in his turn a second draft which he said he was willing to sign. In this he seized at once on the supposition that the tribute was fixed only for ten years and stipulated for an increase at the expiration of that period. He also demanded that certain extra collections should be refunded by the Gaikwár, and assumed the British Government to have become security for the tribute owed by the chiefs to his own government.

It was evident that no accord would be reached on the lines of either of these draft agreements as they stood. Before others were prepared, Gangádhár Shástri had been murdered and the treaty of June 1817 was a completed act, leaving further negotiations unnecessary.

Later  
Arrangements.

Meanwhile the tribute since the expiry of the farm of 1804 had been collected by a joint British and Gaikwár expedition, for it was found that partly from their own disputes and partly owing to the instigation of the agents of Bájiráv, the chiefs were little disposed to act up to the engagements of 1807, either with respect to tribute or good conduct. The Peshwa, whose interference in the affairs of the peninsula had been constantly discouraged, declined to trouble himself to collect the tribute, the responsibility of which he asserted rested entirely upon the British and Gaikwár governments. He subsequently ceded the tribute to the British Government on account of military expenses. After his fall in 1819 his territories, including the rights in Gujarát, fell to the British Government, and in 1820 the Gaikwár arranged that the whole of the Káthiáváda tribute, except that due from the districts directly subordinate to Baroda, should be collected by the agency of the British.

The  
Mahi Kántha

Turning to the events on the mainland, we find that soon after Colonel Walker's return from the Káthiáváda expedition, he introduced the Káthiáváda tribute system into the Mahi Kántha, in spite of the opposition of Sitárám Rávji and the anti-English party in the Darbár.

Supplementary  
Treaty,  
1808.

The territory ceded for the payment of the British contingent in 1805 was found to yield less revenue than had been anticipated, so in 1808 a treaty supplementary to the consolidating one of 1805 was drawn up, allotting additional assignments amounting to about 1,76,168 rupees to the British. This revenue was derived partly from alienated villages in Nadiád, Mahudha, Dholka, Mátar, and near the Ranjar Ghát. The *ghásdúna* or tribute of Bhávnagar was also made over by this agreement. With regard to this latter

acquisition, it is to be noticed that the agreement is drawn up in the name of the Honourable Company alone and not in that of the British Government on account of Anandráv Gáikwár. It also differs from other engagements of a similar nature in containing a provision against the contingency of future irregular demands being made by the Peshwa's army. The reason for this distinction is evidently that the Bhávnagar contribution was not part of the Káthiáváda revenue farmed to the Gáikwár by Bápráy, and was thus not divisible on the expiration of the lease. The right to this tribute rested with the British by virtue of the previous cession of Gogha, of which sub-division the fifty nine villages of the Bhávnagar Bhayád formed part.

Next year the Okhámandal chiefs, who had not come under the settlement of 1807, were driven to engage not to continue their piratical depredations along the coast, and to admit one Sundarji Shrivji as Resident on behalf of the British Government. The Gáikwár government then, too, seems to have become their counter security, an arrangement which led to misunderstandings a short while afterwards.

In 1811, some disturbances in Navánagar and Jmúgadli and symptoms of discontent in Okhámandal took the Resident from Baroda into the peninsula with part of the British contingent.

The Jám of Navánagar had got involved in pecuniary transactions with the Ray of Kachh, and the British Government had mediated with a view of arranging for the repayment by gradual instalments. The Jám, however, repudiated all the engagements of 1807 both as regards the debt and the tribute, ejected the Gaikwar's agent from his dominions, and prepared for war. He also began to invite the neighbouring chiefs to join in sweeping out the paramount power from the whole of Káthiáváda. It was not till after a considerable show of force that he laid down his arms and came to terms. Captain Carmac, the Resident, got him to submit the Kachh claims to the arbitration of the English Government, and after fixing them at Rs. 4,33,830, Captain Carmac made an arrangement similar to that originally intended.

There remained the question of a disputed succession in Jmúgadli. Bahádur Khán, son of a slave girl, was put forward in opposition to a younger aspirant, Salábut Khán, reputed to be the son of a lady of the Rádhanpur house. The Baroda government with the concurrence of the Resident had admitted the claims of the latter. On a report, however, by the Assistant Resident in Káthiáváda, Captain Carmac was induced to alter his opinion and to support Bahádur Khán, on the grounds that Salábut Khán was a spurious child, and that Bahádur was ready to make concessions of value to the Gáikwár government. The Bombay Council, however, disavowed all countenance of the claims of Bahádur Khán, and the matter was let drop.

In the year 1812 the Gaikwar had paid off the pecuniary loan borrowed in 1803 from the British Government, but there still

THE  
MARATHAS,  
A.D. 1760-1819.

Okhámandal,  
1809.

Disturbances in  
Káthiáváda,  
1811.

1812.

THE  
MARÁTHAS,  
A.D. 1760-1819

remained the debts for which that government had become *bhandári* or security in place of the ejected *jamádúrs* of the Arab force. These claims could not be paid off for at least two years longer, so that for that period the Resident was ordered to maintain the same close supervision of Baroda affairs as heretofore.

1813-14.

The next two years were spent chiefly in discussions with the Poona government about the old claims by the Peshwa on the Gáikwár's estate. There is no doubt that at the time of his death, Dámáji had not paid up nearly all that he had bound himself in 1753 to pay. On the other hand there had been at least six intermediate compacts between the Peshwa and various members of the Gáikwár family. Amongst others was that of 1768 fixing the arrears of the previous three years, that of 1778 and of 1781, by the tenth clause of which Páchsingh was excused payment of arrears for the time during which he was engaged in hostilities against Rághobá. Then came the agreement with Govindráv in 1797, to which a sort of debit and credit account is appended.

Peshwa Intrigue  
in Baroda,  
1814.

The Peshwa had been content, for reasons that have been shown above, to let these claims lie dormant during the currency of the ten years' farm. But, as the question of the renewal of this agreement became imminent, he gradually opened more frequent communications with the Baroda council, using these claims as a pretext for sounding the disposition of the chief officials and ascertaining their feelings especially towards the British Government. When the negotiations for the settlement of these claims were fairly set on foot, he used every possible means to protract them till he had finally decided what he should do in 1814, when the Ahmedábad farm expired.

It was easy for Bájráv to discover who were the malcontents at the Baroda Court. Sitánám, the adopted son of Rávjí Appáji, having been found both incompetent and untrustworthy in the management of affairs, had been practically removed from any post of influence in the council, and was moreover chafing at the refusal of the British Government to recognize him in the same way as they had done his father. He had also been superseded as Suba of Káthnáváda by Vitbalráv Deváji. Under these circumstances, and finding that he had the support of a large number of the older court party against the authority of the Resident and of his native agent, he either himself opened communications with Bájráv or readily listened to the counsels sent to him direct from Poona. Before long, agents were sent to the Peshwa's Court by Tukhtái, wife of Anandráv, with instructions, it is supposed, to thwart all the proposals and designs of Gangádhár Shástri, who had been recently sent as envoy by the Gáikwár council of administration. The chief obstacle to the settlement of the Peshwa's claims was the counter-demand made by the Baroda government on account of Broach, which had been disposed of without the Gáikwár's consent, and also on account of the damage caused by the inroads of Ába Shelukar, when accredited agent of Bájráv in Gujarát.

There is no need to detail here the events that took place in Poona during these negotiations. On the expiration of the farm in 1814,

Bájrav appointed Trimbakji Dengle Sarsuba of Ahmedábád. The latter, however, did not leave Poona, where his presence was indispensable to his master, but sent agents with instructions rather of a political than of a fiscal nature. He himself undertook the task of disposing of Gangádhār Shástri, whom he caused to be assassinated at Pandharpur in July 1815.

Meanwhile the Jám of Navanagar had died leaving a disputed succession. The chief's Khavás or family slaves, instigated probably by agents from Ahmedábád, began to usurp the government, and the whole question was submitted by the Darbár to the Peshwa as being lord paramount. The Ahmedábád commander sent a body of two hundred cavalry to Navanagar, but before they could arrive, the Khavás' revolt had been quelled by a British force detached from the contingent. They therefore dispersed through the province inciting discontent and revolt amongst the Jíts and Káthis. In Kaira they instigated a tribe of Kóhs to attack the British lines by night. Sitáráma Rávji's adherents also collected a force at Dhár, a state well-known for lending itself for such purposes, and kept the frontier in confusion. Severe measures at Poona and Baroda soon put an end to this state of things, and at last Trimbakji Dengle was surrendered to the British Government to answer for his share in the murder of Gangádhār Shástri. The discussion of the Gáikwár's debts, however, was carried on all through the year at Poona, whilst Bajirav was maturing his then vacillating plans for extirpating the British from the west of India.

In 1816 the chiefs of Okhamandal again betook themselves to piracy. Their territory was occupied by a British force. It will be remembered that in 1809 the Gáikwár's government had become counter-security for these chiefs, but owing to the distance of the district from a military post, the Baroda authorities found themselves unable to spare troops enough to put a check on the misconduct of their tributaries. In A.D. 1816, at the time of occupation, the Bombay Government informed the Baroda administration that they had no wish to permanently establish themselves at so distant a spot, which contained, moreover, a much frequented shrine of Hindu worship, and that they were willing to put the Gáikwár in possession if he would engage to keep up a sufficient force in the district to protect the neighbouring ports and shores from the pirates and wreckers that infested the island of Dwárká and the adjoining mainland. The Bombay Government made a point of asserting on this occasion, in opposition apparently to some proposal by the Baroda Darbár, that they could not admit that the mere fact of having become security or counter-security gave any preferential right to the possession of the country. Finally, the Gáikwár government agreed to the condition proposed, and the district was made over to them.

In the same year (A.D. 1816) British aid was invoked by the Nawáb of Junágadh who was oppressed by a too powerful minister, backed by the Arab mercenaries. After a settlement of this dispute had been satisfactorily brought about, the Nawáb, in gratitude, waived his rights to tribute over the territories recently ceded to

THE  
MARATHAS,  
A.D. 1760-1819.  
Peshwa Intrigue  
in Baroda,  
1814.

Okhamandal  
ceded to the  
Gáikwár.

British Aid at  
Junágadh.

THE  
MARÁTHAS,  
A.D. 1760-1819.

Treaty of  
Poona,  
1817.

Treaty with  
the Gáikwár,  
1817-18.

1819.

1820.

the British in the peninsula, where his family had formerly great influence and considerable property. The escape of Trimbakji Dengle from Thána, and the subsequent attempts of the Peshwa to prevent the re-capture of his favourite and to re-nite the Marátha confederacy, led to the execution of a fresh treaty on June 13th, 1817, in accordance with the orders of the Supreme Government.

It was intended to bind the Peshwa in such a way that he could never again enjoy the ascendancy amongst the Marátha chiefs to which he aspired. The Resident at Poona took this opportunity of also putting an end to the discussions about the mutual claims on each other by the Poona and Baroda governments. The Peshwa agreed to abandon all claims on any territory in possession of the Gáikwár and to accept an annual payment of four lákhs of rupees in satisfaction of all previous debts. The farm of Gujarát was made perpetual to the Gáikwár on the payment of four and a half lakhs annually, but the Kathnáváda tribute was made over to the British Government in liquidation of military expenses. The latter Government, by this treaty, also entered into possession of the Peshwa's revenue in Gujarát, except that of Ujhád, which had been assigned to a favourite officer. All the Peshwa's rights north of the Narbada were also ceded.

These conditions necessitated a readjustment of the agreements with the Gáikwár. On November 1817, a definitive treaty, afterwards supplemented by one of November 1818, was executed between the Baroda and British Governments. The force furnished by the former state was found inefficient and the employment of a larger body of British troops was therefore necessary. To pay for these the Gáikwár ceded his share in the fort of Ahmedábád and the districts immediately surrounding that city<sup>1</sup>. He also made over some districts near Surat, and the town of Umreth in Kaira with the whole of the rights acquired by the perpetual farm of Ahmedábád. The British remitted the *mughláí* or *daes* taken by the Nawábs of Surat on the Gáikwár's possessions near that city. Okhámandal having now been pacified, was also given up to the Gáikwár, but revolted four months afterwards and was not again subdued for a considerable time.

At the final settlement of the dominions of the late Peshwa in 1819, the whole of his rights in Gujarát passed in sovereignty to the British, who remitted the four lakhs due from the Gáikwár in composition of arrears claimed by Bájráv. The next year a special inquiry was made into the respective shares of the Peshwa and Baroda governments in the Kathnáváda tribute and in the extra allowance levied by the Gáikwár called *ghás-dána* allowance. In the course of this inquiry so many abuses of power and instances of extortion on the part of the Gáikwár's officers were brought to light, that the Bombay Government on these grounds, and on account also of the general deterioration in the province since the

<sup>1</sup> Known as Daskroi,

Gaíkwár's troops were stationed there, prevailed upon Sayájiráv, who had now succeeded to the throne, to let the duty of collection be undertaken and superintended by a British officer stationed in Káthiávád, who should, however, employ the Gaíkwár's troops on occasions of necessity. A similar arrangement was made with regard to the Mahi Kántha, where the effects of the settlement of 1811 had been much weakened by the disorderly conduct of the Gaíkwár's troops stationed there. The administration of nearly the whole of the province passed into the hands of the British and the period of Marátha ascendancy came to an end.

It remains to review generally the nature and characteristics of the Marátha connection with Gujarát, the chief events in which have been chronicled above. The most prominent feature has already been indicated at the beginning of this section and is apparent throughout the whole narrative. It is, in fact, the small space in history occupied during this period by the people, compared with the share appropriated to the actions of the government and its delegates. The reasons for this are as easily seen as the fact itself. From first to last the Marátha interests in Gujarát were, except at one or two special junctures, simply pecuniary ones. In comparison with other countries within reach of Marátha arms, Gujarát has always had a very large proportion of inhabitants engaged in commerce and manufacturing industries. It was the object of Śivájí to get as much booty as he could and carry it away then and there, hence the commercial classes and manufacturers presented the most favourable opportunities for pillage, and the agriculturists were at first only molested in forage and provisions. Rapidity of action was another of Śivájí's aims, so not only were his visits short and their effects transitory, but all his booty consisted of property that could be carried away by his horsemen. No women or followers accompanied his expeditions, no prisoners were made excepting the few who could afford to pay a heavy ransom. Torture was resorted to only when the captive was suspected of having concealed his treasure. Cows, women and cultivators were, according to Śivájí's system, exempted from capture. Assignments of revenue were seldom made by him for fear of weakening his own authority. Subsequently the Maráth demands became more regular and assumed the form of a certain proportion of the revenue. The *sar-deshmukhi* and *chauth* were supposed to be calculated on the standard assessment so as to avoid subsequent claims as tribute or over-collection. In reality, however, they consisted of a fixed share in actual collections together with whatever extras the officer in charge could manage to extort, and which were, of course, kept undefined in any agreement. The expeditions, too, moved more leisurely and in greater force. The passes and roads in their rear were protected by their own comrades, so that the booty could be brought to the Dakhn in carts, and more bulky property therefore was removed than in former times. The times, too, when the demands were likely to be made were known to the headmen of the district and village, so that the cultivators could be pressed beforehand to furnish their share of the

THE  
MARÁTHAS,  
A.D. 1760-1819.  
Close of Marátha  
Supremacy,  
1819.

General  
Review.

THE  
MARATHAS,  
A.D. 1760-1819.

General  
Review.

contributions. The extortion by this means passed from the commercial classes down to the agriculturists, the latter having also the burden of supporting a larger and more cumbersome army for a longer period.

When the power of the Dabhlade and his deputy the Gaikwar was fairly established, a regular system of administration was introduced. It will be remembered that by the treaty of 1729 as few Maratha officers were to be employed as possible beyond those necessary to collect the Dabhlade's share of the revenue. In consequence, however, of the internal struggles of the Muhammadan chiefs, this minimum quota grew to be a large establishment, with the usual accompaniment of alienations and assignments for the support of the officers and their religious institutions which the weakness of the central power had allowed to become customary. The Dabhlade himself was non-resident and his deputy usually being too valuable an assistant to be spared from the arena of Dakhan politics, the collection was left to sub-deputies and their subordinates, who in turn delegated a great part of their duties to village officers and even to strangers. The Dabhlades, who were throughout more interested in the Dakhan than in Gujarat, had, no doubt, an idea of raising up a power in the latter province in opposition to the administration of the Peshwa, which was conducted purely by Brahman agency. It was soon evident, however, that all that could be done politically with Gujarat was to make it a treasury for the support of schemes that had to be carried out in the Dakhan.

The fertility of the soil and the facilities the country afforded for commerce and manufactures both tended to make it unlikely to become a field for recruiting. The inhabitants of the towns had fixed and lucrative occupations; the cultivators were mostly of a class which on account of the fertility of their land neither Muhammadan nor Maratha had been able to impoverish. The Marathas had still to seek for soldiers in the rugged and barren country on the Ghats and in the Konkan, where the people could only look for a hand-to-mouth existence if they remained at home. The warlike tribes of Gujarat were, as has been already seen, too proud by birth and position to engage themselves to fight for any but their own race and interest. The aboriginal races were not likely to prove effective allies even if they had been willing to move from their own woods and fortresses. None of the Maratha governors of Gujarat seem to have consistently attempted to weld the various interests subordinate to them into a cohesion and unity that they might have made politically useful against the Poona influence. All that they endeavoured to do was to draw from their charge as much revenue as possible and to keep out interlopers. To the taxpayer the result was the same, whether his district was invaded by Kantaji or Pilaji. If one anticipated the other in carrying off the harvest, the ryot still had to pay the latter for ejecting the intruder. The only resistance to be feared by the Marathas was that, not of the cultivators, but of their own race or of the Rajput Christians. These latter were treated in all districts as mere robbers, probably because the class which bears that name near Rajpipla

where the Maráthás first came in contact with it subsists usually on blackmail. In the north, however, the Girásiás were land-owners of great influence and fixed residence, not likely to be conciliated by the knowledge that the invaders of their country classed them along with Bhils and Kols as *mehrásis* or outlaws.

THE  
MARÁTHÁS,  
A.D. 1760-1819.

General  
Review.

In order to relieve the chief officials of direct responsibility for the revenue, the Gáákwar towards the last quarter of the eighteenth century if not before, introduced the system of letting out each revenue sub-division in farm for from one to five years at a fixed annual rate. The farmer was as often as not an absentee, but the supervision and administration were never entrusted to any one but a Marátha Bráhman. The revenue for the year was settled by an inspection of the accounts of previous years and the crops of each village. The amount was taken in kind, but the actual distribution of the whole on individual cultivators was left to the headman, who was in most cases made responsible for the assessment imposed on his village.

The frequent passages of hostile armies and other causes had left much cultivable land a desert. In order to restore the population and induce colonists to settle and cultivate in such spots, leases on favourable terms were granted to *desais*, who administered the land as they pleased, and were directly responsible to the head revenue authority of the sub-division for the annual rent. The *patels* and other village officials also made use of their position with reference to the foreign supervisors in appropriating large tracts of waste land to their own uses. The *kamavísdár* or farmer for the time being was interested only in recouping himself for the amount he had agreed to pay the Marátha government, together with a margin for bribes paid to underlings at head-quarters for good offices with regard to the farm. He was ready, therefore, to make use of any agency in collecting his revenue that he found effective, and which saved the cost of a personal establishment. In many parts of the country there were hereditary village headmen accustomed to the duty of extorting money from unwilling ryots. In other places, such for instance as Dhodka, it had been customary for certain Muhammadans called *Kasbátis*, to become responsible for the revenue of certain villages in return for a discount on the *jama* or amount collected (*manoti*). These *manotidárs* were found so useful by the Marátha officials that they gradually acquired an hereditary position and claimed proprietary rights in the villages for which they had been formerly mere agents for collection. They also acted as *desais* or colonists, and succeeded in getting their leases of certain tracts renewed long after they had ceased to actively improve the land, which had in fact been all brought under regular cultivation.

Such was the agency employed in administering the revenue. The *kamavísdár* was also the dispenser of justice both civil and criminal. As his object was to make money and not to improve the condition of his charge, his punishments consisted chiefly in fines, and most offences could be paid for. No record of trials was

THE  
MARATHAS,  
A.D. 1761-1819.

General  
Review.

kept except a memorandum of the amount passed at each decision to the credit of the farmer. In civil suits sometimes one-fourth of the amount in dispute was assigned as costs and appropriated by the court. The Garásias in their own territory exercised somewhat similar jurisdiction, but grave crimes with violence were apparently left to the party injured or his relations to decide after the manner of the offence. Arbitration, too, was a frequent mode of deciding differences of both civil and criminal nature, but the *kamársdár* or *garásá* usually managed that the State should not be a loser by such a method of settlement.

The whole system indicates clearly enough the slight hold the Maráthás had on the province and their desire to make the most out of it for the furtherance of court intrigues or political ends above the Ghats. There is nothing to show that they contemplated a permanent colonization of the country until the British Government undertook the task of dividing the Maráthas by the establishment of a powerful and independent court at Baroda.

The home of the Maráthás was always the Dakhan, and for many years after they had effected a lodgment in Gujarat, their army regularly returned for the rainy season to the country from whence they originally came. Their leaders were encouraged to be as much as possible near the court by the Dabhdé, or the regent on the one side and by the Peshwa on the other; the former on account of their weight with the army and the Maráthas chiefs, the latter in order that their influence in a distant dependency might not grow beyond what prudence recommended or might be counteracted if its tendency to increase became manifest. For similar reasons no force was allowed to be maintained in Gujarát sufficient to consolidate the Maráthas acquisitions there into a manageable whole. Dámáji Gáukwár, had he lived, would undoubtedly have done much towards this end by means of his personal influence; but, as it happened, the thin crust of Maráthas domination rapidly disappeared before it either was assimilated into the system of the province or hardened over it. A military occupation of a large and civilised district at a distance from the mother-country, and prevented by the jealousy of the central authority and the short-sightedness of those in charge of its exploitation, from either conforming itself to the elements it found already established, or absorbing the vital forces of the government it dispossessed, a system without the breath of life, without elasticity, without the capacity of self-direction, imposed bodily upon a foreign people, without even the care of preparing a foundation, such seems to have been the Maráthas government, containing within itself all that was necessary to ensure a precarious, but while it lasted, an oppressive existence.

**GUJARÁT DISTURBANCES.**  
**1857-1859.**

**BY**

**L. R. ASHBURNER Esq., O.S.I.,**  
**LATE OF H. M.'S BOMBAY CIVIL SERVICE.**

*['CONTRIBUTED MAY 1860.']*



# GUJARÁT DISTURBANCES.

1857-1859.

VERY soon after the outbreak of the mutinies in the North-West of India in May 1857, an uneasy feeling began to prevail in the Bombay Presidency, especially in Gujarát. The story of the greased cartridges had been industriously repeated and found credulous listeners in every village. A similar incident occurred in Gujarát. A consignment of salt from the Ran of Kachh having been carried in bags which had previously held red ochre (*sindur*) had become discoloured. This was observed at Sádra in the Makhí Kútha as the salt was in transit to Ráppatána, and a report was at once spread that the salt had been defiled with cow's blood. It was believed in Ahmedabád and throughout Gujarát that this was a device of the British Government to destroy the caste of the people as a preliminary to their forcible conversion to Christianity.

About the time that the cakes or *chapátis* were being circulated throughout the North-West of India, a common pariah dog was passed from village to village in the Panch Maháls and eastern Gujarát. It was never ascertained who first set the dog in motion, but it came from the Central India frontier with a basket of food which was given to the village dogs, and a similar supply with the dog was forwarded to the next village. When pestilence or other calamity threatens an Indian village, it is the custom to take a goat or a buffalo to the boundary and drive it into the lands of the adjoining village, in the hope that it will avert evil from the community. A similar belief prevailed among the Jews. There is no reason to suppose that this movement of the dog in Gujarát was a signal of revolt or had any deeper political significance than a vague feeling that troublous times were approaching. Still it was by many regarded as an evil omen and created considerable alarm.<sup>1</sup>

GUJARAT  
DISTURBANCES,  
1857-1859.

The Red Salt  
Scare,  
1857.

The Passing of  
the Pariah Dog.

<sup>1</sup> The rite of passing cakes from village to village or of passing a dog from village to village is in such complete accord with magical and religious rites practised all over India that it seems hardly possible to accept either as meaningless or as accidental. The passing of a cake and of a dog from one part of the country to another on the bank of the Mutines. Knowing how suitable such a rite is to the state of feeling as well as to the phase of belief prevalent among the plotters of rebellion in Northern India it seems difficult to suppose that the passing of the cakes and the passing of the dog were not both sacramental, that is designed to spread over the country a spirit which had by religious or magical rites been housed in the dog and in the cakes. The cake-spirit, like the sugar-spirit of the Thags, was doubtless Káli, the fierce longing for unbridled cruelty, which worked on the partaker of the Thag sugar with such power that he entered with zest and without remorse on any scheme however cowardly and cruel. Like the Thags those who ate the Mutiny cakes would by partaking become of one spirit, the spirit of the indwelling Káli, and, in that spirit would be ready to support and to take part in any scheme of blood which the leaders of Mutiny might devise and start. Similarly by religious rites the Central India dog, possibly the dog of Báza Bá of Gwahar (See Text page 437), had been made the home of some fierce war spirit, apparently of the dog-formed Khandoh the Marátha Sword God and Dog of War. The inspired dog and the inspired dogs-meat were passed through the land in the confidence that through them the spirit of unrest would pervade every village of Gujarát. Since the Mutinies, by the

GUJARAT  
DISTURBANCES  
1857-1859

Gold Hoarding

Although Gujarāt was apparently tranquil in the hot season of 1857, those who were most familiar with native opinion were aware of the existence of very serious discontent, and indications of the storm which lowered on the horizon were not wanting. When disturbances are impending natives invariably convert their savings into gold, because gold is more portable and more easily concealed than silver. A sudden and unusual demand for gold in the markets, especially by the native troops, had been observed. This fall of the political barometer should never be disregarded. It indicates the approach of a storm with great certainty.

Seditious  
Native Press

The native press, which had been merely disloyal, now assumed an attitude of decided hostility. Every paper contained the most exaggerated accounts of the massacre of Europeans in the North-West Provinces, and absurd rumours were circulated of the approach of a combined Russian and Persian army, which, it was said, had reached Attok and would shortly invade Hyderabad. It is much to be regretted that the measures which were found necessary in 1880 for the suppression of seditious publications were not enforced in 1857. Had this been done much evil would have been averted. The native mind would not have become familiar with the spectacle of the British Government held up to the execration and contempt of its subjects and the vilest motives attributed to every public measure.

Maulvi  
Saraj-ud-din.

The native press was not the only source of sedition. The fall of the British Government was openly predicted in every masjid, and in Ahmedabad a Maulvi named Saraj-ud-din became especially prominent by preaching a *jihad* in the Jāma Masjid to audiences of native officers and *sardars* of the Gujarāt Horse and troops from the

magic of letters, Kali has passed from the water into the bath, and the paid\* pointed propagandist has taken the place of Kumbhā's pious dog.

The correctness of the view suggested above is supported if not established by certain passages in Kaye's Sepoy War, 1, 632-642. Cluin says, 'The cremating of cakes was supposed to foment disturbance and to imply an invitation to the people to mob for some secret purpose.' According to the lang of Dulla's physician (page 636) some charm attached to the cakes. 'The people thought they were made by some adept in the secret arts to help annihilate the religion of the country.' Another authority (page 637) says; 'The first circulation of the cakes was on the authority of a pandit who said the people would rise in rebellion if cakes were sent round and that the person in whose name the cakes were sent would rub India.' The secret comes out in Sitarām Bawa's evidence (pages 646-648). 'The cakes in question were a charm or *pad* which originated with Dulla Bawa the *guru* or teacher of Nādu Sabha. Dasi told Nam Sahib he would make a charm and as far as the magic cakes should be carried so far should the people be on his side. He then took lotus-seed-dough called *mokana* and made an idol of it. He reduced the idol to very small pills and having made an immense number of cakes he put a pilllet in each and said that as far as the cakes were carried so far would the people determine to throw off the Company's yoke.' With this making of a cake as a sacramental home of Durga or Kali compare the Buddhist of Tibet offering in a human skull to the Maharāni or Queen, that is to Durga or Kali, a sacramental cake made of black-goat's fat, wine, dough, and butter. (Waddell's Buddhism in Tibet, 365.) As to the effect of sharing in Durga's smutty cakes compare the statement of the Thag Feringa (Sleeman's Rannaseena, page 216), 'The sugar sacrament, *gur-tapagan*, changes our nature. Let a man once taste the sacramental sugar and he will remain a Thag however skilful a craftsman, however well-to-do. The Urdu proverb says *Tapragi-ki-dhannika gur pise khana wah vauri hai* Who eats the sugar of the sacramental Vase as he is so he remains. The Thags are fools in the hand of the god they have eaten (Compare Rannaseena, 76.)—J. M. C.

Ahmedābād cantonment. The Maulvi was expelled from Ahmedābād and found his way to Baroda, where he was afterwards arrested; but the impunity he so long enjoyed brought great discredit upon Government, for it was very naturally supposed that a government which tamely submitted to be publicly reviled was too weak to resent the indignity. Oriental races are so accustomed to violent measures that they seldom appreciate moderation or forbearance. The generation that had known and suffered from the anarchy of the Peshwa had passed away. The seditious language of the native press and the masjid was addressed to a population too ignorant to understand the latent power of the British Government.

GUJARAT  
DISORDERANCES,  
1857-1859.

In 1857 the immense continent of Hindustān was governed by what appeared to the people to be a few Englishmen unsupported by troops; for they knew that the native army was not to be depended on, and the European troops were so few that they were only seen in the larger military cantonments. It must have seemed an easy task to dispose of such a handful of men, and it probably never occurred to those who took part in the insurrection that the overthrow of the British Government would involve more serious operations than the capture or murder of the Europeans who governed the country so easily. They could not perceive that England would never submit to a defeat, and that the handful of men who ruled India were supported by the whole power of the nation. The plotters had no very definite ideas for the future. The Musalmāns regarded the subversion of a government of Kāfirs as a triumph of Islam, and both Musalmāns and Hindus looked forward to a period of anarchy during which they might indulge that appetite for plunder which had been restrained for so many years. The descendants of the feudal aristocracy of the Peshwa are an ignorant and improvident race deeply involved in debt. They could not fail to see that under the operation of our laws their estates were rapidly passing into the possession of the more intelligent mercantile classes, and they hoped to recover their position in the revolution that was about to ensue.

Apparent  
Weakness of  
British Rule.

A great change had taken place in the character of the administration. The civilians of the school of Duncan, Malcolm and Mountstuart Elphinstone, though not deeply learned in the law, were accomplished earnest men, sufficiently acquainted with the unalterable principles of right and wrong to administer substantial justice to a simple people who had not yet learnt the art of lying. The people asked for justice rather than law. They were satisfied with the justice they obtained from the able and upright men who ruled this country during the first half of this century. The writings and official reports of the officers of that period indicate a knowledge of native customs and feelings and a sympathy with the people that is unknown in the present day, for knowledge and sympathy cannot be acquired except by a long and familiar residence amongst the people which is now becoming every year more impossible. When the overland route rendered communication with England more easy and frequent, a reaction set in against patriarchal administration. Concubinage with native women, which had been common, was now declared vulgar, if not immoral; and the

Administrative  
Effects.

GUJARAT  
DISTURBANCES  
1857-1859.

The Courts  
Unliked.

relations between Europeans and Natives soon became less cordial than they had been during the early period of British rule. About this time a considerable immigration of lawyers appeared in India. These briefless gentlemen, envious of the official monopoly of the Civil Service, raised an outcry that justice was being administered by men who had not acquired that knowledge of law which the formality of eating a certain number of dinners at the Temple was supposed to guarantee. They worked the press so industriously to this cry, that in the course of a few years they had succeeded in impressing their views on the Court of Directors in London and on the less intelligent members of the Civil Service in India.

Unfortunately the Sadar Court was then presided over by a succession of feeble old gentlemen who had not sufficient force of character to resist this selfish agitation, and by way of refuting the charge of ignorance of law devoted themselves to the study of those petty technicalities which have so often brought the administration of justice into contempt, and which the progress of law reform has not even now removed from the law of England. In 1827, Mountstuart Elphinstone had enacted a Civil and Criminal Code which was still the substantive law of the land. It was simple and admirably suited to the people, but justice was administered according to the spirit rather than the letter of the law. A district officer would have incurred severe censure if his decisions were found to be inequitable, however they might have been supported by the letter of the law. The national character for even-handed justice had made the English name respected throughout India and far across the steppes of Central Asia. But the demoralizing example of the Sadar Adalat soon extended to the lower grades of the service. The Civil Service was afflicted with the foolishness which, we are told, precedes ruin. Its members diligently searched their law-books for precedents and cases, and rejoiced exceedingly if they could show their knowledge of law by reversing the decision of a lower Court on some long-forgotten ruling of the Courts of Westminster. The first effect of this evil was to fill the courts with corrupt and unprincipled *vahils* who perverted the course of justice by perjury, forgery, and fraud of every description. Litigation increased enormously, no cause was too rotten, no claim too fraudulent to deprive it of the chance of success. The grossest injustice was committed in the name of the law, and though the Civil Service was above all suspicion of corruption, the evil could hardly have been greater if the Judges had been corrupt. This state of affairs gave rise to great discontent, for the administration of justice fell almost entirely into the hands of the *vahils*. When men quarrelled they no longer said, "I'll beat or I'll kill you," but "I'll pay a *vakil* Rs. 50 to ruin you," and too often this was no mere idle threat.

The Indian  
Commission

The operations of the Lââm Commission and of the Survey Department were also a fruitful cause of alarm and discontent. Many of the estates of the more influential Jâghîrdârs had been acquired by fraud or violence during the period of anarchy which preceded the fall of the Peshwa. The Patels and Deshmukhs had also appropriated large areas of lands and had made grants of villages to temples and assignments of revenue to Brâhmins, religious mendicants, and dancing

irls. The Peshwa had never recognized these alienations as any limitation of his rights, for he farmed his revenues, and so long as a large sum was paid into his treasury by the farmers it was immaterial to him how much land was alienated. But when the Survey Department revealed the fact that nearly a fourth part of the fertile province of Gujarāt was unauthorizedly enjoyed by these parasites; and that in other districts the proportion of alienations was nearly equally large, a due regard for the public interests demanded that there should be an investigation into the title on which the lands were held rent-free. It became the duty of the Inām Commission to make this inquiry, and though a very small portion of land was resumed or rather assessed to the land revenue and the rules for the continuation of cash allowances were extremely liberal, they could hardly be expected to give satisfaction to those who had so long enjoyed immunity from any share of the public burdens. The Brahmans and the priesthood of every sect deeply resented the scrutiny of the Inām Commission and excited an intensely fanatical spirit by representing the inquiry as a sacrilegious attack on their religious endowments and a departure from the principle of neutrality and toleration which had been the policy of Government from a very early period.

Notwithstanding all these elements of danger there would probably have been no revolt if the army had remained loyal. Fortunately the Bombay army was composed of a great variety of races, Musalmāns of the Shia and Sunni sects, Marāthas of the Dakhan and Konkan, Parvars, Pūdeshis, and a few Jews and Christians. Little community of sentiment could exist in so heterogeneous a force, and to this circumstance we may trace the failure of each mutinous outbreak in the regiments of the Bombay army. Many of its regiments had, however, recruited extensively in the North-West Provinces which were then the centre of the political cyclone, and it was soon discovered that seditious overtures were being made to them not only by their brethren in the regiments which had already mutined, but by discontented persons of higher rank. The most important of these was a clever woman known as the Baija Bai. She was the daughter of a Dakhan Sardār named Sirji Rāo Ghātke, and had been married in early life to His Highness Dowlat Rāo Sindia the Mahārāja of Gwālior. On his death she had been allowed to adopt Jankeji Rāo as heir to the *gādi*, and during his minority she had been appointed by the British Government Regent of the Gwālior state. In this position the Bai had accumulated great wealth. She had deposited £370,000 (37 lakhs of rupees) for safe custody in the treasury at Benares, and it was known that she had other resources at Gwālior. Her avarice and ambition were insatiable. She sent emissaries to all the Marātha chiefs and Thākors in Western India calling on them to take up arms and restore the empire of Shivaji. She appealed to the troops, urging them to emulate the deeds of their comrades in the Bengal army who had already nearly exterminated the Europeans in the North-West, and warned them that if they did not now strike in defence of their religion they would shortly be converted to Christianity and made to drink the blood of the sacred cow.

In May and June 1857 our troops were fighting before Delhi, only just holding their own, and making little impression on the walls

GUJARAT  
DISTURBANCES,  
1857-1859.

The Inām  
Commission.

The Army.  
Loyal.

Bāija Bāi of  
Gwālior.

Parsi Riot in  
Broach,  
June 1857.

GUJARAT  
DISTURBANCES  
1857-1859.

Parsi Riot in  
Broach,  
June 1857.

of the city which were strongly held by the mutinous regiments. Gujrat was still tranquil. It is true there had been a riot in Broach originating in a long-standing feud between the Parsis and Musalmans of that town, but it had no political significance and had been promptly suppressed. The ringleaders were arrested, tried, and sentenced to be hanged for the murder of a Parsi, but there is no reason to suppose that this disturbance had any immediate connection with the outbreak in the North-West. It was probably only a coincidence, but the violence of the rioters was no doubt encouraged by the weakness of our position in Gujrat, and the exaggerated rumours which reached them of the massacre of our countrymen.

Mutiny at  
Mhow,  
July 1857.

On July 1st, 1857, the 23rd Bengal Native Infantry and the 1st B. M. Cavalry stationed at Mhow mutinied and murdered Colonel Platt, Captain Fagan, Captain Harris and a number of European subordinates of the Telegraph Department. The troops of His Highness Holkar fraternized with the mutineers, attacked the Residency, and after a desultory fight drove out Colonel Durand the Resident, who took refuge in Bhopal with the surviving Europeans of Indor. Information of the mutiny at Mhow soon reached Ahmedabad, and reasonable negotiations were at once opened for a simultaneous rising of the Gujrat Horse and of the troops in the cantonment; but they could not agree to combined operations. The Marathas hoped for the restoration of the dynasty of the Peshwa, while the Pardeshis looked towards Delhi where their brethren were already in arms, without any very definite comprehension of what they were fighting for, but with some vague idea that they would establish a Musalman *Raj* on the throne of the Great Moghal.

Mutiny at  
Ahmedabad,  
July 1857.

On July 9th, 1857, seven *sardars* of the Gujrat Horse raised a green flag in their regimental lines in Ahmedabad and attempted to seize the quarter guard in which the ammunition was stored, but the guard made some slight show of resistance, and finding the regiment did not join them the mutineers left the lines in the direction of Sarkhej. They were followed by the Adjutant, Lieutenant Pym, with twelve *sardars*, and Captain Taylor, the commandant, joined them soon after with three men of the Koh Corps, whom he had met on the Dholka road. The *sardars* were overtaken near the village of Tajpor, and having taken up a strong position between three survey boundary-marks opened fire on their officers and the Kohs, the *sardars* standing aloof. After many shots had been exchanged without result, Captain Taylor advanced to parley, and while endeavouring to reason with his men was shot through the body. The Kohs now re-opened fire and having shot two of the *sardars* the rest laid down their arms. They were tried under Act XIV. of 1857 and hanged. The *sardars* who followed Lieutenant Pym passively declined to act against their comrades, and if the Kohs had not been present the mutineers would have escaped. Captain Taylor's wound was severe, the bullet passed through his body, but he eventually recovered. The execution of the *sardars* had a good effect on the troops, but it became evident that a serious struggle was impending, and Lord Elphinstone, who was then at the head of the Bombay Government, took all the precautions that were possible under the circumstances.

Mr. Ashburner, Assistant Magistrate of Kaira, was ordered to raise a force of 200 Foot and 30 Horse for the protection of his districts, and Husam Khán Battangi, a Musalmán gentleman of Ahmedabád, was authorized to enlist 2000 of the dangerous classes. It was not expected that this Ahmedabád force would add to our fighting strength, but the employment of the rabble of Ahmedabád on good pay kept them out of mischief till the crisis was passed. Mr. Ashburner's small force was composed of Rajputs, Makrams, and Kohis. They were a very useful body of men and were afterwards drafted into the Kaira Police of which they formed the nucleus. It was this force that suppressed the rising of the Thakors on the Mahi, which will be described below.

General Roberts, a very able soldier, commanded the Northern Division at this time. He fully realized the critical position of affairs in Gujrat. He was aware that the troops were on the verge of mutiny, that the Thakors were sharpening their swords and enlisting men, and that no relief could be expected till after the rains. But he was not the man to despond or to shirk the responsibility now thrown upon him. He proved equal to the occasion and met each emergency as it arose with the calm determination of a brave man.

When the troops at Mhow mutinied, the Rája of Amjara took up arms and attacked Captain Hutchinson the Political Agent of Bhopáwar. He fled and was sheltered by the Rája of Jábwa. At the same time (July 1857) the Musalmán Kammings or accountants and Zamindárs of the Panch Mahals revolted, laid siege to the fort of Dohad and threatened the Kaira district. Captain Buckle, the Political Agent, Rewa Kantha, marched from Baroda with two guns under Captain Sheppee, R. A., and two companies of the 8th Regiment Native Infantry, to relieve Dohad, while Major Andrews, with a wing of the 7th Regiment, two guns under Captain Sanlez, R. A., and 100 Sabres of the Gujarat Horse, marched on Thasra to support Mr. Ashburner and act generally under his orders. On the approach of Captain Buckle's force the insurgents abandoned the siege, and Captain Hutchinson soon after re-established his authority in Bhopáwar by the aid of the Málwa Bhil Corps which remained loyal. He arrested the Rája of Amjara and hanged him.

On the 5th August the Jodhpur Legion stationed at Abu mutinied. They made a feeble attack on the barracks of H. M. 33rd Regiment and Captain Hall's bungalow, into which they fired a volley of musketry, but were repulsed, leaving one of their men on the ground badly wounded. The fog was so dense that it was impossible to use firearms effectively. Mr. Lawrence of the Civil Service was the only person wounded. A party of the 17th Bombay Native Infantry who were on duty at Abu, were suspected of complicity with the Jodhpur Legion and were disarmed. The head-quarters of the Legion mutinied at Brinpur on the same day as the attack at Abu, they made the Adjutant, Lieutenant Conolly, prisoner and plundered the treasury.

GUJARAT  
DISTURBANCES,  
1857-1859.

Mr. Ashburner's  
Force.

Genl. Roberts.

Rising at Amjara.

And in the  
Panch Mahals,  
July 1857.

Mutines at  
Abu and  
Brinpur,  
1857.

GUJARAT  
DISTURBANCES,  
1857-1859.

Disturbance at  
Ahmedabad,  
14th Sept. 1857.

An incident occurred early in September which had an important influence on events. The two Native regiments quartered at Ahmedabad were the 2nd Regiment of Grenadiers and the 7th Native Infantry. The Grenadiers were chiefly Pardeshis from Oudh, while the majority of the 7th Regiment were Maráthás. As is often the case, an enmity sprang up between the two regiments. One night Captain Muter of the 2nd Grenadiers was visiting the guards as officer of the day. On approaching the quarter guard of the 7th Regiment, the sentry demanded the password which Captain Muter could not give. The sentry very properly refused to let him pass. Captain Muter returned to his lines, called out a party of Grenadiers, and made the sentry a prisoner. Next morning General Roberts put Captain Muter under arrest and released the sentry. This incident intensified the ill-feeling between the two regiments, and prevented their combination when the Grenadiers mutinied a few days later. It had been arranged that the two Native Regiments and the Golandanz artillery should mutiny at the same time, but there was mutual distrust between them, and the Native officers of the artillery had stipulated that they should make a show of resistance in order to let it appear that they had been overpowered by a superior force. About midnight on the 14th September 1857 the Grenadiers turned out and fell in on their parade ground armed and loaded. The guns were also brought out and loaded on their own parade ground. A Native officer of the Grenadiers was sent with a party to take possession of the guns in accordance with the preconcerted agreement, but the Subhedar of the Artillery threatened to fire on them, and the Native officer expecting that the guns would be given up without resistance, thought he had been betrayed, and retreated with his party, who threw away their arms as they ran across the parade ground. The Grenadiers were under arms on the parade waiting for the guns, when seeing the disorder in which the party was retreating from the Artillery lines, they also were seized with a panic and broke up in confusion. Then for the first time the Native officers reported to Colonel Gimes that there had been a slight disturbance in the lines. The mere accident that the Native officer detached to take the guns had not been informed of the show of resistance he was to expect from the Artillery, probably averted the massacre of every European in Gujarat. Twenty-one loaded muskets were found on the parade ground, and though the whole regiment was guilty it was decided to try the owners of those muskets by court martial. They were sentenced to death. As it was doubtful if the Native troops would permit the execution it was considered prudent to await the arrival of the 89th Regiment under Colonel Ferryman and Captain Hatch's battery of Artillery. They had been landed at Gogha during the monsoon with great difficulty, and were compelled to make a wide detour to the north owing to the flooded state of the country. On their arrival the executions were carried out; five of the mutineers were blown from guns, three were shot with musketry, and the rest were hanged in the presence of the whole of the troops. They

met their death with a gentlemanly calmness which won the respect of all who were present.

The example thus made, together with the presence of the European troops in Gujarát, restored our prestige and gave us time to attend to affairs on our frontier. The whole country was in a very disturbed state. On the fall of Delhi on September 28th, 1857, a treasonable correspondence was found between the Nawáb of Radhanpur in Gujarát and the Emperor of Delhi, which deeply implicated the Nawab. He and his ministers had forwarded *na'vánás* of gold *mohars* to Delhi and asked for orders from the Emperor, offering to attack the British cantonments at Disa and Abu's'bad. The Nawab had been on the most friendly terms with Captain Black the Political Agent, and had been considered perfectly loyal. Preparations were made to depose him for this treacherous conduct. We were then so strong in Gujarát that his estate could have been seized without the least difficulty, but he was considered too contemptible an enemy and his treason was pardoned.

Lieutenant Alban, with a party of Gujarát Horse, was now sent to settle affairs in Sonth, a petty state in the Rewa Kantha. Mustapha Khán, at the head of a turbulent body of Arabs, had made the Raja a prisoner in his own palace with a view to extort arrears of pay and other claims. Lieutenant Alban's orders were to disarm the Arabs. After some negotiations Mustapha Khán waited on Lieutenant Alban. He was attended by the whole of his armed followers with the matches of their matchlocks alight, thinking no doubt to intimidate Lieutenant Alban. On entering the tent Lieutenant Alban disarmed him, but imprudently placed his sword on the table. While they were conversing Mustapha Khán seized his sword and Lieutenant Alban immediately shot him with a revolver. The Arabs who crowded round the tent now opened fire on Alban and his men, but they were soon overpowered. Mustapha Khán, four Arabs, and one *sardár* of the Gujarát Horse were killed.

Lieutenant Alban, with a party of the 7th Native Infantry under Lieutenant Cunningham then proceeded to Páhi. A few months before one *Sar'jam'*, a claimant of the *Lúnávada gadi*, had attacked the Raja of Lúnávada, but was repulsed with severe loss and had since been harboured in the village of Páhi. On the approach of Alban's force, it was attacked by Smajmal's Rájputs and the village was accordingly burnt. Order was then restored in the Panch Maháls, and it was not again disturbed till Táta Topi entered the Maháls.

In October 1857 a conspiracy was discovered between the Thákor of Samda near Disa and some Native officers of the 2nd Cavalry and 12th Regiment Native Infantry to attack and plunder the camp at Disa and to murder the officers; but the evidence was not very clear, and before the trial could take place the amnesty had been published under which the suspected men were released. The peace of Northern Gujarát was much disturbed at this time by the Thákor of Rova, who plundered the Pálanpur and Sirohi

GUJARÁT  
DISTURBANCES,  
1857 - 1859.

Radhanpur  
Disloyal.

Arab Outbreak  
at Sonth.

Disturbance  
in Lúnávada.

Conspiracy  
at Disa.

GUJARAT  
DISCORDANCES  
1857-1859.

Conspiracy  
at Baroda.

Want of  
Combination.

villages at the head of 500 men, and the Thákór of Mandeta was also in arms but was held in check by a detachment of the 89th Regiment and a squadron of cavalry at Ahmednagar near Idar.<sup>1</sup> The two Thákors were acting in concert with some influential conspirators at Baroda of whom Mallhár Rao Gáikwár *alias* Dada Sáheb was the chief. It was this man who afterwards became Gáikwár of Baroda and was deposed for the attempt to murder Colonel Phayre by poison.

It is very remarkable that the sepoy war did not produce one man who showed any capacity for command. Every native regiment was in a state of mutiny and a large proportion of the civil population was ripe for revolt. If only one honest man had been found who could have secured the confidence and support of his fellow-countrymen, the fertile province of Gujarát would have been at his mercy, but amongst natives conflicting interests and mutual distrust make combination most difficult. In India a conspirator's first impulse is to betray his associates lest they should anticipate him. The failure of every mutinous outbreak in Gujarát was due to this moral defect. This trait may be traced throughout the history of the war and should be studied by those who advocate the independence of India, and the capacity of the native for self-government. It is an apt illustration of native inability to organize combined operations that the most formidable conspiracy for the subversion of our power should have been delayed till October 1857. By this time the arrival of Her Majesty's 89th Regiment and a battery of European artillery at Ahmedábad had rendered a successful revolt impossible. The mutinies of the Gujarát Horse and Grenadiers had been promptly suppressed and severely punished. The termination of the monsoon had opened the ports and reinforcements were daily expected. Had the outbreak occurred simultaneously with the mutiny of the Gujarát Horse, the Artillery, and the Second Grenadiers, Gujarát must have been lost for a time and every European would have been murdered.

Marátha  
Conspiracy.

For many years Govindháo *alias* Bápm Gáikwár, a half brother of His Highness the Gáikwár, had resided near the Sháhábág at Ahmedábad. He had been deported from Baroda for intriguing against his brother and had been treated as a political refugee. This man with Mallháráo, another brother of His Highness the Gáikwár, Bhán Sáheb Pawár, and a Sardár who called himself the Bhonsla Raja, also related to His Highness by marriage, conceived the design to murder the Europeans in Baroda Ahmedábad and Kaira and establish a government in the name of the Rája of Sátára. To Bápm Gáikwár was entrusted the task of tampering with the troops in Ahmedábad, and frequent meetings of the Native officers were held at his house every night. The Bhonsla Rája, with a man named Jhaveri Nálehánd, was deputed to the Kaira district to secure the aid of the Thákors of Umota, Bhádarva, Kera, and Dáima, and of the Patels of Anand and Partábpur.

<sup>1</sup> Roza in the south-east corner of Sirohi. Mandeta in Idar in the Mahi Kantha. P. FitzGerald Esq. Political Agent Mzhi Kantha.

These landholders assured Bápn of their support and the Thakor of Umeta mounted some iron guns and put his fort in a state of defence. An agent named Magumlál was sent into the Gáikwár's Kadi Pargana, where he enlisted a body of 2000 foot and 150 horse, which he encamped near the village of Lodra. The followers of the Kaira Thakors assembled in the strong country on the banks of the Mahi near the village of Partáhpur with a detachment and advanced to the Chank Taliv within five miles of Baroda. The massacre at Baroda was fixed for the night of October 16th. The native troops in Baroda had been tampered with and had promised in the event of their being called out that they would fire blank ammunition only.

The Thakors had been encamped at Partáhpur for several days, but owing partly to the sympathy of the people and partly to the terror which they inspired, no report was made to any British officers till the 15th October, when Mr. Ashburner, who was encamped at Thasra, marched to attack them with his new levies and a party of the Kaira police. There was, as usual, disunion in the ranks of the insurgents; they had no leaders they could depend upon, and they dispersed on hearing of the approach of Ashburner's force without firing a shot. Ninety-nine men who had taken refuge in the ravines of the Mahi were captured and a commission under Act XIV. of 1857 was issued to Mr. Ashburner and Captain Buckle, the Political Agent in the Rewa Kantha, to try them. Ten of the ringleaders were found guilty of treason and blown from guns at Kanvária, nine were transported for life, and the remainder were pardoned. The turbulent villages of Partáhpur and Angar in Kaira were destroyed and the inhabitants removed to more accessible ground in the open country. Their strong position in the ravines of the Mahi river had on several occasions enabled the people of Partáhpur and Angar to set Government at defiance, and this was considered a favourable opportunity of making an example of them and breaking up their stronghold.

In the meantime information of the gathering at Lodra had reached Major Agar, the Superintendent of Police, Ahmedábád. He marched to attack them with the Koli Corps and a squadron of the Gujrat Horse. Mr. Gónd led to the north after a slight skirmish in which two men were killed and four wounded, and was captured a few days afterwards by the *Thakdar* of Samina with eleven followers. They were tried by General Roberts and Mr. Hadow, the Collector of Ahmedábád, under Act XIV. of 1857. Three of them were blown from guns at Wnizápur, three were hanged, and the rest were transported for life.

It is much to be regretted that Malhárráo Gáikwár and the Bhonsla Rájá were allowed to escape punishment. There was very clear evidence of the guilt of the Bhonsla Rájá, but His Highness the Gáikwár interceded for him, and Sir Richmond Shakespeare, the Resident, weakly consented that his life should be spared on condition that he should be imprisoned for life at Baroda, a sentence which, it is hardly necessary to say, was never carried out.

GUJARAT  
DISTURBANCES,  
1857 - 1859.

Marátha  
Conspiracy.

Gathering at  
Partáhpur,

And at Lodra.

GUJARAT  
DISTURBANCES,  
1857-1859.

Partial  
Disarming.

On the suppression of this abortive insurrection it was determined to disarm Gujarat, and in January 1858 strong detachments of the 72nd Highlanders and of Her Majesty's 86th Regiment with the 8th Regiment Native Infantry, two guns under Captain Conybere, and a squadron of Gujarāt Horse were placed at the disposal of Mr. Ashburner to carry out this measure. His Highness the Gaikwār had consented to a simultaneous disarmament of his country, but he evaded the performance of his promise. In the Kaira district and in the Jacobpur taluka of Broach the disarmament was very strictly enforced; every male adult of the fighting classes was required to produce an arm of some kind. The town of Ahmedābād was relieved of 20,000 arms in the first two days, but the Highlanders and 86th Regiment were required for operations in Rajputāna, and after their departure from Gujarāt it was deemed prudent to postpone this very unpopular measure.

Nāikda  
Revolt,  
Oct. 1858.

After these events Gujarāt remained tranquil for nearly a year till, in October 1858, the Nāikda Bhils of Narokot revolted under Rupa and Keval Nāiks, and a few months later Tatia Topi's scattered force being hard-pressed by Colonel Parks' column, plundered several villages of the Panch Mahals during its rapid march through that district.

Tatia Topi,  
1858.

In 1858, after his defeat at Gwahar, at the close of the mutinies in Northern India, Tātia Topi moved rapidly towards the Dakhan. The chiefs of Jambhandi and Nargund had been in treasonable correspondence with the rebel chiefs in the North-West and had invoked their aid. It is more than probable that if Tātia Topi had entered the Dakhan in force, there would have been a general insurrection of the Marāṭha population. Tātia's march to the Dakhan soon assumed the character of a flight. He was closely pressed by two columns under Generals Somerset and Mitchell, and a very compact and enterprising little field force commanded by Colonel Park. Colonel Park's own regiment, the 72nd Highlanders, many of the men mounted on camels, formed the main fighting power of this force. His indefatigable energy in the pursuit of the enemy allowed them no rest, and eventually brought them to bay at Chhotā Udepur. Fearing to face the open country of Betar with such an uncompromising enemy in pursuit, Tātia recrossed the Narbada at Chhokda and marched towards Baroda. He had, by means of an agent named Ganpatrao, for some time been in communication with the Bhān Sāheb Pavār, a brother-in-law of His Highness the Gaikwār, and had been led to expect aid from the Baroda Sardārs and the Thākors of the Kaira and Rewa Kāntla districts. Immediately it became known that Tātia had crossed the Narbada, troops were put in motion from Kaira, Ahmedābād, and Dasa for the protection of the eastern frontier of Gujarat. Captain Thatcher, who had succeeded to the command of the irregular levies raised by Mr. Ashburner in Kaira, was ordered to hold Sankheda with the irregulars and two of the Gaikwār's guns. He was afterwards reinforced by Captain Collier's detachment of the 7th Regiment N. I., which fell back from Chhotā Udepur on the approach of the enemy.

Tátia Topi at this time commanded a formidable force composed of fragments of many mutinous Bengal regiments. He had also been joined by a mixed rabble of Villayatis, Rohullás, and Rajpúts, who followed his fortune in hopes of plunder. Ferozsha Nawáb of Kamora and a Maráthá Sardar who was known as the Ráo Sahéb, held subordinate commands. Each fighting man was followed by one or more ponies laden with plunder which greatly impeded their movements. It was chiefly owing to this that Colonel Park was enabled to overtake the rebels and to force them into action. On reaching Chhota Udepur the troops of the Raja fraternised with the enemy, and Captain Collier having evacuated the town, Tátia Topi was allowed to occupy it without opposition. He had intended to halt at Chhota Udepur to recruit his men and to develop his intrigues with the Barochi Sardárs, but Park gave him no respite. On the 1st December 1858, he fell upon Tátia's rebel force and defeated it with great slaughter, his own loss being trifling. After this defeat there was great confusion in the ranks of the insurgents. Tátia Topi abandoned his army and did not rejoin it till it had reached the forest lands of Parana. Discipline which had always been lax, was now entirely thrown aside. The muster roll of one of Tátia's cavalry regiments was picked up and showed that out of a strength of 300 sabres only sixteen were present for duty. The rebel force separated into two bodies, one doubled back and plundered Park's baggage which had fallen far to the rear, the other under Ferozsha entered the Panch Mahals and looted Baria, Jhabel, Landi, and other villages; Godhra being covered by Muter's force was not attacked. Park's force was so disabled by the plunder of its baggage and by long continued forced marches, that it was compelled to halt at Chhota Udepur, but General Somerset took up the pursuit and rapidly drove Tátia from the Panch Mahals. He fled in the direction of Salunda. The Thákér of that place was in arms, and Tátia no doubt expected support from him, but the Thákér was too cautious to join what was then evidently a hopeless cause. On reaching Nargad on the 20th February 1859, Ferozsha made overtures of surrender, and a week later 300 cavalry and a mixed force of 1500 men under Zahir Ali and the Maulvi Vazí Bég had down their arms to General Mutch. They were accorded to the benefit of the amnesty. The remnant of Tátia's force fled to the north-east.

In October 1858, instigated by the intrigues of the Bháin Sáheb Pavár, the Sankheda Naikdas, a very wild forest tribe, took up arms under Rupa and Keval Naiks, and after having plundered the outpost, *thana*, at Nárukot, attacked a detachment of the 8th Regiment N. I. under Captain Bates at Janabghoda. They were repulsed with considerable loss after a desultory fight during the greater part of two days. On the arrest of Ganpatráo, the Bháin Sáheb's agent, this troublesome insurrection would probably have collapsed, but the Naikdas were joined by a number of Villayatis, matchlock-men, the fragments of Tátia's broken force, who encouraged them to hold out. They occupied the very strong country between Chámpáner and Nárukot, and kept up a harassing warfare, plundering the villages as far north as Godhra.

GUJARAT  
DISTURBANCES,  
1857 - 1859.

Tátia Topi's  
Defeat at  
Chhota Udepur,  
Dec. 1858.

Naikda  
Disturbances,  
1858.

GUJARAT  
DISTURBANCES,  
1857-1859.

Nankda  
Disturbance,  
1858.

A field force commanded by the Political Agent of the Rewa Kántha, Colonel Wallace, was employed against the Nāikdās during the cold weather of 1858, and in one of the frequent skirmishes with the insurgents Captain Hayward of the 17th Regiment N. I. was severely wounded by a matchlock bullet on the 28th January 1859. The only success obtained by the Nankdas was the surprise of Hassan Ali's company of Hussem Khān's levy. The Subhedar had been ordered to protect the labourers who were employed in opening the pass near the village of Sivrájpur, but the duty was very distasteful to him, and his son deserted with twenty-four men on the march to Sivrájpur. They were suddenly attacked by a mixed force of Makrams and Nāikdās. Seven men including the Subhedar were killed and eleven wounded without any loss to the enemy. The Subhedar neglected to protect his camp by the most ordinary precautions and his men appear to have behaved badly. They fled without firing a shot directly they were attacked. But little progress had been made in pacifying the Nāikdās till Captain Richard Bonner was employed to raise and organize a corps composed chiefly of Bhils with their head-quarters at Dohad in the Pauch Maāds. Captain Bonner's untiring energy and moral influence soon reduced the Nankdas to submission. Rupa Nank laid down his arms and accepted the amnesty of the 10th March 1859, and Keval Nank followed his example soon after.

Wagher  
Outbreak,  
1859.

In July 1859 the Waghers of Okhāmandal, a mahāl in Kāthiāvāda belonging to His Highness the Gaikwār, suddenly seized and plundered Dwarka, Bavala, and Bet. They were led by a Wagher chief named Todā Manik, who alleged that he had been compelled to take up arms by the oppression of the Gaikwār's *kam lārs*, but it is probable that he was encouraged to throw off allegiance by the weakness of the Baroda administration and the belief that he would have to deal with the troops of the Darbār only. He soon found he was in error. Major Christie with 200 sabres of the Gujarať Horse and a wing of the 17th Regiment Native Infantry from Rajkot marched to Mandāna on the Ran to cut off the communication between Okhāmandal and the Kāthiāvāda peninsula. The cantonment of Rajkot was reinforced from Ahmedābād by six guns of Ayton's battery, a wing of the 33rd Regiment and a detachment of the 14th Regiment Native Infantry under Captain Hall, and a naval and military force was at the same time prepared in Bombay for the recovery of Bet and Dwarka as soon as the close of the monsoon should render naval operations on the western coast possible.

Expedition  
against Bet,  
1859.

On the 29th September 1859, the following force embarked in the transports *South Ramilies* and *Empress of India*, towed by Her Majesty's steam-ships *Zenobia* and *Victoria*, and followed by the frigate *Fuoz*, the gunboat *Clyde*, and the schooner *Constance*:

Her Majesty's 28th Regiment ...	...	...	500 Men.
Her Majesty's 6th Regiment Native Infantry ...	...	...	600 "
Marine Battalion . . .	...	...	200 "
Royal Artillery . . .	...	...	60 "
Sappers and Miners ...	...	...	90 "

The expedition was under the command of Colonel Donovan

of Her Majesty's 28th Regiment, but it was intended that on arrival at Bet, Colonel Seobie should command the combined naval and military force. Colonel Seobie marched from Rajkot early in October with the wings of Her Majesty's 33rd Regiment and 17th Native Infantry, the 12th Light Field Battery and detachments of the 14th Native Infantry and Gujarāt Horse. Had Colonel Donovan waited for this force he might have effectually invested the fort of Bet, which is situated on an island, and exterminated the rebels; but he was too anxious to distinguish himself before he could be relieved of command. He arrived off Bet on the 4th October 1859, and at sunrise that morning the steam-ships *Picco*, *Zenobia*, *Clyde*, and *Constance* took up their positions off the fort of Bet and opened fire with shot and shell at 350 yards. The fort replied feebly with a few small guns. Shells effectually scorched the fort and temples occupied by the enemy, but the shot made little impression on the wall which was here thirty feet thick. The bombardment continued throughout the day and at intervals during the night. Next morning Dewa Chabasm, the Wagher chief in command of the fort, opened negotiations for surrender, but he would not consent to the unconditional surrender which was demanded, and after an interval of half an hour the artillery fire was resumed and preparations were made to disembark the troops. They landed under a heavy musketry fire from the fort and adjacent buildings, and an attempt was made to escalate. The ladders were placed against the wall but the storming party of Her Majesty's 28th Regiment and 6th Regiment Native Infantry were repulsed with heavy loss. Captain McCormack of Her Majesty's 28th Regiment, Ensign William of the 6th Regiment, and ten European soldiers were killed, and Captain Glasspoole, Lieutenant Grant of the 6th Native Infantry, and thirty-seven men of the 28th Regiment were wounded, many of them severely. One sepoy of the Marine Battalion was killed and five wounded.

During the night which succeeded this disastrous attack the Waghers evacuated the fort. They reached the mainland, taking with them their women, children and the plunder of the temple, but Dewa Chabasm, the Wagher chief, had been killed the previous day. Considering the large and well-equipped force at Colonel Donovan's disposal and the facilities which the insular position of Bet afforded to a blockading force, the escape of the Waghers almost with impunity, encumbered with women and plunder, did not enhance Colonel Donovan's military reputation. Captain D. Nasmyth, R. E., Field Engineer of the Okhāmandal Force, was directed to destroy the fort of Bet and carried out his instructions most effectually. Some of the Hindu temples nearest the walls were severely shaken by the explosion of the mines, and a great outcry was raised of the desecration of the temples; but if Hindus will convert their temples into fortified enclosures, they must take the consequence when they are occupied by the enemies of the British Government.

Lieutenant Charles Goodfellow, R. E., greatly distinguished himself on this occasion. He earned the Victoria Cross by carrying

GUJARAT  
DISTURBANCES,  
1857-1859.

Expedition  
against Bet,  
1859.

Fort  
Taken.

GUJARAT  
DISTURBANCES,  
1857 - 1859.

off a wounded man of Her Majesty's 28th Regiment under a very heavy fire. Treasure valued at 3½ lakhs of rupees was taken on board the *Proserpine* for safe custody. It was eventually restored to the Pupais of the temples, but most of the temples had been carefully plundered by the Waghers before the entry of the British force.

Dwarka Fort  
Taken.

Many of the fugitives from Bet took refuge in Dwarka, and Colonel Donovan's force having re-embarked proceeded to Dwarka to await the arrival of Colonel Scobie's small brigade. Scobie's force did not reach Dwarka till October 20th. The Naval Brigade under Lieutenant Sedley with sixteen officers and 110 men had already landed under very heavy matchlock fire, and thrown up a slight breastwork of loose stone within 150 yards of the walls. A field piece from the *Zenobia* and afterwards a thirty-two pounder were placed in position in this work. The successful result of the siege was mainly due to the determined bravery of this small naval force. They repulsed repeated sorties from the fort and inflicted severe losses on the enemy. As soon as the stores and ammunition could be landed, Colonel Donovan took up a position to the north-east of the fort, Colonel Scobie to the south-east, and Captain Hall occupied an intermediate position with detachments of Her Majesty's 33rd Regiment, the 11th Native Infantry, and Gujarāt Horse under Lieutenant Pym. The garrison made several determined attempts to break through Captain Hall's position, but they were on each occasion driven back with loss.

The first battery opened fire on the northern face of the fort on October 28th, while the *Zenobia* and the *Proserpine* poured a well-directed fire of shells on the houses and temples which sheltered the enemy towards the sea. The shells did immense execution and relieved the attack on the Naval Brigade which continued to hold its position with the greatest gallantry though several times surrounded by the enemy. On the night of the 31st October the garrison evacuated the fort and cut its way through a picket of Her Majesty's 28th Regiment, wounding Ensign Hunter and four men. A detachment under Colonel Christie followed the fugitives next morning and overtook them near Vasatra. A skirmish ensued, but they escaped without much loss and took refuge in the Barda hill. They continued to disturb the peace of Kathiyavada for several years. In one of the desultory skirmishes which followed, Lieutenants LaTouche and Hebbert were killed.

Rising in  
Nagar Parkar

While these events were in progress, Kharanji Hathi the Rāma of Nagar Parkar on the Sindh frontier of Gujarat, took up arms at the head of a band of Sodhās, plundered the treasury and telegraph office at Nagar Parkar, and released the prisoners in the jail. Colonel Evans commanded the field force which was employed against him for many months without any very definite results. The country is a desert and the Sodhās avoided a collision with the troops. The Rāma eventually submitted and peace was restored.

## APPENDIX III

### BHINMÁL,

BHINMÁL,<sup>1</sup> North Latitude 21° 42' East Longitude 72° 4', the historical Bhinmál, the capital of the Chirijakas from about the sixth to the ninth century, lies about fifty miles west of Abu hill. The site of the city is in a wide plain about fifteen miles west of the last outlier of the Abu range. To the east, between the hills and Bhinmál, except a few widely-separated village sites, the plain is chiefly a grazing ground with brakes of thorn and cassia bushes overtopped by standards of the camel-loved *pilu* *Salvadora persica*. To the south, the west, and the north the plain is smooth and bare passing westwards into sand. From the level of the plain stand out a few isolated blocks of hill, 500 to 800 feet high, of which one peak, about a mile west of the city, is crowned by the shrine of Chānunda the Śrī or Luck of Bhinmál. From a distance the present Bhinmál shows few traces of being the site of an ancient capital. Its 1500 houses cover the gentle slope of an artificial mound, the level of their roofs broken by the spires of four Jain temples and by the ruined state office at the south end of the mound. Closer at hand the number and size of the old stone-stripped tank and fortification mounds and the large areas honeycombed by diggers' for bricks show that the site of the present Bhinmál was once the centre of a great and widespread city. Of its fortifications, which as late as A.D. 1611, the English merchant Nicholas Ufflet, in a journey from Jhalor to Ahmedābād, describes as enclosing a circuit of thirty-six miles (21 kos) containing many fine tanks going to ruin, almost no trace remains.<sup>2</sup> The names of some of the old gates are remembered, Surya in the north-east, Śrī Lakshmi in the south-east, Saṅkhor in the west, and Jhalor in the north. Sites are pointed out

### Appendix III.

#### BHINMÁL: Description.

<sup>1</sup> The translations of the inscriptions and the bulk of the history are the work of Mr. A. M. T. Jackson of the Indian Civil Service.

<sup>2</sup> Finch in Kerr's Voyages, VIII, 301. Thirty years later the traveller Faverney (Bibliothèque, II, 87) has Barga. (Was on in Jolpur? to Bimal 15 kos. By to M. J. 1. 1. 4. 1. Of Jhalor Ufflet has left the following description. Jhalor is a castle on the top of a steep mountain three kos in ascent by a fine stone causeway broad enough for two men. At the end of the first kos is a gate and a place of guard where the causeway is enclosed on both sides with walls. At the end of the second kos is a double gate strongly fortified, and at the third kos is the castle which is entered by three successive gates. The first is very strongly plated with iron, the second not so strong with plates above for throwing down melted lead or boiling oil, and the third is thickly beset with iron spikes. Between each of these gates are spacious places of arms and at the inner gate is a strong portcullis. A bower within the castle is a splendid pagoda, built by the founders of the caste and ancestors of Ghazni (Gidney, Khan who were Gentiles). He turned Muhammadan and deprived his elder brother of this castle by the following stratagem. Having invited him and his women to a banquet which his brother requited by a similar entertainment he substituted chosen soldiers well armed instead of women, sending them two and two in a *dhuk* or litter who getting in by this device gained possession of the gates and held the place for the Great Moghal to whom it now (A.D. 1611) appertains being one of the strongest situated forts in the world. About half a kos within the gate is a goodly square tank cut out of the solid rock said to be fifty fathoms deep and full of excellent water. Quoted by Finch in Kerr's Voyages, VIII, 300-301.

## Appendix III.

BHIMMAL.  
Description.

as old gateways five to six miles to the east and south-east of the present town and though their distance and isolation make it hard to believe that these ruined remains were more than outworks, Uflet's testimony seems to establish the correctness of the local memory.<sup>1</sup> Besides these outlying gateways traces remain round the foot of the present Bhimmal mound of a's order and later wall. To the east and south the line of fortification has been so cleared of masonry and is so confused with the lines of tank banks which perhaps were worked into the scheme of defence, that all accurate local knowledge of their position has passed. The Guparāt gate in the south of the town though ruined is well marked. From the Guparāt gateway a line of mounds may be traced south and then west to the ruins of Pipaddnara perhaps the western gateway. The wall seems then to have turned east crossing the watercourse and passing inside that is along the east bank of the watercourse north to the south-west corner of the Jakop or Yaksha lake. From this corner it ran east along the south bank of Jakop to the Jhalor or north gate which still remains in fair preservation its pointed arch showing it to be of Musalmān or late (17th-18th century) Rājasth construction. From the Jhalor gate the foundations of the wall may be traced east to the Kanaksen or Kanāda tank. The area to the east of the town from the Kanāda tank to the Guparāt gate has been so quarried for brick to build the present Bhimmal that no sign remains of a line of fortifications running from the Kanāda tank in the east to the Guparāt gate in the south.

The site of the present town the probable centre of the old city, is a mound stretching for about three-quarters of a mile north and south and swelling twenty to thirty feet out of the plain. On almost all sides its outskirts are protected by well made thorn fences enclosing either garden land or the pens and folds of Rabāris and Bhils. The streets are narrow and winding. The dwellings are of three classes, the flat mud-roofed houses of the Madajāns or traders and of the better-to-do Brāhmins and craftsmen with eaved doors and fronts plastered with white clay. Second the tiled sloping-roofed sheds of the bulk of the craftsmen and gardeners and of the better-off Rabāris and Bhils, and third the thatched bee-hive huts of the bulk of the Rabāris and Bhils and of some of the poorer craftsmen and husbandmen. Especially to the north-west and west the houses are skirted by a broad belt of garden land. In other parts patches of watered crops are separated by the bare banks of old tanks or by stretches of plain covered with thorn and cacia bushes or roughened by the heaps of old buildings honey-combed by shatis sunk by scavengers for bricks. Besides the four spired temples to Parasūth the only outstanding building is the old *kuchel* or state office a mass of ruins which tops the steep south end of the city mound.

Of the 1400 inhabited houses of Bhimmal the details are, Mahājāns 175, chiefly Oswāl Vānis of many subdivisions; Shrivast Brāhmins, 260. Shrivast 35, Maga Brāhmins worshippers of the sun and priests to Oswāls, Sogārs, 30; Bāndhūras or Copper-printers, 35; Kāsāras or Brass-smiths 1, Ghārchis or Oilpressers, 30; Māhs or Gardeners, 25; Kāthins or Woodworkers, 12; Bhāts 120 including 80 Ginnas or Grain-carriers.

<sup>1</sup> The names of these gateways are Shrajpm about six miles (4 kos) east of Bhimmal near Khatapur at the site of a temple of Mahādev; Savidar about six miles (4 kos) to the south near a temple of Hanumān; Dharandhar near Vagdar about six miles (4 kos) west of Bhimmal at the site of a large well; Koshimbivao about six miles (4 kos) to the north near Nartan at the site of a large well and stones. Rottay Lal Pacht.

and 40 Rājūhats or Brāhṃ Bhāts, Genealogists<sup>1</sup>, Kumhārs or Potters, 12; Musalmān Potters, 4, Rehbaris or Herdsmen, 70<sup>2</sup>; Shādhs Beggars, 10, Shāhma Ahks Beggars, 10; Kotwāl and Panjāra Musalmāns, 15, Lohars or Blacksmiths, 3, Dajis or Tailors, 12; Nais or Barbers, 7; Bhūmias that is Solauki Jagudās, 15<sup>3</sup>; Kavās Bhūmias servants, 12, Jāts Cultivators, 2; Deshastris or Saturday Oilheggers, 1; Achāryas or Funeral Brahmans, 1, Dhobis Drumbeaters, 12. Patris or Professionals that is Dancing Girls, 30, Turki Voharas that is Alemons, 2, Vishayati Musalmān Paṭhuk-makers, 1; Rangrez or Dyers, 2; Mochns or Shoemakers, 30; Kurnas or Sukāvat that is Masons, 6; Churigars Musalmān Ivory bangle-makers, 2, Jātyas or Tanners, 17, Khatiks or Butchers working as tanners, 1, Sargaras, Bhil messengers, 1; Bhils, 120, Turgars or Arrow-makers, 5, Goradas priests to Bombas leather-workers, 2, Bombas literally Weavers now Leather-workers, 10, Wāghna Castrator, 1, Muāsīs Musalmān Drummers, 8, Mehtars or Sweepers, 1. •

Inside of the town the objects of interest are few. The four temples of Pārasuāth are either modern or altered by modern repairs. A rest-house to the south of a temple of Barāgi or Varāha the Boar in the east of the town has white marble pillars with inscriptions of the eleventh and thirteenth centuries which show that the pillars have been brought from the ruined temple of the sun or Jag Svām Lord of the World on the mound about eighty yards east of the south or modern Guparāt gate. In the west of the town, close to the wall of the enclosure of the old Mahalakshmi temple, is a portion of a white marble pillar with an

## Appendix III.

BHINMAL.  
People.

Objects.  
In the Town

<sup>1</sup>The Shūmāhī Bhāra-Bhāts are of the following subdivisions. Dhondaleshiar, Hā, Heta, Loh, Porshke, Pitah, and Vāniz. They say Shūmāhī is their original home.

<sup>2</sup>The local explanation of Rehbari is liver out of the way. Their subdivisions are: At, Barod, Boggaro, Dag dhi, Gāron, Gogela, Kilotia, Karantha, Nāron, Patna, Pāndia, Rop. All are strong dark full-bearded men.

<sup>3</sup>The importance of Bhinmal as a centre of population is shown not only by the Shūmāhī Brāhmins and Vāns who are spread all over Gujarat, but by the Pārwas—class of Vāns now represented in the native town who are said to take their name from a suburb of Bhinmal. Oswalds, almost all of whom are Shāyaks or followers of the Jain religion, have practically sprung from Bhinmal. The origin of the name Oswald is (Harris Roy, As. Soc. III, 337) from Os the Mother or lack of Osmogari an ancient town and still a place of pilgrimage about eighteen miles north of Jodhpur. The Oswalds were originally Rājputs of several classes including Pārwas but mainly Solaukis and so apparently (Tod's Western India, 200) of Gurjara origin. Equally of Gurjara origin are the Shūmāhī Vāns who hold a specially high place among Western Indian Jāns. The care taken by the Jāns to secure foreign conquerors within their fold is notable. The Tithādkar is a Rājā who by piety and other virtues attracted *moksha*. (Citation) The fifty-four worshippers *attama-purush*, the forty-four *tithādkars*, the twelve *chakravartis*, the nine *baladras* and the nine *casadras* are Rājās, most of them great conquerors (Trans. Royal Asiatic Society, III 338-341). The local story is that the Solaukis were called to help the people of Shūmāhī to resist the Songara Rājputs of Jhālor who took Bhinmal about A.D. 1200. Before that the Shūmāhīs and Solaukis were enemies. This tradition of hostility is interesting as it may go back to A.D. 710 when Mūlaka Solauki transferred the seat of power from Bhinmal to Audalavīda Patan. (See below page 469.) A class who trace to Bhinmal are the Pīdās or Kālīs of Marwā (Marwār Castes, 41). They claim descent from Rājput men and Brāhmin women. In any part of the tradition the women still keep separate neither eating with nor using the same vessels as their husbands.

<sup>4</sup>These dancing girls hold land. They are said to have been brought by the Songara Rājputs, who according to the local account retreating from Ala-ud-din Khilji (A.D. 1200) took Bhinmal from the Shūmāhī Brāhmins.

<sup>5</sup>The Jātyas all Hindus of the three subdivisions Bahā, Smakaria, and Tadvāna came from Mandu near Dhar in Central India. The name is locally derived from *jatukarta* a skin.

## Appendix III.

BHINMAL.  
Objects

## Surroundings.

inscription dated S. 1342 (A.D. 1286) which apparently has been brought from the same ruined sun temple. In the *kacheri* ruins at the south end of the mound the only object of interest is a small shrine to Mida with two snakes supporting her seat and above in modern characters the words Nágane the *kuldai* or tribe guardian of the Ráhtors.

The chief object of interest at Bhinmal is the ruined temple of the Sun on a mound close to the south of the town. Of this temple and its inscriptions details are given below. About fifty yards west of the Sun temple are the remains of a gateway known as the Gujarát gateway. This modern name and the presence near it of blocks of the white quartz-marble of the Sun temple make it probable that the gateway is not older than Muslim or eighteenth century Ráhtor times. Close to the west of the gate is Khan Biva the Salt Well an old step and water bag well with many old stones mixed with brick work. About a hundred yards south of the Gujarát gate, in a brick-walled enclosure about sixteen yards by eight and nine feet high topped by a shield pinnaclet, is the shrine of Mahadeva Naulakheshwar. An inscription dated S. 1800 (A.D. 1744) states that the enclosure marks the site of an old temple to Naulakheshwar. About fifty yards east of the Naulakheshwar shrine is a large brick enclosure about seventy-five yards square with walls about twelve feet high and a pointed-arched gateway in the Moslem wave-edged style. On entering, to the left, is a plinth with a large Hanuman and further to the left in domed shrines are a Ganpati and a Mátá. A few paces south is Brahma's Pool or Brahmakhund with steep steps on the west and north, a rough stone and brick wall to the east, and a circular well to the south. The pool walls and steps have been repaired by stones taken from Hindu temples or from former decorations of the pool on some of which are old figures of Matas in good repair. The story is that Som, according to one account the builder of the Sun temple according to another account a restorer of Shrinmal, wandering in search of a cure for leprosy, came to the south gate of Shrinmal. Som's dog which was suffering from mange disappeared and soon after appeared sound and clean. The king traced the dog's footmarks to the Brahmakhund, bathed in it, and was cured. As a thank-offering he surrounded the pool with masonry walls. To the south of the pool, to the right, are an underground *ling* sacred to Patishwar the lord of the Under World and south of the *ling* a small domed shrine of Chandi Devi. To the left, at the east side of a small brick enclosure, is a snake-canopied *ling* known as Chandeshwar ling about with strings of *radáksh* *Elencarpus ganitrus* beads.<sup>1</sup> In front of Chandeshwar's shrine is a small inscribed stone with at its top a cow and calf recording a land grant to Shrinmalí Bráhmans. About forty yards north-east of the Brahmakhund a large straggling heap of brick and earth, now known as Lakshmináthala or Lakshmi's settlement, is said to be the site of a temple to Lakshmi built, according to the local

<sup>1</sup> According to a local story there was a hermitage of Jangams near the temple of Jagandeva the Sun-God and a hermitage of Bharatis near Chandeshwar's shrine. In a fight between the rival ascetics many were slain and the knowledge where their treasure was stored passed away. When repairs were made in A.D. 1814 (S. 1870) the Bharati hermitage was cleared. Two large earthen pots were found one of which still stands at the door of Chandeshwar's temple. These pots contained the treasure of the Bharatis. In A.D. 1814 nothing but white dust was found. Most of the dust was thrown away till a Jain ascetic came and examined the whole dust. The ascetic called for an iron rod, heated the rod, sprinkled it with the white dust, and the iron became gold.

legend, by a Brāhman to whom in return for his devotedness Lakshmi had given great wealth. The hollow to the south-east is known as the Khandālia pool. About fifty yards south-east at the end of a small enclosure is a shrine and ristern of Jageshwar, said to be called after a certain Jag who in return for the gift of a son built the temple. Several oil carved and dressed stones are built into the walls of this temple. About seventy-five yards further south-east a large area rough with heaps of brick is said to be the site of an old Vulliya-Sāla or Sanskrit College. This college is mentioned in the local Mahātmya as a famous place of learning the resort of scholars from distant lands.<sup>1</sup> The local account states that as the Bhils grew too powerful the Brāhmins were unable to live in the college and retired to Dholka in north Gujarāt.

The slope and skirts of the town beyond the thorn-fenced enclosures of Bhils and Rākshis lie in heaps honeycombed with holes hollowed by searchers for bricks. Beyond this fringe of fenced enclosures from a half to a whole mile from the city are the bare white banks of pools and tanks some for size worthy to be called lakes. Of these, working from the south northwards, the three chief are the Nimbāh or Narmukhsarovar, the Goni or Gayaknūl, and the Talbā or Trimbaksarovar. The Nimbali tank, about 300 yards south-east of the college site, is a large area opening eastwards whence it draws its supply of water and enclosed with high bare banks scattered with bricks along the south west and north. The lake is said to be named Nimbali after a Vāni to whom Mahādeva granted a son and for whom Mahādeva formed the hollow of the lake by plunging it with his thunderbolt. About half a mile north-east of Nimbali a horseshoe bank fifteen to thirty feet high, except to the open east, is the remains of the Goni lake. Banks of stone along the foot of the north-west and north-east banks shew that portions at least of these sides were once lined with masonry. A trace of steps remains at a place known as the Gan Ghar or Cowgar. The lake is said to have been named Goni after a Brāhman whose parents being eaten by a Rākshas went to hell. For their benefit Goni devoted his life to the worship of Vishnu and built a temple and lake. In reward Vishnu gave to the water of the lake the merit or causing virtue of the water of Gāyā. In the foreground a row of small *chattris* or pavilions marks the burying ground of the Mahajan or high Hindu community of Bhinmal. Behind the pavilions are the bare banks of the Talbā lake. At the west end is the Bombāro well and near the south-west is the shrine of Trimbakeshvar Mahadev. This lake is said to have been made in connection with a great sacrifice or *yag*, that is *yajna*, held by Brāhmins to induce or to compel the god Trimbakeshvar to slay the demon *Trimbaka*. Beginning close to the south of Talbā lake and stretching north-west towards the city is the Karādā Sarovar or Karādā lake said to have been built by Kanaksen or Kanishka the great founder of the Skythian era (c. 678). On the western bank of the lake stands an open air *ling* of Kṛṣṇiteshwar.<sup>2</sup> At the south end of the Karādā

## Appendix III.

## BHINMAL.

## . Objects.

## Surroundings.

<sup>1</sup> According to Alberuni (A.D. 1030) the Brahmasiddhanta was composed by Brahmagupta the son of Jashu from the town of Bhilānāda between Multan and Admlwāra. Saclean's Translation, I. 153. Another light of the college was the Sanskrit poet Magha, the son of Shimali parents, who is said to have lived in the time of Bhoj Rāja of Ujjain (c. 1010-1040). Mārwar Castes, 68.

<sup>2</sup> The local account explains the origin of the name Kanak which also means gold by the story of a Bhil who was drowned on the waxing fifth of Bhādarvā. The Bhil's wife who was with him failing to drown herself prepared a funeral pyre. Mahādeva pleased with the woman's devotion restored her husband to life and made his body shine like gold. As a thankoffering the Bhil enlarged the tank and built a shrine to Kṛṣṇ Mahādeva.

## Appendix III.

BHINMAL.

Object.

Surroundings.

lake, which stretches close to the fenced enclosures round the city, are the remains of a modern bastion and of a wall which runs north-west to the Jhabor gate. Beyond the site of the bastion is an enclosure and shrine of Maheswar Mahadev. To the north and north-west of the Karnat sea lie four large tanks. Of these the most eastern, about 300 yards north-west of Kharadā, is Brahmisarovar a large area fed from the north and with high broken banks. Next about 500 yards north-west lies the far-stretching Vankund or Forest Pool open to the north-east. About 800 yards west is Gautam's tank which holds water throughout the year. The banks of brick and *konkar* form nearly a complete circle except at the feeding channels in the east and south. In the centre of the lake is an islet on which are the white-stone foundations (18' x 12') of Gautam's hermitage. On the bank above the east feeding-channel is an image of Hanuman and on the east side of the southern channel at the foot of the bank is a white inscribed stone with letters so worn that nothing but the date S. 1106 (v. p. 1021) has been made out. Of the balls of *konkar* or nodular limestone which are piled into the bank of the tank those which are pierced with holes are lucky and are kept to guard wooden partitions against the attacks of insects. The last and westmost of the north row of tanks is the Jalkop properly Jakshkop that is the Yaksha's Pool about 600 yards south-west of the Gautam tank and close to the north-west of the town.<sup>1</sup> This tank holds water throughout the year and supplies most of the town's demand. Along the south bank of the Jalkop, where are tombs a shrine to Bharav and a ruined mosque, the line of the later city walls used to run. At the south-east corner of the tank are three square masonry plinths each with a headstone carved with the figure of a man or woman. One of the plinths which is adorned with a pillared canopy has a stone carved with a man on horseback and a standing woman in memory of a Tehsildar of Bhinmal of recent date (S. 1801; A.D. 1812) whose wife became *Sati*. About 200 yards south-east is a row of white *pāli* or memorial slabs of which the third from the south end of the row is dated S. 1245 (v. p. 1186). On the south-east bank is the shrine of Nimghorn Bharav at which Shrivaks as well as other Hindus worship. In the centre of the shrine is a leaning pillar about five feet high with four fronts, Hanuman on the east, a standing Snake on the south, a Sakti on the west, and Bharav on the north. To the south of the pillar, about a foot out of the ground rises a five-faced *ling* or pillar-home of the god one facing each quarter of the heaven and one uncarved facing the sky. Close to a well within the circuit of the lake near the south-east corner is a stone inscribed with letters which are too worn to be read. At the east end of the north bank under a *pāl* *Salvadora persica* tree is a massive seated figure still worshipped and still dignified though the features have been broken off, and the left lower arm and leg and both feet have disappeared. This is believed to be the image of the Yaksha king who made the tank. Details are given Below pages 456-458. To the west of the seated statue are the marks of the foundations of a temple, shrine hall and outer hall, which is believed to have originally been the shrine of Yaksh. About a hundred yards west, under a pillared canopy of white quartz, are two Musalmān

<sup>1</sup> The local explanation of the name Yaksha's Pool is that Ravana went to Abaku the city of the great Yaksha Kuber a god of wealth and stole Pushpak Kuber's *vinda* or carrier. Kuber in sorrow asked his father what he should do to recover his carrier. The father said Worship in Shrināl. Kuber came to Shrināl and worshipped Brahma who appeared to him and said: When Rāmachandra destroys Ravana he will bring back Pushpak.

graves in honour of Ghazni Khān and Ihmāl Khān who were killed about 400 years ago at Jhalor fighting for Shrināl. In obedience to their dying request their Bhāts brought the champions' bodies to Yaksh's tank. The white quartz, the shape of the pillars, and an inscription on one of them dated S. 1333 (A.D. 1276), go to show that the stones have been brought from the Sun temple to the south of the town. To the north of the empy is a large step-well the Dadeh Well separated into an outer and an inner section by a row of Hindu pillars supporting flat architraves. Some of the stones have figures of goddesses and in a niche is an old goddess' image. The upper part of the well and the parapet are of recent brick work. On a low mound about 150 yards to the north is the shrine of Nilkanth Mahadev, with about a hundred pieces to the south-east a fine old step-well. The lake was fed from the south-west corner where is a silt trap built of stones in many cases taken from old temples and carved with the *chaitya* or horse-shoe ornament. Some of the stones have apparently been brought from the great white quartz Sun temple. Several of them have a few letters of the fourteenth century character apparently the names of masons or carvers. Some of the blocks are of a rich red sandstone which is said to be found only in the Rupe quarries eight miles south of Bhinmal.

On the right about half a mile south of the south-west corner of the Jankop lake, is a ruined heap but among trees called the Pipal Dwara or Gateway perhaps the remains of the western Gateway which may have formed part of the later line of fortifications which can be traced running south along the inner bank of the Jankop feeding channel. About a mile south of the Pipal Dwara are the lane banks of the large lake Bansaoyan the Desert Sea. To the north-west north and north-east its great earthen banks remain stripped of their masonry gradually sloping to the west and south the direction of its supply of water. The island in the centre is Lakhaon. This lake was made by Gauri or Parvati when she came from Sunda hill to slay the female demon Uttamya. When Parvati killed the demon she piled over her body Shri's hill which she had brought with her to form a burial mound. At the same time Parvati swept the tank, and crowned Shri's hill with a tower-like temple. This hill where lives the Sri or Luck of Shrināl, rises 500 feet out of the plain about a mile west of the town. It is approached from the south by a flight of unknown stones roughly laid as steps. The hill-top is smoothed into a level pavement of brick and cement. The pavement is supported on the east side by a lofty bastion-like wall. It is surrounded by a parapet about two feet high. On the platform two shrines face each other. To the left or south is the main temple of Lakshmi and to the right or north the smaller shrine of Sunda Mātā. The main shrine has a porch with pillars and shield frieze of white quartz limestone apparently spoils of the great Sun Temple. Three or four bells hang from the roof of the porch and some loose white stones apparently also from the Sun temple are scattered about. In the west wall of the main shrine facing east is the image of the Guardian of Bhinmal covered with red paint and gold leaf. The only trace of ornament on the outside of Lakshmi's shrine is in the north-face portion of a belt of the horse-shoe or *chaitya* pattern and a disc perhaps the disc of the Sun. The smaller shrine of Sunda Mātā to the right or north is square and flat-roofed. The ceiling is partly made of carved stones apparently prepared for, perhaps formerly the centro slabs of domes. The door posts and lintels are of white quartz marble. On the right door post are two short inscriptions of A.D. 1612 and 1664 (S. 1669 and 1691). A second pillar bears the date A.D. 1513

## Appendix III.

## BHINMAL.

Objects.  
Surroundings.

Appendix III.

BHINMAL.

Objects.

Surroundings.

(S. 1600). The roof is supported by four square central pillars which with eight wall pilasters form four shallow domes with lotus carved roof-stones from some other or some older temple. In a recess in the west wall, surmounted with a stone carved in the *chaitya* or horse-shoe pattern, is the Trident or *Trisula* of Śūṇḍa Mātā the only object of worship.

From the hill-top the mound of Bhinmal hardly seems to stand out of the general level. The mound seems hidden in trees. Only in the south gleam the white pillars of the Sun Temple and to the north rise the high mound of the old offices, and still further north the spires of the four temples of Parasnath. Beyond the town to the south and west spread green gardens fenced with dry thorn hedges. Outside of the garden enclosures to the south-east south and south-west run the lofty bare banks of dry lakes confused in places with the hues of old fortifications. To the north-west and north shine the waters of the Jaikop and Gautam tanks. Westwards the plain, dark with thorn brake and green with acacias, stretches to the horizon. On other sides the sea-like level of the plain is broken by groups of hills the Borta range along the north and north-east and to the east the handsomer Ratnagar, Thor, and Ram Sen rising southwards to the lofty clean-cut ranges of Dolala and Sanda.

Only two objects of interest in Bhinmal require special description, the massive broken statue of the Jaksha or Yaksha on the north bank of the Jaikop lake, and the temple to Jagsvān the Sun at the south-east entrance to the city.

Jaikop.

On the north bank of the Jaikop or Yaksha Lake,<sup>1</sup> leaning against the stem of a *pilu* or *jil* *Salvadora persica* tree is a massive stone about 4' high by 2' 6" broad and 1' thick. The block is carved with considerable skill into the seated figure of a king. The figure is greatly damaged by the blows of a mace. The nose and mouth are broken off, half of the right hand and the whole of the left hand and leg are gone and the feet and almost the whole of the seat or throne have disappeared. The figure is seated on a narrow lion-supported throne or *sukhasan* the right hand resting on the right knee and holding a round ball of stone about six inches in diameter. The left foot was drawn back like the right foot and the left hand apparently lay on the left knee, but as no trace remains except the fracture on the side of the stone the position of the left hand and of the left leg is uncertain. The head is massive. The hair falls about

<sup>1</sup> No local tradition throws light on the reason why this figure is called a Yaksha. The holding a ball in his hand suggests that he may have been a guardian Bhaṇḍa in some Buddhist temple and so remembered as a guardian or Yaksha. Or he may have been supposed to be a statue of the builder of the temple and so have been called a Yaksha since that word was used for a man of skillful architects and craftsmen. Trevor's *Rajataranginī*, I. 369. In the Vriji temples in Tirhut which Buddhist accounts make older than Buddhism the objects of worship were ancestral spirits who were called Yakshas. If the Buddhist legends of Saka settlements in Tirhut during Gautama's lifetime (A.D. 540) have any historical value these Vrijis were Sakas. As (J. As. Ser. VI. Tom. II. page 310) Yaka is a Mongol form of Saka the ancestral guardians would be Sakas. Compare in Eastern Siberia the Tarki tribe called Yakuts by the Russians and Sokhas by themselves, *Ecly. Brit.* XXIV. 725. This would explain why the mythic Yaksha was a guardian, a builder, and a white horseman. It would explain why the name Yaksha was given to the Baktrian Greeks who built stupas and conquered India for Asoka (J. As. Ser. VII. Vol. VI. page 170; Hecley in *Indian Antiquary*, IV. 101). It further explains how the name came to be applied to the Yüechi or Kushans who like the Yavanas were guardians white horsemen and builders. In Sindh and Kachh the word Yaksha seems to belong to the white Syrian horsemen who formed the strength of Muhammad Kusun's army, A.D. 712. (Tod's *Western India*, 197; Reinaud's *Fragmente*, 191; Briggs' *Farishtah*, IV. 404-409).

two feet from the crown of the head in four long lines of curls on to the shoulders, and, over the curls, or what seems more likely the curled wig, is a diadem or *mukut* with a central spike and two upright side ornaments connected by two round bands. The face is broken flat. It seems to have been clean shaven or at least beardless. A heavy rug hangs from each ear. A stiff collar-like band encircles the neck and strings of beads or plates hang on the chest too worn to be distinguished. On both arms are upper armlets, a centre lion-face still showing clear on the left armlet. On the right hand is a bracelet composed of two outer bands and a central row of beads. A light belt encircles the waist. Lower down are the *kandora* or hip girdle and the *hopul* or *dhoti* knot.<sup>1</sup> In spite of its featureless face and its broken hands and feet the figure has considerable dignity. The head is well-set and the curls and diadem are an effective ornament. The chest and the full rounded belly are carved with skill. The main fault in proportion, the overshortened lower arm and leg and the narrowness of the throne are due to the want of depth in the stone. The chief details of interest are the figure's head-dress and the ball of stone in its right hand. The head-dress seems to be a wig with a row of crisp round curls across the brow and four lines of long curls hanging down to the shoulders and crisp curls on the top of the head. The *mukut* or diadem has three upright faces, a front face over the nose and side faces over the ears joined together by two rounded bands. At first sight the stone ball in the right hand seems a coconut which the king might hold in dedicating the lake. Examination shows on the left side of the ball an outstanding semicircle very like a human ear. Also that above the ear are three rolls as if turban folds. And that the right ear may be hid either by the end of the turban drawn under the chin or by the fingers of the half-closed hand. That the front of the ball has been wilfully smashed further supports the view that it was its human features that drew upon it the Muslim mace. The local Brahmans contend that the ball is either a round sweetmeat or a handful of mud held in the right hand of the king during the dedication service. But Tappa a Brahmin-Bhat, a man of curiously correct information, was of opinion that the stone ball is a human head. Tappa gives the following tale to explain why the king should hold a human head in his hand. An evil spirit called Satka had been wasting the Brahmans by carrying off the head of each bridegroom so soon as a wedding ceremony was completed. The king vowed that by the help of his goddess Chammaṇḍa he would put a stop to this evil. The marriage of a hundred Brahman couples was arranged for one night. The king sat by. So long as the king remained awake the demon did not appear. When the hundredth marriage was being performed the king gave way to sleep. Satka dashed in and carried off the last bridegroom's head. The girl-bride awoke the king and said I will curse you. You watched for the officers, for me you did not watch. The king said to his lack Chammaṇḍa. What shall I do? Chammaṇḍa said Ride after Satka. The king rode after Satka. He overtook her fourteen miles out of Shrinuil and killed her. But before her

## Appendix III.

BHINMAL.

Objects.

Jaikop.

<sup>1</sup> The measurements are : Height 1'; head round the brow to behind the ear the back of the head not being cut free, 2' 6"; height of head-dress, 8"; length of face, 10"; length of ringlets or wig curls from the crown of the head, 2'; breadth of face, 9"; across the shoulders, 2' 3"; throat to waistband, 1'; waistband to loose hip-belt or *kandora*, 1' 3"; right shoulder to elbow, 1'; elbow to wrist, 9"; head in the right hand 5" high 7" across top; hip to broken knee, 1'; knee to ankle, 1' 5", foot broken off. Left shoulder to broken upper arm, 8"; left leg broken off leaving a fracture which shows it was drawn back like the right leg.

## Appendix III.

BHINMAL.

Objects.

Jaukop

death Satka had eaten the bridegroom's head. What is to be done the king asked Channuda. Trust me said his guardian. The king rode back to Shrināl. As he was entering the city the goddess pointed out to him a gardener or Māli and said Off with his head. The king obeyed. The goddess caught the falling head, stuck it to the bridegroom's neck, and the bridegroom came to life. Thus, ends the tale, the local Brāhmins are known as Shrinālis that is men with gardeners' heads. This meaning-making pun and the likeness of the stone-hull to a human head may be the origin of this story. On the other hand the story may be older than the image and may be the reason why the king is shown holding a human head in his hand. On the whole it seems likely that the story was made to explain the image and that the image is a Bhairav holding the head of a human sacrifice and acting as gatekeeper or guardian of some Buddhist or Sun-worshipping temple.<sup>1</sup> The appearance of the figure, its massive well-proportioned and dignified pose, and the long wiglike curls, like the bag wig on the figure of Chānd on the south-west or marriage compartment of the great Elephanta Caves, make it probable that this statue is the oldest relic of Shrināl, belonging like the Elephanta wigged figures to the sixth or early seventh century the probable date of the founding or refounding of the city by the Gurjjaras.<sup>2</sup> According to the local story the image stands about twenty paces east of the temple where it was originally enshrined and worshipped. The lie of the ground and traces of foundations seem to show about fifty paces west of the present image the sites of an entrance porch, a central hall or *mandap*, and a western shrine. The surface of what seemed the site of the shrine was dug about two feet deep on the chance that the base of the throne might still be in site. Nothing was found but loose brickwork. Mutilated as he is the Yaksha is still worshipped. His high day is the *A'shad* (July-August) fullmoon when as ruin-mediator between them and Indra the villagers lay in front of him *gagri*, that is wheat boiled in water and milk, butter, flour, molasses, and sugar.

<sup>1</sup> The Jains call the guardian figures at Sanchi Bhairava. Massey's Sanchi, pages 7 and 25. Bhairava is revered as a guardian by the Buddhists of Nepal and Tibet. Compare Burgess' Bandilha Rock Temples page 96. A connection between Bhairav and the Sun is shown by the practice among Ajmer Gujar women of wearing round the neck a medal of Bhairava before marriage and of the Sun after marriage.

<sup>2</sup> The Egyptians, Romans and Parthians are the three chief wig-wearers. Some of the Parthian kings (c. 250 - A.D. 240) had elaborate hair like perukes and frizzled beards. In Trajan's time (A.D. 133), fashions changed so quickly that Roman statues were hairless and provided with wigs. Goldman Histone Des Perses, II, 530. Compare Wagner's Manners, 69. The number of wigs in the Elephanta sculptures, probably of the sixth or early seventh century, is notable. In the panel of Siva and Parvati in Kailas are several figures with curly wigs. Burgess Elephanta, page 33; in the marriage panel one figure has his hair curled like a barrister's wig, Ditto 31; in the Ardhanarishwara compartment Garuda and two other figures have wigs, Ditto 22; the dwarf demon on which one of the guardians of the Trimurti leans has a wig, Ditto 44-45, finally in the west wing wigged figures uphold the throne, Ditto 47. Gandharvas in the Brāhmanic Rāvan cave at Elhura probably of the seventh century have curly wigs. Fergusson and Burgess, 435. Wigged images also occur in some of the Elhura Buddhist caves of the sixth or seventh centuries. Ditto, 370-371. In Ajanta caves I, II. and XXXIV. of the sixth and seventh centuries are cherubs and grotesques with large wigs. Among the Bāgh carvings and paintings of the sixth or seventh century are a king with baggy hair if not a wig and small human heads with full wigs: MS. Notes. Finally at the Chandi Sewa temple in Java of about the seventh century the janitor and other figures have large full-bottomed wigs curled all over. Indian Ant. for Aug. 1876, 240-241. On the other hand except the curly haired or Astrakan-capped music boys in Sanchi no trace of wigs seems to occur in the Bhilsa Sanchi or Bharut sculptures between the third century after and the third century before the Christian era. Compare Cunningham's Bharut and Bhilsa; Massey's Sanchi, Fergusson's Tree and Serpent Worship.




# BHINMÁL (ŚRIMÁL)

WEST


SOUTH

NORT



## TEMPLE OF JAG SVAMI THE SUN (Rumed)

Scale of Feet



The second and main object of interest is the ruined Sun temple in the south of the town on a brick mound about eighty yards east of the remains of the Gujarāt gateway. The brick mound which is crowned by the white marble pillars and the massive laterite ruins of the temple of Jagsvāmi Lord of the World has been so dug into that its true form and size cannot be determined. The size of many of the bricks  $1' 16'' \times 1' \times 3''$  suggests that the mound is older even than the massive laterite masonry of the shrine. And that here as at Multān about the sixth century during the supremacy of the sun-worshipping White Hūnas a temple of the Sun was raised on the ruins of a Buddhist temple or relic mound. Still except the doubtful evidence of the size of the bricks nothing has been found to support the theory that the Sun temple stands on an earlier Buddhist ruin. The apparent present dimensions of the mound are 12' broad 60' long and 20' high. Of the temple the north side and north-west corner are fairly complete. The east entrance to the hall, the south pillar of the hall, and with them the hall dome and the outer wall of the temple round the south and west of the shrine have disappeared. A confused heap of bricks on the top of the shrine and of the entrance from the hall to the shrine is all that is left of the spire and upper buildings. The materials used are of three kinds. The pillars of the hall are of a white quartzlike marble; the masonry of the shrine walls and of the passage round the north of the shrine is of a reddish yellow laterite, and the interior of the spire and apparently some other roof buildings are of brick. Beginning from the original east entrance the ground has been cut away so close to the temple and so many of the pillars have fallen that almost no trace of the entrance is left. The first masonry, entering from the east, are the two eastern pillars of the hall dome and to the north of this central pair the pillar that supported the north-eastern corner of the dome. Except the lowest rim, on the east side, all trace of the dome and of the roof over the dome are gone. The centre of the hall is open to the sky. The south side is even more ruined than the east side. The whole outer wall has fallen and been removed. The south-east corner the two south pillars of the dome and the south-west corner pillars are gone. The north side is better preserved. The masonry that rounds off the corners from which the dome sprung remains and along the rim of the north face runs a belt of finely carved female figures. The north-east corner pillar, the two north pillars of the dome, and the north-west corner pillar all remain. Outside of the pillars runs a passage about four feet broad and eleven feet high, and, beyond the passage, stands the north wall of the temple with an outstanding deep arched window above, with white marble seats and backs and massive pillars whose six feet shafts are in three sections square eightsided and round and on whose double-disc capitals rest brackets which support a shallow cross-cornered dome. At its west end the north passage is ornamented with a rich *gokla* or recess  $3\frac{1}{2}$  broad with side pillars  $3\frac{1}{2}$  feet high. On the west side of the dome the central pair of dome pillars and as has been noticed the north corner pillar remain. About three feet west of the west pair of dome pillars a second pair support the domed entrance to the shrine. The richly carved side pillars, a goddess with fly-flap bearers, and the lintel of the shrine door remain but the bare square chamber of the shrine is open to the sky. To the south of the shrine the entire basis of the south side of the spire, the outer circling or *pradakshana* passage and the outer wall of the temple have disappeared. The north side is much less ruinous. There remain

## Appendix III.

BHINMAL.  
Sun Temple.

## Appendix III.

## BHINMAL.

## Sun Temple.

The massive blocks of yellow and red trap which formed the basis of the spire, built in horizontal bands of deep cut cushions and in the centre of the north wall a niche with outstanding pillared frame, the circling passage with walls of plan trap and roof of single slabs laid across and the outer wall of the temple with bracket capituled pillars and a central deep-caved and pillared hanging window of white marble. The circling passage and the outer wall of the temple end at the north-west corner. Of the western outer wall all traces gone. The pillars of the temple are massive and handsome with pleasantly broken outline, a pedestal, a square, an eightsided band, a sixteensided band, a round belt, a narrow band of horned faces, the capital a piece of discs, and above the discs outstanding brackets each ending in a crouching four-armed male or female human figure upholding the roof. The six central dome pillars resemble the rest except that instead of the sixteensided band the inner face is carved into an urn from whose mouth overhang rich leafy festoons and which stand on a roll of cloth or a ring of cane such as women set between the head and the waterpot.<sup>1</sup> On the roof piles of bricks show that besides the spire some building rose over the central dome and eastern entrance but of its structure nothing can now be traced.

## History.

According to a local legend this temple of the Sun was built by Yayati the son of king Nahush<sup>2</sup> of the Chandravanshi or Moon stock. Yayati came to Shrinidhi accompanied by his two queens Sharnustha and Devyani, and began to perform severe austerities at one of the places sacred to Surya the Sun. Surya was so pleased by the fervour of Yayati's devotion that he appeared before him and asked Yayati to name a boon. Yayati said May I with god-like vision see thee in thy true form. The Sun granted this wish and told Yayati to name a second boon. Yayati said I am weary of ruling and of the pleasures of life. My one wish is that for the good of Shrinidhi you may be present here in your true form. The Sun agreed. An image was set up in the Sun's true form (apparently meaning in a human form) and a Hariya Brahman was set over it.<sup>3</sup> The God said Call me Jagat-Svami the Lord of the World for I am its only protector. According to a local Brahman account the original image of the Sun was of wood and is still preserved in Lakshmi's temple at Patan, in North Gujarat.<sup>4</sup> Another account makes the builder of the temple Shripunj or Jagson. According to one legend Jagson's true name was Kanak who came from Kashmir. According to the Brahman Bhit Tappa Jagson was a king of Kashmir of the Jamawal tribe who established himself in Bhinmal about 500 years before Kumarapala. As Kumarapala's date is A.D. 1186, Jagson's date would be A.D. 680.

<sup>1</sup> The ten feet of the pillars are thus divided: pedestal 2', square block 2', eightsided belt 18", sixteensided belt 18", round band 2", horned face belt 6", double disc capital 6".

<sup>2</sup> This according to another account is Nasik town.

<sup>3</sup> Hariya Brahman is said to mean a descendant of Hariyaji, a well known Brahman of Shrinidhi, so rich that he gave every member of his caste a present of brass vessels.

<sup>4</sup> This tradition seems correct. In the temple of Lakshmi near the Tripolia or Triple gateway in Patan are two standing images of *champa* Micheha champaca wood one a man the other a woman black and dressed. The male image which is about three feet high and thirteen inches across the shoulders is of the Sun Jagat Shām that is Jagat-Svami the World Lord: the female image, about 2' 6" high and 9" across the shoulders is Ranadevi or Randel the Sun's wife. Neither image has any writing. They are believed to be about 1000 years old and to have been secretly brought from Bhinmal by Shrinidhi Brahmins about A.D. 1400. Rao Bahadur Himatlal Dharajlal. Compare (Rajputana Gazetteer, II 282) in the temple of Balarikh at Baher about a hundred miles south-west of Jodhpur a wooden image of the sun.

According to the common local story Jagson was tormented by presence of a live snake in his belly. When Jagson halted at the gate of Bhinmal in the course of a pilgrimage from Kashmir to Dwarka, he fell asleep and the snake came out at his mouth. At the same time a snake issued from a hole close to the city gate and said to the king's belly snake 'You should depart and cease to afflict the king.' 'There is a fine treasure in your hole' said the belly snake. 'How would you like to leave it? Why then ask me to leave my home?' The gate snake said 'If any servant of the king is near let him hearken. If some leaves of the *kir* Capparis aphylla tree are plucked and mixed with the flowers of a creeper that grows under it and boiled and given to the king the snake inside him will be killed.' 'If any servant of the king is near' retorted the king's snake 'let him hearken. If boiling oil is poured down the hole of the gate-snake the snake will perish and great treasure will be found.' A clever Kayasth of the king's retinue was near and took notes. He found the *kir* tree and the creeper growing under it, he prepared the medicine and gave it to the king. The withering of the snake caused the king so much agony that he ordered the Kayasth to be killed. Presently the king became sick and the dead snake was thrown up through the king's mouth. The king mourned for the dead Kayasth. So clever a man, he said must have made other good notes. They examined the Kayasth's note book, poured the boiling oil down the hole, killed the gate-snake, and found the treasure. To appease the Kayasths and the two snakes lakhs were spent in feeding Brahmins. With the rest a magnificent temple was built to the Sun and an image duly enshrined. Numerous stories were afterwards added by Vishvakarma.

## Appendix III.

BHINMAL.  
Sun Temple.

The legends of Bhinmal are collected in the Shrinmal Mahatmya of the Skanda Purana a work supposed to be about 400 years old. According to the Mahatmya the city has been known by a different name in each of the chief cycles or Yugas. In the Satyayug it was Shrinmal in the Tretayug Ratunmal, in the Dwaparyug Pashpanmal, and in the Kaliyug Bhinmal. In the Satyayug Shrinmal or Shrinagar had 84 Chandas, 336 Kshetrapals; 27 Varibas; 101 Suryas, 51 Matas; 21 Bredispatis; 300 to 11,000 Lingas, 88000 Rudras, 999 Wells and Tanks, and 34 krosas of *tirthas* or holy places. At first the plain of Bhinmal was sea and Bhargharishi called on Surya and the sun dried the water and made it land. Then Braghu started a hermitage and the saints Kashyap, Atri, Baradwaj, Gautam, Jamdagni, Vishvamitra, and Vashista came from A'bu to interview Braghu. Gautam was pleased with the land to the north of Braghu's hermitage and prayed Trimbakeshwar that the place might combine the holiness of all holy places and that he and his wife Ahilya might live there in happiness. The God granted the sage's prayer. A lake was formed and in the centre an island was raised on which Gautam built his hermitage the foundations of which may still be seen. The channel which feeds Gautam's lake from the north-east was cut by an ascetic Brahman named Yajnasika and in the channel a stone is set with writing none of which but the date S 1117 (A.D. 1060) is legible. Some years after Gautam had settled at Shrinmal a daughter named Lakshmi was born in the house of the sage Braghu. When the girl came of age Braghu consulted Naradji about a husband. When Naradji saw Lakshmi, he said; This girl can be the wife of no one but of Vishnu. Naradji went to Vishnu and said that in consequence of the curse of Durvasarashi Lakshmi could not be born anywhere except in Braghu's house and that Vishnu ought to marry her. Vishnu agreed. After the

Legends.

## Appendix III.

BHINMAL.  
Legends.

On marriage the bride and bridegroom bathed together\* in the holy Trimbak pond about half a mile east of Gantani's island. The holy water cleared the veil of forgetfulness and Lakshmi remembered her former life. The *devatas* or guardians came to worship her. They asked her what she would wish. Lakshmi replied, May the country be decked with the houses of Brāhmanas as the sky is decked with their carriages the stars. Bhagwān that is Vishnu, pleased with this wish, sent messengers to fetch Brāhmanas and called Vishvakarma the divine architect to build a town. Vishvakarma built the town. He received golden bangles and a garland of gold lotus flowers and the promise that his work would meet with the praise of men and that his descendants would rule the art of building. This town said the Gods has been decked as it were with the garlands or *māla* of Sri or Lakshmi. So it shall be called Shrinmāl. When the houses were ready Brāhmanas began to gather from all parts.<sup>1</sup> When the Brāhmanas were gathered Lakshmi asked Vishnu to which among the Brāhmanas worship was first done. The Brāhmanas agreed that Gantani's claim was the highest. The Brāhmanas from South obtruded and withdrew in anger. Then Vishnu and Lakshmi made presents of cloths money and jewels to the Brāhmanas and they, because they had settled in the town of Shrinmāl, came to be known as Shrinmālī Brāhmanas.

The angry South Brāhmanas in their own country worshipped the Sea. And at their request Saundra sent the demon Sarika to ruin Shrinmāl. Sarika carried off the marriageable Brāhman girls. And the Brāhmanas finding no one to protect them withdrew to Ālma. Shrinmāl became waste and the dwellings ruins.<sup>2</sup> When Shrinmāl had long lain waste a king named Shripunj, according to one account suffering from wounds according to another account stricken with leprosy, came to the Brāhmanakund to the south of the city and was cured.<sup>3</sup> Thankful at heart Shripunj collected Brāhmanas and restored Shrinmāl and at the Brāhmanakund built a temple of Chandish Mahādev. When they heard that the Shrinmāl Brāhmanas had returned to their old city and were prospering the

<sup>1</sup> The detail . . . From Kansika 500, from the Ganges 10 000 from Gaya 500, from Kālinjar 700 from Mahendri 300, from Knudal 1000 from Vem 500, from Surparak 808, from Gokan 1000, from Godavari 108, from Paddis 125, from the hill Hījayan or Gumar 115, from the Narbad 110, from Gomati 70, and from Nandiyardhan 1000.

<sup>2</sup> According to one account (Mewar Castles, 61) these South Brāhmanas are represented by the present Pushkar Brāhmanas. In proof the Pushkars are said to worship Śundarī Untadevi riding on a camel. This must be a mistake. The Pushkars are almost certainly Gujaras.

<sup>3</sup> Details are given above under Objects. The local legends confuse Shripunj and Jagson. It seems probable that Jagson was not the name of a king but is a contraction of Jagatsvami the title of the Sun. This Shripunj or at least the restorer or founder of Shrinmāl, is also called Kanak, who according to some accounts came from the east and according to others came from Kashmir. Kanak is said also to have founded a town Kanakvati near the site of the present village of Chlakla about eleven miles (7 kos) east of Bhinmāl. This recollection of Kanak or Kanaksen is perhaps a trace of the possession of Mārwāra and north Gujarat by the generals or successors of the great Kushān or Śaka emperor Kanak or Kanishka the founder of the Śaka era of A.D. 78. According to the local Bhats this Kanak was of the Jūnghrabal caste and the Pradiya branch. This caste is said still to hold 300 villages in Kashmir. According to local accounts the Shrinmālī Brāhmanas, and the Dewala and Devra Rajputs all came from Kashmir with Kanak. Tod (Western India, 213) notices that the Annals of Mewar all trace to Kanaksen of the Sun race whose invasion is put at A.D. 100. As the Shrinmalis and most of the present Rajput chiefs are of the Gujar stock which entered India about A.D. 450 this tracing to Kanishka is a case of the Hindū law that the conqueror assimilates the traditions of the conquered that with the tradition he may bind to his own family the Śrī or Luck of his predecessors.

Brāhman of Sindh once more sent Sarika to carry away their marriage-able daughters. One girl as she was being haled away called on her home-goddess and Sarika was spell-bound to the spot. King Shripunjab came up and was about to slay Sarika with an arrow when Sarika said Do not kill me. Make some provision for my food and I will henceforth guard your Brāhman. The king asked her what she required. Sarika said Let your Brāhman at their weddings give a dinner in my honour and let them also marry their daughters in unwashed clothes. If they follow these two rules I will protect them. The king agreed and gave Sarika leave to go. Sarika could not move. While the king wondered the home-goddess of the maiden appeared and told the king she had stopped the fiend. Truly said the king you are the rightful guardian. But Sarika is not ill disposed let her go. On this Sarika fled to Sindh. And in her honour the people both of Shrimāl and of Jodhpur still marry their daughters in unwashed clothes.<sup>1</sup> The Brāhman girls whom Sarika had carried off had been placed in charge of the snake Kankal lord of the nether world. The Brāhman found this out and Kankal agreed to restore the girls if the Brāhman would worship snakes or *nāgs* at the beginning of their *shrāddh* or after-death ceremonies. Since that time the Shrimāl set up the image of a Nāg when they perform death rites. Other legends relating to the building of the Jagsyam or Sun temple, to the temple of Chandish Mahadev near the Brahmankund and to the making of the Jatkap lake are given above. The dates preserved by local tradition are S. 222 (A.D. 166) the building of the first temple of the Sun; S. 265 (A.D. 209) a destructive attack on the city; S. 491 (A.D. 138) a second sack by a Rakshasa, S. 700 (A.D. 641) a re-building, S. 900 (A.D. 844) a third destruction, S. 955 (A.D. 899) a new restoration followed by a period of prosperity which lasted till the beginning of the fourteenth century.

That Shrimāl was once the capital of the Gurjjaras seems to explain the local saying that Jagatsen the son of the builder of the Sun temple gave Shrimāl to Gujarāt Brāhman whose Gujarāt is a natural alteration of the forgotten Gurjjaras or Gurjjar Brāhman. That Shrimāl was once a centre of population is shown by the Shrimāl subdivisions of the Brāhman and Vām castes who are widely scattered over north Gujarāt and Kathavada. Most Shrimāl Vāms are Shrivāks. It seems probable that their history closely resembles the history of the Osval Shrivāks or Jains who take their name from the ancient city of Osāl about fifteen miles south of Jodhpur to which they still go to pay vows. The bulk of these Osāl Vāms, who are Jains by religion, were Solanki Rajputs before their change of faith which according to Jain records took place about A.D. 715 (S. 800).<sup>2</sup> The present Bhinmal

## Appendix III.

BHINMAL.  
Legends.

Caste  
Legends.

<sup>1</sup> According to a local tradition the people in despair at the ravages of Sarika turned for help to Devi. The goddess said: Kill buffaloes, eat their flesh, and wear their hides and Sarika will not touch you. The people obeyed and were saved. Since then a dough buffalo has taken the place of the flesh buffalo and unwashed cloth of the bleeding hide. Another version sounds like a reminiscence of the Tartar origin of Krishna. The goddess Khamangiri persuaded the Lord Krishna to celebrate his marriage clad in the raw hide of a cow. In the present era unwashed cloth has taken the place of leather. MS. Note from Mr. Ram Lal Pandit.

<sup>2</sup> The tradition recorded by Tod (Western India, 209) that the Gurjjaras are descended from the Solankis of Anahilavada, taken with the evidence noted in the section on History that the Chāvādās or Chāpas and the Parihāras are also Gurjjaras makes it probable that the Chohāns are of the same origin and therefore that the whole of the Agnikulas were northern conquerors who adopting Hinduism were given a place among Rajputs or Kshatriyas.

<sup>3</sup> Epigraphia Indica, II. 40-41.

## Appendix III.

## BHINMAL.

Caste  
Legends.

bards claim the Oswals as originally people of Shrinál. Lakshmi they say when she was being married to Vishnu at Shrinál looked into her bosom and the Jariya goldsmiths came forth: she looked north and the Oswals appeared, east and from her loom were born the Purwals.<sup>1</sup> From her lacy necklace of flowers sprang the Shrimáli Bráhmans. According to other accounts the Shrimáli Bráhmans and Vánis were of Kashmír origin of the Jamawála caste and were brought to south Márwár by Jag Som by which name apparently Kanaksen that is the Kusha or Kshatrapa (A.D. 78-250) dynasty is meant. They say that in S. 59 (A.D. 70) Bugra an Arab laid the country waste and that from fear of him the Shrimáli Bráhmans and Vánis fled south. Another account giving the date A.D. 744 (S. 800) says the assailants were Songara Rajputs. The Shrimáls were brought back to Bhinnál by Abhai Singh Ráhtor when viceroy of Gujará in A.D. 1694 (S. 1750).

The memory of the Gurjaras; who they say are descended from Garab Rishi, lingers among the Bhats or bards of Shrinál. They say the Gurjaras moved from Shrinál to Pushkar about ten miles north-west of Ajmír and there dug the great lake. They are aware that Gurjaras have a very sacred burning ground at Pushkar or Pokarn and also that the Savitri or wife of Brahma at Pokarn was a Gurjara maiden.

But as the leading Gurjaras have dropped their tribe name in becoming Kshatriyas or Rajputs the bards naturally do not know of the Gurjaras as a ruling race. The ordinary Gurjara they say is the same as the Rehbári; the Bad or High Gujars to whom Krishna belonged are Rajputs. The bards further say that the Sompuras who live near Pushkar (Pokarn north of Ajmír) and are the best builders who alone know the names of all ornamental patterns are of Gurjara descent and of Shrinál origin. They do not admit that the Chavadas were Gurjaras. In their opinion Chavadas are the same as Bharads and came north into Márwár from Dánta in Jhalaváda in north-east Káthiaváda. The Choháns they say came from Sámbar to Ajmír, from Ajmír to Delhi, from Delhi to Nágur north of Jodhpur, from Nágur to Jodhpur, from Jodhpur to Bhadgaon thirty miles south of Bhinnál and from Bhadgaon to Sirohi. According to a local Jaghirdár of the Devra caste the Choháns' original seat was at Jhalor forty miles north of Shrinál. They say that in the eighteenth century the Solankis came north from Pátan in north Gujarat to Hiya in Palanpur where they have still a settlement, and that from Hiya they went to Bhinnál.

In connection with the Sun temple and the traces of sun worship among the Jains, whose *gurus* or religious guides have a sun face which they say was given them by the Rána of Chitor, the existence in Bhinnál of so many (thirty-five) houses of Shevaks is interesting. These Shevaks are the religious dependents of the Oswál Shráyaks. They are stranger high-nosed hatchet-faced men with long lank hair and long beards and whiskers. They were originally Magha Bráhmans and still are Vaishnavas worshipping the sun. They know that their story is told in the Námagranth of the Surya Purána. The Bhinnál Shevaks know of sixteen

<sup>1</sup> According to Katta, a Bráhma-Bhát of remarkable intelligence, the Oswals include Rajputs of a large number of tribes, Aulaks, Bhatts, Boráns, Buruds, Chováns, Gehlots, Gohils, Jádavs, Makvanas, Mohils, Parmárs, Ráhtors, Shálas, Tilars. They are said to have been converted to the Jain religion in Osianagara in Sahyat Bia Varsh 23 that is in A.D. 165.

branches or *stikas* but remember the names of ten only : Aboti, Bhinmāla, Devira, Hingota, Kawara, Lalār, Mahtariya, Mundiara, Sagarwāla, and Shānda. The story of these Maghās in the Surya and Bhayishya Purāṇas, how they were brought by Garuda from the land of the Śakas and were fire and sun worshippers, gives these Shovās a special interest. The Devalās are believed to have come from Kaṇamīr with Jog Svāmi who is said to have been a Yūksa of the Rākshas division of Parihār Rajputs. The other division of Parihārs were *gorsas* or Abu who in virtue of the fire baptism of the Agnikūṇḍ became Kshatryās. The Devalās are supposed to got their name because they built Jog Som's temple at Bhinmāl. The Devra Rajputs whose head is the Sirohi chief and who according to the bards are of Chohan descent, came at the same time and marry with the Devalās. With this origin from Kaṇamīr it is natural to associate the Devras and Devalās with the Devaputras of the Samudragupta (A.D. 370-395) inscription. Of Hūca or of Javla, the tribe name of the great Hūca conquerors Toramana and Mihirakula (A.D. 450-530), few signs have been traced. The Jaghirdār of Devra knows the name Hūca. They are a Rākshasa people he says. He mentions Honots or Sonots who may be a trace of Hūcas, and Hūcals in Kūtkiāwāla and a Hūci subdivision among the Kanbis of Marwār. Javla he does not know as a caste name.

The historical interest of Shrināl centres in the fact that it was long the capital of the main branch of the great northern race of Gurjjaras. It is well known that many mentions of the Gurjjaras and their country in inscriptions and historical works refer to the Chaulukya or Solanki kingdom of Anahavāda (A.D. 951-1242) or to its successor the Vaghela principality (A.D. 1219-1304). But the name Gurjjara occurs also in many documents older than the tenth century and has been most variously and inconsistently explained. Some take the name to denote the Chāvādās of Anahavāda (A.D. 746-912), some the Gurjjaras of Broach (A.D. 580-808) and some, among them Dr. Bhagvanlāl Indraprastha, even the Valabhis (A.D. 509-766), but not one of these identifications can be made to apply to all cases. As regards the Valabhis even if they were of Gurjjara origin they are not known to have at any time called themselves Gurjjaras or to have been known by that name to their neighbours. The identification with the Gurjjaras of Broach is at first sight more plausible, as they admitted their Gurjjara origin as late as the middle of the seventh century, but there are strong reasons against the identification of the Broach branch as the leading family of Gurjjaras. Pulakesi II. in his Aihola inscription of A.D. 634 (S. 556)<sup>1</sup> claims to have subdued by his prowess the Lātas Māhavyas and Gurjjaras, which shows that the land of the Gurjjaras was distinct from Lata, the province in which Broach stood. Similarly Hsien Tsung (c. 640 A.D.) speaks of the kingdom of Broach by the name of the city and not as Gurjjara or the Gurjjara country. In the following century the historians of the Arab raids<sup>2</sup> notice Baras (Broach) separately from Jurz or Gurjjara and the Chaulukya grant of 190 that is of A.D. 738-739 mentions the Gurjjaras after the Chāvotakas (Chāvādās) and the Mauryas (of Chitor) as the last of the kingdoms attacked by the Arab army. Later instances occur of a distinction between Lāta and Gurjjara, but it seems unnecessary to quote them as the Gurjjara kingdom of Broach probably did not survive the Rāshtrakūṭa conquest of South Gñjarāt (A.D. 750-760).

The evidence that the name Gurjjara was not confined to the Chāvādās

## Appendix III.

## BHINMAL.

Caste  
Legends.

## History.

<sup>1</sup> Indian Antiquary, VIII. 237.<sup>2</sup> Elliot, I. 432.

## Appendix III.

BHINMAL.  
History.

is not less abundant. It will not be disputed that references of earlier date than the foundation of Anahilavāda (A.D. 746) cannot apply to the Chāvāda kingdom, and further we find the Chālukya grant of A.D. 738-739 expressly distinguishing between the Chāvādās and the Gurjaras and calling the former by their tribal name Chāvotaka. It might be supposed that as the power of the Chāvādās increased, they became known as the rulers of the Gurjara country; and it must be admitted that some of the references to Gurjaras in the Rāshtrakūta grants are vague enough to apply to the Chāvādās. Still, if it can be shown that others of these references cannot possibly apply to the Chāvādās, and if we assume, as we must, that the name of Gurjara was used with the slightest consistency, it will follow that the ninth and tenth century references to the Gurjaras do not apply to the Chāvāda kingdom of Anahilavāda.

The Van-Dandōri and Rādhanpuri plates of the great Rāshtrakūta Govinda III.<sup>1</sup> state that Govinda's father Dhruva (c. 780-800 A.D.) "quickly caused Vatsurāja, intoxicated with the goddess of the sovereignty of Ganda that he had acquired with ease, to enter upon the path of misfortune in the centre of Maru" and took away from him the two umbrellas of Ganda. A comparison of this statement with that in the Baroda grant of Karka II.<sup>2</sup> which is dated A.D. 812-813, to the effect that Karka made his arm "the door-bar of the country of the lord of the Gurjaras, who had become evilly inflamed by conquering the lord of Ganda and the lord of Vanga" makes it highly probable that Vatsurāja was king of the Gurjaras at the end of the eighth century. As no such name occurs in the Chāvāda lists, it follows that the Gurjaras referred to in the inscriptions of about A.D. 800 were not Chāvādās.

It is also possible to show that more than a century later the Chāvādās were distinct from the Gurjaras. The Kāmaresa poet Panpa, writing in A.D. 941,<sup>3</sup> states that the father of his patron Anikesari vanquished Mahapāla king of the Gurjaras, who may be identified with the Mahapāla who is named as overlord in the grant of Dharamiyarāma of Wadhvān,<sup>4</sup> dated A.D. 914. As no Mahapāla occurs in the Chāvāda lists, the Gurjara kingdom must be sought elsewhere than at Anahilavāda. Since the Gurjaras of the eighth and ninth century inscriptions cannot be identified either with the Valabhis, the Branch Gurjaras, or the Anahilavāda Chāvādās, they must represent some other family of rulers. A suitable dynasty seems to be supplied by Hsien Tsiang's kingdom of Kiū-che-lo or Gurjara, the capital of which he calls Pi-lo-mo-lo.<sup>5</sup> The French translators took Pi-lo-mo-lo to be Bālmer in Rappatāna. But Dr. Bühler following the late Colonel Watson, identifies it, no doubt rightly, with Bhinmal or Bhilmal.<sup>6</sup>

<sup>1</sup> Indian Antiquary, XI, 156 and VI, 59.      <sup>2</sup> Indian Antiquary, XII, 166.

<sup>3</sup> Jour. R. A. S. XIV, 1901.

<sup>4</sup> Indian Antiquary, XII, 190 and XVIII, 91.

<sup>5</sup> Beal's Buddhist Records, II, 270.

<sup>6</sup> Indian Antiquary, VI, 63. That the name Bhilmal should have come into use while the Gurjaras were still in the height of their power is strange. The explanation may perhaps be that Bhilmal may mean the Gurjara's town the name Bhil or bowman being given to the Gurjaras on account of their skill as archers. So Chāpa the original name of the Chāvādās is Sanskritised into Chāvotkatas the strong bowmen. So also, perhaps, the Chāpa or Chaura who gave its name to Chapanir or Chapaner was according to the local story a Bhil. Several tribes of Mewār Bhils are well enough made to suggest that in their case Bhil may mean Gurjara. This is specially the case with the Lauriyah Bhils of Nerwer, the finest of the race, whose name further suggests an origin in the Gurjara division of Lor. Compare Malcolm's Trans. Bombay As. Soc. I, 71.

A short sketch of the history of the Gurjjaras, so far as it can be pieced together from contemporary sources, may help to show the probability of these identifications. The Gurjjaras apparently entered India in the fifth century A.D. The earliest notice of them occurs in the *Śrī Harṣacharita*, a work of the early seventh century, in which during the early years of the seventh century *Prabhākara-vardhana*, the father of *Śrī Harṣa* of Magadha (A.D. 606-641) is said to have conquered the king of Gandhara, the *Hūmas*, the king of Sindh, the Gurjjaras, the *Lātas*, and the king of *Mālava*.<sup>1</sup> The date of their settlement at Bhinmal is unknown, but as their king was recognised as a *Kshatriya* in *Hsien Tsiang*'s time (c. 640 A.D.) it probably was not later than A.D. 550. Towards the end of the sixth century (c. 585) they seem to have conquered northern Gujarāt and Broach and to have forced the *Valabhis* (A.D. 509-766) to acknowledge their supremacy. (See above page 465.) They took very kindly to Indian culture, for in A.D. 628 the astronomer *Brahmagupta* wrote his *Siddhānta* at Bhinmal under king *Vyāghramukha*, who, he states, belonged to the *Śrī Chāpa* dynasty.<sup>2</sup> This valuable statement not only gives the name of the Gurjjara royal house but at the same time proves the Gurjjara origin of the *Chāpotkatas* or *Chāvotakas*, that is the *Chāvadās* of later times. Thus *Vyāghramukha* is probably the same as the Gurjjara king whom in his inscription of S. 556 (A.D. 634) *Pulakeśi II.* claims to have subdued.<sup>3</sup> A few years later (c. 640 A.D.) *Hsien Tsiang* describes the king (probably *Vyāghramukha*'s successor) as a devout Buddhist and just twenty years of age. The country was populous and wealthy, but Buddhists were few and unbelievers many. The Gurjjaras did not long retain their southern conquests. In *Hsien Tsiang*'s time both *Kana* (*Ka-cha*) and *Vudmugar* (*Amudapura*) belonged to *Mālava* while the Broach chiefs probably submitted to the *Chalukyas*. No further reference to the Bhinmal kingdom has been traced until after the Arab conquest of Sindh when (A.D. 724-750) the Khalifa's governor *Juna'id* sent his plundering bands into all the neighbouring countries and attacked among other places *Marwād* (*Mārwa*), *Maliba* (*Malwa*), *Baras* (*Broach*), *Uzain* (*Ujjain*), *Al Bahlamān* (*Bhinmal*?), and *Jurz* (*Gurjjara*).<sup>4</sup> As noticed above the contemporary *Chalukya* plate of A.D. 738-9 also mentions Gurjjara as one of the kingdoms attacked. After these events the Arabs seem to have confined themselves to raiding the coast towns of *Kāthiāwāḍa* without attacking inland states such as Bhinmal. Immediately after the Arab raids ceased the Gurjjaras had to meet a new enemy the *Rāshtrakūtas* who after supplanting the *Chalukyas* in the *Dakṣiṇ* turned their attention northwards. *Danti*<sup>5</sup> gave in his *Samangad* grant of A.D. 753-4<sup>6</sup> speaks of plundering the banks of the *Muhī* and the *Rovā* (*Narbada*), and in his *Ellora* inscription<sup>7</sup> of conquering among other countries *Mālava*, *Lāta* and *Tanka*.<sup>8</sup> A few years later (A.D. 757-58) a branch of the main *Rāshtrakūta* line established its independence in *Lāta* in the person of *Kakka*.

## Appendix III.

BHINMAL.  
History.

<sup>1</sup> The *Madhuban Grant* : *Epigraphia Indica*, I, 67.

<sup>2</sup> *Reinoud, Mémoire Sur l'Inde*, 337, fn. quoting this reference through *Alberuni* (A.D. 1031) writes *Pohluṣa* between *Mulṭān* and *Anhalwara*.

<sup>3</sup> *Indian Antiquary*, VIII, 237.

<sup>4</sup> *Elliot*, I, 440-41.

<sup>5</sup> *Indian Antiquary*, XI, 109.

<sup>6</sup> *Arch. Surv. West. India*, X, 91.

<sup>7</sup> *Tanka* may be the northern half of the Broach District. Traces of the name seem to remain in the two *Tankāriās*, one *Sitpore Tankāria* in north Broach and the other in *Āmod*. The name seems also to survive in the better known *Tankāri* the port of *Jambusar* on the *Dhādhar*. This *Tankāri* is the second port in the district of Broach and was formerly the emporium for the trade with *Mālwa*. *Bombay Gazetteer*, II, 413-569.

## Appendix III.

BHINMAL.  
History.

The next notice of the Gurjjaras occurs in the Rádhanpur and Vindhori grants of Govinda III.<sup>1</sup> who states that his father Dhruva (c 780-800 A.D.) caused "Vatsarāja, intoxicated with the goddess of the sovereignty of Gauda that he had acquired with ease, to enter upon the path of misfortune in the centre of Māru" and took from him the two white umbrellas of Gauda. As already stated, a comparison with the Baroda grant of Karka II.<sup>2</sup> shows that this Vatsarāja was a Gurjjara king and that he had made extensive conquests in Upper India as far east as Bengal. Now it is notable that the genealogies of two of the most important Agnikula races, the Paramāras and the Chauhāns, go back to this very time (c 800 A.D.).<sup>3</sup> Taking this fact in connection with the prevalence of the surnames Pavār and Chavān among Gujars in such remote provinces as the Panjāb and Khāndesh, it seems obvious that these two tribes and therefore also the two other Agnikula races, the Parihārs and Solankis are, if not of Gurjjara origin, at all events members of the great horde of northern invaders whom the Gurjjaras led. The agreement between this theory and the Agnikula legends of Ālma need only be pointed out to be admitted. The origin of the modern Rajput races has always been one of the puzzles of Indian history. This suggestion seems to offer at least a partial solution.

The Rádhanpur grant (A.D. 807-8) further states that when the Gurjjara saw Govinda III. approaching, he fled in fear to some unknown hiding-place. This probably means no more than that Vatsarāja did not oppose Govinda in his march to the Vindhya. The next reference is in the Baroda grant of Karka II. of Gujrat who boasts that his father Indra (c 810 A.D.) alone caused the leader of the Gurjjara lords to flee. Karka adds that he himself, for the purpose of protecting Malwa, "who had been struck down," made his arm the door-bar of the country of Gurjjaraśvara, who "had become evilly inflamed" by the conquest of Gauda and Vanga.<sup>4</sup> It is difficult to avoid supposing that we have here a reference to the Paramāra conquest of Malwa and that Karka checked the southward march of the victorious army. For some years no further mention has been traced of the Gurjjaras. But in A.D. 851 the Arab merchant Sulaiman states<sup>5</sup> that the king of Juzr was one of the kings "arround" the Balbarā, that is the Rāshtrakūta, and that he was very hostile to the Musalmāns, which is not surprising, considering how his kingdom was exposed to the Arab raids from Sindh. Dhruva III. of Broach, in his Bagumra grant of A.D. 867<sup>6</sup> speaks of "the host of the powerful Gurjjaras" as one of the dangerous enemies he had to fear. About A.D. 890 a Gurjjara chief named Alakhāna ceded Takkadesa in the Panjāb to Śankaravarman of Kashmir.<sup>7</sup> But as Alakhāna was a vassal of Lalliya, the Śahi of Ohind near Swāt, this event did not affect the Bhinmal empire. To about A.D. 900 belongs the notice of the Rāshtrakūta Kṛṣṇa II in the Deoli and Navsāri grants<sup>8</sup> where he is stated to have frightened the Gurjjaras, destroyed the pride of Lāṭa, and deprived the coast people of sleep. His fights with the Gurjjaras are compared to the storms of the rainy season, implying that while the relations of the two empires continued hostile, neither was able to gain any decisive advantage over the other. To this same period belongs Ibn Khurdādhba's (A.D. 912) statement<sup>9</sup> that the king of Juzr was the fourth

<sup>1</sup> Indian Antiquary, VI. 59 and XI. 156.<sup>2</sup> Indian Antiquary, XII. 156.<sup>3</sup> See the Udaipur *prashasti* in Ep. Ind. I. and the Harsha Inscription in ditto.<sup>4</sup> See the Baroda grant of A.D. 812-13. Indian Antiquary, XII. 156.<sup>5</sup> Elliot, I. 4.<sup>6</sup> Indian Antiquary, XII. 179.<sup>7</sup> Rajataranginī, 142.<sup>8</sup> B. B. R. A. Soc. Jourl. XVIII. 239.<sup>9</sup> Elliot, I. 13.

in rank of the kings of India and that the *Tātariya dirhams* were used in his country. In connection with the latter point it is worth noting that the *pattāvali* of the Upakeśagacchin<sup>1</sup> gives a story which distinctly connects the origin of the Gadhia coinage with Bhinmāl.<sup>2</sup> The grant of Dharanivārāha, the Chāpa chief of Vadhvān, dated A.D. 914<sup>3</sup> gives us the name of his overlord Mahipāla, who, as already pointed out, must be identified with the Mahipāla who was defeated by the Karnātuk king Narasimha.<sup>4</sup> The fact that Vadhvān was a Chāpa dependency implies that Anahilavāda was one also. We may in fact conclude that throughout the Chāvādā period Anahilavāda was in more feudatory of Bhinmāl, a fact which would account for the obscurities and contradictions of Chāvādā history.

The Deoli grant of the Rāshtrakūta Krishna III. which is dated A.D. 940<sup>5</sup> describes the king's victories in the south as causing the hope of Kālayāra and Charakūta to drop away from the heart of the Gurjara. At this time Kālayāra belonged to the Kāluchuris of Central India and Chitakūta or Chitol to the Gichlots of Mewād and the phrase used by Krishna implies that the Gurjara chief had his eye on these two famous fortresses and had perhaps already besieged them unsuccessfully. In either case this notice is evidence of the great and far-reaching power of the Gurjaras. Masādi (A.D. 915) notices that the king of Juzr was frequently at war with the Balhara (Rāshtrakūta) and that he had a large army and many horses and camels.

A Chandel stone inscription from Khajnrāho describes Yaśovarman and Jaskhavarman as successful in war against Gaudas, Khasas, Kosalas, Kāsiniras, Maṇḍilas, Māhivas, Cheds, Karnas, and Gurjaras.<sup>6</sup> And soon after about A.D. 953 during the reign of Bhīmasena a migration of 18,000 Gurjaras from Bhinmāl is recorded.<sup>7</sup> The memory of this movement remains in the traditions of the Gujars of Khāndesh into which they passed with their carts in large numbers by way of Mālwa.<sup>8</sup> An important result of this abandonment of Bhinmāl was the transfer of overlordship from Bhinmāl to Anahilavāda whose first Chālukya or Solanki king Mularāja (A.D. 961-990) is, about A.D. 990, described as being accompanied by the chief of Bhinmāl as a subordinate ally in his war with Graharipu (see Above page 451). The Gurjara or Bhinmāl empire seems to have broken into several sections of which the three leading portions were the Chauhāns of Sāmbhar, the Paramāras of Malwa, and the Solaukis of Anahilavāda.

The inscriptions which follow throw a certain amount of light on the history of Bhinmāl during and after the Solauki period. The two earliest

Appendix III.  
BHINMAL.  
History.

<sup>1</sup> Indian Antiquary, XIX. 233.

<sup>2</sup> According to Cunningham (Ancient Geography, 313) the coins called *Tātariya dirhams* stretch from the fifth and sixth to the eleventh century. They are frequently found in Kābul probably of the ninth century. In the tenth century Ibn Haukal (A.D. 977) found them current in Gandhara and the Panjāb where the Boar coin has since ousted them. They are rare in Central India east of the Arāvali range. They are not uncommon in Rājputānā or Gajarat and were once so plentiful in Sindh, that in A.D. 725 the Sindh treasury had eighteen million Tātariya dirhams. (See Dowson in Elliot's History, I. 3.) They are the rude silver pieces generally known as Indo-Sassanian because they combine Indian letters with Sassanian types. A worn fire temple is the supposed Ass-head which has given rise to the name Gadhia Paisa or Ass money.

<sup>3</sup> Indian Antiquary, XII. 190 and XVIII. 91.

<sup>4</sup> Jour. R. A. S. XIV. 19.

<sup>5</sup> R. B. R. A. S. Jour. XVIII. 239.

<sup>6</sup> Kielhorn in Epig. Indica, I. 122.

<sup>7</sup> Hearnle in Ind. Antiq. XIX. 233.

<sup>8</sup> Details given in Khāndesh Gazetteer, XII. 30.

## Appendix III.

BHINMAL.  
History.

in date (Nos. 1 and 2) which are probably of the tenth century, give no historical details. Nos. 3 and 4 show that between A.D. 1057 and 1067 Bhinmāl was ruled by the Mahārājādhirāja Kṛishnarāja of the Paramāra race. This is a valuable confirmation of Rājput tradition, according to which the Paramāra Rāja of Abū was followed by the prince of Śrīmāla, when he aided Māhārāja against Grakaripa (c. 990 A.D.) and the Paramāras remained paramount in this region until the beginning of the thirteenth century.<sup>2</sup> The title of Mahārājādhirāja meant much less at this period than it meant before the Valabhi kings had cheapened it. Still it shows that Kṛishnarāja's rank was considerably higher than that of a mere feudatory chieftain. Inscription No. 3 gives the names of Kṛishnarāja's father Dhaundhika and of his grandfather Devarāja. The first of these two names occurs in the main line of Abū as the successor of Dhūmarāja the first Paramāra sovereign.<sup>3</sup> According to Rājput tradition the Paramāras were at one time supreme in Marasthān and held all the nine castles of the Wast. But in the historical period their chief possessions in Mārwad lay about Abū and Chandrayātī, though we have a glimpse of another branch maintaining itself at Keraḷa near Bādmēr.<sup>4</sup> The Paramāra chiefs of Abū are constantly referred to in the Solanki annals, and during the golden age of the Solanki monarchy (A.D. 1094-1171) they were the vassals of that power, and their Bhinmāl branch if it was ever a distinct chiefship, probably followed the fortunes of the main line, though the Bhinmāl inscriptions give us no facts for this long period. The next item of information is given by Inscription 5, which is dated in the Samvat year 1239 (A.D. 1183) in the reign of the Mahārani Śrī Jayasinhadeva. This name is of special interest, as it can hardly be doubted that we have here to do with that "Jaitī Parmār" of Abū whose daughter's beauty caused the fatal feud between "Bhūma Solanki" of Anahkavāha and Prithviraj Chohan of Delhi.<sup>5</sup> The title of Mahārani is to be noted as indicating the decline of the family from the great days of Kṛishnarāja.

Towards the end of the thirteenth century the old world was falling to pieces, and the Paramāras lost one after another nearly all their ancient possessions to the Chohāns of Nāḍol. Bhinmāl must have fallen about A.D. 1200 or a few years before, for Inscription No. 6 is dated Samvat 1262 (A.D. 1206) in the reign of the Mahārājādhirāja Śrī Udayasinhadeva, who as we learn from Inscription 12, was the son of the Mahārani Śrī Samrasinhadeva, of the Chohān race. The sudden rise of the son to greatness is implied in the difference of title and it may be inferred that Udayasinha himself was the conqueror of Bhinmāl, though the capture of Abū is ascribed by Forbes to a chief named Lūnga.<sup>6</sup>

Inscriptions Nos. 6 to 8 being dated in the reign of Udayasinha, show that he lived to at least the year A.D. 1249 and therefore reigned at least forty-three years. He is also referred to in the Inscription No. 10, dated A.D. 1274, but in a way that does not necessarily imply that he was still alive, as the record only speaks of an endowment for his spiritual benefit, made by a person who was perhaps an old retainer. His name also occurs in the genealogy in No. 12. His reign was apparently a prosperous one but no historical facts beyond those already noted are known about him.

<sup>1</sup> RAs MAlA, 44.<sup>2</sup> RAs MAlA, 210ff.<sup>3</sup> RAs MAlA, 211.<sup>4</sup> Śrī Bhaṅgar Prā. I, No. 30 of the list of Sanskrit Inscriptions dated Sam. 1218.<sup>5</sup> Śrī RAs MAlA, 161ff.<sup>6</sup> RAs MAlA, 211.

Inscription No. 12 shows that Udayasinha had a son named Vāhadhasinha, who, as he is given no royal title, probably died before his father. Udayasinha's successor, or at all events the next king in whose reign grants are dated, was Cāciga, who is given the title of Mahārāul in Inscriptions 11 (A.D. 1277) and 12 (A.D. 1278).<sup>1</sup> His relationship to Udayasinha does not clearly appear, but he was probably either an elder brother or an uncle of the Cāmuṇḍa for whose benefit the gift recorded in Inscription 12 was made and who seems to be a grandson of Udayasinha. Cāciga appears to be the Maṭṭamandaleśvara Cāciga of Inscription 15 in the Bhāmnagar State Collection (Bhāu. Prā I. list page 5) which is stated to bear the date Śaṃvat 1332 (A.D. 1276) and to be engraved on a pillar in the temple of Pārsvanātha at Ratanpur near Jódhpur. It is clear that he was tributary to some greater power though it is not easy to say who his suzerain was. At this period Mārwar was in a state of chaos under the increasing pressure of the Rāthods. Only five years after Cāciga's last date (A.D. 1278) we meet with the name of a new ruler, the Mahārāul, or Śāmvatasinha. He is mentioned in Inscriptions 13 (A.D. 1283) 14 (A.D. 1286) and 15 (A.D. 1289) and also in 14 of the Bhāmnagar Collection (A.D. 1296 Bhāu. Prā I. list page 13) from a Jain temple at Junā. He is not stated to have belonged to the same family as the previous rulers, but he bears the family title of Mahārāul, and it may be inferred with probability that he was a son of Cāciga. He reigned for at least thirteen years (A.D. 1283-1296). It must have been about A.D. 1300 or a little later, that the Chóhans were deprived of Bhinnmāl by the Rāthods and the line of Udayasinha died out.<sup>2</sup>

## Appendix III.

BHINMAL.  
History.

The Jagsvāmi temple has the honour of supplying fifteen of eighteen unmodern inscriptions found at Bhinnmāl. Of the fifteen inscriptions belonging to Jagsvāmi's temple nine are in place and six have been removed to other buildings. Of the six which have been moved five are in Bīrijī's rest-house in the east and one is in the enclosure of Mahā-lakshāmi's temple in the south of the town. Of the three remaining inscriptions of one (No. 3) the date S. 1106 (A.D. 1043) is alone legible. Of the letters on the two others, one in the bed and the other on the north bank of the Jankop lake, no portion can be read. Arranged according to date the sixteen inscriptions of which any portion has been read come in the following order :

Inscriptions.

I.—(S. 950-1050 ; A.D. 900-1000. No. 1. of Plan.) On the left hand side of the eastern face of the broken architrave of the porch of the shrine of Jagsvāmi. The letter show the inscription to be of about the tenth century.

Śrī Jagasvāmidēvasya vāsare  
on the day of Śrī Jagasvāmi.\*

\* Read Śrī Jagasvāmi

II.—(S. 950-1050 ; A.D. 900-1000. No. 2 of Plan.) On the south face of the eightsided section of the northern pillar of the shrine porch in the temple of Jagsvāmi. Wrongly described in Bhāvanagara prācīnaśodhasaṅgraha I. under No. 46 of the State Collection, as referring to a man called Vasundhara and dated Vi. S. 1330. As the letters show, the inscription is of about the tenth century. It consists of a single

<sup>1</sup> Inscriptions 9 and 10 are not dated in any king's reign.

<sup>2</sup> Compare Tod's Rajasthan, I.

## Appendix III.

BHINMAL.  
Inscriptions.

complete verse :

1. Vasumihara-kāri-
2. tām dyaṁ stambhāḥ-
3. -tau manōhara-
4. svapnāḥ Santaka-
5. sārthā satatān
6. opunāvaddhāḥ ||

These two lovely pillars Vasumihara had made for her father  
Santaka's sake for increase of merit for ever.

III.—(S. 1106; A.D. 1049. Not on Plan.) On the east side of the southern water channel into Gautama's lake three-quarters of a mile north of the town. Except the date nothing can be deciphered.

IV.—(S. 1117, A.D. 1060. Not on Plan.) On the lower part of a pillar in the dharmasāla east of the temple of Baraji on the east of the town. Prose :

1. Om Namah śūryaya | yaśōdayāśāsamayāsuramakuta-
2. śleṣa-caraya-kamalā s pi | kurutōs jalīn Trinetraḥ sa jayati
3. Śūryah | Saṁvat 1117 (A.D. 1067) Magha Śukla 6 Ravana
4. dhlavo Mahārājādhirāja Śrī Krishnarajah Śrī Dhanindh-
5. -ja-panttraḥ tasmā kṣettrī vijayam | vartanam-varsha-
6. jati-Kuṇḍalī 6 Jala-sutā Dada Harir Madhava-sutā Dhan-
7. ramacandāśatas tathā Thakhaṭa jati Dhanadityah Sar-
8. vādēva-sutah | am
9. blośatnribhus tathā Vanyāna Dhanakṣat-jayā Dhanindhakāna
10. -la-mayānāna deva-guru-vrahmaṇa suśrīṣhā paraya Ravi-
11. -trameśa vrahmaṇa (ma-)
12. -hāyana parameśa tathā lokān Sauri dharmā pravarttāya
13. dravyān me . . . (m)
14. -tya-tejo-nidhī Śrī Jagat-svāmī-dēvasya deva-bhavana-
15. jñānoddha . . .
16. (kā)hājatān bhavanasyopari svaraṇṇa-kalasaṁ vrahmaṇa
17. para-(ma-dhā-)
18. -rinmukha Jājākāna nija-dravyena karitam iti || Saṁ 1
19. Jyeshtha Śukla 8 samē rātrān gṛhṭaka 3 pala 25 asmin la-
20. (g)ṇe sarvakarma nishpāḍya kalasān dhvajān en dayapi-
21. tam iti ||
22. (Ta)thā purātana-vṛttina pari devasyāya Rājūā Śrī Krishna-
23. rājāna Śrī-
24. . . . (pu-)rīya-mandalē grāmān prativa° drā. 20 Sucaliya-
25. grāmē kṣetram ēkaṁ
26. . . . . traya rājabhōgāt tu drōna . . . . . sati kā . .
27. . . . || Rāmaś Pōmaraj kā . . . . . prativa° drā. 1 . . . . .
28. . . . vijāpaya caṁdanena kārāpitam iti || Tathā ālav . . .
29. . . . ya pra da . . . likhitān kada . . . . .
30. . . . . kāya . . . . .

## Translation.

## Appendix III.

BHINMAL  
Inscriptions.

- 1 - 3. Om ' Reverence to the Sun ' Victorious is that sun, the storehouse of brightness, at whose rising and setting the three-eyed (Śiva), even though (his own) lotus feet are touched by the diadems of the gods, folds his hands (in adoration).
- 3 - 5. On Sunday the 6th of the light half of Māgha, the year 1113, at holy Śrināla the Mahārājadhīrāja Śrī Kṛṣṇa-  
rāja son of Śrī Dhaṁdhanka and grandson of the glorious Devarāja, of the Paramāra race—in his victorious reign.
- 6 - 7. Kiriṇāditya, Jēla's son, of the Dharkuta family, (being office-holder) in his turn for the current year, Dada Hari son of Mādhyava, Dhaṁdhanka son of Dhanajacandya and Dhanajaditya son of Sarvaditya of the Thākḥāṭa race.
- 8 - 12. By these four and by the Vām (?) Dhaṁdhaka son of Jēla of the Dharkuta race, the ornament of his family, strict in obedience to the gods, to his teachers and to Brahmanas, and full of devotion to the feet of Ravi (the Sun), observing the perishableness of this world, and urging kings Kshatriyas Brahmanas merchants and townsfolk to worship the sun, repairs were done to the temple of the god Śrī Jagatsvāmī, the everlasting store of light.
13. The kaluśa of gold above the temple the very righteous Brāhmana Jajaka had made at his own charges. In the year 1 . . . .
15. on Monday the 7th of the light half of Jyēsthā, in the 25th pala of the 3rd ghāṭika of night—at this moment
16. all the work being finished the kaluśa and banner were set up (?)
17. and after the ancient manner by the king Śrī Kṛṣṇarāja . . . of this complaint . . . .
18. a village in the Śrī . . . pūṭya district, yearly 20 drammas. In Saadhyā village a field
19. . . . But from the king's share (of the crop) a drōpa . . . .
20. . . . yearly 1 dramma . . . .
21. . . . by order was caused to be made by Candana || and . . .
22. . . . written . . . .
23. . . . kṛya . . . .

V - (S 1123, A.M. 10.15. No. 3 of Plan.) On the north face of the upper square section of the more northerly of the two pillars that support the eastern side of the dome of the temple of Jagatvāmī. Entirely in prose:

1. Om. Saṁvat 1123, Jyēsthā Vadi 12 Śanāu ṇ adyēha Śrī Śrī-  
malē Maharājadhīrāja-Śrī Kṛṣṇarāja-
2. ja-rājyē Dēvasītanu-śīṣa-Mahādēva-dharmādhikāra-cēṭakapa-  
rama Pāsupatācārya-Śrī Jāvalasye . . . | Sauva-
3. -rājika Jāvalasye | Śrēṣṭhi Candana Kiraṇāditya Stharā  
varittamāna-varsha-vārika-Joga-candra . . . .
4. Gugā navāi . . . lōkō ca ēka . . . matibhūtvā . . . .  
. . . . Śrīmātya Vra-
5. huana Vāhaṭēna . . . Śrī Candana . . . .  
. . . . dramma . . . .
6. 13. Badly damaged; only a few letters legible here and there.

## Appendix III.

BHINMAL.  
Inscriptions.

## Translation.

- 1-2. Ōm ' On Saturday the 12th of the dark half of Jyêshtha  
Sainvat 1123 on this day at holy Śrīmāla, in the reign  
of the Mahārājādhirāja Śrī Kṛṣṇarāja—of Śrī Jāvala,  
the servant of the offices of religion to the god Śrī Caṇḍikā  
Mahādēva, the supreme teacher of the Pāśupatas . . .
3. The goldsmith Jaganāsa, the son Candana, Kṛṣṇāditya,  
Sihara, Jogacandra the office-holder in turn for the current  
year
- 4-5. Gūḍa . . . and in the world . . being of one mind . . .  
. . . . . by Vāhaṇa the Śrīmālī Bhāṇma . . . . . Śrī  
Caṇḍikā . . . . .

VI.—(S. 1239, A.D. 1183 No. 4 of Plan.) On the upper face of the  
eightsided section of the fallen pillar on the south side of the dome of  
the temple of Jagsvāmi. Entirely in prose:

1. Sam. 1239 Āśvina Vadi 10 Vadhō
2. Adyēha Śrī Śrīmāle Mahārāja-
3. putra Śrī Jayastha-deva-rījyē
4. Gubilo Pramañadasuta-tra arava-
5. saka Vahnyana Vālaka-dēva
6. drava dra. 1 tuthā bhayā Māhmapadē-
7. dī kṛta dra. 1 yē kōṣṇi pa atī bhava
8. nūtīteshān pratidhā° vi 1 labhā yabko(s)
9. pratra-pālō bhavati tena varshān(u-)
10. -varsha(m) dīnē bhavya dātavyam

## Translation.

1. In the year 1239 (1183 A.D.) on Wednesday the tenth of the  
dark half of Āśvina
- 2-3. On this day here in holy Śrīmāla in the reign of his majesty  
Śrī Jayastha the Mahārāj.
- 4-6. Aravasaka Vahnyana the Gubilo, the Tra,\* son of Prama-  
ñada (gave) to Vālaka-dēva one *dramma* in cash.
- 6-7. And (his) wife Māhmapadēvī (dēvī) (gave) one *dramma*.  
Whoever are . . . by them for each *dramma* one  
is to be received. Whoever
- 9 is the ruler by him every
10. year on the . . . day it is to be given to the god.

\* Evidently the name of his office, but the abbreviation is not intelligible.

VII.—(S. 1262; A.D. 1206 No. 5 of Plan.) On the upper face of the  
lower square section of the fallen pillar which is one of the pair of  
three dome pillars. Prose:

1. " || Ōm Namah Suryāya || Yasodyastasamayō sura-  
makṣa-nispri-
2. śhīta-carana-kamalōṣṇi kurutē śhijali(m) trinētra(h) sajayati  
dhimnām niddhi(h) surya ||
3. Sainvat 1262 varshē adyēha Śrī Śrīmāle Mahārājādhirāja Śrī  
Uda-
4. -yasthika dēva kalyāṇa-vijaya-rājyō maha° Āsvipast-prabhī-  
riti-pañca-kula-
5. pratipattāu || Kāyastha-jāṭīya-Vālamyānvayō maha° Yasō-  
pālākrēyō śrthamvō (cē?).
6. -taka-Vilhākēna Śrī Jagasvāmi-dēvīya-bhāmīlāgarē kahāpita  
dra. 40 catvari(m).

## Appendix III.

BHINMAL.

Inscriptions.

7. Śat Āśvina māse yātr(śt-awē?) Āśvina sudi 13 . . . . .  
1 Āgni-āyē.
8. Malayā pushpamū dra 4 agurn dra. . . . .
9. -dra. 1 pramadā kulasya dra. 12 dvādaśa-dramma . . . . .  
Acamdrārkaṇi prativarsham dēvāna karāpa
10. ntyā || tathā śrēyārtham Madrakēna(?) dēva bhāṇiṇāgarē  
kshipita dra. 15 pañcadśa dramma Māgha.
11. -vadi 6 diuś baliṇibandhū(?) gōdhūmā ś 2 pakā ghṛita pall  
9 naivēdya 32 aṅga.
12. -bhōgō prativarsham acamdrārkaṇi yāvat dēvāna karāṇyā . .  
diuś Āhadasya.
13. -m-suhalaṇi/ Bhadrasyam-sulāṇi/ Acamdrārkaṇi āpaṇ-  
ya(ni) likhitaṇi pa Bāndhavada ś(tī)-
14. -na (anulāpa-śakōna hū iksharam adbhukākshuram pramā-  
nam || .

## Translation.

- 1 - 2. On, Reverence to the Sun 'Victorious is that sun, the store-  
house of brightness, at whose rising and setting the three-  
eyed (Śiva) folds his hands (in adoration), even though  
his lotus feet are touched by the diadems of the gods.
- 3 - 5. In the Śaivāt year 1262 (1206 A.D.), on this day here  
in holy Śrīmaṭ, in the prosperous and victorious reign of  
his majesty the Maharajadhiraja Śrī Udayasinha in the  
term of office of the *punch* (consisting of) Ā vapasi &c.
- 5 - 7. For the (spiritual) benefit of Yaśōpala in the Valamya  
family of the Kayastha caste, dra. 10, forty *drammas* were  
deposited by Villaka the Veṭika (or Cēṭaka) in the  
treasury of the god Śrī Jayasvami.
7. At the vatrā festival in the month of Āśvina, on the 13th of  
the light half of Ā vīna . . . . . , at the banking of the  
fire-(altar).
8. . . . . for flowers for the garland dra. 4, alwood dra. . . .
9. 4 *drammas*, for the band of singing women one *dramma* :  
thus dra. 12, twelve *drammas* (in all) are to be applied  
yearly by the god so long as sun and moon endure.
10. So also the dra. 15, fifteen *drammas* deposited in the treasury  
of the god by Madraka(?) for (spiritual) benefit.
- 11 - 12. On the sixth of the dark half of Māgha in the fixed  
ritual of the *bali*, wheat one *ser*, . . . . . *ghi* nine *pall*, the  
*naivēdya* . . . . . , the . . . *pabhōga* is to be performed yearly  
by the god so long as sun and moon endure.
- 12 - 13. On the . . . . . day the *śukḍa* of Āhadasvami and the  
*śukḍa* of Bhadrasyami is to be given so long as sun and  
moon endure.
- 13 - 14. Written by the *pd* Canilapasaika son of Bāndhavada.  
\* The letter less or the letter more . . . . . of authority.

\* c "Errors excepted."

VIII.—(S. 1274; A.D. 1218. Not in Plan.) In Bārāji's rest-house on  
the west face of the third right hand pillar. Prose:

1. Śaivāt 1274 varṣe Bhādrapada sudi 9 Śukrē dyōha Śrī-  
Śrīma.
2. 10 Mahārājādhirāja Śrī Udaya-sinha-dēva-kalyāṇa-vijaya-  
rājyē Sa°.
3. Dēpālāprabhṛiti-panīcakula pratipattāu . . . . .

### Inscriptions.

- Transition.*

- 1-4. **Om.** Reverence to the Sun. Victorious is that sun, the storehouse of brightness, at whose rising and setting the three-eyed (Śiva) folds his hands (in adoration), even though his feet are touched by the dandems of the gods.
- 4-7. In the year Śaka. 1305 (1249 A.D.), on this day here in holy Śrīmāla in the prosperous and victorious reign of his majesty the Mahārājādhirāja Śrī Udaya iha, in the term of office of the *pañch* (consisting of) Mha<sup>a</sup> Gajasiha and others . . . . . *madēvi*.
8. **Vāha** . . . . . *dra*. 50 fifty *drammas* deposited in the treasury of the god Śrī Jagasvāmi.
9. At the Āśvina festival on the 4th day of the light half of Āśvina the day's *baḥ*.
10. . . . .

11. Wheat sers 2½ ght *karshas* (8) . . . . . mung pā 2, ght  
*karshas* 2.

12-15. Illegible.

X.—(S. 1320, A.D. 1264 No. 6 of Man) On the east face of the lower square section of the more northerly of the east pair of dome pillars of Jagsvāmī's temple First thirteen lines in verse, the rest in prose. No. 49 of the Bhānnagar State Collection (Bhāta Prā I.)

1. Ōm namo Viṣṇurājaya namo devāya bhāsvate | namo 3  
naṭa-sva
2. rāṇya Haraye Cakrapānyē || namah Śivaya Soma tyā namah  
para-
3. ma-Vrahmaṇe | Iti phūcapamaskārah sarvapapapūṇa-  
śukāh || sarva-mūṇ-
4. gāla māṇḍalyān sarva-saṅkhyā pradhāyakaḥ | sarvārtha-  
siddhi-sampannam saṅ-
5. -tu me hṛdī° sarvālā || Iti jantū japaṇ nityaṇ nityaṇ  
āśrayate sukham | ta-
6. -mad asmu jape punye ratu astu sadāiva me || Iti dhya-  
nākaushthātma-
7. Kāyastho naigamavyāc | Bōhr istī pma Sādhumandano  
mandamāḥ satam |
8. Sukrīṣṇa-Kṛīṣṇa Govinda-paṇḍhāna parīyanah | Panti-  
ras tasyaṇ Śrīma-
9. -n Sādhanālo Val māṇḍajāh || Sadāiva datta-miśṭma-  
toshatanka-vādavaḥ |
10. Ahara prasāno yasya pūṇyā pūṇmālayalayub | paropakara  
vintam vāśhva
11. vadharmācāmū || vēna jannātmanāśenkre °śūlluvāla-  
vibhūśhātū || tatuh parama-
12. -ilharumātū sadā viśadamaṇsaḥ || devīdatta°vānab  
Śrīman Śubhato 3 bhūt tadamaṇḍalūh |
13. Cāṇeyas tasya Kedāra pūkah Kanhaḥ 3 bhavat | Mahi-  
devasato yasya bhīran Ra-
14. -mū Āśāh || Tēma Śrīkēśaraputraka Kanhaḍēma svafreyase  
Sam 1320 va-
15. -śhē Maḥmā Sa di 9 nayanmūcē prativāśhām bahn-  
mūttūn Śrī Jayasvāmī de-
16. vīya-bhāṇḍāgārē kshīpita dra. 50 pañcāśan dramamūh || bali-  
mūttūnthe godhūma sē 1½
17. ghṛīṇa ka 6 naivēl° ē mā ½ muga mē ½ ghṛīṇa ka ½  
Ābōtī dra ½
18. Vyāsa hē 2 pushpakarūṇkūṇāgāva-mūlyē dra. 2 patra-pūga-  
mū dra | pramālakula
19. dra 1 Rvām prativāśhām dēvakiyabhāṇḍāgārē shat  
dramma vyayē dēvēna kāṛā
20. pyāp || Iyām prāstaṭir Mahā° Sabhātēna bhāṇḍitā | Dhruva-  
Nagvala-suta-Dedā-
21. -kēna likhītā || sūtra° (Gōgā Suṭa Bhīmasūtrēnōtkīrṇā || क ||  
क ||

*Translation.*

1. "Om. Reverence to the lord of obstacles (Gāpasa), reverence  
to the brilliant god (the Sun), reverence to him of ever-  
lasting nature,
2. To Hari, wielder of the discus. Reverence to Śiva (and) to  
Śoma, reverence

**Appendix III.**

**BHINMÁL.**  
Inscriptions.

## Appendix III

BHINMAL.  
Inscriptions.

- 3-5 to the highest Brahma. May these five reverences which destroy all sin, the most auspicious of all auspicious (sayings), which grant all happiness, attended with the accomplishment of all objects, be ever in my heart."
- 5-6. The creature that constantly murmurs (these words) resorts to everlasting happiness. Therefore may I for ever take pleasure in this holy murmur.
- 6-7. There was formerly in the Nangama family a Kiyastha, Rishi son of Sac'lin, the delight of the good, whose mind was solely intent upon (the above) meditation.
- 7-9. (He was) devoted to meditation on (the names) Sri Kṛṣṇa, Kṛṣṇa, and Govinda. To him was born a grandson, the glorious Sadhulbala son of Vahna, who constantly satisfied numerous Brahmanas with gifts of sweet food, whose hand was not stretched out to steal, who was the home of Lakṣmī for the followers of the Vaiṣṇava religion, who not vowed to doing good to others,
10. who adorned his life with the discussions of saints. From him there was the glorious Subhata, the very righteous, whose mind was ever clear and to whom Dēvt granted a boon. Born of his body
- 11-12. was Cagneya. His (grandson) was Kumbhata son of Kēdāra or Mahādīva and his (Kumbhata's) two brothers were Rihua and Āsala.
- 13-14. By this Kumbhata son of Kēdāra for his own benefit, fifty *drammas*, dra 50, were deposited in the treasury of Śrī Jayasānīdeva for a yearly *balī*, on the month (9) of the light half of Mīgha, in the Samvat year 1320 (1261 A.D.)
- 16-18. In the *Balī* endowment wheat  $1\frac{1}{2}$  seers, ghi 6 *karṣhas*, in the *navāḍḍya* 1 measure, *maṇḍa* 2 measure, ghi  $\frac{1}{2}$  *karṣha*, Ābott (?)  $\frac{1}{2}$  *dramma* + 2, Bhātī 16 (?), for the price of flowers turmeric and aloe wood one *dramma*, for the price of leaves and betelnut one *dramma*, for the band of singing women one *dramma*.
19. So let six *drammas* be expended every year by the god from his treasury.
- 20-21. This *prasasti* was spoken (composed) by the Mahatara (?) Subhata. It was written by Dēdāka, son of Nāgvala the Dhruva. It is engraved by the carpenter Elumāsēna son of Gōgā.

XI—(S. 1330; A.D. 1264 No. 7 of Plan) On the south face of the lower square section of the western side of the north pair of dome pillars. First  $11\frac{1}{2}$  lines and lines 21 22 and half of 23 in verse, the rest in prose. No. 47 of the Bhāunagar State Collection. (Bhāu. Prā. I. list page 14):

1. Namaḥ Śrī Viṅhavarajāya namo dēvaya nṛhāsvatē namo
2. Paramāna(m) dadāyīnē cakrapāṇayē | Kā, astha-vānīśa prasavaḥ purāṣit.
3. Śrī Sāqha-nāma puruṣaḥ | mātānaḥ | Rishi . . .
4. }
5. } Damaged and illegible
6. }
7. . . . . dharmārtha . . . . . vigāha-
8. -mānō ānandakārah . . . . . 3 janishṭa ad
9. nuḥ Subhata . . . . . saubhāgya-sampal-lalitā-

## Appendix III.

BHINMAL.  
Inscriptions.

10. -bhiddhānā | tryvangu-sāraṇi tanaya svaraṇpaṇi . . . . .  
sajjanāgrīyaṇi Rājādhi.
11. Rājōdaya-siha-deva-nibhreyasē Śrī Subhataṇa tēna | dēvasya  
kośē . . . . .
12. . . . . mksheṇṇitani . . . . || Tēnaiva Maha' Subhataṇa-  
sva śrē-
13. -yasē Samvat 1330 varshē Āśvina Śudh 4 caturthidīnē divasa  
bali-
14. -pūja-prōkshayakarthā(n) deva Śrī Jayasvāmi-bhāṇā-  
gāre dra 50 paṇi-
15. -cā au' dhamma mksheṇṇitāḥ || Tathā Śrīkarane' Maha'  
Gajasthaṇaṇḍhito-
16. -pañcākulanā uparadhayita(-yati) | Bahūnē varshamānā-  
dhē karapita dra. 4 catin-
17. -ra dhammāḥ prativarshāni svīya pastalā bhavyā . . . paṇi-  
cakulēna datavyāḥ
18. Vah-mvānūdhē gōllhūnā sē 2 ghrīta ka 8 unga mī | vōshān  
na ½ ghrīta ka ½ vya-
19. -sa-mrvapa | Abōṭi mrvapa | Kmūkmūṅgaru dra. 2 pushpa  
dra. 2 patrapūga dra. 2.
20. Pramādākula dra 2 evam etat prativarshāni ācānūdrākkān  
devēna karapyaṇi ||
21. Śrīśalya-ratna-pura-lāṭa bradāṇṇikāṇi, Śrīmāladeśavahikā-  
dhikṛi |
22. -to dhūmrah | vyasena candaharinā vīlūshān varōpa yo 3  
dhyaṇṇitāḥ sa vi-
23. -dadhe Subhataḥ praśastān || Dhru' Dedakēna bhikṣitā sūtra'  
Goshasthē-
24. -na utknṛya || ॐ ||

## Translation:

- 1-2. Reverence to the Lord of Obstacles (Ganeśa). Reverence  
to the shining god. Reverence . . . to (Vishnu) the holder  
of the discus who bestows supreme happiness.
- 2-3. There was formerly an ancient man named Śrī Sādha  
born of the Kayastha race. 'Rishi . . . . .
- 4-6. Illegible.
- 7-9. . . . . for righteousness . . . . entering . . . . . giving  
pleasure . . . . there was born a son Subhata—
- 9-10. . . . (a wife) Lahitē by name, rich in excellence . . .  
the summit of the three objects of human effort  
(religious merit, wealth, and pleasure) in the form of a son  
. . . . the chief of the virtuous—
11. By that Śrī Subhata for the spiritual benefit of the king  
of kings his majesty Udayastha in the treasury of the  
god . . . . deposited . . . . .
- 12-15. By that same Maha' Subhata for his own (spiritual)  
benefit in the Samvat year 1330 (1274 A.D.) on the fourth  
day of the bright half of Āśvina, for the day's *bali*, worship  
and *darśana* dra 50, fifty *drammas* were deposited in the  
treasury of the god Śrī Jayasvāmi.
- 15-17. And he serves (prāpitates?) the *paṇica* consisting  
of Maha' Gajastha and the rest at Śrī Karana. On the  
*bali* day the four (4) *drammas* given for the *bali* endowment  
are to paid every year by the *paṇica* from their own . . . .

## Appendix III.

BHINMAL.  
Inscriptions.

18-20 In the *bali* endowment wheat *ś* 2, gilt *ka(rsha)* 8, *mung* one measure, *cakka*  $\frac{1}{2}$  measure, gilt *ka(rsha)*  $\frac{1}{2}$ , the Bhāt's dole 1; the Abōt's dole 1, turmeric and aloe-wood *dra*, 2, flowers *dra*, 2, leaves and betelnut *dra*, 2, the band of singing women *dra*, 2 : so is this to be given yearly by the god so long as sun and moon endure.

21-23. Subhuta the officer of Śrī Satyapura Ratnapura and Lata-brada, the chief set over the *vahikas* of the Śīmāla country, who was taught by Candā Hari the purāṇik, best of the learned, composed the *prasaśti*.

24. Written by Dadika the Dhruva and engraved by Gōshashta the carpenter.

XII.—(S 1333 : A.D. 1277 Not in Plaut.) On the north bank of Jankop lake on a fallen pillar to the west of Ghazni Khān's tomb. Lines 1-4 and half of line 5 and lines 18-22 (and perhaps 23 and 24) in verse, the rest in prose. No. 52 of the Bikanāgar State Collection (Bham. Prā. I. list pages 15-16).

1. Yab puratra mahāśūmā Śrīmālē kusamagatah | sa deva(h)  
Śrī
2. Mahāvīra . . . . . Bhuyatīta (?) prajñā
3. Yam śāmanam gatah | tasya Virajmēndrasya puṇyartham  
śāmanam navam ॥ 2 Pa-
4. -rāpaddha-mahagacchē puṇya-puṇya-svalbhavina (?) Śrī  
pūrnacandā-śūri-
5. na prasadaḥ likhyate yatha | svasti Samvat 1333 varshē Aśvi-
6. -na śu di 14 Sōmē | adyā Śrī Śrīmālē Mahārajakula Śrī  
(u?)
7. -eṇa-dēva-kalyāṇa-vijayi-rāṇyē taṇnyukta-mahā  
Gajastha-
8. prabhūti-paṇṇakula-pratipattan Śrī Śrīmāla-dēva-vahikā-  
dhikūṭēna
9. Nāgamaṇḍavaya-kayastha-mahattama-Subhātēna tattha(ve?)  
eṭṭaka Karmaśhē-
10. -na svaśrēyase Ā vmaṇḍ-ṭya-yatrā-mahōtsavē Āsvina Śu di  
14 ca-
11. -turdāś-śūmā Śrī Mahāvīradēvaya prativarśmān paṇḍo-  
paṇḍa-pūjanam-
12. -ttam Śrīkarmāyapaṇḍakulān sēlahathā - dāśi - narapāla-  
vārakṭi-pūrnasūbhā-
13. -dhya-talapa debala-sabhaḥ-ṭṭala-ma . . . hula-sabhaḥ
14. -da 5 saptaviśōpakōpē paṇḍadramma samā sēlahathā-  
-bhāvyē ātha
15. -drā<sup>o</sup> ma -dra. 8 a-ḥṭṭān dramma . || ubhayaṁ saptaviśōpa-  
kōpēna trayōdāśa dra-
16. -umā ācāṇḍārakkam dēvadāyē kārapitāh || vartamāṇa-  
paṇḍa-kulēna va-
17. -rttamāna-sēlahathēna dēvadāyē kṛitam idam svaśrēyase  
pālanīyaṁ ||
18. Yasmān paṇḍakulō sarvō māntavyam iti sarvadā | tasya  
tasya tadā śrēyo
19. Yasya yasya yadā padaṁ || || Śrīsatya-ratna-pura-  
Lāṭa-bradādhikārī Śrī-
20. -māla-dēsa-vahikādhikṛito dhurīṇaḥ | vyāśēna Candāhariṇa  
vidushīṇ va-
21. -rēna yodhyāpitāh sa vidadhē Subhātāh prasaśtiṁ || 3 ||  
Iyaṁ Gōgānujātā-

22. (-na)sūtradhārēṇa dhīmatī | utkirṇi Bhīmaśhēna Ācānka-  
shara-mālikā |  
23. . . sanam ilam mathapatinahendhāgoshtika Ācāndra-  
pratipattān || ५ ||  
24. . . vasasamaya . . . (h) khitam tēna dhīmatī | yo vārayat  
punyā-  
25. . . sata . . . . . tī || ६ || ma(n)gala-salīrth || śivamastu  
saṃp.

### Appendix III.

**BHINMÁL.**  
**Inscriptions.**

*Translation.*

1. The god Śrī Mahāvīra who formerly came in (to) this great town Śrīmālā . . . . in whom the wise protected from fear take refuge—a new ordinance is written as follows for the people's sake through the favour of this Vīra, chief of the Jinas by Śrī Pāramacandra Śāhī, whose nature is most holy.
- 5-9. Good luck! In the Sāhva year 1333 (1277 A.D.), on Monday the 14th of the light half of Āśvina—on this day here in holy Śrīmālā in the prosperous and victorious reign of his majesty Śrī Caciṣa the Mahāraja in the term of office of the *punch* (consisting of) Mahā' Cajasīha and others, appointed by him.
- 9-11. By Subhata the leader Kāyastha, of the Nāgama family, the officer in authority over the Vahikas of the Śrīmālā country, and by Karmasīha the Coṭaka (servant) (or *vetika*), for their own (spiritual) benefit, at the great festival of the *jāṭā* of the month of Āśvina on the fourteenth day 14 of the light half of Āśvina, for the worship (consisting of) the five services yearly to the god Śrī Mahāvīra.
- 12-15. [These four lines seem to be made up chiefly of Prākṛit words which I am unable to translate. They specify two *snins*, one of 5 and the other of 8 *dramma*s.]
- 15-17. Both, with the twenty-seventh *upakopa* (?), the 13 *dramma*s have been given in religious endowment. This which has been made as a religious endowment is to be maintained by the *punch* and by the *Sāhathu* (?) officiating (from time to time) for their own (spiritual) benefit.
- 18-19. Because every *punch* is always to be honoured, the benefit (of maintaining the endowment) belongs to whosoever at any time (holds) the office.
- 19-22. Subhata, the officer of Śīsatyapura Ratnapura and Lāṭāhrada, the chief set over the *vahikas* of the Śrīmālā country, who was taught by Candahari the purāṇik, the best of the learned, composed the *prasaṅgi*. The series of letters of this grant was engraved by the wise carpenter Bhūmasīha the son of Gōga.
- 23-25. This grant was written by that wise one . . . at the time . . . . in the term of office of the Abbot Mahēndra and the committeeman Ācamdra (?) . . who causes to speak . . . . Good luck! Bliss for ever! May it be auspicious . . . Finis.

XIII.—(S. 1334; A.D. 1278. No. 8 in Plan.) On the north face of the lower square section of the eastern of the north pair of dome pillars. All in prose :

1. Om namah Sūryāya || yasyōdayastasamayā suramukūṭa-  
nirṛṣita-carana-

## Appendix III.

BHINMAL.  
Inscriptions.

- 2 kāmalo 3 pi kurutē 3 nūjalini trinetra sajayati dhāmnā(nū)  
mūli(h) sūryah || | Samvat 1334.
3. Varshē Āśvina va di 8 mlycha S'ri Śrimalē Mahārājakula-  
Śrī-Caeiga-kalyāna-vija-
4. -ya-rājyē tannynkta-maha° . . . (s)ka-prabhīṭi-paṇicakula-  
pratipatīau | ēvān kalē pravarttamānē
5. Cāhumānauvācē Mahāraja(kula) Śrī Samarasihātmaja-  
Maharajadhirāja-Śrī Udaya |
6. Sihādēvānagaja-S'ri Vāhadhasiha . . . . . Śrī Camuṇḍa-  
rāja-deva-Śrīyascē maha°
7. Dēdākēna . . . . Śrī Jagasvāmudēvya° bhāp'agān . .  
bali . . . . .
8. . . . dra. 100 śatani drauma nūksbōpitā Āśvina-yātrayā(ni)  
Āśvina vadi 8 aṣṭamī dinē divisa-bali ta-
9. -thē anigabhōga . . . prkshamka . . . . . Śrīdevya-  
bhānūlāgarāt kārāpauṇya | bali-nihānīdhe
10. gōdhūma sē 3 ghṛita ka 1 (naivedyē) . . . . . (ś)hā(ni)  
mā 2, muga sē 1, ghṛita ka 1 vyāsamuvapa 1 Ālōṭi.
11. -nirvāpa 1 kumkumāguru-mūly(c) dra. 2 tathā paṇṣpha-  
mūlyē dra. 2 (?) tathā paṭrapūga-mūlyē dra. 2 paṇṇula-  
kulē mūlyē dra. 2 ē-
12. -vañ ētat Vyasa-Ālōṭika-Śrīśrī-goshtika . . . bula pramāli-  
kula prabhūtinānī varsham varsham | ratī a-
13. caṇḍrārka-yāvat tatha . . . . . fī kārāpauṇya śrī-deva-  
kārāpauṇya | puu . . . . . k nāpi na karaṭi-
14. -yā | likhitān dīru° Naṇula-suta-Dēdākēna . . . . . līnā-  
ksharam adhikaksharam va sarvañ paṇamā-
15. -mū || māṇigalañ sadā śrīh || (śrīrudharana ?) Nāna-suta  
Dēpala Sañ 33 varshē Caira va di 15 . . . . . saha.
16. Mānasihēna (?) . . . . || .

## Translation.

- 1-2. Ōm. Reverence to the Sun ! Victorious is that sun, the  
storehouse of brightness, at whose rising and setting the  
three-eyed (Śiva), even though (his own) lotus feet are  
touched by the diadems of the gods, folds his hands (in  
adoration).
- 2-4. In the *Samvat* year 1334 (1278 A.D.) on the 8th of the  
dark half of Āśvina—on this day here in holy Śrīmūla in  
the prosperous and victorious reign of his majesty the  
Mahārāj Śrī Caeiga, in the term of office of the  
*pauca* (consisting of) the Maha° . . . . Śiha and the rest,  
appointed by him—at this time
- 5-6. for the (spiritual) benefit of his majesty Śrī Cāmuṇḍa-  
rāja . . . . (son of) Śrī-Vāhadhasiha the son of his  
majesty Śrī Udayasiha the Mahārājādhirāja, (who was)  
the son of his majesty the Mahārāj Śrī Samarasiha in  
the Cāhumāna race
7. By the Maha° Dēdāka . . . . in the treasury of the god  
Śrī Jagasvāmi . . . . bali . . .
8. dra. 100, one hundred *dramma*s, were deposited. At the  
Āśvina yātrā the day's *bali* on the eighth 8 of the dark  
half of Āśvina

## Appendix III.

BHINMAL.  
Inscriptions.

9. and the *gṛagabhaya* . . *darśana* . . to be expended from the treasury of the god. In the endowment of the *bal*
- 10-11. Wheat *śl*. 3: *ghṛi kṛtishas* 1: in the *auriḍya* . . Cōsha measures 2, munga *śl*. 1, *ghṛi kṛ(rsha)* ½, the Bhat's dole 1, the Abbot's dole 1, for buying turmeric and aloe wood *dra*. 2, and for buying flowers *dra*. 2 (2), and for buying leaves and betel *dra*. 2, for the band of singing women *dra*. 2.
- 12-13. Thus this for the Bhat's, Abbots, Communitemen, . . . band of singing women &c. every year so long as sun and moon (candra) is so . . . to be expended, is to be expended by the god. Interruption (?) is to be made by no one
14. Written by Dadaka son of Nagula the *dhenu* . . . the letter less or the letter more—all is of (no?) authority.
15. Good luck! Bliss for ever. By the carpenter Depala son of Naba, on the 15th of the dark half of Cūtra in the year '33 . .
16. By Ma-asiba (?) . . .

XIV.—(S 1359. A.D. 1283 Not on Plan) In Bārājī's rest-house on the south face of the first right pillar. Prose. No 51 of the Bhāunagar State Collection (Bhān. Prā. I. list page 5):

1. Ōm namah Sūryayā || yasyōdayasasunayē sma-mukta-  
nṣqī-śīṣa-araṇa
2. -kaṇṇa- pa | kṛite ½ mjalun trinetra sa jayati dharmān  
mūlāḥ -śivah | samvā
3. t. 139 varṣe Aśvina Sū-d | sanāv adyāha Śīl Sīmalā  
Maharaja kula-Śīl-mvā-
4. -a-śha-deva-kalyāṇa-vijaya-rajyē samyukta-mahā  
-śha prahṛita-paṇi-akula-
5. pratiputtan Śīl-dēvaputrat atayāta-tūhilo  
-Ru-
6. -dāpala-suta -śha<sup>o</sup> Sahajapāl na-atmaśī yase pitṛmātṛ-śī-  
yase bah-puja-
7. aṅga bhōga pratyam(gaṇ) Śīl Jayasvāmi-dēvāya Sūrya-  
vaya bhānūdagarē (k)shēpita dra. 20 mu
8. śrī-drummā || Svā-śha-śha-sarab Rudrāmārga-  
samjpe Kat -va-pat
9. ābhīdāna kṣātra | ēka pralattah | devāva  
dinē pūjā manṭa an Saha Saha-
10. -ja-pāla-lhāryā Atma-śīcyasē māta pūtrōśrēyasē  
bhānūdagarē (k)shēpita-
11. dra. 10 dasa-drummā . . . . .  
drummā Asvi-
12. -na-yātrāyām Aśvina-Sū-d | dinē diva-sa-bali-puja  
bhānūdagarāt Śīl-dēv<sup>o</sup>
13. -na kārāpantya | valī-nivānūdhē gōdhuma śē 2  
ghṛita ka 8 naivēlyē cōshā(ni) pā 2 mu-
14. -ga ghṛita<sup>o</sup> ka ½ aṅgabhōgē  
patra-puja
15. pratyam(gaṇ) dra. | Vyāsanirvāpa . . . . . pott-nirvāpa |  
pramadā-kula dra. 2 etat sanirva Śīl-dēvya . . . . .

## Appendix III.

BHINMAL.  
Inscriptions.

16. kosa dra. . . . . : pramadākylēna . . . . .  
 ācamindrā-kālam yāva  
 17. -t. . . . . nīkāpantyaṁ || karapantyaṁ . . . . .  
 nāgula-sutēna maha° Dē-  
 18. -dakēna . . . . . | Guhlō Śāha° Rudrapāla-suta-  
 sōḍha° Haristhēna (Sridē-)  
 19. -vīya-sthūtakā dra. 4 Sahajapāla-suta-sā  
 sthīla-  
 20. -ka dra 4. . . . .  
 21-23. Illegible.

## Translation.

- 1-2. Ōm. Reverence to the Sun ! Victorious is that sun, the store-  
 house of Brightness, at whose rising and setting the three-  
 eyed (Śiva), even though (his own) lotus feet are touched  
 by the diadems of the gods, folds his hands (in adoration)  
 3-5. On Saturday the first of the light half of Āśvina in the year  
 1339 (1283 A.D.) on this day here in holy Bhinmal, in the  
 prosperous and victorious reign of his majesty the  
 Mahārani Śīlāvatastha, in the term of office of the  
*pamea* (consisting of) the maha° . . . . . stha and the  
 rest, appointed by him.  
 6-8. Dra. 20, twenty drammaas, were deposited in the treasury  
 for the sun-god Śīl Jagaśvami by Saha° Sahajapāla son  
 of Rudrapāla the Guhlā, who came here from Śīl  
 Javālpura, for every part of the *bali*, the worship, and  
 the *amgubhaga*, for his own (spiritual) benefit and for the  
 benefit of his father and mother.  
 8-9. . . . . near the Kucha road 1 one field was given called  
 Kathana-panā  
 9-11. To the god on . . . . . day for worship, the wife of  
 Saha° Sahajapāla for her own benefit and for the  
 benefit of her father and mother. . . . . deposited  
 dra. 10, ten drammaas, . . . . .  
 11-12. \* Drammaas in the Āśvina Yūti on the first day of the  
 light half of Āśvina are to be expended by the god from  
 the treasury (for) the day's *bali*, worship. . . . .  
 13-17. In the *bali* endowment wheat s' 2. . . . *gha ka(sha)* 8  
 in the *mūṇḍya cōsha* pā 2 mung . . . . *gha ka(sha)* 4 ;  
 in the *amgubhaga* for every part of the leaves and betel  
 dra. 1, the Bhat's dole . . . . ., (the Abjoti's dole 1,  
 the band of singing women dra. 2 ; all this the god's  
 treasury dra. . . . . by the band of singing  
 women . . . . . so long as sun and moon  
 endure . . . . . is to be doled out, is to be  
 expended.  
 17-20. By the Maha° Dīdāka son of Nāgula . . . . .  
 By Sōḍha° Haristha son of Sāha Rudrapāla the Guhlā,  
 four *sthitaka drammaas* of the god . . . . . By  
 Sā . . . . . son of Sahajapāla . . . . .  
*sthitaka drammaas* 4. . . . .  
 21-23. Illegible.

XV.—(S 1342; A.D. 1286. Not in Plan.) In the ground close to the  
 wall on the right in entering the enclosure of old Mahālakshmi's temple.  
 Prose. No. 50 of the Bhāunagar State Collection (Bhāu. Prā. I. page 15.)

1. Ōm. Namaḥ Sūryāya || Yasyōdayāstasamayē sura-ma-
2. -kūṭa-niṣprishṭa-curaua kamalō pi kurutō 3 nijaḥin trinōtra  
saja-
3. -yati dhānuānā nidhiḥ sūryaḥ || Śaṁvat 1312 (1286 A.D.)  
Āśvina vadh 10 Ra-
4. -vāvatyācā Śrī Śrīmālō Mahārajakula Śrī Śāmvatasīha dē-
5. -va-kalyāṇa-vijaya-rājyē śāmyukta-mahā° Pandyā-prabhṛiti-  
pamca-
6. -kula pratipattāu | Śāsanāk-śharāṇi praya(c)chati yathā | Rāthō-  
da-
7. -jātya-Ūtiśvatīha-pāutra Vāgasasuta Sīla° Alhaṇasīhē-
8. -na ātmya māta-patē śrēyaśō svaśrēyaśō Śrī Jagasvāmi-dō-
9. -vāya Āśvini yātrāyān dāśamīdhūc dvasa-bali-pūja prē-
10. -k-śmākaḥ amṛga-bhōga-nim(ē)tanī śēlahathābhāya-
11. -t Śrī kaṇṇaṭṭa ācāndrerkayavat pradatta dra. 4½.
12. Śrīdēvya-kōṭṭa.
13. Āraṇḍārkaṇi yāḥ kōpi Śēlahathō bhavati tēnu varṣaṇi  
varṣaṇi prati pā-
14. -lauṭyān ca | vāḥbhūir vasudhā bhukta rājābhū Sagarādābhū  
yasya
15. yasya yada bhūmi tasya tasya tadā phalaṇi || 1 Āśvina vadh  
10 va-
16. -li-nihāndhe gōdhūma sō ghṛta ka 12 māyēdyē  
coshān pā 4.
17. mugān mā 1 ghṛta ka 3 Vyasanirvāpa 1 Abōṭṭhūrvāpa  
1 kuṇṭkuma
18. kastūri-pratyān(gaṇi) dra. 1 pushpa-pratyān(gaṇi) dra. 4  
pamadakula-pratyān(gaṇi) dra. 1 patra-pā-
19. ga-pratyān(gaṇi) dra. 1 cīṭa sarvaṇi varṣaṇi 2 prati Śrī-  
dēvya bhāṇḍagat
20. Vantāpakai kaṇṇapātyān || māṇḍalaṇi sadāśīḥ || bhikṣān  
Dhruva
21. Nāgula-suta-dhru° Dedakēna Utkrppa sūtra° Bhīmasīhēna||.

## Translation.

- 1 - 3. Ōm. Reverence to the Sun ' Victorious is that sun, the store-  
house of brightness, at whose rising and setting the three-  
eyed (Siva), even though (his own) lotus feet are touched  
by the diadems of the gods, folds his hands (in adoration).
- 5 - 6. Śaṁvat 1312 on Sunday the 10th of the dark half of  
Āśvina, on this day here in holy Śrīmāla, in the prosperous  
and victorious reign of his majesty the Maharāṇ Śrī Śāma-  
vatasīha-dēva, in the term of office of the *pamca* (consisting  
of) Mahā° Pāndyā and the rest, appointed by him, he sets  
forth the writing of the grant as follows.
- 6 - 11. By Sīla° Alhaṇasīha son of Vāgasa and grandson of Ūti-  
śvatīha of the Rāthōda race, for the benefit of his own  
mother and father and for his own benefit, 4½ *drammas*  
(were) given to the god Śrī Jagasvāmi, for the day's *bali*,  
the worship, the *darsana* &c., and the *amgabhōga* on the  
10th day at the Āśvina yātrā . . . . so long as sun and  
moon (endure) . . . .
- 12 - 14. The god's treasure house . . . . . whosoever is Śēlahatha,  
by him every year it is to be maintained also.

## Appendix III.

BHINMAL.

Inscriptions.

## Appendix III.

BHINMAL  
Inscriptions.

- 11-15. The earth has been enjoyed by many kings, beginning with Sagara. Whosoever the earth is at any time, his is also the fruit thereof.
- 15-16. In the endowment of the *baṭi* for the 10th of the dark half of Āśvina wheat *ci* . . . *gha ket(ishus)* 12; in the *nairadya cōsha pā* 4.
- 17-19. Mung *mā* 4, *gha ka* 1 the Bhat's dolo 1, the Abōt's dolo 1, for turmeric and musk each dra. 4 for flowers each dra. 4, for the baid of singing women each dra. 1, for haves and betel each dra. 4.
- 19-21. All this is to be expended yearly from the god's treasury . . . Gooa kock! Bha for ever. Written by Dhru° Dīdāka son of Dhruva Nāgula. Engraved by Bhīmasīha the carpenter.

XVI.—(S. 1345, A.D. 1289, No. 9 of Plan) On the south face of the lower square section of the north-east corner pillar of the *dhūmra*. The first thirteen lines are in verse, the rest in prose. No. 48 of the Bhānagar State Collection (Bhaṇ Pra. I. list page 14):

1. Svargapavargasukhalaṁ paramatmapāṇi dhṛisayanīti yaṁ  
sukṛtino hṛdī sa-
2. -rvadaya tasmāi munij-panahitaya sārā-māndia saṁstāya-  
māna-paritaya
3. namah Śivaya || 1 Ślaghyah satām sukṛt sakṛtī manushyōs-  
mānyō maha-
4. -ttama-gaṇaḥ Subhataḥ sa ēva | yaśca jagatrayagurmū girijā-  
dhūmathaṁ devāni
5. namasyati natō 3 undmanī mahōśa || 2 Sōmō 3 si cātha nati-  
mittara-kairavō-
6. -sha puṇya Prabhāsa-sarasi sthūm a'ritōśm | tasmā . . . . .  
mahabala-
7. -the s'ri Sōmanātha itī siddhigataṁ sinaram || 3 Puṇyah Pra-  
bhāsaśaśi-bhūsha-
8. -na-Karṇamāla-papa pramōcana runānti-vimōcanādyaḥ | ēt-  
āḥ Ka-
9. -pārā-kṛta-sat-tithihīḥ pradhānais tīrthār alani kṛitam  
idam hṛdayaṁ mamāstu ||
10. 4 Ētasya puṇya-pāyasō jaladhōs tathasya Sarasvata-niva-  
hasyata.
11. Da° || Ōm namah Sūryāyah Jaj(j)yōti prasaratī tarha lōka  
kṛtyāya ni-
12. -tyam | yanuāmōktaṁ sakalikalushaṁ jātī pāraṁ payodhō  
| sarvasyātmaṁ sngati-
13. -surathō -dhvānta-mātāniga-siṁgha | diśhā-sūryō  
nava(bha) si bhagavān sarvasyāntyanika-
14. -rōti || Saṁvat 1315 varshē Māgha Vadi 2 Sōmō 3 dyāha s'ri 2  
mālē mahārāja-
15. -kula-Śrī śāmvata-siṁgha-dēva-kalyāṇa-vijaya-rājyō tan-  
niyukta-maha° chāmāha-
16. -prahṛti-panicakula-pratipatāu ēvamkāle pravarttamāno  
Śrī-Jāvālipuravastavya-
17. Puskaraṇisthāntya-yajur-vēda pāthakāya | Padamalasyagō-  
trāya | Vrahma° na-
18. -vaghana-vaniśotpānnādhyava° Vāihāpāutra | Jyōti° Mā-  
dhava-pratidāuhitrā Jyō°

19. Tilaka-nāhūitra-Saṅgha-pātra-mātu-Pānala-suta | Vrahma°  
Vāgaṇa sāṁsārasya°  
20. Aśratān jñātva | Śrī Jagasvāmīn | Śrī-Śrīya-ya-mūrttē  
prāsāda-sāvaripaka-  
21. -laśarōpita | jatasradha-dēvaṁ saṁpūjya sama-sta-dēva-lōka-  
Vrahma-lōka-pra-  
22. -tyaksham | Vamśulvayōgharapī-samaksham | Ātmanaśca  
Ācānīdrakayāvat sūrya-prasāda-pra-  
23. -pta-tyartham | pratīvarsham | pūjām Śrī Jagasvami-dēva-  
bhāṁdagatō mksbpita | mūkma-vi  
24. sama-pū-dra. 100 dvitu Śatam Amśham dhammanām vyā-  
japadat Asvini-yātrayām Aśvi-  
25. -na vadi || dūc divasa vahi kayōvahi māmāthe gōdhūma sē  
4 pakvō ghrita ||  
26. ka 16 ānyelva cōshām mā 1 mūga mā 1½ ghrita ka | Vīdakē  
pūti 8 pūga 2 mūga-  
27. -bhōga-pratya dra. 1 pūshpa-pratya dra. 6 patrapūga-pra-  
tya° dra. 4 vyāsa-nirvapa-Ābhō-mrva-  
28. -pa-māmāthe cōsham sē ¼ mūga pa 3 ghrita ka 1 dakṣiṇā lō  
2 pramudakula dra. 4 cū-  
29. -t sa vām pratīvarsham acānīdrāka-yavat Śrīdevasya bhān-  
dagatāt vīcāntyam karāpa-  
30. -māsa ca | subham bhavatu sarvada | Jyoti Śūguda-sutēna  
Cānīdrādyena samaksham h-  
31. -khitam Kava Nagula sutonī Devakena utkīrṇa Śūtra°  
Nana-suta-Dēpaka-  
32. -m || māngalam sūta Śiṅh.

*Translation.*

- 1-3. Reverence to that Siva! the benefactor of those who bow to him, whose actions are praised by the leaders of gods and demons who gives the happiness of heaven and of salvation, whose form is the supreme soul, whom the wise ever lay hold upon in (their) heart.
- 3-5. Oh Mahesha, whosoever bowing daily does reverence to the god who is *gūṇa* of the three worlds, the lord of the mountain's daughter (Parvati), that man is worthy of praise from the righteous, fortunate, wise, to be honoured for most excellent virtues, a true hero.
- 5-7. Oh Lord thou art the moon among the bending lotuses that have secured their place in the holy pool of Prabhasa, therefore I make mention (of thee) famous by the name of Sōmāntha on the seashore . . . .
- 7-9. May this heart of mine be adorned by these holy chief *Arthas*, Prabhasa, the moon's ornament, the Lotus (pool), the Release from Sin, the Release from Debt and Suffering &c., whose lucky days have been fixed by Kapardi (Siva).
10. Of this pool of pure water and . . . . of Sarasvati.
11. Da Om! Reverence to the Sun, whose light ever reaches far for the work of mankind, at the mention of whose name all sin goes beyond the ocean: the soul of all, whose path and whose ear are good, related to the trumpeting elephants (of darkness): When the Lord Sun is seen in the sky, he makes the last (?) . . . of all.

**Appendix III.**

• **BHINMAL.**  
Inscriptions.

## Appendix III.

BHINMAL.  
Inscriptions.

- 14-16. On Monday the second of the dark half of Māgha in the Sāmvat year 1345 (1289 A.D.), on this day there in holy Śrīmāla, in the prosperous and victorious reign of his majesty the Mahārām Śrī Samvata Singh, in the term of office of the *pamca* (consisting of) the Maha' Chāṇkhā and the rest, appointed by him.
- 16-21. At this time to (read by) Vagada the Brāhmana son of Sodhala and grandson of Adhyaya Vākya, of the Nava-ghana family, of the Padamala gōtra, student of the Yajurveda, of the town of Paskarān and living in Śrī Jivakpura, son of his mother Pūnala, and daughter's son of Tilaka the Joshi, and granddaughter's son of Mādhava the Jōshi—recognizing the impermanence of this world, a golden *kala-a* was set up on the palace . . . of the Sun Jagasvami.
- 21-24. (By him) worshipping the god in faith, before the world of the gods and the world of Brahma, for the purpose (?) of saving his ancestors in both hues, and himself, to gain the favour of the Sun so long as sun and moon (endure), (for) worship every year, 200 *Vishapiṇi dramma*s of gold were deposited in the treasury of the god Śrī Jagasvami.
- 24-28. Out of the interest of these *drammas*, in the endowment of the day's *hala* and the *kāyāvali* on the 11th of the dark half of Āśvina at the Āśvina festival, wheat *ś* 1, *ghṛi ka(rsha)* 16 in the Navvōdya cōsha measure 1, mung *pā.* 1½, *ghṛi ka(rsha)* 1, for *pāṇsupāṇi* leaves 8, betel 2; for the Anṅabhāgā severally *dra* 1, for flowers severally *dra* 6, for leaves and betel severally *dra.* 1 in the endowment of the Bhat's dole and the Abūt's dole, cōsha *ś.* 1, mung *pā.* 3, *ghṛi ka(rsha)* 1, dakṣiṇya *lā* 2, the land of singing women *dra.* 4.
- 29-32. All this is to be separated and expended from the treasury of the god every year so long as sun and moon (endure). May it always be auspicious. Written by Dōdaka son of Kava' Nāgala for Chāndrāditya son of Jyoti' Vāgada. Engraved by Depāla son of Nāna the carpenter. Good luck! Bless for ever!

## APPENDIX IV.

## JAVA AND CAMBODIA.

AN incident redrems the early history of Gujarát from provincial narrowness and raises its ruling tribes to a place among the greater conquerors and colonisers. This incident is the tradition that during the sixth and seventh centuries fleets from the coasts of Sindh and Gujarát formed settlements in Java and in Cambodia. The Java legend is that about A.D. 603 Hindus led by Bhuvanajaya Sayelachála the son of Kasamarudra or Bálya Acha king of Kupat or Gujarát settled on the west coast of the island<sup>1</sup>. The details of the settlement recorded by Sir Stamford Raffles<sup>2</sup> are that Kasamarudra, ruler of Gujarát, the tenth in descent from Arjun, was warned of the coming destruction of his kingdom. He accordingly started his son Bhuvanajaya Sayelachála with 5000 followers, among whom were cultivators artisans warriors physicians and writers, in six large and a hundred small vessels for Java. After a voyage of four months the fleet touched at an island they took to be Java. Finding their mistake the pilots put to sea and finally reached Mataram in the island of Java. The prince built the town of Mendang Kramah. He sent to his father for more men. A reinforcement of 2000 arrived among them carvers in stone and in brass. An extensive commerce sprang up with Gujarát and other countries. The bay of Mataram was filled with stranger vessels and temples were built both at the capital, afterwards known as Bramhaman, and, during the reign of Bhuvanajaya's grandson Ardivijaya that is about A.D. 660, at Boru Buddor in Kedah<sup>3</sup>. The remark that an ancestor of the immigrant prince had changed the name of his kingdom to Gujarát is held by Lassen to prove that the tradition is modern. Instead of telling against the truth of the tradition this note is a stronger argument in its favour. One of the earliest mentions of the name Gujarát for south Marwár is Hsien Tsiang's (A.D. 630) Km-che-la or Gujjara. As when Hsien Tsiang wrote the Gujjara chief of Bhinnál, fifty miles west of Abu, already ranked as a Kshatriya his family had probably been for some time established, perhaps as far back as A.D. 190 a date by which the Mihira or Gujjara conquest of Valabhi and north Gujarát was completed.<sup>4</sup> The

## Appendix IV.

## JAVA.

<sup>1</sup> Sir Stamford Raffles' Java, II. 83. From Java Hindus passed to near Binjai Massin in Borneo probably the most eastern of Hindu settlements (Jour. R. A. Soc. IV. 185). Temples of superior workmanship with Hindu figures also occur at Waahon 400 miles from the coast. Dalton's Diaks of Borneo Jour. Asiatic (N. S.) VII. 153. An instance may be quoted from the extreme west of Hindu influence. In 1873 an Indian architect was found building a palace at Gondar in Abyssinia. Keith Johnson's Africa, 269.

<sup>2</sup> Raffles' Java, II. 65-85. Compare Lassen's Indische Alterthumskunde, II. 10, 40; IV. 460. <sup>3</sup> Raffles' Java, II. 87.

<sup>4</sup> Compare Tod's Annals of Rájasthan (Third Reprint), I. 87. The thirty-nine Chohan successions, working back from about A.D. 1200 with an average reign of eighteen years, lead to A.D. 498.

Appendix IV.  
JAVA.

details of the help received from Gujaraṭ after the prince's arrival show that the parent state had weathered the storm which threatened to destroy it. This agrees with the position of the Bhinnal (Gujjaras) at the opening of the seventh century, when, in spite of their defeat by Prabhakara-vardhana (A.D. 600-606) the father of Śiṅgha (A.D. 606-641) of Magadha, they maintained their power at Brach and at Valabhi as well as at Bhinnal.<sup>1</sup> The close relations between the Gujjaras and the great seafaring Mihiras or Meds make it likely that the captains and pilots who guided the fleets to Java belonged to the Med tribe. Perhaps it was in their honour that the new Java capital received the name Mendang, as at a later period it was called Brambanum or the town of Brāhmanas. The fact that the Gujjaras of Brach were sun-worshippers not Buddhists causes no difficulty since the Bhinnal Gujjaras whom Hsuen Tsang visited in A.D. 630 were Buddhists and since at Valabhi Buddhism, Shaivism and sun-worship seem to have secured the equal patronage of the state.

Besides of Gujaraṭ and its king the traditions of both Java and Cambodia contain references to Hastinagata or Hastinapura, to Taxila, and to Rumadesa.<sup>2</sup> With regard to these names and also with regard to Gandhara

<sup>1</sup> Compare Note on Bhinnal page 467.

<sup>2</sup> According to Cunningham (Ancient Geography, 12) and Beal's Buddhist Records, I. 109 (note 92) the site of **Hastinagara** of the early times is on the Swat river eighteen miles north of Peshawar. In Vedic and early Mahābhārata times Hastinapura was the capital of Gandhara (Beal's Jour. Roy. As. Soc. XXI. 217). In the seventh century it was called Pushkalavati (Beal's Buddhist Records, I. 109). **Taxila**, the capital of the country east of the Indus, was situated about forty miles east of Attock at Shahdri near Kila a s.d. Cunningham's Ancient Geography, 106. According to Cunningham (Ibid. 109), Taxila continued a great city from the time of Alexander till the fifth century after Christ. It was then laid waste apparently by the great White Hun conqueror Mihiridatta (A.D. 500-550). A hundred years later when Hsuen Tsang visited it the country was under Kashmir, the royal family were extinct, and the nobles were struggling for power (Beal's Buddhist Records, I. 136). **Rumadesa**. References to Rumadesa occur in the traditions of Siam and Cambodia as well as in those of Java. Fleets of Rome are also noted in the traditions of Bengal and Orissa as attacking the coast (Fergusson's Architecture, III. 640). Compiling the mention of Rōm with the tradition that the Cambodian temples were the work of Alexander the Great Colonel Yule (Ency. Brit., Article Cambodia) takes Rōm in its Musulmān sense of Greece or Asia Minor. The variety of references suggested to Fergusson (Architecture, III. 610) that these exploits are a vague memory of Roman commerce in the Bay of Bengal. But the Roman rule was that no fleet should pass east of Ceylon (Remond Jour. As. Ser. VI. Tom. I. page 322). This rule may occasionally have been departed from as in A.D. 166 when the emperor Marcus Aurelius sent an ambassador by sea to China. Still it seems unlikely that Roman commerce in the Bay of Bengal was ever active enough to gain a place as settler and coloniser in the traditions of Java and Cambodia. It was with the west not with the east of India that the relations of Rome were close and important. From the time of Mark Antony to the time of Justinian, that is from about B.C. 30 to A.D. 550, their political importance as allies against the Parthians and Sassanians and their commercial importance as controllers of one of the main trade routes between the east and the west made the friendship of the Kushans or Sakas who held the Indus valley and Bactria a matter of the highest importance to Rome. How close was the friendship is shown in A.D. 60 by the Roman General Corbulo escorting the Hyrcanian ambassadors up the Indus and through the territories of the Kushans or Indo-Skythians on their return from their embassy to Rome. (Compare Rawlinson's Parthia, 271.) The close connection is shown by the accurate details of the Indus valley and Bactria recorded by Ptolemy (A.D. 166) and about a hundred years later (A.D. 247) by the author of the Periplus and by the special value of the gifts which the Periplus notices were set apart for the rulers of Sindh. One result of this long continued alliance was the gaining by the Kushan and other rulers of Peshawar and the Panjāb of a knowledge of Roman coinage, astronomy and architecture. Certain Afghan or Bactrian coins bear the word Roma apparently the name of some Afghan city. In spite of this there seems no

and to Cambodia, all of which places are in the north west of India, the question arises whether the occurrence of these names implies an historical connection with Kábul Pesháwar and the west Panjáb or whether they are mere local applications and assumptions by foreign settlers and converts of names known in the Bráhmaṇ and Buddhist writings of India.<sup>1</sup> That elaborate applications of names mentioned in the Mahábhárata to places in Java have been made in the Java version of the Mahábhárata is shown by Raffles.<sup>2</sup> Still it is to be noticed that the places mentioned above, Kamboja or Kábul, Gandhara or Pesháwar, Taxila or the west Panjáb, and Ramadesa apparently the south Panjáb are not, like Ayodhya, the capital of Siān or like *Latta-patta-puri*, that is Imbrapastha or Dohli the later capital of Cambodia,<sup>3</sup> the names of places which either by their special fame or by their geographical position would naturally be chosen as their original home by settlers or converts in Java and Cambodia. Four ground can then four be claimed for the presumption that the leading position given to Kamboja, Gandhara, Taxila and Ramadesa in Javan and Cambodian legends and place-names is a trace of an actual and direct historical connection between the north-west of India and the Malay Archipelago. This presumption gains probability by the argument from the architectural remains of the three countries which in certain peculiar features show a marked resemblance both in design and in detail as in the judgment of Mr. Fergusson to establish a strong and direct connection.<sup>4</sup> A third argument in favour of a Gujarát strain in Java are the traditions of settlements and expeditions by the rulers of Malwa which are still current in south Márwár.<sup>5</sup> Further a proverb

## Appendix IV.

## JAVA.

reason to suppose that Rome attempted to overlord the north-west of India still less that any local ruler was permitted to make use of the great name of Rome. It seems possible that certain notices of the fleets of Róm in the Bay of Bengal refer to the fleets of the Arab Al-Róm that is Arab or north-west Soudan apparently the Roman of the Chaldean history of the Malabar Coast. (Yule's Cathay, I. lxxxix. note and Marco Polo, II. 243.)

<sup>1</sup> Compare Fergusson's Architecture, III. 610. Yule in Huey, Hist. Cambodii.

<sup>2</sup> Java, I. 411. Compare Fergusson's Architecture, III. 644.

<sup>3</sup> See Yule in Jour. Roy. As. Soc. (N. S.), I. 356. Fergusson's Architecture, III. 631.

<sup>4</sup> Of the Java remains Mr. Fergusson writes (Architecture, III. 644-648). The style and character of the sculptures of the great temple of Boro Buddor are nearly identical with those of the later caves of Ajunta, on the Western Ghats, and in Salsette. The resemblance in style is almost equally close with the buildings of Takht-i-Blu in Gandhara (Ditto, 647). Agam (page 647) he says: The Hindu immigrants into Java came from the west coast of India. They came from the valley of the Indus not from the valley of the Ganges. Once more, in describing No. XXVI. of the Ajunta caves Messrs. Fergusson and Burgess (Rock-cut Temples, 345 note II) write: The execution of these figures is so nearly the same as in the Boro Buddor temple in Java that both must have been the work of the same artists during the latter half of the seventh century or somewhat later. The Buddhists were not in Java in the fifth century. They must have begun to go soon after, since there is a considerable local element in the Boro Buddor.

<sup>5</sup> Traditions of expeditions by sea to Java remain in Márwár. In April 1895 a bard at Bhūmál related how Bhūgráji of Ujjain in anger with his son Chāndravan drove him away. The son went to a Gujarát or Káthiáwár port obtained ships and sailed to Java. He took with him as his Bráhmaṇ the son of a Magh, Pandit. A second tale tells how Vikram the redresser of evils in a dream saw a Javanese woman weeping, because by an enemy's curse her son had been turned into stone. Vikram sailed to Java found the woman and removed the curse. According to a third legend Chāndravan the grandson of Vir Prāmīr saw a beautiful woman in a dream. He travelled everywhere in search of her. At last a Rishi told him the girl lived in Java. He started by sea and after many dangers and wonders found the dream-girl in Java. The people of Bhūmál are familiar with the Gujarát proverb referred to below Who goes to Java comes not back. MS. Notes, March 1895.

## Appendix IV.

## JAVA.

still well known both in Mûrwâr and in Gujarât runs :

● *Je jar Jave te kali nahi dew*  
*A'is to sâth pulhi bathke khêve.*  
 Who to Java nâsa ne'er come home.  
 If they return, through seven lives  
 Seated at ease their waltz survives.<sup>1</sup>

Once more the connection with Gujarât is supported by the detail in the Java account which makes Lant Mira the starting point for the colonising fleet. This Sir S Raffles supposed to be the Red Sea but the Mihirs' or Meds' sea may be suggested as it seems to correspond to the somewhat doubtful Arab name Baharimad (sea of the Meds') for a town in western India sacked by Junaid. Against this evidence two considerations have been urged: (a) The great length of the voyage from Gujarât to Java compared with the passage to Java from the east coast of India, (b) That no people in India have known enough of navigation to send a fleet fit to make a conquest. As regards the length of the voyage it is to be remembered that though Sumatra is more favourably placed for being colonised from Bengal Orissa and the mouths of the Godavari and Krishna, in the case either of Java or of Cambodia the distance from the South and Kathiavâda ports is not much greater and the navigation is in some respects both safer and simpler than from the coasts of Orissa and Bengal. In reply to the second objection that no class of Hindus have shown sufficient skill and enterprise at sea to justify the belief that they could transport armies of settlers from Gujarât to Java the answer is that the assumption is erroneous. Though the bulk of Hindus have at all times been averse from a seafaring life yet there are notable exceptions. During the last two thousand years the record of the Gujarât coast shows a genius for seafaring fit to ensure the successful planting of north-west India in the Malay Archipelago.<sup>2</sup>

<sup>1</sup> Another version is .

*J. jai lat to phan nâra*  
*Jo pho ar to poya poma khêve*  
*I bala dhan lat*

Who go to Java they for aye.  
 If they return they feast and play  
 Such stores of wealth their risks repay.

<sup>2</sup> Compare Crawford (A.D. 1820) in As. Res. XIII 157 and Lassen Ind. Alt. II. 1043.

<sup>3</sup> The following details summarise the available evidence of Gujarât Hindu enterprise by sea. According to the Greek writers, though it is difficult to accept their statements as free from exaggeration, when in B.C. 325 Alexander passed down the Indus the river showed no trace of any trade by sea. If at that time sea trade at the mouth of the Indus was so scanty as to escape notice it seems fair to suppose that Alexander's ship-building and fleet gave a start to deep sea sailing which the constant succession of strong and vigorous northern tribes which entered and ruled Western India during the centuries before and after the Christian era continued to develop.\* According to Vincent (Periplus, I. 23, 36, 264) in the time of Agathareudes (B.C. 200) the ports of Arabia and Ceylon were entirely in the hands of the people of Gujarât. During the second century after Christ, when, under the great Rudradaman (A.D. 143-158), the Sinh or Kshatrapa dynasty of Kathiavâda was at the height of its power, Indians of Tientso, that is Simlha, brought presents by sea to China (Journal Royal Asiatic Society for January 1896 page 9). In A.D. 166 (perhaps the same as the preceding) the Roman emperor Marcus Aurelius sent by sea to China ambassadors with ivory rhinoceros' horn and other articles apparently the produce of Western India (D. Guignes' Hmas, I. [Part I.] 32). In the third century A.D. 217 the Periplus (McCrindle, 17, 52, 61, 96, 109)

\* Alexander built his own boats on the Indus. (McCrindle's Alexander, 77.) He carried (pages 93 and 131) these boats to the Hydaspes on the Jhelum (134 note 1, where he found some country boats he built a flotilla of gallees with thirty oars he made dockwards (pages 146-157), his crews were Phoenicians, Syrians, Karians, and Egyptians.

That the Hindu settlement of Sumatra was almost entirely from the

## Appendix IV.

## JAVA.

notices large Hindu ships in the east African Arab and Persian ports and Hindu settlements on the north coast of Sokotra. About a century later occurs the doubtful reference (Wilford in Asiatic Researches, IX. 224) to the Diveni or pirates of Din who had to send hostages to Constantine the Great (A.D. 320-340) one of whom was Theophilus afterwards a Christian bishop. Though it seems probable that the Kshatrapas (A.D. 70-400) ruled by sea as well as by land fresh seafaring energy seems to have marked the arrival on the Sindhi and Kathiawar coasts of the Juan Juan or Avars (A.D. 390-450) and of the White Huns (A.D. 450-550). During the fifth and sixth centuries the ports of Sindhi and Gujarat appear among the chief centres of naval enterprise in the east. How the sea ruled the religion of the newcomers is shown by the fane which gathered round the new or revised gods Śiva the Poseidon of Somnāth and Krishna the Apollo or St. Nicholas of Dwarka. (Compare Tod's Annals of Rajasthan, I. 525.) In the fifth century (Yule's Cathay, I. lxxviii.) according to Hamza of Isfahan, at Hira near Kuta on the Euphrates the ships of India and China were constantly moored. In the early sixth century (A.D. 518-519) a Persian ambassador went by sea to China (Ditto, I. lxxiv.). About the same time (A.D. 526) Cosmas (Ditto, I. clxxviii.) describes Sindhu or Dabul and Orlota that is Soratha or Veraval as leading places of trade with Ceylon. In the sixth century, apparently driven out by the White Huns and the Mihiras, the Jats from the Indus and Kachh occupied the islands in the Bahrein gulf, and perhaps manned the fleet with which about A.D. 570 Nushirvan the great Sassanian (A.D. 531-578) is said to have invaded the lower Indus and perhaps Ceylon.\* About the same time (Pergusson Architecture, III. 612) Amāvati at the Krishna mouth was superseded as the port for the Golden Chersonese by the direct voyage from Gujarat and the west coast of India. In A.D. 630 Hiuen Tsiang (Ditto's Buddhist Records, II. 269) describes the people of Śmāshīa as deriving their livelihood from the sea, engaging in commerce, and exchanging commodities. He further notices that in the chief cities of Persia Hindus were settled enjoying the full practice of their religion (Remond's Abulfeda, clxxv.). That the Jat not the Arab was the moving spirit in the early (A.D. 637-770) Muhammadan sea raids against the Gujarat and Konkan coasts is made probable by the fact that these seafaring ventures began not in Arabia but in the Jat-settled shores of the Persian Gulf, that for more than fifty years the Arab heads of the state fought them, and that in the Mediterranean where they had no Jat element the Arabs were powerless at sea. (Compare Elliot, I. 416, 417.) That during the seventh and eighth centuries when the chief migrations by sea from Gujarat to Java and Cambodia seem to have taken place, Chinese fleets visited Din (Yule's Cathay, lxxix.), and that in A.D. 759 Arabs and Persians besieged Canton and pillaged the storehouses going and returning by sea (De Guignes' Huns, I. [Pt. II.] 503) suggest that the Jats were pilots as well as pirates.† On the Sindhi Kachh and Gujarat coasts besides the Jats several of the new-come northern tribes showed nautical energy at sea. It is to be remembered that as detailed in the Statistical Account of Thana (Bombay Gazetteer, XIII. Part II. 433) this remarkable outburst of sea enterprise may have been due not only to the vigour of the new-come north-ers but to the fact that some of them, perhaps the famous iron-working Turks (A.D. 580-680), brought with them the knowledge of the magnet, and that the local Brahman, with religious skill and secrecy, shaped the bar into a divine fish-melon or *calantra*, whelf floating in a basin of oil, he consulted as a private oracle. In the ship and when the stars were hid guided the pilot in what direction to steer. Among new seafaring classes were, on the Makran and Sindhi

\* Remond's Memoire Sur l'Inde, 127. The statement that Nushirvan received Kachh from the king of Scindib (Elliot's History, I. 407. Tabari, II. 221) throws doubt on this expedition to Ceylon. At the close of the sixth century Kachh or Dabul could not have been in the gift of the king of Ceylon. It was in the possession of the Bahman kings of Aror in Upper Sindhi perhaps of Shahi Tegin Devaja who then reigned. (Compare Cunningham's Oriental Congress, I. 212.) According to Garret (J. As. Soc. VI. Trans. XIII. 182 note 2) this Scindib is Suradeb that is Syria and Antioch places which Nushirvan is known to have taken. Several other references that seem to imply a close connection between Gujarat and Ceylon are equally doubtful. In the Mahabharata (A.D. 100-300) the Śubhalas being *śaṭayam* (rubies?) elephants' housings and heaps of pearls. The meaning of Śubhalaka in Samudragupta's inscription (A.D. 350) Early Gujarat History page 64 and note 5 is uncertain. Neither Mihirakula's (A.D. 530) nor Lalitaditya's (A.D. 700) conquest of Ceylon can be doubted. In A.D. 1095 when Abul Fatih the Carnation ruler of Multan was attacked by Mahmud of Ghazni he retired to Ceylon. (Remond's Memoire, 225.) When Somnāth was taken (A.D. 1023) no people embarked for Ceylon (Ditto, 270).

† Compare at a later period (A.D. 1312) Ibn Batuta's great ship sailing from Kandahar (Gandhar north of Bouch) to China with its guard of Abyssinians as a defence against pirates. Remond's Abulfeda, clxxv.

## Appendix IV. east coast of India and that Bengal Orissa and Masulipatam had a large

## JAVA.

coasts the Badhas Kerks and Meds and along the shores of Kachh and Kāthiavada the closely connected Meils and Gurjjaras. In the seventh and eighth centuries the Gurjjaras, chiefly of the Chāpa or Chavada clan, both in Dvārka and Somnāth and also inland, rose to power, a change which, as already noticed, may explain the efforts of the Jats to settle along the Persian Gulf and the Red Sea. About A.D. 710 the Chāpas or Chavadas, who had for a century and a half been in command in Dvārka and Somnāth, established themselves at Anahilavada Pattan. According to their tradition king Yugaraja (A.D. 720-780) and his successor Yogaraja (A.D. 806-841) made great efforts to put down piracy. Yugaraja's sons plundered some Bengal or Red ships which stress of weather forced into Veraval. The king said 'My sons with labour we were raising ourselves to be Chāvdas of jameely rank; your greed throws us back on our old nickname of Choras or thieves.' Yogaraja refused to be comforted and mounted the funeral pyre. Dr. Bhagvanlal's History, 24. This tale seems to be a parable. Yogaraja's efforts to put down piracy seem to have driven large bodies of Jats from the Gujarat coast. In A.D. 831-35, according to Hui Alathyi (A.D. 834), a fleet manned by Hjaths or Jats made a descent on the Tigris. The whole strength of the Khilafat had to be set in motion to stop them. Those who fell into the hands of the Moslems were sent to Anarabie on the borders of the Greek empire (Remond's Fragments, 201-2). As in the legend, the Chavadi king's sons, that is the Chauras Mers and Gurjjaras, proved not less dangerous pirates than the Jats whom they had driven out. About fifty years later, in A.D. 892, Al-Buldhuri describes as pirates who scourged the seas the Meds and the people of Saurashtra that is Devpatan or Somnāth who were Choras or Gurjjaras † Buldhuri (Remond Sur L'Inde, 167) further notices that the Jats and other Indians had formed the same type of settlement in Persia which the Persians and Arabs had formed in India. During the ninth and tenth centuries the Gurjarat kingdom which had been established in Java was at the height of its power. (Ditto, Abulfeda, cccxxxviii.) Early in the tenth century (A.D. 915-930) Masudi (Yule's Marco Polo, II, 341; Elliot, I, 65) describes Sukotra as a noted haunt of the Indian corsairs called Biwarij which chase Arab ships bound for India and China. The merchant fleets of the early tenth century were not Arab alone. The Chauras of Anahilavada sent fleets to Bhot and Chin (Rās Mada, I 11). Nor were Mers and Chauras the only pirates. Towards the end of the tenth century (A.D. 980) Grahari the Chudasami, known in story as Grahariya the Ahir of Sorath and Gurnar so passed and repassed the ocean that no one was safe (Ditto, I 11). In the eleventh century (A.D. 1021) Alberuni (Sachau, II, 104) notes that the Biwarij, who take their name from their boats called *bihar* or *bira*, were Meds, a seafaring people of Kachh and of Somnāth a great place of call for merchants trading between Sofala in east Africa and China. About the same time (A.D. 1025) when they despaired of withstanding Mahmud of Ghazni the defenders of Somnāth prepared to escape by sea, and after his victory Mahmud is said to have planned an expedition by sea to conquer Ceylon (Tod's Rajasthan, I 108). In the twelfth century Idrisi (A.D. 1135) notices that Tatriva dirhaus, that is the Gajira (A.D. 319-500) and White Huiya (A.D. 500-580) (comage of Smidh and Gurjarat, were in use both in Madagascar and in the Malay islands (Remond's Memoires, 239), and that the merchants of Java could understand the people of Madagascar (Ditto, Abulfeda, cclxxvii). With the decline of the power of Anahilavada (A.D. 1260-1300) its fleet ceased to keep order at sea. In A.D. 1290 Marco Polo (Yule's Ed. II, 325, 328, 341) found the people of Gurjarat the most desperate

\* As an example of the readiness with which an inland race of northerners conquer seafaring compare the Franks of the Pontus who about A.D. 271 pressed in a few years from the Pontus to the Mediterranean in ports and leaving behind them the limit of Greek voyages sailed through Gibraltar to the Baltic. Gibbon, I 404-405.

† Remond's Memoires Sur L'Inde, 201. The traders of Chorwar, that is of the old Chauras or Chapa country near Veraval and Mangrol, are now known in Bombay as Chapadhas. The received explanation of Chapadhas is the roofed men; it is said in derisive allusion to their large and heavy head-dresses. But as the Porbandar head-dress is neither specially large nor ungraceful the common explanation can be hardly more than a pun. This suggests that the name Chapadhas is a trace of the early Chapa tribe of Gurjjaras who also gave their name to Chāpāmī. Tod's (Western India, 250, 258) description of the Chauras race with tradition of having come from the Red Sea and as a nautical Araba is the result of taking for Sukotra Sankodwara that is Red to the north of Dvārka.

‡ According to Abulfeda A.D. 1134 (Remond's Abulfeda, cccxxxix) some of the besieged fled to Ceylon. Furishtah (Briggs' Muhammadan Powers, I, 75) records that after the fall of Somnāth Mahmud intended to fit out a fleet to conquer Ceylon and Pegu. According to Bird (Muhammad-Ahmed, 146) Ceylon or Suwandu remained a dependency of Somnāth till A.D. 1280 when the king Vijayabahu became independent.

§ The common element in the two languages may have been the result of Gurjarat settlements in Madagascar as well as in Java and Cambodia. This is however doubtful as the common element may be either Arabic or Polynesian.

share in colonising both Java and Cambodia cannot be doubted<sup>1</sup>

## Appendix IV.

JAVA.

pirates in existence. More than a hundred corsair vessels went forth every year, taking their wives and children with them and staying out the whole summer. They joined in fleets of twenty to thirty and made a sea-rondon five or six miles apart. \*Sokotra was infested by multitudes of Hindu pirates who encamped there and put up their plunder to sale. Ibn Batuta (in Elliot, I. 344-345) fifty years later makes the same complaint. Muslim ascendancy had driven Rajput chiefs to the coast and turned them into pirates. The most notable addition was the tholms who under Mokherap Chul, from his castle on Piram island, ruled the sea till his power was broken by Muhammad Tughlik in A.D. 1315 (Ris Mala, I. 318). Before their overthrow by the Muhammadans what large vessels the Rajput sailors of Gujarat managred is shown by Friar Oderic, who about A.D. 1321 (Stevenson in Kerr's Voyages, XVIII. 324) crossed the Indian ocean in a ship that carried 700 people. How far the Rajputs went is shown by the mention in A.D. 1270 (Yule's Cathay, 57 in Howorth's Mongols, I. 217) of ships sailing between Sumatra or Somnath and China. Till the arrival of the Portuguese (A.D. 1500-1508) the Ahmedabad sultans maintained their position as lords of the sea.\* In the fifteenth century Java appears in the state list of foreign landars which paid tribute (Bud's Gujarat, I. 11), the tribute probably being a cess or ship tax paid by Gujarat traders with Java in return for the protection of the royal navy. In east-Africa in A.D. 1498 (J. As. Soc. of Bengal, V. 781) Vasco da Gama found sailors from Cambay and other parts of India who guided themselves by the help of the stars in the north and south and had nautical instruments of their own. In A.D. 1510 Albuquerque found a strong Hindu element in Java and Malacca. Sumatra was ruled by Para-meshwara a Hindu whose son by a Chinese mother was called Rajput (Commentaries, II. 63, III. 73-79). After the rule of the sea had passed to the Portuguese, tinjarat Hindus continued to show marked courage and skill as merchants, seamen and pirates. In the seventeenth century the French traveller Mandelslo (A.D. 1678, Travels 701, 108) found Achin in north Sumatra a great centre of trade with Gujarat. During the seventeenth and eighteenth centuries the Sangamans or Sangar Rajputs of Mandvi in Kathi and of Bhavnagar in north Kathiawar were much dreaded. In A.D. 1750 Grose describes the small cruisers of the Sangamans troubling boats going to the Persian Gulf, though they seldom attacked large ships. Between A.D. 1800 and 1808 (How's Indian Navy, I. 274) pirates from Bat established themselves in the round temple at Somnath. In 1820, when the English took Bat and Dwarka from the Waghels, among the pirates besides Waghels were Bidhels a branch of Bahlons, Bhattis, Kharwas, Lohanas, Makwanas, Rahtors and Waghams. A trace of the Chauras remained in the neighbouring chief of Arana.† Not had the old love of seafaring deserted the Kathiawar chiefs. In the beginning of the present century (A.D. 1825), Tod (Western India, 152, compare Ris Mala, I. 215) tells how with Bip Singh of Bhavnagar his port was his grand hobby and shipbuilding his chief interest and pleasure; also how Rao Ghor of Kachh (A.D. 1760-1778) built equipped and manned a ship at Mandvi which without European or other outside assistance safely made the voyage to England and back to the Malabar Coast where arriving during the south-west monsoon the vessel seems to have been wrecked‡.

<sup>1</sup> Crawford (A.D. 1820) held that Hindu influence in Java came from Kalunga or the island of Madras. Fergusson (Ind. Arch. 103, Ed. 1876) says: "The splendid remains at Amaravati show that from the months of the Krishna and Godavari the Buddhist of north and north-west India, colonised Pegu, Cambodia, and eventually the island of Java." Comp. Tavernier (A.D. 1666; Ball's Translation, I. 171) Masulistan is the

\* When in A.D. 1515 he secured Bahadur's splendid jewelled belt Humayun said: "These are the trappings of the lord of the sea." Bayley's Gujarat, 486.

† Compare in Bombay Public Diary 10, pages 197-207 of 17-6-67, the revenue headings Surat and Cambay with entries of two per cent on all goods imported and exported from either of these places by traders under the Honorable Company's protection.

‡ These Bidhels seem to be Humiloh's (A.D. 1720) Wares of Chance (New Account, I. 116). This chance is Chich near Dau apparently the place from which the Bhettias get their Bombay name of Chichnas. Towards the close of the eighteenth century Bhettias from Chich seem to have formed a pirate settlement near Daham on the Thana coast. Major Price, Memoirs of a Field Officer, 322 notes (A.D. 1793) June, the cantonary speed with which in travelling from Surat to Bombay by land they passed Daham through the Chansah jungle the district of a practical immunity of that name.

§ According to Sir A. Burnes (Jl. Bombay Geog. Soc. VI (1845) 27, 28) the special skill of the people of Kachh in navigation and ship-building was due to a young Rajput of Kachh, Ramnath Malan, who about a century earlier had gone to Holland and learned those arts. See Bombay Gazetteer, V. 116 note 2.

## Appendix IV.

## JAVA.

Reasons have been given in support of the settlement in Java of large bodies of men from the north-west coasts of India and evidence has been offered to show that the objections taken to such a migration have little practical force. It remains to consider the time and the conditions of the Gujarāt conquest and settlement of Java and Cambodia. The Javan date S. 525 that is A.D. 603 may be accepted as marking some central event in a process which continued for at least half a century before and after the beginning of the seventh century. Reasons have been given for holding that neither the commercial nor the political ascendancy of Rome makes it probable that to Rome the Rūm of the legends refers. The notable Roman element in the architecture of Java and Cambodia may suggest that the memory of great Roman builders kept for Rome a place in the local legends. But the Roman element seems not to have come direct into the buildings of Java or Cambodia; as at Amrāvati at the Krishna mouth, the classic characteristics came by way of the Panjāb (Tāhira) only, in the case of Java, not by the personal taste and study of a prince, but as an incident of conquest and settlement.<sup>1</sup> Who then was the ruler of Rūm near Taxila, who led a great settlement of Hindus from the Panjāb to Java. Names in appearance like Rome, occur in north-west India. None are of enough importance to explain the prince's title.<sup>2</sup> There remains the word *raum* or *rum* applied to salt land in the south Panjāb, in Mūrwār, and in north Sindh.<sup>3</sup> The great battle of Karnr, about sixty miles south-east of Multān, in which apparently about A.D. 530 Yaśodharman of Malwa defeated the famous White Hūna conqueror Mihirakula (A.D. 500-550) is described as fought in the land of Rūm.<sup>4</sup> This great White Hūna defeat is apparently the origin of the legend of the prince of Rūm who retired by sea to Java. At the time of the battle of Karnr the south Panjāb, together with the north of Sindh, was under the Śihabās of Aror in north Sindh, whose coins show them to have been not only White Hūnas, but of the same Jāva family which the great conquerors Toramāṇa

only place in the Bay of Bengal from which vessels sail eastwards for Bengal, Airakan, Pegu, Siam, Sumatra, Coruh China, and the Malibus and west to Hormuz, Makha and Madagascar. Inscriptions (Indian Antiquary, V. 314, VI. 356) bear out the correctness of the connection between the Kalinga coast and Java which Java legends have preserved. As explained in Dr. Bhandarkar's interesting article on the eastern passage of the Śakas (Journ. B. B. R. A. S., XVII.) certain inscriptions also show a Magadhi element which may have reached Java from Sumatra and Sumatra from the coast either of Bengal or of Orissa. Later information tends to increase the east and south Indian share. Compare Notices et Extraits des Manuscrits de la Bibliothèque Nationale Vol. XXVII. (Partie II) 2 Fascicule page 350.

<sup>1</sup> Compare Hsien Tsiang in Beal's Buddhist Records, II, 222 note 102. *Takua* may be Tochara that is Baktria, but the Panjah seems more likely. Compare Beal's Life of Hsien Tsiang, 136 note 2.

<sup>2</sup> Idrisi A.D. 1135 (Elliot, I, 92) has a Romala a middling town on the borders of the desert between Multān and Ser-tau. Cunningham (Ancient Geog. 252) has a Romaka Bazaar near where the Nāra the old Indus enters the Ran of Kachhi.

<sup>3</sup> Cunningham's Num. Chron. 3rd Ser. VIII, 241. The Mūhābhārata Romakas (Wilson's Works, VII, 176; Cunningham's Anc. Geog. 187) may have taken their name from one of these salt stretches. Ibn Khurdādhbih (A.D. 912) mentions Rumala (Elliot, I, 14, 87, 92, 93) as one of the countries of Sindh. In connection with the town Rumala Al Idrisi A.D. 1153 (Elliot, I, 74, 93) has a district three days' journey from Kalhata.

<sup>4</sup> Cunningham's Numismatic Chronicle 3rd Ser. VII, 236. The date of Karnr is uncertain. Fergusson (Arch. III, 746) puts it at A.D. 544. It was apparently earlier as in an inscription of A.D. 532 Yaśodharman king of Malwa claims to hold lands which were newly held by either Guptas or Hūnas. Cunningham Num. Chron. 3rd Ser. VIII, 236. Compare History Text, 76, 77.

and Mibirakula adorned. So close a connection with Mibirakula makes it probable that the chief in charge of the north of the Aror dominions shared in the defeat and disgrace of Kārur.<sup>1</sup> Seeing that the power of the Sāharās of Aror spread as far south as the Kāthuvāda ports of Somnāth and Diu, and probably also of Dmī at the Indus mouth, if the defeated chief of the south Panjāb was unable or unwilling to remain as a vassal to his conqueror, no serious difficulty would stand in the way of his passage to the seaboard of Aror or of his finding in Diu and other Sindh and Gujurāt ports sufficient transport to convey him and his followers by sea to Java.<sup>2</sup> This then may be the chief whom the Cambodian story names Phra Tong or Thom apparently Great Lord that is Mahārāja.<sup>3</sup>

The success of the Javan enterprise would tempt others to follow especially as during the latter half of the sixth and almost the whole of the seventh centuries the state of North India favoured migration. Their defeats by Sassanians and Turks between A.D. 550 and 600 would close to the White Hūnas the way of retreat northwards by either the Indus or the Kābul valleys. If hard pressed the alternative was a retreat to Kashmir or an advance south or east to the sea. When, in the early years of the seventh century (A.D. 600-606) Prabhakarasvārddhana the father of Śrī Harsha of Magadha (A.D. 610-612) defeated the king of Gandhāra, the Hūnas, the king of Sindh, the Gurjaras, the Iatas, and the king of Malava,<sup>4</sup> and when, about twenty years later, further defeats were inflicted by Śrī Harsha himself numbers of refugees would gather to the Gujurāt ports eager to escape further attack and to share the prosperity of Java. It is worthy of note that the details of Prabhakarasvārddhana's conquests explain how Gandhāra and Iata are both mentioned in the Java legends, how north-cruisers from the Panjāb were able to pass to the coast, how the Mārwar stories give the king of Mālwa a share in the migrations; how the fleets may have started from any Sindh or Gujurāt port, and how with emigrants may have sailed artists and sculptors acquainted both with the monuments and styles of the Kābul valley and Peshawar and with the carvings of the Ajanta caves. During the second half of the seventh century the advance of the Turks from the north and of the Arabs both by sea (A.D. 637) and through Persia (A.D. 650-660),<sup>5</sup> the conquering progress of a Chinese army from Magadha to Bannan in A.D. 645-650, the overthrow (A.D. 642) of

## Appendix IV.

## JAVA.

<sup>1</sup> Jour. As. Soc. B. VII. (Plate I) 298; Burnes' Bokhara, III. 76; Elliot's History, I. 405. Diu which is specially mentioned as a Sāharā port was during the seventh and eighth centuries a place of refuge for Arab ships. Yule's Cathay, I. lxxv.

<sup>2</sup> Diu, the name Panjāb Ports of the embassy to Augustus in no. 30 (though the Pafos may be so called merely because he ruled the lands of Alexander's Pafos) may seem to be the favourite Parthian name Phraates. But no instance of the name Phraates is noted among White Hūna chiefs and the use of Phra as in Phra Bat or Lord Buddha seems ground for holding that the Phra Tong of the Cambodia legend means Great Lord.

<sup>3</sup> Epigraphia Indica, I. 67.

<sup>4</sup> In A.D. 637 invaders attacked Thina from Oman and Broach and Sindh from Bahrein. Renaud's Mémoires Sur L'Inde, 170, 176.

<sup>5</sup> The passage of a Chinese army from Magadha to the Gandhāra river about A.D. 650 seems beyond question. The emperor sent an ambassador Onang-h-waentse to Śrī Harsha. Before Onang-h-waentse arrived Śrī Harsha was dead (died A.D. 642), and his place taken by an usurping minister (Se-na-fu-ti) Alana-chun. The usurper drove off the envoy, who retired to Tibet then under the great Songtsap. With help from Tibet and from the Rāja of Nepāl Onang returned, defeated Alana, and pursued him to the Gandhāra river (Kien-to-wei). The passage was forced, the army captured, the king queen and king's sons were led prisoners to China, and 580 cities surrendered, the magistrates proclaimed the victory in the temple of the ancestors and the emperor raised Onang to the rank of T'eh'no-san-ta-fore. Journal Asiatique Ser.

## Appendix IV.

## JAVA.

the Buddhist Sâharâis by their usurping Brâhmanist minister Chach and his persecution of the Jats must have resulted in a fairly constant movement of northern Indians southwards from the ports of Sindh and Gujârât.<sup>1</sup> In the leading migrations though fear may have moved the followers, enterprise and tidings of Java's prosperity would stir the leaders. The same longing that tempted Alexander to put to sea from the Indus mouth; Trajan (A.D. 116) from the mouth of the Tigris; and Mahmûd of Ghazni from Somnâth must have drawn Śaka Hûna and Gurjjara chiefs to lead their men south to the land of rubies and of gold.<sup>2</sup>

Of the appearance and condition of the Hindus who settled in Java during the seventh and eighth centuries the Arab travellers Sulaimân A.D. 850 and Masûdi A.D. 915 have left the following details. The people near the volcanoes have white skins pierced ears and shaved heads: their religion is both Brâhmanic and Buddhist; their trade is in the costliest articles-camphor aloes cloves and sandalwood.<sup>3</sup>

## CAMBODIA.

## CAMBODIA.

The close connection between Java and Cambodia, the alternate supremacy of Cambodia in Java and of Java in Cambodia, the likelihood of settlers passing from Java to Cambodia explain, to a considerable extent, why the traditions and the buildings of Java and Cambodia should point to a common origin in north-west India. The question remains: Do the people and buildings of Cambodia contain a distinct north Hindu element which worked its way south and east not by sea but by land across the Himalayas and Tibet and down the valley of the Yang-tse-kiang to Yunnan and Angkor. Whether the name Cambodia<sup>4</sup> proves an actual race or historical connection with Kamboja or the Kâbul valley is a point

IV. Tom. X, pages 81-121. The translator thinks the whole war was in the east of India and that the mention of the Gandhâra river is a mistake. The correctness of this view is doubtful. It is to be remembered that this was a time of the widest spread of Chinese power. They held Balk and probably Bannan. Yule's Cathay, I. lxviii. Compare Julien in Jour. As. Soc. Ser. IV. Tom. X, 289-291.

<sup>1</sup> Regarding these disturbances see Beal's Life of Hiuen Tsang, 156. Max Muller's India, 286. The Arab writers (A.D. 713) notice to what a degraded state Chach had reduced the Jats. In comparing the relative importance of the western and eastern Indian strains in Java it is to be remembered that the western element has been overlaid by a late Bengal and Kalinga layer of fugitives from the Tibetan conquest of Bengal in the eighth century, the Babu with the Gurkha at his heels, and during the ninth and later centuries by hands of Buddhists withdrawing from a land where their religion was no longer honoured.

<sup>2</sup> In A.D. 116 after the capture of Babylon and Ctesiphon Hadrian sailed down the Tigris and the Persian Gulf, embarked on the waters of the South Sea, made inquiries about India and regretted he was too old to get there. Rawlinson's Ancient Monarchies, VI, 313.

<sup>3</sup> Reinaud's Abulfida, cccxc.

<sup>4</sup> The origin of the name Kamboja seems to be Kâmbojâpura an old name of Kâbul preserved almost in its present form in Ptolemy's (A.D. 160) Kaboura. The word is doubtfully connected with the Achaemenian Kamhyse (B.C. 529-521) the Kamhujia of the Behistun inscription. In the fifth of the Aśoka edicts (B.C. 240) Kâmbôja holds the middle distance between Gandhâra or Peshâwar and Yona or Bactria. According to Yâska, whose uncertain date varies from B.C. 500 to B.C. 200, the Kâmbôjas spoke Sanskrit (Muir's Sanskrit Texts, II 355 note 145). In the last battle of the Mahâbhârata, A.D. 100 to 300 (Jl. Roy, As. Soc. [1842] VII. 139-140), apparently from near Banian the Kambojas ranked as Mlecchhas with Śakas Duradas and Hûgas. One account (Fergusson, III, 666) places the original site of the Kambojas in the country round Taxila east of the Indus. This is probably incorrect. A trace of the Kambojas in their original seat seems to remain in the Kambojas of the Hindu Kush.

on which authorities disagree. Sir H. Yule held that the connection was purely literary and that as in the case of *Inthapatha-puri* or *Indraprastha* (Dehli) the later capital of Cambodia and of *Ayodhya* or *Udhyana* the capital of Assam no connection existed beyond the application to a new settlement of ancient worshipful Indian place-names. The objection to applying this rule to Cambodia is that except to immigrants from the *Kábul* valley the name is of too distant and also of too scanty a reputation to be chosen in preference to places in the nearer and holier lands of *Tihnt* and *Magadha*. For this reason, and because the view is supported by the notable connection between the two styles of architecture, it seems advisable to accept Mr. Fergusson's decision that the name Cambodia was given to a portion of *Cochin-China* by immigrants from *Kamboja* that is from the *Kábul* valley. Traces remain of more than one migration from India to Indo-China. The earliest is the mythic account of the conversion of Indo-China to Buddhism before the time of *Asoka* (B.C. 240). A migration in the first century A.D. of *Yavanas* or *Śakas*, from *Tamluk* or *Ratnagiri* on the *Hugli*, is in agreement with the large number of Indian place-names recorded by *Ptolemy* (A.D. 160).<sup>1</sup> Of this migration *Hinen Tsiang's* name *Yavana* (*Yen-mo-na*) for Cambodia may be a trace.<sup>2</sup> A *Śaka* invasion further explains *Pansanias'* (A.D. 170) name *Sakav* for *Cochin-China* and his description of the people as *Skythians* mixed with *Indians*.<sup>3</sup> During the fifth and sixth centuries a fresh migration seems to have set in. Cambodia was divided into shore and inland and the name *Cambosé* applied to both.<sup>4</sup> Chinese records notice an embassy from the king of Cambodia in A.D. 617.<sup>5</sup> Among the deciphered Cambodian inscriptions a considerable share belong to a *Bráhmanic* dynasty whose local initial date is in the early years of the seventh century,<sup>6</sup> and one of whose kings *Somavarman* (A.D. 610) is recorded to have held daily *Mahábhárata* readings in the temples.<sup>7</sup> Of a fresh wave of Buddhists, who seem to have belonged to the northern branch, the earliest deciphered inscription is A.D. 953 (S. 875) that is about 350 years later.<sup>8</sup> Meanwhile, though, so far as information goes, the new capital of *Angkor* on the north bank of lake *Tale Sap* about 200 miles up the *Mekong* river was not founded till A.D. 1078 (S. 1000),<sup>9</sup> the neighbourhood of the holy lake was already sacred and the series of temples of which the *Nakhonwat* or *Nága's Shrine*<sup>10</sup> is one of the latest and finest examples, was begun at least as early as A.D. 825 (S. 750), and

#### Appendix IV. CAMBODIA.

<sup>1</sup> See *H. 1111* s. *Orissa*, I. 310.

<sup>2</sup> *Yavana* to the south-west of *Siam*. *Beal's Life of Hinen Tsiang*, xxxii.

<sup>3</sup> Quoted in *Bainbury's Ancient Geography*, II. 659. *Bainbury* suggests that *Pansanias* may have gained his information from *Marcus Aurelius'* (A.D. 166) ambassador to China.

<sup>4</sup> *Jour. Bengal Soc.* VII. (I.) 317.

<sup>5</sup> *Remusat Nouveau Melanges Asiatiques*, I. 77 in *Jour. Asiatique Series*, VI. Tom. XIX. page 199 note 1; *Fergusson's Architecture*, III. 678.

<sup>6</sup> *Barth in Journal Asiatique Ser. VI. Tom. XIX. page 150.*

<sup>7</sup> *Barth in Journal Asiatique*, X. 57.

<sup>8</sup> *Barth in Jour. As. Ser. VI. Tom. XIX. page 190; Journal Royal Asiatic Society, XIV. (1882) cit.*

<sup>9</sup> *Barth in Journal Asiatique Ser. VI. Tom. XIX. pages 181, 186.*

<sup>10</sup> Mr. *Fergusson* (*Architecture* page 666) and Colonel *Yule* (*Ency. Brit. Cambodia*) accept the local Buddhist rendering of *Nakhonwat* as the City Settlement. Against this it is to be noted (*Ditto ditto*) that *nagara* city corrupts locally into *Angkor*. *Nagara* therefore can hardly also be the origin of the local *Nakhon*. Further as the local Buddhists claim the temple for Buddha they were bound to find in *Nakhon* some source other than its original meaning of Snake. The change finds a close parallel in the *Nága* that is snake or *kythian* now *Nágará* or city *Bráhma*n of *Gujarat*.

#### Appendix IV. CAMBODIA.

Nakhonwat itself seems to have been completed and was being embellished in A.D. 950 (S. 875).<sup>1</sup> During the ninth and tenth centuries by conquest and otherwise considerable interchange took place between Java and Cambodia.<sup>2</sup> As many of the inscriptions are written in two Indian characters a northern and a southern two migrations by sea seem to have taken place one from the Orissa and Masulipatam coasts and the other, with the same legend of the prince of Rûm land, from the ports of Sindh and Gujarat.<sup>3</sup> The question remains how far there is trace of such a distinct migration as would explain the close resemblance noted by Fergusson between the architecture of Kashmir and Cambodia as well as the northern element which Fergusson recognises in the religion and art of Cambodia.<sup>4</sup> The people by whom this Panjâb and Kashmir influence may have been introduced from the north are the people who still call themselves Khmers to whose skill as builders the magnificence of Cambodian temples, lakes and bridges is apparently due.<sup>5</sup> Of these people, who, by the beginning of the eleventh century had already given their name to the whole of Cambodia, Alberuni (A.D. 1031) says: The Khmers are whitish of short stature and Turk-like build. They follow the religion of the Hindus and have the practice of piercing their ears.<sup>7</sup> It will be noticed that so far as information is available the apparent holiness of the neighbourhood of Angkor had lasted for at least 250 years before A.D. 1078 when it was chosen as a capital. This point is in agreement with Mr. Fergusson's view that the details of Nakhonwat and other temples of that series show that the builders came neither by sea nor down the Ganges valley but by way of Kashmir and the back of the Himalayas.<sup>6</sup> Though the evidence is incomplete and to some extent speculative the following considerations suggest a route and a medium through which the Roman and Greek elements in the early (A.D. 100-500) architecture of the Kabul valley and Peshâwar may have been carried inland to Cambodia. It may perhaps be accepted that the Ephthalites or White Huns and a share of the Kedarites, that is of the later Little Yuechi from Gandhâra the Peshâwar country, retreated to Kashmir before the father of Sri Harsha (A.D. 590-606) and afterwards (A.D. 606-612) before Sri Harsha himself.<sup>8</sup> Further it seems fair to assume that from

<sup>1</sup> Barth in *Journal Asiatique* Ser. VI, Tom. XIX, 190.

<sup>2</sup> Yule's *Marco Polo*, II, 108; Reinaud's *Abulfeda*, cxv.

<sup>3</sup> Barth in *Journal Asiatique* Ser. VI, Tom. XIX, 171.

<sup>4</sup> Mr. Fergusson at first suggested the fourth century as the period of migration to Cambodia. He afterwards came to the conclusion that the settlers must have been much the same as the Gujarât conquerors of Java. *Architecture*, III, 665-678.

<sup>5</sup> Fergusson *Architecture*, 665. Compare Tree and Serpent Worship, 49, 61. The people of Cambodia seem Indian serpent worshippers: they seem to have come from *Exala*.

<sup>6</sup> The name Khmer has been adopted as the technical term for the early literature and arts of the peninsula. Compare Barth *J. As. Ser. VI*, Tom. XIX, 193; Renan in ditto page 75 note 3 and Ser. VII, Tom. VIII, page 68; Yule in *Encyclopedia Britannica* Art. Cambodia. The resemblance of Cambodian and Kabul valley work recalls the praise by Chinese writers of the Han (B.C. 206 - A.D. 24) and Wei (A.D. 386 - 556) dynasties of the craftsmen of Kipin, that is Kophene or Kumboja the Kabul valley, whose skill was not less remarkable in sculpturing and chiselling stone than in working gold silver copper and tin into vases and other articles. Specht in *Journal Asiatique*, II, (1883), 333 and note 3. A ninth century inscription mentions the architect Achyuta son of Râma of Kumboja. *Epigraphia Indica*, I, 243.

<sup>7</sup> Reinaud's *Abulfeda*, cxvi.; Sachau's *Alberuni*, I, 210.

<sup>8</sup> Fergusson's *Architecture*, III, 666.

<sup>9</sup> For the joint Kedarite-Ephthalite rule in Kashmir see Cunningham's *Ninth Oriental Congress*, I, 231-2. The sameness of names, if not an identity of rulers, shows how close was the union between the Ephthalites and the Kedarites. The coins preserve one difference depicting the Yuechi or Kedarite ruler with bushy and the White Huna or Ephthalite ruler with cropped hair.

Kashmir they moved into Tibet and were the western Turks by whose aid in the second half of the seventh century Srongtsan or Srongdzan-gambo (A.D. 610-698), the founder of Tibetan power and civilization, overran the Tarim valley and western China.<sup>1</sup> During the first years of the eighth century (A.D. 703) a revolt in Nepal and the country of the Bráhmans was crushed by Srongtsan's successor Donsrong,<sup>2</sup> and the supremacy of Tibet was so firmly established in Bengal that, for over 200 years, the Bay of Bengal was known as the sea of Tibet.<sup>3</sup> In A.D. 709 a Chinese advance across the Pamirs as said to have been checked by the great Arab soldier Kotiebn the comrade of Muhammad Kasim of Sindh.<sup>4</sup> But according to Chinese records this reverse was wiped out in A.D. 713 by the defeat of the joint Arab and Tibet armies.<sup>5</sup> In the following years, aided by disorders in China, Tibet conquered east to Hosi on the upper Hoangho and in A.D. 729 ceased to acknowledge the overlordship of China. Though about A.D. 750 he was for a time crippled by China's allies the Shado Turks the chief of Tibet spread his power so far down the Yangtsekiang valley that in A.D. 787 the emperor of China, the king of Yunnan to the east of Burma, certain Indian chiefs, and the Arabs joined in a treaty against Tibet. As under the great Thsrong (A.D. 803-845) and his successor Phu-tsong-ti (A.D. 878-901) the power of Tibet increased it seems probable that during the ninth century they overran and settled in Yunnan.<sup>6</sup> That among the Tibetans who passed south-east into Yunnan were Kedarites and White Húyas is supported by the fact that about A.D. 1290, according both to Marco Polo and to Rashid-ud-din, the common name of Yunnan was Kárájang whose capital was Yachi and whose people spoke a special language.<sup>7</sup> The name Karajang was Mongol meaning Black People and was used to distinguish the mass of the inhabitants from certain fair tribes who were known as Chaganying or Whites. That the ruler of Karajang was of Hindu origin is shown by his title Maharaa or Maharaja. That the Hindu element came from the Kabul valley is shown by its Hindu name of Kandhar that is Gandhara or Pesháwar, a name still in use as Gandaharit (Gandhara-rashtra) the Burmese for Yunnan.<sup>8</sup> The strange confusion which Rashid-ud-din makes between the surroundings of Yunnan and of Peshawar is perhaps due to the fact that in his time the connection between the two places was still known and admitted.<sup>9</sup> A further trace

#### Appendix IV. CAMBODIA.

<sup>1</sup> About A.D. 700 Ummtsi Kashgar Khoten and Kuche in the Tarim valley became Tibetan for a few years. Fa-hien's Thousand Years of the Tartars, 243. In A.D. 691 the western Turks who for some years had been declining and divided were broken by the great eastern Turk conqueror Mercho. The following passage from Masudi (Præf. D'Or, I. 289) supports the establishment of White Hunn or Mihri power in Tibet. The sons of Amir (a general phrase for Turks) mixed with the people of India. They founded a kingdom in Tibet the capital of which they called Med.

<sup>2</sup> Encyclopædia Britannica Article Tibet and Turkestan.

<sup>3</sup> Both Ibn Hānkāl and Al Istakhrī (A.D. 950) call the Bay of Bengal the sea of Tibet. Compare Renaud's Ahulfedn, cccxvii., Encyclopædia Britannica Article Tibet page 345.

<sup>4</sup> Yule's Cathay, I. lxxxi.

<sup>5</sup> Ency. Brit. China, 646.

<sup>6</sup> Thsrong besides spreading the power of Tibet (he was important enough to join with Maññu the son of the great Harua-ar-Rashid (A.D. 788-809) in a league against the Hindus) brought many learned Hindus into Tibet, had Sanskrit books translated, settled Lamaism, and built many temples. It is remarkable that (so far as inscriptions are read) the series of Nakhonwat temples was begun during Thsrong's reign (A.D. 803-845).

<sup>7</sup> Yule's Marco Polo, II. 39-42; J. L. A. Soc. I. 335.

<sup>8</sup> Yule Jour. R. A. Soc. (N. S.) I. 356.

<sup>9</sup> Compare Yule in Jour. R. A. S. (N. S.) I. 355. Kandahar in south-west Afghanistan is another example of the Kedarite or Little Yucchi fondness for giving to their colonies the name of their parent country.

Appendix IV.  
CAMBODIA.

of stranger whites like the Chaganjang of Yunnan occurs south-east in the Ann or Hani whose name suggests the Húnas and whose fondness for silver ornaments at once distinguishes them from their neighbours and connects them with India.<sup>1</sup> Even though these traces may be accepted as confirming a possible migration of Húnas and Kodanas to Yunnan and Ann a considerable gap remains between Ann and Angkor. Three local Cambodian considerations go some way to fill this gap. The first is that unlike the Siamese and Cochin Chinese the Khmers are a strong well made race with very little trace of the Mongoloid, with a language devoid of the intonations of other Indo Chinese dialects, and with the hair worn cropped except the top-knot. The second point is that the Khmers claim a northern origin; and the third that important architectural remains similar to Nakhonwat are found within Siam limits about sixty miles north of Angkor.<sup>2</sup> One further point has to be considered: How far is an origin from White Húnas and Kedáras in agreement with the Nága phase of Cambodian worship. Hien Tsiang's details of the Tarim Oxus and Swát valleys contain nothing so remarkable as the apparent increase of Dragon worship. In those countries dragons are rarely mentioned by Fa Hien in A.D. 100: dragons seem to have had somewhat more importance in the eyes of Sung-Yun in A.D. 520; and to Hien Tsiang, the champion of the Maháyána or Broadway, dragons are everywhere explaining all misfortunes earthquakes storms and diseases. Buddhism may be the state religion but the secret of luck lies in pleasing the Dragon.<sup>3</sup>

<sup>1</sup> Compare Yule's Marco Polo, II. 82-84.

<sup>2</sup> Yule in *Ency. Brit. Art. Cambodia*, 724, 725, 726.

<sup>3</sup> Fa Hien (A.D. 100) about fifty miles north west of Kananj found a dragon chapel (Beal's Buddhist Records, I. 40) of which a white-cared dragon was the patron. The dragon, he notes, gives seasonable showers and keeps off all plagues and calamities. At the end of the rains the dragon turns into a little white-cared serpent and the priests feed him. At the deserted Kapilavastu in Tihet Fa Hien was shown a tank and in it a dragon who, he says, constantly guards and protects a tower to Buddha and worships there night and morning (Ditto, I. 50).

Sung-Yun (A.D. 519) notices (Beal's Buddhist Records, I. 69) in Swát (Udyana) a tank and a temple with fifty priests called the temple of the Nága Rája because the Nága supplies it with funds. In another passage (Ditto, 92) he notices that in a narrow land on the border of Posse (Fars) a dragon had taken his residence and was stopping the rain and piling the snow. Hien Tsung (Ditto, I. 20) notes that in Kucha, north of the Tarim river east of the Bolor mountains, the Shen horses are half dragon horses and the Shen men half dragon men. In Aksu, 150 miles west of Kucha, here dragons molest travellers with storms of flying sand and gravel (Ditto, 25); the hot lake or Johai, 100 miles north-east of Aksu, is jointly inhabited by dragons and fish, scaly monsters rise to the surface and travellers pray to them (Ditto 26). An Arhat (page 63) prays that he may become a Nágaraaja. He becomes a Nágaraaja, kills the real Nágaraaja, takes his palace, attaches the Nágas to him, and raises winds and tempests; Kanishka comes against him and the Arhat takes the form of a Bráhman and knocks down Kanishka's towers. A great merit-flame bursts from Kanishka's shoulders and the Bráhman Nágaraaja apologises. His evil and passionate spirit, the fruit of evil deeds in a former birth, had made the Arhat pray to be a Nágaraaja. If clouds gathered the monks knew that the Nágaraaja meant mischief. The convent gong was beaten and the Nágaraaja pacified (or scared) Ditto, 64-66. Nágas were powerful brutes, cloud-riding wind-driving water-walking brutes, still only brutes. The account of the Naga or dragon of Jelaláhal (in Kaudhoja) is excellent. In Buddha's time the dragon had been Buddha's milkman. He lost his temper, laid flowers at the Dragon's cave, prayed he might become a dragon, and leaped over the cliff. He laid the country waste and did so much harm that Tathágata (or Buddha) converted him. The Nága asked Buddha to take his cave. Buddha said No. I will leave my shadow. If you get angry look at my shadow and it will quiet you (Ditto,

## JAVA AND CAMBODIA.

*No sufficient instance*

This apparent increased importance of dragon or Nāga worship in north-west India during the fifth and sixth centuries may have been due partly to the decline of the earlier Buddhism partly to the genial wonder-loving temper of Hiuen Tsiang. Still so marked an increase makes it probable that with some of the great fifth and sixth century conquerors of Bactria Kábul and the Panjáb, of whom a trace may remain in the snake-

Appendix IV.  
CAMBODIA.

94). Another typical dragon is Apalāla of the Swāt river (Ditto, 68). In the time of Kaśyapa Buihla Apalāla was a weaver of spells named Gaugi. Gaugi's spells kept the dragons quiet and saved the crops. But the people were thankless and paid no tithes. May I be born a dragon, cursed Gaugi, poisonous and ruinous. He was born the dragon of the Swāt valley, Apalāla, who belched forth a salt stream and burned the crops. The ruin of the fair and pious valley of Swāt reached Śakya's (Buddha's) ears. He passed to Maugala and beat the mountain side with Indra's mace. Apalāla came forth was lectured and converted. He agreed to do no more mischief on condition that once in twelve years he might ruin the crops. (Ditto, 122.) In a lake about seven miles west of Takshāśilā, a spot dear to the failed Kambojan, lived Ekpatra the Nāgarāja, a Bhikṣu or ascetic who in a former life had destroyed a tree. When the crops wanted rain or fair weather, the Shamans or medicine-men led the people to pray at Ekpatra's tank (page 137). In Kashmir, perhaps the place of halt of the Kambojan in his conquests eastwards, in old times the country was a dragon lake.\* Madhyantika dove out the waters but left one small part as a house for the Nāga king (I. 150). What sense have these tales? In a hilly land where the people live in valleys the river is at once the most whimsical and the most dangerous force. Few seasons pass in which the river does not either damage with its floods or with its failure and at times glaciers and landslips stop the entire flow and the valley is ruined. So great and so strange an evil as the complete drying of a river must be the result of some one's will, of some one's temper. The Dragon is angry he wants a sacrifice. Again the river pounds into a lake, the lake tops the earth bank and rushes in a flood wasting as only a dragon can waste. For generations after so awful a proof of power all doubts regarding dragons are dead. (Compare Drew's *Cashmere and Jummoo*, 414-421.) In India the Chinese dragon turns into a cobra. In China the cobra is unknown; a cobra than the cobra no power is more dreaded. How can the mighty unwieldy dragon be the little silent cobra. How not? Can the dragon be worshipful if he is unable to change his shape. To the spirit not to the form is worship due. Again the worshipped dragon becomes the guardian. The great earth Bodhisattva transforms himself into a Nāgarāja and dwells in lake Anavatapta whose flow of cool water enriches the world (Buddhist Records, II. 11). In a fume in Swāt Buihla takes the form of a dragon and the people live on him (125). A pestilence wasted Swāt. Buddha becomes the serpent Bana, all who taste his flesh are healed of the plague (126). A Naga maiden, who for her sins has been born in serpent shape and lives in a pool, loves Buddha who was then a Śakya chief. Buddha's merit regains for the girl her lost human form. He goes into the pool shows the girl's snake-kin and marries her. Not even by marriage with the Śakya is the serpent spirit driven out of the maiden. At night from her head issues a nine-crested Nāga. Śakya strikes off the nine crests and ever since that how the royal family has suffered from headaches (132). This last tale shows how Buddhism works on the coarser and darker tribes who accept its teaching. The converts rise to be men though a snake head may peep out to show that not all of the old heaven is dead. In other stories Buddha as the sacramental snake shows the moral advance in Buddhism from fiend to guardian worship. The rest of the tales illustrate the corresponding intellectual progress from force worship to man, that is mind, worship. The water force sometimes kindly and enriching sometimes fierce and wasting becomes a Bodhisattva always kindly though his goodwill may have to give way to the rage of evil powers. So Brāhmanism turns Narayana the sea into Śiva or Viṣṇu the sea ruler. In this as in other phases religion passes from the worship of the forces of Nature to which in his beginnings man has to bow to the worship of Man or conscious Mind whose growth in skill and in knowledge has made him the Lord of the forces. These higher ideals are to a great extent a veneer. The Buddhist evangelist may dry the lake; he is careful to leave a pool for the Nāgarāja. In times of trouble among the fierce struggles of pioneers and settlers the spirit of Buddha withdraws and leaves the empty shrine to the earlier and the more immortal spirit of Force, the Nāgarāja who has lived on in the pool which for the sake of peace Buddha refrained from drying.

\* Kashmir has still a trace of Gandhāra. Compare (Ency Brit. Art, Kashmir page 13. The races of Kashmir are Gandhāras, Khasās, and Daradās.

**Appendix IV.**  
**CAMBODIA.**

worshipping Nāgas and Takkas of the Kumaon and Garhwal hills, the Dragon was the chief object of worship. Temple remains show that the seventh and eighth century rulers of Kashmir, with a knowledge of classic architecture probably brought from beyond the Indus, were Naga worshippers.<sup>1</sup> The fact that the ninth century revision of religion in Tibet came mainly from Kashmir and that among the eighteen chief gods of the reformed faith the great Serpent had a place favours the view that through Tibet passed the scheme and the classic details of the Kashmir Naga temples which in greater wealth and splendour are repeated in the Nakhonwat of Angkor in Cambodia.<sup>2</sup> It is true that the dedication of the great temple to Nāga worship before the Siamese priests filled it with statues of Buddha is questioned both by Lieut Gardner and by Sir H. Yule.<sup>3</sup> In spite of this objection and though some of the series have been Buddhist from the first, it is difficult to refuse acceptance to Mr. Fergusson's conclusions that in the great Nakhon, all traces of Buddhism are additions. The local conditions and the worshipful Tale Snp lake favour this conclusion. What higher dragon site can be imagined than the great lake Tale Sap, 100 miles by 30, joined to the river Mekong by a huge natural channel which of itself empties the lake in the dry season and refills it during the rains giving a water harvest of fish as well as a land harvest of grain. What more typical work of the dragon as guardian water lord. Again not far off between Angkor and Yunnan was the head-quarters of the dragon as the unsquared fiend. In Carrapan ten days west of the city of Yachi Marco Polo (v.p. 1290) found a land of snakes and great serpents ten paces in length with very great heads, eyes bigger than a loaf of bread, mouths garnished with pointed teeth able to swallow a man whole, two fore-legs with claws for feet and bodies equal in bulk to a great cask. He adds, 'These serpents devour the cubs of lions and bears without the sire and dam being able to prevent it. Indeed if they catch the big ones they devour them too and no one can make any resistance. Every man and beast stands in fear and trembling of them.' Even in these head dragons was the sacramental guardian element. The gall from their inside healed the bite of a mad dog, delivered a woman in hard labour, and cured itch or it might be worse. Moreover, he concludes, the flesh of these serpents is excellent eating and toothsome.<sup>4</sup>

<sup>1</sup> Mr. Fergusson (*Architecture*, 219) places the Kashmir temples between A.D. 600 and 1200 and allots Mirānd the greatest to about A.D. 750. The classical element, he says, cannot be mistaken. The shafts are fluted Grecian Doric probably taken from the Gandhāra monasteries of the fourth and fifth centuries. Fergusson was satisfied (*Idem*, 289) that the religion of the builders of the Kashmir temples was Naga worship. In Cambodia the Brahman remains were like those of Java (*Idem*, 667). But the connection between the Nakhonwat series and the Kashmir temples was unmistakable (*Idem*, 297, 665). Naga worship was the object of both (*Idem*, 677-679). Imperfect information forced Fergusson to date the Nakhonwat not earlier than the thirteenth century (*Idem*, 660, 679). The evidence of the inscriptions which (*J. As. Soc. Brit. VI* Tom. XIX page 190) brings back the date of this the latest of a long series of temples to the ninth and tenth centuries adds greatly to the probability of some direct connection between the builders of the Mirānd shrine in Kashmir and of the great Nakhonwat temple at Angkor.

<sup>2</sup> *Ency. Brit. Art. Tibet*, 344.

<sup>3</sup> *Ency. Brit. Art. Cambodia*.

<sup>4</sup> Yule's *Marco Polo*, II. 45, 47.

## APPENDIX V.

### ARAB REFERENCES.<sup>1</sup>

THE earliest Arab reference to Gujarāt is by the merchant Sulaimān<sup>2</sup> A.D. 851 (A.H. 237). Other Arab accounts follow up to A.D. 1263, a period of over four centuries. Sulaimān describes Jurz or Gujarāt as bordering on the kingdom of the Ballāra (A.D. 743-974) and as forming a tongue of land, rich in horses and camels and said to have "mines of gold and silver, exchanges being carried on by means of these metals in dust."

Al Bilāduri<sup>3</sup> (A.D. 892) states that the first Islāmic expedition to India was the one despatched against *Tānā*<sup>4</sup> (Thāna) by Usmān, son of Al-Āsi the Thakafi, who in the fifteenth year of the Hijrah (A.D. 636) was appointed governor of Bahrein and Umān (the Persian Gulf) by the second Khalīfah Umar, the son of Khattāb. On the return of the expedition, in reply to his governor's despatch, the Khalīfah Umar is said to have written: "Oh brother of Thakif, thou hast placed the worm in the wood, but by Allāh, had any of my men been slain, I would have taken an equal number from thy tribe." In spite of this threat Usmān's brother Hakam, who was deputed by the governor to the charge of Bahrein, despatched a force to Bārūz<sup>5</sup> (Baruch). Al Bilāduri does not record the result of this expedition, but

### Appendix V.

ARAB  
REFERENCES,  
A.D. 851 - 1350.

<sup>1</sup> Contributed by Khān Sāhib Fazlullah Lutfullah Faridi of Surat.

<sup>2</sup> This account which is in two parts is named *Silsilat-ut-Tawārikh*, that is the Chain of History. The first part was written in A.D. 851-52 by Sulaimān and has the advantage of being the work of a traveller who himself knew the countries he describes. The second part was written by Abū Zaid-al-Hasan of Sirāf on the Persian Gulf about sixty years after Sulaimān's account. Though Abū Zaid never visited India, he made it his business to read and question travellers who had been in India. Abū Hasan-el-Masūdī (A.D. 915-943) who met him at Basrah is said to have imparted to and derived much information from Abū Zaid. Sir Henry Elliot's *History of India*, I. 2.

<sup>3</sup> Ahmed bin Yuhay, surnamed Abū Ja'afar and called Bilāduri or Bilazuri from his addiction to the electuary of the bilazen bean (*bilazur* بلزر) or anacardium, lived about the middle of the ninth century of the Christian era at the court of Al-Mutawakkil the Abbāsi, as an instructor to one of the royal princes. He died A.H. 279 (A.D. 892-93). His work is styled the *Futuh-ul-Buldān* The Conquest of Countries. He did not visit Sindh, but was in personal communication with men who had travelled far and wide.

<sup>4</sup> Sir Henry Elliot's *History of India*, I. 115-116.

<sup>5</sup> The reason of Umar's dislike for India is described by Al Mas'udi (Murij Arabic Text, Cairo Edition, III. 166-171), to have originated from the description of the country by a philosopher to whom Umar had referred on the first spread of Islām in his reign. The philosopher said: India is a distant and remote land peopled by rebellious infidels. Immediately after the battle of Kadesiah (A.D. 636) when sending out Utbah, his first governor to the newly-founded camp-town of Basrah Umar is reported to have said: I am sending thee to the land of Al-Hind (India) as governor. Remember it is a field of the fields of the enemy. The third Khalīfah Usmān (A.D. 643-655) ordered his governor of Irāk to depute a special officer to visit India and wait upon the Khalīfah to report his opinion of that country. His report of India was not encouraging. He said: Its water is scarce, its fruits are poor, and its robbers bold. If the troops sent there are few they will be slain; if many they will starve. (Al-Bilāduri in Elliot, I. 116.)

<sup>6</sup> Sir H. Elliot's *History of India*, I. 116.

## Appendix V.

ARAB  
REFERENCES,  
A.D. 851 - 1350.

mentions a more successful one to Debal at the mouth of the Indus sent by Hākam under the command of his brother Mughāfir. On the death of his uncle Al-Hajjāj (A.D. 744; H. 95) Muhammad the son of Kāsim the Arab conqueror of Sindh, is said to have made peace with the inhabitants of Surast or Kāthiāyūd with whom he states the people of Bātia<sup>1</sup> that is Bet to the north of Dwārka were then at war. Al Bilāduri describes the Bātia men as Meds seafarers and pirates. In the reign of Hishām (A.D. 724) Junaid, son of Ahdar Rahmān Al Murri, who was appointed to the frontier of Sindh is stated to have conquered Jurz (Gujarāt) and Bārūs (Broach).<sup>2</sup> A more permanent result followed a great expedition from Mansūrah in Sindh. This result was the overthrow, from which it never recovered, of the great seaport and capital of Vala or Vudabhi.<sup>3</sup> Al Bilāduri's next mention<sup>4</sup> of Gujarāt is in connection with the conquest of Sindān in Kachh and the founding there of a Jāmā mosque by Fazl, son of Mahān in the reign of the Abbāsi Khalifah Al Māmūn (A.D. 813-833) the son of the famous Hārūn-ur-Rashid. After Fazl's death his son Muhammad sailed with sixty vessels against the Meds of Hind, captured Mūh<sup>5</sup> apparently Mālia in north Kāthiāyūd after a great slaughter of the Meds and returned to Sindān.

The dissension between Muhammad and his brother Mahān, who in Muhammad's absence had usurped his authority at Sindān, re-established the power of the Hindus. The Hindus however, adds Al Bilāduri, spared the assembly mosque in which for long the Musalmāns used to offer their Friday prayers.<sup>6</sup> Ibn Khurādadhbih (A.D. 912; H. 300) erroneously enumerates Bārūs and Sindān (Broach and Sindān) as cities of Sindh.<sup>7</sup> The king of Juzr he describes as the fourth Indian sovereign. According to Al Masūdī<sup>8</sup> (A.D. 915) the country of the Balhāras or Rāshtrakūṭas (A.D. 743-974), which is also called the country of Kumkar (Konkan), is open on one side to the attacks of the king of Juzr (Gujarāt) a prince owning many horses and camels and troops who does not think any king on earth equal to him except the king of Bābul (Babylon). He prides himself and holds himself high above all other kings and owns many elephants, but hates Musalmāns. His country is on a tongue of land and there are gold and silver mines in it, in which trade is carried on. Al Istakhri<sup>9</sup> (H. 340; A.D. 951) gives an itinerary in which he shows the distance between

<sup>1</sup> Sir H. Elliot (Hist. of India) transliterates this as *Batua*. But neither *Batua* nor his other supposition (Note 4 Ditto) *Budha* seem to have any sense. The original is probably *Batiah*, a form in which other Arab historians and geographers also allude to *Bart*, the residence of the notorious *Barday* who are referred to a little farther on as seafarers and pirates. Ditto, I. 123.

<sup>2</sup> This important expedition extended to Ujjain. \* Details Above page 199 and also under Bhīmāl. Raids by sea from Sindh were repeated in A.D. 758, 760, 756, and perhaps A.D. 830. Reinaud's Fragments, 212. See Above Bhigvānāp's Early History page 96 note 3. <sup>3</sup> Details Above pages 94-96.

<sup>4</sup> Sir Henry Elliot's History of India, I. 129.

<sup>5</sup> Sir Henry Elliot (History of India, I. 129) calls it Kallari though (Ditto note 3) he says the text has Mali. <sup>6</sup> Sir H. Elliot's History of India, I. 129.

<sup>7</sup> Ibn Khurādadhbih a Musalmān of Magian descent as his name signifies, died H. 300 (A.D. 912). He held high office under the Abbāsi Khalifas at Baghdād (Elliot's History of India, I. 13).

<sup>8</sup> Abul Hasan Al Masūdī, a native of Baghdād, who visited India about A.D. 915 and wrote his "Meadows of Gold" (Murūj-uz-zahab) about A.D. 950-51 and died A.D. 956 in Egypt. (Sir Henry Elliot's History of India, I. 23-25.)

<sup>9</sup> Abu Is-hāk Al Istakhri, a native (as his cognomen signifies) of Persepolis who flourished about the middle of the tenth century and wrote his Book of Climes (Kitābul Akālīm) about A.H. 340 (A.D. 951). Elliot's History of India, I. 26.

Mansurah and Kāmbhal<sup>1</sup> (Anhilwāra) to be eight days' journey; from Kāmbhal to Kambāya (Cambay) four days; from Kambāya to the sea about two *farsangs* that is between seven and eight miles<sup>2</sup>; from Kambāya to Surabāya<sup>3</sup> perhaps Surabāra the Surat river mouth which is half a *farsang* (between 1½ and two miles) from the sea, about four days. He places five days between Surabāya (Surat) and Sindān (St. John near Daman) and a like distance<sup>4</sup> between Sindān and Sammur (Chawal or Chenl) thirty miles south of Bombay. Ibnī Haukal<sup>5</sup> (H. 366; A.D. 976) enumerates<sup>6</sup> (Fāmbhal)<sup>7</sup> (Anhilwāra), Kambāya (Cambay), Surbārāh (Surat), Sindān (Daman), and Sammur (Chenl) as cities of Al Hind (India), as opposed to As Sindh or the Indus valley. From Kambāya to Sammur, he writes is the land of the Bahārā which is in the possession of several kings<sup>8</sup>. Ibnī Haukal describes the land between Kāmbhal (Anhilwāra) and Kambāya (Cambay), and Banin three days' journey from Mansurah as desert,<sup>9</sup> and between Kambāya and Sammur as thickly covered with villages. Al Bīrūnī,<sup>10</sup> in his famous Indica about A.D. 1030-31 writes: From Kamanj, travelling south-west you come to Asi, a distance of eighteen *farsakhs*<sup>11</sup> that is of seventy-two miles; to Sahica 17 *farsakhs* or sixty-eight miles; to Chamra 18 *farsakhs* or seventy-two miles; to Rajauri fifteen *farsakhs* or sixty miles, and to Nārāna (near Jaipur) the former capital of Ujjarāt, 18 *farsakhs* or seventy-two miles. Nārāna he adds was destroyed and the capital transferred to another town on the frontier. From Nārāna at a distance of 60 *farsakhs* or 240 miles south-west lies Anhilwāra, and thence to Sumnath on the sea is fifty *farsakhs* or 200 miles. From Anhilwāra, passing south is Lārdes with its capitals Bārnach (Branch) and Rahānjūr<sup>12</sup> (Rāndir) forty-two *farsakhs* (168

## Appendix V.

ARAB  
REFERENCES,  
A.D. 851-1350.

<sup>1</sup> See Appendix A, Volume I. Sir Henry Elliot's History of India.

<sup>2</sup> Elliot's History of India, 394, where Sir Henry Elliot calculates a *parasang* or *farsang* (Arabic *farsakh*) to be 3½ miles. Al Bīrūnī, however, counts four *kroh* or miles to a *farsakh*. Sachau's Al Bīrūnī Arabic Text, chapter 18 page 97.

<sup>3</sup> Sir Henry Elliot (History of India, I. 403) locates Surabāya somewhere near Surat. The mouth of the Tapti is still known in Surat as the Bāra.

<sup>4</sup> Ibnī Haukal (Muhammad Abul Kasim) a native of Baghdad, left that city in H. 331 (A.D. 943), returned to it H. 358 (A.D. 968) and finished his work about H. 366 (A.D. 976). Sir Henry Elliot's History of India, I. 31. <sup>5</sup> Elliot, I. 31.

<sup>6</sup> Sir Henry Elliot (History of India, I. 363) correctly takes Fāmbhal to be a misreading for Anhal that is Anhilwāra. Al Bīrūnī (A.D. 970-1039) uses the name Anhilwāra without any Arab peculiarity of transliteration or pronunciation. Sachau's Arabic Text, 100. Al Idrisi (end of the eleventh century) styles Anhilwāra "Nahrwāra" (Elliot, I. 84) an equally well known name.

<sup>7</sup> See Elliot's History of India, I. 31.

<sup>8</sup> M. Gildemeister's Latin translation of Ibnī Haukal's Ashkāl al-Bilād (Sir Henry Elliot's History of India, I. 39).

<sup>9</sup> Abu Rihān Al Bīrūnī was a native of Balkh in Central Asia. He accompanied Mahmūd of Ghazni to India in his expeditions and acquired an accurate knowledge of Sanskrit. His acquaintance with this language and Greek and his love of enquiry and research together with his fairness and impartiality, make his Indica a most valuable contribution to our information on India in the end of the tenth and beginning of the eleventh centuries. He finished his work after the death of his patron in A.D. 1030-31.

<sup>10</sup> See Sachau's Preface to the Arabic Text of the Indica, ix.

<sup>11</sup> Al Bīrūnī makes his *farsakh* of four miles. Sachau's Arabic Text, 97.

<sup>12</sup> Sir Henry Elliot's translation and transliteration of Rahānjūr (History of India, I. 61) are, be it said with all respect to the memory of that great scholar, inaccurate. He cannot make anything of the word (note 3) while in the Arabic Text of Sachau (page 100) the first letter is a plain *j* = *r* and not *z* = *l*. From the context also the ancient town of Rāndir seems to be meant. It is plainly written (رمندور) Rahānjūr and is very likely the copyist's mistake for the very similar form رهمدور or Rāhandūr.

## Appendix V.

ARAB  
REFERENCES,  
A.D. 851-1350.

miles). These he states are on the shore of the sea to the east of Tāna (the modern Thāna).<sup>1</sup> After describing the coast of Makrān till it reaches Dehal<sup>2</sup> (Karāchi or Thatta). Abu Rihān comes to the coast of Kachh<sup>3</sup> and Somnāth, the population of which he calls the Bawārij because, he says, they commit their piratical depredations in boats called Bairi.<sup>4</sup> He gives the distance<sup>5</sup> between Dehal (Karāchi or Thatta) and Kachh the country that yields *muhl* (gum or myrrh)<sup>6</sup> and *bādrūd* (balm) as six *farsakhs* (24 miles); to Somnāth (from Dehal) fourteen (56 miles); to Kambāya thirty (120 miles); to Asāwal the site of Ahmodābād (from Cambay) two days' journey; to Bahrūj (Broach) (from Dehal)<sup>7</sup> thirty; to Sindān or St John (from Dehal) fifty; to Subāra (Sopara) from Sindān, six<sup>8</sup>; to Tāna (from Sopara) five. Rashid-ud-dīn in his translation (A.D. 1310) of Al Bīrūnī (A.D. 970-1031) states<sup>9</sup> that beyond Gujarāt are Koukhan and Tāna. He calls Tānah the chief town of the Koukhans and mentions the 'forest of the Dāngs as the habitat of the *shaurra* an animal resembling the buffalo, but larger than a rhinoceros, with a small trunk and two big horns with which it attacks and destroys the elephant. Al Idīsī,<sup>10</sup> writing about the end of the eleventh century but with tenth century materials, places<sup>11</sup> in the seventh section of the second climate, the Gujarāt towns of Māmbal (Amalwāra), Kambāya (Cambay), Subāra (apparently Surabāra or Surat), Sindān<sup>12</sup> (Sanjān in Thāna), and Sumūr (Chawal or Cheal). He adds, probably quoting from Al Janhari (A.D. 950), that Nahrwāra is governed by a great prince who bears the title of Bahūra who owns the whole country from Nahrwāra to Sumūr. He ranks the king of Juzr fourth among Indian potentates. The country from Dehal to Kambāya (Karāchi to Cambay) he describes<sup>13</sup> as "nothing but a marine strand without habitations and almost without water, and impassable for travellers."<sup>14</sup> The situation of Māmbal (Amalwāra) he gives as between Sindh and Hind. He notices the Meds as Mānds<sup>15</sup> grazing their flocks to within a short distance of

<sup>1</sup> Sachau's Arabic Text of Al Bīrūnī, 98 and Sir Henry Elliot's History of India, I. 61.

<sup>2</sup> Elphinstone's History of India, Book V Chapter I, 263 Note 25 (John Murray's 1819 Edition) on the authority of Captain MacMurdo and Captain Alexander Burnes inclines to the opinion that Dehal was somewhere near the site of the modern Karachi.

<sup>3</sup> Sir Henry Elliot's History of India, I. 65. Sachau's Text of Al Bīrūnī, chapter 18 page 102.

<sup>4</sup> Al Bilādari uses the word Baija for a strong built war vessel. Sir Henry Elliot derives the word from the Arabic and gives an interesting note on the subject in his Appendix I. 539. The word is still used in Hindustani as *bahā* (بحا) to signify a boat or lark.

<sup>5</sup> Sachau's Arabic Text, 102.

<sup>6</sup> According to Richardson (Arabic Dictionary voce مغل myrrh) though rendered gum by all translators. According to the *Makhzan* the word *muhl* (Urdu *quqlah*) is Balsamedendron and Bāhrūd the corruption of *Batrūz* (Urdu *batroza*) is balsam or bezoar.

<sup>7</sup> Sachau's Arabic Text page 99 chapter 18.

<sup>8</sup> After giving the distances in days or journeys the Text (page 102 Sachau's Text of Al Bīrūnī) does not particularise the distances of the places that follow in journeys or *farsakhs*.

<sup>9</sup> Elliot's History of India, I. 67.

<sup>10</sup> Abu Abdallah Muhammad Al Idīsī, a native of Ceuta in Morocco and descended from the royal family of the Idīsīs of that country, settled at the court of Roger II. of Sicily, where and at whose desire he wrote his book *The Nuzhat-ul-Mushtak* or *The Seeker's Delight*. Elliot's History of India, I. 74. Almost all Al Idīsī's special information regarding Sindh and Western India is from Al-Janhari governor of Khurāsān (A.D. 893-909), whose knowledge of Sindh and the Indus valley is unusually complete and accurate. Compare Reinaud's *Almufeda*, lxxi.

<sup>11</sup> Sir Henry Elliot's History of India, I. 77.

<sup>12</sup> Bombay Gazetteer, II. 69.

<sup>13</sup> Elliot's History of India, I. 79.

<sup>14</sup> Elliot's History of India, I. 76.

<sup>15</sup> Elliot's History of India, I. 79.

Mámhal (Anhilwára). He speaks of Mámhal, Kambáya, Subára (probably Surabára or Surat), Sindán, and Suimúr as countries of Hind (India) touching upon Sindh.<sup>1</sup> He describes Mámhal as a frontier town, numbered by some among the cities of Sindh, and he classifies Auhkin, Mánd, Kulámmali (Quilon),<sup>2</sup> and Sindán (Sandhánin Kachh) as maritime islands. Among the numerous towns of India are Mámhal (Anhilwára), Kambáya (Cambay), Subára, Asáwal (Ahmedábád), Janáwal (Chauvál), Sindán, Suimúr, Jandur<sup>3</sup> (Rándir), Sandur (apparently a repetition of Rándir), and Rúmála (perhaps the south Punjab).<sup>4</sup> He speaks of Kalbata, Augasht, Nahrwára (Anhilwára), and Lahawar (Lahori Bundur) as in the desert<sup>5</sup> of Kambáya. Of the three Subára (Surabára or Surat), Sindán (the Thána Sanján), and Suimúr (Chenl), he says Suimúr alone belongs to the Bulhára, whose kingdom, he adds, is large, well-peopled, commercial, and fertile. Near Subára (apparently Surabára) he locates small islands which he styles Bára where, he adds, coconuts and the costus grow.<sup>7</sup> East of Sindán, due to a confusion between Sandhán in Kachh and Sanján in Thána, he places another island bearing the same name as the port and under the same government as the mainland, highly cultivated and producing the cucumber the banana and the cane. Five miles by sea from Kulámmali lies another island called Máli, an elevated plateau, but not hilly, and covered with vegetation. The mention of the pepper vine suggests that Al Idrisi has wandered to the Malabar Coast. In the eighth section of the second clume Al Idrisi places Bárúh (Broach), Sandapúr (apparently ten), Táma (Thána), Kandarma (Gandhár, north of Broach), Jorháta a town mentioned by Al Idrisi as the nearest in a voyage from Ceylon to the continent of India on that continent. It is described as a populous town on a river supplying rice and grain to Ceylon.<sup>6</sup> Kalkáyan, Lalawn, Kauja, and Samundirán, and in the interior Dulaka (Dholka), Janwal (Chauvál or Varangán), and Nahrwár (Anhilwára).<sup>8</sup> Opposite the sea-port of Bárúh (Broach), Al Idrisi places an island called Mullán, producing large quantities of pepper. Al Idrisi describes the port of Baruh (Broach) as accessible to ships from China and Sindh. The distance from Bárúh to Saimúr he puts at two days journey, and that between Bárúh and Nahrwara (Anhilwára) at eight days through a flat country travelled over in wheeled carriages drawn by oxen, which he adds furnished the only mode for the conveyance also of merchandise. He locates the towns of Dulaka and Hanawal

## Appendix V.

ARAB  
REFERENCES,  
A.D. 851 - 1350.

<sup>1</sup> Elliot's History of India, I. 84.

<sup>2</sup> The letters of Kulámmali given by Al Kazwini (A.D. 1263 - 1275) seem to show it is Qdilon on the Malabar Coast. When a ruler died his successor was always chosen from China.

<sup>3</sup> Elliot (I. 363-364) on the authority of Al Istakhri thinks that all the names Auhhal, Kámhal, Kámhal, and Mámhal are faulty readings of Anhal (Anhilwára) owing to irregularity in the position or absence of diacritical points.

<sup>4</sup> This is probably Rándir, a very natural Arab corruption. Instance Al Biruni's Ranjhar. See page 507 note 11 and page 520.

<sup>5</sup> Rúmála is mentioned at pages 14, 87, 92 and 93 volume I. of Elliot. It is first mentioned (page 14) by Ibní Khuradbeh (A.D. 912) as one of the countries of Sindh. It is next mentioned by Al Idrisi (end of the eleventh century according to Elliot, I. 74) as one of the places of the eighth section describing the coast of India, but is mentioned along with Nahrwára, Kandhár, and Kallbata (?). At page 92 (Ditto) the same writer (Idrisi) says that Kalbata and Rúmála are on the borders of the desert which separates Máltan from Sijistán. Again at page 93 (Ditto) Idrisi gives the distance between Kalbata and Rúmála as a distance of three days.

<sup>6</sup> Elliot's History of India, I. 84.

<sup>7</sup> Elliot, I. 90-93.

<sup>8</sup> Sir H. Elliot's History of India, I. 85.

<sup>9</sup> Elliot's History of India, I. 89.

## Appendix V.

ARAB  
REFERENCES,  
A.D. 851-1350.

or Janāwal (Chānwāl or Jhalāwar) with Asāwal (Ahmedābād) between Bārūh and Nahrawān. He represents all three of these towns to be centres of a considerable trade, and among their products mentions the bamboo and the cocconut. From Bārūh to Sundāhūr (that is Goa), a commercial town with fine houses and rich bazārs situated on a great gulf where ships cast anchor, the distance along the coast given by Al Idrīsī is four days. Al Kazwīn<sup>1</sup> writing about the middle of the thirteenth century A.D. 1263-1275, but mainly from information of the tenth century notes Samūr (Chenl) "a city of Hind near the confines of Sindh" with its handsome people of Turkish extraction worshippers of fire having their own fire-temples. Al Kazwīn (A.D. 1230) dwells at length on the wonders of Somnāth and its temple. He calls it a celebrated city of India situated on the shore of the sea and washed by its waves. Among its wonders is Somnāth, an idol huge in space resting on nothing. In Somnāth he says Hindus assemble by the ten thousand at lunar eclipses, believing that the souls of men meet there after separation from the body and that at the will of the idol they are re-born into other animals. The two centuries since its destruction by the idol-breaker of Ghaznāh had restored Somnāth to its ancient prosperity. He concludes his account of Somnāth by telling how Mahmūd ascertained that the chief idol was of iron and its canopy a lion stone and how by removing one of the walls the idol fell to the ground.

## Rivers.

Regarding the rivers and streams of Gujarāt the Arab writers are almost completely silent. The first reference to rivers is in Al Masūdī (A.D. 914) who in an oddly puzzled passage says "On the Lārwā Sea (Cambay and Chenl) great rivers run from the south whilst all the rivers of the world except the Nile of the Egypt, the Mehrān (Indus) of Sindh, and a few others flow from the north." Al Bīrūnī (A.D. 970-1030) states that between the drainage areas of the Sarsut and the Ganges is the valley of the river Narmazā<sup>2</sup> which comes from the eastern mountains and flows south-west till it falls into the sea near Bahrūch about 180 miles (60 *yojanas*) east of Somnāth. Another river the Sarsut (Sarasvatī) he rightly describes as falling into the sea an arrowshot to the east of Somnāth<sup>3</sup>. He further mentions the Tāpī (Tapti) from the Vindh or Vindhya hills and the Tāmbra Bāmani or copper-coloured, apparently also the Tāpī, as coming from Mālwa. In addition he refers to the Māhūndri or Māhi and the Sūrusa apparently

<sup>1</sup> Zakariyah Ibn Muhammad Al Kazwīnī, a native of Kazwīn (Kashin) in Persia, wrote his *Asar-ul-Bilād* or "Signs or Monuments of Countries" about A.H. 661 (A.D. 1263) compiling it chiefly from the writings of Al Istakhrī (A.D. 951) and Ibn Haukal (A.D. 976). He also frequently quotes Muṣār bin Muḥallab, a traveller who (A.D. 942) visited India and China. Sir Henry Elliot's *History of India*, I. 94.

<sup>2</sup> Barbier De Meynard's Text of Al Masūdī's *Les Princes D'Or*, I. 382.

<sup>3</sup> Sir Henry Elliot insists on *Tamraz* for Al Bīrūnī's Arabic form of *Narmaza*. He says: It comes from the city of Tamaraz and the eastern hills; it has a south-easterly course till it falls into the sea near Bahrūch about 60 *yojanas* to the east of Somnāth. The literal translation of the text of Al Bīrūnī (see Sachau's *Al Bīrūnī's India*, 130) is that given above. It is hard to believe that the accurate Al Bīrūnī while in one place (see Sachau's Text, 99) giving the name of the Narmada faultlessly, should in another place fall into the error of tracing it from *Tamraz* a city of Central Asia. A comparison of Elliot's version with the text sets the difficulty at rest. Compare Sir Henry Elliot's *History of India*, I. 49 and note 3 ditto and Sachau's Arabic Text of Al Bīrūnī, 130 chapter 25.

<sup>4</sup> Compare Sachau's *Al Bīrūnī* with Sir Henry Elliot, I. 49, who is silent as to the distance.

Sarasvati perhaps meant for the Śābarmati. Al Idrisi (A.D. 1100) is the only other Arab writer who names any of the Gujarāt rivers. As usual he is confused, describing Dūka (Dholka), as standing on the bank of a river flowing into the sea which forms an estuary or gulf on the east of which stands the town of Bārūh (Broach).<sup>1</sup>

The Arab writers record the following details of twenty-two leading towns :

**Anahavā'da** (ANHAL, FĀMHAL, KĀMHAL, KĀMUHUL, MĀMHUL, NAHL-WĀRA, NAHRWĀLA) Al Istakhrī (H. 340; A.D. 951) mentions Āmhal Fāmhāl and Kāmhal, Ibn Hānkāl (A.D. 976) Fāmhāl Kāmhal and Kāmuhāl, and Al Idrisi (end of the eleventh century) Māmhal. That these are perversions of one name and that they stood on the border of 'Hind' or Gujarāt (in contradistinction to Sindh) the position given to each by the Arab geographers<sup>2</sup> places beyond question. Al Istakhrī (A.D. 951) alone calls the place by the name of Āmhal which he mentions<sup>3</sup> as one of the chief cities of 'Hind'. Later he gives the name of *Fāmhāl* to a place forming the northern border of "Hind", as all beyond it as far as Makrān belongs to Sindh. Again a little later<sup>4</sup> he describes Kāmhal as a town eight days from Mansūrah and four days from Kambāya, thus making Kāmhal the first Gujarāt town on the road from Mansūrah about seventy miles north of Hādārahād in Sindh to Gujarāt. Ibn Hānkāl (A.D. 968-976) in his *Ashkāl-ul-Bilād* gives Fāmhāl in his text and Kāmhal in his margin<sup>5</sup> and again while referring<sup>6</sup> to the desert between Makrān and Fāmhāl as the home of the Meds, he styles it Kāmhal. Once more he refers to Fāmhāl as a strong and great city, containing a Jamā' or Assembly Mosque; a little later<sup>7</sup> he calls it Kāmuhāl and places it eight days from Mansūrah and four from Kambāya. He afterwards contradicts himself by making Mansūrah two days' journey from 'Kāmuhāl,' but this is an obvious error.<sup>8</sup> Al Bīrūnī (A.D. 970-1039) notices Anahilwāra and does not recognize any other form.<sup>9</sup> Al Idrisi (end of the eleventh century) adopts no form but Māmhal referring to it as one of the towns of the second climate<sup>10</sup> on the confines of a desert between Sindh and "Hind" (India or Gujarāt) the home of the sheep-grazing and horse and camel-breeding Meds,<sup>11</sup> as a place numbered by some among the cities of Hind (Gujarāt) by others as one of the cities of Sindh situated at the extremity of the desert which stretches between Kambāya, Debal, and Bāniā.<sup>12</sup> Again he describes Māmhal as a town of moderate importance on the route "from Sindh to India," a place of little trade, producing small quantities of fruit but numerous flocks, nine days from Mansūrah through Bāniā and five from Kambāya.<sup>13</sup> Al Idrisi (quoting from tenth century

## Appendix V.

ARAB  
REFERENCES,  
A.D. 851-1350.

Towns.  
*Anahavāda.*

<sup>1</sup> See Ahmedabad Gazetteer, IV, 338; also Elliot's History of India, I, 356-357.

<sup>2</sup> See Appendix Elliot's History of India, I, 363.

<sup>3</sup> Al Istakhrī in Elliot (History of India), I, 27.

<sup>4</sup> Al Istakhrī in Elliot (History of India), I, 30.

<sup>5</sup> Ibn Hānkāl in Elliot (History of India), I, 32-34.

<sup>6</sup> Ibn Hānkāl in Elliot (History of India), I, 34-38.

<sup>7</sup> Ibn Hānkāl in Elliot (History of India), I, 39.

<sup>8</sup> Ibn Hānkāl in Elliot (History of India), I, 40.

<sup>9</sup> Al Bīrūnī in Elliot (History of India), I, 61.

<sup>10</sup> Al Idrisi in Elliot (History of India), I, 77.

<sup>11</sup> Al Idrisi in Elliot (History of India), I, 79.

<sup>12</sup> Bāniā seems to be a copyist's error for Bazāna or Nārāyana. The distances agree and the fact that to this day the neighbourhood of Jan is noted for its flocks of sheep bears additional testimony to the correctness of the supposition.

<sup>13</sup> Al Idrisi in Elliot's History of India, I, 84.

## Appendix V.

ARAB  
REFERENCES,  
A.D. 851 - 1350.  
Towns,  
*Anahilavāḍa*.

materials) also notices Nahrwān as eight days' journey from Bārūh (Bioach) across a flat country a place governed by a prince having the title of the Balhāra, a prince with numerous troops and elephants, a place frequented by large numbers of Musalmāns who go there on business.<sup>1</sup> It is remarkable that though Vanarāja (A.D. 720 - 780 ?) founded Anhilwāra as early as about A.D. 750 no Arab geographer refers to the capital under any of the many forms into which its name was twisted before Al Istakhri in A.D. 951. At first Anhilwāra may have been a small place but before the tenth century it ought to have been large enough to attract the notice of Ibn Khurdādhbih (A.D. 912) and Al Masūdi (A.D. 915). In the eleventh century the Musalmān historians of Mahmūd's reign are profuse in their references to Anhilwāra. According to Farishtah<sup>2</sup> after the capture of Anhilwāra and the destruction of Somnāth (H. 411; A.D. 1025) Mahmūd was anxious to make Anhilwāra his capital especially as it had mines of gold and as Singaldip (Ceylon) rich in rubies was one of its dependencies. Mahmūd was dissuaded from the project by his ministers<sup>3</sup>. But two mosques in the town of Pattan remain to show Mahmūd's fondness for the city. The next Muhammadan reference to Anhilwāra is by Nūr-ud dīn Muhammad U'fi, who lived in the reign of Shams-ud dīn Altamsh (A.D. 1211).<sup>4</sup> In his Romance of History U'fi refers to Anhilwāra as the capital of that Jan Rāj, who on receiving the complaint of a poor Musalmān preacher of Cambay, whose mosque the Hindus instigated the fire-worshippers of the place to destroy, left the capital alone on a fleet dromedary and returning after personal enquiry at Cambay summoned the complainant and ordered the chief men of the infidels to be punished and the Musalmān mosque to be rebuilt at their expense.<sup>5</sup>

The Jāmi-ul-Hikāyāt of Muhammad U'fi alludes<sup>6</sup> to the defeat of Sultān Shahāb-ud-dīn or Muhammad bin Sām, usually styled Muhammad Ghori, at the hands of Mūlarāja II. of Anahilavāḍa in A.D. 1178. And the Tājul Maāsir<sup>7</sup> describes how in A.D. 1297 the Musalmāns under Kutb-ud-dīn Aibak retrieved the honour of their arms by the defeat of Karan and his flight from Anhilwāra. This account refers to Gujarāt as "a country full of rivers and a separate region of the world." It also notices that Sultān Nāsr-ud-dīn Kabāchah (A.D. 1246-1266) deputed his general Khāshkhān from Dehal to attack Nahrwān and that Khāshkhān brought back many captives and much spoil. After the conquest of Gujarāt, in A.D. 1300 Sultān Alā-ud-dīn Khilji despatched Ulughkhān (that is the Great Khān commonly styled Alfkhān) to destroy the idol-temple of Somnāth. This was done and the largest idol was sent to Alā-ud-dīn.<sup>8</sup>

Chief Towns,  
*Asāwal*.

**Asāwal.** Abū Rihān Al Bīrūni is the first (A.D. 970 - 1039) of Arab geographers to mention Asāwal the site of Ahmedābād which he correctly

<sup>1</sup> Al Idrisi in Elliot's History of India, I. 9. The Balhāras or Rāshtrakūṭis lost their power in A.D. 974. The only explanation of Idrisi's (A.D. 1100) Balhāras at Anhilwāra is that Idrisi is quoting from Al Bīrūni A.D. 950.

<sup>2</sup> Farishtah Persian Text Lithographed Bombay Edition, I. 57.

<sup>3</sup> Farishtah Persian Text Lithographed Bombay Edition, IV. 48. The Rauzat-us-Safa states that it was at Somnāth the Ghaznavide wanted to fix his capital (IV. 42 Persian Text, Lucknow Edition). Anahilavāḍa seems more likely.

<sup>4</sup> Sir Henry Elliot's History of India, II. 155.

<sup>5</sup> The Jāmi-ul-Hikāyāt in Elliot (History of India), II. 162.

<sup>6</sup> Elliot's History of India, II. 200.

<sup>7</sup> Elliot's History of India, II. 229-30.

<sup>8</sup> Sir Henry Elliot's History of India, III. 74.

places two days' journey from Gandāy.<sup>1</sup> The next notice is along with Khābirūn (probably Kāvi on the left mouth of the Māhi) and near Hamāwal or Janāwal, apparently Chunvāl or Virangām, by Al Idrīsī (end of the eleventh century) as a town, populous, commercial, rich, industrious, and productive of useful articles.<sup>2</sup> He likens Asāwal "both in size and condition" to Dhūlaka both being places of good trade.<sup>3</sup> In the early fourteenth century (A.D. 1325) Zānd-dīn Bāmi refers to Asāwal as the place where Sultan Muhammad Taghlik (A.D. 1325-1351) had to pass a month in the height of the rains owing to the evil condition to which his horses were reduced in marching and countermarching in pursuit of the rebel Tāghī. In the beginning of the fifteenth century (A.D. 1403-4) the Tārīkh-i-Mubārak Shāh notices Asāwal as the place where Tātārkhān the son of Zafarkhān had basely seized and confined his own father.<sup>4</sup> The Mirāt-i-Sikandarī also speaks of Asāwal (A.D. 1403) but with the more courtly remark that it was the place where Zafarkhān the grandfather of Sultan Ahmad the founder of Ahmedabad, retired into private life after placing his son Tātārkhān on the throne.<sup>5</sup> The Mirāt-i-Sikandarī states that the city of Ahmedabad was built<sup>6</sup> in the immediate vicinity of Asāwal. The present village of Asarwa is, under a slightly changed name, probably what remains of the old town.

**Barda.** See VALABHI.

**Broach** (Bāru'ī, Bāru'ī, Bāru's) is one of the places first attacked by the Muslim Arabs. In the fifteenth year of the Hijrah (A.D. 636) the Khālifah Umar appointed Usman son of Abdul Asī to Bahrain. Usman sent Hakam to Bahrain and Hakam despatched a fleet to Bārāūz (or Broach).<sup>7</sup> Al Bilāduri (A.D. 892-93) speaks of Junaid the son of Abdur Rahmān Al Marri on his appointment to the frontier of Sindh in the Khilāfat of Hishām bin Abdul Malik (A.D. 724-743) sending an expedition by land against Birus (Broach) . . . and overrunning Jurz<sup>8</sup> (Gujarāt). Ibnī Khurdādhah (A.D. 912) enumerates Bārūh among the countries of Sindh.<sup>9</sup> Broach is next noticed<sup>10</sup> by Al Birūni (A.D. 970-1039) as standing near the estuary of the river Nābhada, as 120 miles (30 *parasangas*) from Debal, and as being with Rahanjur (Rander) the capital of Bārdes. In describing the coasts of the Persian Gulf and the Indian Ocean Al Masūdī (A.D. 915-944) speaks of Broach as *Barūsī* adding from which come the famous lance shafts called *Bārūsī*.<sup>11</sup> Al Idrīsī (A.D. 1100) mentions<sup>12</sup> Bārūh as a large town well-built of brick and plaster, the inhabitants rich, engaged in trade and ready to enter upon speculations and distant expeditions, a port for vessels coming from China and India, being two days' journey from Sammīr (Chenā) and eight days from Nahrwāra Anbilwāra Pattan. In the fourteenth century (A.D. 1325) Broach is described as in the flames of the insurrection

## Appendix V.

ARAB  
REFERENCES,  
A.D. 851-1350.  
Chief Towns,  
*Asāwal.*

*Ahmedabad.*

*Barda.*

Capital and  
Port Towns.  
*Broach.*

<sup>1</sup> Sachau's Text, 102.

<sup>2</sup> Al Idrīsī in Elliot (History of India), I. 87.

<sup>3</sup> Al Idrīsī in Elliot (History of India), I. 88. <sup>4</sup> Elliot's History of India, III. 260.

<sup>5</sup> Bayley's Gujarat, 81. <sup>6</sup> Elliot's History of India, IV. 39, History of Gujarat, 81.

<sup>7</sup> Bayley's Gujarat, 90. <sup>8</sup> Al Bilāduri (A.D. 892) in Elliot's History of India, I. 116.

<sup>9</sup> Al Bilāduri (A.D. 892) in Elliot's History of India, I. 126. Details of this far-stretching affliction of Sindh, Kachh, the Chāvādās, Chitor, Bhūmal, and Ujjain are given above, History 109.

<sup>10</sup> Ibnī Khurdādhah in Elliot (History of India), I. 14.

<sup>11</sup> Al Birūni in Elliot (History of India, I. 19-66), and Sachau's Arabic Text, 100.

<sup>12</sup> Barbier De Meynard's Arabic Text of Les Prairies D'Or, I. 239.

<sup>13</sup> Al Idrīsī in Elliot (History of India), I. 87.

## Appendix V.

ARAB  
REFERENCES,  
A.D. 851-1350

Port or Coast  
Towns  
*Cambay.*

censed by the foreign *amirs* or nobles of the hot-tempered and impolitic Muhammad bin Tughlak (A.D. 1325-1351) who visited it in person to quell their revolt. Ziauddin Barini the famous annalist of his reign and the author of the *Tarikh-i-Firuz Shahi* speaks of his deputation to Broach by Malik Kabir the future Sultan Firuz Shah with a letter to the Sultan.<sup>1</sup>

**Cambay** (KAMBAYA 'KAMBAYAT, 'KAMBAYAT KRAMBAT) According to Al Istakhri (A.D. 951) Kambaya formed the north boundary of the land of the Balharis.<sup>2</sup> Al Istakhri describes it as four days' from Kambal (Anhilwara) sixteen miles (4 *farsangs*) from the sea and four days' from Surabaya probably Surabara or the mouth of the Tapi a term which is still in use.<sup>3</sup> Al Masudi (A.D. 915) in speaking<sup>4</sup> of the ebb and flow of the ocean mentions Kambaya. He notices that Kambaya was famous in Baghdad as it still is famous in Gujrat, for its shoes. These shoes, he says, were made in Kambaya and the towns about it like Samlan (Sanjan in Thana) and Suhali (Shipara). He notices that when he visited Kambaya in H. 303 (A.D. 913-11) the city was ruled by a Brahman of the name of Barma on behalf of the Balhara lord of Malkir (Malkhet). He states that this Barma was kind to and held friendly discussions with stranger Muslims and people of other faiths. He gives a pleasing picture of Cambay, on a gulf far broader than the estimates of the Nile, the Euphrates, or the Tigris whose shores were covered with villages, estates and gardens wooded and stocked with palm and date groves full of peacocks, parrots and other Indian birds. Between Kambiya and the sea from which this gulf branches was two days' journey. When, says Al Masudi, the waters ebb from the gulf stretches of sands come to view. One day I saw a dog on one of these desert-like stretches of sand. The tide began to pour up the gulf and the dog hearing it ran for his life to the shore but the rush was too rapid. The waters overtook and drowned him. Al Masudi speaks of an emerald known as the Makkani emerald being carried from Kambaya by Adu to Makkah where it found a market.<sup>5</sup> Ibn Haukal (A.D. 968-996) names Kambaya among the cities of Hind.<sup>6</sup> In his time there were Jāma or assembly mosques in Kambaya, where the precepts of Islām were openly taught. Among the productions of Kambaya he gives mangoes, coconuts, lemons and yucca in great plenty and some honey but no date trees.<sup>7</sup> He makes Kambaya four miles (one *farsang*) from the sea and four (that is four days' journey) from Suhara apparently Surabara that is Surat. The distance to Kambal or Anhilwara by some mistake is shown as four *farsangs* instead of four days' journey.<sup>8</sup> Al Biruni (A.D. 970-1031) places Kambaya within the large country of Gujrat (120 miles)<sup>9</sup> (30 *farsaks*) from Dabul (Karachi). He says the men of Kambaya receive tribute from the chiefs of the island of Kis or Kish (probably Kich-Makrin).<sup>10</sup> Al Idrisi (A.D. 1100) places Kambaya with other Gujrat cities, in the second

<sup>1</sup> Elliot's History of India, III. 256-260.

<sup>2</sup> Al Istakhri in Elliot (History of India), I. 27.

<sup>3</sup> Al Istakhri in Elliot (History of India), I. 30.

<sup>4</sup> Prairies D'Or (Barber DeMeynard's Arabic Text), I. 253-54.

<sup>5</sup> Prairies D'Or (Arabic Text), III. 17.

<sup>6</sup> Ibn Haukal in Elliot (History of India), I. 34.

<sup>7</sup> Ibn Haukal in Elliot (History of India), I. 38.

<sup>8</sup> Ibn Haukal in Elliot (History of India), I. 39.

<sup>9</sup> Rashid-ud-din from Al Biruni in Elliot's History of India, I. 66 and Sachau's Arabic Text, chapter 18 pages 99-102.

<sup>10</sup> Sir Henry Elliot's History of India, I. 67.

climate.<sup>1</sup> He says it is a pretty and well known naval station second among the towns of Guprāt.<sup>2</sup> It stands at the end of a bay three miles from the sea where vessels can enter and fast anchor. It is well supplied with water and has a fine fortress built by the Government to prevent the inroads of the pirates of Kish (Makran). From Kambāya to the island of Anbkin (Pirān) is two and a half days' sail and from Anbkin to Debal (or Karāchi) two days more. The country is fertile in wheat and rice and its mountains yield the bamboo. Its inhabitants are idolaters. In his *Taziyat-ul-Amsar*, Abdullāh Wassaf in A.D. 1300 (H. 699) writes: "Guprāt which is commonly called Kambāyat contains 70,000 villages and towns all populous and the people abounding in wealth and luxuries. In the course of the four seasons seventy different species of beautiful flowers bloom. The purity of the air is so great that the picture of an animal drawn with the pen is lifelike. Many plants and herbs grow wild. Even in winter the ground is full of tulips (poppies). The air is healthy, the climate a perpetual spring. The moisture of the dew of itself suffices for the cold season crops. Then comes the summer harvest which is dependent on the rain. The vineyards bring forth blue grapes twice a year."

The trade in horses from the Persian isles and coast and from Kutif, Bahsa, Bahrein, and Hormuz was so great that during the reign of Atāhak Abū Bakr<sup>3</sup> (A.D. 1154-1189) 10,000 horses worth 2,20,000 *dinārs* (Rs. 1,10,00,000) were imported into Cambay and the ports of Malabār. These enormous sums were not paid out of the government treasures but from the endowments of Hindu temples and from taxes on the courtezans attached to them. The same author mentions the conquest of Guprāt and the plunder of Kambāyat by Malik Mu'izz-ud-dīn (called by Faushlah Ali and by Barni U'lugh meaning the great Khan.) The *Tārkh-i-Firuz Shāh* states that Nasrat Khan and not U'lugh Khan took and plundered Cambay and notices that in Cambay Nasrat Khan purchased Kāfur Hazar Dīnār (the thousand Dīnār Kāfur), the future favourite minister and famous general of Ala-ud-dīn. About fifty years later the hot-headed Muhammad bin Tughlak (A.D. 1327-1351) was in Cambay quelling an insurrection and collecting the arrears of Cambay revenue.<sup>4</sup>

## Appendix V.

ARAB  
REFERENCES,  
A.D. 851-1350.

Port or Coast  
Towns.  
Cambay

<sup>1</sup> See Henry Elliot's History of India, I, 17.

<sup>2</sup> See Henry Elliot's History of India, I, 18. <sup>3</sup> *Taziyat-ul-Amsar* in Elliot, III, 32.

<sup>4</sup> Sibt's place is mentioned by him as the garden of Roses.

<sup>5</sup> The word *dirham* is from the Latin *denarius* a silver coin worth 10 oz. of brass) through the Greek *δραχμή*. It is a Kufic word, the ancient Arabic equivalent being *mithkal*. The *dirham* or *diert* varied in value in different times. In 'Abū Hanīfah's (the greatest of the four Sunni jurists) time (A.D. 719) its value ranged from 10 to 12 *dirhams*. Then from 20 to 25 *dirhams* or *drachmas*. As a weight it represented a *drachma* and a half. Though generally fluctuating, its value may be assessed at 9s. or 10 francs to half a sovereign. For an elaborate article on the *dirham* see Yule's *Cathay*, II, 439, Burton's *Ali* Leilah, I, 32. The word *Dirham* is used in Arabic in the sense of "silver" (vulg. *siller*) the Greek *δραχμή* and the *drachma* of Plautus. This silver piece was 9 grs. and as a weight 66½ grains. Sir Henry Elliot does not speak more at length of the *dirham* and the *dirham* than to say (History of India, I, 161) that they were introduced in India in the reign of 'Abdūl Malik (A.D. 685) and Elliot, VIII, 31) that the *dirham* was a Rūm and the *dirham* a Persian coin. The value of the *dirham* in modern Indian currency may be said to be Rs. 4 and that of the *dirham* nearly equals 4.

<sup>6</sup> Wassaf gives the date of this event as A.C. 1298, but the *Tārkh-i-Alāi* of 'Amir Khosrow places it at A.C. 1300. See Elliot's History of India, III, 43 and 74.

<sup>7</sup> Elliot's History of India, III, 256-57.

## Appendix V.

ARAB  
REFERENCES,  
A.D. 851-1350  
Port or Coast  
Towns,  
*Cheul.*

**Cheul (Saimūr).** Al Masūdī (A.D. 913) is the first Arab geographer to mention *Saimūr*.<sup>1</sup> He says, "On the coast as in Saimūr Sukhāra and Tān the *Lōḥiyah* language is spoken. In describing Saimūr Al Masūdī states<sup>2</sup> that at the time of his visit (A. 304, A.D. 914) the ruler on behalf of the Bahāra was Jhānjha (this is the fifth *Shihāra* A.D. 916). Nearly ten thousand Musalmāns were settled in Saimūr including some (called Bayāsirah) born in the land of Arab parents and others from *Sīrāj* and Persian Gulf, Basrah, Baghdad, and other towns. A certain Mūsā bin Is-hāk was appointed *Kadī* or ruler<sup>3</sup> by the Bahāra or Valubhī, that is the reigning *Rāshtrakūta* Indra Nityanvarsha to adjudicate Muhammadan disputes according to Musalmān law and customs. He describes at length the ceremony of self-destruction by a *Ḥesā*'s youth (a Hindu by religion) to gain a better state in his future life, his scalping himself and putting fire on his head, his cutting out a piece of his heart and sending it to a friend as a souvenir.

Al Istakhri (A.D. 951) mentions Saimūr as one of the cities of Hind, makes it the southern end of the Bahāra kingdom with Kambhaya as the northern,<sup>4</sup> and places it at a distance of five days from Sindān (the Thāma Sanjan) and fifteen days from *Sarandīb* or Ceylon.<sup>5</sup> Ibn Haukal (A.D. 968) notices Saimūr as one of the cities of Hind known to him and mentions the sea of Fars (or the Indian Ocean) as stretching from Saimūr on the east to *Tiz* or Makran.<sup>6</sup> He states<sup>7</sup> that the country between Saimūr and Tāmhil (Anbilawara) belongs to Hind. He makes<sup>8</sup> the distance between Subara (probably Surabāra or Swat), Sindan, and Saimūr five days each and between Saimūr and Sarandīb (Ceylon) fifteen days. Al Bīrūnī (A.D. 1020) says:<sup>9</sup> "Then you enter the land of Laran in which is Saimūr also called *Jaimūr* or *Chaimūr*." Al Idrisī (end of the eleventh century) mentions Saimūr as one of the towns of the second climate.<sup>10</sup> He describes it as large and well-built, five days from Sindān and among its products notes coconut trees in abundance, henna (*Lawsana inermis*), and on its mountains many aromatic plants.<sup>11</sup> His remark that Saimūr formed a part of the vast, fertile, well-peopled and commercial kingdom of the Bahāras must be taken from the work of Al-Jauhari (A.D. 950).

Al Kazwīnī (A.D. 1236) quoting Misān bin Muḥalhil (A.D. 912) describes Saimūr as one of the cities of Hind near the confines of Sind,<sup>12</sup> whose people born of Turkish and Indian parents are very beautiful. It was a flourishing trade centre with a mixed population of Jews, Firewor-

<sup>1</sup> Al Masūdī in Elliot (History of India), I, 24.

<sup>2</sup> P. 85, D'Orcy, II, 85.

<sup>3</sup> He was called a *Huīram* or *Huīramah* in the language of the country. Al Masūdī's *Muruj Arabic Text* Cairo Edition, II, 56.

<sup>4</sup> Al Masūdī's *Muruj Arabic Text* Cairo Edition, II, 56-57.

<sup>5</sup> One born in India of an Arab father and an Indian mother probably from the Gujarati word *ḥalḥ-bhara* meaning mixed blood. This seems the origin of the *Bais Rajput*. The performer in the case in the text was a Hindu. Al Masūdī (*Muruj Arabic Text* II, 57 Cairo Edition) says that the singular of Bayāsirah is *Besar*.

<sup>6</sup> Al Istakhri in Elliot (History of India), I, 27.

<sup>7</sup> Al Istakhri in Elliot (History of India), I, 30.

<sup>8</sup> Ibn Haukal in Elliot (History of India), I, 33-34.

<sup>9</sup> Ibn Haukal in Elliot (History of India), I, 38.

<sup>10</sup> Ibn Haukal in Elliot (History of India), I, 38.

<sup>11</sup> Al Bīrūnī Sachau's Arabic Text, 102; Elliot's History of India, I, 39, 66.

<sup>12</sup> Al Idrisī in Elliot (History of India), I, 77.

<sup>13</sup> Al Idrisī in Elliot (History of India), I, 77, 8.

<sup>14</sup> Al Kazwīnī in Elliot (History of India), I, 97.

shippers, Christians, and Musalmāns.<sup>1</sup> The merchandise of the Turks (probably of the Indo-Afghan frontier) was conveyed thither and the best of aloes were exported and called *Sannāri* after its name. The temple of Sannār was on an eminence with idols of turquoise and *baidjak* or ruby. In the city were many mosques churches synagogues and fire-temples.

**Dholka** (DULAKA). Al Idrisi (end of the eleventh century) places Duhaka and another town he calls Hanawal that is Chnuwal or Junawal perhaps Jhalāwār between Barūh (Broach) and Nahrwāra. He describes Dūlakā as on the banks of a river (the Sābarnatī) which flows into the sea, which forms an estuary or gulf on the west (east) of which stands the town of Barūh. Both these towns, he adds stand at the foot of a chain of mountains which lie to the north and which are called *ʿndlān* apparently Vindhya. The *kana* (bamboo) grows here as well as a few coconut trees.<sup>2</sup>

• **Goa** See SINDHUR.

**Gondal** (KONDAL) Zai-ud-dīn Barni in his *Tārīkh-i-Firuz Shāhi* states<sup>1</sup> that Sultan Muhammad Tughlak spent (A.D. 1349) his third rainy season in Gujarat in Kōndal (Gondal). Here the Sultan assembled his forces before starting on his fatal march to Sindh.

**Kachh**. Al Birūnī (A.D. 970-1031) is the only Arab writer who refers to Kachh. He calls Kachh<sup>1</sup> with Somnath the head-quarters of the country of the Bawārij or Medh parafes. Speaking of the Indus he notices<sup>2</sup> that one of its branches which reaches the borders of Kachh is known as Sind Sāgar. In a third passage he refers<sup>3</sup> to Kachh as the land of the *maki* or balsamodendron and of *bādrūd* or bezoar. It was twenty-four miles (6 *farsangs*) from Debal (Karachi). According to the *Tārīkh-i-Maāsūmī*<sup>4</sup> when (A.D. 1069) the sovereignty of Sindh passed from the descendants of Mahmūd of Ghazni to the Sammas, Singhar, the grandson of Sumra (A.D. 1069)<sup>5</sup> extended his sway from Kachh to Nasarpūr<sup>6</sup> near Sindh. Haidarābād and Khafif the son of Singhar consolidated his power and made Kachh a Samma dependency.<sup>7</sup> Dūda the grandson of Khafif quelled a threatened Sumra rising by proceeding to Kachh and chastising the Sammas.<sup>8</sup> On the fall of the Sammas the Chāmrās became masters of Kachh from whose hands the country passed to those of the Sammas. Crushed down under the iron sway of the Sammas a number of Sammas fled from Sindh and entered Kachh where they were kindly received by the Chāmrās who gave them land to cultivate. After acquainting themselves with the country and the resources of its rulers the Samma immigrants who seem to have increased in numbers and strengthened themselves by union, obtained possession by stratagem but not without heroism of the chief fortress of Kachh.<sup>9</sup> This fort now in ruins

## Appendix V.

ARAB  
REFERENCES,  
A.D. 851-1350.

Chief Towns.  
*Dholka.*

*Goa.*  
*Gondal.*

Capitals.  
*Kachh.*

<sup>1</sup> Though Al Kazwini wrote in the thirteenth century, he derives his information of India from Misā'ir bin Muḥalbil, who visited India about A.D. 912. Elliot (History of India), I. 94.

<sup>2</sup> Al Idrisi in Elliot (History of India), I. 87.

<sup>3</sup> *Tārīkh-i-Firuz Shāhi* by Zia Barni (Elliot's History of India), III. 204-65.

<sup>4</sup> Rashid-ud-dīn (A.D. 1310) from Al Birūnī in Elliot's History of India, I. 65.

<sup>5</sup> Rashid-ud-dīn (A.D. 1310) from Al Birūnī in Elliot's History of India, I. 49.

<sup>6</sup> Rashid-ud-dīn (A.D. 1310) from Al Birūnī in Elliot's History of India, I. 66.

<sup>7</sup> Written A.D. 1600 (Elliot, I. 213).

<sup>8</sup> *Tārīkh-i-Maāsūmī* in Elliot, I. 16.

<sup>9</sup> *Tuhfatul Kirām* in Elliot, I. 344.

<sup>10</sup> *Tārīkh-i-Maāsūmī* in Elliot, I. 217.

<sup>11</sup> *Tārīkh-i-Maāsūmī* in Elliot, I. 218.

<sup>12</sup> *Tārīkh-i-Tāhiri* (Elliot's History of India), I. 267-68.

## Appendix V.

ARAB  
REFERENCES,  
A.D. 851 - 1350.

Capitals.

*Kaira.*

Chief Towns.

*Kābirūn.*

*Kambay.*

*Kanauj.*

was the fort of Gūndī.<sup>1</sup> The Tārīkh-i-Tahiri states that up to the time the history was written (A.D. 1621)<sup>2</sup> the country was in the possession of the Sammas, both the Rais<sup>3</sup> Bhāra and Jām Sūta of great and little Kūfih in his time being of Samma descent.

**Kaira (KARRA).** One mention of Kaira apparently Kaira or Kheda occurs in Ziauddin Barni's account of Muhammad Tughlak's (A.D. 1325) pursuit of his rebellious Gujarāt noble Taghi. He speaks of Muhammad's detention for a month at Asāwal during the rains and his overtaking and dispersing Taghi's forces at Karra. From Karra the rebels fled in disorder to Nahwāra (Anhilwāra). Several of Taghi's supporters sought and were refused shelter by the Rām of Mandal that is Patia near Vināgam.

**Kābirūn.** Al Idrisi (end of the eleventh century) mentions Kābirūn and Asāwal as towns of the same 'section' both of them populous, commercial, rich, and producing useful articles. He adds that at the time he wrote the Musalmāns had made their way into the greater portion of these countries and conquered them. Kābirūn like the Akaberson of the Periplus (A.D. 210) is perhaps a town on the Kāveri river in south Gujarāt.

**Kambay.** See CAMBAY.

**Kanauj.** Al Masūdi<sup>4</sup> (A.D. 956) is the first Arab traveller who gives an account of Kanauj. He says<sup>5</sup> "The kingdom of the Banua king of Kanauj extends about a hundred and twenty square *parasangs* of Sindh, each *parasang* being equal to eight miles of this country. This king has four armies according to the four quarters of the world. Each of them numbers 700,000 or 900,000. The army of the north wars against the prince of Multan and with his Musalmān subjects on the frontier. The army of the south fights against the Balhāra king of Mankir. The other two armies march to meet enemies in every direction. Hui Hankal (A.D. 968-976) says<sup>6</sup> that from the sea of Fars to the country of Kanauj is three months' journey. Rashīd-ud-dīn from Al Biruni (A.D. 970-1039) places<sup>7</sup> Kanauj south of the Himālayās and states<sup>8</sup> that the Jamna falls into the Ganga below Kanauj which is situated on the west of the river (Ganga). The chief portion of Hind included in the "second climate" is called the central land or Madhya Desh. He adds that the Persians call it Kanauj. It was the capital of the great, haughty, and proud despots of India. He praises the former magnificence of Kanauj, which he says being now deserted by its ruler has fallen into neglect and ruin, and the city of Bān, three days' journey from Kanauj on the eastern

<sup>1</sup> Journal Asiatic Society of Bengal for February 1838, 102.

<sup>2</sup> Sir Henry Elliot's History of India, I, 268.

<sup>3</sup> Tārīkh-i-Futūḥ Shāhin in Elliot, II, 260.

<sup>4</sup> In his Arabic Text of the Murāj (Pranée D'Or, Cairo Edition) Al Masūdi writes the name of the Kanauj king as Farwarah. (If the *F* stands for *P* and the *r* for *m*, as is quite possible in Arab writing, then this can be *Parmārah* the Arab plural for *Parmar*.) At volume I, page 240 the word Farwarah is twice used. Once, "And the king of Kanauj, of the kings of Sindh (India) is Farwarah." Again at the same page (210): "And Farwarah he who is king of Kanauj is opposed to Balhara." Then at page 241: Farwarah is again used in the beginning of the account quoted by Elliot in I, 23.

<sup>5</sup> Elliot's History of India, I, 23. In the Cairo Edition of the Arabic Text of Al Masūdi's Murāj (Pranée D'Or) vol. I, page 241 is the original of this account.

<sup>6</sup> Elliot's History of India, I, 33.

<sup>7</sup> Elliot's History of India, I, 45.

<sup>8</sup> Elliot's History of India, I, 49.

side of the Ganges being now the capital. Kananj was celebrated for its descendants of the Pāṇḍavas as Mahara (Muthra) is on account of Bās Dev (Kṛṣṇa). Al Idrisi, end of the eleventh century, speaks<sup>1</sup> of Kananj in connection with a river port town of the name of Samandar "a large town, commercial and rich, where there are large profits to be made and which is dependent" on the rifle of the Kananj king Samandar, he says, stands on a river coming from Kashmir. To the north of Samandar at seven days is, he says, the city of Inner Kashmir under the rule of Kananj. The Chāh Nāmah (an Arabic history of great antiquity written before A.D. 753, translated into Persian in the time of Sultan Nāsiruddīn Kāmbūh) (A.D. 1216) says<sup>2</sup> that when Chāh (A.D. 631-670) advanced against Akham Lohān of Brahmanabad that the Lohān wrote to ask the help of "the king of Hindostan," that is Kananj, at that time Sathān son of Kāsal, but that Akham died before his answer came.

**Kol.** Ibn Khurādādhbih (A.D. 912) has Kol seventy-two miles (18 *farsakhs*) from Sanjān in Kachh.<sup>3</sup> And the Taj-ul-Maāsir<sup>4</sup> relates how in A.D. 1194 Kutubuddin advanced to Kol and took the fort.

**Mālkhet (Mankheta).** Al Masūdī (A.D. 943) is the first Arab writer to mention *Mankheta* that is Mānyakheta now Mālkhet about sixty miles south-east of Sholāpūr. In relating the extinction of the great Brāhma-Ārya dynasty of India Al Masūdī states<sup>5</sup> that at the time the city of Mānkīr, the great centre of India, submitted to the kings called the *Balhāras* who in his time were still ruling at Mānkīr.<sup>6</sup>

Al Masūdī correctly describes the position of Mālkhet as eighty Smūdh or eight-mile *farsakhs* that is six hundred and forty miles from the sea in a mountainous country. Again he notices that the language spoken in Mānkīr was Kūrya,<sup>7</sup> called from Kārah or Kanara the district where it was spoken. The current coin was the *Tartariyyah dirham* (each weighing a dirham and a half) on which was impressed the date of the ruler's reign. He describes the country of the Balhāras as stretching from the Kamkar (or Konkan) in the south or south-west north to the frontiers of the king of Jnṣr (Gujarat), "a monarch rich in men horses and camels." Al Istakhrī (A.D. 951) describes Mānkīr as the dwelling of the wide-ruling Balhāra. Ibn Hunkal (A.D. 968-976) repeats almost to the letter the information given by Al Istakhrī. The destruction of Mālkhet (Manya Kheta) by the western Chāḷukya king Tailappa in A.D. 972 explains why none of the writers after Ibn Hunkal mentions Mānkīr.

<sup>1</sup> *Ibid.*, I. 30.

<sup>2</sup> Elliot's History of India, I. 147.

<sup>3</sup> Sir Henry Elliot's History of India, I. 15.

<sup>4</sup> Taj-ul-Maāsir in Sir Henry Elliot's History of India, II. 222. "After staying some time at Dādi he (Kutub-ud-din) marched in A.D. 1194 (H. 590) towards Kol and Bacera passing the Jumna which from its exceeding purity resembled a mirror." It would seem to place Kol near Bacera.

<sup>5</sup> Al Masūdī's Prairies D'Or (Arabic Text), I. 162.

<sup>6</sup> Al Masūdī in Elliot (History of India), I. 19, 20, 21 and Prairies D'Or, I. 178.

<sup>7</sup> Al Masūdī Arabic Text Prairies D'Or, (I. 381); Al Masūdī in Elliot (History of India), I. 21.

<sup>8</sup> That is an Arab dirhem and a half. Al Istakhrī in Elliot (History of India), I. 27. These *Tartariyya* dirhems are mentioned by almost all Arab writers. Al Idṛīsī says they were current in Manstrah in Sindh and in the Malay archipelago. See Elliot, I. 3 note 4. According to *Sulamān* (A.C. 851) the Tartariya dirham weighed "a dirham and a half of the coinage of the king." Elliot, I. 3. Al Masūdī (Prairies D'Or, I. 382) calls these "Tartariyyah" dirhams, giving them the same weight as that given by *Sulamān* to the Tartariyyah dirhams. *Ibn Hunkal* calls it the Titarī dirhem and makes its weight equal to "a dirham and a third" (Elliot, I. 85).

## Appendix V.

ARAB  
REFERENCES,  
A.D. 851 - 1350.  
Chief Towns.  
*Kānauj.*

*Kol.*

*Mālkhet.*

## Appendix V.

ARAB  
REFERENCES,  
A.D. 861 - 1350.  
Chief Towns.

*Nadriana.*

**Ma'ndal.** Ibnī Khurādādhah (A.D. 912) enumerates Māndal (in Virangām) with Rūmla,<sup>1</sup> Kulī, and Bārūh as countries of Sindh. During the Khilāfat of Hishām the son of Abdul Malik (A.D. 724-743) Jumaid son of Abdul Rahman-al-Murri was appointed to the frontier of Sindh. According to Al Bilāduri (A.D. 892) Jumaid sent his officers to Māndal,<sup>2</sup> Dahmaj perhaps Karlej, and Bāhrūs (Broach).

**Na'ra'na.** In his India Al Biruni (A.D. 970-1031) notices Nārāna near Jaipur as the ancient capital of Gujarat. He says that its correct name is Bazānah but that "it is known to our people (the Arabs) as Nārān." He places it eighty miles (20 *farsakhs*) south-west of Kanauj, and adds that when it was destroyed the inhabitants removed to and founded another city.<sup>3</sup> Abū Rihān makes Nārāna the starting point of three itineraries to the south the south-west and the west. Al Biruni's details suffice to place this centre in the neighbourhood of the modern Jaipur and to identify it with Nārāyan the capital of Bairat of Matsya which according to Farishtah<sup>4</sup> Mahmūd of Ghazni took in A.D. 1022 (H. 412).

*Rander.*

**Ra'nder** (RĀHANJĪR OR RAHANJE'N). Al Biruni (A.D. 1031) gives<sup>5</sup> Rāhanjūr and Bāhrūj (Broach) as the capitals of Lar Dosh or south Gujarat. Elliot (Note B. I. 61) writes the word Damūhūr or Dahanhūr but the reading given by Sachau in his Arabic text of Al Biruni (page 100 chapter 18) is plainly Rāhanjūr (رہانجور) and the place intended is without doubt Rānder on the right bank of the Tāpti opposite Surat. In his list of Indian towns Al Idrisi (end of the eleventh century) seems to refer<sup>6</sup> to it under the forms Jandūr and Sandūr.

*Sanjan.*

**Sanja'n** (SINDĀN). The two Sanjāns, one in Kachh the other in Thāna, complicate the references to Sindān. Sindān in Kachh was one of the earliest gains of Islām in India. Al Bilāduri<sup>7</sup> (A.D. 892) speaks of Fazl, the son of Māhan, in the reign of the greatest of the Abbāsi Khulifāhs Al-Māmūn (A.D. 813-833), taking Sindān and sending Al Māmūn the rare present of "an elephant and the longest and largest *soj* or timber or teak spar ever seen." Fazl built an assembly mosque that was spared by the Hindus on their recapture of the town. Ibn Khurādādhah (A.D. 912) includes this Kachh Sindān with Broach and other places in Gujarat among the cities of Sindh. In his itinerary starting from Bukkar, he places Sindān seventy-two miles<sup>8</sup> (18 *farsakhs*) from Kol. Al Masūdi (A.D. 915-944) states that Indian emeralds from (the Kachh) Sindān and the neighbourhood of Kambūyat (Cambay) approached those of the first water in the intensity of their green and in brilliance. As they found a market in Makkah they were called Makkah emeralds.<sup>9</sup> Al Istakhrī (A.D. 951) under cities of Hind places the Koukan Sindān five days from *Surabāya* (Surabāra or Surat) and as many from *Sarmūr*<sup>10</sup>

<sup>1</sup> Kumlak is *rauma* salt land. There is a Rūm near Karūr about sixty miles south-east of Multān. Al Idrisi (A.D. 1135) has a Rūmalah three days from Kullata the salt range. Elliot, I. 92.

<sup>2</sup> Probably Okhāmandal. See Appendix vol. I. page 390 Elliot's History of India.

<sup>3</sup> Sachau's Arabic Text of Al Biruni's India, 99.

<sup>4</sup> Persian Text Bombay Edition of 1832, I. 53.

<sup>5</sup> Sachau's Arabic Text of Al Biruni, 100.

<sup>6</sup> Elliot's History of India, I. 84.

<sup>7</sup> Al Bilāduri in Elliot (History of India), I. 120. The word *soj* in the Arabic text means besides a teak-spar (which seems to be an improbable present to be sent to a Khulifāh), a large black or green turban or sash.

<sup>8</sup> Ibn Khurādādhah in Elliot (History of India), I. 14 and 15.

<sup>9</sup> De Meynard's Arabic Text of Les Piarres D'Or, III. 47-48.

<sup>10</sup> Al Istakhrī in Elliot (History of India), I. 27 and 30.

(Chewal). Ibnī Hānkal (A.D. 968) mentions (the Kachh) Sindān among the cities of Hind, which have a large Musalmān population and a Jāma Masjid<sup>1</sup> or assembly mosque. Al Bīrūnī (A.D. 970-1031)<sup>2</sup> in his itinerary from Debal in Sindh places the Kokan 200 miles (50 *farsakhs*) from that port and between Broach and Supāra. At the end of the eleventh century probably the Kachh Sindān was a large commercial town rich both in exports and imports with an intelligent and warlike, industrious, and rich population. Al Idīsī gives the situation of the Konkān Sindān as a mile and a half from the sea and five days from Sumūr (Cheval)<sup>3</sup>. Apparently Abul Fida<sup>4</sup> (A.D. 1324) confused Sindān with Sindābūr or Gon which Ibnī Batūta (A.D. 1340) rightly describes as an island<sup>5</sup>.

**Sinda'bu'r or Sinda'pu'r.** Al Masūdī (A.D. 943) places *Sindapūr* he writes it Sindābūra or Gon in the country of the Baghara (Bāhāra) in India.<sup>6</sup> Al Bīrūnī (A.D. 1021) places Sindāpūr or Sindābūr that is Gon as the first of coast towns in Malabār the next being Bākūr.<sup>7</sup> Al Idīsī (end of the eleventh century) describes Sindābūr as a commercial town with fine buildings and rich bazars in a great gulf where ships cast anchor, four days along the coast from Thina.

**Somna'th** Al Bīrūnī (A.D. 970-1031) is the first of the Arab writers to notice Somnāth. He calls Somnāth and Kachh the capital of the Bawārj pirates who commit their depredations in boats called *hijra*.<sup>8</sup> He places Somnāth (14 *farsakhs*) fifty-six miles from Debal or Karāchi 200 miles (50 *farsakhs*) from Anulwār and 180 miles (60 *yajūnas*) from Broach. He notes that the river Sarsūt falls into the sea an arrow-shot from the town. He speaks of Somnāth as an important place of Hindu worship and as a centre of pilgrimage from all parts of India. He tells of votaries and pilgrims performing the last stage of their journey crawling on their sides or on their ankles, never touching the sacred ground with the soles of their feet even progressing on their heads.<sup>9</sup> Al Bīrūnī gives<sup>10</sup> the legendary origin of the Somnāth idol how the moon loved the daughters of Prajāpati, how his surpassing love for one of them the fair Rohini kindled the jealousy of her slighted sisters, how their angry sire punished the partiality of the moon by pronouncing a curse which caused the pallor of leprosy to overspread his face, how the penitent moon smelt for forgiveness to the saint and how the saint unable to recall his curse showed him the way of salvation by the worship of the *Lingam*, how he set up and called the Moon-Lord a stone which<sup>11</sup> for ages had lain on the sea shore less than three miles to the west of the mouth of the Sarasvati, and to the east of the sea of the golden castle of *Badrī* (Veraval) the residence of Isak and near the scene of his death and of the destruction of his people the Yādavas. The waxing and the waning of the moon caused the flood that hid the *Lingam* and the ebb that showed it and proved that the Moon was its servant who bathed it regularly. Al Bīrūnī notices<sup>12</sup> that in his time the castellated walls and other fortifications round the temple were not more than a hundred

## Appendix V.

ARAB  
REFERENCES,  
A.D. 851-1360.

Port or  
Coast Towns.  
*Sindabur* or  
*Sindapur*.

*Somnath*.

<sup>1</sup> Ibnī Hānkal in Elliot (History of India), I. 34 and 38.

<sup>2</sup> Al Bīrūnī in Elliot, I. 66.

<sup>3</sup> Al Idīsī in Elliot, I. 77-85.

<sup>4</sup> Sir Henry Elliot's History of India, I. 403 Appendix.

<sup>5</sup> Ibnī Batūta, 166.

<sup>6</sup> Al Masūdī in Elliot (History of India), I. 21.

<sup>7</sup> Rashid-ud-dīn from Al Bīrūnī in Elliot, I. 68.

<sup>8</sup> Al Idīsī in Elliot, I. 89.

<sup>9</sup> Sir Henry Elliot's History of India, I. 65; Sachau's Arabic Text of Al Bīrūnī, 102.

<sup>10</sup> Elliot's History of India, I. 67.

<sup>11</sup> Sachau's Arabic Text, 253.

<sup>12</sup> Sachau's Text of Al Bīrūnī, 252.

<sup>13</sup> Sachau's Arabic Text, 253 chapter 58.

## Appendix V.

ARAB  
REFERENCES  
A.D. 851 - 1350.  
Port on  
East Towns,  
Somnāth.

years old. Al Birūni represents the upper part of the *Lingam* as hung with massive and jewelled gold chains. These chains together with the upper half of the idol were, he observes, carried away by the Emir<sup>1</sup> Mahmūd to Ghazna, where a part of the idol was used to form one of the steps of the Assembly Mosque and the other part was left to lie with *Chakra Sudm*, the Thānesar idol, in the *amida'n* or hippodrome of Mahmūd's capital. Sorquath, says Al Birūni,<sup>2</sup> was the greatest of the *Lingams* worshipped in India where in the countries to the south-west of Sindh the worship of these emblems abounds. A jar of Ganges water and a basket of Kashmir flowers were brought daily to Somnāth. Its worshippers believed the stone to possess the power of curing all diseases, and the mariners and the wanderers over the deep between Sofāla and China addressed their prayers to it as their patron deity.<sup>3</sup> Ibnī Asīr<sup>4</sup> (A.D. 1121) gives a detailed account of the temple of Somnāth and its ancient grandeur. He says Somnāth was the greatest of all the idols of Hind. Pilgrims by the hundred thousand met at the temple especially at the times of eclipses and believed that the ebb and flow of the tide was the homage paid by the sea to the god. Everything of the most precious was brought to Somnāth and the temple was endowed with more than 10,000 villages. Jewels of incalculable value were stored in the temple and to wash the idol water from the sacred stream of the Gunga was brought every day over a distance of two hundred *farsangs* (1200 miles). A thousand Brāhmans were on duty every day in the temple, three hundred and fifty singers and dancers performed before the image, and three hundred barbers shaved the pilgrims who intended to pay their devotions at the shrine. Every one of these servants had a settled allowance. The temple of Somnāth was built upon fifty pillars of teakwood covered with lead. The idol, which did not appear to be sculptured,<sup>5</sup> stood three cubits out of the ground and had a girth of three cubits. The idol was by itself in a dark chamber lighted by most exquisitely jewelled chandeliers. Near the idol was a chain of gold to which bells were hung weighing 200 *mans*. The chain was shaken at certain intervals during the night that the bells might rouse fresh parties of worshipping Brāhmans. The treasury containing many gold and silver idols, with doors hung with curtains set with valuable jewels, was near the chamber of the idol. The worth of what was found in the temple exceeded two millions of *dirārs* (Rs. 1,00,00,000). According to Ibnī Asīr Mahmūd reached Somnāth on a Thursday in the middle of *Zilkāda* H. 414 (A.D. December 1023). On the approach of Mahmūd Bhīm the ruler of Anhilvād fled abandoning his capital and took refuge in a fort to prepare for war. From Anhilvād Mahmūd started for Somnāth taking several forts with images which, Ibnī Asīr says, were the heralds

<sup>1</sup> It appears that at the time of his expedition to Somnāth Mahmūd had not adopted the title of Sultan.

<sup>2</sup> Sachau's Arabic Text, 253 chapter 58.

<sup>3</sup> Sachau's Text, 253 chapter 58.

<sup>4</sup> The *Tārīkh-i-Kamil*. Ibnī Asīr (A.D. 1160 - 1232) is a voluminous and reliable historian. Ibnī Khallikān, the author of the famous biographical dictionary, knew and respected Asīr always alluding to him as "our Sheikh." See Elliot, II. 245.

<sup>5</sup> From the term 'sculptured' it would seem the idol was of stone. It is curious how Ibnī Asīr states a little further that a part of the idol was "burned by Mehmūd." See Elliot, II. 471. The *Tārīkh-i-Alfi* says (Elliot, II. 471) that the idol was cut of solid stone. It however represents it as hollow and containing jewels, in repeating the somewhat hackneyed words of Mahmūd when breaking the idol regardless of the handsome offer of the Brāhmans, and finding it full of jewels.

or chamberlains of Somnāth. Resuming his march he crossed a desert with little water. Here he was encountered by an army of 20,000 fighting men under chiefs who had determined not to submit to the invader. These forces were defeated and put to flight by a detachment sent against them by Mahmūd. Mahmūd himself marched to Dabalvārah a place said by Ibnī Asīr to be two days journey from Somnāth. When he reached Somnāth Mahmūd beheld a strong fortress whose base was washed by the waves of the sea. The assault began on the next day Friday. During nearly two days of hard fighting the invaders seemed doomed to defeat. On the third the Musalmāns drove the Hindus from the town to the temple. A terrible carnage took place at the temple-gate. Those of the defenders that survived took themselves to the sea in boats but were overtaken and some slain and the rest drowned.<sup>1</sup>

**Supāra** (SUBĀRĀ, SĪFĀRA, OR SĪRBĀRĀH.)—The references to Subārā are doubtful as some seem to belong to Surabara the Tāpti mouth and others to Sopāra six miles north of Bassāin. The first Arab reference to Subārā belongs to Sopāra. Al Masūdī's (A.D. 915)<sup>2</sup> reference is that in *Saimūr* (Cheval), *Subāra* (Sopāra), and *Tāna* (Thāna) the people speak the Lāriyāh language, so called from the sea which washes the coast. On this coast Al Istakhri (A.D. 951)<sup>3</sup> refers to *Subāra* that is apparently to Surabara or Surat a city of Hind, four days from Kambāyah (Cambay).<sup>4</sup>

Ibnī Haukal (A.D. 968-976) mentions *Surbārāh* apparently the Tāpti mouth or Surat as one of the cities of Hind four *farsakh*s, correctly days, from *Kambāyah*, and two miles (half *farsakh*) from the sea. From *Surbārā* to *Sindūn* perhaps the Kachh Sanjūn, he makes ten days. Al Birūnī (A.D. 970-1031) makes *Subāra* perhaps the Thāna Sopāra six days' journey from *Debal*<sup>5</sup> (perhaps Dū). Al Idrīsī (A.D. 1100) mentions *Subārā* apparently Sopāra as a town in the second climate, a mile and a half from the sea and five days (an excessive allowance) from *Sindūn*. It was a populous busy town, one of the entrepôts of India and a pearl fishery. Near *Subāra* he places *Bāra*, a small island with a growth of cactus and coconut trees.<sup>6</sup>

**Sura'ba'ra** See SUPĀRA

**Thāna** (TĀNA).—That Thāna was known to the Arabs in pre-Islām times is shown by one of the first Musalmān expeditions to the coast of India being directed against it. As early as the reign of the second Khalīfah Umar Ibn al Khattāb (A.D. 634-643; II.13-23) mention is made<sup>7</sup> of Usman, Umar's governor of Umān (the Persian Gulf) and Bahrein,

## Appendix V.

ARAB  
REFERENCES,  
A.D. 851-1350.

Port or  
Coast-Towns,  
Somnāth.

*Supāra*

*Surabara*,  
Capital,  
*Thāna*.

<sup>1</sup> The *Rauzat-us-Safa* (Lithogl. Edition, IV. 48) speaks of Mahmūd's project of making Somnāth his capital and not Anhilwāra as stated by Farishtah (I. 57, Original Persian Text). The *Rauzat-us-Safa* says that when Mahmūd had conquered Somnāth he wished to fix his residence there for some years as the country was very large and had a great many advantages including mines of pure gold and rubies brought from Sarandīb or Ceylon which he represents as a dependency of Gujarāt. At last he yielded to his minister's advice and agreed to return to Khurāsān.

<sup>2</sup> *Prairies D'Or* (DeMeynard's Arabic Text, I. 381; also Al Masūdī in Elliot (History of India, I. 24). <sup>3</sup> Al Istakhri in Elliot (History of India), I. 27.

<sup>4</sup> Al Istakhri in Elliot (History of India), I. 30.

<sup>5</sup> Ibnī Haukal in Elliot (History of India), I. 31, 39.

<sup>6</sup> Thus in Sachau's Arabic Text page 102, but Elliot (I. 66) spells the word *Sufara* in his translation. It might have assumed that form in coming from the Arabic through Rashīd-ud-dīn's Persian version from which Sir Henry Elliot derives his account.

<sup>7</sup> Al Idrīsī in Elliot (History of India), I. 77 and 85.

<sup>8</sup> Al Bilāzuri in Elliot, I. 116.

## Appendix V.

ARAB  
REFERENCES,  
A.D. 851-1350.

Capitals,  
Thana.

Vala or  
Valabhi.

sending a successful expedition against Thana. Al Masûdi (A.D. 943) refers to Thana on the shore of the Lârwi sea or Indian Ocean, as one of the coast towns in which the Lârwi language is spoken.<sup>1</sup> Al Birûni (A.D. 970-1031) gives<sup>2</sup> the distance from *Mahrut Desh* (the Marâtha country) to the Konkan<sup>3</sup> with its capital Thana on the sea-shore<sup>4</sup> as 100 miles (25 *farsakhs*) and locates the *Lâr Derh* (south Gujarât) capitals of *Bâhrûj* and *Rahanjur*, (Branch and Rânder) to the east of Thana. He places Thana with Somnâth Konkan and Kambaya in Gujarât and notices that from Thana the Lâr country begins. Al Idrisi (end of the eleventh century) describes<sup>5</sup> Thana as a pretty town upon a great gulf where vessels anchor and from where they set sail. He gives the distance from Sindapur (or Goa) to Thana as four days' sail. From the neighbourhood of Thana he says the *kand* or bamboo and the *tabashir* or bamboo pith are transported to the east and west.<sup>6</sup>

**Bara'da (PORBANDAR).**—Of the Arab attacks on the great sea-port Vala or Valabhi, twenty miles west of Bhavnagar, during the eighth and ninth centuries details are given Above pages 94-96. The manner of writing the name of the city attacked leaves it doubtful whether Balaba that is Valabhi or Barada near Porbandar is meant. But the importance of the town destroyed and the agreement in dates with other accounts leaves little doubt that the reference is to Valabhi.

In the fourth year of his reign about A.D. 758 the Khulifâh Ja'far-al-Mansûr<sup>7</sup> (A.D. 754-775) the second ruler of the house of Abbas appointed Hishâm governor of Sindh. Hishâm despatched a fleet to the coast of Baradah, which may generally be read Balabha, under the command of Amru bin Jamâl Taghlabi Tabari (A.D. 838-932) and Ihm Asir (A.D. 1160-1232)<sup>8</sup> state that another expedition was sent to this coast in A.H. 160 (A.D. 776) in which though the Arabs succeeded in taking the town, disease thinned the ranks of the party stationed to garrison the port, a thousand of them died, and the remaining troops while returning to their country were shipwrecked on the coast of Persia. Thus he adds deterred

<sup>1</sup> Ruben DeMeysman's Text of Masûdi's *Primes D'Or*, I. 330 and 381.

<sup>2</sup> Sachau's Arabic Text of Al Birûni, chapters 18, 99, 102 and Elliot's History of India, I. 60-61, 66-67.

<sup>3</sup> Al Idrisi in Elliot, I. 49.

<sup>4</sup> Al Idrisi says the real *tabashir* is extracted from the root of the reed called *sharkî*. *Sarkî* is Gujarati for reed. It is generally applied to the reeds growing on river banks used by the poor for thatching their cottages. *Tabashir* is a drug obtained from the pith of the bamboo and prescribed by Indian physicians as a cooling drink good for fever.

<sup>5</sup> The name *Baradah* بارده in Arabic orthography bears a close resemblance to باره *Barâh*, بارلہ *Bârlah*, بارلہ *Barlah*, all three being the forms or nearly the

forms in which the word بارلہ *Walabah* or بارلی *Walab* would be written by an Arab, supposing the diacritical points to be, as they often are, omitted. Besides as *Baridah* the word has been read and miswritten بارند *Narand* or *Barand* and باره *Barad* or *Barad*. In the *shikastah* or broken hand *Narand* or *Barand* بارند would closely resemble بارلہ *Bârlah* or *Baradah* بارده. Al Bilazari in Elliot's History of India I. 127, writes the word *Narand* or *Barand*. Sir Henry Elliot (History, I. 444) reads the word Barada and would identify the place with the Barda hills inland from Porbandar in south-west Kâthiawâd. The objection to this is that the word used by the Arab writers was the name of a town as well as of a coast tract, while the name of Barda is applied solely to a range of hills. On the other hand Balaba the coast and town meets all requirements.

<sup>6</sup> Reigned A.H. 754-775.

<sup>7</sup> Sir Henry Elliot's History of India, II. 246 and Frag. Arabes 3, 120, 212; Wetz's Geschichte der Chahsen, II. 115.

Al Mahdī<sup>1</sup> (A.D. 775-785) the succeeding Khalīfah from extending the eastern limits of his empire. Besides against Balāba the Smilhi Arabs sent a fleet against Kandhar apparently, though somewhat doubtfully,<sup>2</sup> the town of that name to the north of Broach where they destroyed a temple or *budd* and built a mosque. Al Bīrūnī<sup>3</sup> (A.D. 1030) writing of the Valabhi era describes the city of Balabāh 𐤁𐤋𐤁𐤀 as nearly thirty *jauzhan* (*yojans*), that is ninety miles to the south of Anhilvāra. In another passage<sup>4</sup> he describes how the Banian Rānka sued for and obtained the aid of an Arab fleet from the Arab lord of Mansūrah (built A.D. 750) for the destruction of Balāba. A land grant by a Valabhi chief remains as late as A.D. 766. For this reason and as the<sup>5</sup> myraders of that expedition fled panic-stricken by sickness Valabhi seems to have continued as a place of consequence if the expedition of A.D. 830 against Balā king of the east refers to the final attack on Valabhi in identification which is supported by a Jain authority which places the<sup>6</sup> final overthrow of Valabhi at 888 Samvat that is A.D. 830.\*

Of the rulers of Gujarāt between A.D. 850 and A.D. 1250 the only dynasty which imposed the Arabs was the Balhāras of Mānkhet or Manyakheta (A.D. 630-972) sixty miles south-east of Sholāpūr. From about A.D. 736 to about A.D. 978, at first through a more or less independent local branch and afterwards (A.D. 911) direct the Rāshtrakūtas continued overlords of most of Gujarāt. The Arabs knew the Rāshtrakūtas by their title *Vallabha* or Beloved in the case of Govind III. (A.D. 803-811), Prithivīvallabha Beloved by the Earth, and of his successor the long beloved Amoghavarsha Vallabhaskanda, the Beloved of Siva. Al Masūdī (A.D. 915-941) said: Balārā is a name which he who follows takes. So entirely did the Arabs believe in the overlordship of the Rāshtrakūtas in Gujarāt that Al Ihīrī (A.D. 1100, but probably quoting Al Jahharī A.D. 950) describes Nehrwalla as the capital of the Balāras. Until Dr. Bhāmlākar discovered its origin in Vallabha, the case with which meanings could be tortured out of the word and in Gujarāt its apparent connection with the Valabhi kings (A.D. 509-770) made the word Balārā a cause of matchless confusion.

The merchant Sulaimin (A.D. 851) ranks the Balhāra, the lord of Mānkīr, as the fourth of the great rulers of the world. Every prince in India even in his own land paid him homage. He was the owner of many elephants and of great wealth. He refrained from wine and paid his troops and servants regularly. Their favour to Arabs was famous. Abū Zaid<sup>6</sup> (A.D. 913) says though the Indian kings acknowledge the supremacy of no one, yet the Balhāras or Rāshtrakūtas by virtue of the title Balhāra are kings of kings. Ibn Khurdaadbeh (A.D. 912) describes the Balhāras as the greatest of Indian kings being as the name imports the king of kings. Al Masūdī (A.D. 915) described Balhāra as a dynastic name which he who followed took. Though he introduces two other potentates the king of Jurz and the Baūra or Pūmār king of Kanauj fighting with each other and with the Balhāra he makes the Balhāra, the lord of the Mānkīr or the great centre, the greatest king

## Appendix V.

ARAB  
REFERENCES,  
A.D. 851-1360.

Capitals.

Vāla or  
Valabhi.

Kings.

<sup>1</sup> Sir Henry Elliot's History of India, I. 444.

<sup>2</sup> Sir Henry Elliot (History of India, I. 145) identifies Kandhar with Kandadār in north-west Kātlāvad.

<sup>3</sup> Sachau's Original Text, 205.

<sup>4</sup> Sachau's Original Text, 17-91.

<sup>5</sup> Details Above in Dr. Bhagvanlal's History, 96 note 3.

<sup>6</sup> Elliot's History of India, I. 7.

**Appendix V.**

ARAB  
REFERENCES,  
A.D. 851 - 1350.  
Kings.

of India<sup>1</sup> to whom the kings of India bow in their prayers and whose emissaries they honour. He notices that the Balhára favours and honours Musalmáns and allows them to have mosques and assembly mosques. When Al Masúdi was in Cambay the town was ruled by Bāna, the deputy of the Balhára. Al Istakhri (A.D. 951) describes the land from Kanbayah to Samúr (Cheul) as the land of the Balhára of Mankir. In the Konkau were many Musalmáns over whom the Balhára appointed no one but a Musalmán to rule. Ibní Haukal (A.D. 970) describes the Balhára as holding sway over a land in which are several Indian kings.<sup>2</sup> Al Idrisi (A.D. 1100 but quoting Al Jauhari A.D. 950) agrees with Ibní Khurdádbah that Balhára is a title meaning King of Kings. He says the title is hereditary in this country, where when a king ascends the throne he takes the name of his predecessor and transmits it to his heirs.<sup>3</sup>

*Condition.*

That the Arabs found the Ráshtrakútas kind and liberal rulers there is ample evidence. In their territories property was secure,<sup>4</sup> theft or robbery was unknown, commerce was encouraged, foreigners were treated with consideration and respect. The Arabs especially were honoured not only with a marked and delicate regard, but magistrates from among themselves were appointed to adjudicate their disputes according to the Musalmán law.

\* The  
Gurjaras.

The ruler next in importance to the Balhára was the Jurz that is the Gurjjara king. It is remarkable, though natural, that the Arabs should preserve the true name of the rulers of Aulhvala which the three tribe or dynastic names Chápa or Chaura (A.D. 720-956), Solanki or Canluka (A.D. 961-1242), and Vághela (A.D. 1240-1290) should so long have concealed. Sulaimán (A.D. 851) notices that the Jurz king hated Musalmáns while the Balhára king loved Musalmáns. He may not have known what excellent reasons the Gurjaras had for hating the Arab raiders from sea and from Sindh. Nor would it strike him that the main reason why the Balhára fostered the Moslem was the hope of Arab help in his struggles with the Gurjaras.

*Jurz.*

According to the merchant Sulaimán (A.D. 851) the kingdom next after the Balhára's was that of Jurz the Gurjjara king whose territories "consisted of a tongue of land." The king of Jurz maintained a large force his cavalry was the best in India. He was unfriendly to the Arabs. His territories were very rich and abounded in horses and camels. In his realms exchanges were carried on in silver and gold dust of which metals mines were said to be worked.

The king of Jurz was at war with the Balháras as well as with the neighbouring kingdom of Tápak or the Panjab. The details given under Bhīmál page 168 show that Sulaimán's tongue of land, by which he apparently meant either Káthiávád or Gujarát was an imperfect idea of the extent of Gurjjara rule. At the beginning of the tenth century A.D. 916 Sulaimán's editor Abu Zaid describes Kanauj as a large country

<sup>1</sup> Elliot's History of India, I. 22, 21, 25.    <sup>2</sup> Elliot's History of India, I. 31.

<sup>3</sup> Elliot's History of India, I. 16.

<sup>4</sup> Al Masudi Les Prairies D'Or, II. chapter 18 page 85.

<sup>5</sup> Giving an account of the diviners and jugglers of India Abu Zaid says: These observations are especially applicable to Kanauj, a large country forming the empire of Jurz. Abu Zaid in Elliot's History of India, I. 10. References given in the History of Bhīmál show that the Gurjjara power spread not only to Kanauj but to Bengal.

forming the empire of Juzr,<sup>1</sup> a description which the Gurjjara Vatsarāja's success in Bengal about a century before shows not to be impossible. Ibn Khurdādhbih (A.D. 912) ranks the king of Juzr as fourth in importance among Indian kings. According to him "the Tātariya dirhams were in use in the Juzr kingdom." Al Masūdi (A.D. 943) speaks of the Konkān country of the Balhāra as on one side exposed to the attacks of the king of Juzr a monarch rich in men horses and camels. He speaks of the Juzr kingdom bordering on Tāfān apparently the Panjāb and Tāfān as bounded by Rahma<sup>2</sup> apparently Barma and Sūmātra. Ibn Haukal (A.D. 968-976) notices that several kingdoms existed, including the domain of the Silāhāras of the north Konkān within the land of the Balhāra between Kambāyah and Sūmūr<sup>3</sup>. Al Bīrūnī (A.D. 970-1031) uses not Juzr, but Gujarāt<sup>4</sup>. Beyond that is to the south of Gujarāt he places Konkān and Tāna. In Al Bīrūnī's time Nārāyan near Jaipur, the former capital of Gujarāt, had been taken and the inhabitants removed to a town on the frontier.<sup>5</sup> Al Idrīsī (end of the eleventh century really from tenth century materials) ranks the king of Juzr as the fourth and the king of Sāfān or Tāfān as the second in greatness to the Balhāra<sup>6</sup>. In another passage in a list of titular sovereigns Al Idrīsī enters the names of Sāfir (Tāfān) Hazr (Juzr-Juzr) and Dūmī (Rahm)<sup>7</sup>. By the side of Juzr was Tālak (doubtfully the Panjāb) a small state producing the whitest and most beautiful women in India; the king having few soldiers; living at peace with his neighbours and like the Balhāras highly esteeming the Arabs.<sup>8</sup> Ibn Khurdādhbih (A.D. 912) calls Tāman the king next in eminence to the Balhāra.<sup>9</sup> Al Masūdi (A.D. 943) calls Tālak the ruler of a mountainous country like Kashmir<sup>10</sup> with small forces living on friendly terms with neighbouring sovereigns and well disposed to the Moslems<sup>11</sup>. Al Idrīsī (end of eleventh century but materials of the tenth century) notices Sāfān (Tāfān) as the principality that ranks next to the Konkān that is to the Rāshtrakūtas.

**Rahma** or **Buhmi**, according to the merchant Sulaimān (A.D. 851) borders the land of the Balhāras, the Juzr, and Tāfān. The king who was not much respected was at war with both the Juzr and the Balhāra. He had the most numerous army in India and a following of 50,000 elephants when he took the field. Sulaimān notices a cotton fabric made in Rahma so delicate that a dress of it could pass through a signet-ring. The medium of exchange was *cowries* Cyprian moneta shell money. The country produced gold silver and aloes and the whisk of the *sa'mara* or *yāk* *Bes porcephagus bebbhy-tes* of Ibn Khurdādhbih<sup>12</sup> (A.D. 912) places Rahmī as the sixth kingdom. He apparently identified it with Al Rahm or north Sūmātra as he notes that between it and the other kingdoms communication is kept up by ships. He notices that the ruler had five thousand elephants and that cotton cloth and aloes probably the well-known Kumari

## Appendix V.

ARAB  
REFERENCES,  
A.D. 851-1350.

Kings.  
Juzr.

Rahma or  
Ruhmi.

<sup>1</sup> Ibn Khurdādhbih in Elliot's History of India, I. 13.

<sup>2</sup> Al Masūdi in Elliot (History of India), I. 25.

<sup>3</sup> Ibn Haukal in Elliot (History of India), I. 84.

<sup>4</sup> Al Bīrūnī in Elliot (History of India), I. 67.

<sup>5</sup> Al Bīrūnī in Elliot (History of India), I. 59.

<sup>6</sup> Al Idrīsī in Elliot (History of India), I. 76.

<sup>7</sup> Al Idrīsī in Elliot (History of India), I. 86.

<sup>8</sup> The merchant Sulaimān (851 A.D.) in Elliot's History of India, I. 5.

<sup>9</sup> Ibn Khurdādhbih in Elliot (History of India), I. 13.

<sup>10</sup> Al Masūdi in Elliot (History of India), I. 23.

<sup>11</sup> Al Masūdi in Elliot (History of India), I. 25.

<sup>12</sup> Ibn Khurdādhbih in Elliot's History of India, I. 14.

## Appendix V.

ARAB  
REFERENCES,  
A.D. 851-1350.

Kings.  
*Rahma* or  
*Rahm*.

Products

7

or Cambodian aloes, were the staple produce. Al Masûdi (A.D. 913) after stating that former accounts of Râhm's<sup>1</sup> elephants' troops and horses were probably exaggerated, adds that the kingdom of Rahm extends both along the sea and the continent and that it is bounded by an inland state called Kâman (probably Kâmarup that is Assam). He describes the inhabitants as fair and handsome and notices that both men and women had their ears pierced. This description of the people still more the extension of the country both along the sea and along the continent suggests that Masûdi's Al Rahm is a combination of Burma which by dropping the B he has mixed with Al Rahma. Lane identifies Rahm<sup>2</sup> with Sumâtra on the authority of an Account of India and China by two Mahammadan Travellers of the Ninth Century. This identification is supported by Al Masûdi's mention of Râm as one of the islands of the Java group, the kingdom of the Indian Mîhrâj. The absence of reference to Bengal in these accounts agrees with the view that during the ninth century Bengal was under Tibet.

In the middle of the ninth century mines of gold and silver are said to be worked in Gujârât.<sup>3</sup> Abu Zaid (A.D. 916) represents pearls as in great demand. The Tartaryah, or according to Al Masûdi the Tâhîriyah *dinars* of Sindh, fluctuating in price from one and a half to three and a fraction of the Baghdad *dinars*, were the current coin in the Gujârât ports. Emeralds also were imported from Egypt mounted as seals.<sup>4</sup>

Ibn Khurdadbeh<sup>5</sup> (A.D. 912) mentions teakwood and the bamboo as products of Sûdan that is the Konkân Sangan.<sup>6</sup> Al Masûdi (A.D. 913) notes that at the great fair of Multan the people of Sindh and Hind offered Kûmar that is Cambodian aloes-wood of the purest quality worth twenty *dinars* a *man*.<sup>7</sup> Among other articles of trade he mentions an inferior emerald exported from Cambay and Samûr to Makkah,<sup>8</sup> the lance shafts of Brouch,<sup>9</sup> the shoes of Cambay,<sup>10</sup> and the white and handsome maidens of Tâlan<sup>11</sup> who were in great demand in Arab countries. Ibn Haukal (A.D. 968-976) states that the country comprising Fânhal, Sûdan, Samûr, and Kambâyah produced mangoes coconuts lemons and rice in abundance. That honey could be had in great quantities, but no date palms were to be found.<sup>12</sup>

Al Birûni (A.D. 1031) notices that the import of horses from Mekran and the islands of the Persian Gulf was a leading portion of Cambay trade.<sup>13</sup> According to Al Idrîsî (A.D. 1100) the people of Mâghal<sup>14</sup> (Anbilwâra) had many horses and camels.<sup>15</sup> One of the peculiarities of

<sup>1</sup> Al Masûdi in History of India by Sir Henry Elliot, I, 25.

<sup>2</sup> Lane's Notes on his Translation of the Alt Leilah, III, 80.

<sup>3</sup> Al Masûdi's Mûmû (Arabic Text Cairo Edition, I, 221).

<sup>4</sup> The merchant Sulamân (Elliot's History of India), I, 4 and 5.

<sup>5</sup> See page 519 note 8.

<sup>6</sup> Sir Henry Elliot's History of India, I, 11.

<sup>7</sup> Ibn Khurdadbeh in Elliot's History of India, I, 14.

<sup>8</sup> Ibn Khurdadbeh in Elliot's History of India, I, 15.

<sup>9</sup> Al Masûdi (Elliot's History of India), I, 23.

<sup>10</sup> Barbier De Meynard's Arabic Text of Les Prairies D'Or, III, 47-48.

<sup>11</sup> Barbier De Meynard's Arabic Text of Les Prairies D'Or, I, 239.

<sup>12</sup> Barbier De Meynard's Arabic Text of Les Prairies D'Or, I, 253.

<sup>13</sup> Barbier De Meynard's Arabic Text of Les Prairies D'Or, I, 384.

<sup>14</sup> Ibn Haukal (Ashkâl-ul-Bihâl) and Elliot's History of India, I, 39.

<sup>15</sup> Elliot's History of India III, 33.

<sup>16</sup> Mâghal is by some numbered among the cities of India. Al Idrîsî in Elliot, I, 84.

<sup>17</sup> Al Idrîsî in Elliot, I, 79.

the Nahrwāla country was that all journeys were made and all merchandise was carried in bullock waggons. Kambāyah was rich in wheat and rice and its mountains yielded the Indian *kanā* or bamboo. At Sahāra<sup>1</sup> (Sopāra) they fished for pearls and Bāra a small island close to Sndāra produced the coconut and the costus. Sindān according to Al Idrisi produced the cocoa palm, the rattan, and the bamboo. Samūr had many cocoa palms, much lignum (Lawsonia inermis), and a number of aromatic plants.<sup>2</sup> The hills of Thāna yielded the bamboo and *tabāshīr*<sup>3</sup> or bamboo pith. From Samūr according to Al Kāzīmī (A.D. 1236, but from tenth century materials) came albes. Rashid-ud-dīn (A.D. 1310) states that in Kambāyah, Sonmath, Kankan, and Thāna the vines yield twice a year and such is the strength of the soil that cotton-plants grow like willow or plane trees and yield produce for ten years. He refers to the heli leaf, to which he and other Arab writers and physicians ascribe strange virtues as the produce of the whole country of Malabar. The exports from the Gujarāt coasts are said to be sugar (the staple product of Mālwa), *bābūd* that is bezoar, and *kabli* that is turmeric.<sup>4</sup>

According to Ibnī Haukal (A.D. 170) from Kambāya to Samūr the villages lay close to one another and much land was under cultivation. At the end of the eleventh century trade was brisk merchandise from every country finding its way to the ports of Gujarāt whose local products were in turn exported all over the east. The Rāshtrakūta dominion was vast, well-peopled, commercial, and fertile. The people lived mostly on a vegetable diet, rice peas beans haricots and lentils being their daily food.<sup>5</sup> Al Idrisi speaks of certain Hindus eating animals whose deaths had been caused by falls or by being gored,<sup>6</sup> but Al Masūdī states that the higher classes who wore the 'baldric like yellow thread' (the *jamā*) abstained from flesh. According to Ibnī Haukal (A.D. 968-970) the ordinary dress of the kings of Hind was trousers and a tunic.<sup>7</sup> He also notices that between Kambāyah and Samūr the Muslims and infidels wear the same cool fine muslin dress and let their beards grow in the same fashion.<sup>8</sup> During the tenth century on high days the Balhāra wore a crown of gold and a dress of rich stuff. The attendant women were richly clad, wearing rings of gold and silver upon their feet and hands and having their hair in curls.<sup>9</sup> At the close of the Hindu period (A.D. 1300) Rashid-ud-dīn describes Gujarat as a flourishing country with no less than 80,000 villages and hamlets the people happy the soil rich growing in the four seasons; seventy varieties of flowers. Two harvests ripened the husband and the earlier crop refreshed by the dew of the cool season the late crop enriched by a certain rainfall.<sup>10</sup>

\* In their intercourse with Western India nothing struck the Arabs more than the toleration shown to their religion both by chief and peoples.

## Appendix V.

ARAB  
REFERENCES,  
A.D. 851-1350.  
Products.

## Review.

<sup>1</sup> Al Idrisi in Elliot, I. 85.<sup>2</sup> Al Idrisi in Elliot's History of India, I. 85.<sup>3</sup> Al Idrisi in Elliot's History of India, I. 85.<sup>4</sup> Rashid-ud-dīn in Elliot's History of India, I. 67-69.<sup>5</sup> Ibnī Haukal (A.D. 968) in Elliot, I. 39.<sup>6</sup> Al Idrisi (A.D. 968) in Elliot, I. 84 and 87.<sup>7</sup> Al Idrisi speaking of Cambay in Elliot's History of India, I. 84.<sup>8</sup> Al Idrisi in Elliot, I. 85.<sup>9</sup> Al Idrisi in Elliot, I. 84.<sup>10</sup> Al Masūdī in Elliot's History of India, I. 9.<sup>11</sup> Ibnī Haukal in Elliot, I. 35.<sup>12</sup> Ibnī Haukal in Elliot, I. 39.<sup>13</sup> Al Idrisi in Elliot's History of India, I. 88.<sup>14</sup> Rashid-ud-dīn (A.D. 1310) in Elliot's History of India, I. 67. The passage seems to be a quotation from Al Bīrūnī (A.D. 1031).

## Appendix V.

ARAB  
REFERENCES,  
A.D. 851-1350  
Review.

This was specially marked in the Rāshtrakūta towns where besides five use of mosques and Jāma Mosques Musalmān magistrates or *kāzis* were appointed to settle disputes among Musalmāns according to their own laws.<sup>1</sup> Toleration was not peculiar to the Bahāras. Al Bīrūnī records<sup>2</sup> that 'in the ninth century (A.D. 581), when the Hindus recovered Sindan (Sanjān in Kuchh) they spared the assembly mosque where long after the Faithful congregated on Fridays praying for their Kālifāh without hindrance. In the Bahāra country so strongly did the people believe in the power of Islām for which is perhaps more likely so courteous were they that they said that our king enjoys a long life and long reign is solely due to the favour shown by him to the Musalmāns. So far as the merchant Sulamān saw in the ninth century the chief religion in Gūjarāt was Buddhism. He notices that the principles of the religion of China were brought from India and that the Chinese ascribe to the Indians the introduction of Buddhas into their country. Of religious beliefs metempsychoses or re-birth and of religious practices widow-burning or *sati* and self-torture seem to have struck him most. As a rule the dead were burned.<sup>3</sup> Sulamān represents the people of Gūjarāt as steady abstemious and sober abstaining from wine as well as from vinegar, 'not' he adds 'from religious motives but from their disdain of it.' Among their sovereigns the desire of conquest was seldom the cause of war.<sup>4</sup> Abū Zaid (A.D. 916) describes the Brahmins as Hindus devoted to religion and science. Among Brahmins were poets who lived at kings' courts, astronomers, philosophers, diviners, and drawers of omens from the flight of crows.<sup>5</sup> He adds: 'So sure are the people that after death they shall return to life upon the earth, that when a person grows old he begs some one of his family to throw him into the fire or to drown him.'<sup>6</sup> In Abū Zaid's time (A.D. 916) the Hindus did not seclude their women. Even the wives of the kings used to mix freely with men and attend courts and places of public resort unveiled.<sup>7</sup> According to Ibn Khurādādhbih (A.D. 912) India has forty-two religious sects "part of whom believe in God and his Prophet (on whom be peace) and part who deny his mission."<sup>8</sup> Ibn Khurādādhbih (A.D. 912) describes the Hindus as divided into seven classes. Of these the first are Thākarnas<sup>9</sup> or Thākurs men of high caste from whom kings are chosen and to whom men of the other classes render homage, the second are the Bārahmas<sup>10</sup> who abstain from wine and fermented liquors, the third are the Kātariya or Kshatriyas who drink not more than three cups of wine; the fourth are the Sudhāri or Shūdras husbandmen by profession, the fifth are the Basara or Vais̄h artificers and domestics; the sixth Sandaliya or Chandalā menials, and the seventh the 'Lahūd,' whose women adorn themselves and whose men are fond of amusements and games of skill. Both among the people and the kings of Gūjarāt<sup>11</sup> wine

<sup>1</sup> Ibn Haukal in Elliot's History of India, I, 31-38, also Al Kazwini, I, 97.

<sup>2</sup> Sir Henry Elliot's History of India, I, 29.

<sup>3</sup> The merchant Sulamān in Elliot's History of India, I, 7.

<sup>4</sup> The merchant Sulamān in Elliot's History of India, I, 6.

<sup>5</sup> The merchant Sulamān in Elliot's History of India, I, 7.

<sup>6</sup> Abū Zaid in Elliot's History of India, I, 10.

<sup>7</sup> Abū Zaid in Elliot's History of India, I, 9-10.

<sup>8</sup> Abū Zaid in Elliot's History of India, I, 11. <sup>9</sup> Ibn Khurādādhbih in Elliot, I, 17.

<sup>10</sup> See Elliot, I, 76, where Al Idrisi calls the first class 'Sthakara' the word being a transliteration of the Arabic Thākuriyah or Thākurs.

<sup>11</sup> The Arabic plural of the word Barahman

<sup>12</sup> Ibn Khurādādhbih in Elliot's History of India, I, 13-17.

was "unlawful and lawful" that is it was not used though no religious rule forbade its use. According to Al Masûdh (A.D. 913) a general opinion prevailed that India was the earliest home of order and wisdom. The Indians chose as their king the great Brâhman who ruled them for 366 years. His descendants retain the name of Brahman and are honoured as the most illustrious caste. They abstain from the flesh of animals.<sup>1</sup> Hindu kings cannot succeed before the age of forty nor do they appear in public except on certain occasions for the conduct of state affairs. Royalty and all the high offices of state<sup>2</sup> are limited to the descendants of one family. The Hindus strongly disapprove of the use of wine both in themselves, and in others not from any religious objection but on account of its intoxicating and reason-blinding quality. Al Birûnî (A.D. 974-1031) quoted by Rashîd-ud-din (A.D. 1310) states that the people of Gûjarât are idolaters and notices the great penances-pilgrimages to Somnath details of which have already been given.<sup>3</sup> Al Idrisî (end of the eleventh century) closely follows Ibn Khuradâdh's (c. 912) division of the people of India. The chief exception is that he represents the second class, the Brâhmanas, as wearing the skins of tigers and going about staff in hand collecting crowds and from morn till eve proclaiming to their hearers the glory and power of God. He makes out that the Kâstûras or Kshatriyas are able to drink three *ratl* (a *ratl* being a pound Troy) of wine and are allowed to marry Brahman women. The Sabdâhyân Chandal women, he says, are noted for beauty. Of the forty-two sects he enumerates worshippers of trees and adoration of serpents, which they keep in stables and feed as well as they can, deeming it to be a meritorious work. He says that the inhabitants of Kândâya are Buddhists (idolaters)<sup>4</sup> and that the Balhâm also worships the idol Badlha.<sup>5</sup> The Indians says Al Idrisî (end of the eleventh century) are naturally inclined to justice and in their actions never depart from it. Their reputation for good faith, honesty, and fidelity to their engagements brings strangers flocking to their country and aids its prosperity. In illustration of the peaceable disposition of the Hindus, he quotes the ancient practice of *dabû* or coining in the name of the king, a coin which is still in vogue in some native states. When a man has a rightful claim he draws a circle on the ground and asks his debtor to step into the circle in the name of the king. The debtor never fails to step in nor does he ever leave the circle without paying his debts. Al Idrisî describes the people of Nahrwâra as having so high a respect for oxen that when an ox dies they bury it. "When one disabled by age or if unable to work they provide the oxen with food without exacting any return."<sup>6</sup>

## Appendix V.

ARAB  
REFERENCES,  
A.D. 851-1350  
Review.

<sup>1</sup> Text Les Paires D'Or, I, 149-151 and Elliot's History of India, I, 19.

<sup>2</sup> Arabic Text Les Propres D'Or, I, 149-151, and Elliot's History of India, I, 20.

<sup>3</sup> Al Masûdh's Paires D'Or, I, 169 and Elliot's History of India, I, 20.

<sup>4</sup> Rashîd-ud-din from Al Birûnî in Elliot's History of India, I, 67-68.

<sup>5</sup> Al Idrisî in Elliot (History of India), I, 76.

<sup>6</sup> Al Idrisî in Elliot (History of India), I, 85.

<sup>7</sup> Al Idrisî in Elliot (History of India), I, 87.

<sup>8</sup> See Henry Elliot's History of India, I, 88.

<sup>9</sup> Al Idrisî in Elliot (History of India), I, 88.

## APPENDIX VI.

### WESTERN INDIA AS KNOWN TO THE GREEKS AND ROMANS.

**Appendix VI.**  
**EARLY GREEKS**  
**AND ROMANS.**  
*Ktesias.*

**Herodotos** and **Hekataios**, the earliest Greek writers who make mention of India, give no information in regard to Western India in particular.

**Ktesias** (c. 400 B.C.) learned in Persia that a race of Pygmies lived in India in the neighbourhood of the silver mines, which Lassen places near Udaipur (Merwar). From the description of these Pygmies (Photios, *Bibl.* LXXII 11-12) it is evident that they represent the Bhils. Ktesias also mentions (Photios *Bibl.* LXXII 8) that there is a place in an uninhabited region fifteen days from Mount Sardons, where they venerate the sun and moon and where for thirty-day days in each year the sun mounts his heat for the comfort of his worshippers. This place must apparently have been somewhere in Marwar, and perhaps Mount Abu is the place referred to.

*Aleza*

**Alexander** (B.C. 326-25) did not reach Gujarât, and his companions have nothing to tell of this part of the country. It is otherwise with

*Megasthenes.*

**Megasthenes** (c. 300 B.C.) who resided with Chandragupta as the ambassador of Seleukos Nikator and wrote an account of India in four books, of which considerable fragments are preserved, chiefly by Strabo, Pliny, and Arrian. His general account of the manners of the Indians relates chiefly to those of northern India, of whom he had personal knowledge. But he also gave a geographical description of India, for Arrian informs us (*Ibid.* VII) that he gave the total number of Indian tribes as 118, and Pliny (VI. 17ff) does in fact enumerate about 90, to whom may be added some seven or eight more mentioned by Arrian. It is true that Pliny does not distinctly state that he takes his geographical details from Megasthenes, and that he quotes Seneca as having written a book on India. But Seneca also (Pliny, VI. 17) gave the number of the tribes as 118 in which he must have followed Megasthenes. Further, Pliny says (*ibid.*) that accounts of the military forces of each nation were given by writers such as Megasthenes and Dionysius who stayed with Indian kings; and as he does not mention Dionysius in his list of authorities for his Book VI, it follows that it was from Megasthenes that he drew his accounts of the forces of the Gangaridæ, Mologalingæ, Andaræ, Prasæ, Megallæ, Asmagæ, Orabæ, Smaratatæ, Antomulæ, Charinæ, and Pandæ (VI. 19), names which, as will be shown below, betray a knowledge of all parts of India. It is a fair inference that the remaining names mentioned by Pliny were taken by him from Megasthenes, perhaps through the medium of Seneca's work. The corruption of Pliny's text

and the fact that Megasthenes learnt the tribal names in their Prakrit forms, make it extremely difficult to identify many of the races referred to.

That part of Pliny's account of India which may with some certainty be traced back to Megasthenes begins with a statement of the stages of the royal road from the Hypasis (Bias) to Palibothra (Patna) (Nat. Hist. VI 17). The next chapter gives an account of the Ganges and its tributaries and mentions the Gangaridai of Kalunga with their capital Porthis as the most distant nation on its banks. In the 19th chapter, after an account of the Jyces of the Gangaridai, Pliny gives a list of thirteen tribes of which the only ones that can be said to be satisfactorily identified are Megagalingi (the three Calingae - Caldwell, *Drav. Gr.*), Melundae (compare Mount Mahendya of Varaha Mihira Br. S. XIV) and Thalata (McCrindle reads Talueta and identifies with the Tomralipakas of Tamilk on the lower Ganges). He then mentions the Andario (Andhrai of Tohingana) with thirty cities 100,000 foot 2,000 horse and 1,000 elephants. He then digresses to speak of the Dardae (Dards of the Upper Indus) as rich in gold and the Scae (of Mewar, Lassen) in silver, and next introduces the Persi (Praevae) of Palibothra (Pataliputra) as the most famous and powerful of all the tribes, having 600,000 foot 30,000 horse and 8,000 elephants. Inland from these he names the Megades (Munda of Singhbhum) and Sauri (Sauras of Central India) among whom is Mount Mahens (Mahendra Malez). Then after some account of the Iamnes (Yamuna) running between Methora (Mathura) and Chrysobota (McCrindle reads Chrysobota - Arrian Ind. VIII. Kleisobota - Kusthagura ?) he turns to the Indus, of some of whose nineteen tributaries he gives some account in chapter 20. He then digresses to give an account of the coast of India, starting from the mouth of the Ganges, whence to Point Calingon (Point Godavari) and the city of Dardaguda (Cunningham's Raja Mahendri, but more probably the Dhanakataka or Dhenkakata of the Western cave inscriptions) he reckons 625 miles. The distance thence to Tropina (Tropinatara near Kochin according to Burgess) is 1225 miles. Next at a distance of 750 miles is the cape of Perimula, where is the most famous mart of India. Further on in the same chapter is mentioned a city named Antonula on the sea shore among the Arakastae (or Salabastae and Oenae, McCrindle) a noble mart where five rivers together flow into the sea. There can hardly be a doubt that the two places are the same, the two names being taken from different authorities, and that the place meant is Chennula or Chind (Ptolemy's Smaula) the five rivers being those that flow into Bombay Harbour northward of Chind. The distance from Perimula to the Island of Patula in the Indus is 350 miles. Pliny next enumerates as hill tribes between the Indus and Jambou shut in a ring of mountains and deserts for a space of 625 miles, the Caei (the Kekoi of Arr. Ind. IV. and Kekayas of the Ptolemaei, about the head waters of the Sutlej), the Cetriboi of the woods (..... Vauri?), the Megallae (Mekalas) with 500 elephants and unknown numbers of horse and foot, the Chrysei (Karusha) Parasangae (Parasava, corrupted by the likeness of its first three syllables to the word *παρσαγγα*), the Asmagi (Asmaka of Varaha Mihira) with 30,000 foot 300 elephants and 800 horse. These are shut in by the Indus and surrounded by a circle of mountains and deserts for 625 miles. Next come the Daei and Sauri and then deserts again for 187 miles. Whether these are or are not correctly identified with the Dhaes and Sauri of Sindh, they must be placed somewhere to the north of the Ran. Below them come five kingless tribes living in the hills along the sea-

## Appendix VI.

### EARLY GREEKS AND ROMANS.

#### *Megasthenes.*

## Appendix VI

EARLY GREEKS  
AND ROMANS.*Megasthenes.*

coast—the Mallecorno Singhar, Marolha, Rarupga, and Moruni—none of whom are satisfactorily identified, but who may be placed in Kachh. Next follow the Naraca enclosed by Mount Capitala (Abu) the highest mountain in India on the other side of which are mines of gold and silver. The identification of Capitala with Abu is probable enough, but the name given to the mountain must be connected with the Kapashthala of the *Puranas*, who have given their name to one of the recensions of the Yajur Veda, though Kanthal, their modern representative lies far away from Abu in the Karnal district of the Panjab, and African places his *καρπασθολοι* (In I. IV) about the head waters of the Hydrates (Ravi). After Capitala and the Naraca come the Orata with but ten elephants but numerous infantry. This must be the Aparantakas of the inscriptions and *puranas*, Megasthenes having learnt the name in a Prakrit form (Avarata Orata). The name of the next tribe who have no elephants but horse and foot only is commonly read Sraatarata (Nobbe) but the preferable reading is Vartata (McCrimble) which when corrected to Varelata represents Vimalatta, the sixth of the seven Konkans in the pirame lists (Wilson As. Res. XV. 17), which occupied the centre of the Thian district and the country of the wild tribe of the Vahis. Next are the Ododagors, whose name is connected with the *odumbura* ficus glomerata tree and who are not the Andumbari Salvys of Pannu (IV. i. 173) but must be placed in Southern Thana. Next come the Arabastre Orata (so read for Arabastre Thence of Nobbe, and Salabastre Horatio of McCrimble) or Arabastra division of the Orata or Konkanis. Arabastra may be connected with the Araya of Vimala-Mihira's South-Western Division (Bis. S. XIV. 17) where they are mentioned along with Barbari (the seventh or northernmost Konkan). This tribe had a fine city in a marsh lined by crocodiles and also the great mart of Automile (Chen) at the confluence of five rivers, and the king had 1600 elephants 150,000 foot and 5000 horse, and must therefore have held a large part of the Dakhan as well as of the seacoast. Next to this kingdom is that of the Charana, whose forces are small, and next to them the Pandia (Pandya of Travancor) with 30 cities 150,000 foot and 500 elephants. Next follows a list of thirteen tribes some of which St. Martin has identified with modern Rajput tribes about the Indus, because the last name of the thirteen is Orosini, who reach to the island of Patala and may be confidently identified with the Saurashtia of Kârnâvada. We must however assume that Megasthenes after naming the tribes of the west coast enumerates the inland tribes of the Dakhan until he arrives at the point from which he started. But the only identification that seems plausible is that of the Deranga with the Telingus or Telugus. Next to the Orosine follows a list of tribes on the east of the Indus from south to north—the Mathon (compare Mânthava, a Bahika town Pân. IV. ii. 117), Bohing (Bhânungi, a Salya tribe Pân. IV. i. 173), Gallatalata (perhaps a corruption of Talakhal, another Salya tribe, *ib.*), Durnu, Megari, Arabae, Mesae (Matsya of Jaipur?), Abu, Suri, (v. l. Abhis Uri), Sike and then deserts for 250 miles. Next come three more tribes and then again deserts, then four or five (according to the reading) more tribes and the Asini whose capital is Bucephala (Julapur) (Cunningham Anc. Geog. 177). Megasthenes then gives two mountain tribes and ten beyond the Indus including the Orsi (Urasa) Taxila (Taksilasilâ) and Peneolitw (people of Pushkalavati). Of the work of Dêmachos, who went on an embassy to Allitrochadès (Bindusâra) son of Candragupta, nothing is known except that it was in two books and was reckoned the most untrustworthy of all accounts of India (Strabo. II. i. 9).

**Ptolemy II. Philadelphos** (died 217 B.C.) interested himself in the trade with India and opened a caravan road from Koptos on the Nile to Berekê on the Red Sea (Strabo, XV. ii. 15) and for centuries the Indian trade resorted either to this port or to the neighbouring Myos Hormos. He also sent to India (apparently to Asoka) an envoy named Dionysos, who is said by Pliny (VI. 17) to have written an account of things Indian of which no certain fragments appear to remain. But we know from the fragments of

**Agatharkhides** (born c. 250 A.D.) who wrote in old age an account of the Red Sea on which we have considerable extracts in Diodoros (III. 12-18) and Photios (Müller's Geogr. Gr. Min. I. 1111), states that in his time the Indian trade with Patala (Patala) was in the hands of the Sabaians of Yemen. (Müller I. 191.) In fact it was not until the voyages of Eudoxos (see below) that any direct trade sprang up between India and Egypt. The mention of Patala as the mart resorted to by the Arabs shows that we are still in Pliny's first period (see below).

**The Baktrian Greeks** extended their power into India after the fall of the Maurya empire (c. 180 B.C.) their leader being Demetrios son of Euthydemos, whose conquests are related to by Justin (XLII. 6) and Strabo (XI. ii. 17). But the most extensive conquests to the east and south were made by Menandros (c. 110 B.C.) who advanced to the Jumna and conquered the whole coast from Pattalène (lower Sindh) to the kingdoms of Sakastros (Sakastara) and Sigettis (Phrygia Sigetis?) (Strabo, XI. ii. 1). These statements of Strabo are confirmed by the author of the Periplus (c. 250 A.D.) who says that in his time *drakhamai* with Greek inscriptions of Menandros and Apollodotos were still current at Barygaza (Per. 47). Apollodotos is now generally thought to have been the successor of Menandros (c. 100 B.C.) (Brit. Museum Cat. of Bactrian Coins page xxxiii.). Plutarch (Rep. Ger. 170c.) tells us that Menandros' rule was so mild, that on his death his towns disputed the possession of his riches and finally divided them.

**Eudoxos of Cyzicus** (c. 137 B.C.) made in company with others two very successful voyages to India, in the first of which the company were guided by an Indian who had been shipwrecked on the Egyptian coast. Strabo (II. iii. 1), in quoting the story of his doings from Pseudonimos, lays more stress upon his attempt to circumnavigate Africa than upon these two Indian voyages, but they are of very great importance as the beginnings of the direct trade with India.

**The Geographers** down to Ptolemy drew their knowledge of India almost entirely from the works of Megasthenes and of the companions of Alexander. Among them Eratosthenes (c. 275-194 B.C.), the founder of scientific geography, deserves mention as having first given wide currency to the notion that the width of India from west to east was greater than its length from north to south, an error which lies at the root of Ptolemy's distortion of the map. Eratosthenes' critic Hipparkhos (c. 130 B.C.) on this point followed the more correct account of Megasthenes, and is otherwise notable as the first to make use of astronomy for the determination of the geographical position of places.

**Strabo** (c. 63 B.C.-23 A.D.) drew his knowledge of India, like his predecessors, chiefly from Megasthenes and from Alexander's followers, but adds (XV. i. 72) on the authority of Nikolaos of Oikiasens (tutor to the children of Antony and Cleopatra, and envoy of Herod) (an account of three Indian envoys from a certain king Páros to Augustus (ab. A.D. 14),

## Appendix VI.

### EARLY GREEKS AND ROMANS.

#### *Ptolemy II.*

#### *Agatharkhides.*

#### *The Baktrian Greeks.*

#### *Eudoxos of Cyzicus.*

#### *Eratosthenes.*

#### *Strabo.*

## EARLY GREEKS AND ROMANS.

### Appendix VI.

#### EARLY GREEKS AND ROMANS.

##### *Strabo*

who brought presents consisting of an armless man, snakes, a huge turtle and a huge partridge, with a letter in Greek written on parchment offering free passage and traffic through his dominions to the emperor's subjects. With these envoys came a certain Zarnanokhêgas (*Śraṇuñā-cārya* Lassen) from Barygese (Broach, the earliest mention of the name) who afterwards burnt himself at Athens "according to the ancestral custom of the Indians." The fact that the embassy came from Broach and passed through Antioch shows that they took the route by the Persian Gulf, which long remained one of the chief lines of trade (Perc. chap. 36). If the embassy was not a purely commercial specification on the part of merchants of Broach, it is hard to see how king Poros who had 600 under-kings, can be other than the Indo-Skythian Kozolakadaphus, who held Poros' old kingdom as well as much other territory in North-West India. This if correct would show that as early as the beginning of our era the Indo-Skythian power reached as far south as Broach. The fact that the embassy took the Persian Gulf route and that their object was to open commercial relations with the Roman empire seems to show that at this period there was no direct trade between Broach and the Egyptian ports of the Red Sea. Strabo however mentions that in his time Arabian and Indian wares were carried on canals from Myos Hormos (near Râs Abu Somer) on the Red Sea to Koptos on the Nile (XVII. i. 15 and XVI. iv. 24) and dilates upon the increase of the Indian trade since the days of the Ptolemies when not so many as twenty ships dared pass through the Red Sea "to peer out of the Straits," whereas in his time whole fleets of as many as 120 vessels voyaged to India and the headlands of Ethiopia from Myos Hormos (II. v. 12 and XV. i. 13). It would seem that we have here to do with Pliny's second period of Indian trade, when Sigerus (probably Janjira) was the goal of the Egyptian shipmasters (see below). Strabo learnt these particulars during his stay in Egypt with Aelius Gallus, but they were unknown to his contemporary Diodoros who drew his account of India entirely from Megasthenes (Diod. II. 31-42) and had no knowledge of the East beyond the stories told by Jamboulas a person of uncertain date of an island in the Indian Archipelago (Bah, according to Lassen) (Diod. II. 57-60). Pomponius Mela (i.n. 43) also had no recent information as regards India.

##### *Pliny*

**Pliny** (A.D. 23-79) who published his Natural History in A.D. 77 gives a fairly full account of India, chiefly drawn from Megasthenes (see above). He also gives two valuable pieces of contemporary information:

(i) An account of Ceylon (Taprobane) to which a freedman of Annus Plaucanus, former of the Red Sea tribute, was carried by stress of weather in the reign of Claudius (A.D. 41-54). On his return the king sent to the emperor four envoys, headed by one Rachus (VI. 22).

(ii) An account of the voyage from Alexandria to India by a course which had only lately been made known (VI. 23). Pliny divides the history of navigation from the time of Nearchus to his own age into three periods:

(a) the period of sailing from Syagrus (Râs Fartak) in Arabia to Patalê (Indus delta) by the south-west wind called Hippalus, 1332 miles;

(b) the period of sailing from Syagrus (Râs Fartak) to Sigerus (*Ptol.* Milizôgyris, *Peripl.* Mohzeigura, probably Janjira, and perhaps the same as Strabo's Sigertis);

(c) the modern period, when traffic went on from Alexandria to Koptos up the Nile, and thence by camels across the desert to Borenice (in Foul Bay) 257 miles. Thence the merchants start in the middle of

summer before the rising of the Dogstar and in thirty days reach Okelis (Ghulla) or Cane (Hiss Ghorah), the former port being most frequented by the Indian trade. From Okelis it is a forty days' voyage to Muzis (Muyyiri, Kranganur) which is dangerous on account of the neighbouring pirates of Nitrus (Mangalore) and inconvenient by reason of the distance of the roads from the shore. Another better port is Beure (Kallada, Yale) belonging to the tribe Nekyndon (*Plol.* Melkynda, *Peripl.* Nelkynda) of the kingdom of Pandion (Pandyas) whose capital is Modura (Madura). Here pepper is brought in canoes from Cottomara (Kadattanadu). The ships return to the Red Sea in December or January.

It is clear that the modern improvement in navigation on which Pliny lays so much stress consisted, not in making use of the monsoon wind, but in striking straight across the Indian ocean to the Malabar coast. The fact that the ships which took this course carried a guard of archers in Pliny's time, but not in that of the *Periplus*, is another indication that the direct route to Malabar was new and unfamiliar in the first century A.D. The name Hippalus given to the monsoon wind will be discussed below in dealing with the *Periplus*.

Dionysios Periegetes who has lately been proved to have written under Hadrian (A.D. 117-138) (*Christ's Greek Literature* (Gesch. page 507)) gives a very superficial description of India but has a valuable notice of the Southern Skythians who live along the river Indus to the east of the Gedrosi (l. 1087-88).

Klaudios Ptolemaios of Alexandria lived according to Strabo under Marcus Annius Antoninus (A.D. 161-180). He compiled his account of India as part of a geographical description of the then known world. He drew much of his materials from Marmos of Tyre, whose work is lost, but who must have written about A.D. 130. Ptolemy (or Marmos before him) had a very wide knowledge of India, drawn partly from the relations of shipmasters and traders and partly from Indian lists similar to those of the *Panduas* but drawn up in Prakrit. He seems to have made little if any use of Megasthenes and the companions of Alexander. But his map of India is distorted by the erroneous idea, which he took from Eratosthenes, that the width of India from west to east greatly exceeded its length from north to south. Ptolemy begins his description of India with the first chapter of his seventh book, which deals with India within the Ganges. He gives first the names of rivers, countries, cities, and capes along the whole coast of India from the westernmost mouth of the Indus to the easternmost mouth of the Ganges. He next mentions in detail the mountains and the rivers with their tributaries, and then proceeds to enumerate the various nations of India and the cities belonging to each, beginning with the north-west and working southwards and he finally gives a list of the islands lying off the coast. In dealing with his account of western India it will be convenient to notice together the cities of each nation which he mentions separately under the heads of coast and inland towns.

He gives the name of Indo-Skythia to the whole country on both sides of the lower course of the Indus from its junction with the Koa (Kábul river), and gives its three divisions as Patalênê (lower Sindh) Abiria (read Sabiria, that is Sanvira or upper Sindh and Multan) and Surastrênê (Surâshtra or Kâthiâvâda). We have seen that Dionysios knew the southern Skythians of the Indus, and we shall meet with them again in the *Periplus* (chapter 39ff).

## Appendix VI.

EARLY GREEKS  
AND ROMANS.

• Pliny.

Dionysios  
Periegetes.

Klaudios  
Ptolemaios.

## Appendix VI.

EARLY GREEKS  
AND ROMANS.*Klaudius  
Ptolemaeus.*

He enumerates seven mouths of the Indus, but the river is so constantly changing its course that it is hopeless to expect to identify all the names given by him (Sagapu Sinthôn, Khariphron, Sipara, Sibalacessa and Lônbaré) with the existing channels. Only it may be noted that Sinthôn preserves the Indian name of the river (Sindhu) and that the easternmost mouth (Lônbaré) probably represents both the present Kori or Lari and the Lûni river of Marwar a fact which goes some way to explain why Ptolemy had no idea of the existence of Karachi, though he knows the Ran as the gulf of Nanthi. Hence he misplaces Surastrênê (Suraštra or Kathiāvāda) in the Indus delta instead of south of the Ran. Ptolemy enumerates a group of five towns in the north-western part of Indo-Skythia (Kohat, Bannu, and Dery Ismail Khan) of which Cunningham (Anc. Geog. pages 81ff) has identified Banagara with Bannu, and Andrapama with Daraban, while the sites of Artoanta, Sabana and Kodrama are unknown. Ptolemy next gives a list of twelve towns along the western bank of the Indus to the sea. Of these Embolma has been identified by Cunningham (Anc. Geog. page 52) with Amb sixty miles above Attok, and Pasipeda is identified by St. Martin with the Besmail of the Arab geographers and placed near Mithankot at the junction of the Chenab with the Indus. Sousikama, which comes next in the list to Pasipeda, is generally thought to be a corruption of Monsikama, and is placed by the latest authority (General Haig, *The Indus Delta Country* page 130) in Bahawalpur, though Cunningham (Anc. Geog. page 257) puts it at Alor, which is somewhat more in accordance with Ptolemy's distances. Kôlaka the most southerly town of the list, cannot well be the Krokala of Arrian (Karachi) as McCrindle supposes, for Ptolemy puts it nearly a degree north of the western mouth of the Indus.

The two great towns of the delta which Ptolemy next mentions are placed by General Haig, Patala at a point thirty-five miles south-east of Haidarâbâd (*op cit* page 19) and Barbarea near Shah Bandar (*op cit* page 31). Barbarea is mentioned again in the *Periplus* (chapter 38) under the name of Barbarikon. Ptolemy gives the names of nine towns on the left bank of the Indus from the confluence to the sea, but very few of them can be satisfactorily identified. Panasa can only be Osampur (St. Martin) on Fliellen's principles. Boudana must represent the Budhîya of the Arabs, though it is on the wrong side of the river (see Haig, *op cit* page 57ff). Naagramma may with Yule be placed at Nanshalro. Kathigara cannot be Aror (McCrindle), if that place represents Sousikama. Bîngara is commonly thought to be a corrupt reading of Minuagara (compare *Piri plus* chapter 38). Haig (*op cit* page 32 note 47) refers to the *Tahfatul Kirâm* as mentioning a Minuagar in pargana Shâhulâdpur (north-east of Haidarâbâd). Paralali, Sydhos, and Epitansa have not been identified, but must be looked for either in Haidarâbâd or in Thur and Pârkar. Xonna may with Yule be identified with Siwana in the bend of the Lûni and gives another indication that Ptolemy confounded the Lûni with the eastern mouth of the Indus.

On the coast of Surastrênê (Kathiāvāda) Ptolemy mentions, first, the island of Barukê (Dvârakâ Bêt): then the city Barduxêma which must be Porbandar (Yule), in front of the Barada hills: then the village of Surastra, which perhaps represents Verâval, though it is placed too far north. Surastra cannot well be Junâgad (Lassen) which is not on the coast and in Ptolemy's time was not a village, but a city, though it is certainly strange that Ptolemy does not anywhere mention it. Further south Ptolemy places the mart of Monoglôsson (Mafgrol). The eastern

boundary of the coast of Indo-Skythia seems to have been the mouth of the Mōphis (Muh) Ptolemy's account of Indo-Skythia may be completed by mentioning the list of places which he puts to the east of the Indus (i.e. the Lāni) and at some distance from it.

These are: Xodrakê, which has not been identified, but which must be placed somewhere in Mewâr, perhaps at the old city of Pâr, seventy-two miles north-east of Udaipur, or possibly at the old city of Ahar, two miles from Udaipur itself (Tod's Rajasthan, I 677-78).

Sarwama, which is marked in Ptolemy's map at the head-waters of the Muih in the Apokopa mountains (Aravallis), must be identified with Sarwan about ten miles north-west of Ratlām. There is also a place called Sarwama close to Nimach, which Ptolemy may have confused with Sarwan.

Auxomnis, which St. Martin identifies with Sîm and Yule with Ajmer, but neither place suits the distance and direction from Sarwan. If Ptolemy, as above suggested, confused Sarwan and Sarwama, Auxomnis may be Ahar near Udaipur, Pâr being then Xodrakê. Otherwise Auxomnis may be Idar. The question can only be settled by more exact knowledge of the age of Ahar and of Idar. Orbadagan may provisionally with Yule be placed at Abu.

Asinda must be looked for near Sadhpur, though it cannot with St. Martin be identified with that place. Perhaps Vadnagar (formerly Anandapura and a very old town) may be its modern representative.

Theophilus may be Devahya (Yule) or Thau (Burgess) in north-east Kathiavâda.

Aslakapra is admitted to be Hastakavapra or Hâthab near Bhâvnagar (Bühler).

Larikê is described by Ptolemy next after Indo-Skythia on his way down the West Coast. The northern limit of its coast was the mouth of the river Mophis (Muh). Its name is the Latin of *portus* and inscriptions. Ptolemy mentions as on its coast the village of Pakidare, which may be a misreading for Kapidare and represent Kavi (Kapika of inscriptions) a holy place just south of the Muh. Next comes Cape Malak, which Ptolemy both in his text and in his map includes in Larikê though there is no prominent headland in a suitable position on the east side of the Gulf of Cambay. As he puts it 2½ degrees west of Borech, it may probably be identified with Gôpnâj Point in Kathiavâda on the other side of the gulf (the Pâpkê of the Periplus), its name for it surviving in the neighbouring shoals known as the Malak banks. It is in agreement with this that Ptolemy puts the mouth of the river Narmados (Narmada) to the north of Cape Malak. South of the river is Kammônê which may be identified with the Kammijja or Karmancyn of inscriptions, that is with Kamlej on the Tapti above Surat. It has been supposed to be the Kammônê of the Periplus (chapter 43), which was the village opposite to the reef called Hêronê on the right (east) of the gulf of Barygaza. But it is perhaps best to separate the two and to identify Kammônê with Kim, north of Olpâd. The next town mentioned is Nonsaripa, which should probably be read Nonsarika, being the Navasârikâ of inscriptions and the modern Nausârî. The most southerly town of Larikê is Poulipoula, which has been identified with Phulpâdâ or old Surat, but is too far south. Bilimora is perhaps the most likely position for it, though the names do not correspond (unless Pouli is the Dravidian *Puli* or *poli* = a tiger, afterwards replaced by *Bili* = a cat). Ptolemy begins his list of the inland cities of Larikê with Agrinagara, which may with Yule be identified with

## Appendix VI.

EARLY GREEKS  
AND ROMANS.

Klaudios  
Ptolemaios.

## Appendix VI.

EARLY GREEKS  
AND ROMANS.*Klaudios  
Ptolemios.*

Âgar, thirty-five miles north-east of Ujjain, and the Âkara of inscriptions. The next town is Sripadla, which has not been identified, but should be looked for about thirty miles to the south-east of Agar, not far from Shahjahanpur. The modern name would probably be Shrol. Bannagomra must be identified, not with Pâwangad (Yule), but with Hsien Tsang's "city of the Brâhmanas" (Beal, Si-yu-ki, II. 262), 206 li (about 33 miles) to the north-west of the capital of Mâlava in his time. The distance and direction bring us nearly to Jaora. Sazantion and Zerogerei have not been satisfactorily identified but may provisionally be placed at Ratlâni and Badnawar respectively, or Zêrogerci may be Dhâr as Yule suggested. Ozânê the capital of Tistandês is Ujjain the capital of the Kshatriya Çashtan who reigned c. 130 A.D. His kingdom included Western Mâlwa, West Khandesh, and the whole of Gujârât south of the Mahî. His grandson Rudrakâman (A.D. 150) tells us in his Guear inscription (I A VII. 259) that his own kingdom included also Mârwar Sindh and the lower Panjâb. Next to Ujjain Ptolemy mentions Munnâgara, which must have been somewhere near Manpur. Then we come to Tiatoma or Chandor (Yule) on the ridge which separates Khandesh from the valley of the Godâvari, and finally on that river itself Nâsika the modern Nasik. It is very doubtful whether Nâsika at any time formed part of the dominions of Çashtana, since we know from the inscriptions in the Nâsika caves that the Kshatriyas were driven out of that part of the country by Gautamîputra Satakarni, the father of Ptolemy's contemporary Pulmâyî. Ptolemy probably found Nâsika mentioned in one of his lists as on a road leading from Ujjain southwards and he concluded that they belonged to the same kingdom.

*Ariakê* of the Sadinoi included the coast of the Konkanas far south as Baktipatna (near Mahād) and the Deccan between the Godavari and the Krishna. The name occurs in Varaha Mihira's *Bhât* Samhita XIV in the form Âryaka. The tribal name Sadinoi is less easy to explain. The suggested connection with the word *Sādhanā* as meaning an agent (Lassen) and its application to the Kshatriyas of Gujârât, are not tenable. The only authority for this meaning of *Sādhanā* is Wilson's Sanskrit Dictionary, and at this time it is certain that Ariakê belonged, not to the Kshatriyas of Gujârât, but to the Satakarnis of Puthan on the Godâvari. Bhândarkar's identification of the Sadinoi with Varaha Mihira's *Śāntikas* seems also somewhat unsatisfactory. Ptolemy's name may possibly be a corruption of Satakarni or Sātavāhana. The coast towns of this region were Soupara (Suparā near Bassem), south of which Ptolemy places the river Goaris (Vaitarânî), Doungâ (perhaps Dugâd ten miles north of Bhivndi) south of which is the Bênda river (Bhivndi Creek), Smyllê, a port and a cape, the Automala and Perminla of Pliny and the modern Chenl (Chemnh); Milizêgyris an island, the same as the Mehzôgara of the Periplus and (probably) as the Sigerus of Pliny and the modern Janjira; Hippokonra, either Ghodêgâon or Kudâ (Yule) in Kolâhâ district; Baktipatna, probably the Palaiptmai of the Periplus and the same as Pal near Mahād.

The inland dominions of the Sadinoi were much more extensive than their coast line. Ptolemy gives two lists of cities, one of those lying to the west (i. e. north) of the Bênda, whose course in the Deccan represents the Bhimâ river, and the other of those between the Bênda and the Pseudostômos (here the Mâlprabhâ and Krishna or possibly the Tungabhadra with its tributaries). The most easterly towns in the first list, Malippala and Sarisabis, are not satisfactorily identified, but must be looked for in the Nizâm's country to the south-east of Hailârâhâd. Next comes Tagara mentioned in the Periplus (chapter 51) as ten days east from Paithan, and

therefore about the latitude of Kullbarga, with which it is identified by Yule. The distance and direction make its identification with Deagiri (Wilford and others), Junnar (Bhagwanlal), or Kolhāpur (Fleet) impossible. The best suggestion hitherto made is that it is Dārur or Dhārur (Bhāpālākar), but Dārur in the Bhār district is too far north, so Dhārur fifty miles west of Haidarābād must be taken as the most likely site. Next to Tagara Ptolemy mentions Baitāma, which is the Paithana of the Periplus and the modern Paithan on the Godāvari. It is called by our author the capital of Sinoptolemyos, who is the Śrī-Pulumāyi of the Nāsik cave inscriptions. Next to Baitāma comes Deopadi, which may safely be identified with the modern Deoli in the suburbs of Ahmednagar. Gaimūba, the next stage, must be placed somewhere on the line between Ahmednagar and Junnar, which later ancient town as to be identified with Ptolemy's Omēnōgōra, although this name is not easy to explain.

The second list of towns in Ariakē begins with Nagaronris (Nagarpur) which probably represents Poona which even then must have been a place of importance being at the head of the great road down the Bhorghat. Tabasō (compare Varaha Mihira's Tapasasramāḥ and Ptolemy's own Tabason) may be the holy city of Pandharpur. Indē has retained its ancient name (Indi in the north of the Bijapur district). Next follows Turpangulida (Tikota in the Kurundwād State ?) and then Hippokoura, the capital of Paleokmos. Dr. Bhandārkar has identified this king with the Vihyāyākūra of coins found in the Kolhapur state. His capital may possibly be Hippargi in the Sindgi taluka of the Bijapur district. Sonbottion, the next town on Ptolemy's list, is not identifiable, but the name which follows, Siemalaga, must be Simal in the Bijapur taluka of the same district.

Kalligeris may be identified not with Kaulhagiri (McCordle) but with Galgah at the crossing of the Kṛṣṇa and Modogontha is not Mūdgol (McCordle) but Madhol on the Ghatprabhā. Petrigada should probably read Penengala, and would then represent the old town of Pannigala or Hongal in the Dharyad district. The last name on the list is Bannomasei, which is Vannavāsi, about ten miles from Sasi in Kanara, a very old town where a separate branch of the Śātakarnis once ruled.

*The Pirate Coast* is the next division of Western India described by Ptolemy, who mentions five sea-ports but only two inland cities. It is clear that the pirates were hemmed in on the land side by the dominions of the Śātakarnis, and that they held but little territory above the ghāts, though their capital Monsopallu was in that region. The places on the coast from north to south were Munlagama, the Mandugma of the Periplus (chapter 53) which has been satisfactorily identified with Mandangul to the south of the Bānkot creek.

Byzantion, which, as Dr. Bhandārkar first pointed out, is the Vaijayanti of inscriptions may be placed either at Chiplun or at Dabhol at the mouth of the Vāsishthī river. Chiplun is the only town of great antiquity in this part of the Konkan, and if it is not Vaijayanti Ptolemy has passed over it altogether. The similarity of the names has suggested the identification of Byzantion with Jaygaḥ (Bhandārkar) or Vijayadrug (Vincent), but both these places are comparatively modern. There are indeed no very ancient towns in the Konkan between Sangamēshvar and the Sāvantvāli border.

Kleronēsos is generally admitted to be the peninsula of Goa.

## Appendix VI.

### EARLY GREEKS AND ROMANS.

Klaudios  
Ptolemaios.

**Appendix VI.**EARLY GREEKS  
AND ROMANS.*Klaudios  
Ptolemaios.*

Armagara is placed a little to the north of the river Nanagomma and may be represented by Capo Ramas in Portuguese territory.

The river Nanagomma here is generally supposed to be the Kálinálí, though in its upper course it seems to represent the Tapí, and a confusion with the Nānā pass led Ptolemy to bring it into connection with the rivers Goaris and Bēda (Cunipbell).

Nitra, the southernmost point on the pirate coast, is the Nitria of Pliny, and has been satisfactorily identified by Yule with Mangalur on the Netravati.

The inland cities of the Pirates are Olokhorra and Mousopolis the capital, both of which must be sought for in the rugged country about the sources of the Krishna and may provisionally be identified with the ancient towns of Karād and Karvir (Kolāpūr) respectively. To complete Ptolemy's account of this coast it is only necessary to mention the islands of Heptanēssa (Burnt Islands), Trikādiba and Pēperiaē. We are not here concerned with his account of the rest of India.

*Bardesanes.*

Bardesane's met at Babylon certain envoys sent from India to the emperor Antoninus Pius (A.D. 154-181) and received from Damadanis and Samlanēs, who were of their number, accounts of the customs of the Brahmins and of a rock temple containing a statue of Śiva in the Ardhanārī form. Lassen (III. 62 and 318) connects Sandanes with the Sadma and places the temple in Western India but neither of these conclusions is necessary. The object of the embassy is unknown.

*Periplus*

The *Periplus of the Erythrean Sea* formerly though wrongly attributed to Arrian (150 A.D.), is an account of the Egyptian trade with East Africa and India, written by a merchant of Alexandria for the use of his fellows. It is preserved in a single manuscript which in some places is very corrupt. The age of this work has been much disputed; the chief views as to this matter are,

(i) that the *Periplus* was written before Pliny and made use of by him (Vincent, Schwanbeck, and Glaser). The arguments of Vincent and Schwanbeck are refuted by Müller (Geogr. Gr. Min. I. xcvi) (Glaser's case is (Ausland 1891 page 15) that the Mahkhas of the *Periplus* is Malchos III of Nabathana (A.D. 49-71), that the *Periplus* knows Meroe as capital of Ethiopia, while at the time of Nero's expedition to East Africa (A.D. 68), it had almost vanished, and lastly that the author of the *Periplus* is Basilis or Basilēs, whom Pliny names as an authority for his Book VI. It may be replied that Mahkhas is the title Mahk and may have been applied to any Arab Sherkh (Reinaud); that the *Periplus* does not with certainty mention Meroë at all; and that Basilis whether or not a contemporary of Ptolemy Philadelphos was at any rate earlier than Agatharkhidēs (c. 200 B.C.); who quotes him (Geogr. Gr. Min. I. 156);

(ii) that the *Periplus* was written at the same time as Pliny's work, but neither used the other (Salmasius). This view is refuted by Müller (*op. cit.* page 155);

(iii) that the *Periplus* was written after 161 A.D. (Dodwell); Müller has shown (*ibid.*) that Dodwell's arguments are inconclusive;

(iv) the received view that the *Periplus* was written between A.D. 80 and A.D. 89 (Müller);

(v) that the *Periplus* was written about the middle of the third century (Reinaud Mém. de l'Ac. des Inscr. XXIV. Pt. ii. translated in I. A. VIII. pages 330ff).

The only choice lies between the view of Muller and that of Reinand. Muller argues for a date between A.D. 80 and A.D. 89, because the *Periplus* knows no more than Pliny of India beyond the Ganges, whereas Ptolemy's knowledge is much greater; because the *Periplus* calls Ceylon Palaisimonandou, which is to Ptolemy (VII. iv. 1) an old name; because the Nabathæan kingdom, which was destroyed A.D. 105, was still in existence at the time of the *Periplus*; because the *Periplus* account of Hippalos shows it to be later than Pliny; and because the *Periplus* mentions king Zōskalēs, who must be the *Za Hakalē* of the Abyssinian lists who reigned A.D. 77-89.\* It may be replied that the *Periplus* is not a geography of Eastern Asia, but a guide book for traders, with certain ports only; that Ptolemy must have found in his lists three names for Ceylon, Taprobane, Palaisimonandou, and Sahkē, and that he has wrongly separated Pala from Simonandou taking it to mean "formerly" and therefore entered Simonandou as the old and Sahkē as the "modern name," whereas all three names were in use together; that the Nabathæan king Malikhās was simply the Sheikh of the tribe (Remaud), and points to no definite date; that the *Periplus*' account of Hippalos is certainly later than Pliny; and that the Zoskalēs of the *Periplus* is the *Za Sagal* or *Za Asgal* of the Abyssinian lists, who reigned A.D. 216-17 (Remaud).

It follows that Remaud's date for the *Periplus* (A.D. 250) is the only one consistent with the facts, and especially with the Indian facts. As will appear below the growth of the Hippalos legend since Pliny's time, the rival Parthians in Sindh, the mention of Mauboros and the supplanting of Ozēne by Munnagara as his capital since Ptolemy's time, the independence of Baktria, and the notices of Saraganes and Soudanēs, are all points strongly in favour of Remaud's date.

In the time of the *Periplus* the ships carrying on the Indian trade started from Myos Hormos (near Ras Abn Somer) or Berenike (on Foul Bay) and sailed down the Red Sea to Monza (Masa twenty-five miles north of Mokhā) and thence to the watering place Okelis (Ghaffa) at the Straits. They then followed the Arabian coast as far as Kapor (Hish Ghurah in Hadramaut) passing on the way Endamou Arabia (Aden) once a great mart for Indian traders, but lately destroyed by king Elhasā (Muller's conjecture for ΚΑΙΣΑΡ of the MS.) From Kapor the routes to India diverge, some ships sailing to the Indus and on to Barygaza, and others direct to the ports of Limyrike (Malabar Coast). There was also another route to Limyrikē, starting from Arōmata (Capo Guardafui). In all three voyages the ships made use of the monsoon starting from Egypt in July. The monsoon was called Hippalos, according to the *Periplus* (chapter 57), after the navigator who first discovered the direct course across the sea, and it has been inferred from Pliny's words (VI. 23) that this pilot lived in the middle of the first century A.D. But Pliny's own account shows that, as we should expect, the progress from a coasting to a direct voyage was a gradual one, with several intermediate stages, in all of which the monsoon was more or less made use of. There was therefore no reason for naming the wind from the pilot who merely made the last step. Further though Pliny knows Hippalos as the local name of the monsoon wind in the eastern seas, he says nothing of its having been the name of the inventor of the direct course. The inference seems to be that Hippalos the pilot is the child of a seaman's yarn arising out of the local name of

## Appendix VI.

EARLY GREEKS  
AND ROMANS,  
*Periplus.*

\* We learn from Pliny (VI. 22) that Palaisimonandou was the name of a town and a river in Ceylon, whence the name was extended to the whole island.

**Appendix VI.**EARLY GREEKS  
AND ROMANS.*Periplus.*

the monsoon wind, and that his presents in the *Periplus* and not in Pliny shows that the former writer is much later than the latter.

The merchant bound for Skythia (Sindh) before he reaches land, which lies low to the northward, meets the white water from the river Sinthos (Indus) and water snakes, (chapter 38). The river has seven mouths, small and marshy all but the middle one, on which is the port of Barbarikon (Shālibandar, Haig, page 31) whence the merchants' wares are carried up by river to the capital Minnagar (near Shāhdādpur, Haig, page 32), which is ruled by Parthians who constantly expel one another (chapter 39). These contending Parthians must have been the remnant of the Kyrén Pahlavs who joined with the Kushāns to attack Ardeshir Papakān (Journ. As. [1866] VII 431). The imports are clothing, flowered cottons, topazes, coral, storax, frankincense, glass vessels, silver plate, specie and wine, and the exports costus (spice), bdellium (gum), yellow dye, spikenard, emeralds, sapphires, furs from Tibet, cottons, silk thread, and indigo. The list of imports shows that the people of Skythia were a civilised race and by no means wild nomads.

The *Periplus* next (chapter 40) gives an accurate account of the Ran (Birmen) which in those days was probably below sea level (Haig, page 22, Burnes' Travels into Bokhara, III. 309ff), and was already divided into the Great and the Little. Both were marshy shallows even out of sight of land and therefore dangerous to navigators. The Ran was then as now bounded to south and west by seven islands, and the headland Barakê (Dvārakâ) a place of special danger of whose neighbourhood ships were warned by meeting with great black water-snakes.

The next chapter (41) describes the gulf of Barygaza (gulf of Cambay) and the adjoining land, but the passage has been much mangled by the copyist of our only MS. and more still by the guesses of editors. According to the simplest correction (*ἡπρωτῆς Ἀριακῆς ᾠρᾶς*) our author says that next after Barakê (Dvārakâ) follows the gulf of Barygaza and the country towards Ariake being the beginning of the kingdom of Mamburos and of all India. Mamburos may possibly be a corruption of Makhatrapos or some similar Greek form of Mahakshatrapa, the title of the so-called "Sâh Kings" who ruled here at this period (A.D. 250). According to the reading of the MS. the author goes on to say that "the inland part of this country bordering on the Hêra (read Salaria = Sanvira) district of Skythia is called . . . (the name, perhaps Maru, has dropped out of the text), and the sea-coast Sykasiônê (Surāshtra)." The country abounded then as now in cattle, corn, rice, cotton and coarse cotton cloth and the people were tall and dark. The capital of the country was Minnagara whence much cotton was brought down to Barygaza. This Minnagara is perhaps the city of that name placed by Ptolemy near Mānpur in the Vindhya, but it has with more probability been identified with Janāgad (Bhagānlāl) which was once called Mānipura (Kath. Gaz. 487). Our author states that in this part of the country were to be found old temples, ruined camps and large wells, relics (he says) of Alexander's march, but more probably the work of Menandros and Apollodotos. This statement certainly points to Kāthiāvāda rather than to Mānpur. The voyage along this coast from Barbarikon to the headland of Pāpikê (Gopnāth) near Astakapra (Hāthab) and opposite to Barygaza (Broach) was one of 3000 stadia=300 miles, which is roughly correct. The next chapter (42) describes the northern part of the gulf of Cambay as 300 stadia wide and running northward to the river Mais (Mabi). Ships bound for Barygaza steer first northward past the island

Baidnes (Peram) and then eastward towards the mouth of the Namnadios (Narmadâ) the river of Broach. The navigation (chapter 43) is difficult by reason of rocks and shoals such as Hêrônê (perhaps named from some wreck) opposite the village of Kamônî (Kin) on the eastern shore and by reason of the current on the western near Pâpikê (perhaps a sailor's name meaning Unlucky). Hence the government sends out fishermen in long boats called Trappaga or Kotumba (Kotia) to meet the ships (chapter 44) and pilot them into Barygaza, 300 stadia up the river, by towing, and taking advantage of the tides. In this connection our author gives a graphic description of the Bore in the Narmadâ (chapter 45) and of the dangers to which strange ships are exposed thereby (chapter 46).

Inland from Barygaza (that is, from the whole kingdom, which, as we have seen, bordered on Sanvira or Multan) lay (chapter 47) the Aratrioi (Arattas of the Mahâbhârata and Purânas, who lived in the Panjab), the Arakhôsioi (people of eastern Afghanistan), Gandaraiioi (Gandhâra of N.-W. Panjab), Proklais (near Peshâwar), and beyond them the Baktrianoi (of Balkh) a most warlike race governed by their own independent sovereigns. These last are probably the Kushans who, when the Parthian empire fell to pieces in the second quarter of the third century, joined the Karen Pahlavs in attacking Ardeshr. It was from these parts, says our author, that Alexander marched into India as far as the Ganges—an interesting glimpse of the growth of the Alexander legend since the days of Arrian (i. p. 360). Our author found old *drakhmai* of Menandros and Apollodotos still current in Barygaza.

Eastward in the same kingdom (chapter 48) is the city of Ozônê, which was formerly the capital, whence onyxes, porcelain, muslins, and cottons are brought to Barygaza. From the country beyond Proklais came costus, bdellium, and spikenard of three kinds, the Kattybourino, the Patropigie, and the Kabalitæ (this last from Kabul).

We learn incidentally that besides the regular Egyptian trade Barygaza had commercial relations with Monza in Arabia (chapter 21) with the East African coast (chapter 14) and with Apologos (Obollah) at the head of the Persian Gulf and with Omana on its eastern shore (chapter 36). The imports of Barygaza were wine, bronze, tin and lead, coral and gold stone (topaz?), cloth of all sorts, variegated sashes (like the horrible Berlin wool comforters of modern days), stamox, sweet clover, white glass, gum sandarac, stibium for the eyes, and gold and silver coin, and unguents. Besides, there were imported for the king costly silver plate, musical instruments (music boxes are still favoured by Indian royalty), harpisonic gits for the harem (these are the famous Yayani handiworks of the Indian drama), high-class wine, apparel and choice unguents, a list which shows that these monarchs lived in considerable luxury. The exports of Barygaza were spikenard, costus, bdellium, ivory, onyxes, porcelain, box-thorn, cottons, silk, silk thread, long pepper (chillies), and other wares from the coast ports.

From Barygaza our author rightly says (chapter 50) that the coast trends southward and the country is called Dakshinabadês (Dakshinâpatha): much of the inland country is waste and infested by wild beasts, while populous tribes inhabit other regions as far as the Ganges. The chief towns in Dakshinabadês (chapter 51) are Paithana (Paithan) twenty days journey south of Barygaza and Tagara (Dhârur): very large city ten days east of Paithana. From Paithana come onyxes, and from Tagara cottons, muslins and other local wares from the (east) coast.

## Appendix VI.

EARLY GREEKS  
AND ROMANS.*Periplus.*

**Appendix VI.**  
**EARLY GREEKS**  
**AND ROMANS.**  
*Periplus.*

The smaller ports south of Barygaza are Akaharon (perhaps the Khabiran of Mahomedan writers and the modern Kāvēri the river of Nāṁkāri) Souppara (Supārā near Bassin) and Kalliena, which was made a mart by the elder Saragauēs, but much injured when Sandanēs became its master, for from his time Greek vessels visiting the port are sent under guard to Barygaza. This interesting statement is one of the clearest indications of the date of the Periplus. As Bhāndārkar has shown the elder Saragauēs implies also a younger, who can be no other than Yajñuśrī Śatakarni (A.D. 110), and the Periplus must be later than his time. The Sandanēs of the text must have been a ruler of Cinjarat and may be identified with the Kshatrapa Saṅghadāman (A.D. 224).

South of Kalliena (chapter 53) are Sēmylla (Chaul) Mandagora (Mandargol) Palurpatmai (Pal near Mahad) Melizeigara (probably Janjira) and Byzantion (Chiplun). The words which follow probably give another name of Byzantion which was formerly also called "Tyrannosboas," the name Toparon being a misunderstanding (Müller, Geogr. Gr. Min. I. 296). South of this are the islands of Sēsekroēnai (Burnt Islands), Angidōi (Angelha), Kaimutai (Island of St. George) near the Khersonēsos (Gon), and Lauke (Laccadives?) all pirate haunts. Next comes Limyrike (the Tamil country) the first parts of which are Namura (Cannanore or Bilheery rather than Honavar, which is too far north) and Tyndis (Kadalundi near Beypur) and south of these Muziris (Kraungnur) and Nelkynda (Kallada). Tyndis and Muziris were subject to Kēkolaitas (Kēkalaputra that is the Cera king) and Nelkynda to Pandia (the Pandya king of Madura). Muziris was a very prosperous mart trading with Ariake (North Konkan) as well as Egypt. Nelkynda was up a river 120 stadia from the sea ships taking in cargo at the village of Bekarē at the mouth of the river. Our author gives an interesting account of the trade at these ports and further south as well as on the east coast, but we are not concerned with this part of his work.

*Markianos.*

Markianos of Hierakleia about the year 400 A.D. is the leading geographer of the period following Ptolemy, but his work consisted chiefly in corrections of Ptolemy's distances taken from an obscure geographer named Prôtageoras. He adds no new facts to Ptolemy's account of western India.

*Stephanos.*

Stephanos of Byzantium wrote about 450 A.D. (or at any rate later than Markianos whom he quotes) a large geographical dictionary of which we have an epitome by one Hefimaios. The Indian names he gives are chiefly taken from Hekataios, Arrianos, and especially from a poem called Bassarika on the exploits of Dionysos. But his geography is far from accurate: he calls Barakē (Dvāraka) an island, and Barygaza (Brouch) a city, of Gētrōsia. Among the cities he names are Argantē (quoted from Hekataios), Barygaza (Brouch) Boukephala (Jalalpur), Byzantion (Chiplun), Gēreia, Gēgrippa, Darsana famous for woven cloths, Dionysopolis (Nysa?), Kathia, (Mulfan?), Kaspapyros and Kaspeiros (Kāśmīr), Margana, Mūsaka (in Syāt), Nysa, Palimbothra (Pātalyptar), Pannionra near the Indus, Patola (thirty-five miles south-east of Haidarābād, Sindh), Rhodō, Rhōganō, Rhon in Gaurikā, Saneia, Sesuphon, Sindia in the great gulf (perhaps Ptolemy's Asunda, Vāgnagar), Sōlimna, and Tuxila. He also names a number of tribes, of whom none but the Orbitai (Makrān) the Pandai (Pāndya) Bōlingar (Bhānulingi Sālvus) and possibly the Sulinger (Sālānkāyana) belong to the western coast.

**Kosmas Indikopleustes**, shipman and monk, who wrote his *Topographia Christiana* between A.D. 530 and 550, is the last of the ancient writers who shows independent knowledge of India. He says that Sindh (Sindh), is where India begins, the Indus being the boundary between it and Persia. The chief ports of India are Sindh (Debal), which exports musk and nard; Orrhothia (Sarāshtra that is Yeraval) which had a king of its own; Kalliana (Kalyān) a great port exporting brass and sisam (black-wood) logs and cloth having a king of its own and a community of Christians under a Persian bishop; Sapor which also had a king of its own and therefore cannot be Saporā, which is too close to Kalliana but must be Gera the Sindabur of the Arabs; Parā, Mangarūth (Mangalore), Salopatana, Nalopatana, and Pudopatana which are the five marts of Malā the pepper country (Malabār) where also there are many Christians. Five days' sail south of Malālay Siedeha or Taprobane (Ceylon), divided into two kingdoms in one of which is found the hyacinth-stone. The island has many temples and a church of Persian Christians, and is much resorted to by ships from India, Persia and Ethiopia dealing in silk, aloewood, cloves, sandalwood, &c. On the east coast of India is Marallo (Morava opposite Ceylon) whence conch-shells are exported. Then Kaher (Kaveripatam or Pegu, Yule's *Cathay Introduct.* page clxxvii) which exports Albandum, further on is the clove country and furthest of all Tzauris (China) which produces the silk. In India further up the country, that is further north, are the White Onnoi or Hmas who have a king named Gollas (Mihirakula of inscriptions) who goes forth to war with 1000 elephants and many horsemen and tyrannises over India, exacting tribute from the people. His army is said to be so vast as once to have drunk dry the ditch surrounding a besieged city and marched in dryshod.

In his book XI, Kosmas gives some account of the wild beasts of India but this part of his work does not require notice here.

This is the last glimpse we get of India before the Arabs cut off the old line of communication with the Empire by the conquest of Egypt A.D. 644-2).

## Appendix VI.

### EARLY GREEKS AND ROMANS.

*Kosmas.*



# INDEX.

- ĀBA SHIPLUKAR:** Peshwa's Subhedar of Gujarāt, levies contributions on the Garkwār's villages, 111, is made over to the British Government (1807), 116.
- ABDUL AZIZ KHAN:** of Junnar, becomes viceroy by a forged order and appoints Jawan Mard Khan his deputy in Gujarāt, 326, his defeat and death at Ken Kathodra 328.
- ABDUL KADIR:** son and prime minister of Ghatotakhil Khilji, 362, 364. See Nasiruddin.
- ABDUL KARIM:** successor of the emperor Jehangir, repairs buildings at Mandu (1617), 373.
- ABDULI (or) KHAN UZBAK:** Akbar's general, reconquers Mdwa (1563), 369.
- ABDULLAH WASSAF:** author of *Taziyat ul-Amir*, 515 and note 6.
- ABHAYASINGH RATHOR:** 461. See Abhaysingh.
- ABHAYATILAKAGANI:** Jain monk (1255), revised the *Dvaya naya* 156.
- ABHAYSINGH Maharaja:** fifty-third viceroy of Gujarāt (1730-1733) 310, his defeat by Mahārā ul-Mulk, 311, procures assassination of Pilaji Garkwar and takes Baroda (1733), 313, is re-appointed fifty-fifth viceroy of Gujarāt, 319.
- ABHLOHANA CHINTAMANI:** work, written by Hemachandra, 192.
- ABHIMANYU:** early Rishabhakuti prince, his copperplate grant, 120.
- ABHIRA:** name of a tribe, and province, 52, 64, note 3. See *Abir* and *Chudasama*.
- ABHIRAS:** tribe, 137.
- ABI:** tribe, 531.
- ABIR:** name of a province, 52, 53 note 1, 137; Upper Sindh and Multan, 537. See *Abhira*.
- ABU:** king of, present with Maharaja in the battle with Garkwar, 160, magnificent temple of Nagnāth built by Vastupāla and Tejapāla on, 199, 202, inscription on the temple of Vastupāla at, 204; Mutia at, 139; Purnāgar possession, 170, Mount, 532, 534.
- ABULĀMA:** perhaps Oballah, 35.
- ABUL FAZL:** Akbar's historian (1590), his account of Sultan Bahādur's death, 349, 371.
- ABU RIHAN:** 508, 510. See *Al Biruni*.
- ABU ZAYD:** Arab writer (913), 525, 526 note 5, 528, 530.
- ABU ZEFAR HASAN:** author of the second part of *Nisbat ut-Tawārikh*, 505 note 2.
- ACCAL:** early race, 174 and note 1.
- ACHARYAS:** funeral Brahmans, 451.
- ADILAB:** battle of (1730), 311.
- ADIN:** 514, 513.
- ADHYATMORASINHA:** religious work compiled by Hemachandra, 193.
- ADINATHA:** temple on Satranjaya of, 70 note 3. See *Adinatha*.
- ADIVYARA:** Jain god on Satranjaya hill, 177, 186.
- ADMINISTRATION:** of the Valabhis (500 to 700) 51.
- ADINATH:** temple of, completed, 186. See *Adinatha*.
- ADIN'S GATES:** 536.
- ADONANISIAN:** 545.
- ADONA:** 535.
- AGATHARKHIDES:** (born 250 A.D.) 535, 542.
- AGNIKULAS:** Rājputs, 163, 468.
- AGHA MUHAMMAD HUSSAIN:** commander of the fort of Petlad, his surrender, 327.
- AGRA:** fort, 368.
- AGREEMENT:** between the Peshwa and the Dabhade 303.
- AGRIKADARA:** identified with Nagar, 539.
- AGADA:** son of Ulava Vama, high officer in the reign of Kumbhāpala, 170, not acknowledging Kumbhāpala goes to Anoraja, 184.
- AGAR:** city, 539.
- AGIR:** 175. See *Chudasama* and *Abhira*.
- AGIRS:** settlement of, 137, 138.
- AHMAD:** 513. See *Ahmed*.
- AHMADABAD:** built (1413), 236, 513; sacked (1583), 224, 225; manuscript found at, 205; riot at (1681), death of the leader Abu Bakr by poison, 286, 287; riots at (1730), 310; Umbar, widow of Khandarav Dabhade marches upon, 314; siege of and capture by the Marāthās and Momin Khan (1737-1738), 320, prosperity of, 320; disputes about the government of, between Rangoji and Momin Khan (1738), 322; disturbances at, between the Musalmāns and the Marāthās, 325; mutiny of troops at, confinement of Fida-ud-din and Miftaklūr Khān at, capture of the city of, by Jawan Mard Khan, 327; Marāthās in (1743-44), 327, siege of by Fakhru-ud-daulah and Rāi-singh of Idar and defeat and capture of the Viceroy at, by Jawan Mard Khan, 329; expulsion of Khānderav Garkwār's deputy Trilhubak from, by

- Rangoji, 329; siege and capture of, by the Maráthas under Raghnáthrao, 337, minting of coins in the emperor's name stopped at, (1753), 338; assassination of Rangoji the Marátha deputy at and expulsion of the Maráthas from, by Momin Khán; Kols attempt to plunder the Dutch factory at, 339-340; siege of, by the Maráthas, Shah Nur intercedes with the Peshwa to settle the affairs of, and fails, surrender of (1758), 341, 342, Sadashiv Raurchandras appointed viceroy at (1760), 341, state of the parties at, 390; riots at (1738), 391, captured by General Goddard (1760), 109, surrendered to Govindray Garkwar by A'ha Shahukan, 111, cession of the fort of, to the English by Garkwar in 1817, 138, mutiny at (1857), 438; disturbances at (14th September 1857), 440, suppression of the mutiny at, 442. See Ahmedabad.
- AHMAD AYZ** governor of Gujarat, 280.
- AHMED I.** Ahmedabad king (1411-1441), builds Ahmedabad (1414); defeats the Pdar chief (1414), suppresses a revolt, spreads Islam, sends expedition against Malwa (1417), attacks Champuner (1418), his war with Malwa (1422), defeats the Pdar chief (1425), recovers Malwa (1429) and Baglan (1431) 207 note 1, 215, 219, 235-241.
- AHMEDABAD.** 513. See Ahmedabad.
- AHMEDABAD KINGS.** rule of (1403-1573), 207, 209, 210, 231, 264.
- AHMED KHÁN** see Ahmad I.
- AHMED KHÁN HANSHI**, commandant of the Surat fort, expelled by the English (1759), 343.
- AHMEDNAGAR.** fort built (1427), 238.
- AHMED SHAH** son and successor of Emperor Muhammad Sháh, 332, deposed (1754), 339.
- AHMED SHAH** grandson and successor of Muzaffar I of Gujarat (1393-1411), besieges Mándu twice between A.D. 1418 and 1422, 359.
- AIAGHORI** Angedivá, 546.
- AIGOR** inscription at, 107.
- AIN-UL-MULK MILEFANI** Gujarat governor (1318), 229, 230.
- AJAYAPALA** Chohán king (840), 157.
- AJAYAPALA** Chaulukya king (1174-1177), successor of Kuntapála persecuted Jain officers and scholars, is murdered by the door-keeper, 194-195.
- AJMAL** monarch of Kanauj, killed by Naimpal, 120.
- AJISINGH** son of Maharaja Juvantsingh of Marwár, causes disturbance (1689-1692), 288, 289, his plans of rebellion checked (1705), 291; recovers Jodhpur (1709), 295, 296, is reconciled with the emperor (1711), gives his daughter to him in marriage, 297; is appointed forty-seventh viceroy of Gujarat, disagrees with Haider Kuli Khan, 299-300; is appointed forty-ninth viceroy of Gujarat (1719-1721), 301.
- AJMIR** Mher settlement at, 136; capital of Chohán kings, 157, 180.
- AKABAR** perhaps Khahiran, 518, 516.
- AKALAVARSHA** Ráshtrakúta king of the Gujarát branch, re-establishes himself in the territory of his father Dhruva, 126.
- AKALAVARSHA** another name of Krishna, the Dakhan Rashtrakúta king, recovers the disputed area to the south of the Tapti, his grants, 127-128. See Krishna.
- AKAG (VANTI)** ancient name of Málwa, 36 and note 1.
- AKBAR**, Delhi emperor (1573-1604), struggles with the Desodias, 110, 207, 211, 220, marriage Miran Mahabak Khán's daughter at Mándu (1561), 339.
- AKBAR** Aurangzib's son, rebels (1697), 290.
- AKBAR** the palace at, built by Nasir-ud-din of Malwa (1500-1512), 365.
- AKHAM** IZMANA of Brahmanabad, asks help of the king of Hindu-ém, 519.
- AKHKA**, brother of Pichunda, 129.
- AKOTA** 125.
- AKOTRE VARA** Ankavara, 115.
- AKOT KHAN** 191, brother of Alaud din Khilji leads an expedition against Gujarat and conquers it (1297), invades Tominath, constructs a Jama mosque at Anaholaváda with white marble pillars taken from Jain temples, 205.
- AKSHANA** Gujjara king (890), 3, cedes Takkadasi, 468.
- AKSHIR II.** Azizuddin, son of Jahándar Shah, succeeds to the throne of Delhi (1751-1759), 339.
- AL A'BI**, father of Usáid, 505.
- ALANKARA CHIDAMANI**, work on rhetoric compiled by Hémachandra 193.
- ALAM ALI KHAN** deputy viceroy of the Dakhan, pursues the Nizam, is defeated and slain at Bákrpur (1720), 301.
- ALAUDDIN KHILJI**, Delhi emperor (1296-1315), desecrates the Somnath temple, 190, 207, 229, 512, 515.
- ALBAHMAN** identified with Bhimál, expedition against, 109, 167.
- ALBAN** Lieutenant, disarms and shoots Musaphakán the Arab leader in revolt at Sunth, 111.
- ALBFRUNI** 78 and note, 81, 167 note 1. See Al Buuni.
- AL BILAFRIT** Ahmed bin Yáhya, surnamed Abu Jafar, writer of Futuh-ul-Buláin (802), 505 and note 3, 506, 518 and notes 8 and 9, 520.
- AL BIRUNI** Abu Rihán, Arab traveller (970-1039), 153, 500, 507 and note 9, 508 and note 8, 510 and note 3, 511 and note 9, 512 and note 1, 513 and note 11, 514, 516 and note 11, 517, 518, 520, 521, 522, 523, 524, 525, 527, 528, 730, 531. See Al Biruni and Abu Rihán.
- ALEXANDER** the Great, Macedonian emperor (B.C. 326-325), 164 note 5, 497, 532, 536, 537, 544, 545.
- ALEXANDRIA** town, 536.
- AL HAJAJ** (714), 506.
- AL HIND** India, 505 note 5, 507.

- ALI AKBAR** : of Ispahān, governor of Surat and Cambay, 280 ; his assassination (1616), 280.
- AL IDRISI** : Abu Abdallah Muhammad, author of *Nuzhat-ul-Mushtāk* (1100), 508 and note 10, 509 note 5, 510, 511, 512 and note 1, 516, 517 and note 2, 519, 521, 523, 524, 525, 526, 527, 528, 529, 531.
- ALIB** : 386.
- ALINGA** : appointed second counsellor, 181. See *Sajjina*.
- AL ISAKHRI** : Abu Is-hak, author of *Kitāb-ul-Akāhūn* (951), 509 note 3, 510 note 1, 511 and notes 3 and 4, 512, 514 and notes 2 and 3, 516 notes 6 and 7, 520 and note 10, 523.
- AL JAHNABI** : Arab writer (982-999), 503 note 10, 525, 526.
- AL KAWINI** : Zakariyah Ibn Muhammad author of *Asar-ul-Bid'at* (1263-1275), 504 note 2, 510 and note 1, 516 and note 14, 517 note 1, 529.
- ALIAHABAD** : inscription of Samudragupta at, 63, 65.
- ALITHROCHADIS** : Bindusāra, son of Chandragupta, 534.
- AL MAHDI** : Khadifah (775-785), 525.
- AL MAMIN** : Abū al-Khadifah (713-733), 506, 520.
- AL MAS'UDI** : Ahmad Hasan, Arab traveller (915-944), 505 note 5, 506 note 8, 510, 512, 513, 514, 516, 518 and note 4, 520, 521, 523, 524, 525, 526, 527, 528, 529, 531.
- AL MUKRI** : Abdul Rahman, 513.
- AL MUTAWAKKIL** : 505 note 3.
- AIOR** : town, 535.
- ALF KHAN**, governor of Gujarat (1310), 229 note 6.
- ALANAT KHAN**, military governor of Surat (1690), 288. See *Ismād Khan*.
- AMARABHATA**, Sanskrit form of Ambada, 185 note 3.
- AMARAKA** : branch of Saivism 138.
- AMARJI** : Dewan of Jamnagar (1759-1784), 70.
- AMBI PRAYAGI** : irrigated land beyond, owned by a branch of the Vaghelas, 206.
- AMUNAH** : son of Udayana, rises to prominence in the reign of Kumarapala, 170, fights with Mallikarjuna and in a second fight kills him for which he is honoured with the title of *Rājapitamaha*, 185-186, 186. 187. 188. rises to prominence at Ajayapala in religious matters and is killed in a fight, 195.
- AMRKA** : Sanskrit form of Ambada, 185 note 3.
- AMBAPATA** : village, grant of, to a Jain temple at Navasari, 125.
- AMBIKA** : goddess, temple of, at Kodinār, 182 and note.
- ANAHIL** : 511. See *Anahilavāda*.
- ANAL** : sub-divisional officer, 210, 212.
- AMIN** : chief treasurer, 212, 214.
- AMIRANI SADAT** : insurrection of (1346), 230.
- AMIRKIHAN** : Raghoba's general, 405.
- AMIR KHUSRAO** : author of *Tarikh-i-Alai*, 515.
- AMJERA** : rising at, 439.
- AMOGHAVARSHA I.** : Dakhan Rāshtrakūṭa king, 123, 124 ; invades Gujarat, 125, 126, 128, 525.
- AMRABHATA** : see *Ambada*.
- AMRĀKĀNDAVA** : Gupta chief, 66.
- AMRELI** : battle at (1730), 312 ; Mahāls, 418.
- AMRU BIN JAMAL** : TAGHLABI, 521.
- AMRUVARMAN** : inscription of, 81.
- ANAHILA** : Bhavād, shows Vamarāja the site of Anahilavāda, 151.
- ANAHILAPURA**, city, 151 ; Vamarāja's installation at, 152 ; Ambada returns victorious to, after his flight with Mallikarjuna, 186. See *Anahilavāda*.
- ANAHILAVADA** : Chāvalas of, 124 ; foundation of (716), 466 ; removal of the capital of Mularāja Solanki to, 139 ; named after a Bhavād who shows its site ; founding of Jain temple at, 151-152 ; chronicles, 156 ; Mularāja's father and uncles stop at, 156 ; cavalry parade at, 157 ; Jinn and Mahadev temples at, 160, 161, lake built by Durlabha at, 163 ; invasion by Kalachandra of, 163-164 ; Bhima I, king of, at Mahmud's advance abandons it and flies away, 164, proposed capital of Mahmud of Ghazni, 168 note 1 ; Karnamern temple at, 170 ; Vikramasinha imprisoned at, 185, lion-temple at, 193, sack of (1194), 229, its different names, 511. See *Anahilapura*.
- ANAHILAVATA**, Sanskrit form of Anahilavāda, 151.
- ANAHILAPATAKA** : 204. See *Anahilavada*.
- ANAKA** : see *Armoṛāja*.
- ANAND** : name of Armoṛāja, father of Dhavānprastha, as given in an inscription, 209.
- ANANDADEVA** : name of Anataja as given in the *Harimuramahakavya*, 182. See *Armoṛāja*.
- ANANDAPURA** : ancient name of Varanagata, 6 and note 2.
- ANANDRAY GATKAD** : heir of Govindrao, 412.
- ANANDRAYANAR** : settles at Dhar (A.D. 1731), 382. His Highness Sir K.C.S.I., C.I.E., the present Maharaja of Dhar 383.
- ANANDAPURA** : fort of, 180 note 2.
- ANANDRAY** : king of Sakandhar, 181 and note 3, 182. See *Armoṛāja*.
- ANALITA** : ancient division of Gujarat, 6, 35, 36, legendary Gujarat king, 8.
- ANANDAPURA** : see *Anahilapura*.
- ANDAR** : Andhras 532, 533.
- ANDHRAS**, the (A.D. 138), 32, 52. king of, at the bridegroom-choosing of Durlabhadevi, 163, 533.
- ANDRAPANA** : identified with Darlan, 538.
- ANDHARABHITYAS** : see *Andhras* and *Sātakarnis*.
- ANERKARHANIMAMATI** : Collection of words of more than one meaning, compiled by Hemachandra, 192.
- ANGA** : king of, at the bridegroom-choosing of Durlabhadevi, 163.
- ANGAR** : village, destruction of, by Mr. Ashburner, 443.
- ANGENIVA** : island, 546.
- ANILAVARA** : 516. See *Anahilavāda*.
- ANILWARA** : 512, 514. See *Anahilavāda*.
- ANKAVARA** : Akalavarsha Krishna's Bagunia grant from, 128 ; Marāthās defeated at (A.D. 1711), 297.
- ANGKOR** : capital of Cambodia, 499, 500, 502.

- ANNIUS FLOCIANUS 536.  
 ANKOTĀKA : modern Akota, 125.  
 ANO : Prakrit local name of Anaraja, 181 note 3.  
 See Anoraja.  
 ANOPESINGH BHANDĀRI : deputy of the viceroy Ajitsingh, 301.  
 ANUĀJA : statue of, 153.  
 ANTĀJĪ BHĀSKER : Maratha leader in Gujarat, 391.  
 ANTIQCH 536.  
 ANTONIO DE SILVEIRA : Portuguese command-  
 er in India, 349.  
 ANTONINUS PIUS : Roman emperor (154 - 181),  
 512.  
 ANPHOLI : plate at, 122.  
 ANPHOLI-CHĀROLI : Kalka, the Rāshtrakūṭa  
 prince's grant at, 121.  
 ANUPA : name of country, 36 note 2.  
 ANUPAMA : wife of Tejahpala, 202.  
 ANPA (GANESH) : Peshwa's viceroy of Gujarat,  
 345.  
 APARĀDITYA : successor of Mallikārjuna, 186.  
 APARĀNTA, the western seaboard, 36 and  
 note 8.  
 APARINPAKAS 534.  
 APOKOPA : the Aravallis 539.  
 APOLODORUS : Hellenistic-Greek king, 17, 18 ;  
 his inscriptions, 535, 544, 545.  
 APOLOGOS : modern Obollah, 545.  
 APABASTRA 534.  
 APABASTRA 533, 534.  
 APANPA : 513.  
 ARAB GUARD : at Baroda, disbanded (1803),  
 413.  
 ARABHATIA : see Ahada.  
 ARABS : invasion by, 117, raids of, 465, advance  
 of, by sea and land (637) and through Persia,  
 (650 - 660), 197, 525, 527, 529.  
 ARABOSIOI : people of eastern Afghanistan,  
 545.  
 ARATRIOI : Arattas of the Mahābhārata, 545.  
 ARATTAS : 515.  
 ARĀS : battle of (1723), 305.  
 ARĀUDĀ : see Abu.  
 ARCHIPELAGO : Malay, 492.  
 ARDABE : tribe, 531.  
 ARDESHIR PAPAKĀN : 544, 545.  
 ARDHĀSHITAMA : district, 191.  
 ARDIVIJAYA : grandson of Bhuvijaya (660), 489.  
 ARGANER : city, 516.  
 ARHĀĪ DINKĀ JIOPDĀ : mosque in Ajmer,  
 originally Sanskrit school, 180.  
 ARHAT ACHĀRA : great monastery built by, 79.  
 ARĀKKE : north Konkan, 540, 544, 546.  
 ARĀKESARI : 466.  
 ARĀCHITANEMI : Jain temple of, 181, modern  
 Ahmadabad.  
 ARJUNA, visit of, to Kāthiavada, 9.  
 ARJUNADEVA : Vaghela chief (1262-1274), 176,  
 succeeds Viśaladeva ; extension of his kingdom  
 and his inscriptions, 203-204, 206.  
 ARJUNĀYANA : Khattriya tribe, 64 note 3.  
 ARMAGABA : probably Cape Ramas, 542.  
 ARNORĀJA : king of Sambar, 179, 182, 184 ;  
 fights with Kumārāpāla and is defeated, 184,  
 188. See Anarāja.  
 ARNORĀJA : son of Dhavala, king of Bhima-  
 palli, helps Bhima II. in resisting the power  
 of his nobles (1176 - 1206), 196, 197, 198, 206.  
 See Anāka.  
 ARORĀJA : Cape Guadafui, 543.  
 AROR DIVISIONS : spread of, 195.  
 ARRIAN : (150 A.D.), 532, 533, 534, 542, 545.  
 ARRIANOS : 516.  
 ARTOGATA : town, 539.  
 ARYAKA : country, 510.  
 ASA BHIL, defeat of (1413-14), 233.  
 ASAPALA : prince, 172 and note 1.  
 ASAPALLI : modern Ahmedabad, 205.  
 ASARU JAN NIZAM-UL-MULK : governor of  
 Mdwā (1717 - 1721), 382.  
 ASAR-UL-BILĀD : work by Al Kazwini, 510 and  
 note 1.  
 ASĀHVA : village, 329, 513.  
 ASĀVAL : village, temples at, 170.  
 ASĀWAL : Ahmadabad, 231, 234, 235, 508, 509,  
 510, 512, 513, 518.  
 ASHA : Bhil chief, slain by Karna, 170.  
 ASHĀBALLI : modern Asaval, seat of Bhil chief,  
 Asha, 170.  
 ASHTUNKER Mr., Assistant Magistrate, Kaira,  
 raises a fort for the protection of the district,  
 439, suppresses a rising of Thākors at Par-  
 labpur 443, 444.  
 ASHĀKUL-UL-BILĀD : work by Ibnī Hnukal, 511.  
 ASHĀKUL : coins, 342.  
 ASINDA : identification of, 539.  
 ASINI : tribes 534.  
 ASMAĞI : the Asmakas, 532, 533.  
 ASMAKAS 533.  
 ASOKA : Mauryan emperor (n.c. 260), 13, 14 ;  
 raises monuments in Buddha's places of rest,  
 79.  
 ASRAVAS : Brahman stages of life, 116.  
 ASSAM 528. See Kaman.  
 ASSIGNED LANDS : during Musalman period,  
 209, 210, 211, 213, 214.  
 AS SINDH : Indus valley, 507.  
 ASṬAKAREĀ : town, identified with Hastaka-  
 vāpi or Hithab, 539, 544.  
 ASUDADA : son of Udaya, rises to a high posi-  
 tion under Kumārāpāla, 170.  
 ASINAYĀ : darūd hall, built by Suddharaja,  
 179.  
 ATANAK ABU BAKR : king (1154-1159), Saādī's  
 patron, 515 note 4.  
 ATHVA : village, on the Tāpti, 309 ; fort,  
 built at (1730), 310, 331.  
 ATIPA : 84.  
 ATRI : sage, 161.  
 ATTOK : town, 539.  
 AUNKIN : Pirum, 509, 515.  
 AUDICHYAS : subdivision of Brāhmins, origi-  
 nally northerners, 161 ; grants to, 172.  
 AI DUMHARI ŚĀLYAS : tribe, 534.  
 AUGUSTUS : (A.D. 14) 535.  
 AURANŪZ : Mughal emperor ; 226 ; Prince  
 Muhammad, twenty-fifth viceroy of Gujarat  
 (1644-1646), 280 ; his rule marked by re-  
 ligious disputes, is recalled, 280 ; joins with  
 Muṣṣād, defeats Jasvantsingh and Dārāli  
 Shikoh, confines Muṣṣād and ascends the

- throne (1658), 282; appoints Sidi Yácut of Janjira Mughal admiral (1670), 285; his campaigns against Udepur and Márvár; imposes jazyah tax in Gujarát (1670), 286; his death (1707), 295.
- AUTOMULA**: tribe, 532; modern Chaul, 533, 534, 540.
- AUXOIMIS**: town, identification of, 539.
- AVADKITA**: father of Yugesvara, 126.
- AVANTI**: king of, at the bridegroom-choosing of Durlabhadra, 163.
- AVAR**: 144.
- AVARS**, tribe, 75.
- AVASARPINI**: age, 193.
- AYODHYA**: capital of Assam, 191.
- AZAM KHÁN**: viceroy of Gujarát (1635-1642), 278, subdues Kolis and Kathis, robbers in Jhalaváda, Kathiaváda, Navinagar and Káthi (1639) 278, and marches against Navanagar (1640); is recalled (1642), 279.
- AZAM SHÁH**: prince, defeated and slain (1707), 296.
- BÁBAL**: Babyloñ, 506.
- BÁBÁJI**: military minister of Gáikvár leaves the command of the forces in Káthiaváda and takes part in the civil administration at Barda 416.
- BÁBA PIRAH**: ford, defeat of the Musalmáns at (1705), 294; advance of the Marathás to (1711), 297.
- BÁBARJA V** (DA) 375 187.
- BÁBARO**: demon, helps Siddharája in his magical feats, 174.
- BÁH PAKH**: power of the, 286; disagreement with Hagar Kúh Khán, 300, 301.
- BABRANWAR**: fort, invested by Bahada 187.
- BÁBURÁV**: guardian of Yashvantrá, infant son of Eshmáhi Dabhlde, 396.
- BÁDAMI**: town in Bijápur district, 125.
- BADARASIDHI**: apparently Borsad, 126.
- BAD GUJJARS**: high Gujjars, 164.
- BÁDMER**: town, 470.
- BÁDMER**: Mher settlement at, 136.
- BAGHÍDÁV**: 514, 516.
- BAGÁN**: hills, hiding place of Karádeva, 205.
- BAGUMRA**: village, copper and grant from, 117 plate of Akálavarsa at, 125; grant of Dhruva II at, 126; Akálavarsa Krishna's grant at, 127, Krishna, the Gujarát Ráshtrakúta king's grant at, 129; Dhruva II.'s plate at, 130, 468.
- BAGVÁDA**: fort, capture of, by Shivaji (1672), 387; by Lieutenant Welsh in 1780, 409.
- BÁHADA**: son of Udaya, rises to high position under Kumárapáha, 170; is made chief counsellor, 184; establishes Báhadapura, 186.
- BÁHADAPURA**: town established by Bahada, 186 note 4.
- BAHÁDUR**: Sultán of Gujarát (1526-1536); captures Mandu and sends Mahmud II. of Máliwa prisoner to Gujarát; incorporates Máliwa with Gujarát (1526), 367; takes refuge at Mandu after his defeat at Mandasor, flees from Mandu to Chámpánir, 367, 368; cedes the town of Bassein to the Portuguese, 347; his death (1536), 348-351.
- BAHÁDUR KHÁN**: son of a slave girl, claims the chiefship of Junagádh (1811), 425.
- BAHÁDUR KHÁN**: Khán Jehán, thirty-fourth viceroy of Gujarát (1668-1671); sent as viceroy of the Dakhan (1671-1674), 285.
- BAHÁDUR SHÁH I.**: (1707-1712) emperor of Delhi, 296; his death, 297.
- BAHALIM**: Indian viceroy of the Ghazni king, 174 note 1.
- BAHARIMAD**: (Mevad?), 109, 492.
- BAHÁVALPUR**: 538.
- BÁHINJI NÁIK**: Shivaji's spy in Gujarát in 1661, 386.
- BAHRAM SHÁH**: Ghazni king (1116-1157), 174 note 1.
- BAHRÉIN**: 505, 513, 515, 523.
- BAHRUCH**: 510. See Broach.
- BAHRUJ**: 508, 513. See Broach.
- BAHRUS**: 520. See Broach.
- BÁHULODA**: apparently the modern village of Bhulidá, remission of pilgrim tax at, 172.
- BAHUSANAYA**: see Dadda III.
- BADJADAK**: Arabe for milky, 517.
- BAIONES**: Piran, 545.
- BAHA**: pirate boats, 508 note 1, 521.
- BAISURA**: Vaiskya, 530.
- BAITHANA**: Pathan, 37, 541.
- BÁIZA BAI**: daughter of Shiji Ráo Ghatke and widow of Dowlatrav Sindia of Gwalior, 437.
- BÁJIRÁV BALLÁL**: Peshwa (1720-1740), sends Uday Pavar to Gujarát to drive away PÍLÁJI Gáikvár; carried on negotiations with the Gujarát viceroy and promises to exclude PÍLÁJI, Kántáji, and other freebooters from Gujarát, 308; discovers the intrigues of Trimbakráv Dabhlde; advances to Barda and besieges it; raises the siege and on his way to the Dakhan defeats the forces of Trimbakráv and Píljí and kills Trimbakráv (1731), 303; his negotiations with the Nizam (1731), 312, 313; is appointed governor of Máliwa with Anandráv Pavar as his deputy, 382.
- BÁJIRÁV II.**: Peshwa, son of Raghunáthráo (1796-1818), appoints his younger brother governor of Gujarát, 411, appoints Trimbakji Dhangar Sar Subha of Ahmedábad, 427.
- BAKKAR**: place, 520.
- BAKSHI**: military paymaster, 214.
- BAKTRIA**: independence of, 543.
- BAKTRIAN (GREEKS)**: 456 note 1, 535.
- BAKTRIANOL**: warlike race, 545.
- BAKULÁDEVI**: queen of Bhim I. (1169), 169; concubine, 181.
- BALABHA**: town, 524, 525.
- BÁLÁDEVAS**: Jain saints, 451 note 3.
- BÁLÁDITYA**: of Magadha, 75 notes 2 and 5.
- BALÁH**: Alberuni's era of, 78 note 1; starting of era, 81.
- BALAI**: Ptolemy's name for Gopnáth, 78 note 1.
- BALÁJI BAJIRAO**: Peshwa (1740-1761), sends an army to Gujarát and frees Rangoi, 338;

- his negotiations with Jawán Mard Khán (1750); imprisons Damáji and compels him to surrender half his rights and conquests (1751); includes Cambay in his share at the request of Momin Khán; imprisons all the members of the Gáikwár and Dabháde families and sends Rayghunáthrao to Surat, 331.
- BÁLÁJI VISHWANÁTH** Peshwa (1714 - 1720) advances to Ahmadabád and levies tribute, 295, 296; his negotiations at Dehli respecting the Gwalat tribute (1717), 389.
- BALLOKROS**, king, identified with Vilivayakura, 511.
- BALHARA**: 505.
- BALHARAS**: Rashtrakutas, 468, 469, 506, 509, 512, 514, 516, 518; rulers of Malkhet, 519, 525, 526, 527, 529, 530, 531.
- BÁL MÚTARÁJA**: see Mularaja II.
- BÁL YÚR**: battle of (1720), 301, 389.
- BÁLÁ, INOR**: residence of the Bala family, 314; captured by Bhagvantráy from Sardar Muhammad Khan Babi, 341; recaptured by Sardar Muhammad Khán (1761), 345.
- BÁLPH**: see Valph.
- BALISAR**: village, 127.
- BALISA**, village, identified with Wanesa, gift of, 111.
- BALKH**: 141, 545.
- BALKHA**: king of Málwa, defeated by Kunnárapála, 185.
- BÁLMAK**: 188, 196, 166.
- BÁLMAK**: grant of Vinayaditya Mangilarája, 108, 123; sacked by the Portuguese in A.D. 1531-347.
- BALUPATNA**, modern Pal, 510.
- BÁLYA ACHA**, Kasamachitra, ruler of Gujarát, 189.
- BAMIAN**: 197.
- BAMNOLOURA**: town, 510.
- BANA** poet, 14.
- BANAGARA** identified with Banmi, 538.
- BANAGASBÉ** Vamvasi 511.
- BÁNDHÚGAS**: calico-printers, 150.
- BANDHUVARMAN**: 76.
- BANIA**: Bana or Náryan, 511 and note 12.
- BANIA**: Brahman, lord of Munkir, 514.
- BÁNIA RÁNKA**: 525.
- BANQ**: town, 538.
- BANSAROVAR**: desert sea, 155.
- BAPPA**: Shuivite or Vaishnava pontiff, 84-85, 85 note 1.
- BÁPU GÁIKWÁR**: half-brother of the Gáikwár, a political refugee at Ahmedabád (1857), 412.
- BÁLA** island, 529.
- BÁRADA**: Porbandur, 524.
- BÁRADWÁJ** sage, 151.
- BARÁGI**: Varaha the Bour, temple of, 151.
- BARÁHMANS** Bráhmans, 530 and note 11.
- BARÁJI**, rest-house of, 471.
- BARÁKE**: Dvarka, 538, 544, 546.
- BÁRAPPÁ**: Tailapa's general and king of Lata or south Gujarát, killed by Mularája, 157, 158.
- BÁRÁTH**: Broach, 513.
- BARBARA**: 174, 534. See Barbaraka.
- BARBARAKA**: demon, 173 and note 3; non-Aryan tribe, 174 and note 1; 175.
- BARHARE**: town, 174 note 1, 538.
- BARHARFON** Shahbandur, 174 note 1, 538 544.
- BARHARIAS**, ancient Barbaraka, 175.
- BARNOSA** traveller (1611 - 1614), 219.
- BARNÁ**: hills 87, 185, 136; town, 513.
- BAROI**: main division of Mher chiefships, 136.
- BARDOLI**: 130.
- BARDAKEMA**, Porbandur, 538.
- BARDESANES**: 542.
- BARGOSE** Broach, 536.
- BARR** city, 518.
- BAROP**: Karka's grant at, 122, 124, 125; Dhruva's grant at, 126, 127; Kunnárapála's visit to, 183, granted by Kunnárapála to Kutuka, 184, 235; one-fourth revenue of, assigned to Piláji Gáikwár by Hamid Khán, 306; capture of, by the Marathas under Mahadaji Gáikwár (1734), 314-315, invested by Govindray Gáikwár (1775), 401; affairs at managed by Ray and Babuji Appa, 412; affairs of (1803), 413; Maratha conspiracy at (1857), 442-443.
- BAROZA** ancient name of Broach, 18.
- BARTU** Broach, 506, 509, 510, 511, 512, 513, 517, 520.
- BARTS** identified with Bhurch, expedition against, 109, 165, 167, 506, 513.
- BARTS**, Ardhe for lance shafts, 513.
- BARUZ** Broach, 506.
- BARWI** Velaval, 521.
- BARXGAZA**, Broach, 535, gulf of, 539, 541; exports and imports of, 545, 546.
- BASDEV** Krishna, 519.
- BASHE** reputed author of the Periplus, 542.
- BASHI** 505 notes 2 and 5, 516.
- BASARIKA**, poem, 546.
- BASSEIN** Mallikarjuna's inscription at, 186; destroyed by the Portuguese (1532), 347; ceded to the Portuguese by Sultan Bahádur of Gujarát (1534), 347; captured by the Marathas (1739), 322; besieged by General Goddard (1780), 109; treaty of (1802), 413 523, 546.
- BASDEV**, 521. See Basdev.
- BATHA**: Bet, 506 and note 1.
- BÁVA**: 85 note 1. See Bappa.
- BAWARIS**: people of Kutch and Somnath, 508; Mith pirates, 517, 521.
- BAZÁNA**: Bana or Náryan, 511 note 12, 520.
- BÁZ BARÁDUR**: the last of the independent chiefs of Mándu, 355; Malik Bázáq kills his brother Daulat Khán; the defeat of, by the Gondis; his poetic love of Rupmati or Rupmani; expulsion of, by Pir Muhammad, Akbar's general (1560); his restoration and the death of Pir Muhammad in 1561; recapture of Mándu by the Mughals under Abdullah (1562), the retirement of, to Gondwal (1562); accepts service under the Mughals (1570), 369-371.
- BECAE**: village 537, 546.
- BENDA**: Bhiwandi creek, 510, 542.
- BENGÁL**: 124; original place of Srigaudas, 161,

- 469, 491; Gurjjara Vatsarāja's success in 527; under Tibet, 528.  
**BRENICE** 536, 543.  
**BERENIKE** town on the Red Sea, 535.  
**BERUNI**: 81. See Al Biruni.  
**BESAB**. 516 and note 5.  
**BET**: island and fort, seized by Yāghers, captured and destroyed by the English (1859), 446-447.  
**BIĀBHĪYA**: minister of Bhima II., 200.  
**BIADHAB**: river, 160.  
**BIADHAKĀLI**: inscription in the temple of, 79 note 3, 81, shrine of, at Pttan, 190.  
**BIADHVSAB**: inscription in a temple near, 172, in Kachh, expedition against the chief of, 201, inscription slab at, 204.  
**BIADHVSARA**: see Bhadravar.  
**BIĀHĪLA**: 180 note 2.  
**BIAGVASTAT**: Dh., 111, 117 note, 124, 127, 129 note 3, 137, 138, 141, 144, 145, 167 note 1, 165, 541, 544.  
**BIAGVANTHIV**: Peshwa's deputy, marches on Cambay; is surrounded and taken prisoner by Momin Khan; his release, 338. His engagements with Nizam Khan (1754), 339, conquers Bālsamur and levies Peshwa's share of the revenue, 341.  
**BIAGVAT**: share system of levying land revenue in kind, 279.  
**BIADHAB**: shrine of, 154, Buddhist guardian, 458 and note 1.  
**BIĀNDARKAB**: Professor, 110, 127, 541, 546.  
**BIANIGPTIA**: Gupta ruler (511), 72.  
**BIARODS**: 161.  
**BIARITRIDAMAN**: nineteenth Kshatrapa (278-291), cons of, 48.  
**BIARUCH**: see Barus.  
**BIARA**: military officer, 125.  
**BIARĀKA**: 80, founder of the Valabhidynasty of Gurjjara descent, cons ascribed to him (509-520), 85, 86, 87, 136.  
**BIARĀ**: reduced by Mahmūd of Ghazni, 168.  
**BIARĀKA**: settlement of, 135. See Bhatarika.  
**BIARS**: genealogists, 451 and note 1.  
**BIATĀRAKA**: attribute of priests of Digāmbhara Jain sect, 85.  
**BIATTIS**: 137.  
**BIĀLLINGI**: Salva tribe, 534, 10.  
**BIĀVA**: BHĀSPATI: state officer at Somnātha, 193.  
**BIĀVISHYA**: early Rāshtrakūṭa prince, 120, Pitrān, 465.  
**BIĀU SĀDEN PAVAR**: Baroda officer, his intrigue (1857), 442, 445.  
**BIĀVNAGAR**: town and creek, 78, state collection, 471, 534.  
**BIĀVSINGH**: of Viramgām, invites the Marāṭhās to Viramgām and expels the Kachhīs from the town (1735), 317; attacks the fort and expels the Marāṭhās, 323.  
**BIHLMĀL**: 466. See Bhinnāl.  
**BIHLS**: 451, 532.  
**BIHMA I.**: Chaulukya king (1022-1064) succeeds Durlabha, leads victorious expeditions against the kings of Sindh and Chōḍi; Kulachandra attacks his capital Anahilavāḍa; he escapes at the advance of Mahmūd of Ghazni (1021), his plates, 79 note 2, 163-170, 181; builds the Somnātha temple, 190, 522.  
**BIHMA II.**: Chaulukya king (1179-1212) succeeds Mularāja II.; his grants, 195 and note 3; his nickname Bhilo (Simpleton) 196, 470.  
**BIHMADIVA I.**: 79 note 2, 181, 190. See Bhuma I.  
**BIHMADIVA II.**: Chaulukya ruler, 229. See Bhuma II.  
**BIHMAPALLI**: town, 196.  
**BIHMASIN**: (553), 169.  
**BIHMA SETHA**: husbandman, concealed Kumbhāpala, 182; is appointed head of the royal bodyguard, 184.  
**BIHMOR**: temple of, near Dumas, 403.  
**BIHMAL**: Shrivat town, 3 and note 3; expedition against, 109 and note 2, Gurjras of, 115, 169, Chāḍagās connected with Chāpas of, 139-155 its king sides with Mularāja, 160, description of, 449, people of, 150, objects in the town, 151-52, surroundings, 152-156; of Jankop, 156-158, sun temple at, 459-461, legends, 161-163; caste legends of, 163-165, history, 165-171; origin of the name of, 166 note 6; 469, descriptions at, 171-188, Gurjar chief of, 189; affliction of, 513 note 9, 526.  
**BIHMA**: king of Mulwa 163, 164, 180, 453 note 1.  
**BIHNSLA RĀJA**: Sardār and kinsman of the Gaikwar (1867), his indignities, 112; obtains pardon at the intercession of the Gaikwar, 113.  
**BIOPAL**: town, 138.  
**BIOPALADIVI**: installed as Pattarāni or queen-regnant of Kumarapala, 181. See Bhupālekadevi.  
**BIOPALBHISHI**: Sage, 461.  
**BIOPALBHISHI**: modern Broach, 127; Kumārāpala meets a soothsayer at, 183.  
**BIHNAVĀVA SĀPIACHĀVA**: son of Kasambhātra, king of Gujārāt, 189.  
**BIHUVADA**: 156. See Bhuvah.  
**BIHUMS**: 215 note 2, 451 note 3.  
**BIHUMIKA**: 137.  
**BIHMIT**: fort, capital of Mbers, 136, 137, 138.  
**BIH PĀLADIVI**: wife of Kumarapala, 182. See Bhupālekadevi.  
**BIHVA**: Chaulukya king, kills Jayasekhara, 150-157.  
**BIHVANADITYA**: Mularāja's ancestor, 157.  
**BIHVA**: another name of Chumunda, 154, 157.  
**BLA**: uncle of Mularāja, 156, 160.  
**BIYAPUR**: 10. See Vijayapura.  
**BIHANA**: poet (c. 1930 A.D.), 156.  
**BIHRI CH**: Broach, 507.  
**BIHARA**: town, 538.  
**BIHSA**: Gupta inscription at, 67.  
**BLA**: Captain, political agent, Radhanpur, 441.

- BOLINGE**: 534, 546. See Bhaulingi.
- BOMBABO**: name of a well, 453.
- BOMBAY**: island, burned by the Portuguese (1532), 347; harbour, 533.
- BOMBAYS**: leatherworkers, 451.
- BORE**: 545.
- BORO BUDDOR**: Javan town, 489.
- BORSAD**: 126, fort, built by Jagjivan Patár, Marátha leader (1712), 325; given up by Rangon to the Muslims, 326, siege and fall of, 332, besieged by Momu Khan, 339; recovered by Rangon from Hamba, adopted son of Khanderao Gaikwár, retaken by Khanderao and Damáji Gaikwár (1748), 396.
- BOSARI**: Kumárapála's companion in exile, 182; appointed viceroy of Lata or south Gujarát, 184.
- BORRA**: hill range, 466.
- BOUDAIA**: town, 534.
- BOURHUALA**: Jalálpur, 546.
- BOURMIER**: Mr., Governor of Bombay (1759), 343.
- BRABMA**: inscription in the temple of, on the Chitoda fort, 188, king of the Indians, 531.
- BRABMAGUPTA**: astronomer (628), his work on astronomy called *Brahmagupta Siddhánta*, 138, 453 note 1, 467.
- BRABMAKIND**: Brahma's pool, 452, 462, 463.
- BRABMAN**: 530, 531.
- BRABMAN (TAK)**: town, 519.
- BRABMASABOVAR**: lake, 454.
- BRABMASIDDHÁNTA**: work on astronomy by Brahmagupta, 453 note 1.
- BRABMAVAKA**: family name of Prachanda, 123.
- BRABMANTM**: capital of Bhruvijaya, king of Java, 489.
- BRIGGS**: Colonel (1827), 383.
- BRINASPATI**: Ganda Bháva, repairs the Sonanátha temple, 189, 194. God, 461.
- BRINATAMUHA**: work by Varáha Mihira, 540.
- BRITISH**: the, intervention for protection of the chiefs of Kathiawá against the Mulakgori system, 421-422, secret treaty of the, with Bhávi; reward Rávi with a village, 413, make a fresh treaty with the Gaikwár, consolidating all previous engagements into a single treaty and constitute themselves arbiters in all disputes of the Gaikwár with foreign powers and the Peshwa (1805), 115. See English.
- BROACH**: Valabhi grants in, 86, district, Gujjar dynasty of, 107, 113; Valabhi king's camp of victory at, 114; described by Hsiao Tsang; port, submitted to Pulakesi II., grant at, 116, 117, 126; Dhruva II.'s Bágumra and Barola grants made at, 127; a soothsayer at, promises Kumárapála the throne, 185, Lavaprasáda's fight with Singhana at, 199, insurrection at (1325), 513-514, siege and relief of (1347), 230, (1412), 235; plundered by the Maráthas (1675), 387; plundered second time by the Maráthas (1685), 387-388; captured of, by the Mátás and Momás (1691), 288; siege of, by Damáji and the Maráthas (1741), 324, 326, defended by the Nizám's lieutenant Nek Alqm Khan; raising of the siege by Damáji; concessions of a share in the customs revenues of, to Damáji by the Nizám, 324; governor of, becomes independent (1752), 334; capture of, by the English (1772), 401; given over to Sindia in 1802, 110, captured by the English from Sindia (1803), ceded to the English by the treaty of Sirje Anjanagou (1803), 414, its different names, 513, 521, 525, 536, 545, 546.
- BUCCADE**: weaving of, at Ahmedábád, encouraged by emperor Aurangzib (1703), 292.
- BUCCAPALA**: Jalálpur, capital of the Asini, 534.
- BUCCLE**: Captain, political agent of Rewa Kanth (1857), 139, 443.
- BUDDHA**: idol of, 531, introduction of, in China, 530.
- BUDDHAYARMAN**: ruler of Kaira, 108, 110, 111; Kalaeburi prince, 114.
- BUDDHAGUPTA**: Gupta king (A.D. 494-500), 71, 72, 135; overthrown by Toramana, 136.
- BUDDHISM**: state religion in Cambodia, 502; religion in Gujrat, 530.
- BUDDHISTS**: 531.
- BUDDHA**: town, 538.
- BULLER**: Dr., 79, 111, 113, 117 note, 155, 156, 157, 161, 174 note 1, 195 note 1, 466.
- BUILDINGS**: constructed in Siddhamaga's time, 179-180.
- BUNDILKHAND**: Krishna's son Jagattunga, lived at, 130.
- BURGESS**: 533.
- BURHANPUR**: plundered by the Maráthas in 1675, 387.
- BURMA**: 527.
- BURNS' TRAVELS INTO BOXHARA**: 544.
- BYZANTION**: Vajrayanti, 546; Chiplún, 540.
- BYZANTIUM**: 546.
- CACHIA**: 471.
- CAESI**: Kekayas, 533.
- CATINGON**: Point Golávari, 533.
- CAMUVA**: Stambhatirtha, 123; Kumárapála, repairs to, 182, Jain temple at, repaired by Kumárapála, 190; plundered by Alafkhán's army, 165, sack of (1573), 220 and note 2, 221 and note 2, 225 and note 2, sack of (1347), 230, 232, 235; siege of, by Timbakrao Nalabade, 306; Momu Khan appointed governor of, 311, 317; customs house at, 323; included in the Peshwa's share of tribute (1752), 334; failure of a Marátha attempt on (1753), 338, 398; interview of Rávi of Buoda with Governor Duncan at (1800), 112, Musalmán preacher of, 512, 513, its different names, 514; importation of horses into, 515.
- CAMBODIA**: 498-501; origin of the name Kamboja, 498 note 4; Brahmanic dynasty of; inscriptions, king of, an embassy from to China (67), 499; alocs, 528.
- CAMUNDA**: 471.
- CANDRAGUPTA**: 532. See Chandragupta.
- CANE**: port, Hsu Ghorah, 537.

- CAPITALIA** : identified with Mount Abu, 534.
- CARNELIANS** : 78 note 1.
- CASHTAN** : 530. See *Chastana*.
- CASTANEDAS** : history of the Portuguese in India up to A.D. 1538, 349.
- CASTES** : Gujar underlayer in Gujarāt, 4; legends of, 163-465.
- CAULUKYA** : 526. See *Chaulukya*.
- CEYLON** : 509, 516, 536.
- CHACH** : (631-670), 519.
- CHACH NAMA** : Arabic history of Chach, 519.
- CHACHIGA** : Mother Varna of Dhandhuka, father of Hemachandra, 191.
- CHAGANJANG** : white people, 501.
- CHAHADA** : son of Udaya and younger brother of Bhada rises to a high position under Kumpatapa, 170; leads an expedition against Simhar; title of Rajacharatta conferred on him, grants half a village, 187.
- CHAKRAVARTI** : Jula saints, 151 note 3.
- CHALUKYA** : grant of, 166, 467.
- CHALIKYA** or **CHALKYA** : see *Chaulukya*.
- CHALUKYA** : Dakhan dynasty (A.D. 552-973), 156; early trace in Gujarat of its rule, come from the Dakhan and establish themselves in Gujarāt, their grants genealogy, 107-112.
- CHAMPANIR** : attacked by Ahmed I, (1118), 237, taken by Mahmud Beghela and made his capital under the name of Muhammadshah (181) 247; captured by the Marathas (1728), 308, 367, 368, 391-392.
- CHAMUNDA** : Chavada king (A.D. 880-908), 154, 155, son of Mudaraja Chaulukya, slays in fight Dattappa and Barappa, 159; his reign (A.D. 997-1010), installs his son Vallabha goes on pilgrimage to Benaras, is insulted by the Malwa king, 162. The family stock of Hemachandra, 191. Ruler of Vantali, killed by his brother-in-law Viradhaval Vaghela, 200.
- CHAMUNDA** : shrine of, 449, 457, 458.
- CHANDALA** : memals, 531.
- CHANDREKA** : dynasty in Bundelkhand, 178.
- CHANDRESHWAR** : shrine of, 162 and note 1.
- CHANDIS** : 461.
- CHANDIDFVI** : shrine of, 452.
- CHANDISH MAHIDEV** : 462, 463.
- CHANDADANDA** : officer of P. No. 11 takes Pori, 107.
- CHAND LHAN** : illegitimate brother of Sultan Bahadur of Gujarāt, is supported by the Portuguese (1532), 347, 367.
- CHANDRADITYA** : Muladapa's ancestor, 157.
- CHANDRAGUPPA** : founder of Maurya dynasty (B.C. 319), 13-14.
- CHANDRAGUPTA I.** : third Gupta king (A.D. 349-369), 61, 67.
- CHANDRAGUPTA II.** : fifth Gupta king (A.D. 396-415), inscriptions, coins, founded Gupta era (291), 65-67, 86, 129.
- CHANDRAPURA** : identified with Chandavar near Gokarna, 171 and note 1.
- CHANDRAVATI** : visited by Kunharapala, 185, 188; capital of Visaladeva, 204; Parmara possession, 170.
- CHANGIZI** : coin, 222 note 2.
- CHANGODEVA** : original name of Hemachandra 191.
- CHAPA** : dynasty, 133 and note 1, family of Bhimaji, 139, 463 note 2, 526.
- CHAPOTAKATA** : Gurjara origin of, 467; Sanskrit form of Chivada, 150.
- CHARACTER** : of Valabhi copperplates, 80.
- CHASHFANA** : second Kshatrapa (A.D. 130), coins of, 29-31, 32.
- CHARMA** : tribe, 532, 534.
- CHARRIS** : pavilion works, 153.
- CHITRAPANA** : Andhra king, 58.
- CHATHANS** : Rajputs of Satohar, 468, 469. See *Chohans*.
- CHAVL** : 516. See *Chaul*.
- CHAVLUKYA** : Sanskrit form of Chalkya, 156, ruling dynasty of Anahilavada (A.D. 961-1212), invasion of Somnatha by Mahmud of Ghazni, remission of pilgrim-tax, architectural buildings, ascendancy of Jainism and division of the kingdom among the nobles under the, 156-197, kingdom of, 465.
- CHAVRAS** : ministers of Kachh after the fall of the Sumras, 517, dynasty, 526. See *Chavadas*.
- CHAVIN** : contribution, 388.
- CHAVADAS** : of Anahilavada (720-956), 124; of Gujara race establish a small chiefship at Panchasar which falls in A.D. 696; establish a kingdom at Anahilavada, their genealogy, 149-155, 163 note 2, their settlements, 164, 165, 166, feudatories of Bhimaji, 469; their affliction, 513 note 9. See *Chapas*, *Chauras*, *Chapotakas*, *Chavotikas*, and *Chavatis*.
- CHAVAN** : Gurjara surname, 468.
- CHAVOTAKA** : kingdom of the Chavatis, afflicted by Arab army, 109. See *Chavadas*.
- CHAVOTAKAS** : identified with Chavadas of Panchasar, 150, 151, 465, 466, 467. See *Chavadas*.
- CHAWARAS** : identified with Chapas of Bhimaji, 139. See *Chavadas*.
- CHEDI** : era, 57, 58 and note 1, 114; dynasty, 114, modern Bundelkhand, 130, 163; its king, present at the bridegroom-choosing of Durlabhadevi, 163; its king strangled, 186-187, 169. See *Trakutaka* and *Kalachuri*.
- CHIMULA** : modern Chaul, 533.
- CHENAB** : river 538.
- CHERA** : kingdom of, conquered by Pulikesi II, 111.
- CHILUL** : port, 351, 513, 516. See *Chaul*.
- CHHAGALAGA** : 61 note 3, 66.
- CHHANDANTS(SANA)** : work on Prosody, compiled by Hemachandra, 193.
- CHIKHI** : given to the English, 412.
- CHIMANAJIRAV** : brother of Bajirao Peshwa, captures Chimpulser, 309, 322, 391, 392, is appointed Peshwa's Subhedar of Gujarāt, 411.
- CHIMLA** : army of, marching from Magadha to Banian 197; vessels coming from, 513, 522, 528; religion of, 530.
- CHITRAN** : Mallikarjun's inscription at, 186; 510, 516.
- CHIRIKYA** : see *Chaulukyas*.

- CHITORA**: fort, 181; inscription of Kumārapāla at, 188.
- CHITOR**: Mauryas of, afflicted by Arab army, 109 note 1, 513 note 9, visited by Kumārapāla in his exile, 183.
- CHITRAKANTHA**: breed of horses, 111.
- CHITRAKUTA**: peak of Abu, 169. modern Chitor, 183, 369.
- CHUDHANS**: tribe, Ajmīr kings, 167, 463 note 2, 465, 470; see Bhūmā, 471.
- CHILA**: kingdom, conquered by Pulakēśi II., 111.
- CHORYADA**: Vēlari betel vine cultivators' settlement at, 113 and note 3, zikāh in Kathiavāda, 208 and note 3.
- CHORA** UPRISER, defeat of Tatva Topi at, 445.
- CHRISTIANS**: in Ajmīr, 517.
- CHRONICLES**: Jani 156, Anahlavādā, 156, Jani, 179, 201, 202.
- CHRUSHI**: Kausha, 533.
- CHRUSHORA**, 534.
- CHUHARI**: fort, 180 note 2.
- CHUDACHANDRA**: first ruler of Vantahā, 138, 139.
- CHUDASMAN**: invading tribe, originally of the Abhira tribe, 137; foreigners (800-940), 138-139, 178. See Ahir.
- CHUNAB**, 513, 517.
- CINTRA**: in Portugal, inscription from Somnātha found at, 205.
- CIAPDIUS**: reign of (11-51), 536.
- CODE**: a civil and criminal enacted by Mr Mountstuart Elphinstone (1827), 136.
- COINS**: of Euclides (c. 1554, 16-17, of Apollodorus, 18 19, of Menander, 18 19, of Nahapāna, 21, 25, Gupta, 29; of Chashtana (A.D. 301), 29 30, Sopari *Shapur* or mound, 38, hoards of, 48-49, 57, 60; of Samudragupta, five varieties of 62-63, 66, 67-68, Gupta, 70, 71, of king Mahāpāda, 136, Hindu sun, 142.
- COMBOST**: Cambodia, 499.
- CONDITION**: of Gujārāt (1297-1760), 217-228.
- CONJEYRAM**: visited by Kumārapāla in his exile, 183.
- COPPERPLATES**: Valābhi, description of 79-80, of Gujārāt Chālukyas, 108, of the Gujārāas, 113-114, three forged, 117 note 118, 121, of Bhūma I., 163.
- COPPER COINAGE**: (1668) introduced into Gujārāt by the viceroy Mahābat Khān (1662-1668), 281.
- CORREIA**: Portuguese historian (1512-1550), died at Goa (1550), 349.
- CORYAT**: English traveller (1670), 377.
- COSMAS**: Indikopleustes, 86, 143, 146.
- COTTONARA**: Kadattanādu, 337.
- COWRIES**: shell money, 527.
- CROWN LANDS**: under Mughal administration, 211.
- CUNHA**: Nondā, Portuguese viceroy in India (1629) sends an expedition against the island of Diu; his defeat; supports Chānd Khān; sends an embassy to the Court of Humayūn; makes peace with Sultān Bahādur (1531), comes to Diu in 1536; murder of Sultān Bahādur at a meeting with (1536), 347, 348.
- CUNNINGHAM**: General, 86, 144, 178, 533, 534, 538.
- CURRNEY**: under Mūsalmāns, 222 note 2.
- CURRI**: Gupta conquest of, 70. See Kachh.
- DABAI**: see Chedi.
- DABALWAR**: plundered by Mahānād of Ghazni, apparently Delvada, 166 and note 2, 522.
- DABHOI**: fort, its building ascribed to Siddharāja, 179; in south Gujārāt, its fortifications repaired by Visalakṣa, 203, Gāikwār's station in Gujārāt (1732), 391, surrendered to Raghobā and Colonel Keating, 405, occupied by General Gōddard 1789, 108.
- DABSHETNIS**, ancient royal family, 168.
- DADKA**: minister of Siddharāja, 172.
- DADRA I.**: Gujārā king of Nandol (580), 108, 111, in Gujārā feudatory of Bhūmal Gujārā kingdom, 115.
- DADRA II.**: Gujārā king (650-650), 56; Gujārā chief of Nandol, helps the Valabhis, 85, his grand, 111, 114, 115, 116.
- DADRA III.**: Gujārā king (680), 114, feudatory of Javānshāh the Chāhukya; first Sūya of his family adopts the Pūrāṇic pilgrimage traced to Kūṇa, 116-117.
- DADRI WELL**, 155.
- DADHAPUR**: fort, 170 note 2.
- DADHARI**: village granted to Devayrasāda, son of Keshavnāga, for maintenance, 170, residence of Kumārapāla's ancestors, 181.
- DAHNAV**: perhaps Kāndē, 520.
- DAHRA-SAL**: Thakutā king (157), 55, 58.
- DAHMAN**, 534.
- DAHMANABHAI**: Dākshināpatla, 545.
- DAROR**: Pilāp Gāikwār assassinated at (1732), 313.
- DAKSHINA**: founded by Khanderāy Dābhāde, renewed by Bagra I (1731), 393.
- DAKSHINAPATNA**: Dakkhan, 545.
- DAIMAR**, 109.
- DAMADANIS**: envoy, 542.
- DAMADASARI**: twelfth Kshatrapa (230), coins of, 45. Sixteenth Kshatrapa (250-255), coins of, 47.
- DAMAJI**: founder of the Gāikwār family; distinguishes himself at the battle of Balapur (1720), 389.
- DAMAJI**: Gāikwār, son of Pilāji, starts Bhils and Kols to revolt (1733), 391; levies tribute from the chiefs of Sorath (1738), 321; attacks Chūmal Kols and burns the Chidamgar village, 321-322, appoints Rangoji as his deputy in place of Māhārāo Khān (1741), 323; besieges Broach and receives a share in its customs revenues (1741), 324, 395, goes to Cambay from Sātara, 326, defeats Peshwa's army but is treacherously seized by the Peshwa and imprisoned (1751), 397, is released; his negotiations with the Peshwa (1752), 397, 398; returns to Gujārāt and is reconciled to his brother Khanderāo, 330, 396; captures Kapadvanj and appoints his deputy

- Shevakrāi to collect his share of revenue, 338; joins the Peshwa's deputy to invest Ahmedabad (1756), 340; helps the Rāo of Kachh in his expedition against Smāh, 342; defeats Momin Khān at Cambay and recovers Visalnagar, Kherah, Vainagar, Bijapur, and Patan, 345; captures Bālasinor (1761), 392, accompanies the Peshwa to Dholi and escapes from Pāmpat (1761), 399, marries a daughter of the Gohāl chief of Lāthi whose dowry in land gives him the standpoint in the heart of Kathiavār, 418, his death (1768), 400, quarrels for succession in his family, 400.
- DAMAN: coins found at, 58; burned by the Portuguese (1532), 217.
- DAMARA: Bhima I.'s general, takes Kāna captive, 163.
- DAMPANA: eleventh Kshatrapa (A.D. 226-236) coins of, 45.
- DAMASHRI: twenty-third Kshatrapa (A.D. 320) coins of, 50.
- DAMAZARA: fifth Kshatrapa (A.D. 153-168) coins of, 39-40.
- DAM: coin, 222 note 2.
- DANDAGIRYA: city, 533.
- DANDAH: village, 169.
- DANDHAI: local name of Kadi district, 203 note 3.
- DANG: forests, 508.
- DANDAKA: Mubārāj's uncle, 156, 160.
- DANDARAJAMRI: 207 note.
- DANIA: 464.
- DANTILOGA: inscriptions at Eghna, 120, 120 note 122, 467.
- DANTIVAJMAN: 120, son of the Rashtrakuta prince Narka, his joints, 125-127.
- DARĀ SHIKOH: Prince Mubārak, twenty-seventh viceroy of Gujarat (1618-1658); sent to Kathiavār, 280; obtains the transfer of Mithal from Gujarat to Berar, is defeated at Dholpur by Muzal and Amrangzoh, flies to Dāli and thence to Lahore (1688-1682); his rebellion; is defeated at Ahmedabad, flies to Smāh; is taken prisoner (1689), 282.
- DARHAVATI: modern Dahoda, 203.
- DARLE: birds of the Upper Indus, 533.
- DARI: tribe, 53.
- DARJIS: takers, 451.
- DARJA KHAN: Gujarat governor (1373), 231.
- DAROGHAN: official, 214.
- DARUR: 541. See Dhārur.
- DARAR (MIS): see Atit.
- DARARATHA: Asoka's grandson (B.C. 210), 14-15.
- DARTADEVI: Gupta queen, 65.
- DAUD KHAN PANNA: forty-sixth viceroy of Gujarat (1714-1715); religious riots at Ahmedabad; his introduction of Dakhan Pandits into official posts, 298, 299.
- DANDU DĀTĀTRI: commander of Ahmedabad garrison (1753), 338.
- DANLATAV SINHA: treacherously seizes Nāna Phadnavis and A'ba Shetukar (1797), 411.
- DAYAKA: kingdom of, 64 and note 2.
- DEBAL: expedition to, 506, 511, 512, 513; identified with Karachi or Thatta, 508 note 2, 514, 517, 521; perhaps Dm, 523, 547.
- DEBARLOS: Portuguese historian (1570), 349.
- DECADAS: (1497-1539), a work by De Barros, a Portuguese historian, his death in 1570, 349.
- DEBADRA: reservoir, 180 note 2.
- DEGADI: Prachandi's ancestor, 129.
- DIAMACHOS: ambassador, 534.
- DEHLI: fall of (28th September 1857); emperor of, in a treasonable correspondence with the Nawab of Badkhanpur, 411.
- DILASPAU: Major, Political Agent of Dhār (1895), 384.
- DELVADA: town, 233 and note 3.
- DEMETRIUS: king of the Indians (B.C. 190-165), 16.
- DETA VAILE: traveller (1628), 224 note 2.
- DIOLI: grant from 168, 469, 511.
- DIOPALI: town, identified with Deoli, 541.
- DEKA ISMAIL KHAN: 538.
- DIKANG: identified with the Telugas, 531.
- DI-SAS: position and duties of, 210, 212, 223, and note 2.
- DI-SANTRIS: Saturday oil-beggars, 451.
- DI-SANAMATA: Prakrit work on local and provincial words compiled by Hemachandra, 193.
- DISOIZA: Emmanuel, captain of the fort of Dm (1536), 317.
- DEVACHANDRA: Jain priest, visits Dhandluka, carries Mahāgodeva to Kuntivati, changes his name from Ichindha to Hemachandra, 191.
- DEVATI TAKPAR: lieutenant of Dāmaji Cankar, defeats Abdul Aziz (1741), 378.
- DEVATADIVI: sister of Kumarapala, married to Anaraji king of Sakambhari, 181, 182. Daughter of Karmadeva, the last Vaghela chieftain, married Khazar Khān, 205.
- DEVATAS: 465.
- DEVANAGARI: character, 50.
- DEVAPRASADA: son of Kshemraj, 170; recommended by Karna to Siddharaja, burns himself on the funeral pile, 171.
- DEVAPURIA: Kushan name, 64 and note 5.
- DEVARAJA: early Rashtrakuta prince, 120; grantor in Dhruva's Baroda grant, 126, 470.
- DEVASRI: lady of Udumbara village, feeds Kumarapala in exile, 182, 184.
- DEVATRI: S'vetambara Jain Acharya, holds a religious discussion with Kumdachandra, Digāmbhara Jain Acharya, 181 and note 3; Hemachandra's teacher advises Kumarapala to rebuild the Somanātha temple, 189.
- DEVAYANI: wife of Yayati, 460.
- DEVAYO: village, 181.
- DIVGANI: Danlatāhid, 229 and note 4.
- DEVOTION: exultation of, to Viradhavala, 203.
- DEWACHABASNI: Wagher chief in command of the fort of Bot, 447.
- DWLA RAJPUTS: 462, 463.
- DWAR RAJPUTS: 465. See Dewla Rajputs.
- DHAMMAKANTO: Yavan evangelist (B.C. 230), 13.

- DHAN**: Mehr of Dhandhuka, 87 note.
- DHANAJI JADHAV**: enters Gujarat and defeats the Muslims at Ratipar and Baba Pirāh ford (1705), 204.
- DHANAKATAKA**: 533.
- DHANUJAR**: local name of Pāṇpur zillah, 208 note 3.
- DHANUJGA**: Parmāra chief of Xbu, subdued by Vimala, general of Bhūma I., 169.
- DHANUJKA**: Hemachāra's birthplace, tūka town, 191 and note 1; district under the Vaghelas, 198, 470.
- DHAR** plateau, 352; capital of the old Hindu kings of Malwa, 357; Anandray Pavār settles at (1751), 382; defeat of Sultan Hoshing by his uncle Muzaffar I. of Gujarat (1408), 358.
- DHAR**: capital of Malwa, attacked by Siddharaja, 178; carving on pillars of a mosque at 180. See Dhār.
- DHARNIDHAR** gateway, 456 note 1.
- DHARANIVARĀHA**: Chapa king of Wadhwa (914), 134, 166, 169.
- DHARAPATEA**: Valabhi king, devotee of the sun, 83.
- DHARAPURI**: sacked by Karna, 163.
- DHARASENA I.**: Valabhi king, 114, 115.
- DHARASENA II**: Valabhi king, copperplate of, 79 note 1.
- DHARASENA IV.**: Valabhi king, 116.
- DHARĀSĀYA JAYASIMHA**: see Jayasimhavarman.
- DHARĀVARSHA**: another name of Dhruva I., also of Dhruva II., 126.
- DHARS**: tribe, 533.
- DHARUR**: town, 541, 545.
- DHAWALA**: king of Bhinapalli, 196; Vaghela chief (1160), 206.
- DHAWALAGADIA**: see Dholka.
- DHAYALPRA**: Prachanda's father and general of Krishna Akshavarsha, 129.
- DHENUKAKALA**: Dhenukataka, 533.
- DHINIKI**: forged grants at, 87; village, 137.
- DHODDI**: Brahmana, Tema granted to, 131.
- DHOLI**: village, battle at (1735); defeat and death of Solirab Khān at, 316.
- DHOLKA**: Malavya lake at, built by Siddharaja, 180 note 2; district under the Vaghelas, 198; assigned to Rataning Bhandari (1735), 315; defeat of Rangon by Rataning Bhandari at (1736), 317; defeat of the Marathas at (1741), 324, 517.
- DHOLPUR**: battle of (1658), 282.
- DHOZAR**: fort in the Ajntha range; defeat of Raghunathrao Peshwa at (1764), 400.
- DHRUVA**: feudatory Rāshtrakūṭa ruler of Gujarat, 121, 122.
- DHRUVA I.**: (795) Dakhan Rāshtrakūṭa king spreads his conquest from South India to Allahābād, 123; Gujarat Rāshtrakūṭa king, his war with Dakhan Rāshtrakūṭa king Amoghavarsha, 121, 126, 466.
- DHRUVA II.**: (867) Gujarat Rāshtrakūṭa king, opposed by Dakhan Rāshtrakūṭa, his relations by the Gurjjaras and by a Mihir king, 121, 126-127, 136.
- DHRUVA III.**: of Broach, his grant, 468.
- DHRUVAPĀTU**: Valabhi king, 79.
- DHRUVASENA I.**: first Valabhi king (526), follower of Vaishnava sect, 83; his grant, 86, 116.
- DHULAKA**: town, 513.
- DHUMRAA**: first Paramāra sovereign, 470.
- DIA BAHĀDUR**: governor of Māndu; defeated and slain by Mulharāy Holkar (1732), 382.
- DILAWAR KHAN (GHORI)**: founds an independent kingdom in Malwa, adorns the hills with buildings and strengthens the defences (1387-1405), 352, 357; entertains Mahmud Tughlak (1398), 358.
- DIMARI**: tribe, 534.
- DINARS**: coins, 66; found at Somanātha, 167, 515 and note 5, 522.
- DIPOROS**: 535, 536.
- DIONYSIOS PERIEGES**: 537, 546.
- DIOXYLUS**: Greek writer, 532, 535.
- DIRMAYS**: coins, 469 note 2, 515 note 5.
- DISA**: conspiracy at (1857), 441.
- DISCUSSIONS**: literary and poetic, held at Siddharaja's court, 181.
- DISORDER**: in Gujarat (1535-1573), 220-221, 225.
- DIV** island, attempts of the Portuguese to obtain a footing on their defeat (1531), fort; Emmanuel De Souza the governor of, meeting of the Portuguese viceroy Nuno de Cunha and Sultan Bahadur and the death of the latter at (1536-1537), 220, 317, 349, 350, 351; place of call for China ships, 197 note 1.
- DIVAN**: Mughal chief secretary, 211, 214.
- DIVISIONS**: ancient Gujarat, 6-7.
- DOGBOIO**: Portuguese writer (1609), 349.
- DODALA**: hill range, 456.
- DOHAD**: 124, inscription at, 175, 179; restored by the English to Smidha under the treaty of Siraj Anjungaon (1803), 414.
- DOVOYAN**: Colonel, commander of the expedition against Bet (1859), 446.
- DORSEOND**: crushes a revolt in Nepal and establishes his supremacy in Bengal (703), 501.
- DONGA**: perhaps Dugad, 540.
- DRACHME**: Greek coins found in Kāthiāvāda, 10, 17, 18.
- DRAGON WORSHIP**: 502.
- DRACHMAI**: 535, 545.
- DRAMA**: distribution of the coin, 130; coin, 151, 201.
- DRONAMMA**: military officer, 125.
- DUDIA**: quells a Samra rising, 517.
- DULAI**: rite, 531.
- DULAKA**: Dholka, 509, 517.
- DULEA**: 511. See Dholka.
- DUMAS**: village, 403.
- DUNAN**: Jonathan, Governor of Bombay (1802), 405; assumes chief authority in Surat, 411; his interview with Rājā of Baroda, 412; arranges about the collection of tribute in Gujarat and Kāthiāvāda by the employment of a British contingent, 414.
- DURAND**: Colonel, Resident at Mhow, driven out by the troops of Holkar; takes refuge in Bhopāl, 438.

- DEBAGHATTA**: father of Nemūhtya, 125; father of Nirāṣana, 125, 126.
- DEBAGADAS RARHON**: incites prince Akbar to rebellion, 288; causes disturbances in Marwar (1672), 289; is reconciled with the emperor (1698), 290, obtains for Ajitsing pardon and lands in the districts of Jhalor and Sicheor (1699), 291, is appointed governor of Putan (1703), 291, intrigues against (1704), his escapes, 291-292, joins Ajitsing in his rebellion; takes shelter with the Kols, his disappearance, 295.
- DEBAGARH**: identified with Jimgadh, 130.
- DEBLAKHA**: Chandikya king (A.D. 1011-1022), attends the *stanmān* or choice marriage of Durlabhadra and is selected as groom, builds a lake at Anulavata and abbeys in favour of his nephew Bhumi, 162-163.
- DEBIAHADRA**: sister of Mahendra Raja of Nandol, selected Durlabha Chandikya king at a *stanmān*, 162-163.
- DEBLAPHASAGHARA**: Idol, built at Anulavata by Durlabha the Chandikya king, 163.
- DEBLAPHASASA**: 168.
- DEBAYASAGH**: saga, 161.
- DESSALA**: king of Siamblama, 171.
- DETAKA**: gramon, 125.
- DEVAKAPPA**: king of Latulesa, 159 and note 1. See Ruappu.
- DEVASAMPURA**: capital of Hoysala Ballalas, 203 note 3.
- DEVKA**: 6, 160, Musahin post at, attack on, orders of the emperor to raze to the ground the temple at 205, is captured by Vaghos of Okhamdold 1859, 116, taken by the English, 118, 161, 516.
- DVYASRAYA**: work compiled by Hemachandra, 137, 156, 159, 162, 163, 170, 171, 173, 182, 185, 193.
- DVYASRAYA KOSHA**: 180-192. See Dvyaśraya.
- DVYAPARVA**: third cycle 191.
- DWARAKA**: 461. See Dvārka.
- EASTWICK**: Captain (1833), 383.
- ECLIPSE**: held sacred by Hindu, 165 and note 2, 522.
- EDUCES**: of Asoka (B.C. 250) 11.
- EGYPT**: 536, trade of, 516, 516.
- EUKINON**: the Han, 514.
- EKAULA VIBA**: shrine, visited by Vastupala, 200.
- ELPHINSTON**: probably old Puri, 107; cave temple at, 158.
- ELISAR**: 543.
- ELPHINSTONE**: Mr. Mountstuart, enacts a civil and criminal code in 1827, 136.
- ELPHINSTONE**: Lord, Governor of Bombay (1857), 438.
- ELURA**: inscription of Dantidurga at, 120, 122, 467; Devaladevi captured near, 205.
- EMBOLIMA**: town identified with Aul, 538.
- ENGLISH**: the, their factory at Surat besieged and plundered, 333; plundered second time, take the fort of Surat with the help of the Marāthīs (1759), 343; become chief of the affairs of Surat, and enter into agreement with Fatesingh Gāikwār (1773), 401; capture Broach (1772), 401, capture Thana and Versova fort, 401; enter into an alliance offensive and defensive with Fatesingh Gāikwār (1780), 408; operations of, against Sindhia and Holkar, 409, aid Govindrao Gāikwār's party (1802), 412, settle the treaty of Bassein (1802), 413; capture Broach and Pavagad, restore Pavagad and Dahad to Sindhia (1803) 414, enter into a fresh treaty with the Gāikwār, and obtain the Gāikwār's share in Ahmedabad, Surat, and Kara (1817), 428, sovereignty of Gujarat passes into the hand of (1819), 428, capture Bet and Hwāka (1859) 416-418. See British.
- EUFRATITE**: ruling class of White Hūmas, 86, 115, defeat of the Kāshmir (590-612), 500. See Hūmas.
- EUFRATIS**: town, 538.
- ERA**: Of Nahapāna: 26 the Māhāva, 28-29, 67; the Samvat, 29, the Gupta, 29; Valabhi, 81; Trakutaka, 113, Chedi, 114; of Sindhia, 176 and note.
- ERAN**: Gupta pillar inscription at, 71.
- ERASTOSTHENES**: Greek geographer (275-194 B.C.) 535-537.
- ERINPER**: uniting at (1857), 439.
- ERKINE**: Mr., the chief of the factory at Chunday (1750), 343.
- ETHIOPIA**: headlands of 536.
- EUERATINGS**: Bakhtiar king, 16-17.
- EUERATON ARABIA**: modern Aden, 513.
- EUERATON**: of Cyrene (117 B.C.) his voyage to India, 535.
- EUFRATIS**: river, 511.
- EUERATON**: 535.
- EXPORTS**: from Gujarat coasts, 529; from Skythia, 511.
- F**
- FALIAN** (100), 502.
- FALIS**: revenue clerks, 212.
- FALHUR-UD-DARAH**: attacks Ahmedābād; is deserted by his supporters Sherkhān Bahi and Rūnughji of Idar, is defeated and captured by Jawan Mard Khan, intrigues with the Marāthi leader Pannaji Vithal 329, besieges Kapadvanj, 330, returns to Dakh (1748), 333.
- FALHUR-UD-DIN**: son of Molla Muhammad Ali, chief of merchants at Surat, is imprisoned by Sayad Achehan, is sent to Bombay in disguise by the chief of the English factory at Surat, 332.
- FALHAI**: Anulavata, 511.
- FAMILY TREE**: Chālukya, 110.
- FAMINE**: in Visaldeva's time, 203 and note 5; in Gujarat (1681), 286; (1684), 287; (1698), 290, 1719, 300, (1732), 313; (1747), 332.
- FARHAT-UL-MULK**: Gujarat, governor (1376-1391), 231.
- FARISHTAH**: Muslimān historian, 348, 361, 372, 512 notes 2 and 3.

- FARRUKHSIYAR**: emperor (1713-1719) 213, son of Azim-us-shāh, second son of Aurangzib, marches on Delhi and puts Jahanḍār Shāh to death (1713); remains under the influence of the Sayad brothers, makes treaty with Aṭsing of Mārṡār and marries his daughter, (1715), religious riots in Ahmedābād (1714) 297-298; his deposition and death (1719), 300.
- FARJAKS**: Mughal governors of crown domains, 211, military police, 211.
- FATISINGH**: son of Dāmājī Gāikwār by his third wife; comes to Poona and gets a reversal of the recognition of the claim of Govindrāv from the Peshwā in favour of Sayajī, appointed Sayajī's deputy in Gujrat; negotiations of, with the English in Surat, 100, 401, shuts himself up in the city of Broda, 401, negotiates with the English (1780), 108; dies (1789), 110.
- FATMA**: founds a Jama mosque at Sindh, 506, 520.
- FAZL-UL-ILAH**: Mamlūk, physician of Mehmūd Khilji, 362.
- FEROZ SHAH**: during Muslim period 209.
- FERRISSON**: Mr. ('859), 383, 191, 199, 500, 501.
- FIROZSHAH**: Nawāb of Kanauj and follower of Tāha Topi 115.
- FIRMAN**: Colonel, 110.
- FIRDAUS KHAN**: acts as viceroy (1713); schemes of Rangzī for his assassination, returns to Cambay, defeats Rangzī and becomes sole minister of Gujrat (1713), 326, confined by his troops for arrears of pay, escapes to Agra, 327.
- FIRUZ KHAN**: under Valabhi, 3.
- FINANCIAL REFORM**: of Muza Isa Tukhān, 279.
- FIRE-WORSHIPPERS** in Samu, 516.
- FIRUZ SHAH**: Sultan, 514. See Muḥk Kalār.
- FIRUZ TUGHLAGH**: Emperor (1351-1388), 231.
- FISCAL ADMINISTRATION**: of Gujrat, during Muslim period, 210.
- FLEET**: Mr., 81 notes 1 and 2, 111, 117 note, 121, 142, 511.
- FLOODS**: Sābarmati (1683), 287.
- FLORENCE** 538.
- FORBES**: the late Mr., author of the Ras Māla, 163, 159, 160, 188, 170.
- FORBES**: Major, 109.
- FORBES**: Mr., on the Muḥk-giri systems of the Marathās in 1775, 419.
- FOREIGNERS**: settlement of, in Gujrat, 13.
- **GADARAKALHATA**: fight of Narkdevi at, 195.
- GADIA**: coinage, 469.
- GAIKWAR**: 227. See Dāmājī Gāikwār, Fat-singh Gāikwār, Govindrāv Gāikwār, Pilājī Gāikwār, and Sayājī Gāikwār.
- GAJARABAI**: mother of Kanōji son of Govindrāv, taken refuge at Surat; applies for assistance to the English as well as to Malhar, son of Shāndarāo Gāikwār (1800), 412.
- GALLPATIAR**: perhaps Tālakhalī Sālva tribe, 534.
- GAMALINA**, 511.
- GAMBHATA**: ancient name of Cambay, 123.
- GAMBIE**: Mr., chief of the English at Surat, 101.
- GANDARIVAI**: see Brahōspati.
- GANDARAPOL**: Gandhara, 515.
- GANDHARAF**: Gandharavashita or Yunnan, 501.
- GANDHARA**: old town, 75, establishment of the power of Kādās in 111, 467, 191; retreat of White Hōqs from to Kashmir, 500, 515.
- **GANDHARA**: image of, 163.
- GANGA**: the river Ganges 165 and note 5, 518.
- GANDHARAF SUASERI**: Gāikwār's envoy to Poona for the settlement of the Peshwā - old claims on Gāikwār's estate (1814), 127.
- GANGAMAH**: younger brother of Mularāja, 160.
- GANGALID**: tribe, 532, 533.
- GANGES**: river, eastern boundary of Kumbhā-piles kingdom, 179, 510, water of the, for Somnath, 522, 533, 537, 515.
- GARASIS**: position of 217 and note 2.
- GARGYA**: disciple of Narkdevi, founder of a branch of Pāṇinī school, 1.
- GARJAVAKA**: Sanskrit form of Ghaznavi, 195.
- GARNI**: monument 504.
- GARTI**: eagle god, 165.
- GARDA**: country, 121, 166, 168, 169.
- GARHAF**: 153.
- GARTHAF**: Buddha (B.C. 560-480), travel through Valabhi country, 79 Sage, tank and hermitage of, 151-161.
- GARTHAFIHA**: Aśthva king (A.D. 138), 32, 38; Satakarni 540.
- GAYAKALNA**: see Varma.
- GAYAKI**: see Gom, 153.
- GIDRASA**: 516.
- GIDRASHI**: 517.
- GIDRASHI**: name derived from Valabhi king, 85, 169.
- GIDRASHI**: of the Gujrat Kshatrapas, 51; of the Gupta (519-170), 60, of the Ghāva-dās, 165, of the Vaghelas, 206.
- GIDRASHI**: of Maratha supremacy in Gujrat, 429.
- GIDRASHI**: Chavada king (A.D. 908-937), 151, 155.
- GIDRASHI**: 507.
- GIDRASHI**: oppressors, 450.
- GIDRASHI**: second Gupta chief, 61, 67.
- GIDRASHI**: Khān Bahādur Furz Jang, forty-third viceroy of Gujrat (1708-1710); his death; confiscation of his property, 296, 297.
- GIDRASHI**: capital of Mahmūd, 165, 510.
- GIDRASHI KHAN**: grave of, 455.
- GIDRASHI**: near Vajeh town, probably a river in Valabhi time, 79.
- GIDRASHI**: son and successor of Mahmūd Khilji (1469-1499); appoints his son Abdu Kādir prime minister; builds Māndu Shādi.

- Abād or abode of joy; invasion of Mālwa by Bahlol Lodi (1482); death of, by poison administered by his son and prime minister Nasir-ud-din, 362-365.
- AGHAS VU DIN TUMLEK: emperor (1620), 230.
- AGHURIA: chief of Godhna, attacked by Tejapada, 201.
- AGHURIA: see Bhumi.
- AGHURIA: Raja, Nagar Mahman; governor of Minda (1722-1724); defeat of, by Chānuā Pandy and Uday Pavar, 38.
- AGHURIA: Juna, 11.
- AGHURIA: Jain at, 9, Skandagupta's inscription at, 135; Vastupada's temple at, 153; inscription at, 176; temple of Nemutha repaired at, 176, 177, 186; inscription at, 190; visited by Hemachandra, 192, holy, magnificent temple of Nemutha built on, 193, 202, 231 and note 2, 236.
- AGHURIA: Brahmins, 70.
- AGHURIA: inscription of Skandagupta, 69-70.
- AGHURIA: 512.
- AGHURIA: 517.
- AGHURIA: river Varanasi 510-512.
- AGHURIA: General conducts negotiations with Poona on behalf of the Supreme Government and the Government of Bombay advances against Dahan, 408 takes Ahmedabad by storm; he takes the fort of Basam (1780), 109.
- AGHURIA: chief of deserts Lavanajnasada and pans Malwa chief 199, 201.
- AGHURIA and AGHURIA: see Godhna.
- AGHURIA: capture of (117), 230; counter for the government of, 311, captured by Moam Khan (1759), 349; delivered to the Marathas by Moam Khan (1759), 312; report 110.
- AGHURIA: main division of Mhar chiefships, 136.
- AGHURIA: name derived from a Valabhi king, 85, 86, Rajput tribe, 217 note 3.
- AGHURIA: Zillah 208 and note 3.
- AGHURIA: ruler, 76, Hun king, 56, 113.
- AGHURIA: 231, 517.
- AGHURIA: tank, 153.
- AGHURIA: Lieutenant Charles, R. E., 447, 418.
- AGHURIA: temple, 79.
- AGHURIA: priests, 151.
- AGHURIA: feudatory Rāshtrakūṭa prince ruling in Gujarat, 121, 122 Gujarat Rāshtrakūṭa king (827), 126.
- AGHURIA, I., Dakhan Rāshtrakūṭa king (680), 120, 121.
- AGHURIA II.: Dakhan Rāshtrakūṭa king, 122.
- AGHURIA III.: (827-833) holds the Gujarat province independently of the Dakhan sway, completes the conquest of the north and marches to the south, hands the Gujarat kingdom to his brother Indra, 123, 160, 468, 528.
- AGHURIA: brother of Dhruva II., 127.
- AGHURIA: Ghikwār, son of Dāmaji by his first wife; sides with Raghunāthrao and is taken prisoner with him at Dhorap (1768); promises increased tribute and heavy fine for his conduct and is invested with his father's title and estates, 399-400; grant made in his favour is cancelled (1771); is reinstated by Raghunāthrao (1773), 401; invests Baroda (1775), 401; leads Rāghoba's army, 403; secures the favour of Mahadji Sindhia and applies to him for restoration, 410; takes up the office of regent at Baroda (1793), 111, forces Aba Shelukar to surrender Ahmedabad and keeps him in confinement (1797), 111, his death (1799), 112.
- AGHURIA: Mularāja's opponent, 139.
- AGHURIA: king of the Chūlāsamas, 137; Mhecharuler of Korah, wars with Mularāja and is made prisoner, 160, 161.
- AGHURIA: copperplate, 55.
- AGHURIA: Colonel, 110.
- AGHURIA: vessels, 516.
- AGHURIA: see Gihasona.
- AGHURIA: follower of Buddha, 83; Valabhi king (A.D. 559-567), 85.
- AGHURIA: boundaries and extent, 1; the name, 2-5, Rāshtrakūṭa in, 119-134, invaded by Alif Khan, 205 note 2, under the Mughals (A.D. 1673-1760), 221-225, under the rule of Aurangzib (1611-1617), 280, Shivaji's incursions in (1661-1670), 281, 346, predatory incursions of the Marathas, their growth, their power, and their supremacy in, 3-5, expeditions of Khanderio Dābhad in (1700-1711), 388; administration of, left entirely in the hands of the Ghikwār family after the treaty of Salba, 110, 111; under the management of Aba Shelukar (1796-1797), 111, turned to Ghikwār by the Peshwa (1799), 111; renewal of the farm of, to Bhagwantrao Ghikwār for ten years (1801), 115, appointment of Trimbakji Dengle as Sasnidha of Ahmedabad, 127, Peshwa's rights passed to the British (1819), 385, disturbances (1857-1859), 413-418, disarming (1857), 114; gateway, 152, 459, Brahmins, 163; Hindu enterprise by sea to Java, 192 note 3, conquest and settlement of Java and Cambodia (603), 196, earliest Arab references to, 505, 508, 511, conquest of (1306), 512, 514, 515, 517, 526, 529, religion in, 530; people of, 531, 532. See Jnr.
- AGHURIA: a tribe, 2-3, 58.
- AGHURIA: 113. See Mihargulla.
- AGHURIA: Bodhisattva, 79.
- AGHURIA: Kshatrapa inscription at, 42.
- AGHURIA: fort seized by Sammas, 139, 518.
- AGHURIA: first Gupta king, 60, 61.
- AGHURIA: era, 29, 58, 67, 81, 87, 110.
- AGHURIA: in Magadha, 73, 77.
- AGHURIA: kingdoms, 3-4; foreign tribe, Valabhis believed to be Gurjjaras, 97; defeated by Arabs, 109; establish themselves at Nandol (580-808), 113; territory, 113; copperplate grants, 113-114; family tree, 114; give up san-worship and their name for Saivism and Purāṇic pedigree, 116; march against Dhruva II., 127; Chāvāṇās said to belong to them, 127 note 2,

458, 463; origin of, 464; of Branch, 465, 466; their appearance in India and earliest notice, 467, 468; migration of, 469; are defeated by Prabhākara-vaiśṇava (600-606), 490; retain Broach, Valabhi, and Bhinnadi, 490; their relation with Mihirās, or Meds, 490, 526. See Juzr.

GURJJARARĀJA: province of Gujaraṭ, name derived from Valabhi kings, 85.

GUVAKA: first Chohan king, 153 note 1.

**HADALAKA:** village, 202.

HADDALA: copperplate found at, 138.

HADOW. Mr, Collector of Ahmedabad, 443.

HADRIAN: Roman emperor (117-138), 537.

\*HAIDARĀBĀD: Sindhi town, 511, 517, 538, 546.

HAIQAR KUTBI KHĀN: fiftieth viceroy of Gujaraṭ; disorder in Ahmedabad (1721); his leniency to Babā of Gujaraṭ, frees the emperor from the tyranny of the Sayads (1721); is honoured with a title and the governorship of Gujaraṭ (1721-22), 302; subdues Kolis of Udhavāl; shows signs of independence and is recalled (1722), 303.

HAJI: General, 538.

HAIHAYAS: a Kshatriya tribe, 58.

HAIMAKHADDA: Hemu's pit, 193.

HAIMINAMĀVALI: string of names composed by Hemachandra, 192.

HAIRĀL: 145.

HĀKAM: brother of Usmān, second Khālifāh, 505; sends an expedition to Debal and Branch, 505, 506, 513.

HĀLĀR: zillāh 208 and note 3.

HAMĀL KHĀN: grant of, 455.

HAMBIRĀV: the title of Hasājī Mohite, Shivājī's commander, 387.

\*HAMID BĒG: is appointed governor of Branch (1754), 339.

\*HAMID KHĀN, nephew of Nizām-ul-Mulk: deputy viceroy of Gujaraṭ (1722), 303; joins his forces with Kāntājī Kadam, and defeats and kills Shujāt Khān near Ahmedabad; takes up his quarters at Shāh Bāgh and gets possession of all Ahmedābād except the city; attempt of Ibrahim Khān son of Shujāt Khān to assassinate him, 304-305; defeated by Rustam Ali at Aras (1723), 305, 213; assigns one-fourth share of the territory north of the Mahi to Kāntājī and a corresponding interest in the territory south of Mahi to Pilājī, 305; unites his forces with the Marāṭhās under Kāntājī and Pilājī and marches on Ahmedābād, defeat of, at Sojitra; second defeat, 307.

HAMMIRAMAHĀKĀVYA: 157, 159, 171, 182, 184.

HAMMUKA: king of Sindh, invaded by Bhima I., 163.

HANAWAL: Janāwāl, apparently Chunwāl or Jhālāwar, 510, 513, 517.

HANUMĀN: progenitor of Porbandar chiefs, 135.

HĀNNHĀNJI: chief of Limbūli (1753), 337.

HARIPA: adopted son of Khanderiō Gankwār, attacks Rangoji's deputy and kills him; his expulsion by Rangoji from Borsad, 331.

HARIPĀLA: minister of Siddharāja, 173; grandfather of Kumārpalāh, 181.

HARIPANT FADKE: Peshwa's general, enters Gujaraṭ and compels Govindāy and Rāghoba to raise the siege of Baroda, 402.

\*HARĪYA BRĀHMAN: 460 and note 3.

HARĀKAR: messengers, 214.

HARSHA: 116.

HARSHADĀRITA: Sanskrit work by the poet Bana, 114.

HARSHADĒVA: Harshavardhana of Kanauj (607-618), 115.

HARSHAPURA: identified with Harsoi, 129.

HAISHAVARĀHANA: Kanauj king (629-645), 56, 72, 108.

HARSHA: temple at Verāval of, 203.

HASAN MOHITE: plunders Branch (1675), 387. See Hambirāva.

HASAN MUHAMMAD KHĀN: author of Mirāt-i-Ahmedī (1739), 310.

HASTINAGARA: town, 190.

HASTINATH: same as Hastinagana.

HATCH: Captain (1857), 110.

HATISHYAM MAHADĪV: Nagai Brāhman's special guardian at Vadnagar; destruction of the temple of, 289.

HAYADAR: Mughal village officer, 212.

HAZI MUHAMMAD KHĀN: governor of Māfdu (1568) 370.

HEAD TAX: the report of (1719), 301.

HEKATĀIOS: Greek writer, 532, 546.

HEMACHANDRA: Jain devotee and chronicler (A.D. 1079-1173), 156, patronised by Siddharāja. 180, his teacher, 181 note 2, tells Kumārpalāh his future, 182-183, birth and education, 191, becomes Kumārpalāh's religious adviser, 192-193, his works and death, 193.

HEMACHARYA: 179, 183, his canon 188. See Hemachandra.

HERBERT: Sir Thomas, English traveller in India (1626), 361. Master Thomas, 381.

HERANSEA: island, 542.

HERODOTOS: geographer, 546.

HERODOTOS: Greek historian, 532.

HERON: roof, 539, 545.

HIMALAYAS: the, 518.

HIND: 511, cities of, 514, 516, 518; king of 529.

HINDI: 512, 529; classes of, 530; king, 531.

HINDU CHURCH: of Māfdu, expelled by Sultān Shams-ud-din Altamash (1234), 367.

HIPPARCOS: 536, 537, 543.

HIPPARKHOS: Eristhenes' critic (130 B.C.), 535.

HIPPOKOURA: either Godegoun or Kūda, 540; possibly Hippurgi, 541.

HERAKLEIA: 546.

HIRANYA KASIP: demon, 120.

HISTORIANS: Sqaṭki, 165.

HUIEN TSANG: Chinese traveller and pilgrim (A.D. 612-640), 3, 7, 77; his description of the Valabhis, 79; 85; 111; 115; notices Branch kingdom, 116; 143, 465, 466, 467, 489, 490, 499, 502, 540.

HISHĀM BIN ABDUL MALIK: (724-743), 506, 513, 520.

- HIJMAUDDIN PARMAR**, Gujarāt governor, 239 and note 1.  
**HJEN GHORAB** 537.  
**HISTORY**: of Bhimā, 465-471.  
**HONORS** 465.  
**HORNBY**, chief of the council at Bombay (1779), 408.  
**HOSHANG SHAH GHORI** Sultan of Malwa (1405-1432), the establisher of Mandu's greatness, goes to Jajmgar (Jajpur) in Cut-lack of Orissa (1432), returns to Mandu at the news of the siege of Mandu by Ahmed Shah of Gujarāt in 1422, prosperity of Malwa and extension of his power by his ministers Malik Mughis Khān and Mahmūd Khān his son, his death, 358-359.  
**HUTCHINSON** Th., 129 note 3.  
**ILAKHMAN**, emperor of Delhi (1539-1556), 220: defeats Sultan Bahadur of Gujarāt (1531) at Mandu, captures the fort of Sangar, re-tires to Mandu from Gujarāt (1535), returns to Agra (1535-36), 367, 368.  
**ILAKHMAN**, emperor, 219 note 2, 222 note 2.  
**ILAKHMAN**, king of the *conqueror* of choice-marrage of Durlabha, 163.  
**ILAKHMAN** 465.  
**ILAKHMAN** White (A.D. 150-520), 69, 73, 74, 76, 112-116, 465, 467. See *Ilaks*.  
**ILAKHMAN** subdivision of Marwar Kumbha, 465.  
**ILAKHMAN** White, 69, 73, 86. See *Ilaks*.  
**ILAKHMAN** horse trade from, 515.  
**ILAKHMAN** town, capital of Prithviraj 129.  
**ILAKHMAN KHAN BAHADUR** 139.  
**ILAKHMAN** Captain, Political Agent of Bhopawar, takes the Raj of Amjora (1857), 139.  
**ILAKHMAN** Kushan king (A.D. 100-123), 37.  
**ILAKHMAN** the River 231.  
**ILAKHMAN** the Inas, 535.  
**ILAKHMAN** district of Skythia, 511.  
**ILAKHMAN** the See *Ilakha Khudābāh*.  
**ILAKHMAN** Arab historian, author of *Taukh-i-Kamil* (1160-1232), his account of the destruction of Somnātha 165.  
**ILAKHMAN** A.D. 522 and note 4, 53, 54. See *Ibn Asir*.  
**ILAKHMAN** Muhammad Alauddin Kāsim (995-996), 507, 511 and notes 6, 6, 7, 8, 510 note 1, 511 and notes 6, 7, 8, 516 and notes 8, 9, 10, 518, 519, 521, 523, 526, 527, 528, 529.  
**ILAKHMAN KHAN** author of the biographical dictionary, 522 note 4.  
**ILAKHMAN KHURDADHAK**: Arab writer (912), 506 and note 7, 509 note 5, 512, 513 and note 10, 519, 520, 527, 528, 530, 531. See *Ibn Khur-dādhā*.  
**ILAKHMAN KHAN**: fortieth viceroy of Gujarāt (1705), 293; forty-second viceroy (1706), 295; resigns (1708), 296.  
**ILAKHMAN**: gold coin, 219 note 2; 222 note 2.  
**ILAKHMAN** 218, 226, 232, 233, 236, 237, 238; revolt of, capture of, by Mughals, death of the chief of (1679), 286; unsuccessful attack on, by Jawān Mard Khān, 315.  
**ILAKHMAN**: copperplate grant found at, 146 note 3, 117.  
**ILAKHMAN** decay of (1720), 301.  
**ILAKHMAN** into Skythia, 511.  
**ILAKHMAN** by Akbar, 223.  
**ILAKHMAN** fanatical spirit excited by the proceedings of, 436.  
**ILAKHMAN** 541.  
**ILAKHMAN** fort taken by Lieut. Welsh in 1780, 109.  
**ILAKHMAN** religious sects of, 530, home of wisdom, 531.  
**ILAKHMAN** 536.  
**ILAKHMAN** conversion of, to Buddhism (A.D. 210), immigration to of Sakas or Yavanas from Tamluk or Rathavati on the Nighli (A.D. 100), 109.  
**ILAKHMAN** 537, 538, 539.  
**ILAKHMAN** Rashtrakuta king (about A.D. 500), 120, Founder of the Gujarāt branch 121, 123-124.  
**ILAKHMAN** Rashtrakuta king, 120, 121.  
**ILAKHMAN** Rashtrakuta king, his grants found at Narsara, 128, (A.D. 911), 130, 516.  
**ILAKHMAN** 517, 533, 534, 537, 538.  
**ILAKHMAN** 12, 13, 65, 66, 67, 69, 71, of God Kāladāsa, 172 note 3, of Nāravarman, 173, of Mohavarman, 178, 203-204; at Bhimā 471-488.  
**ILAKHMAN** Indraprastha, capital of Cambodia, 194.  
**ILAKHMAN** the Yavanas, 533.  
**ILAKHMAN** second of the, 10 and note 2.  
**ILAKHMAN** converts to, 111, spread of (1114), 236-237, prospects of taught in Kumbhaya, 514, 530.  
**ILAKHMAN** military post of the Mughals. See *Sohā*, 285.  
**ILAKHMAN** See *Naravara*.  
**ILAKHMAN** the collector of customs at Cambay in 1701, 323.  
**ILAKHMAN** Kshatrapa ruler (230-250), coins of, 51-52, rubi, 57.  
**ILAKHMAN** Aldra king, 52.  
**JAGAT-AL-MANSHUR** Abbāsī Khalīfah (754-775), 521.  
**JAGAT-AL-MANSHUR** Visaldeva retires to, for help, 203.  
**JAGAT-AL-MANSHUR** Raja of, shelters Captain Hutchinson, 439.  
**JAGAT-AL-MANSHUR** king, copperplate of, 136.  
**JAGAT-AL-MANSHUR** same as Yalava, 139.  
**JAGAT-AL-MANSHUR** corruption of *bandhaja*, 137.  
**JAGAT-AL-MANSHUR**: invading tribe, 137.  
**JAGAT-AL-MANSHUR** son of Unadai Bahade, 314.  
**JAGAT-AL-MANSHUR** chief, general of Siddharāja, 172 and note 3.  
**JAGAT-AL-MANSHUR** world guardian, another name of Durlabha, Chandukya king, 162.  
**JAGAT-AL-MANSHUR** gives Shrināl to Gujarāt Brāhmans, 463.  
**JAGAT-AL-MANSHUR**: 460, 463. See *Jagavāmi*.  
**JAGAT-AL-MANSHUR** Durlabha Rashtrakuta prince, son of Krishna, 128, 130.

- JAG DAY** : see Jagaddewa.
- JAGDHWAR** shrine and eastern of, 453.
- JAGIRDARS** Musaharā landholders, 215.
- JAGO** John de St., Portuguese apostate in the service of Sultan Bihādar of Cambay (1536), 350, 350.
- JAGSON** kmz, 460, 461, 464; temple of, 460.
- JAGSAMI** san temple of, 451, 456, 459, 463, 471.
- JAHANGIR** Mughal emperor (1605-1627), visits Mandu in 1611, receives English ambassador Sir T. Roe at Mandu, 361, 372-377.
- JAHAUDAR** copperplate of, 81, Mōr king, his grant, 87, another name of Jachakadeva, 137; his grant at Morla, 139.
- JAIKOP** properly Jakshkop, 454 and note; lake, 455, 456-458, 471.
- JAIPTER** 511 note 12, 520.
- JAJJAKA** minister of Akalavarsha Krishna, 128.
- JAL**: 456. See Pihu.
- JALHANA** daughter of Amoghā, marries Kumārapāla, 185.
- JALPTER** town, 531, 546.
- JAM** 215 and note 2.
- JAMA** fixed sum of land revenue, 212.
- JAMAWAL** tribe, 160, 164.
- JAMBA** Bama minister of Varmāya, 152.
- JAMBHULI** river, 160.
- JAMHUSAR** Brahmins of, mentioned as granters, 111, attacked and plundered by Mōmū Khān in 1755, 339.
- JAMBIVADA**: 125.
- JAMBIVATIKA** modern Jambivada, 125.
- JAMBAGNI**: size, 161.
- JAMRUL-HIKAYAT**, work of Muhammad Ufī, 512 and note 5.
- JAMRUL** king 512.
- JAMUNA** the river Yamuna, 518.
- JAMS** Gujarati cloths, 139.
- JAM SINGH**: Summa chief of little Kaehl, 518.
- JANAGRAVA** 56.
- JANAWAI** Chhivāl, 509, 513.
- JANDER** Rander, 509 note 1, 520.
- JANTRA** identified with Pihu, 107 and note 207, note 1; fort, residence, and stronghold of the Sidi or Abyssinian nobles of Bijapur, 285, 546.
- JANKOTIRAO SINDIA** adopted son of Buzibai, widow of Dowlatrav Sinha, 137.
- JANOLI BHONSLE**: of Nagpur, partisan of Rāghoba, 399.
- JANWAL** Chhivāl or Vāṅgām, 509. See Janawal and Janwāl.
- JARIYA** goldsmiths, origin of, 464.
- JATIYAS** tanners, 451.
- JASDAN**: Kshatrapa inscription at, 13.
- JASVANTSINGH RATHOR** Mubārāja, viceroy of Malwa (1657), thirty-second viceroy of Gujarāt (1659-1662), 282; sent from Gujarāt by Aurangzib to join prince Mu'izzam against Shivaji in the Dehli (1662), 283, 387, thirty-fifth viceroy of Gujarāt (1671-1674; sent to Kabul (1674), 285.
- JARS** cultivators, 451; persecution of, by Brahmanist Chāch (612), 498.
- JATWAR** village, 208 and note 3.
- JAUDHITA** 137.
- JAYHANS** Yojana, 525.
- JAYLA**: identified with the tribe annihilated by Toramāya, 116.
- JAYA** island, early Hindu settlements in, 189; traditions of expeditions by sea to, 190, 191 note 5, 192; mention of Gondhara and Latu in the legends of, 197, emigration to, of refugees from the defeats of Prabhakravardhana and Shriharsha of Magadha (600-612), 497, appearance and condition of Hindu settlers in, 498.
- JAYADA** corruption of Chavala, 150.
- JAWLA**: see Jhawla.
- JAWAN MAMUN KHAN BAHU**, his unsuccessful attempt on Idar and negotiations with the Marathas, 315; proclaims himself deputy viceroy of Gujarāt 326; assumes charge of the city of Ahmedabad and persuades the troops to release Fida-ud-din, drives the viceroy to Cambay and invites Abdul Aziz Khan of Junnar, 327, 328, reconciles himself with his brother Safdar Khan Babi of Radhampur and imprisons Fakhr-ud-din and his family 329, appoints Janardhanpant in place of Ruzop, 331; enters into negotiations with Balapant Peshwa (1750), 331; joins the Marathas against Mōmū Khān, 310, 342, 345.
- JAYLA** tribal name, 165.
- JAYAHATA I.** Gujjara king (605-620), 114, 115.
- JAYAHATA II.** Gurjara chief of Nandod, helps Valabhi, 85, (650-675), 116.
- JAYAHATA III.** Gurjara king of Nandod, his copperplates, 56, 108, (700-734), 114, 116; his grants, 117; deprived of his dominion by Dantidurga, 122.
- JAYAHMAN** third Kshatrapa (110-113) coins of, 33-34.
- JAYACHIVA** sun temple, 126.
- JAYAKSI** Kadamba king of Chhindrapura, marries his daughter to Karna, burns himself on the funeral pile, 170 and note 5.
- JAYAKI** II. Gur Kadamba king, 172 note 3.
- JAYANTAPALA** Vastupala's son, 202.
- JAYANTAVUDA**: Chalukya noble (1221), 196.
- JAYANTIDevi** goddess in Agrval, 170.
- JAYASIKHARA** Chivada king of Panchisar (606), killed by Bhuvada, 150, 156.
- JAYASIMHA**: Chālukya prince, 111, 117. See Jayasimbavarman.
- JAYASIMHA I.**: Chalukya prince, defeats Indra, Rashtrakuta prince (A.D. 500), 120.
- JAYASIMHAYARJUNAN** Chalukya king, 56, younger brother of Vikramāditya Satyashaya drives out the Gurjars and establishes Chalukya power in south Gujarāt (A.D. 666-693), 107, 108, 110.
- JAZIAN**: capitation tax, 213; imposition of, by Aurangzib 286.
- JEHANDARSUHAN**. Abul Fatah Muiz-ud-din, son and successor of Bahādur Shāh I. of Dehli (1712-13), 297.
- JESALMER** Mhars settle at, 136; Jain temple at, 161 note 1.

JETHVÁS : Porbandar chiefs, 135 ; Rajputs, 139 ; foreign tribe, 139-140 ; identified with Jats, 145.

JĀWS in Saimur, 516.

JĀLAS : Rajputs, 139 ; foreign tribe, 146, 206 note.

JĀLĀVĀ : established in Rājputāna, 110, 208 note 3.

JĀLĀWAR : local name, 233 and note 5, 517.

JĀLĀNDAR : ancient name of Jhalor, 229.

JĀLĀOR : in Jodhpur, 229 and note 5, 149, 151.

JĀLĀOKS : 301.

JĀNĀNA : Sindh king (316), 129, 516.

JĀYTRĪ NĪCHĀND : agent of the Badda conspirators in the Kāna district, 142.

JĀYVĪA : division of Paṇḍya Gujjars, 116.

JĀYVĪA : town, 10 note 2.

JĀMĀKĀVĪYĀ : temple, built by Karmāpādāt Dhundhaka, 199.

JĀNĀPHĀNĀSĪTĪ : Jñā sage and writer, 6, 15, 78 ; author of the Tithakalpa, 176, 182 note.

JĀNĀVĪA : town, 509.

JĀNĪ : father of Bhīmadagupta, 153 note 1.

JĀNĪR : birth of (1391), 23 and note 2, 238.

JĀNĪ ANĀSĪPĀNA : reservoir, 180 note 2.

JĀNĪĀNĀ : sixth Kshatriya (178), coins of, 40-41.

JĀNĪPĪ : town, 163.

JĀNĪYĪ : 165.

JĀNNA : 535. See Janna.

JĀNĀGĪRĪ : Mauryan capital of Gujarat, 14 ; establishment of Ahir kingdom at, 138 ; capital of Chāndisā ruler, 176 ; independent ruler of, 206, note, 236 ; taken by Mahmūd Begada and made his capital under the name of Mustafāghī (172, 215, 216, disputed successions 111, 125 ; British not invoked at (1616), 127-638.

JĀNĀNĪ : South governor of Khāḍī Hashānā, his expeditions, 109, 167 ; sends expeditions against Gujarat, 506, 513, 520.

JĀNĀWĪ : 517. See Janawal.

JĀNĀD : see Janād.

JĀNĀB : perhaps ancient Tākiḍī, 57.

JĀRZ : see Jūr.

JĀSTHĪKĪ : Mughal administration of, 213.

JĀSTHĪ : historian (A.D. 250), 16, 535.

JĀZĪ : Gujjars and Gujjars, expedition against, 109, 165, 167, 168, 169, 500, 506, 515, 520, 521.

KĀMĪRĪN : perhaps a town on the Kāveri, Misalibhūm, 518.

KĀMĪL VĀLLĪY : stupas or mounds of, 497.

KACCH : migration of Samras to, 139 ; Bhīm's copperplate in, 163 ; stone inscription from, 203, 508 ; affliction of, 513 note 9, 517, 521, 530, 534, 538. See Kagechella.

KACCHĪLLA : identified with Karhh, 109.

KĀCHĪA : coins, 62 note 2.

KACCHĪHĪ : Kāchh, 36 and note 5.

KADALUNDI : near Bejur, 546.

KĀDAMBĀHĪ : Bāna's work, 114.

KĀDESIĀH : battle of (C36), 505 note 5.

KĀI : town grant from, 203, 231.

KĀI : fort, captured by the English (1802), 412.

KĀDVA : Gujarat Kanbi subdivision, 4-5.

KĀERĪ : Hāzār Dīmā, minister and general of Alā-ul-dīn, 515.

KĀNĪLEI : island of St. George, 516.

KĀIRA : grant of, 110, 167, 518 and note 3.

KĀIHĀL : 531.

KĀKA : town, 64 note 3.

KĀKĀRA : village, 152.

KĀKA : founder of Rashtrakūṭa kingdom in Gujarat, 467.

KĀKA II : Rashtrakūṭa king, his grants, 122.

KĀKA III : Rashtrakūṭa king, 120.

KĀKĀIA : Rashtrakūṭa king, 120.

KĀKĀRZ : name of sub-division, 208 note 3.

KĀKĀRĪRĪ : era, 57 ; dynasty, 111, 169. See Uch, Hadilaka.

KĀMĀVĀPĪYĀNA : city visited by Karmāpādā, 183 and note.

KĀNĀGĪRĪ : era, 57 and note 1, fort, 178.

KĀNĀNĪ : river identified with Kāveri, 185 and note 4.

KĀNĀVĀNĀ : legendary Dakṣin hero, 9.

KĀNĪKA : Yuga of Ujjāta, 114.

KĀNĪNĀR : Kānānā possession, 169.

KĀNĪVĪKA : month cycle, 6, 161.

KĀNĪYĪ : 507.

KĀNĪYĀ : modern Kalyān, great port, 517.

KĀNĪYĀ : modern Kalyān, 80.

KĀNĪYĪRĪ : probably Gadgaḍ, 511.

KĀLĪKA : father of Jappuka, 128.

KĀLYĀN : 80, see Kāthiā, capital of Chāḍḍya kingdom, 150 ; great port, 517.

KĀLYĀNĀKĀTĀKA : capital of Guvāḍa Chāḍḍya king, 150. Capital of king Parnad, 173.

KĀMĀYĪA : mother of Lakṣmī, causes Mula-raj's descendants, 160.

KĀMĀ : probably Kāmāpād, that is Assam, inland state, 528.

KĀMĀNĪ : identified with Kānā, 539.

KĀMĀVĪDĪRĪ : revision of, 212 note.

KĀMĀYĪ : 518. See Cambay.

KĀMĀYĪA : 507, 508, 509, 511, 511, 531. See Cambay.

KĀMĀYĪYĪ : 514, 523, 528, 529. See Cambay.

KĀMĀYĪVĪ : 514, 515, 520. See Cambay.

KĀMĀYĪRĪ : Kābul, 491, 498 and note 4.

KĀMĀYĪ : 507, 511, 511. See Anābilavāḍa.

KĀMĀYĪA : town, 538.

KĀMĀYĪRĪ : Konkan, 519.

KĀMĀYĪ : district, 108 ; expedition against, 109, 130, 520.

KĀMĀYĪYĪ : modern Kāmbay, 130.

KĀMĀYĪNĪ : identified with Kāmbay, 539 ; village, 515.

KĀMĀYĪLA : Rājā of, 230 and note 2.

KĀMĀ : defeated by Kṛishṇa, 178.

KĀMĀYĪYĪ : 511, 514. See Anābilavāḍa.

KĀNĀK : 462 note 3.

KĀNĀKĪN : founder of the Skythian era (78), 453, 464.

KĀNĀM : local name for Jambusay, 208 note 3.

KĀNĀI : 507, 518, 519.

KĀNĀBIS : origin of the name, 4.

KĀNĀCHĪ : modern Conjeeveram, visited by Karmāpādā, 183.

- KANDARINA**: Ganilhár, north of Broach, 589.  
**KANDHAR** 525.  
**KANDOLA**: palace, 180 note 2.  
**KAND**: modern Hindu Ghulch, 643.  
**KANDADA**: 181. See Kanhadaya.  
**KANDHUR**: cave inscription at, 126, 128.  
**KANDORI**: Garkwar, son of Govindráy by a Rajpután princess of Dharmpur, kept in confinement during Govindráy's time, manages to secure the government for his idiot brother Amardá (1800), again kept in confinement by his Arab guard, 122, collects an army, obtains possession of Amardá and is subdued by the English (1803), 113.  
**KANISHKA**: Kushan king (A.D. 78), 23, 33, 37, 64 note 5, 153, 162 note 3. See Kanab.  
**KANU**: Chuvayá Koli soldier, subdued by Azam Khan viceroi (1605-1612), 278, Koli chief of Chhanchi, 321.  
**KANKAR**: village, Dandá's brother Pratáprád died at (1757), 318.  
**KANADDEVA RASA** 229.  
**KANOL**: birth of, 150.  
**KANODAS**: Brahman, 761.  
**KANORI LAKHAR**: Garkwar's lieutenant, 330; goes with Fakhr-ud-daulah into Sorath and captures the town of Vavhali, retires to Dholi and expels Muhammad Jarkhar, joins Raisingi and marches on Sonol 341, 336.  
**KANRAH KADAM BANDU**: officer of the Peshwa, enters Gujarat and levies tribute for the first time (1723), 301, 310, 317, 320, takes Champner, 321; leaves Gujarat, 321.  
**KANFLUX**: see Simlam.  
**KANIHADI**: ascetic, 161.  
**KANIHADUR**: 168. See Kanthkot.  
**KANUR** 535.  
**KANTHKA**: coast tract, from Belch northward, or between Bombay and Cambay, 123, 125.  
**KANTHOKOT**: fort in Cutch, 158, 204, 235 and note 2.  
**KANUNGO**: Mughal accountants, 212.  
**KANVANI**: village, 113.  
**KANVAKRMA** 79 161. See Kanauj.  
**KARAVANS**: grant at, 123, 129, reservoir built at by Subhadrá, 180 note 1, battle of (1725), 307, capture of by the Mutáhs (1736), 317; Fakhr-ud-daulah meets Raisingi of Idar at, 329, siege of raised by Holkar (1746), 330, taken by Dandá from Sher Khán (1753), 338.  
**KARÁLESVARA**: 127.  
**KARARI**: Kunirapála's chief minister after the death of Udayana, 130; becomes Ajayapála's minister, is thrown in a cauldron of boiling oil, 194.  
**KARADI**: 156.  
**KARIKA**: identified with Kávi, 126.  
**KARILAKOT**: Mularája slew Lakha in a combat at, 160.  
**KARISHMALA**: 531.  
**KARUR AND BHANSA**: leading merchant of Ahmedábad, murder of, by Anopsing Bhandari, 302.  
**KARAD**: town, coin-board found at, 18-49.  
**KARÁDA SAROVAR**: lake, 173.  
**KARAVISHVAR**: 453 and note 2.  
**KARWANG**: Yunnan (1290), 501.  
**KARAMBÁKA VIKRA**: temple, built by Karmámpála at Pátan, 190.  
**KARAK**: defeat of, by the Musalmáns, 512. See Karan Ghelo.  
**KARAK GHULO**: Vaghela ruler of Gujarát (1296-1301), 229.  
**KARÁVANA**: modern Kari in chief shrine of Lakshmi and temple of Chamundadevi at, 83 and note.  
**KARDA**: plate, 128, 130.  
**KARIN PARIYAS**: 545, 545.  
**KARIS**: Salavats, 16.  
**KARKA I**: Ráshtrakuta king of Gujarát branch (812-821) accepts the overlordship of Lakshman dynasty, helps Amoghavajra in establishing his supremacy and receives in return a portion of country south of the Tapti, his grants 124-129.  
**KARKA II**: grant of (812-813), 163-168.  
**KARMAKSA AHARA**: district of Kankrej 108.  
**KARNA**: Pálin king, 1. Mihabhinata hero, 85, 86, 116. Second successor of Bhuma I (1004-1024) removes his capital to Karnavati, 169 170-171. King of Chedi, pays tribute to Bhuma I, 163. marches against Karmámpála and dies on the way, 156 and note 5, 157.  
**KARNADEVA**: last Vaghela king (1296-1301); flees before Musalmáns to Devan, dies a fugitive, 205-206.  
**KARNADEVA**: 157.  
**KARNAL**: district of Panipat, 531.  
**KARNAMERI**: temple at Anahavavá, built by Karma the Chaulukya king, 170.  
**KARNA SAGARA**: lake made by Karma the Chaulukya king, 170.  
**KARNARA**: king of, 203 and note 3.  
**KARNAVATI**: city founded by Karma the Chaulukya king and made his capital; temple of Ulava Varaha at, 170, modern Ahmedabad, 181, Hemachandra's birthplace, 191.  
**KARNESVARA**: god Mahadeva in Asaval, 170.  
**KARPAKA**: 156.  
**KARRA**: Karna, 518.  
**KARRANAI HATI**: Rána of Nagur Pukar, rises in revolt, subdued by Colonel Evans, 418.  
**KARIALAR KULAN**: viceroi, suppresses the mutiny at Ahmedábad (1688), 258.  
**KARTTIKA**: 64 and note 2.  
**KARUR**: battle of, 113, 496.  
**KARUSHA**: disciple of Nakulisa, 81.  
**KARVÁN**: see Karávana.  
**KASÁKULA**: division, 110.  
**KASAMACHITRA**: ruler of Gujarát, sends an expedition to Jáva (603), 49.  
**KASAM KULAN**: thirtieth viceroi of Gujarát (1657-1659), 282.  
**KASARAS**: brass-smiths, 450.  
**KASBAH**: town, 213.  
**KASBÁTIS**: of Pátan (1718), 333.

- KĀSHMĪR : state, 460, 461, 464, 465, 468, 519, 522.  
 KASHYAP : sage, 461.  
 KĀSI, king of, present with Mularāja in the battle with Ugraharjuna, 160, present at the *stayerment* of Durgabhadra, 163.  
 KĀMIR : 165, 527-546.  
 KĀMIRADEVI, wife of Tribhuvanapala, 181.  
 KĀSMIRAS : 169.  
 KASPIKOS : Kashmir city, 516.  
 KASALIAS : Kashmir city, 531.  
 KATAPPA : Katalappa, 530.  
 KĀPĪSĀRĪSĀGARA : 78.  
 KATHIAS : woodworkers, 150.  
 KĀTHIYĀDA : the tribe, 208, 209, 211 in Sorath, 208 and note 3, 209; Gupta sway in, 135, arrival of Meis in 110 and note 5, disturbance in (1192), 288; settlement of tribute by Colonel Walker, 416, state of (1807), 416, the revenue and system, 117, 118, and 119, 420-421, the tribe of taking securities in all engagements in, 420. Peshwa's share of tribute in, 122-123, cession of the share to the English for military expenses, 123-124, disturbances in (1811), 125, 526, 544, 548.  
 KATHIS : the tribe, 209, 217 note 3.  
 KATUKA : Bana, gives patch of ground to Kumbhaja on credit, 183, is given Binda, 181.  
 KĀTĀDEVI : wife of Kumbhaja, taken captive by Alāf Khān and admitted into the Sultan's harem, 205.  
 KĀVAS : Bhūmas : servants, 151.  
 KĀVĪ : 518, 519.  
 KĀVĪ : toward 111, grant of, 123-125, 126.  
 KĀVĪSĀMĪ : modern Kosol, 128.  
 KĀVĪSĀMĪ : writer, 41.  
 KĀZĪ : position and date of, 213, 214-539.  
 KĀZĪ-Ī-KĀZZĪ : Mughal appellation, 243.  
 KĀZĪNG : Colonel, sent to help Raghoba, 402, puns Raghoba at Durgaj or Durgaj in Cambay (1770-1803), negotiates with Tiberius on behalf of Raghoba, 405, receives orders to leave Raghoba to him of, 405.  
 KĀDĀRĪVĀRĪ : temple in 1 or 5, paid by C. 11, Pithapala, 190.  
 KĀDĀRĪS : retreat of, to Kishan, 500, south with Tibetans on Yunnan in the north century, 501.  
 KĀDĀRĪ : Gailwā, Damāp's cousin, receives one-third of the revenues of Surat for his aid from Sayid Achutan, 342.  
 KĀMĀPĀPĀNĀ : probably modern Kolam or Gnilon, 183 note.  
 KĀPĀPĀNĀ : chief of Nador, 193.  
 KĀPĀPĀNĀS : Keralaputra, 516.  
 KĀRĀP : inscriptions near the ruined town of, 188.  
 KĀRĀPĀPĀ : Cera-king, 546.  
 KĀRĀP : village, inscription at, 196, 470.  
 KĀSĀVĀ : Nagara Brāhman, minister of Karmadeva, slain, 205 note 2.  
 KĀYĪ : Nāik : Nāikla Bhil leader, surrender of (1859), 116.  
 KĀYĪTRĪ : probably Kavi, 513, 546. See Akabayan.  
 KĀYĪTRĪ : son of Singhat, 517.  
 KĀYĪTRĪ : inscription from, 403.  
 KĀYĪTRĪ : Hārām (724-743), 109.  
 KĀYĪTRĪ : crown domain, 209, 214.  
 KĀYĪTRĪ : 511. See Cambay.  
 KĀYĪTRĪ : see Cambay.  
 KĀYĪTRĪ : town, headquarters of the Navagar chiefs between 1671-1707, 285.  
 KĀYĪTRĪ : battle of (1801), 232 and note 2.  
 KĀYĪTRĪ : obtains a title of Ghālib Janā, 307.  
 KĀYĪTRĪ : fort, attacked by Mahmūd of Ghazni, 167.  
 KĀYĪTRĪ : Dāblade, Rām Rāja's deputy in Biglan, makes incursions into the Surat district (1699), 388, his expeditions in Gujarat (1700-1711); his defeat at Ankeshwar by the Mughals (1711), 388, defeats the army sent against him under Zulfiqar Bāg by the Deccan authorities (1716), 388, his outpost between Surat and Burhanpur (1716), 388, is appointed Senāpati by Rājā Shahu, 389.  
 KĀYĪTRĪ : Garkwā, brother of Dīmāji, demands his share, negotiates with Jawān Mūr Khān, appoints Dīmāji Mōr his deputy at Ahmadabad and goes to Sorath, 326, 327, confirms Kingor and Fakir-dāmlah, appoints Tembak Pādā his deputy, 329, is appointed his brother's deputy in Gujarāt, 322, 310.  
 KĀYĪTRĪ : Bōm : unsuccessfully besieges Mandh, 381.  
 KĀYĪTRĪ : prince, 23.  
 KĀYĪTRĪ : salt well, 157.  
 KĀYĪTRĪ : morph of the Indus, 534.  
 KĀYĪTRĪ : king of Kumbh, 190.  
 KĀYĪTRĪ : 169.  
 KĀYĪTRĪ : general of Sultan Nāsir-ud-din Kabālah, 512.  
 KĀYĪTRĪ : butcher, 151.  
 KĀYĪTRĪ : father of Umar the second Khilāf, 505.  
 KĀYĪTRĪ : family slaves, usurp government of Nāgaur, dispersed by British contingent (1811), 17.  
 KĀYĪTRĪ : imperial treasury, 213.  
 KĀYĪTRĪ : grant of, 108, 115-116, 125, 126, 129, 51.  
 KĀYĪTRĪ : king of Sorath, killed by Siddharaj, 176.  
 KĀYĪTRĪ : Chulāsama king of Junāgadh (1271-1333), repairs Somnāth after its desecration by Alā-ud-din Khilji, 190.  
 KĀYĪTRĪ : the peninsula of Gon, 547, 548.  
 KĀYĪTRĪ : brother and successor of Nek Alam Khan II. of Broach; his death, 333-339.  
 KĀYĪTRĪ : Kheda, 115, 128.  
 KĀYĪTRĪ : 513.  
 KĀYĪTRĪ : prince, son of Alā-ud-din Khilji, and husband of Devaladevi, 205.

- KHMERES** : Panjāb and Kashmir settlers in Java and Cambohia, 500 note 6, 502.  
**KHOKHAR** : village, inscription at, 204.  
**KHURRAN** 168.  
**KHURSHID RANI** : mother of Nasir-ud-din Khilji (1500-1512) 365.  
**KHUSHAIYAND SHIR** : chief merchant of, Ahmedabad, 333.  
**KHUSHNAWAZ** : White Huma emperor (160-500), 76.  
**KIDARAS** : division of Bactrian Yuchtai, 144.  
**KIECHIA** 116. See Khoda.  
**KIM** 515. See Kaunmoung.  
**KIM KAHODRA** : birth of (1714), 328; customs station its revenue made over to the English by the Baroda minister Ravi (1803), 111.  
**KIRZ** : Capparis aphylla 461.  
**KIRATAKIPPA** : see Kiradu.  
**KIRIYA** : language spoken at Malkhet 519.  
**KIRTIKAMUDRI** : compiled by Samavara, 159, 171, 178, 179, 191, 195, 196, 198, 199.  
**KIRIVARMAAN** : Chalukya king, 107.  
**KIRIHARA** : grandson of Parappa and king of Lata, his grant at Smat 159.  
**KIRIPATA** : brother of Kumarapala, 14.  
**KIRITIRATA** : Patma king, 160.  
**KIRISTAMBHA** : reservoir, 150 note 2.  
**KIS** 54. See Kish.  
**KISH** : probably Kich-Mulim island 514.  
**KISHANGIRAO** : gateway 154 note 1.  
**KI'CHU' AKATIM** : Book of Chines, work of Al Istakhrī, 506 note 9.  
**KITOTI** : last Kushān king, 75 and of Yuchtai, 144.  
**KIT-CHU'ID** : northern Gurjara kingdom (A.D. 620), 3; Chm-sam of Gurjara, 161, 189.  
**KLAIDIOS PROLIMAITIS** : of Alexandria, 537.  
**KOLA** : Kabul river, 537.  
**KOCHHARVA** : goddess in Asaval, 170.  
**KUCHIN** 533.  
**KUDINAR** : town, temple of Ambal, Cat, 12 and note.  
**KODRANA** : town, 535.  
**KOHAR** : town, 538.  
**KOKATMIR** : Mithi settlement at, 136.  
**KOI** : town 519 and note 4, 520.  
**KOLAKA** : town, 538.  
**KOLAMBARATANA** : probably modern Qalon, 183 note.  
**KOLHAPUR** : Kumarapala's visit to, 183.  
**KOLIS** : rebellion of 43.  
**KONDAL** : Gomhal, 517.  
**KONKANA** : northern boundary of (A.D. 88-), 5 note, 524, 527, 528, 531.  
**KONYALAI** : village, 127.  
**KOPALADIN** : the residence of Bāghoba after the treaty of Sālba, 410.  
**KOPIOS** : town on the Nile, 535-536.  
**KORI** : 538.  
**KOSAD** : village, 128.  
**KOSAIAS** : 469.  
**KOSMA INDIKOPLEFUS** : shipman and monk, author of Topographia Christiana (530-550), 547.  
**KOTIRIA** : Arab commander, checks Chinese advance (709) 501.  
**KOTIRUR** : village 126.  
**KOTUMBA** : boats, 515.  
**KOTWAL** : city police inspector, 211.  
**KOZILAKADAPPA** : Indo-Skythian king, 536.  
**KRISHAN** : 537, 546.  
**KRISHNA** : father of Rashtrakuta prince, India, 120; Dakṣiṇa Rashtrakuta king (765), 121, 122; Akalavarsha, last Guptat Rashtrakuta king (888-128; Alalavarsha, Dakṣiṇa Rashtrakuta king (888-911) brings south Gujarat under the sway of the Dakṣiṇa, 128-129.  
**KRISHNA** : boundary connection with Dwārakā 8-11; incarnation of Vishnu, his image at Veraval 81; claimed by the Chudasamīs as their ancestor, 139, 178; builds the Somnatha temple, 190; claimed by Gujjaras as their ancestor 461.  
**KRISHNA III** : Rashtrakuta king, 169.  
**KRISHNADITYA** : chief general of Siddharapa and brother-in-law of Kumarapala, 181, 182; helps Kumarapala to secure the throne, 183; murders Kumarapala, 184.  
**KRISHNACH** : foster son of Kāmalajī, captures the fort of Chāmpāner (1728), 398.  
**KRISHNADITYA** : Purnima king, 170.  
**KSHATRIYAS** : dynasty of 1147 A.D. 398-1, the name, 461 note 21; northern and western, 2-4, 65, 66; dynasty of 161.  
**KSHATRIYA** : 161 note 2, 165, 530, 531.  
**KSHIMAKATA** : Chavadi king (841-880) of Anahilavala, 127 note 2, 151, 155.  
**KSHIMAKATA** : son of Bhima I, Chalukya king of Anahilavala, 169, 170, 181.  
**KSHIMARAPPA** : 161.  
**KUTIAS** : (P.C. 100), 532.  
**KUTIA** : see Kuta.  
**KUTIA** : name of province, 36 and note 7.  
**KUTAMMALI** : Qulon, apparently of the Malabar coast maritime island, 509 and note 2.  
**KUTACHANDRA** : general of the Malwa king, invades and sacks Anahilavala city, 163-164.  
**KUTU** : country of South, 529.  
**KUYAN** : temple in, visited by Garuda Bala-sena 190.  
**KUMARADITYA** : Gupta queen (c. 360 A.D.), 61 and note 1.  
**KUMARAGUPTA** : Gupta king (A.D. 330), -2.  
**KUMARAGUPTA I** : sixth Gupta king (A.D. 116-155), inscriptions, coins, 66, 67, 68-69, 71, 78 note, 80.  
**KUMARAGUPTA II** : Gupta king, 74.  
**KUMARATA** : local chief 172 and note 1.  
**KUMARATA** : Chalukya king (1143-1171), 156, 170, 176; his ancestry 179, 181; his death planned by Siddharapa, goes into exile; his wanderings; coins issued in his name by Pratāpasimha, is chosen king, 182-183; rewards his friends in exile; his wars with the kings of Sāmliha, Malwa, the Konkan, and Surashtra, 184-187; traditions regarding his Seodha Rani, 188; extent of his kingdom; construction of the temple of Somnatha; his vow to keep apart from women and eschew flesh and wine, 189; his Jani benefactions; is credited with building 1144 temple; scholars at his court, 190; dies, 194.

- KUMARAPĀLACHARIYA**: life of Kumārapāla in Sanskrit, 149 note 3, 170, 177 note 1, 178, 182, 185, 186.
- KUMARAPĀLAPRAHANDYA**: history of Kumbhārapāla in Sanskrit, 149 note 1, 173, 183, 194.
- KUMĀRAŚĪVA**: temple of, 172.
- KUMĀRIS**: 500. See Khmers.
- KUMĀYA**: Rana of Chitor, defeated by Mahmūd Khilji (1113), 361.
- KUMHARS**: potters, 151.
- KUMKAR**: Kofkum, 506.
- KUMDABHATTIA**: granted to the Kavi grant, 126.
- KUMDACHANIKIA**: Digambara Jain from Karnataka his religious discourse with Devasmi and defeat, 181.
- KUMKANAS**: great Naga Brahmins, 5 page.
- KUMBH**: king of, present at the *svamimela* on choice marriage of Durlabhidēvi, 153.
- KUMBHAKHURA**: holy place, 161.
- KUMBS**: 169.
- KURUSTAKA**: investiture festival at, 130 and note 3.
- KURVA**: Son of Rama of the Solimara, measurement of Vishnu, 149.
- KUSASTHANA**: name of Dwarka, 8.
- KUSHAN**: 156 note 1, dynasty, 461, warlike.
- KUSKA**: disciple of Nalukisa, founder of a branch of Paupata school, 81.
- KUTIA**: an attribute meaning prominent, 119.
- KUTUB-D-DIN**: Mughal general in Gujarat, captures Navanagar and annexes the territory (1664), 283.
- KUTUB-D-DIN ATOK**: defeats Kaveri Vaghela (1297), 512.
- KUTUB-D-DIN GIBAK**: Delhi emperor (1394), 229 advances to Kol, 519 and note 1.
- KUTUB-D-DIN SHAH**: king of Gujarat, defeats Mahmūd Khilji of Malwa (170), etc.
- KUTUMBIN**: old name for cultivators, 1.
- KUTALS**: princes, 215 note 2.
- LALITH**: Torumān's father, 71-7.
- LAHAWAR**: Lahori Bindar, etc.
- LAHORE**: city of Hindus, 530.
- LAKHA**: son of Phula king of Kachhi, slain by Mularaja, 160.
- LAKSHAVARMAN**: 169.
- LAKSHMI**: daughter of king of Chedi married to Jagadnaga son of Krishna, 130. Younger sister of Mahendra married to Naga Raja, 163.
- LAKSHMI**: temple of, 160.
- LAKSHMI**: daughter of Brighm, 161-162.
- LAKSHMANBHALA**: Lakshmi's settlement, 152.
- LAKULISA**: founder of Paupata sect, chief shrine at Kārayana, 83, 84. See Nakulisa.
- LALITABHETI**: wife of Vastupala, 202.
- LALLIYA**: the Śālin of Ohmā near Swat, 168.
- LAMB**: Mr., chief of the English factory at Surat; sends Mulla Fakhr-ud-din in disguise to Bombay, 332; his suicide, 333.
- LAND ASSESSMENT**: under Vālidhū, 82 and 83.
- LAND TAX**: under Mughals, 212.
- LANJA BHATTA**: Bhatta prince, son-in-law of Saddharaja, 171 note 1.
- LAR**: seat of a Guclia prince, tribe, 191 note 1.
- LAR DESH**: South Gujarat, 520, 521.
- LARKE**: the province Lita, 7-539.
- LARIYAN**: language, 516, 523.
- LARWI**: Sea (Indian Ocean), 510, language, 521.
- LASSIN**: 532-533, 536.
- LARA**: ancient name of central and southern Gujarat 5 note 1-6-7 and note 5-116, 117; its conquest by Kuntidurga, 12; its chief deserted Lavamprasad and pained Singhana, 199, 165-167, 168.
- LARAS**: 165-167.
- LARPA**: same as Ratta, 7.
- LAROTARA**: original city of the Rattas, 7.
- LAVNI**: 518.
- LAVI MUR**: Red Sea, 112.
- LAVANAPRASADA**: 196-197, Vaghela chieftain (1200-1215) minister of Bhima II, rule of Andharavata in his sovereign's name, 199; he was with the Devagiri Yadavs and the Marwar chief, his abdication in favour of his son Vimalavata, 198-200, 206.
- LAVANAPRASADA**: see Lavamprasad.
- LEGENDARY ORIGINS**: of Gommāthi, 521.
- LEGENDS**: of Gujarat, 8-11, of Bhimād, 461-463, of Jait 197.
- LENGAS DA ASIA** (A.D. 1497-1539) work of Cortes, a Portuguese writer (1512-1550), 349.
- LEWAT** (Leucocytes), porcupine quills, 516.
- LEWA**: Gujarat Kumbh subdivision, 4 and 5.
- LEW**: certain measure of distance, 79.
- LEUCHAVAS**: dynasty of the, 61 and note 1, 63.
- LEUC SAVING**: Jait used for, 193.
- LEUDEVAT**: sister of Samantasūha married to Raj 157.
- LEUDEVAT**: queen of Bhima II, daughter of Chohin chief Samantasūha, 197.
- LEWAS**: of the country under Kumārapāla's sway, 181 and note 1.
- LEWDEHAT**: Malabar coast, 513, Tāmil country, 516.
- LESGAM**: worship of the, 521, 522.
- LESGANESASANA**: a work on genders compiled by Hemachandra, 193.
- LENGAS**: 161.
- LENGHAI**: village place of *legas*, 81 note.
- LOCAL CHIEFS**: power of, 228.
- LODRA**: gathering of Thakurs at (1557), 113.
- LOHARS**: blacksmiths, 151.
- LOSTHARI**: mouth of the Indus, 538.
- LOTHI TEMPLE**: 193.
- LOTHARA**: village, engagement of the Marāthas with the Kolis at, 338.
- LOTHAPALA**: Vastupāla's chief supporter, shrine, 200 note 2.
- LUNAKHIA**: disturbance at, crushed by Lieutenant Adnan, 111.
- LUNAKHIA**: 538.
- LUNIGA**: chief, 170.

**MADANAPATA** : brother of Karna's mother, his death, 172.

**MADANARAJNI** : wife of Lavaneprāsada, 198.

**MADANAVARMAN** : Chandela king of Mahabala, modern Mahoba, his inscription, his surrender to Siddhamaja, his hospitality, 178-179.

**MADHAVA** : Nagar Brahman, minister of Karna-deva, invites Muhammadans into Gujarat, is appointed civil minister of Alai Khan, 205 and note 2.

**MADHARAY GAIKW** (R) : brother of Pādaji, takes Dandak (1734) from Sīdā Khan Bādu the governor, 391.

**MADHARAY PISHWA** : son and successor of Bādaji Pishwa (762-1772), 399, marches against Raghoba and defeats him at Dhodap (176) 400.

**MADHARAY** : country between the Ganges and the Yamunā, 161-168.

**MADINA** : sacred place of the Muhammadans, 201.

**MADINAKAS** : tribe, 61 and note 3.

**MADINA** : 505.

**MAGA** : Brahmins, sun-worshippers, 450.

**MAGADHA** : Gupta rule in (7th century), 73-77.

**MAGANCAI** : agent of Bīpm Chākwān, a political refugee at Ahmedabad, 113.

**MAGAS** : sun-worshippers, 142.

**MAGHA** : Sanskrit poet, 453 note 1.

**MAGHA** : Brahmins, 161, 165. See Magas.

**MAGHAR KHAN** : thirty third viceroy of Gujarat (1662-1668) suppresses the rebellion of the Chuvādi Kohis headed by a Beluch personating Dārā Shukoh (1664), 283.

**MAHABHARATA** : 515.

**MAHARAJ SINDIA** : receives the town of Broach from the English, 110.

**MAHARANS** : 450.

**MAHARASHTRI** : temple of, 151, 171.

**MAHARASA** : Gujrat princess, married to a Kanvākubja king, 151.

**MAHARASA** : attribute of priestly Brahmins, 5.

**MAHARATAPMANY** : Jain temple at Salipur, 172.

**MAHARASHTRA** : southern boundary of Vaidhaval's kingdom, 201.

**MAHARASA** : 193.

**MAHARASA** : Raja of Nadol, holds a *stānamāra* or choice-marrriage of his sister, 162, 163.

**MAHARWAR MAHARAJ** : shān of, 151.

**MAHARABCHERYA** : granted in the Haddila copperplate, 138.

**MĀHĪ** : river, 124, 167, 513.

**MAHĪ KĀNHA** : Colonel Walker's titlote system introduced in (1808), 124.

**MĀHIM** : port, 207 note 1.

**MAHIMBHI** : the river Mahi, 510.

**MAHESHA** : Chulāsama ruler of Kathiavādi (917), his coins, 138. Brother of Kumārāpala, 181; father of Ajayapāla, Chulhukya king, 194. \* King of Gurjara, 466, 469.

**MAHESHADEVYA** : see Mahipāla.

**MAHESHADEVYA** : Rājā Sālāh, 180 note 2.

**MAHESHA** : of Ghuzni, sacks Somanatha and attacks Anahlavādi and other places, 164-

168, 219, 498, 510, 512, 517, 522 and note 1, 523.

**MAHMOUD BAGADA** : Ahmedābād king (1459-1513), 213-250, defeats a conspiracy of his nobles (1459), improves the soldiery (1459-1461), 243-244, helps the king of the Dakhan against the Sultan of Malwa (1461) 244-245; his expedition against the acute Zamindars of the full fort of Barur and the wharf of Durr or Dahann; his expedition against Junagadh (1467) and capture of Gurner (1472), 245, repairs the fort of Jachinmad and makes Junagadh his capital under the name of Mustalabād, 245-246, expedition against Sindh and defeat of the Jachpās in Kachh, takes the fort of Jagat or Dwarla and destroys the idol temples, 246, founds the city of Muhammadabad on the Vatriak, second conspiracy of the nobles (1486) headed by Khindawand Khan, his war against Chām-pura (1482-1484), captures Prvagad (1484) and makes Chāmpura his capital under the name of Muhammadabad, 247, invades Somanatha (1490, 1491), places his nephew Miran Muhammadadil Khan Tarkhi on the throne of Asir-Burhman (1508), 248, his religious zeal; his death (1513) 249-250.

**MAHMOUDS** : coin, 222 note 2.

**MAHOLA** : in Bundelkhand, 178.

**MAHOMIDAS** : wives, 516.

**MAHRAH** : the Maratha country, 521.

**MAHRAH** : 519. See Mathma.

**MAIS** : Mathura, 511.

**MAHIMAS** : 169.

**MAHIMKAS** : tribal name of Mehars, 75 and note 6, 87-88, identified with Mhars, 135, 136, 141, 142 and note 2.

**MAHIMYA** : disciple of Nakhśa, founder of a branch of Pāsupata school, 84.

**MAHIMYA** : village, 176.

**MAHIMKAS** : district accountants, 22, 213 note 2.

**MAHARA** : fish tribal lodge of the Mehars, 87, 135.

**MAHARAHIVARA** : chief of Mehars, his fights with Maymadhivara, 7, ancestor of Mheri chiefs of Porbandar, 135.

**MAKKA** : 204.

**MAKKAH** : 511, 520. See Mahla.

**MAKKAH** : 508, 511, 516.

**MAKKAH** : same as Jhadra, 110.

**MAKKAH** : port of, 515, 529, 537.

**MAKKAH** : chief minister of Arjuna-deva and Sārngadeva, 201.

**MAKKAH** : tribe, 28; kingdom of, 61; era, 67, 124, 165, 167, 169. See Mālwa.

**MĀKAYVA** : lake at Dholka, built by Siddharāja, 180 note 2.

**MALCOLM** : Sir John, 180 note 3; (1820), 33.

**MALLO** : name of, identification of, 539.

**MALF** : Mī, chief of the English at Surat, 102.

**MALF** : Mount, 533.

**MALHARAY** : son of Khanderiv Chākwār, retires on a pension to Nārād, 412, breaks out in rebellion in Kathiavādi, is captured by Bādaji Appaji and Vithal Devaji, 413.

- MAHARAJA GAIKWAR**: called *Dādā Sahab*, takes part in the Maratha conspiracy at Baroda (1877), escapes punishment, is imprisoned, succeeds Khandorāy, is deposed (1878), 112-113.
- MAHARAJA HOLKAR**: Bājirāy, Peshwa's officer, plunders Dandā and Vadnagar and exacts tribute from Palanpur, 387, offends Dāyā Bahādūr, governor of Māndh and captures Māndh, 382.
- MAHARAJA KIRKAR**: Dandājī Gaikwār's deputy at Ahmedabad, collects tribute in Gujarat (1710), 322, 323.
- MAL**: apparently Malh in north Kāthiāwāda, capture of, 506 and note 5, island 509.
- MALIA**: temple at, 153, Rapt of, plunders Kachh and Sindh, 122.
- MALWA**: identified with Malwa, expedition against, 109, 107.
- MALIK BAYAZID**: son and successor of Chāmpat Khan Sultan of Malwa, with the title of Rīz Bahadūr (1565-1570), 369.
- MALIKHANS**: Nodduham Ling, 512-513.
- MALIK KAPUR**: Sultan Fīrūzshah, deposes Zān-d-din Bāmir to Broach, 511.
- MALIK KAPUR**: Chumbay slave, rises in Bahā emperor's favour, is sent to subdue the Dāhli 203, 229.
- MALIK MECHIS MECHIS**: minister of Subhan Ho-lang (1105-1131), 370.
- MALIK MUZZI DŌS**: conquers Gujarat and plunders Kambayāt, 515.
- MALIK MUKHĀ**: Gujarat governor, 230.
- MALIK TUGHAN**: captain of horsebores (1317), 270-231.
- MALIS**: gardeners, 150.
- MALINDVA**: Mount, 533.
- MALIPPALA**: town 510.
- MALKHED**: capital of the late Rāshtrakūṭa, 120. See *Mumakhet*.
- MALKHET**: Malkh, 511; destroyed by Tailappa, Chālukya king (972), 519.
- MALIK (MALIK)**: Sīdhārā king of the Konkan (1160) is killed in battle by Kumārāpala's general, 180, his stone inscriptions, 186.
- MALIK KHAN**: commandant of Malh assumes the title of Rādhashāh, 371 and makes Malh his capital, indifference of to the orders of Sher Shāh Sūr, does homage to Sher Shāh at Srirangpur (1542), flies to Gujarat and attacks Malh with Gujarat forces, the defeat of, by one of Sher Shāh's generals, 368, 369.
- MALH**: name, 531.
- MALWA**: 24, 28, Gupta conquest of, 67; conquered by Gōvinda III, Rāshtrakūṭa king, 123, 124; its king taken prisoner by Siddharaja, 175; annexed to Chālukya kingdom by Siddharaja, 178, its king Bāhala defeated by Kumārāpala, 185, its king crushed by Viśālaya, 203, incorporation of, to Gujarat by Sultān Bahādūr of Gujarat (1526-1536), invasion of, by the emperor Humayūn (1534), 367, under Sher Shāh Sūr (1542-1545), 368; under his successor Salm Shāh (1545-1553), becomes independent under Shujāt in 1554, 369, 510. See *Mahila*.
- MAWA SUKAPALA**: (1400-1570), 356-371.
- MAWARS**: 513, 511.
- MAWHA**: 508, 509 note 3, 511. See *Anahilavāda*.
- MAWA**: see *Manna*.
- MAWHA**: brother of Fatchsingh Gaikwār, assumes the government of Baroda, 110; his death, 111.
- MAWHA MURAR**: Sonopati of Rāja Shāh, 389.
- MAWANKA**: early Rāshtrakūṭa prince, Rāshtrakūṭa family, 120.
- MAWAPURA**: city 51-52, 132.
- MAWASAS**: associated with the introduction of sun-worship 112.
- MAW**: maritime island, 509.
- MANDAGABA**: identified with Mandangad, 541.
- MANDAGA**: Sūha class of sun-worshippers, 112.
- MANDAGORA**: 516. See *Mandangad*.
- MANDAI**: village near Anungim, expedition against, 109, 518, 520 and note 2.
- MANDALA**: kingdom 130.
- MANDALI**: modern Mandala, Mulanāthadev, temple at, 161 and note 2.
- MANDALIKA**: Chudāsama ruler of Junāgadh, 70.
- MANDALI-NAGARA**: temple of Mahesvara at, 161 and note 2.
- MANDAGAD**: 516.
- MANDALIKĀ**: gold camp, won from Kama the Chāch Ling and presented to Samantitha, 163.
- MANDASON**: town in western Malwa, 77, inscription of Ansh Varman at, 81, defeat of Sul-tān Bahādūr of Gujarat at (1541), 367.
- MANDH**: traveller (1623) 521 note 2; at Ahmedabad (1638), 279 note 2.
- MAWAS**: identified with Mers, 100 and note 5, 112 and note 2 508.
- MANDH**: expedition against (1390) 232 (1419) 237, full list, description of, 352-356, is made capital of Malwa by Sultān Hoshang, 358; besieged by Alupshah of Gujarat (1418-1422) 359 captured by Mahmūd II of Malwa and Muzaffar of Gujarat (1519), besieged by Sultān Bahādūr of Gujarat (1529), 367; local Musalman chiefs attempt to establish at (1536-1542), Malh Khan the Sultān of, 368, captured by Akbar's general Pir Muhammad (1560), retaken by Sultān Bīz Bahādūr (1561), recaptured by Akbar's general Abdullah Khān Uzlak (1562), visited by Akbar (1563), 369, Mughal province (1570-1720) 370, 371 is given to Muzaffar III of Gujarat by Akbar, 371; described by Abul Fazl (1590) Farishtah (1610), emperor Jahāngir (1617), the Reverend Edward Terry (1617) 371-381; besieged by Khan Jafār Lodh, 381; captured by Jāy Pāvār (1696) and emperor Bahādūr Shāh (1708), Asaph-oh Nizām-ul-Mulk, governor (1717-1721); Rāja Giridhar Bahādūr, governor (1722-1724); defeated by Chimanājī Pandit and Udājī Pāvār; Bājirāy Peshwa, governor of

- (1734); included in the Payár territory; Mumtaz, mother of R. Ruchandri Payár, takes shelter in (1805), 382; under the Marathas, (1720-1820), 382.
- MANGALAPIPA**, establishment of a gess at, 176.
- MANGALAPURI**, identified with Puri, 108.
- MANGAIAR GJA**, Gujarát Chahukya ruler (698-731), 56, his plates 108-109; at Navsari 110.
- MANGALVARASAR GYA**, 56. See **Mingalar Gja**.
- MANGALISA**, Chahukya king (600), 111.
- MANGHOL**, Veláti betelvine cultivators' settlement at, 113 note 3; village, *simpa* via mentioned in an inscription at, 176. See **Mangalapura**.
- MANGAIOR**, 537.
- MANGROL**, port, burned by the Portuguese (1582), 317.
- MANKIR**: 511, 518, 519. See **Malkhet**.
- MANGEL DI SOT ZA**, same as **Imagel Desonza**, captain of the fleet of Dm 349, 350, 351.
- MANSUR**: identification of, 541.
- MANSÁ**: taken by Dmápi 321.
- MANSURA**, in Central Sind, invaded by Mahmud of Ghazni 167.
- MANSURAH**, 506, 507, 511, 515. See **Mansura**.
- MANSURVA**, Biluka town, 534.
- MANPRAASTHIS**, proficient in charms 161.
- MANTRIS**: agents 209.
- MANSARKHIV**, modern Malkhet 120, capital of Dakhin Ráshtrakútas, 128, 130, 519. See **Malkhet**.
- MANSARVA**: king of east Malwa, submits to Govind III, 123.
- MARASHALI**, Marwar 170.
- MARÍTHAS**, their ascendancy in Gujarát (1760-1802), 227, ends on Surat (1661), 284, (1696) 291, threaten Surat (1700), 212, enter Gujarát under Dhamaji Jadhav (1705), 293, plunder Mahadha, enter Ahmedabad and levy tribute (1707), 295, 296, defeated at Ankleshvar (1711), 297; plunder the treasures sent by Muhammad Tahir (1713), 358, yearly raids into Gujarát, 297, besiege Vadnagar (1725), 307; quarrels between their leaders Dmápi and Kántápi, under Dmápi expel the Virangám Kshátrís, under Rangop are defeated at Dholli by Bhatansingh, 316, 317, defeat Rustam Ali governor of Surat, 305, defeated by Khánahad at Soptra, and Kapadvanj (1725), 307, compel Muláriz ul-mulk to confirm his predecessor's grants in their favour (1726), 307, make terms with the viceroy of Gujarát, 314; driven out of Baroda (1732), 394, defeat Sher Khán Báhi and capture Baroda (1734), 314-315, capture Kapadvanj (1736), 317; expelled from Virangám fort; call in the aid of Momu Khán; take Virangám, 323-324, take Pethál, 327; engagements with Momu Khán, 340, 341, 342; their arrangements in Ahmedabad (1758); strike coins of their own at the Ahmedabad mint, 342; levy tribute in Umeta, Bálóságar, Lamaváda, Visalnagar, and Pálanpur (1758), 343; their supremacy in Gujarát (1760-1819), 315, 385; help the Rao of Kachh in an expedition against Thattu in Sind (1758), 398, join in attack against the English (1780); driven from their posts in Angleshvar, Hapsot, and Amud by the English (1780), 408; chase of their supremacy (1819), 128-429.
- MARCO POLO**: Italian traveller (1290), 501, 504.
- MARÍTHAS AGMÍTHAS ANTONINIS**: (161-180), 537.
- MARINOS**, of Pura, 537.
- MARRIANDS**, geographer (n.c. 100), 516.
- MARONIA**, tribe, 534.
- MARIVAGAS**, 187 and note 1.
- MARV**, ancient name of Marwar, 36 and note 1, 165, 168.
- MARWAR**: Marwar, expedition against, 109, 167.
- MARWAR**, king of, present with Grahapuri in the battle with Mulnaga, 160, chiefs of, attack Lavanaprasad and are defeated, 199, 200 disturbance in (1692), 289, 464, 532.
- MASAIWADA**, local name, 298 note 3.
- MASMI**, 169, 198. See **Al Masmi**.
- MASUPARIAM**, 191.
- MATAR**, taluka of the Kaira district, 122 and note 3.
- MATARIUM**, in the island of Java, 189.
- MATAY MAHIDHA**, made over to the English by Raghu, Baroda minister, in payment of the subahdar force at Baroda (1763), 111.
- MATAS**, goddesses 161.
- MATHOI**, tribe, 531.
- MATHURA**, local in Mathura, 519.
- MATHURIA**, king of, present at the *vyagamvata* or choosamarriage of Durladhadvi, 163, Prince Mucád confined in (1581), 282, 533.
- MATIAS**, with Mommas march against Bionch, and murder the governor (1691), then defeat and slaughter, 288.
- MATIR**, 122. See **Mátar**.
- MATIR**, northern Kshatriya king (n.c. 70), 22.
- MAINA**, Purank name for the Hindus, 141 note 2, 143.
- MATRYA**, chiefs, later (500), 15; ruling dynasty of the Konkani, 107, kingdom identified with Mativas of Clator, 109, of Clator, 165; empire n.c. 100, 535.
- MATRYA**, peacock, symbol of the Guptas, 135.
- MATRYADHYA**, 135.
- MATRYKHAS**, of. See **Morkhand**.
- MCCRINTY**, Mr., 538, 541.
- MEVA**, see **Meva**.
- MEHASTRI**, commander-in-chief of Mahmud II. of Malwa (1512-1530), suppresses the revolt of Mahabz Khán, defeats the combination of Muzaffar II. of Gujarát and Sikandar Shah of Delhi; attempts of Mahmud II. of Malwa for the assassination of; expulsion of, with terrible slaughter by joint forces of Mahmud II. and Sultan Muzaffar of Gujarát; supported by Rama Sanga of Chitor, 366-367.
- MEHIS**: 140; Bawárij pirates, 517. See **Mehrs**.
- MEHS**, 140; Mánds, 508, 511. See **Mehs**.
- MELIUS HYDASPES**, Virgil's phrase for the Jhelum, 144.

- MEKALTE**: the Mekalas, 532, 533  
**MEGARI**, tribe, 534  
**MEGASTHENES**, ambassador of Seleukos Nikator, his account of India, 532, 533, 534, 535, 536, 537.  
**MEHMOU II.** (1512-1530), son and successor of Nasir-ud-din of Māndu, revolt of his commandant Muḥaḥḥ Khan crushed by his Rajput commander-in-chief Medani Rāi, combination by Muzāḥar II (1511-1526) of Gujarat and Sikandar Shah of Dehli (1488-1560) baffled by Medani Rāi, the attempt of, to crush the power of Medani Rāi, siege of Māndu by Sultan Muzāḥar of Gujarat (1511-1526), massacre of Rajputs, capture of Māndu, defeat and capture of, by Rana Sangh of Chitor, men's the wrath of Bahadur Shah of Gujarat by giving protection to Chand Khan and Razi-ul-mulk, invasion and capture of Māndu by Bahadur Shah of Gujarat, surrender and death of, 366-367.  
**MEHMUD II.** (1626)  
**MEHMDIYAD**, town in Gujarat, 219 note 3  
**MEHMOU KICCA**, son and minister of Sultan Hoshang of Malwa (1165-1191), 379  
**MEHMOU KICCAI**, becomes Sultan of Malwa (1436), his victory over Rana Kumal of Chitor (1440), builds his tower of victory, is defeated by Kutub-ud-din Shah of Gujarat (1453), makes his son Ghias-ud-din minister, his death (1469), 362  
**MEHR**, northern tribal name, 87, Hindu name of, 87.  
**MEHRAN**, the Indus, 540.  
**MEHARS**, sweepers, 151  
**MEKONG**, river, 504.  
**MEKONGARA**, probably Lampu, 536, 540, 546  
**MENANDER**, Baktiṇ king of India, 16, 17  
**MENANDROS** (see III) conqueror of, 545-544, 545  
**MENDAN**, town in Java, 190  
**MENFANG**, town, built by Bhuvijaya Jayachand, 189  
**MEIS**, Musalmān, identified with Mei, 110 and note 8.  
**MERL**, 542  
**MERS**, sun worshipping foreigners (c. 900), passed through Punjab, 8, 24, 10, north Gujarat into Kathiawar and ruled there (770), allied to Jethvas and Jhalas, descendants of Huzas, 135-147  
**MEETUA**, district, conferred upon Durgadas by the emperor Aurangzib (1697), 290.  
**MEHURTINGA**, author of Prabandha-kintamani, 151, 152, 155, 156, 196.  
**MESSE**, tribe, 534.  
**METHORA**, modern Mathura, 533.  
**MEVAS**, name of tribe, 33.  
**MEWAS**, origin of the name, 33, Kumarāpala's conquests extend to, 188; chief of, subdued by Viśaladeva, 203.  
**MEWAR**, 532, 533. See Mewar.  
**MEYDS**, 142.  
**MIHARVADA**, Mier settlement at, 136.  
**MINW.** Colonel Pratt, Captain Fagan, and Captain Harris murdered at, (1857); Colonel Durand, Resident, expelled from, 138.  
**MIGRATION**: from India to Indo-China, traces of, 199.  
**MINIRA**, king of Kāthiawar Mehrs; his invasions against Dhruva II, 127, tribe, 135-147, or Gujjara conquest of Vatabhi (190), 189, 190.  
**MINIRAGAS**, 142 and note 5.  
**MINIRAKVIA**, king of the White Hūnas (504-530), 72, 74, 75, 76, 142 and note 2, son of Toramana (500-510), 116, 165, 196, 497.  
**MINIRGITA**, Indian emperor of the White Hūnas 143.  
**MITZGARIS**, modern Junjra, 510. See Mehargara.  
**MINIS**, of gold and silver in Gujarat, 528.  
**MINNARIS-SHAI**, 195 note 1.  
**MISNAGALA**, ancient Greek capital, 15 note 3, 538, 540, 543, 544.  
**MISS**, identified with Meis, 110.  
**MIHAR-JAHMADI**, 205, the author of, suppresses the riots at Ahmedabad and is rewarded with the title of Hassan Muhammad Khān (1730), 310; superintendent of customs, 328, 337.  
**MIHAR-SULANDARI**, Muḥammad history of Gujarat (1536), 548, 543.  
**MIH-PAKIR-UD-DIN**, obtains the governorship of Junjra from the victory Abheysingh (1730) 311  
**MIKHAND**, 168.  
**MIH-MHAMMAO I**, 168, minister of Azam Khan victory of Gujarat (1635-1642), 298.  
**MIHA AZIZ KOKTASH**, Mughal victory, 242.  
**MIHA ISA-TAPKAN**, governor of Sorath, afterwards twenty-fourth Mughal viceroy of Gujarat (1612-1614), 212, 279.  
**MIHAR MIHARMI**, Arab traveller and writer, 510 note 1, 516, 517 note 1.  
**MIHASKOT**, town, 548.  
**MIHSAHABAT**, daughter of Jayakoti, kṛug of the Karmuk queen of Karna and mother of Siddhartha Jayasinha, her regency, her pilgrimage to Sonamatha, remits pilgrim tax, 170-172.  
**MIHAR**, shoemaker, 151.  
**MIHARA**, town, capture of (1414), 236.  
**MIHAR ASANIKHA**, Jain monastery at Dhan-dhula, 191.  
**MIHARAVINCA**, the Palungas, 532, 533.  
**MIHARAVIA**, probably Mudhol, 541.  
**MIHARA**, modern Madura, 537.  
**MIKIRHAR**, Gohel chief of Pirān (1347), 87 note, 230.  
**MIHARMI**, Indian tribe, 533.  
**MIHAR KHAN I.**, is appointed governor of Surat by Nizam-ul-Mulk (1722), 303; is made governor of Cambay by Abheysingh (1730), 311, 312, 315, 316; schemes independence at Cambay (1736), 317; is appointed fifty-fourth viceroy of Gujarat (1737), assumes the title Nizam-ud-daulah Momin Khān Bahādur Firūz Jang; asks Jawāḥir Mard Khān Bābi to help him, his disastrous alliance with the Marāṭhas which gives a final blow to Mughal power in Gujarat, 318; receives secret instructions to disregard the appointment of Abheysingh fifty-fifth viceroy and to drive

- his Rathhuds from Gujarāt, 319, captures Ahmedabād (1738), is appointed fifty-sixth viceroy (1738-1743), 320, is honoured with a title and dress by the emperor of Delhi (1742), 325, his death (1743), his wife seeks protection of Rangoji, 326.
- MUMIN KHAN II.**, son of Momin Khan I., 207, is confirmed as governor of Cambay (1748), 330, 331, at his request Cambay is included in Peshwa's share (1741), 331, is compelled by Raghunathrao to pay an annual tribute of Rs. 10,000 (1757), 338, takes Gogha, attacks Janabasa and besieges Bhand (1759), 339, captures Ahmedabad (1760), 339, receives compliments and a sword from the emperor of Delhi 310, besieged in Ahmedabad, receives help from the Raja of Idar, Shah Nur's attempt to make peace between Momin Khan and the Peshwa fails, Ahmedabad and Gogha surrendered to the Peshwa (1761), 341, 342, oppresses and extorts money from his followers, 342; contracts friendship with the English and visits Poona (1759), 343, 344, receives instructions from Delhi to join in driving the Marathas out of Gujarāt, is defeated (1761), 345.
- MOMIAS**: revolt of (1691), 288.
- MOMIDIS**: Munda of Sonbham, 533.
- MOMODASSON**: Munda of Mangrol, 635.
- MOMINS**: river Mahr, 539.
- MOMIN**: copperplate of Jambadevan 21, 87, earliest set of Jathvas, 136, grant of Jambadevan, 139.
- MORHANDA**, capital of the country ruled by Govinda, son of Dhruva, Rashtrakuta king, 123.
- MORO TRIMAI**: Shivaji's general, captures the fort of Sakri in Baglan (1672), 387.
- MULANI**: tribe 534.
- MOSTYN**, Mr., resident envoy in Poona (1777) 407.
- MOTAKA**: Brahman settlement of, 127.
- MORSORAIK**: provisionally identified with Karvir, 542.
- MOTZA**: modern Musa, 543-545.
- MOZAIAR**: givades Sonanatha, 190.
- MU'AZZAM**, son of Aurangzib and commander of the Mughl army sent against Shivaji 387.
- MU'AZZAM SHAH**: Prince Muhammad 296, 297. See Bahadur Shah of Delhi.
- MUBARAK KHAN**: emperor, 229.
- MUBARIZ-UL-MULK**: 304-306, 307, 308, 309, 310, 311. See Farhad Khan.
- MUTFRID KHAN**: son of Momin Khan schemes of Rangoji for the assassination of, unites his forces with Fida-ud-din Khan, defeats Rangoji and obtains Darsad and Virangim from him, 326; fifty-seventh viceroy (1743-1744), appoints Jawan Mard Khan his deputy, the house of, besieged by Jawan Mard Khan, his escape, joins Rangoji and retires to Cambay, 327.
- MUGHAIRA**: brother of Hakkim, leads an expedition to Debul, 506.
- MUGHALS** the administration of, in Gujarāt (1573-1760), 221-227; emperors in Gujarāt (1573-1760), 207, 345; at Mandu (1570-1720), 370-382.
- MUHAMMAD KHAN**: commandant of Mahmud II of Malwa (1512-1530), the revolt of, suppressed by Mahmud Rai, 366.
- MUHAMMAD**: prophet, his era, 291.
- MUHAMMAD**: son of Fazl, sails against the Mals of Hind and captures Mahr, 506.
- MUHAMMAD**: son of Kasim 506.
- MUHAMMAD IV.** (1618-1657) Turkish Sultan, ambassador from, lands at Surat, 280.
- MUHAMMAD AZIZU SHAH**: thirty-ninth viceroy of Gujarāt (1703-1705), 291.
- MUHAMMAD AMIN**: poisons Abu Baker, the leader and suppresses the riot at Ahmedabad (1681), 286-287.
- MUHAMMAD AMIN KHAN**: Umadut-ul-Mulk, thirty-sixth viceroy of Gujarāt (1674-1683), 285.
- MUHAMMAD BAHLOI KHAN SHIKHANI**: Mughal general, captures Idar (1679), 286.
- MUHAMMAD BIDAR BAKHI**: forty-first viceroy of Gujarāt (1705-6), 291-295.
- MUHAMMAD BUDLA**: ruler of, into Gujarāt 195 note 1, 512, Sultan Ghizni Khan, son and successor of Sultan Hoshang of Malwa (1451-1459) poisoned by Mahmud, son of Malik Mughl, 372-380.
- MUHAMMAD KASIM**: (1712), 176 note 1.
- MUHAMMAD SHAH I.** (1603-1611), 231 and note 1.
- MUHAMMAD SHAH II.** Raushan Alhar, emperor of Delhi (1721-1748), 222, 301, sends Mubarez-ul-Mulk against Humud Khan and the Marathas, 306; his death (1748),
- MUHAMMAD TUGHRAK**: Sultan (1325-1351) 290, 231; at Aswad, 513, expels the usurper from Bhand and Cambay 511, 515, in Goghat (1310) 507, pursues Tagla, 518.
- MUHAMMAD TUGHRAK II.**: emperor (1391-1393) 232.
- MUHAMMAD III.** 195 note 4.
- MUHAMMID**: secretary, 211.
- MURASIN**: city governor, 211.
- MURUD-DIN**: Gujarāt governor (1317), 231.
- MURUD-DIN BAHAM SHAH**: Sultan of Delhi (1191-1207), defeated by Anandhavan, 201.
- MURADDAM**: 242. See Pahl.
- MURTHAL KHAN**: thirty-seventh viceroy of Gujarāt (1683-4) 287.
- MURTHAS**: crown domain officers, 209 and note 2.
- MURATA**: son of Salajen makes grants to Sonanatha, is mentioned in the inscription at Mangrol, 176.
- MURKUBI**: land-raiding system in Kathiawād under the Mughals and Marathas, 417; special rules 418, 421.
- MURANATHAPURA**: temple of, at Mandali, 161 and note 2.
- MULARAJA**: Solanki king, 131, 139, 153, 169, 470. See Mularaja, Chaulukya king.
- MULARAJA**: Chaulukya king (961-996); his descent and birth; kills his maternal uncle and ascends the Chavada throne; his fight with

- # 1746-74**

- NAKHONWAT**: Naga's shrine in Cambodia, begun in A.D. 825 and completed in A.D. 950, 499, 500, 504 and note 1.
- NAKARIBHAIJA**: village, 127.
- NAKELAVARA**: temple of Siva at Kārvān, 83 note.
- NAKULISA**: 83 note and note 1.
- NAKULISA PĀSĪPATA**: sect, 205.
- NALKĀNTHA**: district, 208 and note 3.
- NAMADIS**: the Narmada, 539.
- NAMAGRANTHI**: 161.
- NAMNADIOS**: the Narmada, 515.
- NĀNĀGHĀT**: inscription at, 38.
- NANAGOI NA**: supposed to be the Kāśmādi, 542.
- NANA PHADNIS**: at the head of affairs in Poona (1774); drives Raghoba from power 491; schemes of, against the English, demands the cession of Salsette and the person of Raghoba, 408, his proposals to Govindrao Gaikwār, 411.
- NANDI**: bull, badge of the religion of Vaidika dynasty, 80.
- NĀNDIPURI**: modern Nandod, 1, 5; capital of Gurjjara dynasty of Broach district, 107, palace of Gurjjara kings, 111, capital of the Gurjjars, 113. See Nandor, 113.
- NĀNION**: capital of the Gurjjara dynasty of Broach district, 107, 108, capital of Rajputra, 113. See Nāndipuri and Nandor.
- NANDOL**: in Mārwar, its chief slain by Jayanaprasāda, 198.
- NĀNDOL**: capital of the Gurjjaras, modern Nāndod, 13 and note 3. See Nāndipuri and Nandol.
- NAOURA**: 516.
- NARADJI**: divine sage, 161.
- NĀRĀNA**: 507, 520. See Nārāyan.
- NARASIMHA**: 111. : Hoysali Ballala king of Dyava amudra (A.D. 1251), 203 note 3.
- NARASIMHA**: Kūmātuk king, 169.
- NARASIMHAGUPTA**: Gupta chief, 71, 77.
- NARAYARMA**: king of Mālwa, at war with Siddharāja, 177, his inscription, 173, 180.
- NĀRĀYANA**: minister of war and peace, writer of Karka's Surat grant, 125, writer of Dhruva's Baroda grant, 126, 511 note 12, 520, ancient capital of Gujarat 527.
- NĀRĀYAN**: Banna or Bazāna, battle of (1192), 193 note 1.
- NĀRAYANARĀV PESHWA**: murder of (1772), 401.
- NARBĀDA**: river, special holiness of, 81, its lower valley occupied by wild tribes, 114, crossed by the Marāṭhās for the first time (1675), 198, 387; 444, estuary of, 513.
- NARBHERĀM**: Gaikwār's deputy, 315.
- NARE.Æ**: tribe, 531.
- NARMADA**: 545. See Narbada.
- NARMAZA**: the Narbada, valley of, 510 and note 3.
- NARMIKHAROVAR**: see Nimbali.
- NASARPUR**: town, 517.
- NĀRO PANDIT**: deputy of Sadāshiv Rāmchandra in Ahmedābād, 342.
- NAROTAMDĀS**: Raghoba's agent for negotiating the terms of the treaty of Surat, 402.
- NĀRUKOT**: Nāikda Bhils in revolt at (1858), 411, 415.
- NĀSIKA**: modern Nāsik, 540.
- NĀSIK**: northern Chhukya capital, 112.
- NĀSIR-UD-DIN**: Abdul Kādir, son and successor of Ghāṣ-ud-din (1502 - 1512); poisons his father, becomes Sultan, and subjects his mother Khurshid to indignities and torture, 365. See Abdul Kādir.
- NĀSIR-UD-DIN KĀSHGAR**: Sulṭān (1246 - 1266) deposes his general to attack Nārwāh, 512, 519.
- NASMYTH**, Captain D., 447.
- NĀSIRAT KHĀN**: companion of Alif Khān in the Guprāt expedition, 205, plunders Cambay, 515.
- NAVAKHUSHWAR**: shrine of, 152.
- NAV-ĀRI**: 546.
- NAV-BAHRO**: town, 538.
- NAVAGHANI**: see Noghm.
- NAVĀGAR**: town, 226, revolt of the Jam crushed by Azam Khān victory (1604), 279, chief-lup of, usurped by Rasmahp, captured and annexed and the name changed into Ishmagan by Kutub-ud-din (1631), 283, restored to Tamachi son of Rasmahp, the city remains in the hands of the Mughals till 1707-285; quarrels of the Jam of, with the Rū of Kachh, ejects Baroda agents (1807); British intervention 125, Jam's death, 127.
- NAV-ĀRI**: inscription of Śilāditya at, capital of Jayasimhavarman 297, copperplate of Jayabhatta at 108, capital of Pulike 1, destruction of the Chhukya kingdom of, 110; the great Arādhyaśāst, displaced by Pulakesi Jinasraya at, 117, grant of Karka 1 at, 121, 125, copperplate grants found at, 128; India's copperplates at 128, 130, grant of Chhukya king Pulakesi Jinasraya at, 119, 168.
- NĀWĀR**: of Smā and Broach 211.
- NAZAR ALI KHĀN**: governor of Baroda retakes the fort of Broach from the Mughals and Momnas (1691), 288, nephew of Momin Khān viceroy of Gujarat (1738 - 1743), 325.
- NEKYNDON**: Melkynda of Ptolemy and Nekynda of the Periphs, 537.
- NEARHUS**: 536.
- NEK ĀLAM KHĀN**: Nizām's lieutenant at Broach, 324, governor of Broach dies (1754), 338.
- NEKNĀM KHĀN BAHĀDUR**: the title of Hamidbeg, governor of Broach 339, supports Sayad Achelman at Surat (1759), 313.
- NEKYNDA**: Kallada, 546.
- NĪMĀPIYA**: minister of war and peace of Karka I., 125.
- NĪMĀNTHA**: same temples of, on Satruñjaya, Abu, and Gernār hills, 177, 202.
- NEKNAPA**: grantee in Dhruva II's Bagumrā grant, 131.
- NERĀL**: inscription of Amsuvarman in, 81.
- NETRAVATT**: river, 512.
- NICHOLAS UFFLET**: traveller (1610), 224 note 2.

- NICOLÒ DE CONTI**: traveller (1120 - 444) 220, note 2.
- NIHĀNĀMĀLLĀ**: King of Amalillapataka, 204.
- NIKOLAOS**: of Damascus, 535.
- NIKUMBHĀLLĀ ŚAKTI**: Sindraka chief, his grant, 55-56, 111.
- NILAKANTHA MAHĀDEVĀ**: Kumārīpāla's royal god, 189.
- NILAKANTHĒSVARA MAHĀDEVĀ**: image of, Nile river, 50, 314.
- NILĀ**: queen of Grachapin, 160.
- NILKANTH**: pleasure house at Māndu, visited by Akbar in 1574 and by Jehangir in 1617, 356; inscriptions, 370-371.
- NILKANTH MAHĀDEVĀ**: shrine of, 175.
- NIMACH**: 531.
- NIMNĀT**: tank, 153. See Nirmukhīśvay.
- NIMHORIA BHADRA**: 151.
- NIRHĪLĀKA**: grant of, 58 note 1, chieftain of a wild tribe, 111-115. See Nāga.
- NIRPĀN**: grant of Nigavarddhana Tribhuvanashaya at, 108, 110.
- NIRPPAMA**: another name of Dhruva I. and Dhruva II., 16.
- NISHADA**: country, 36 and note 9.
- NITRA**: identified with Mangalore, 542.
- NITRIAS**: 337, 542. See Nitra.
- NITYAMĀRSHA RĀTĀKANDARPA**: 130.
- NIZĀMSHAH KĪRĪS**: of the Dakhn (1190-1595), 221.
- NIZAM-UL-MULK**: governor of Gujrat (1351), 231. Asafgh. viceroy of Ujjain (1790), retires to the Dakhn, defeats and kills Fayad Dilawar Khan, retires to Amangarbad, battle of Bālpur in the Betas and death of Akbar Khan, deputy viceroy of the Dakhn, 301, appointed joint minister of the empire (1721), 302, his disagreement with Haidar Kuli Khan (1722), 303; appointed fifth-in-command of Gujrat, (1722), appoints Haidar Khan deputy viceroy and Akbar Khan, governor of Surat, 303, defeats Rustam Ali, 300, sends cavalry Mithan and Aghlan to Surat to avenge Mulla Muhammad Ali (1718), 311.
- NOBHAN**: Abu ruler of Turashtra, attacked and slain by Siddharaja, 176.
- NOZ**: Portuguese viceroy in India, 349, 351.
- NOLHERN INDIA**: conquest of, by Timur (1398-1400), 357.
- NOTSARJĀ**: modern Namsari, 539.
- NU**: Neuh, given as the first ancestor of the Chudāsammā, 139.
- NU JIHĀN**: wife of emperor Jehangir at Māndu, 375.
- NUB-UD-DIN MUHAMMAD UFI**: author of Jamī-ul-Hikayat (1211), 512.
- NUZHAR-UL-MUSHIRĀK**: work of Al Idrisi, 508 note 10.
- OBOLAH**: 545.
- O-CHĒ-LO**: Chinese name of the Arhat Achāra, 79.
- ODONBOGORES**: tribe, 531.
- OFFICE-BEARERS**: under the Valabhi administration (A.D. 500-700), 81, 82.
- OHIND**: 168.
- OKETIS**: modern Ghalla, 537, 543.
- OKHĀNIR**: 208; Okhānumāl.
- OKHĀMĀNDAL**: villah, 208 and note 3; chiefs of, admit Sundarji Shivaji as resident on behalf of British Government, 425, chiefs of, take to piracy (1816) and are crushed by a British force, the district of, made over to the Gākwār (1816), 427; Waghers of, besiege and plunder Dwārka Barvala and Bet (1859) - expedition against Bet - capture of the forts of Bet and Dwārka, 446-448.
- OLĀTĀYAKA**: grantor mentioned in Akāl vaishya Kushi's grant at Bāgumra, 128.
- OLOKHONKA**: provisionally identified with Karād, 542.
- OLĀD**: 539.
- OMANA**: east of the Persian Gulf, 545.
- OMINODĀVA**: probably Jannar, 541.
- ORĀT**: the Apurantikas, 532, 533, 534.
- ORĀTURA**: probably Surāshtra, 6.
- ORĀDAROH**: identification of, 539.
- ORĀTĀI**: Makri tribe, 546.
- ORĀS**: of the name of Gujrat, 25, of the Valabhis, 85-86; of Bhūmal, 166.
- ORISA**: 194.
- ORMIZ**: shipowner of, 201.
- ORO FRI**: tribe, 531.
- ORHOFUA**: forth, 547.
- ORST**: Orasa tribe 534.
- OSANIR**: town, 538.
- OSĀ**: town, 463.
- OSUMHĀTĀ**: village 108.
- OSĀS**: caste 163, 464, origin of, 164 note 1.
- OSIA**: same as Hoya, 116.
- OSIS**: river, 141.
- OZENK**: Ujjain, 37 510, 543, 545.
- PADMAPURA**: city in Kāshmir 188.
- PADMAVATI**: wife of Kumarapala, 188.
- PAGODA**: 101 219 note 2.
- PADAR KHAN JIHORI**: governor of Pālanpur (1744) 328.
- PĀHINI**: mother of Hemachandura, 191.
- PĀHĀVAS**: tribe, 35.
- PĀTHAN**: town, 37, 132, 540, 541, 545.
- PĀRIDARI**: modern Kāvī, 539.
- PĀL**: 216. See Vol.
- PAL**: village, 540.
- PALAI**: 543.
- PALĀIPATMAI**: modern Pāl, 540, 546.
- PALĀISTIMOUNDOU**: Ceylon, 543.
- PĀLANPĒR**: birth-place of Siddharaja, Chauhan king, 171, 310.
- PĀLĀOTHA**: Pātāliputra, modern Patna, 533.

- PĀLIMBOHRA** . Pataliputra, 516.  
**PĀLĪKĀNA** : 186.  
**PALLAVA** : dynasty of Dakṣiṇa kings, 36, 58.  
**PAISANA** . village, 127 and note 3.  
**PĀLWĀRA** . local name, 208 note 3.  
**PASIPA** : Kumbhese poet (941), 466.  
**PANAS** : town, 538.  
**PANCHAL** : zillah, 208 and note 3.  
**PANCHASAR** . village, Chūvādā chiefship at its fall (696), 119-150, 155.  
**PANCHASARA PARASVATĪ** . Jain temple of, 152.  
**PANCH MAHĀS** . rising in, siege of Dohad raised by Captain Buckle's forces, 439, Tatta Topi in, his expulsion from, 455.  
**PANDE** . Pandyas, 532, 534.  
**PANDU** . Pandyas, 516.  
**PANDYAS** . the, 519.  
**PANDION** . kingdom of the Pandyas, 537, 546.  
**PANJIB** . at courts of Gujarāt kings 180.  
**PANJIRANG PANJIB** . Peshwa's agent in Gujarāt, touches on Cambay and Ahmedābād, makes peace with Memon Khān and Jawān Mard Khān and retires to Sorath (1752), 335.  
**PANDIRANG PANI** . 398. See Pandurang Pandit.  
**PĀNDYA** . kingdom of, conquered by Pulkeśi II., 113, 534, 546.  
**PANJAB** . kingdom of, 526, 527, 534, 519.  
**PANINI** . grammarian, 36, 534.  
**PANIPAT** . battle of (1761) 315.  
**PANVIL** . village, assigned to the author of *Mhat-i-Ahmed*, 322.  
**PANOLI** . village, 328.  
**PAPIKL** : cape of, identification of, 539, 544, 545.  
**PARADATI** . tribe, 538.  
**PARAHANAKA** . village, granted, its identity with Palsana, 127 and note 3.  
**PARAMADEVYA** . Raja, identified with Paramara, king of A'bu, 168 note 2.  
**PARAMĀRAS** : Rājputs, 168, of Mālwa, section of the Gurjara or Bhīmāśī empire, 169, supreme in Malvāthali, lose their possession, 170.  
**PARĀNFIJ** : assigned to the Marāṭhās (1737), 110, 319.  
**PARASANG** : local measure, 165.  
**PARASANGĀ** : Pārasava, 533.  
**PARASĀTHI** : Jain saint, 166.  
**PARASIRAMA** : son of Sūryana, finishes the temple of Nemnāth, 177 note 1.  
**PARDI** . 110.  
**PARĠAĠĠIS** : sub-divisions, 210.  
**PARKHER** . local name of Baroda 208 note 3.  
**PARIAH DOG** . passing of the (1757), in Gujarāt, 433.  
**PARIHĀRS** : Rājputs, 165, 168.  
**PARISHITAPARYAN** : work of Hemachandra, 193.  
**PARIYAYA** : village, granted, 110.  
**PARK** : Colonel, 445.  
**PĀRIPTUR** : town, 119.  
**PARADATTA** : Śurāshtra governor of Śāṇḍa-gupta, 69.  
**PAREXA** : fort, captured by Shivājī (1672), 387, fort, 402, taken by Lieutenant Welsh (1780), 109.  
**PARPAS** . local name, 208 note 3.  
**PARUVANATHA** . temple of, 471.  
**PĀRŚIS** . 191 note 1, riot of, in Breach (1557), 137, 138.  
**PARĀBHER** : gathering at, destruction of, 143.  
**PĀRTHIANS** . 513, 514 : capture of, 515.  
**PARVATĪ** . Shiv's wife, 455.  
**PASĀITĀS** . see Vitāmas.  
**PASIPIDA** . town identified with Besmūd, 538.  
**PASIPARA** . sect 83, 190.  
**PASIPARAS** . take service in army, 84.  
**PAVALA** : island, 533, 534, 535, town, 538, 546.  
**PĀVALI** . Indus delta, 536.  
**PARAFENE** . 537. See Pattakene.  
**PĀRĀISHYAR** . 452.  
**PĀRĀIPĪRA** . city, 516.  
**PARAN** . town, 231, 232, 235, inscription at, 167 note 1, 174, 175, Sthasalinga lake built by Siddharāja at, 179, Sthā called at, by Siddharāja, 181, stone inscription at, 190, vacated by Jhaloris and Rathods and seized by Jawān Mard Khān (1737), 318, 160 and note 4.  
**PĀRAS SOMNĀTH** . zillah, 208 and note 3.  
**PARATAMALZA** . another name of Kacha I., 124.  
**PATON** : fort, given to Bhavsingh by the Marāṭhās, 323-324.  
**PATIL** . village headman, 210.  
**PATIKĀ** . northern Kshatriya ruler, 23 and note 1, 33.  
**PATRI** . Māndal, 518.  
**PATRIAS** : dancing girls, 451 and note 4.  
**PATIBANJON** . investiture festival, 130.  
**PATIKENE** . Lower Sindh, 535.  
**PATIAN** . town, mosque in, 512.  
**PATTAN SOMNATH** : burned by the Portuguese (1532), 347.  
**PATĪVARE** . 469.  
**PAWĀRI** . Mughal village officer, 212.  
**PAUSANIAS** : (170) 199.  
**PAVĠAR** . hill fort, goddess Kālī on, 206 note, taken from and restored to Sindh by the English (1803), 414.  
**PAVĀR** . Gujar surname, 468.  
**PAWANGAD** . 540.  
**PEARL FISHERIES** : in the gulf of Kutch, 285.  
**PENTH** . 110.  
**PEPERINI** : island, 542.  
**PERAMI** . 516.  
**PERIMUTIA** : Chaul, 533, 540.  
**PERIPLUS** : the, 7, 17, 535, 537, 539, 538 ; its author a merchant of Alexandria, the chief views about its age, 512-516.  
**PERMADI** : king, 172 and note 3 ; Kndamba king, 196.  
**PERSIA** . country, 497, 532, 547 ; gulf of, 516, 536, 545.  
**PĒRIATIS** . capital of the Gangaridæ .  
**PESHQAR** : *shupas* of, 497, 515.  
**PESHAWAR** : Kidāras established at, 141.  
**PESHKASH** : Marāṭha contributions, 216.  
**PESHWA** : opens for the first time direct negotiations with the viceroy of Gujarāt (1726) ;

- appoints Udaji Pavār his deputy to levy tribute in Gujarat and to operate against Pilaji, sends Chimmaji with an army through Gujarat; obtains tribute on the whole revenue of Gujarat (1728), 307, 309, 391, negotiates with the Nizam and the adherents of Trimbak-rāy Dabhade; recognises the Nizam's rights to several places in Gujarat and agrees to help him in severing the Dakhn from the possessions of the emperor, 393, negotiates with Jawan Mard Khan (1750), 397, treaty of Bassin (1802), 413, his intrigue in Baroda, 426, treaty of Poona (1817), his fall (1818), 428.
- PIERABANGARAKA** Dakshina Siva shrine at, 132.
- PIERALA** probably Paungala or Hongal, 511.
- PIERAD** fort, captured and demolished by Bangori (713), 327.
- PIEROTH**: people of Pushkalavati, 544.
- PIRTHOS** 535.
- PIRA TONG** apparently Great Lord, 197.
- PIR TA**: king of Kachh, 160.
- PIRUPADA** old Surat, 399.
- PIR TARA** father of Lakha, 160.
- PIRAN GAIKWAR** nephew and successor of Dāmaji Gaikwār, marches on Surat (719), defeats Musalmāns, establishes himself at Sangal; is secretly favored by Aptsamh, 301, 390, marches on Surat and defeats Momin Khan, buys contribution, overruns Surat province and builds forts in Rappihla, 303, 304, 390, obtains Baroda and Dabhoi, prevents Udaji Pavār from joining his forces with the victory at Baroda (1727), 308, 391; negotiates with Mustahid Khan, governor of Surat (1730), 311, assassinated (1732), 313, 391.
- PIRIMAGOS**: Vastupāla's, 292 note 1.
- PILAR** Mahabād, inscriptions on, of Samudragupta, 63-65.
- PIL-MOHO** Blinnāl in Bhinnāl, 3, 166.
- PILU**: Salvadoria persica, 449, 456.
- PINGALKA** 171.
- PINAL DUARA** 155.
- PIRAM**, island in the gulf of Cambay, 309.
- PIRAE CHAST**, 541.
- PIRATIS**: 192, note 3.
- PIR MOHAMMAD** Akbar's general in Malwa, drives Sultan Baz Bahadur out of Mandu (1560); his defeat and death (1561), 369.
- PIROZ**, Muhammadan shipowner of Ormuz, builds a mosque at Sonmāth Patan, 24.
- PIRE**: forgety of, 110, 111.
- PIRY**: (23-79), 6, 532, 533, 535, 536, 537, 513.
- PLUTARCH**: 535.
- PIKARN**: 464. See Pushkar.
- POLEMAIOS**: 37.
- POMPINIUS MELLO** (A.D. 13), 536.
- POONA**: treaty of, between the English and the Peshwa (1817), 428.
- PORHANDAR**: port, 524.
- POROS**: Indian king, 535, 536.
- PORTS**, Gujarat (1513-1515), 220 and note 2.
- PORTUGUESE**: Affairs of the, in Din (1529-1536), 317; send an expedition to south Kathiāvadh and sack Tarapur, Balsār, and Surat (1531), burn the ports of Sonmāth Patan, Mangrol, Talaja, and Mazaffarābād; destroy Bassin and burn Daman, Thāna, and Bombay; send an embassy to the court of Humayun to obtain Din, treaty with Sultan Bahadur of Gujarat, disputes with Sultan Bahadur (1536), 317, 318, in Surat (1700-1703), 292.
- PORTUGUESE ASIA**: historical work by Faria-Correia (1659), 349.
- PORWATS**: caste, origin of, 164.
- POSTICOLOS**: 535.
- POSINA** boundary of the Vaghela kingdom at, 1297, 206.
- POT**: in Musalmān period, 214.
- POSTAL CHAKIS** 214.
- POIANA** Pātala, 535.
- POTIPOTIA**: identification of 539.
- PRABANDHACHINAMANI** historical work dealing with the Chavala kings, 149 and note 2, 151, 152, 154, 155, 156, 158, 159, 160, 162, 163, 169, 170, 171, 172, 173, 174, 176, 178, 179, 180, 183, 184, 185, 186, 189, 190, 193, 194, 195.
- PRABANDHĀSANA**: work of Ramachandra, Karmapala's Panth, 190.
- PRABHAKARAVARDHANA**: king of Māgadh (600-606), 167, 197.
- PRABHASA**: Mulharaj's visit to, 160; holy place, 164, inscription at, 176. See Sonmāth Patan.
- PRABHĀVARSHA**: another name of Govind Rāshtrakūṭa 126.
- PRABHANDA**: noble of Krishna, Dakhn Rāshtrakūṭa king, 129.
- PRAJAPATI**: daughter of, loved by the Moon, 521.
- PRAKRI** dialect, 533, 534.
- PRAMUNA**: a tribe, 61 and note 3.
- PRASANNARĀGA**: title of Puda II. Gurjjara ruler 115.
- PRASATI**: poetical eulogium on the Sahasrabhaga lake written by Supala, 180.
- PRASY**: Prayag of Palibothra, 532, 533.
- PRATAPAMALLA** son of Kumarpāla's daughter 194. Second son of Vmadhavya, 203.
- PRATAPĀV**: brother of Dāmaji Gaikwar advances with Devaji Tākpai and exacts tribute and plunders the country, leaves tribute from the chiefs in Sorath, dies of small-pox at Kānkar near Dholka (1737), 317.
- PRATAPASIMHA**: king of Kulumbajattana, receives Kumārpalu, builds a temple, and issues a coin named after Kumarpāla, 183.
- PRATH-NAGRI**: local name of Dholka, 208 note 3.
- PREHISTORIC REFERENCES**: to Gujarat, 11 note 2.
- PREMALADEVI**: sister of Kumārpalu married to Krishnadeva, Sultharaju's general, 181.
- PRITHIBĀJ CHOHĀN**: king of Delhi, 470.

- PRITHIVISENA : ninth Kshatriya (A.D. 223), coin of, 43.
- PROKLAIN : 546.
- PROTAGORAS : geographer, 546.
- PSEUDOSIOMOS : river, 510.
- P'TOLIMY : Egyptian geographer (A.D. 150), 6, 7, 78 note 1; 137, 199, 333, 538, 539, 540, 544, 546.
- PTOLEMY II. PHILADELPHOS : (died 247 B.C.), 535, 542.
- PULAKESI II. (610-640), 110, 116. See Pulakesi Vallabha Satyashayana, 165.
- PULAKESI JANASRAYA : Gujarat Chalukya king at Navsari (738-739), 110, repulses the great Arab invasion at Navsari, 117.
- PULAKESI VALLABHA SATYASHAYANA : Dakhni Chalukya king (610-640), 110, 111. See Pulakesi II.
- PULIKESI : grant of, 109.
- PULIKESI II : 107. See Pulakesi II.
- PULIKESI JANASRAYA : his grants, 149. See Pulakesi Janasraya.
- PULUMAYI : Andhrabhritya king 38-510.
- PUNABI VITHAL : Peshwa's agent in Gujarat, 329.
- PUR : town, 539.
- PURAGUPTA : Gupta chief (A.D. 470), 71.
- PURANA : Bhavishya, 142, 533, 534, 545.
- PURANDHAR : treaty of (1776) between the Peshwa and the English, 106.
- PURI : Konkani Mandras of, its identity with Jānpura or Elephanta, 107, 108, ancient name of Branch, 159.
- PUSHPAMALA : 461.
- PISHKAR : holy place, 464.
- PUSHYAGUPTA : Gujarat governor of Chandragupta, 14.
- PUSHYAMITRA : name of king or tribe, 69, and note 4, 73-74.
- PYGMIES : race of, in India, 532.
- PYM : Lieutenant, 183.
- RACHMAS : envoy 536.
- RADDI : 119. See Ritti.
- RADHANPUR : grant of Govind III. at, 123; disloyalty of the Nawab of, 441, plate from, 466, grant of, 468.
- RATTIES : Sir Stamford, 489, 491.
- RATAPID-DARAYI : grandson and successor of the emperor Ferozkshiyar (1719), his murder by the Sayads, 301.
- RAGHUBA : Balaji Bajirav Peshwa's brother, called also Raghumathray, leaves tribute in Gujarat, takes possession of Rewa and Mulu Kantha districts and marches on Surat (1752), 334; takes Ahmedabad (1753), 336-337; compels Momin Khan to pay tribute, appoints Shripatri his deputy at Ahmedabad and collects tribute from Lambdi and Wadhwan chiefs, 337; acts as guardian of his nephew Madhavrav, is joined in his intrigues by Jānoji Bhonsle and Govindrav Ginkwar, is defeated by the young Peshwa at Dhorap (1768) and confined at Poona, 399-400, is invested with the robe of Peshwa by the titular king of Satara; reinstates Govindrav Gāikwar in title and estates of Dāmaji Gāikwar (1774); sets out for Gujarat and attacks the city of Baroda (1775), 401-402; opens negotiations with the English through Mr. Chamber the chief at Surat, 401, joins Govindrav Ginkwar (1776), sends an agent to negotiate with the Bombay Council; flies to Cambay and through the help of Mr. Mulet goes to Surat via Bhavnagar, 402; reception of by the Nawab of Cambay, 403; abandoned by the English after the treaty of Prandhar (1776); takes refuge at Surat, 406; at Bombay; a fresh alliance of, with the English (1778), 407, handed over to Sindia, flies to Branch (1779), 408; receives a pension and goes to Koprangon (1782), 410. See Raghumathray.
- RAGHOBHAI : Maratha deputy, assassination of, at Ahmedabad (1756), 339.
- RAGHOSHANKAR : Marathi leader, sent to Subhadra Kohis (1753), 338.
- RAGHOBHAI BHONSLE : of Barar, joins with Damaji in attacking the Peshwa, 395.
- RAGHUSAMHAR : Raja, Nizam's minister, 333.
- RAGHUSAMHAR : 334, 336, 337, 338, 394, 400. See Raghubai.
- RAHADA : mother name of Ghaghuda the Chauda king, 154, 156.
- RAHATUR : Randur, capital of Lude, 507 and note 11, 513.
- RAHMA : Rohma, apparently Burma and Sumatra 527, 528.
- RAHMI : 527.
- RAHMI : spine of Indra, 110; 133.
- RAHOD RASHTRASENA : image of, 133.
- RAIS : of Alor, 113.
- RAIS BHARA : Samma chief of great Kachhi, 518.
- RAISINGHI : usurps the chiefship of Navanagar, is defeated and slain in 1664, 283.
- Raja of Idar joins Fakhr-ud-Daulah, 329, 331.
- RAIVARA : legendary king, 8.
- RAIVATAKA : Gaurahul 177.
- RAJA : chief, 215 and note 2.
- RAAGHARAYA : title conferred on Chāhāda by Kumārpal 187.
- RAJADAMSA : Prachanda's grandfather, 129.
- RAJA MAHENDRI : 533.
- RAJAPRAMANA : title of Solāhara kings, 185.
- RAJAPURI : see Puri.
- RAJI : father of Muburaja, 156, 157; marries Lakha's sister Rayaji; is slain by Lakha, 160.
- RAJPIPIA : 226.
- RAJ UL-MUTAK : special rules for conducting the *mulakgiri* or land-ruding system, 418.
- RAJAVULA : northern Kshatriya, 23.
- RAKHATCH : son of Rāji and Lakha's sister Rayaji, 160.
- RAKSHAS : division of Parihar Rajputs, 465.
- RAMA : ancestor of the Chudāmbhama clan, 139.
- RAMACHANDRA : Pandit in Kumarapala's court, writes the *Prabandhasata*, 190; Jain scholar, ordered by Ajayapala to sit on a red-hot sheet of copper, 194.

- RĀMI : island of the Jāva group, 528.  
 RĀM RĀJA : king of Sāṭyā, appoints Khandarāv Dāhīde to collect *chauth* and *sardeshmukhi* in Bāglān, 388.  
 RĀMRĀV BHĀSTRĪ : adviser of the Peshwā ; decides in favour of Sayajirāv, son of Dāmājī by his second wife, 460.  
 RĀM SEN : hill range, 156.  
 RAN : 538.  
 RANA : of Chitān, 164.  
 RANAGRĀHA : durgpāya prince (639), brother of Dudda II., his copperplate grant, 115.  
 RĀNĀKA : chieftain, title of the Vaghelas, 199.  
 RĀNĀKADĒVI : daughter of a poetess sought in marriage by Siddhārāja, 176.  
 RANER : Bahmūr or Bahmūr, 513, 520.  
 RĀNĀSUKA : district, 187.  
 RANDEVI : is appointed agent by Dāmājī Gāikwar in Gujrat, defeats Kāntaji at Ajund-Mogri (1735), 316, 317, agrees to and Moḃam Khan on condition of receiving half the revenues of Gujrat (1737), 318, 391, again appointed deputy by Dāmājī to collect tribute in Gujrat (1741), 323, 325, defeated by Muḃlharī Bhāy and Fida-ul-din, deserted by Sher Khān Bala, is taken prisoner, his escape (1743), 326, 395, captures and demolishes the fort of Pottal, employed by the Musalmāns in the quarrels regarding the viceroyalty of Gujrat (1743-44), 327, 395, imprisoned by Khandarāv Gāikwar & released by Candib and appointed her agent (1745), 329, 396, expels Trimbakrāy from Ahmedabad and himself collects the Marāṭha share of the city revenues, 329, takes shelter with Sher Khān Bala in Kapadvanj, besieged at Kapadvanj by Fakir-ud-daulah, requests Holkar to come to his help, the siege raised at the approach of Holkar, his interview with Jawān Mard Khān at Ahmedabad (1747), 330, captures Borsad and forces Hariba to leave the country, 331, deserted by his allies and imprisoned (1747), 332.  
 RANDEKZ : dyes, 151.  
 RANMALJĪ : Navnagar Jām (1664), 283.  
 RĀNGAL SINDHĀ : at Idar, 315.  
 RAO : title. See RAY.  
 RARTOLA : tribe, 534.  
 RAY FARUK : in Aṭahā, 536.  
 RAYHĀN : div. Aṭahā geographer (1310), 501 ; translated Al-Biruni, 508, 511 note 9, 518, 529, 531.  
 RĀSHTRAKUṬAS : Gujrat branch of the, overthrow Chālukya kingdom, 117, Dakhan Branch of the, 119 ; dynasty (713-974), 119-131, their origin and name 119-120, their early dynasty (450-500), their main dynasty (630-973), 120, their conquest of Gujrat (760-760), 465, their grants, 466, 467, 500, 512 and note 1 ; in Gujrat, 525, 526, 527 ; their dominions, 529 ; their towns, 530.  
 RĀS MĀLA : 116, 153.  
 RASULNAGAR : name given by Aurangzib to Visalnagar, 286.  
 RATANLĀL PANDIT : Mr., 463 note 1.  
 RATANMĀL : 461.  
 RATANPUR : town, 471.  
 RATANSINGH BHANUJĪ : deputy viceroy of Gujrat (1733-1737), 311, receives Dholka ; defeats Sohrāb Khān at Dhol near Dhan-dhuka, 316-316, immunity of, with Moḃam Khān 316, 319 ; his attempts to oppose the Gāikwar, 317, defends Ahmedabad, 319 ; leaves Ahmedabad, 320.  
 RATTI 19. See RATTI.  
 RĀTHOD : chief, at Idar, 217 note 3 ; dynasty, identified with Rāshtrakuṭas, their origin, 119.  
 RATH : pound (trov) 531.  
 RĀTHUṬIYA : Chāṭāda king, 154, 155.  
 RĀTHGAR : hill range, 456.  
 RĀTHMĀLA : poetic history, 149 note 2, 156, 157, 157.  
 RĀTHVARI : Tamluk port on the Hugli, 199.  
 RATHA : dynasty of kings, 7, 119.  
 RĀZAT-UL-SAYA : 168, 512 note 3, 523 and note 1.  
 RAY : village, inscription and stone well at, 204.  
 RAY : title, 215 and note 2, of Kachh, makes an expedition against Sindh (1758), 342.  
 RAYAL : title, 25 and note 2.  
 RAYANA : demon king of Lanka, builder of the silver temple of Somnāth, 190, 154 note 1.  
 RAYAL : perhaps Rander, 220 note 2.  
 RAYJI : brought with his father Bāhājī Aya to Baroda (1792) by Govindrāv Gāikwar, 112 ; both the brothers receive from the Bombay Government the assistance of an auxiliary force under Major Walker, take the fort of Kachh by storm and compel Muḃlharīrāy to surrender, 112, his interview with Governor Duncanson at Cambay, 112, death of Rayji Aya (1803), 111.  
 RAYAJI : sister of Lakṣma married to Rājī, 160.  
 RAYGAD : fort, 284, stronghold of Shivājī, 386.  
 REBBI : Komars caste name, 119. See RABBI.  
 RECHIA : 535, 536.  
 RECHGIS : in Gujrat, 7.  
 REFORMS : of Amangzib, 283.  
 REHĀNIS : herdsmen, 451.  
 REHMAN : 512-513.  
 REHMAN : of the Valabhi kings, 83-85.  
 REHMAN'S DISPUTES : 280.  
 RIVA : Nābhādri river, 167.  
 RIVĀLMĪTRA : present with Mularāja in the battle with Gaharjūn, 160.  
 RIVATI : under Ahmedabad kings, 219 and note 2 ; in 1571, 221, in 1760, 222 note 2.  
 RIVAT KHĀN : minister of Azam Khān, (Gujrat viceroy (1635-1642), 278.  
 ROMNIS : General, 439, 443.  
 ROR, SIR THOMAS : traveller (1615-1618), 217, note 2, 222 note 1.  
 ROHINI : daughter of Prajapati, loved by the Moon, 521.  
 ROMAN : element in the architecture of Java and Cambodia, 496 ; empire, 536.  
 RORI : 143.  
 RUMDĀMAN : fourth Kshatrapa (143-158), coins and inscriptions of, 6, 11 note 2, 13, 34-36, 80 note 1 ; his kingdom, 610.

**RUDRAGANA** : Traikūṭika king, 5<sup>8</sup> and note 1.  
**RUDRAMAHARAYA** : great shrine of Rudra at Siddhapur, 161; built by Siddharaja, 179, 180.

**RUDRAM** (1) 172.

**RUDRASINA I** : eighth Kshatriya (203-220), coins and inscription of, 42-43.

**RUDRASENA** : seventeenth Kshatriya (259-272); coins of, 47.

**RUDRASENA III** : twenty-fifth Kshatriya (378-388), coins of, 51.

**RUDRASENA IV** : twenty-fourth Kshatriya (318-376); coins of, 50-51.

**RUDRASIMHA I** : seventh Kshatriya (181-196), coins and inscription of, 41-42.

**RUDRASIMHA II** : twenty-first Kshatriya (308-311), coins of, 49.

**RUPA** : 527. See Bahma.

**RUINS** : of Valabhi, 7-79.

**RUKA-UD-DIN AMIR** 201.

**RUMUKSA** : 490, south Punjab, 491.

**RUMILA** : perhaps south Punjab 509 and note 5.

**RUMI KHAN** : officer of Sultan Balahun of Gujarat (1536), 349, 350, 351.

**RUMLA** : country of Sindh, 520 and note 1.

**RUPA NAIK** : leader of Nakda Bhils, surrender of (1809), 446.

**RUPA SUNDARI** : wife of Jaya'ekkhara, gives birth to a son in the forest, 150, 151.

**RUPGI** : quarries of, 455.

**RUPMAH** : same as Rupman, wife of Baz Bahadur of Malwa (1555-1570), her pavilion at Mandu, 353, 356, 371; captured by Adam Khan Atkari at Sarangpur, commits suicide (1562), 369, 371.

**RUSHIS** : sages, 461.

**RISAM AH KHAN** : marches on Jodhpur with Shujaat Khan and captures it (1723), 303; governor of Surat, asks Pilapi Gaikwad's aid against Hamid Khan and Kantaji; defeats Hamid Khan at Aris, his severe defeat and death by the Maráthas near Ahmedabad (1723), 305, 390.

**RESTAMRAY** : Maratha leader in the army of Abdul Aziz, 328.

**SAAADI** : Persian poet (1200-1230), 189 note 2.

**SABAIASSA** : mouth of the Indus, 538.

**SABANA** : town, 533.

**SABARMATI** : river, 159, 193, 206; floods, (1693) 287, (1739), 322, 511, 517.

**SABARIYA** : Chandal, 531.

**SABANTVASANA** : grammatical work of Hemachandra, 193.

**SABZANS** : people, 535.

**SABIRIA** : 537. See Abiria.

**SADARAT** : Mughal department of justice, 213.

**SADASHIV RAMOHANDIA** : Peshwa's general, besieges and takes the town of Ahmedabad from Momin Khan (1758); helps the Ráy of Kachhi, 340, 341, 342; besieges Balasnor (1758) and levies tribute, 343, 398; defeats the chief of Dhrángdhra at Halvál and captures him, 344; appointed viceroy of Ahmedabad by the Peshwa (1760), 344.

**SADHARA JESINGH** : work of Ráo Sáheb Mahipatráñ Rupráñ, 189 note 2.

**SADHARO JESINGH** : another name of Siddharaja, 173.

**SADIR** : Mughal judge, 213.

**SADIRAH** : tribe, 510-542.

**SADRA** (Sb. Sadra), military post of the Mughals, in Mahi Kantha (1674), 285, 433.

**SADRA** : fort, 180 note 2.

**SADRA** : Táfán, principally next to Konkan, 527.

**SADRA MUHAMMAD KHAN** : successor of Teghlug Khan, governor of Surat, 330, expelled by Sayal Achchan, 331, returns to Sind, 332, brought back to Surat by the Dutch and other merchants, 333.

**SAGARA-VASANTKA** : temple at Cambay, 190.

**SAGARA** : mouth of the Indus, 538.

**SAGARA** : forest tract, 388.

**SAGHGA** : father of Mulaki, mentioned in the inscription at Mangrol, 176.

**SAGHGA-SARA** : temple at Prabhása, 176.

**SAHARAS** : of Aror in the north of Sindh, rule over south Punjab and north Sindh, 496. Buddhists, overthrow of, by usurping Brahmanist Chach (642), 497-498.

**SAHASKATINGA** : Lake, built by Siddharaja, 177, 179.

**SAMHARAKA** : tribal name, 64 and note 5.

**SAMIR** : 507, 508, 509, 510, 513, 516, 520, 523, 528, 529. See Chaud.

**SAMISM** : religion of the Valabhi kings, 83.

**SAMANA** : Siddharaja's victory, in Surashtra, builds a temple at Gurni, his inscription, 176-177. Póter, hules Kumbhápala, 182; is rewarded by Kumbhápala with seven hundred villages 184.

**SAKA** : tribe, 22, 67 note 2, era, 29; Yavans, 490.

**SAKAS** : 456 note 1, branches of Bhummá's chevaks, 464-465, 496 note 1.

**SAKAMBHARI** : the Saubhar lake; goddess, place; 158 and note 1.

**SAKIA** : Pansonis' (170) name for Cochim China, 499.

**SAKASTANI** : land of the Sakas, 112 note 5.

**SAKUNIKA VIKARA** : 186.

**SAKARBAT** : widow of Shahn, applies to Dámqi Gakwar and Raghuñath Bhonslé against the minister (1748), 396.

**SALABAI KHAN** : claimant to the chiefship of Junághat, 425.

**SALAGOL** : Salankayana, tribe, 516.

**SALANKAYANA** : tribe, 516.

**SALUKI** : treaty of (1782), between the English and the Maráthas, 410.

**SALTIR** : fort, in Bághán, captured by Moro Timnal (1672), 387.

**SALOGGAN** : zillah, 208 and note 3.

**SALIKE** : Ceylon, 543.

**SALIM SHAH** : (1545-1553) Sher Sháh Sur's successor, 369.

**SÁLVAS** : king of Mrittikávati, 10 and note 1.

**SÁLVAS** : tribe, 534.

**SAMADHIGATA-PANCHAMAHÁSHABADA** : title of the Gurjjars, 113.

**SAMANDAR** : river port town, 519.

- ŚAMANGAD**: plate, 122; grant from\* (753-754), 167.  
**ŚAMANTA**: feudatory, title of the Gurjjars, 113.  
**ŚAMANTI (DHIPATI)**: title of Javahlati 111.  
     Gurjjara king, 113 and note 6.  
**ŚAMANTASIMHA**: Chivada king, defeated and slain by Mulharaja, 157.  
**ŚAMARA**: king of Surāshtra, at war with Kūmarapāla, 186 and note 1.  
**ŚAMARA-SIMHA**: Chohin chief, 197.  
**ŚAMARA-SIMHADITYA**: 270.  
**ŚAMATAVA**: name of province, 61 and note 2.  
**ŚAMHAR**: expedition of Chaghala against, 187, 188.  
**ŚAMDA**: Thakor of, 441.  
**ŚAMIPADRAKA**: village, gift of, 125.  
**ŚAMMA**: tribe, 138, masters of Kachh after the fall of the Chūlas, 57.  
**ŚAMMAIYA**: school, 79.  
**ŚAMPRAPI**: grandson of A oka, 15.  
**ŚAMSAM-UD-DAULAH**: Dauran Nasrat Jang Bahādur, forty-eighth viceroy of Gujarat (1716-1719), 300.  
**ŚAMUDRAGIPIA**: fourth Gupta king (370-395), coins, Allahabad inscription, 62-65, 67.  
**ŚAMVAR**: Vikram era, 204.  
**ŚAMVAPASTIMHA**: 471.  
**ŚANAK (NIKA)**: name of province, 61 and note 3, 65.  
**ŚANCHI SUTPA**: Gupta inscription on, 66.  
**ŚANCHOR**: gate name 149.  
**ŚANDARI**: Govt. commercial town, 570.  
**ŚANDALAS**: Chandala, mounds, 630.  
**ŚANDANIS**: of the Pūrpas, 14 note 2; envoy, 542, 543, ruler of Gujarat, 546.  
**ŚANDAPUR**: apparently Govt, 509.  
**ŚANDHIN**: in Kachh, 509.  
**ŚANDHUR**: Rāndh, 509, 520.  
**ŚANDHANA**: ruler of Vantahā, killed by Virādhaṇḍa, 200.  
**ŚANQAVADA**: village, 177.  
**ŚANQHADAMAN**: tenth Kshatrapa (222-226) coins of, 13-14, 546.  
**ŚANJAN**: in Thūra, 509, 520, in Kachh, 530. See Sindan.  
**ŚANJIR**: name borne by the Jims, 139.  
**ŚANKAR (CHĀRYA)**: 84.  
**ŚANKARADITYA**: Devagiri Yadav 11, 15.  
**ŚANKARAGATA**: father of Buddhivarmman, Kalachuri prince, 111. See Śankaragana.  
**ŚANKARANA**: 111. See Śankaragana.  
**ŚANKARAVARMAN**: Kashmir king (890), 3, 168.  
**ŚANKH**: claims Cambay; is defeated by Vasatupala, Broach chieftain, 200 and note 2.  
**ŚANKHEDA**: grant at, 118.  
**ŚANOLI**: Sanoli, burning place of Pūji Gankwar (1732), 313.  
**ŚANTIKAS**: a Kūukan tribe, 41 note 2, 540.  
**ŚANTINĀTHA**: Jain Tirthankara, 192.  
**ŚANU**: minister of Chaulukya king Karna, builds a Jain temple, 170; Siddharaja's minister, 172, attacks an army of Bhils, 178.  
**ŚANTIVASANI**: Jain temple, built by Śantu Karna's minister, 170.  
**ŚĀPĀDALAKSHA**: name of the Ajmir kings, 157, Sambhar territory, 181. See Sewalik.  
**ŚĀPĀDALAKSHIYA**: 157.  
**ŚĀPARA**: mouth of the Indus, 538.  
**ŚĀRAGANIS**: 513, the younger and the elder, 546.  
**ŚĀRĀ-UD-DIN**: Malik, preaches *panth* or religious war in Ahmedābād (1857), 131.  
**ŚĀRANIB**: Ceylon, 516.  
**ŚĀRANIP**: dependency of the Gujarāt kingdom, 168.  
**ŚĀRANGADITYA**: Vaghela king (1275-1296), 203, succeeds Arjunadeva, his inscriptions, 204-205, 206.  
**ŚĀRANGPIL**: battle of (1122), 207 note, town, 368.  
**ŚĀRĀSTHIS**: probably Surāshtra, 6, 535.  
**ŚĀRĀVAH**: river, 161, 173, well of talent in Dhāt, 180, 511, 521.  
**ŚĀRVA**: town, identified with Sarwan 539.  
**ŚĀRNON**: place in Amol taluka of Broach; Govind III, holds at, 123.  
**ŚĀRTHAN KHAN**: Khān Bahādur Mubinz ul mulk Dilawar Jang, is appointed deputy viceroy of Gujarat (1712-13), rebuked on his way to Gujarat (1713), 297, appointed fifty-second viceroy (1723-1730), his deputy defeated (1724) 301, ordered to proceed in person with a strong army to Gujarat (1725), 306; is compelled to pay tribute to the Marāṭhas (1726), 307, makes alliance with the Peshwa, extorts tribute in Sonath, and marries the daughter of Jhala Prātsingh whom he exempts from tribute (1728) 308; grants formally to the Peshwa one fourth and one-tenth share of the revenue of the province (1729), 309, levies tribute in Kathiawar (1730), 310, defeats the new viceroy at Adalaj and returns (1730), 311. See Mubinz ul-mulk.  
**ŚĀRDAR MUHAMMAD KHAN**: captures Balāsīnor from the Marāṭhas, 315.  
**ŚĀRDHAR**: lake, 10 note 2.  
**ŚĀRDUPS**: Mount 532.  
**ŚĀRĀRAS**: Bhil messengers, 451.  
**ŚĀRIKA**: demon, 162, 163.  
**ŚĀRISARI**: town, 540.  
**ŚĀRKARS**: Gujarāt divisions, 209, 218-219.  
**ŚĀRKHUR**: village, 138.  
**ŚĀRSHI**: the river Śarasvati 510, 521.  
**ŚĀRSHI**: apparently the river Śarasvati, but perhaps the Sabarmati, 510.  
**ŚĀRYA**: Rashtrakuta or Gurjjara king, his coins 7. See Amoghavarsha.  
**ŚĀRYAMANGALA**: village, 126.  
**ŚĀRYABHAI**: Audhva dynastic name, 37, 38, 49.  
**ŚĀRYABHAI**: Yagnasi (1401) 546.  
**ŚĀRYABHAI**: of Panthan, 541.  
**ŚĀRYAN**: son of Rāsal, king of Himānā that is Kanauj, 519.  
**ŚĀRI**: 451.  
**ŚĀTKA**: evil spirit, 157.  
**ŚĀTRĀPA**: same as Kshatrapa, 21.  
**ŚĀTRUNJAYA**: Jain hill, 78, 79 note 3, 164 note 5, 177, 186; Hemacharya's visits to, 189, 197, temple of Nemunātha on, 202.  
**ŚĀTYASENA**: Chālukya king, 51.  
**ŚĀTYĀTĀ**: first cycle, 461.

- SATBUHA**: name of country, perhaps Svabhra, 10 and note 1.
- SAURASHTRA**: afflicted by an Arab army, 109, tribe of Kathiawar, 531.
- SAI RS.**: of Sindh, 533.
- SAISARA**: king of Surashtra, 186 and note 1.
- SAIVIRA**: Upper Sindh and Multan, 537, 542.
- SALIDAR**: gateway, 150 note 1.
- SAVIRI**: wife of Brahma, said to be a Ganga maiden, 161.
- SAVISHINDHARS**: news-writers, 211.
- SAYAD**: Musahibanbader, arrest of at Cambay, 202.
- SAYAD ACHUNAN**: paymaster at Surat, aspires to the governorship of Surat, seeks Marathe help (1717), 396, takes the city of Surat and gets the merchants to sign a deed addressed to the emperor and the Nizam that he should be appointed governor (1718), 331-332, makes over one-third of Surat revenue to the Marathas, 332, oppresses influential persons, surrenders tithe to the Nabab and withdraws to Bombay and thence to Poona (1740), 333, receives the governorship of Surat from the Peshwa and establishes himself in the government (1758), 343, receives a body-guard from the Peshwa (1759), 399.
- SAYAS**: brothers Hassan Ali and Abubilla Khan, king-makers at Delhi, 207, 301.
- SAYAD IMAM UD-DIN**: Ismailiah missionary in Gujarat during the reign of Mahmud Begada (1159-1513), 288.
- SAYAD JIJAL BUKHARI**: chief law officer or Sub-us-Sudm for the whole of India (1612-1641), 279.
- SAYAD MUHAMMAD**: marches on Surat and returns unsuccessful his suicide, 331.
- SAYAD SHAHAR**: preceptor of Matras of Khandesh and Momins of Gujarat, his suicide, 288.
- SAYAD GADKWAR**: son of Damaji Gadkwar, 312, 398, collects tribute in Sorath (1731), 344; appointed successor of Damaji (1771), 400, 401.
- SAYAN**: village, 130.
- SAYER**: land customs, 213.
- SAYANTION**: town, 510.
- SCHWABRUCK**: 512.
- SEBIR**: Colind, 147.
- SEAL**: Valabhi, 80.
- SEA OF PARS**: the Indian ocean, 516, 518.
- SELA-VINDHARAS**: with Konkan Sidhharas, 129.
- SELEKOS NIKATOR**: 532.
- SEMYLLA**: modern Chaul, 546.
- SINAPATI BHATARKA**: see Bhatarka.
- SENDRAKA**: chief, 55; grant 111.
- SINERA**: his book on India, 532.
- SESE KRIPENAI**: Bunt islands, 546.
- SETE**: tribe of Mewar, 533.
- SEWLIK**: hills, 157; king of, 191.
- SHAHUPDI**: town, 538.
- SHAHAR-UD-DIN GHORI**: defeat of (1178), 229.
- SHADHS**: beggars, 461.
- SHAH-MAT KHAN**: forty-fifth vicerey (1713), 297.
- SHAH (KUSHAN)**: Kushan dynastic name, 61 and note 5.
- SHAH-PANDAR**: harbour master, 212 Town, 538.
- SHAH-BURKAN**: Hajrat, son of Samt Shahr-Alam, the tomb of, on the Sabmati near Ahmedabad, 337 note 1.
- SHAH-BURHAN KHAN**: is appointed commandant of Menda (1568), builds Nalkantha, 370.
- SHAH-JEWAN**: emperor, stays at Mandu; is defeated, his brother Shah Farwaz retreats to Menda (1621-1622), 384; his death (1666), 284.
- SHAH NAWAZ KHAN SA'AT**: thirty-first vicerey of Gujarat, joins prince Dara in his rebellion against Aurangzeb (1659), 282.
- SHAH-NUR**: Hassan Kuli Khan Bahadur, viceroy of Oudh, sets out for Makkah; his unsuccessful attempt to arrange matters between Momin Khan and the Peshwa, 311.
- SHAHU**: Kushan name, 61 and note 5.
- SHAHU**: Raja of Satara, appoints Khanderav Pahlale Senapati, 389; settles the terms of agreement between the Peshwa and the Pahlale 393.
- SHAHISTAN KHAN**: twenty-sixth vicerey of Gujarat (1616-1617), 280; twenty-eighth vicerey of Gujarat (1652-1653), his expedition against the Chavvaha Kohis, 281.
- SHAKISTAN**: Sir Richmond, resident at Bussid, 113.
- SHAMERUJAM**: Nôur Brahman, supporter of Momin Khan at the siege of Ahmedabad, is taken prisoner by Damaji and cut off hands to Baroda, 312.
- SHAMIA AIBS**: beggars, 151.
- SHAM-SHIR BAHADUR**: title conferred on Damaji by Shahu after the battle of Balapur (1720), 389.
- SHAM-SHODIN ALIYASH**: Sultan, 171 note 1, takes the fort of Mandu and drives away the Hindu chief (1234), 357.
- SHANKRAJI**: governor of Viramgam (1753), 338.
- SHARMI-THA**: wife of Yayati, 160.
- SHAZA**: an animal, 508.
- SHILL-MONEY**: sowing of, 163, 164 and note 1.
- SHIR KHAN-BÄM**: governor of Baroda; defeat of; capture of Baroda, 311; deputy governor of Sorath (1738), 321; allows Rang to escape to Darsul and joins Khanderav, Damaji's brother, 326, joins Rangaji and marches against Fakhir-ud-daulah, wounded in the battle of Kapadvanj, 330, dispute of, with his Arab mercenaries at Balasamor, 338; dies (1758) at Junagadh, 313.
- SHIR SHAH-SHIR**: revolt of, in Bengal, 368; emperor (1542-1545), 368-369.
- SHIRJI**: commander of the Ahmedabad garrison (1753), suffers a defeat, 338.
- SHIVAKS**: 450, 164.
- SHIVARAJ**: Raja, commandant of Mandu (1658), 382.
- SHIVSINGH**: Raja of Idar, sends Sajjan Singh to help Momin Khan at the siege of Ahmedabad by the Marathas (1767) 311.

- SINDHAPUR** : 519.  
**SINDHARSHA** : king of Magadha (610-612), defeats the Huns, Ghorjjaras, Lāṭis and the king of Sindh and Mālava, 197; drives away White Huns, 500.  
**SINDHIA** : Brahmins, 150, 162 and note 2, Vāṇas, 463; Brahmins, Amer origin, 11. See Bhinnal.  
**SINDHIALIS** : meaning-making of the name of, 15; brought back to Bhinnāl (1691), 461.  
**SINDHIAL M. M. M. M.** : legendary account of Bhinnāl, 161.  
**SINDHINAGAR** : Shinnal, 161.  
**SINDHIPATRA** : deputy of the Peshwa in Gujarat, negotiates with Momin Khan for the release of Bhagyantrī, is recalled, 338.  
**SINDHIPUR** : another name of Jagsonr, 160, 162, and note 3.  
**SINDHIS** : 530. See Sudaris.  
**SINDHIA KHAN** : Kariab Khan, thirty-eighth viceroy of Gujarat (1681-1703), 287, his campaign in Jhalakā and Sorath and storming of the fort of Thim, 288, captures Jodhpur (1721), 303, see Kariab Khan. One of Sher Shah's generals in Malwa, defeats Kāḍr Khan at Mandu, appointed commander of Mandu, 368-369, recovers Malwa (1551), 369.  
**SINDHIA D. D. D. D.** : nawāb of Lucknow, 311.  
**SINDHIA** : sailors of Sonmāth, 91.  
**SIDDHARHATH** : grantee in Inha's grant, 731.  
**SIDDHARHATHAKHATIN** : title of Siddhartha, 154.  
**SIDDHARHATHA** : grammar by Hemachandra, 180.  
**SIDDHARHATHACHANDRA** : 121. See Siddhartha.  
**SIDDHARHATHA** : 167. See Bhinnal Siddhanta.  
**SIDDHARHATH** : town, Vamanā's mosque at, 152. hol. place, Mulinji's grants at, 161. Jain temple at 172, Radhaoacharya temple at, 179, Kumarpala's visits to, 183, Ahmed-shah's march against, 237.  
**SIDDHARHATHA** : Chanduka king (1091-1113), 163, 161, 162, succeeds Kāṇṇi, regency of his mother, intrigues regarding his succession, remission of pilgrim tax, his wars with the kings of Samāshtra, Malwa, and Sindh, his etc., his religious donations and architectural buildings, 171-181.  
**SIDDHARHATH** : 151, 161, 172, 237. See Siddhartha.  
**SIDDHARHATH** : commandant of Jaupra, offers to become a vassal of the emperor through the governor of Sindh and receives the title of Yāḍat Khān from the emperor with an annual subsidy of 1½ lakhs payable from the port of Sindh, 285.  
**SIGERDAS** : perhaps Sagardvipa or Cutch, 16.  
**SIGERDAS** : kingdom of, 535.  
**SIGERDAS** : probably Jaupra, 535, 536, 540.  
**SINDH JAGAPURA** : palace, 180 note 2.  
**SINDH** : village in Kāthiavada, 64 note 5, 161, reservoir at 180 note 2.  
**SHADITYA** : of Malwa, reigning king of Kāṇṇi Kulpa, 79.  
**SHADITYA IV** : Valabhi king (691), 117.  
**SHADITYA V** : Valabhi king (722), 117.  
**SHADITYA SHYASHRAYA** : Gujarāt Chālukya king, 56, 108.  
**SHADITYASURI** : Jain priest, 151.  
**SHADITYAS** : of the north Kingdom, 527.  
**SHADITYA** : perhaps Sindh in Jhalakā, king of, present with Mularāja in the battle with Grahuripa, 160 and note 2.  
**SHADITYA** : title, 531.  
**SHADITYA-11-TI W. R. K. H.** : written (851-852) by the merchant Sulaman, 505 note 2.  
**SHADITYA** : James de, Portuguese captain, burns the ports of Pattan - Sonmāth, Mangrol, Talāpa, and Muzafarabād; Thāna, Basson, and Bombay, 317.  
**SHADITYA** : country, king of, imprisoned by Sulhārāja, 179.  
**SHADITYA** : maternal uncle of king Visaladeva, 292; etc., 276, 201.  
**SHADITYA** : see Shor.  
**SHADITYA** : twenty-sixth Kshatrapa, coin of, 51.  
**SHADITYA** : modern Chandi, 533.  
**SHADITYA** : modern Chandi, 510.  
**SINDH** : for Kadamba chief, 173 and note 5.  
**SINDH** : perhaps Vadnagar, 516.  
**SINDHIA** : Goa, 517-521.  
**SINDHIA** : in Kachh conquest of, and Jama mosque founded at 506, St. John or Sangu in Thāna near Daman, 507, 508, 509, 511, 516, 521, 523, 528, 529, 530.  
**SINDHIA** : conquered by Chudisamas, 139; expedition against by the Rito of Kachh, 342; Bhinnas, 132 and note 2, king of, 405, 509, 511, 513, 517, 533. See Sindh.  
**SINDHIA** : identified with Sindh, afflicted by Yādavya, 109 river, 181.  
**SINDHIAV** : killed by Siddhartha, 175, 179.  
**SINDHIA** : Maratha leader, his unsuccessful attack on Sindh (1781), 109, at war with the English, his treaty with the English at Sindh, Anjan, 1803, 111.  
**SINDHIAV** : branch of the Indus, 517.  
**SINDHIA** : Delal, 517.  
**SINDHIAV** : Cutch, 512.  
**SINDHIA** : title, 531.  
**SINDHIAV** : Devagiri Yādava king (1209-1217), 138, attacks Lavamānasāla, his etc., 199.  
**SINDHIAV** : grandson of Sindh, extends his sway (1069), 517.  
**SINDHIAV** : see Singhana.  
**SINDHIA** : attacked by Sindh (1781), 109.  
**SINDHIA** : mouth of the Indus, 538.  
**SINDHIA** : Indus river, 511.  
**SINDHIAV** : modern Sindh, 511.  
**SINDHIAV** : town, 510.  
**SINDHIAV** : Sri Pulmāyī, Andhra king, 37.  
**SINDHIAV** : Sisola, village, 115.  
**SINDHIA** : chief of, head of Deva Rajputs, 165.  
**SINDHIAV** : Sri-Pulmāyī, 511.  
**SINDHIA** : Amoghavarsha's inscription at, 124.  
**SINDHIAV** : queen of Kumarpala, 188.  
**SINDHIAV** : Raja of Movād, struggles with Akkur, 110.

- SIKOPRA**: village, 115.  
**SILHA**: in Jhalavada, 160 note 2.  
**SIVACHITRA**: Goa Kadamba king (1147-1175), 173 and note 3, 195.  
**SIVAJI**: 145, founder of the Maratha empire, plunders Surat (1661), 281, 386, plunders it for the second time (1670), 281, 386, compels fleet at Alibag, comes to the mouth of the gulf of Cambay, carries off Mughal pilgrims, 386, captures Parnera and Bagvada forts to the south of Surat (1672), 387.  
**SIVANANDA KUMARAPALLAVARA**: temple of, 183.  
**SIVASANA**: king of, conquered by Hammuka, 163.  
**SIVAPUR**: success of the Nankdas at, 116.  
**SIWANA**: town, 538.  
**SIVAJIRAJ GAIKWAR**: 312. See Sawaji GaiKWAR.  
**SKANDPA**: twenty seventh Kshatriya, 51.  
 • Another name of Amoghavarsha, Dakhan Rashtrakuta king, 126.  
**SKANDAPATI**: seventh Gupta king (451-479),  
 • inscription at Bhitar and Carnar, 69; at Jimnagalli, 73, 71, coins, 70, 71, 80 note 1, 86.  
**SKANDA PURANA**: 161.  
**SKYTHIA**: Smthi, 544.  
**SODHAI VAY**: step wall at Mangrol, 176.  
**SODHA PARMARS**: 217 note 3.  
**SOPALA**: 522.  
**SOPADA**: ruler of Malwa, 198.  
**SOHRAB KHAN**: 313. See Sohrab Khan.  
**SOHRAB KHAN**: governor of Surat (1730), 310, confirmed in the appointment; driven out of Surat (1732), settles at Bhavnagar, 313, appointed governor of Viramgam (1735), is defeated at Dholi by Ratan Singh Bhandari, 315-36.  
**SOJIRA**: village, battle of (1725), 307.  
**SOJARI**: see Sojuki.  
**SOLANKIS**: 150, 191, Rajputs their settlements, 461, then kingdom 465, then change of faith (743), 463 and note 2, 465; of Anhilavada, section of the Bhimral empire, 469, dynasty (961-1212), 526. See Chaulukyas.  
**SOLLA**: son of Iclava Vamm, minister of Karna, 170.  
**SOM**: builder of the Sun temple 452.  
**SOMA**: builds the gold temple of Somanatha 190.  
**SOMACHANDRA**: Hemachandra's name after his consecration, 191.  
**SOMADITYA**: Mularaja's ancestor, 157.  
**SOMANATHA**: temple, 79 and 3, 154, 161, destroyed by Mahmud of Ghazni (1024) 165, 168; Myanalladevi's pilgrimage to, 172; Kunnarapala's pilgrimage to, 187-190; Jayanaprasada grants a village to, 200, destroyed by Muhammadans in 1297, 205. See Somanath.  
**SOMANATHA PATAN**: inscription in Bhadrakali's temple at, 81, rebuilding of the shrine at, 189, house-tax imposed for the maintenance of a mosque at, 204.  
**SOMARAJA**: son of Sahajiga, builds a temple at Prabhasi, 176.  
**SOMACHANDRA**: Brahmanic king of Cambodia (610) 499.  
**SOMESVARA**: poet, author of Kirtikamudi and Vastupadhehmit, 171, 199, 202.  
**SOMESVARA**: shrine, re-built by Kunnarapala, 189 and note 2.  
**SOMESVARA**: king of the Hoysala Ballalas of Uvarasamudra (1252), 203 note 3.  
**SOMNATH**: 229 and note 1, 232-233, 507, 508, 510; destruction of (1025), 512; pilgrimages to 531, legendary origin and description of the temple of, 521, 522, 523, 529, 531. See Somanatha.  
**SOMPURAS**: 164.  
**SONARS**: goldsmiths, 150.  
**SONGAD**: head-quarters of Pilaji GaiKWAR, 301; 336, 340. Fort, the Citadel of Mandu captured by Hufiayun in 1534, 356-367-368.  
**SONNARA RAMPALS**: 151 notes 3 and 4.  
**SONNIS**: 165.  
**SOHRAB KHAN**: see Sohrab Khan.  
**SOPARA**: near Bassen, southern Mauryan capital, 11-38.  
**SORATH**: chief of, owes allegiance to Gollas, 113, annexed to the Chaulukya kingdom of Anhilavada 176, name and extent, 208 and notes 1 and 3, 209, land and system of the Marathas in 118-119.  
**SORTER MIGAS**: coins of, 19.  
**SOROTHODI**: town, 511.  
**SOPARI**: modern Supari, 510.  
**SOPPARA**: 546. See Supari.  
**SOSIKANA**: town, 538.  
**SOUTHERN SKYTHIANS**: 537.  
**SOUSA**: Famae, Portuguese writer (1650), 319.  
**SPIGHT**: author, 115.  
**SPINCEY**: Mr., chief of the English factory at and governor of the Castle of Surat, 313.  
**SRI BHAVANA**: identified with Sarbbon, 123.  
**SRI CHAPA**: dynasty, 167.  
**SRI DEVI**: 152.  
**SRI GAUDAS**: branch of Gujrat Brahmins, then origin 161.  
**SRI GUPTA**: see Gupta.  
**SRI HARSHA**: king of Magadha (606-647), 467.  
**SRI HARSHACHANDRA**: life of Sri Harsha, 467.  
**SRI JAYASIMHADITYA**: 170.  
**SRI LAKSHMI**: gate name, 119.  
**SRI MAIA**: identified with Bhimral, 160.  
**SRINAGARA**: seat of Jethva power, 138.  
**SRIPALA**: Siddharaja's poet laureate, 180.  
**SRISTHANA-SIDDHAPURA**: troubled by Rakshasas or demons, 174.  
**SRI VALLABHA**: see Amoghavarsha.  
**SRONDOZAN-GAMRO**: (640-698), founder of Tibetan power and civilization, overruns Tarim valley and Western China, 501.  
**SRIVARAYA SIKADITYA**: (669-691), his plates, 107-108; Yuvaraja (691-692), 110, 111, 112.  
**SIAMMA**: king, threatens Rashtrakuta kingdom in the Dakhan, 123.  
**SRAMBHAIRITHA**: modern Camhay, 123; granted to Sriganadas by Mularaja, 161, temple at, repaired by Kunnarapala, 190.  
**SRIPHANOS**: of Byzantium, geographer, 516.  
**SIHAVIRAS**: 193.

- STHIRAMATI**: name of a Bodhisattva, 79 and note 1, 86.  
**ST. MARTIN**. 534, 538, 539.  
**STRABO**. Roman geographer (B.C. 50 - A.D. 20), 16, 17, 532, 535, 536.  
**STRANGERS**: settlements of, in Gujarāt, 1.  
**STRATILABATI**. 532, 541.  
**STRATI**. Sāvaras of Central India, 533.  
**STRATH**: province, 211.  
**STRIBHAR**: Muzhal vicar, 211.  
**STRABA**. 508, 509, 514, 516, 523 note 1, 529.  
   See SUPARA, Sinalana, and SURAT.  
**STRIBHAR**. Krishna's sister, 9, 10.  
**STRIBHAR**: king of the Karnataka, 170.  
**STRIBHARMA**. king of Malwa, 19.  
**STRIBHAR**: another name of Akalavastha, 126.  
**STRIBHAR**. Shudra, husbandman, 530.  
**STRIBHAR**. ancient lake near Gurnar, 35, 36, 69.  
**STRIBHAR**. northern Kshatriya king, 23.  
**STRIBHAR**. ancestor of Prachanda, 129.  
**STRIBHAR**. 511. See SUPARA.  
**STRIBHARMA**. inscription at Vala of, 107.  
**STRIBHAR**. place on the Narmada, 162.  
**STRIBHAR**. Sanskrit work on Chyavala kings, 149 and note 2, 151, 156, 159 note 3, 171, 191, 196, 196.  
**STRIBHAR**. merchant and traveller, author of Sukut-m-Tawrikle 198, 505 and note 2, 525, 526, 527, 530.  
**STRIBHAR**. Supara at 51.  
**STRIBHAR**. Hindu settlements of, 193, 527 528.  
**STRIBHAR**. chief, 159, king of Sindh 160, tribe, sovereignty of Sindh passes to, 517.  
**STRIBHAR**. hill range, 456.  
**STRIBHAR**. shrine of, 155, 156.  
**STRIBHAR**. Chinese ambassador (A.D. 50) 74, 75 502.  
**STRIBHAR**. 155, description of, 159-160, history, 160-161, dates, 163.  
**STRIBHAR**. Arab outbreak at, 141.  
**STRIBHAR**. Mithun, 142 and note 2 and 3.  
**STRIBHAR**. near Bassin, its various names, 523, 529, 546, 547.  
**STRIBHAR**. apparently See 511 516, Supara 529.  
**STRIBHAR**. Surabāta, Surat, 507 and note 3, 514.  
**STRIBHAR**. tribe, 533.  
**STRIBHAR**. claimant to the Lamāvāda gadi or chiefship, 141.  
**STRIBHAR**. gateway, 450 note 1.  
**STRIBHAR**. brother-in-law of Javan khana, 150, 151.  
**STRIBHAR**. ancient division of Gujarāt, 6, 35, 36, 135, lord of, taken prisoner by Siddharāja, 175, kingdom of, 535; Veraval, 547.  
**STRIBHAR**. Kāthiyāvād, 506.  
**STRIBHAR**. village, 538.  
**STRIBHAR**. Surāshtra, 15-16, 537, 538.  
**STRIBHAR**. plate of Śrīyāsraya Śiladitya at, 107, 108, Karka's grant at, 121; Kirtirāja's grant at, 159, 230; 235; sacked by the Portuguese in 1531, 317; plundered by Malik Ambar in 1609, 214 and note 2, by Shivaji in 1664, 284, 386; Shivaji's second attack on, in 1670, 284, 386; Marāṭhs at, permission granted by the emperor to let pass the Portuguese ships from (1700-1703), 292, affairs at, Mulla Muhammad Ali's success at, his imprisonment and death at, by Teghbir Khān, the governor (1732-1734) 313, affairs at (1748) 331, cession of the revenues of Surat to the Marāṭhs under Kadirji Gāikwār (1717) 332, affairs at (1750); 333; attacked by Raghunathji (1752), 334, affairs at (1758), castle taken by the English (1759), 313, treaty of (1775), between Rāghoba and the Bombay Government, negotiated by Narotmādas, 402; treaty of, declared invalid by the Supreme Government, 105-106; 514; 523.  
**SURAT**. Athavasi, plundered by the Marāṭhs (1780), 401.  
**SURAT**. mouth of the Tapti, 523.  
**SURAT**. sage, title conferred on Hemachandra, 191, title 531.  
**SURAT**. by Foder Mad (1575), 223.  
**SURAT**. gate name, 149, Sun Gadi, 161, Purān, 161, 165.  
**SURAT**. another name of Karka I., 124.  
**SURAT**. installation of, in Śakavika Vihāra, 86.  
**SVABHAR**. name of country, 10 note 1, 36 and note 3.  
**SVABHAR**. See Sābharat.  
**SVABHAR**. shrine, on Śātrūjaya in honour of Vastupāla, 202.  
**SVABHAR**. handicrafts-clothing, of Durhahad, 162-163.  
**SVABHAR**. 468.  
**SVABHAR**. Ras Pantak in Arabia, 536.  
**SVABHAR**. town 538.  
**SVABHAR**. 511.  
**TABAKAT-I-NASHIR**. 196.  
**TABAN**. king of Tāfak, 527.  
**TABAT**. Arab winter (838-932), 521.  
**TABAT**. probably Pandharpur, 511.  
**TABAT**. 511. See Tabaso.  
**TABAT**. the Tapti 510.  
**TABAT**. the Panjāb, 526; women of, 527.  
**TABAT**. apparently the Panjāb, 527.  
**TABAT**. town, identification of, 510-511, 515.  
**TABAT**. rebellious Gujarāt noble, 513, 518.  
**TABAT**. sub-divisional officer, 210.  
**TABAT**. Sāva tribe, 531.  
**TABAT**. king of Telungana, 158, 159.  
**TABAT**. western Chālukya king, overthrew the Rashtrakūṭa dynasty (972), 120, 131, 519.  
**TABAT**. Arals, 149.  
**TABAT**. village, 438.  
**TABAT**. 512, 519 and note 1.  
**TABAT**. wife of Annudrāv Gāikwār, 400 and 68.  
**TABAT**. Gujarāt governor (1320), 230.

- TAKKADGSA**: tract of country (Panchab), 3, 468.  
**TALABDAS**: wild tribe, 115.  
**TALAJA FORT**, burned by the Portuguese (1532), 347.  
**TALMI** lake, 153.  
**TALL SAP**: lake, 499, 504.  
**TAPAR**: state land 215, 227.  
**TAMACHU**: name borne by Jains, 139.  
**TAMACHU**: son of Raisingji, restored to Navanagar (1673), 285.  
**TAMARA BARANI**: apparently the Tapti, 510.  
**TAMRA**: Anhilwara, 516.  
**TAMBASAGRI**: local name of Cambay, 205 note 3.  
**TAMLUK**: port on the Hugh (A.D. 100), 199, 533.  
**TAMRALIPTAKAS**: of Tamluk, 533.  
**TANA**: modern Than, expedition against by Usman, 505, 508, 509, 523.  
**TANAH**: 508. See **THANI**.  
**TANKA**: country, 467 and note 7.  
**TANKAS**: coin, 222 note 1.  
**TANTRIKS**: proficient in *tantra* (charms) branch of learning 161.  
**TAPPA**: Brhm-Bhat, 157, 166.  
**TAPROBANE**: Ceylon, 513.  
**TAPPI**: river, 511, 523.  
**TARAPUR**: near Cambay, 337. In the Thani district, sacked by the Portuguese (1531), 347.  
**TARAKH-I-ALAI**: work of Amir Khosro, 515 note 6.  
**TARAKH-I-FIRUZSHAH**: work of Zia-ud-din Bami, 514, 515, 517.  
**TARAKH-I-KAMIL**: work of Ibn Asir, 522 note 4.  
**TARAKH-I-MASUMI**: written in 1690 A.D., 517 and notes 7, 8, and 10.  
**TARAKH-I-MULAKASHAH**: notices Asiwal (1403-1501) 513.  
**TARAKH-I-TAMIRI**: written A.D. 1521, 139, 517 note 12, 518.  
**TARIZAKAI**: sea customs dues 212 note 1.  
**TARFARIGH-DIHHAM**: coin, 169 and note 2, 519 and note 8.  
**TARTAKHAN**: sultan of Gujarat, 613.  
**TARUAGAIA**: see **Gautama**.  
**TARJA TOP**: rebel, enters the Panch Malohs, 141, corresponds with the chiefs of Jamkhani and Nargund, is defeated at Chhota Udepur 145.  
**TAXILA**: town, 190, 191, 516. TakshaSila tribe, 531.  
**TAYLOR**: Captain (1857) 138.  
**TAZJAVAT-ANSAR**: work of Abdullah Wassaf (1300), 518.  
**TIGRO KHAN**: governor of Surat, defeats the forces of Momis Khan and contrives (1733) to become governor of Surat, 313; intrigues of, at Surat, 315; kills Mulla Muhammad Ali, 331; dies (1746), 330.  
**TRAHPATA**: minister of the first two Vaghela chieftains and famous temple-builder, 199, accompanies Vitadhavala in the expedition against the rulers of Vantoli; defeats Chaghula, chief of Godhra, 201.  
**TRINGANA**: Andhras of, 533.  
**TRINGAS**: Pchugas, 534.  
**TRINGUS**: 531.  
**TRIVAS**: in Gujarat, of brick and wood up to ninth century 79 and note 2.  
**TRINAI**: village granted, 130.  
**TRITORIAL DIVISIONS**: under the Valabhis, their identification with the present, 12 and note 1.  
**TRITORIAL LIMITS**: of Gujarat under Muslims 207 and note 1, 208.  
**TRIVY**: 221 note 1, 224 note 2. The Rev. Edward, chaplain to Sir T. Roe (1617), 376.  
**TRULI**: 145.  
**TRUKAS**: caste, 530 and note 10.  
**TRUKERS**: petty chieftains, 215 note 2. High caste men, 530 note 10. See **Thakarias**.  
**TRUTIA**: identified with Tamraliptakas, 533.  
**THAN**: 180 note 2, fort in Kathiawada, headquarters of the Kathis, stormed by Shujat Khan (1692), 288.  
**THANA**: town, burned by the Portuguese (1532) 317, captured by the English (1774), 161, 523, 524, 529, 531.  
**THANAVAS**: local officers, 210.  
**THAR AND PAKKAR**: district, 538.  
**THAVCHER**: Captain, 141.  
**THAVAS**: fortified outposts, 210.  
**THUSONG**: king of Tibet (803-815), 501.  
**THUSONGU**: king of Tibet (87-911), 501.  
**THOM**: apparently Great Lord, 197.  
**THOPHIA**: town, identification of, 539.  
**THUK**: ball image, 150.  
**THYASANS**: Thashama, 37, 540.  
**THYOTRYA**: modern Chunder 510.  
**TIBET**: country, ceases to acknowledge the overlordship of China (729), spreads its power to the Yangtsi-kiang valley (750), confederacy formed by the king of China with Tibetan chiefs and Arabs against it (757), 501.  
**TIGRIS**: river, 511.  
**TIGARS**: arrowmakers, 151.  
**TIGRAI**: birth place of Srigandas, 161, 456 note 1.  
**THAPANGALIDA**: town, 511.  
**THIRAKALPA**: work, 176, written by Jinaprabhram, 182 note 1.  
**THIRANKARS**: Jain sants, 151 note 3.  
**THIRANATARA**: near Kochin, 563.  
**TOD**: Colonel, 81, 145, 188, 203 note 7.  
**TODA GIRLS**: ready-money payment, 216, 227 and note 1.  
**TORAMANA**: king (171), 72, 71-75, overthrow Budhagupta, 136, 146, 165, 196.  
**TOWER**: of victory, built by Mahmud Khilji (1142) at Mandu, 351.  
**TRAKIYAKA**: era, 110, era (219-250), 113, 114, dynasty (250-450), 55-57.  
**TRAJAN**: (106), 197.  
**TRAMBASARVAR**: lake, 153. See **Talbi**.  
**TRANSOXIANA**: country, 139.  
**TRAPPAGA**: boat, 515.  
**TRAVANORE**: Pandyas of, 531.  
**TREATIES**: forms of, 199-200.

- TREATY** : conditions of, between Singham and Lavamprasad, 200.  
**TRIP** : of Gurjara-genealogy, 114 ; of Rashtrakuta family, 121. See Genealogy.  
**TRIVASTA** : second cycle, 161.  
**TRIVASTA** : district, 111.  
**TRIM** : Indian, 535.  
**TRIBHUVANAPALA** : great-grandson of Bhima I. (1022-1061), and father of Kumārapala, murdered by Saddharaja, 182. Representative of Anahavāda Solankis, 203.  
**TRIBHUVANAPALAVASTI** : temple at Bāladapura, 126.  
**TRIKADIBA** : shunt, 549.  
**TRILAKA** : perhaps Jumar, 57, 58 note 1.  
**TRIMBAK** : pond, 162.  
**TRIMBAK** : Pandit, deputy of Khondarā Gīl-wan at Ahmedabad, his intrigues with Fakhr-ul-daulah, 329.  
**TRIMBAKISHWAR MAHADEV** : shrine of, 154.  
**TRIMBAK** : Dangle, appointed Sarsabha of Ahmedabad, causes the assassination of Gargādhra Shīstā (1815), 127, his escape from Thina, 128.  
**TRIMBAKHA** : Pulhadey, son and successor of Khondarā [Bhade] (1720), 389, advances with an army to Cambay (1726), 306, 31, his jealousy of the interference of the Peshwa in Gujarāt affairs, intrigues of, against the Peshwa, intercourse of, with the Nizam, confederacy with Pilāp, Kāntāp and Udip to rescue the Marāṭha Rajā from the Brahman minister, defeat of the allies by the Peshwa (1731) and death of, in battle 312, 392-393.  
**TRIPURA** : city, 57 note 4.  
**TRIPURANTAKA** : religious benefactions of, 205.  
**TRIPURISHAPALASDA** : Mahadeva's temple at Anahavāda, 161, new temple of, 164.  
**TRISASTUTI SAIKĀPIKASACHALITHA** : lives of sixty-three Jainsants conquered by Hemachandra, 193.  
**TROPINA** : Tinpanmata, 533.  
**TUFAI-UL-KIRAM** : the, 139, 538.  
**TIGHELIK** : name borne by Jains, 139.  
**TU-LI-HU-TO-IT** : Chinese name of Dhanva-jatn Valabhi king, 49.  
**TURKS** : 189, advance of, 497, 507.  
**TURUSKA** : Mahomedan a. . . . . ed by M. . . . . in childhood, . . . . . and note 4.  
**TURKISH** : 189. See Turks.  
**TUSASPA** : Yavana governor of Asoka in Surashtra, 11.  
**TANDI** : Kadalandi, 546.  
**UDA** : see Udaya, 172.  
**UDAJI PAVAR** : Peshwa's general in Gujarāt (1727) ; is outmaneuvered by Pilāji and Kāntāji ; his retirement to Malwa, 308 ; captures Māmū (1696), 382 ; in Surashtra, 14.  
**UDAPIRE** : town (Mevad), 532.  
**UDALASARA** : temple, 172.  
**UDAMBARA** : village, 182.  
**UDAYA** : minister of Chandukya king Karna and builder of the temple Udaya-Vardha, 170.  
**UDAYACHANDRA** : one of Kumārapala's leading Pandits, 190.  
**UDAYADITYA** : inscription of, at Udepur, 164 ; Kumārapala's inscription in the temple of, 185.  
**UDAYAGIRI CAVIS** : Gupta inscriptions at, 65-66.  
**UDAYAMATI** : queen of Bhima I., builds a stepwell at Andulavān, 119, persuades her son Karna to marry Mivānalladevi, 171.  
**UDAYANA** : Saddharaja's minister, helps Kumārapala, 183, is appointed minister by Kumārapala, 184, and is mortally wounded in the fight with the king of Smāshṭra, 186.  
**UDAYAVIRA** : inscription of Udayaditya at, 164, Kumārapala's inscriptions in the temple at, 185, grant to the god of, 187 ; 194 note 1. See Udepur.  
**UDAYA VARAHA** : temple at Karmavati, 170.  
**UDAYASIMHADIVA** : Chohan king, captures Bhimāli, 170.  
**UDIPUR** : 161. See Udayapuri.  
**UDIPUR** : Nicholas, English merchant (1611), 221 note 2, 119 and note 2.  
**UDAYANA** : legendary Yādava chief of Dwāraka, 9.  
**UDAYAN** : 174, visited by Kumārapala in his exile, 183, 513 note 9.  
**UDIGH KHAN** : general (1297), 229, 512 ; 515.  
**UDHAI** : widow of Khondarā Dabholde, goes to Gujarāt to avenge Pilāp's death and marches upon Ahmedabad, 314, 393, intrigues of, against the Peshwa, recognises Dāmāji as her agent in Gujarāt (1736), 394, causes Kungop to be set at liberty and reappoints him her agent in Gujarāt (1745), 329, 396 ; dies (1748) 332, 396.  
**UDHAN** : Persian Gulf, 505, 523.  
**UDHAI INVAL KHAN** : Khahfah (634-643), 505 and note 5, 513, 523.  
**UDHAI** : copperplate grant from, 113 note 6, 117.  
**UDHAR** : identified with Umin, 130.  
**UDHAR** : apparently Vindhya mountain, 517.  
**UDHARAGADHIA** : 469.  
**UDHARAVATA** : Vindhavata's horse, 201.  
**UDHAR** : Colonel, special envoy deputed by the Calcutta Government to negotiate with ministers in Poona, 106.  
**UDHARAVATA** : Saka viceroy (100-120), gifts of, 25-26.  
**UDHAR** : governor of Bahrain and Persian Gulf, 505, 513, 523. Third Khalifah (643-655), 505 and note 5.  
**UDHAR** : governor of Basrah, 505 note 5.  
**UDHARPANI** : age, 193.  
**UDHARAPURSHAS** : Jain saints, 451 note 3.  
**UDHAR** : female demon, 455.  
**UDHAR** : identified with Ujjaini ; expedition a. . . . . 109, 467.

- V**  
**ṬḌA** : inscription of Suleṭnvarmān at, 107.  
**VADĀ** : religious discussion, 181.  
**VADAPADRAKA** : identified with Paroda, 125.  
**VADĀḌA** : convention of, disavowed by the Bombay Council (1779), 407.  
**VADHĪAR** 149, 150.  
**VADHVAN** 169. See Vadhvān.  
**VADHVAN** : capital of the Chapa dynasty 138, 139; 180 note 2, 186.  
**VADNAGAR** : town; ancient names of, 6, besieged by Antap Bhāṣṭa, again by Kantāp, burnt (1725), 307; 467; 516.  
**VĀDĀH** : local name, 208 note 3.  
**VĀGABHĀVA** : see Bhāṣṭa.  
**VAGGĪCHCHUNA** : mob in Vāghelā, 125.  
**VĀGHĒIA** : principality of, 165, dynasty (1240-1290), 526.  
**VĀGHĒIA MĪRO** : See Vāṣa Vāghelā.  
**VĀGHURIS** : branch of the Chālukyas of Anahilavāḍa, help the last Chālukya king and succeed him, 196-197, their rule and genealogy, 198-206.  
**VĀGHODIA** 125.  
**VĀGRA** : 129 and note 3.  
**VĀHABHĀSIMHA** 171.  
**VĀHISIMHA** : Chāvada king, 154-155.  
**VĀISHA** : 539. See Baiswa.  
**VĀJISANKAR GAṆPISANKAR** : Mī, Nāb Divān of Bhāvnagar, his collection of articles forged in Valabhi, 78 note 1.  
**VAKHAPSINGH** : fifty-ninth or the last viceroy of Gujarat appointed by the imperial court, 332.  
**VALA** : Valabhi, 506.  
**VALABHI** : probably Gujars, 1, 5 note 1; capital of Valabhi dynasty, identified with Valchi, 78 and note 1, history, 78-106, year, 201, 465, 466, Mīr or Gujpurā conquest of (490), 489, its great seaport and capital overthrown, 506; 524, 525.  
**VALABHI** : Balhāra or Rishtrakūta king, 516.  
**VALĀHAKA** : province, mentioned by Jinaprabhāsuri, 78.  
**VALABHI** : Valabhi, mentioned by Jinaprabhāsuri, 78.  
**VALĒH** : modern name of Valabhi, town, its site examined (1872), 78 and note.  
**VALLABHA** : head of the Dakhan Rāshṭra, 127, 525.  
**VALIABHARJA** : is installed by his father Chāṇurich, marches against Mālwa, dies of small-pox, 162.  
**VALLE** : De la, Italian traveller at Māndu (1623), 381.  
**VĀMANASHĪALI** : modern Vantah, 160.  
**VĀVARṢI** : Pandit in Kudrāpāla's court, insults Hemachandra, loses his amnity, 193.  
**VARARAJA** : Chavāda king (720-780), born and bred in forest, founded Anahilavāḍa; his installation, his image, his successors, 150, 151-152, 153, 155; 512.  
**VAN-DINDORI** : grant of Govind III. at, 123; 166, 468.  
**VANGA** : modern Bengal, 124, 168.  
**VĀNKĀNER** : 295.  
**VĀNKĪ** : creek near Balsār, 125.  
**VĀNKĪKA** : 125. See Vanki.  
**VANKIND** : forest pool, 454.  
**VĀNKA** : shrine, 215.  
**VANṬĀR** : shrines, 212.  
**VANṬĀLI** : 136, Chudisūmas settle at, 139; capital of Grakāṭipā 160; its rulers killed by Virodhavāla Vāghelā, 200-201.  
**VARADAPĀLIKA** : village, 130.  
**VARAHĀ** : wild boar coin, 219 note 2; Boar god, 457.  
**VARĀHA MĪHRA** : astronomer, 533, 534, 540.  
**VARĀṬṬA** : tribe, 534.  
**VARDHAMĀNAPURĀ** : modern Vadhvān, 176.  
**VĀRĪATĪ** : see Varalatte.  
**VĀRĪĀṬ** : see Varalatte.  
**VĀRĪYĀ** : modern Vantā 198.  
**VĀRĪS** : wild tribe, 534.  
**VĀRĪYĀS** : police subordinates, 212.  
**VĀRṬHĀ** : traveller (1503-1508), 220 note 2.  
**VARVAR** : 144, 174 note 1. See Barbaraka.  
**VARVARAKA** : see Barbaraka.  
**VASAKA** : camp, 113.  
**VASANTASENA** : king of Nepāl, 81.  
**VĀSHIṢṬA** : sage, 461.  
**VĀSINGAPURĀ** : 10 note 2.  
**VĀSĪRTHI** : fair, 541.  
**VĀSṬHĪKA** : Divānprasadā's minister builds magnificent Jain temples, 199 and note 2, 200, 201, 202 and note 1.  
**VĀSTUPĀLA** : life of Vastupāla by Somavāh, 199.  
**VĀSTUDEVĀ** : Kushan king (AD 123-150), 37.  
**VĀSTUDEVĀ** : Chohan king (780-157).  
**VĀSTUDEVĀS** : Jain saints, 154 note 3.  
**VĀTAPADHĀPIKA** : probably Bireda, 183.  
**VĀTARĀJA** : 466, 468, Gurjara king, his success in Bengal, 527.  
**VĀYAVĀLLĀDEVA** : manager of Tripura-chāpāśīda temple, 161.  
**VĒNṬHĀLI** : Vāma's Vantah, 133.  
**VĒVĀVĀ** : inscription at, 81, 176, 203, 204, 521, 547.  
**VĒRISĀLI** : of Rājpipla, 295.  
**VERSOVA** : fort in Sālsette, taken by the English (1774), 401.  
**VICHARAKING** : list of kings, 149 and note 2, 152, 154, 155, 156, 162, 170, 171, 183, 201.  
**VIDĀSĀLA** : Sanskrit college, 453 & note 1.  
**VIGISA** : B-nagar near Bhāṣṭa, 65, 66.  
**VIDYADHARĀS** : ancestors of north Konkan Sūlāhāras, 129.  
**VIGRAHARĀJA** : king of Ajmir, 157.  
**VITAYADITYA** : Chālukya king (696-775), 150.  
**VITAYAPURĀ** : identified with Bijāpur near Purānti, 108, 140.  
**VITAYARĀJA** : Chālukya prince, his grant, 108, 110, 112.  
**VITAYĀRKA** : Goa Kadamba king, 172 note 3.  
**VITAYASENA** : fifteenth Kshatrapa (238-249) coins of, 46-47, 49.  
**VITJALĀDEVA** : Ajayapāla's doorkeeper and murderer, 195.  
**VIKRAMA** : era, 204.  
**VĪKRAMĀDITYA** : Dakhan Chālukya king, 56;

- Satyāśraya, Chālukya king (680), 107, 110, 111, 112; gives Lāta to his brother Jayasimha, 117.
- VIKRAMĀDITYA: name of Chandragupta II., 65.
- VIKRAMASIMHA: Paramāra king of Chandravati, joint-king of Sāmbhara and is dethroned by Kūmarapāla, 185, 188.
- VILLAGE OFFICERS: Mughal, in Gujarāt, 212.
- VIMALA: general of Bhīma I., subduces Dhār-dhuka chief of A'bu and builds on A'bu Jain temples, 169.
- VIMALAVASANI: group of Jain temples on A'bu, 169 and note 1.
- VINAYĀDITYA: Chālukya king, 56, 110; his inscriptions, 111.
- VINAYĀDITYA MANGALARĀJA: copperplate grant at Bilāsi of, 108.
- VINCENT: 342.
- VINDHYA: mountain, northern limit of Dādā's Gurjara kingdom, 115; its king, 163; southern boundary of Kūmarapāla's kingdom, 189; 168; 517.
- VINDU: the Vindhya, 510.
- VIRĀMAN: thirteenth Kshatrpa (A.D. 236-238), coins of, 46.
- VIRĀDHVALA: Vāghela king (1233-1238), 179, 196, 197; his father abdicates in his favour, his expeditions against Vamthah, Bhadravara, and Godhira, and his treaty with the Sultan of Delhi, 200-201, 206.
- VIRĀMARI: Jain nun, brings up Vanarāja, 151.
- VIRAMA VISALA: see Visaladeva.
- VIRAMGĀM: Mūma lake at, 180 note 2; disturbance at (1734), 314, Shāh Kūmār Bāhū appointed governor of, 315, expulsion of the Marāthas from, by Bhay Singh, 323, besieged by the Marāthas, surrendered by Bhay Singh, 323, 324, given by Rāngoji to the Muslims, 326, 513, 518.
- VIRPIR: 180 note 2, 206.
- VIRA VĀGHELA: 198 and note 6. See Virādha-vala.
- VIRĀDHVALA: Vāghela king (1243-1261), defeats his brother and Tribhuvanapāla Solāṅki, refuses to acknowledge an overlord and lessens the miseries of a three years' famine, 203, 206. Ruler of Chandravati, 204.
- VISALANAGARA: fortifications of repaired by Visaladeva, 203.
- VISHNU: a god, 461.
- VISHNUVA: chief, 65.
- VISHOPAKA: 169.
- VISHVAKARMA: divine architect, 461, 462.
- VISHVAMITRA: sage, 161.
- VISVASKA: twentieth Kshatrpa (294-300), coins of, 48-49.
- VIVASIMHA: eighteenth Kshatrpa (272-278), coins of, 47.
- VISVAVARĀHA: father of Girhāri, 139.
- VITARĀGA: title of Jayabhata I., Gurjara ruler, 115, Jain Tirthankara, 195.
- VITHAL DEVĀJI: Gāikvār's officer, captures Mallharrav Gāikvār (1803), 413, appointed Subha in Kāthāváda, 426.
- VITHAL SHUKDEV: lieutenant of Raghunāth-rāv in Gujarāt, settles peace with Jawan Māid Khān (1753), 337.
- VOL: exactions, 216, 227 and note 1.
- VRIJIS: 456 note 1.
- VYĀGHRAVĀLI: Vāghela, the home of Vāghr-lās, 198.
- VYĀGHRAMIKHA: Gurjara king, 167.
- VYĀGHRAKĀJA: Chāpa king, 138 note 1.
- VYĀGHRAŚA: perhaps Vāgra, 129 and note 3.
- WAGNER: outbreak of (1859), 446.
- WAGHIA: castrator, 451.
- WAIZAPUR: village, 143.
- WAKI: UNICAR: news-writer, 214.
- WALKER: Major, sent by Governor Duncan to help Govindráv's party at Baroda, 412; resi-dent at Baroda, 413, 414. Colonel, settles the Kāthāváda tribute question, 416, 422, 423.
- WALLACE: Colonel, political agent of Rewa Kānth, 446.
- WANGSA: 111. See Balisa.
- WATKIN: Mr., 120.
- WATSON: Colonel, 145, 466.
- WAZIRAN: land grants, 212, land held on reli-gious tenures by Hindus, confiscation of, by an order of Aurangzib between 1671 and 1674, 285.
- WELSH: Lieut., takes the forts of Pārnara, Indragad, and Bagvada (1780), 409.
- WELSH: the late Colonel, 110.
- WEST NARIK: connected with south Gujarāt under the Chālukya rule, 110.
- WHITE HINAS: foreigners 142-146; 149, in north Smūla and south Panjab, 496, defeat of, by Sassanians and Turks (550-600), 497; settle in Yunnan with Tibetans and Kedarites 501. See Hinas.
- WIGGILLIGRIS: 158 and note 2.
- WILKED: 511.
- WILSON: Dr John, 115.
- XOANA: town, 538.
- XODRAKE: 539.
- YACHI: capital of Kārājāng or Yunnan (1290), 501, 504.
- YĀDAVA KINGDOM: at Dwārikā, establishment of, 8.
- YADAV: 521.
- YAJÑASATTA: Brahmin, 461.
- YAJÑASHRI: Andhra king, 38.
- YAJÑEVINA: 634.
- YAKSHA: king, 151, 456 and note 1, statue of, described 156-158, high day of, 458, 465.
- YAMUNA: river, 533.
- YASADAMAN I.: fourteenth Kshatrpa (A.D. 239), coins of, 46.
- YASADAMAN II.: twenty-second Kshatrpa (A.D. 320), coins of, 49.
- YASHVANTHĀV: minor son of Triambakráv Dabhāde made Senapati by Bājirāv Peshwa (1731), 393, 396.
- YASODHARMAN: king of Mālwa, 76, 77, defeats Hous, 143; defeats Mihirakula the famous White Hun conqueror at Kāgur (530), 496.

- YASODHARALA** : Kumārapāla's viceroy, 187; set on his uncle's throne by Kumārapāla, 18'.  
**YASOVARMAN** : king of Mālwa, 160, 172, 173, 174; his war with Siddharāja, is taken prisoner and kept in a cage, 177-178, 496.  
**YAUDHEYA** : Kshatriya tribe, 19 and note 3, 86-87, 64 and note 3, 138.  
**YAVANA** : 12; people, 119; language, 160, 456 note 1; migration of, to Indo-China (100), 499.  
**YAVANĀŚVA** : Yavana prince of Pārlipur, 119.  
**YAVANI** : handmaids, of the Indian drama, 545.  
**YAYĀTI** : king, son of Nahushī, asks boon from the Sun, 460 and note 2.  
**YEMEN** : country, 535.  
**YESODHARMAN** : 143. See Yasodharman.  
**YE-TA-I-LI-TO** : 145.  
**YE-THA** : White Huns, 75, 142, 145. See Ye-ta-i-li-to.  
**YOTA** : Brāhman donee, 126.  
**YOGARāja** : Anahilavāda chief (805-841), 124; mounts funeral pyre, 151, 155.  
**YOGĀŚĀSTRA** : work compiled by Hemachandra, 193.  
**YOGĒSVARA** : writer of Govind's Kāvī grant, 126.  
**YOSANA** : three miles, 510, 521.  
**YUAN-YUAN** : 144.  
**YUECHI** : foreign tribe, 141, 456 note 1 : little. 540. See Kedarites.  
**YUETCHI** : see 144. See Yuechi.  
**YUGS** cycles, 461. "  
**YUKĀVIMĀNA** : louse temple, 193.  
**YUSE** : Sir H., 499, 504, 537, 538, 539, 540.  
**YUNNAN** : settlement in, of Thsrong and his successor Thi-tsong-ti, 501.
- ZAFAR KHĀN** : (injarāt governor (1371), 230, 231, (1391-1403), 232, 234; confined by his son Tātār Khān at Asāwa, 513.  
**ZAKĀT** : a tax, 212 note 1.  
**ZAMINDĀRS** : landholders, 215, 216 note 1; three classes of, 226.  
**ZAMOTIKA** : father of Kshātrapa Chastana, 31.  
**ZARMANOKHĒGAS** : S'ramanācaryā at Athens, 536.  
**ZĒROGEREI** : town, 540.  
**ZIA-UD-DIN BAKNI** : anpalist of Muhammad Tughlak', reign and author of Tarikh-i-Firuz-Shahi (1325), 513, 514, 517, 518.  
**ZIMMIS** : infidels, 213.  
**ZŌSKALĒS** : king Za Sīgal or Za Asgal or Za Hukalē, 543.  
**ZULFIKAR BEG** : Mughal leader, is defeated by the Marāthas (1716), 388.









